Appendix G

QUALITY ASSURANCE DOCUMENTATION



Quality Assurance Statement

Omega Point Laboratories, Inc. is an independent, wholly owned company incorporated in the state of Texas, devoted to engineering, inspection, quality assurance and testing of building materials, products and assemblies. The company has developed and implemented a Quality Assurance Program designed to provide its clients with a planned procedure of order and document processing for inspection and testing services it provides to assure conformity to requirements, codes, standards and specifications. The Program is designed to meet the intent of ANSI 45.2 Quality Assurance Program Requirements for Nuclear Power Plants, and complies with the requirements of the ASME Code, SPPE, Military Standards and other less stringent programs. It is the Laboratory's intention to adhere strictly to this Program, to assure that the services offered to its clients remains of the highest quality and accuracy possible.

The overall responsibility of the supervision, operation and coordination of this Quality Assurance Program is that of the Quality Assurance Manager, a person not involved with the performance of the inspection or testing services, and who is under the full time employ of the Laboratory. This individual is responsible for implementing and enforcing all procedures presented in the Quality Assurance Manual and the Procedures Manual. All personnel involved with activities which fall under the scope of this Program are required to cooperate with the letter and intent of this Program.

All QA Surveillance documents remain on file at the Laboratory, and are available for inspection by authorized personnel in the performance of an on-site QA Audit. All materials, services and supplies utilized herein were obtained with appropriate QA Certifications of Compliance, and the inclusion of these in this report would not be practical nor useful to the reader.





ACCEPTABILITY DOCUMENTATION

PROJECT NO. 14790-123263

SANDIA NATIONAL LABORATORIES

The following signatures attest to the review and acceptance of each attribute (Hold Point) listed regarding the above-noted project:

I. TEST ARTICLE DECK	
Signed	1/27/05
Omega Point Laboratories, Inc.	Date
Frank / Nu av	1/27/05
SANDIA National Laboratories	Date

11. **TEST ARTICLE RACEWAYS & JB**

Omega Point Laboratories, Inc.

SANDIA National Laboratories

Omega Point Laboratories, Inc. 16015 Shady Falls Road Elmendorf, Texas 78112-9784 USA 210-635-8100 / FAX: 210-635-8101 / 800-966-5253 www.opl.com moreinfo@opl.com

TEST SPECIMEN THERMOCOUPLE PLACEMENT III.

Segue	2/8/05
Omega Point Laboratories, Inc.	Date
Frank Wyas	2/8/05
SANDIA National Laboratories	Date

COPPER WIRE THERMOCOUPLE PLACEMENT IV.

Degrand	2/8/05
Omega Point Laboratories, Inc.	Date
Thum	2/8/05
SANDIA National Laboratories	Date /

	DDFF	DEDO	INSTAL	IA	TION	ADDDC	I A \ /
V.	PRFF	- H-HS	INSIAI	1 4	TICIN	APPRU	IVAL

Omega Point Laboratories, Inc. SANDIA National Laboratories

ERFBS INSTALLATION APPROVAL

Omega Point Laboratories, Inc.

SANDIA National Laboratories

VII. COMPLETED PRE TEST	ARTICLE INSPECTION
Omega Point Laboratories, Inc.	3(11/05 Date
SANDIA National Laboratories	3/11/05 Date
VIII. PRE-TEST DATA ACQUI	SITION VERIFICATION
Omega Point Laboratories, Inc.	3/11/05 Date
SANDIA National Laboratories	3/11/05 Date
IX. POST-TEST DATA ACQU	JISITION VERIFICATION
Omega Point Laboratories, Inc.	3/11/05 Date
Offiega Foliti Laboratories, inc.	7/1/-
SANDIA National Laboratories	3/11/05 Date



1e5t Page 373

EVENT LOG

Fire Resistance Test of Conduits
Protected by Hemyc ERFBS

PROJECT NUMBER:

14790-123263

SANDIA NATIONAL LABORATORIES

EVENT LOG

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

Protected by Henry Ci-Hour Hated Em Bo.			
	Р	age 🛴	of 8
TEM		ATE	INIT'L
	20	1-1011	CH
Reguest for Quotation (RFQ)# 7253		15/04	CA
Patricia Brown of Sandia Labs.			
Technical Proposal no. P041206-01	13	2/6	CH
issued to Sandia Labs by Deg	,		
Priest President of Omega Point ta	les.	nInn	121
Sandia Laby estreed furchase	int.	2/22	Cry
Dea Prient from Omega Point acce	4/	2/22	CH
contract terms by signing a	nd		
returning P.O. sighature sage	- 1	10.1	021
by fax second acceptance tagate	2/3/	12/30	07
(Jeg) Priest completes much pro-	ect!	750	C/Y
Project Hold Points are determine	1 1	14/05	CH
light Frank Wyant, Santia, Jech	ni-	/	
Cal contact and Connie Human	rec	Vin	107/
De CH 1405 all of Ditter of anstart	ug se	4/05	CH
sidera moiest steel for test diche	,	1/- 4	
Connie Themshree beceives approv	ral 1	15	CH
for the qualification method of	he		
thermorough supplier divereso	app. B)	15	17/
shi and I and OPL technicians		10	CY
be bin fabrication of the steel			
deapst for all three Sandia pro	ilco	, ,,	1
Construction of test alche continu	ue,	1/6	CH
The extent of the video mobilion	ito	1/1/	CA
of the construction process of the	ie d		
that articles is made by France	2		
Wyant of Sandia Labs, 1 to the	16	trata	7-
Construction continues on test all	Le, 1	11010	10/

Test 1

EVENT LOG

Page 375

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

TIEM Deg Priest issues Junction Boy 1/1/1/15 CH Thermosouple diawing. OPI AHOC personnel Belleve the 1/11 CH Assuments for Shipment #44855 enroute to Omliga Point from Sandia Jaks. CPI OH/OC personnel ship 46 1/11 CH Church Disconnest thermosouples Using Transmittal tetter # 1/2h OPI AHOC personnel wife, the 1/12 CH Test dick dimensions + 1/15/15 OPI AHOC personnel require the 1/14 CH Hardware shipment #44855 from Spandia Latis all jeans services 1/18 CH The test artigle receives the 1/18 CH The test artigle receives and 1/18 CH OPI technicians begin serving 1/18 CH OPI test artigle receives and 1/18 CH Church Sirard Sandia Censultani/124 CH OPI test article receives the 1/14 CH OPI test artigle receives and 1/18 CH Church Sirard Sandia Censultani/124 CH OPI test article receives as the 1/18 CH OPI test article receives as 1/18 CH OPI test article receives as a serving 1/18 CH OPI test article receives as a serving 1/18 CH OPI test article receives as a serving 1/18 CH OPI test article receives as a serving 1/18 CH OPI test article receives as a serving 1/18 CH OPI test article receives the serving 1/18 CH OPI test article receives 1/18 CH OPI test article	Protected by Helliye 1-Hour Rated EAF B3.		
Deg Priest issues Junction Boy 1/1/85 CH Thermocouple diawing. OPI OH/OC personned thelewe the 1/11 CH aruments for Shipment #44855 exroute to amega Point from Sandia sabs. OPI OH/OC personnel ship 46 Quick Disconnect thermocouples to Bruce Levin, Jechnical Centact at Sandia Labs for ventication using Transpuitfal Letter# 1/26, OPI OH/OC personnel receive the 1/14 CH That dick personnel receive the 1/14 CH Plandware shipment #44855 from Sandia Labs all jtems selected 1/18 CH That test article sheeping for tichnicians begin for tichnication 1/18 CH OPI technicians begin for tichnication 1/18 CH Church Strand Sandia Constitutes 1/19 CH OPI technication fontinue coope on the test article sheeping for the 1/19 CH on the test article sheeping for the 1/19 CH on the test article sheeping 1/25 CH or the Strand Sandia Consultant/124 CH or the Strand Sandia Consultant/124 CH or the Strand Sandia Consultant/124 CH or held to discuss project ORIGINAL STRAND CH ORIGINAL STRAND		Page 2	of 8
The mocouple discoving. OPI GATOC personnel tillewe the 1/11 CH accuments for Shipmont #44855 exercite to mega wint from Sandia Jaks. OPI OHICC personnel ship 46 1/11 CH Quick Disconnect thermocouples at Sandia Lavin, Jechnical Contact at Sandia Lavin, Jechnical Contact at Sandia Laving, Jechnical Contact at Sandia Laving, Jechnical Contact Alace personnel verify the 1/12 CH tist disco dimensions + 1/12/11 OPI OHICC personnel receive the 1/14 CH Hardware shipment #4485 OPI tichnicians begin fabrication 1/18 CH The test article sacchays OPI tichnicians begin fabrication 1/18 CH OPI technicians centime work OPI technicians centime work OPI technicians centime work OPI technicians partine work OPI technicians partine work OPI technicians centime work OPI technicians project OPI technical of Thomas meeting 1/25 CH OPI technical constitution 1/25 CH	ITEM		
The mocouple discoving. OPI GATOC personnel tillewe the 1/11 CH accuments for Shipmont #44855 exercite to mega wint from Sandia Jaks. OPI OHICC personnel ship 46 1/11 CH Quick Disconnect thermocouples at Sandia Lavin, Jechnical Contact at Sandia Lavin, Jechnical Contact at Sandia Laving, Jechnical Contact at Sandia Laving, Jechnical Contact Alace personnel verify the 1/12 CH tist disco dimensions + 1/12/11 OPI OHICC personnel receive the 1/14 CH Hardware shipment #4485 OPI tichnicians begin fabrication 1/18 CH The test article sacchays OPI tichnicians begin fabrication 1/18 CH OPI technicians centime work OPI technicians centime work OPI technicians centime work OPI technicians partine work OPI technicians partine work OPI technicians centime work OPI technicians project OPI technical of Thomas meeting 1/25 CH OPI technical constitution 1/25 CH	Dec Priest issues Junction Boy	1/11/05	CH
ope affor supment #44855 enroute to shipment #44855 enroute to omega Point from Sandia Fabs. Ope OHIGE personnel ship 46 1/11 CH Quick Disconnact Thermoscouples Uto Bruce Levin, Sechnical Contact at Sandia Labs for verifications using Transmittal Letter # 1126 OPE A/OC personnel verification OPE OHIGE personnel receive the 1/14 CH Hardware shipment #44855 from OPE dichnicians begin fabricating 1/18 CH The test article racedary on times 1/19 CH OPE technicians begin fabricating 1/18 CH The test article racedary (on times 1/19 CH OPE technicians Centime work OPE technicians Centime work OPE technicians Centime work OPE technicians begin fabricating 1/18 CH Churk Strand Sandia Censultant/124 CH OPE technicians Centime work OPE technicians Centime work OPE technicians Centime work OPE technicians from project OPE technicians from project OPE technicians of the	Thermocouple drawing.	//	7
aroute to moneya Point from Sanctia Labs. OPI OHIGC Personnel ship 46 1/11 CH Quick Disconnect Thermosouples At Sancja Labs for verification using transmittal tetter # 1/26 OPI OHIOC personnel verify the 1/12 CH test dich dimensions + 1/19/11 OPI OHIOC personnel receive the 1/14 CH Hardware spipment #44855 from Sancia Labs all items sergived OPI technicians began fortunes 1/19 CH The test article receive work on the test article receive of 1/31 CH origins at OPI. Though meeting 1/35 CH whire at OPI. Though meeting 1/35 CH Measurements of per to Deg Priest issues freque & draw 1/25 CH	OPL AHOC sessonnel necewe the	1/11	CH
Sandia Jaks. OPI OA/GC Persannel ship 46 Quick Disconnect Thermocouples Oto Bruce Jevin Jechnical Contact at Sandia Zaks for verification using Transpirital Letter # 1126 OPI OA/GC Personnel verify the 1/12 CH test dick dimensions + 1/13/17 OPI OA/GC Personnel receive the 1/14 CH Hardware shipment # 44855 from Sandia Zaks all jitems relieved, OPI technicians begin fabricating 1/18 CH The test article raceway, opt technicians begin fabricating 1/18 CH The test article raceway, on the test article raceway, on the test article sacceracy o	documents for Shipment # 44855	1	
OPI PAJOC Personnect Thermocourples Oto Bruce Jewin Technical Contact at Sandia Labs for verification using Transquittal Letter # 1/26 OPI CAJOC Personnel verification OPI OHTOC Personnel verification OPI OHTOC Personnel relaine the 1/14 CH Hardware Shipment # 44855 from Sandia Labs, all items selected OPI technicians begin fabrication 1/18 CH The test article raceway for technication continues 1/19 CH OPI technicians continue cross on the test article raceway 1/21 CH church Sirard Sandia consultantifay CH verives at OPI, Inoug neeting 1/25 CH Neasurements of pour to Deg Priest isoners from a draw 1/25 CH			
Quick Disconnect Thermorougles Oto Bruce Levin, Jechnical Centact at Sandia Labs for venification using Transmittal Litter # 1126 OPI DATOC Sersonnel verify the 1/12 CH test dich dimensions + 1/19/19 OPI DATOC personnel receive the 1/14 CH Hardware shipment # 44855 from Sandia Labs, all items received OPI technicians begin fabricating 1/18 CH The test article raced and fortimes 1/19 CH OPI technicians begin fabricating 1/18 CH OPI technicians begin fabricating 1/18 CH OPI technicians continues 1/19 CH OPI technicians continues 1/19 CH on the test article raced article 1/25 CH whire at OPI, Inous meeting 1/25 CH Negwirements. Church Firand verifies test article 1/25 CH Measurements of out to	Sandia Labs.	1/	10-11
Ito Bruce Levin, Technical Centact at Sandia Labs for verification using Transpirital Letter # 1/26, OPL OFFICE personnel verify the 1/12 CT test dients dimensions + 1/15" OPL OFFICE personnel reseive the 1/14 CT Hardware shipment # 44855 from Sandia Labs all items received, OPL technicians begin fobricating 1/18 CT The test article raceday, Paceyay fobrication Continues 1/19 CT OPL technicians technicians 1/19 CT OPL technicians 1/19 CT OP	OPL OA/GC personnel ship 46	1/11	614
at Sandia Labs for verification using Transmittal Letter # 1/26. OPL OFA/OC DESSOUNDED VERIFIE THE 1/12 CH tist dich dimensions + 1/12' OPL OFA/OC DESSOUNDED RECEIVE the 1/14 CH Hardware shipment # 44855 from Sandia Labs, all items received, OPL technicians begin fabricating 1/18 CH The test article raceways, Parenagy fabrication Continues 1/19 CH OPL technicians continue work on the test article raceway (31 CH church dirard Sandia Consultant/34 CH arrives at OPL Though meeting 1/25 CH requirements of wrifies test while 1/25 CH Measurements of wrifies test while 1/25 CH Neg Priest isoners tiggine 3 draw 1/25 CH			
ope of 100 personnel verify the 1/12 CH test dick dimensions + 6/25" OPE OFFICE personnel receive the 1/14 CH Hardware spipment # 44855 from Sandia Labs, all items received OPE technicians begin fabricating 1/18 CH The test article raceway, Paceyay fabrication Continues 1/19 CH OPE technicians continue work on the test article raceway, 1/31 CH Church Sirard Sandia Consultant/124 CH arrives at OPE, Troug meeting 1/25 CH we held to alsown project Church Firard verifies test article 1/25 CH Measurements chave to Deg Priest isoners trigger 3 draw 1/25 CH	Will Love City of the state of		
OPL & A/OC Sersonnel verify the 1/12 CT test dech dimensions + 1/15". OPL AHOC personnel receive the 1/14 CT/ Hardware shipment #44855 from Sandia Labs all items serviced. OPL technicians begin fabrication 1/18 CT/ The test article raceway fortimes 1/19 CT/ OPL technicians continue work on the test article raceway 1/21 CT/ Church Strand Sandia Consultant/1/24 CT/ Wrives at OPL. Though meeting 1/25 CT/ Negurements. Church Strand verifies test article 1/25 CT/ Measurements. of Pew +0 Deg Priest issues tigge 3 draw 1/25 CT/		1	-
Test dech dimensions + 0/1/2 (7) OPI OHIOC personnel receive the 1/14 CH Hardware spripment #44855 from Sandia Labs, all items received from 1/18 CH The test article raceways, Paceway fabrication Continues 1/19 CH OPI technicians continue work on the test article raceway (2) CH church Sirard Sandia consultant/124 CH arrives at OPI, Inoug meeting 1/25 CH we held to discuss project Church Firard verifies test article 1/25 CH Measurements repents 3 draw 1/25 CH		1/19	17/
OPI OFFOC personnel reseive the 1/14 CH Hardware spripment #44855 from Sandia Lales all items received OPI technicians begin fabricating 1/18 CH The test article race ways Pareway fabrication Continues 1/19 CH OPI technicians continue work on the test article raceway In CH Churk Dirard Sandia consultant/124 CH arrives at OPI Shoup meeting 1/25 CH while Firard verifies test article 1/25 CH Measurements report to Deg Priest issues tigge 3 draw 1/25 CH		1/12	CIV
Hardware spipment #4985 from Sandia Lales, all items selectived Opt technicians begin fabricating 1/18 CH The test article saccinant Continues 1/19 CH Opt technicians continue work on the test article saccinant (3) CH Church Stirard Sandia Consultant/124 CH verives at Opt. Though meeting 1/25 CH is held to discuss project Church Firard verifies test article 1/25 CH measurements spow to Deg Priest issues Higgs 2 draw 1/25 CH		1114	07/
Sandia Lalis, all plems sectioned (18 CH) The test article saccourage, fabrication (18 CH) Parenay fabrication Continues (1/9 CH) OPE technicians continue work on the test article saccourage (1/21 CH) Church Sirard Sandia consultantify (1/24 CH) wrives at OPE, Thous meeting (1/25 CH) is held to discuss project Church Sirard verifies test article (1/25 CH) Measurements of pour to Deg Priest issues figure 3 draw (1/25 CH)	Destinant #44855 from	1//	
The test article raceways, Parenay fabrication Continues 1/19 CH OPE technicians continue work on the test article saccuracy 1/31 CH Church Stirard Sandia consultant/124 CH arrives at OPE, Thous meeting 1/25 CH is held to discuss project Church Firard verifies test article 1/25 CH Measurements of port to Deg Priest issues of tigge 3 draw 1/25 CH	Sandia Lakes all items received		
The test article sacchary. Pacenay fabrication Continues 1/19 CH OPE technicians continue work on the test article saccuracy 1/21 CH Churk Sirard Sandia Consultant/124 CH wrives at OPE Group meeting 1/25 CH is held to discuss project Chuck Sirard verifies test article 1/25 CH Measurements of per to Deg Priest issues figure 3 draw 1/25 CH	OPL Ferhnicians begin babrication	01/18	CH
of the test article saceway (13) CH church Tirard, Sandia consultantify CH arrives at OPC. Thous meeting 1/25 CH is held to discuss project requirements, verifies test article ips CH measurements of per to Deg Priest issues Freque 3 draw 1/25 CH		1	-
on the test article saccway, 1/31 CH Church Surard Sandia Consultantifat CH while at OPC. Though meeting 1/25 CH is held to discuss project requirements, verifies test article ips CH measurements of per to Deg Priest issues freque a draw 1/25 CH	Pareway fabrication Continues	1/19	CH
church Stirard, Sandia Consultantifay CH arrives at OPC. Though meeting 1/25 CH is held to alsown project requirements, verifies test article ips CH measurements of per to Deg Priest issues Figure 3 draw 1/25 CH	OPC technicians continue work	1	051
reguirements, verifies test article its CH measurements of per to Neg Priest issues tigure 2 draw 1/25 CH		1/2/	CO X
is held to alsows project requirements, Charles Finance verifies test unice ips CH measurements of per 1 to Deg Priest issues Figure 3 draw 1/25 CH		1/24	C 34
requirements. Chuck Firand verifies test article ips CH measurements of Dev 1 to Deg Priest issues Freque 3 draw 1/25 CH		1/25	A
Chlick Finance verifies test drucke ips CH measurements offer to Deg Priest issues tigine a draw 1/25 CH	20 1000		
Deg Priest issues Figure 3 draw 1/25 CH	The state of the s	Point	041
Deg Frien issues Figure daran 1/2 CH	ware of the	1/20	91
	Measurements of Devitor 2 days	1/25	1071
Ten Jest one lable train are 1/26 CH weighed after removement som deals.	1	1/25	
Wonduits and Cable trays are 1/26 CH weighed after removing tromdeals.	The Tot and		,
weighed after removement som deals.	Honduits and cable train are	1/26	CH
of at acre very the instal+	weighed after removement som deale	7.	
Matter a bas a Michael alter alter	OF OHOC re-verify the instal.	<u> </u>	,
eactor medourements ragger and to the	lation measurements after the	1/2/2/2	77
saleways are re-installed so 1/20/0) C/	raceways are re-installed to	1/2010	10/

EVENT LOG

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

	Page 3	of 8
ITEM	DATE	INIT'L
the tost decke	1/26/05	CH
Frank Wyant, Sandia Technical	1/27	CH
Contact Gernines. a meeting is	1	
held in the conference warm		
with all involved personnel	1/27	100
the Bare #8 capper were are cen	1101	
The and under distriction of France	6	
Wyant and Church Finand De	2	
Policit biguned the fill Der-0	1	
Contact the capper wire		-
in all Candity. The file		
was calculated at approxi-		
mately 30 %.	1/2-	05/
Die Phiest issues tiene 7, Jest 1	127	071
Steel and Unistrut Support		
Diquing:	1/28	071
the water to personal to	130	CA
all conduits and rable treis are	1128	CX
marked for thermocounte	1	
Operation by OPL Technicians		
OPF technicians been installed	1/28	C4
the fiverglas wrapped thermo-	//	
causles on test and	1/20	10-41
Junction vapes are welded to frame	1/28	11
This is weighed along with	ans	
the steel supports on the wine	1/31	1024
are verified less ope GATAC person	hel.	
the verified way and braine	1/3/	CH
in vinstalled	/	
Thermocounter installed on the	2/2	CH
Bare #8 Mapper wires are verifie	011	
by OPL ONIOC personnel.	2/2/0	CH

Test 1

EVENT LOG

Page 377

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

Protected by Hemyo 1-Hour Rated ERFBS.		
	Page 4	of 8
ITEM	DATE	INIT'L
Technicians out Barl #8 Copper	2/2/05	CH
wire for 1B /4" conduit,	1 1	70 11
Quick Discouncet Thermolouples	2/3	CH
Sent to Sandia for verification	/	
are received attope long GA/OC.	1/2	171
Fechnicians Cut Bare# 8 Copper	2/3	CN
wire for 10 (2-12" conduct";	2/11	1071
Thermocouples are verificed by	2/T	CZY
CHICA CONTRACTOR OF THE STATE O	2/4	(07)
copper wire for the two air	7/ 7	
than on that one	,	
Installation of the Quick Discon-	-2/4	CH
next thermocoulace sto the	7	1
sunction box is completed by		
DPC Technicians and verified		
by attac sersonnal.	2/2	07/
One hundred and thisteen Vare # 8	2/1	CH
capper wires are cut for the 2-12"		
Vall #8 Capper wice is instru-		
val #8 Capper wells is institu-		
Menella worth They way to and		
Wille hundles are weighed and	2/1	ast
Venter of bundles measured.	-7	
French Officiant arrives at OPla	2/1	CH,
mike murshy and Michael Joylan	3/8	CH
of Promater Dechnologies askine		
to meet with thank Want		
The instrumented thermocourse	7	
for conduct 1-5 were aam aged		
fin in allempe to pull the will		
mundle in the 4 constitute	1 1	
with was be-instrumented with	2/8/10	CN
we was in a morrow - and the	1-1-1	

EVENT LOG

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

TIEM THEN THE MOTOUPE'S and again 2/80 CH NERTHER HISTORIAN AGAIN 2/80 CH NERTHER HISTORIAN AGAIN 2/80 CH ARACE THE INSTRUMENTED TRAVEL OF THE WITE LUNCHER AS PRESENT OF THE WITE LUNCHES TO THE CENTES OF THE WITE LUNCHES TO THE CENTES OF THE WITE LUNCHES TO THE CENTES OF THE CONSULTS. COSSILITA MENTELS I B (W") I-D (2-12) and ET AND HISTORIAN AND PROMATER FRANK HISTORIAN AND PROMATER THE PROMATER METALLIANT TO WITHEN HEMICA INSTALLATION WITH PROMATER INSTALLATION THE PROMATER METALLE PROMATER THE MUNICIPAL METALLE PROMATER INSTALLES TRANK HOUSE AFTER 3/3 CH MATERIAL AND OTHER SELECTION PROJECT MATERIALS HOUSELT BY PROJECT MATERIALS AND		Page <u>5</u>	of 8
new thermolouples and again 2/80 CH whiled he was the present and from the present and from the proper of the protect of the property and the property and the property of	ITEM	I DATE	
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	now thormsalaunton and acains	2/8/2	01
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	While and the water Dea Drient	70/0	
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	and Franch Whyant decaded to		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	Dane the instrumented bare		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	HE Capper were in the center		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	of the wire bundle to protect		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	othe TC's when being installe		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	ente the conducts conduits,		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	members 1-B(4") 1-D(2-12"), and	-	
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	1-F (1") had the wife vundle	7	
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	installed by ore securing cares.	110	1071
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	train again and Promater	0/8	T
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	secondes sersonne repart	2/22	17/
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	est and and and much friend	10/00	C/Y
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	to situan Hemma installation		
departs. Frank Wyant departs Of 3/34CH mike Midrohi michael Jordan 3/3 CH Proparatec. Trank Haese lantract installers arrives at Opc. OPL SHOC receives the Hemyc 3/3 CH material and other solated project materials brought by Promatec sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Quilan and attended by promatic personnel and lede patton OPL OFFICE.	by t the Promaton installers	7	
Propriete Trank Haese hanhad installers arrives at Ope of AHOC receives the Henry 3/3 CH material and other solated by Promatic sersonnel. Draining session on project 3/3 CH installation require ments is held by michael Cardan and allegated by Promatic sersonnel of AHOC. Promatec installers begins 3/3	did not show, Chuck Things	2/22	07/
Propriete Trank Haese hanhad installers arrives at Ope. OPE AHOU receives the Hemye 3/3 OH material and other solated by Promatic sersonnel. Draining session on project 3/3 OH installation require ments is held by michael Cardan and allegated by Promatic sersonnel of the file of the promatic sersonnel and these patron of Office of The Promatic sersonnel and these patron of Office of The Promatic sersonnel and these patron of Office of The Office of The Promatic sersonnel and these patron of Office of The Office o	departs:		
Propriete Trank Haese hanhad installers arrives at Ope of AHOC receives the Henry 3/3 CH material and other solated by Promatic sersonnel. Draining session on project 3/3 CH installation require ments is held by michael Cardan and allegated by Promatic sersonnel of AHOC. Promatec installers begins 3/3	Frank Wyant departs OPEn	2/24	07
material and other selated is project materials serought by Promatec sersonnel. Jacining session on project 3/3 CZI installation require ments is held by michael Cardan and attended by Promatec personnel and Cleda fatton OPE OFFICE.	mike murphy, mechael Jordan	3/3	07/
material and other related in project materials serought by Promatec sersonnel. Promatec sersonnel. Jacining session on project 3/3 CZI installation require ments is held by michael Cardan and attended by Promatec sersonnel and Cleda fatton OPE office. Promatec installers begins 3/3	Cerry Thorton arrive from	1	
material and other related in project materials berought by Promater sersonnel. Promater sersonnel. Jacining session on project 3/3 CH installation require ments is held by michael Cardan and attended by Promater sersonnel and Cleda fatton OPE OFFICE.	Propratec. Frank Haese, Canha	at	
material and other related in project materials serought by Promatec sersonnel. Promatec sersonnel. Jacining session on project 3/3 CZI installation require ments is held by michael Cardan and attended by Promatec sersonnel and Cleda fatton OPE office. Promatec installers begins 3/3	installers, arrives at OPC.	2/2	1071
installation require month is held by michael Jardan and attended by Promatic personnel and Cloda Patton OPL OF 1616.	OPL SAJOC receives the Hemye	3/3	CH
installation require monts is held by michael Jardan and attended by Promatic personnel and Cleda Patton OPL Office.	material and other selated		
installation require monts is held by michael Jardan and attended by Promatic personnel and Cleda Patton OPL Office.	project malerials shought by		
installation require monts is held by michael Jardan and attended by Promatic personnel and Cleda Patton OPL Office.	Fromatec sersannel.	2/2	12/
held by michael Gardan and attended by Promatic personnel and Cleda Patton OPE OF 160;	Transfer to the state of the st	112	
attended by Prostratec personnel	tild to sanial allow the sand		
Promatec installers blain 313	The first of the Bacache attended	0	
Promatec installers blain 33		1	
installing the Henrice waterial 3/3/01 CA	Promater installars blein	3/3	
	installing the Henrice waterial	3/3/03	CA

EVENT LOG

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

	Page 6	of 8
ITEM	DATE	INIT'L
and continue wark on 3/4/05	34105	CH
Frank Wyant arrives to wither	2	
installation procedures.		1
Henry installation is completed	3/5	COX
Insportion of completed fest		
article revealed eseveral great		
on the Henry material that		
needed patching. These ageas		
are identified by morrail		
Gordan of gramater frame		
Myani of Janua ang Clifta		
Frank Hasse Promater actual	+3/7	C71
Thank the ser the water to care	(3//	
Market a Frank Wigant		
of services		
DOL fer hixiceans install the	3/8	C7/
decline insulation.	/,	
Test Article is moved to the	3/9	CoH
tost burnace by ppy techni-		
Tearles with Frank Wyant		
observing.	-/-	071
michael Gardan adarry Mortan of	3/9	C.A
Dromated arrived, additional		-
ceramic fiver blanket is graded		-
to the 4 " condent go vend and	0	-
repatched with Hemize Mittenia	<i>C</i> .	
Live appending varias were		
michael Chardan Verry Thouton	3/10	07/
Frank Wyant and Cleda Potton	5/1-	
review the documents of		
project requirements. Ochry		
Tharten demants OPL	1 1	
Mark Salley USNRC, Roy Woods	3/10/0	CX
	-	

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

MEM USNRC and Mark allen of Sandia 3/10/05004 array to inspect test article and witness testing OPL OA OC verifies Other thermor 3/10 CH couple attachment to the flata acquisition equipment to the flata acquisition equipment to the flata acquisition equipment to the flata and total of 1380 thermocouples, thought The following sensagnel, 3/11 Ct alle arrived at OPL oth witness The test of project #1 32 3 2 3 2; The test of project #1 32 3 2 3 2; The test of project #1 32 3 2 3 2; The test of project #1 32 3 2 3 2; The test of project #1 3 2 3 2 3 2; The test of project #1 3 2 3 2 3 2; The test of project #1 3 2 3 2 3 2; The test of project #1 3 2 3 2 3 2; The test of project #1 3 2 3 2 3 2 2 3 2 3 2 3 2 3 3 3 3 3 3	The state of the s	Page 7	of 8
USNRC and Mark Allen of Sandia 3/10/0 CT arrive to inspect tist artisle and withers lighting thermo 3/10 CT, Couple attachment to the thata acquisition liquipment. There are a total of 380 thermocouples, the 3th In tollowing persequel. The tollowing Sandia Mark ablen Mark ablen By Woods Ol technocians and praject Manage. Deg Priest perform pur from checklisted trank Wydnit and Dee Priest vien Whe following operations are present to languat this fire test: Occapiest, Prenduct this fire test: Occapiest, Prenduct this fire test: Occapiest by Dept of Marian Woods Patton of Cohnician Zandencio Castanan Zandencio Castanan Trockard Regille Prochard Regille Prochard Regille Trank Hadde Teleptic Handet Temperature at time of flost shall 3/11/05 CT	ITEM		
arrive to inspect test article and wither tisting OP OF OC verifies the thermos 3/10 CH Couple affactment to the fata acquisition equipment, there are a total of 380 thermocouples, Ato 3/1/2 the following personnel, The test of project #, 23263; Panh Woods Sardia Mark aslen Boy Woods Woods OPI technicians and project Manager Dee Priest perform the form checking to trank Wyant and the priest sign Wind following of personnel, are Present to cardiot this fire test: Dee Priest President this fire test: Cardie Humphre, At Director Weda Patton S OF/18 Michael Degrale Sechnician Xandences Castanon Town Istrada Trank Jacke Carther May Michael Operannel on site! Manh Jacke Carther Amount 3/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1		The state of the s	CON
Couple aftachment to the fata acquisition lanipment, Ifile all a total of 550 thermocouples, the step of plowing personal 3/11 CT attle assured at OPL off witness The test of project #133263; Trank Wyunt Sandia Mark after Boy Woodso Ple technicians and project Manager Dea Priest Perform pur brush checklist trank Wyunt and Dee Priest view final popular and Dee Priest view final popular and Dee Priest view The following OPL personnel are Present to conduct this fire test: Dea Priest, President Canne Humphry Off Director Wicke Deer Priest, President Trank Humphry Dept O2 Mgr Pichard Extrada Tray gronstada	arrive to inspect test article		
Couple aftachment to the fata acquisition lanipment, Ifile all a total of 550 thermocouples, the step of plowing personal 3/11 CT attle assured at OPL off witness The test of project #133263; Trank Wyunt Sandia Mark after Boy Woodso Ple technicians and project Manager Dea Priest Perform pur brush checklist trank Wyunt and Dee Priest view final popular and Dee Priest view final popular and Dee Priest view The following OPL personnel are Present to conduct this fire test: Dea Priest, President Canne Humphry Off Director Wicke Deer Priest, President Trank Humphry Dept O2 Mgr Pichard Extrada Tray gronstada	and witness testing.		
acquisition langment, There are total of 580 thermocouples, the total of 580 thermocouples, the total of 1380 thermocouples, atte arrived at 0 ft 9th witness the arrived at 0 ft 9th witness the start of project #13323; Then by Woodso Plant and Saller Wark after us NRC Roy Woodso Or technicians and project manager Dee Priest person are fraject manager That Wyant and Dee Priest view of the following of person and accuments, The following of person and are Present to conduct this fire test: Orea Priest, principal Clocka Pattan Orth Dept 02 Mgr Wichard Harley Dept 02 Mgr Propagation astalanam That Deep personal of site of the person of the personal of the person of the p	OPL OA OC verifies the thermo,	3/10	CZI
are a total of 380 thermocouples, too the The Hollowine personnel 3/11 CT atte arrived at 0 Pt of switness the test of project #133263; Mark adlen Mark Saller Words Ore priest perform and project Manager Log Priest perform and project manager trank lityant and Dee Priest sign trank lityant and Dee Priest sign The following of personnel are Orean to sonduct this fire test: Deg Priest, President Consider Humphre Of Dientar Orean Estrada Trank Deer Saster Premaler personnel on site; Premaler personnel on site; Premaler personnel on site; Muchael Cordan Project Man Trank Haube Contact Anotalla Trank Haube Contact Anotalla	couple attackment to the data	-	
Atte assived at OPI The witness the test of project #123263; Trank Wyunt Sandea Mark Aller Mark Saller OPI technolicians and project Manager Dec Priest perform pre- frush checklist trank Myant and Dec Priest night final pole burn apprihaal dalumente, The following apri personnel are Present to addit personnel are Cannie Humphre At Director Weda Putter Dept 02 Mar Micke Decy Dept 02 Mar Pickard Pegsler Dechnician Tang pronstad foreman CH3/pls Premaler personnel on site; Randy Brown Steveral Mar Trank Haebe Cantact Anstaller Trank Haebe Cantact Anstaller Temperature at temp of test start 3/1/ps CH			
ate arrived at OP of witness the test of project #123263; Frank Wyant Sandia Mark affer Mark bespans and project manager Lea Prest perform pre- fruin chicklist trank Wyant and Dee Priest sign John Myant and Dee Priest sign John following affer personnel, are Present to confluct this fire test: Connie Humphre, affer Director Connie Humphre, affer Director Mike Deep Prest President Connie Humphre, affer Director Mike Deep Rasher Sechnician That pronstad forman (H3/1/ps Promater personnel on site; Rand, Brown Hereial Mark Michael Cordan project Mar Michael Cordan project Mar Michael Cordan project Mar Trank Hallse Carthers Anotalla	are a total of 380 thermocouples.	2/1	
The test of project #123263: Frank Wylint Sandia Mark Adlen Mark Saller Boy Woods OP tachoricians and project Manager Dee Priest Perform Die brush checklist! Frank Wyant and Die Priest vien The following GPI personnel are Present to conduct this fire test: Connie Humphre, Of Director Cloda Pattern D'OH/OR Michael Begster Zandencio Castanon Zandencio Castanon Troy Grongtod Forman CH3/1/ps Promater personnel on site: Rand, Brown Michael Gordan Project Mar Michael Gordan Project Mar Trank Jacke Central Andrew Temperature at teine of first staller Temperature at teine of first staller	, Fro 3/1/05 The following personnel	2/11	C 7
Trank Wylint Sandia Mark Ablen Wark Saller Boy Woods OPI technicians and praject Manager Dee Priest Perform pre-brush checklist! trank Wyant and Dee Priest man The following GPI personnel are Present to conduct this fire test: Connie Humphre, OA Director Cloda Pattern S OA/OC Michael Begsle, President Zandencio Castanon Zandencio Castanon Troy Gronstad Farman CH3/1/ps Promater personnel on site: Rand, Brown Serval Man Michael Gordan Project Man Trank Jacke Control Andaller Temperature at teine of test stall 3/1/ps CH			
Mark Saller USNRC Roy Woods O OPI technicians and project Manage Dec Priest perform pre-bown checklist Frank Myant and Dec Priest vien final pole burn approval documents, The following opt personnel are Present to enduct this fire test: Cannie Humphie, Of Director Clocka Patton S (A/DE) Pichard Begsler Dechnician Thoughous astanon Trong Gronstad Fareman CH3/1/ps Promater personnel on site; Randy Grown Serval Man Michael Grown Serval Man Trans Grown Fraject Man Trans Halve Centras Installer Temperature at time of test start 3/1/ps CH	the test of project # 123263:		
Mark Saller Roy Woods OPI technolicians and project Manager Dec Priest perform pre- bown checklist French Wyant and Dec Priest viens Jimal pole burn approval darryneuts, The following GPI personnel are Present to conduct this fire test: Consideration of the Director Cloda Patton of Cotto Miche Dey Dept 02 Man Pichard Brasler Dechnician Zandencio Castanon Tray Gronstad Forman CH 3/1/ps Promater personnel of site Man Promater personnel of site Man Trank Halse Cantact Installer Trank Halse Cantact Installer Temperature at sime of test start 3/1/ps CH			
Por technicians and praject manager Dec Priest perform pre- frush checklist! Frank Ungant and Dec Priest vient final pollowing of personnel are Present to a anduct this fire test: Cannie Humphre Of Director Clada Patton D Cot/Co Micke Dec Dept 02 Mgs Pichard Beasler Dechnician Zandencia Castanon Tray Bronstad Forman CH3/1/ps Promater personnel on site; Pandy Prown Frank Halve Cantact Mgs Trank Halve Cantact Mgs Temperature at time of test start 3/1/ps CH			
Deg Priest perform pue frush checklist! Isanh Mydert and Dee Priest vien Sinal pole burn approprial documents, The following OPI personnel are Present to conduct this fire test: Connie Humphre, OA Director Connie Humphre, OA Director Connie Humphre, OA Director Mich Dey Dept 02 Mgs Pichard Program Dept 02 Mgs Pichard Prospect Ochnician Zandencio Castanon Tong Browstad Farenam CH3//ps Promater personnel oy site; Promater personnel of test start 3//ps CH	Due Woods		
Deg Priest perform pue frush checklist! Isanh Mydert and Dee Priest vien Sinal pole burn approprial documents, The following OPI personnel are Present to conduct this fire test: Connie Humphre, OA Director Connie Humphre, OA Director Connie Humphre, OA Director Mich Dey Dept 02 Mgs Pichard Program Dept 02 Mgs Pichard Prospect Ochnician Zandencio Castanon Tong Browstad Farenam CH3//ps Promater personnel oy site; Promater personnel of test start 3//ps CH	mi tole a is in and miest many	2	
Frank My ant and Dee Priest sign final pole burn approval documents, The following OPI personnel are Present to conduct this fine test: Connie Humphre, OA Director Cloda Patton & CA/CC Mike Dey Dept 02 Man Pichard Begsler Dechnician Zandencio Castonon Orar Estrada Troy Bronstad Forman CH3/1/ps Promater personarel on site; Promater personarel on site; Michael Dordan Project Man Tranh Halve Cantroit Smotaller Temperature at teine of test start 3/1/ps CH	The Distance of the state of th	1	
The following of segsowned are Present to conduct this fire test: Consider Humphrey, Of Director Clocka Patton of CA/CC Mike Dey Pichard Beasley Dept 02 Mgs Pichard Beasley Dechnician Zandencio Castanon " Oscar Estrada Troy Bronstad Forman CH3/1/65 Premater personal on site; Premater personal on site; Premater personal on site; Premater personal on site; Trank Hadse Cantract Anotaller Temperature at time of test start 3/11/65 CH	Del Tour Control of the State o	-0	
The fallowing OPI sessamel are Present to adduct this fire test: Deg Priest, President Cannie Humphre, OA Director Cloda Patton D' CA/OC Mike Dey Dept 02 Mgr Pichard Beasler Dechnician Zandencio Castanon Zandencio Castanon Tray Bronstad Foreman CH3/1/05 Promatec personarel on site: Randy Brown Hereral Mgr Michael Gordan Project Mgr Michael Gordan Project Mgr Temperature at time of test start 3/11/05 CH		7.	
Present to conduct this fire test: Connie Humphrey, Ot Director Cloda Patton & CA/OC Mike Den Dept 02 Mgr Pichard Beasley Dechnician Zandencio Castanon Zandencio Castanon Trong Bronstad Foreman CH3/1/ps Promatec personanel on site; Randy Brown Hereral Mgr Michael Cordan Project Mgr Frank Halpe Contract Anotaller Temperature at time of test start 3/11/ps CH			
Connie Humphre, OA Duectas Noda Patton D CA/CC Mike Dey Dept 02 Mgs Pichard Beasler Dechnician Zandencia Castanon " Orcar Estrada Tray Bronstad Fareman CH3/1/ps Promater personarel on site; Randy Brown Steveral Mgs Michael Opedan Project Mgs Trank Halse Contract Anstaller Temperature at time of test start 3/11/ps CH			
Olega Patton D' OA/OC Mike Dey Dept 02 Mgs Pichard Beasler Dechnician Zandencio Castanon '' Oscar Estrada Tray Grons tad Foreman CH 3/11/05 Promatec personanel on site; Randy Brown Hereral Mgs Michael Gordan Project Mgs Tranh Hadse Contract Installer Temperature at time of test start 3/11/05 CH	Deg Priest, President,		
Pichard Beasler Pechnician Landencia Castanon Oscar Estrada Thay Brown tod Farman CH3/1/05 Promater personard on site; Randy Brown Several Man Michael Gordan Project Man Frank Halbe Contract Anstaller Temperature at time of test start 3/11/05 CH	Connie Humphrey, Of Buectas		
Pichard Beasler Pechnician Landencia Castanon Oscar Estrada Thay Brown tod Farman CH3/1/05 Promater personard on site; Randy Brown Several Man Michael Gordan Project Man Frank Halbe Contract Anstaller Temperature at time of test start 3/11/05 CH	aleda Patton & CA/CC		
Jandencia Castanon Oscar Estrada Tray Bronstad Foreman CH3/11/05 Promatec personarel on site; Randy Brown Several Man Michael Dordan Project Man Frank Halve Centrail Anstaller Temperature at time of test start 3/11/05 CH			
Orcar Estrada Francis Brown Farman CH3/1/05 Promater personal on site: Promater personal on site: Promater personal on site: Man Suchael Cordan Project Man Frank Halbe Centrail Anstaller Temperature at time of test start 3/11/05 CH			
From aler personarel on site: Promater personarel on site: Randy Brown Hereral Man Michael Gordan Project Man Frank Halbe Centract Anstaller Temperature at time of test start 3/11/05 CH			
Promater personal on site! Randy Brown Several Man Michael Gordan Project Man Frank Halve Centrait Installer Temperature at time of test start 3/11/05 CH			
Randy Brown Several Man Michael Gordan Project Man Frank Halbe Contract Installer Temperature at time of test start 3/11/05 CH			
Frank Halve Contract Installer Temperature at time of test start 3/11/05 CH	The state of the s		
Temperature at time of test start 3/11/05 CH			
is 5/4° F and the Relative Humidit	Frank blade Contains de stalla	2	
is 5/4° F and the Relative Humidit	The serature at time of fort start	3/1/25	(7/
13 60,		27.705	
	15 60, War		

EVENT LOG

Page 381

SANDIA NATIONAL LABORATORIES Client # 14790

NOTE:

This Log is used to document the date and note the significant events during the completion of test project #123263 for SANDIA National Laboratories. The following is a brief description of this project:

Project No. 123263:

Protected by Hemyc 1-Hour Rated ERFBS.		
	Page 8	of 8
ITEM	DATE,	INIT'L
The one hour firetest of Project	3/11/05	CH
#123263 is started at 9:09 am	, ,	
The test formace is shut off		
at 10:09 and the thermocodyles		
are disconnected from the data		
acquisition equilament.		
The test article is moved by	3/11	CH
overhead crane to the hose other	1 5	
area. a five minute, hase stream	7	
test followed the firetest using		
al-1/20 fog nozzle with a 15degre	e	
spray pattern at 75 psi from		
a distance of 10 feet.	,	/
after completion of the testing	3/11	071
Wike Deey OPL Dept 2 manages		
performed the past lest data		
acquisition verification		0-1
mar down and inspection of the	3/11	CX
test article was performed by		
Mike bly and OPC Connicians with		
Frank Wyant observing.		
0	ľ	

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 800-966-5253 FAX 210-635-8101

Certificate of Verification

Certification No.:

92143

Verification Date:

02/25/2005

Re-verification Date:

08/25/2005

Manufacturer:

Yokogawa

Model No.:

300 Channel DAU-

Serial No.:

48JF0082

Equipment Description:

300 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Calibration Sources:

Tegam T-156701 due: 07/26/2005

PERFORMANCE:

Temperature:	Temperature:	Temperature:	Temperature:	Temperature:	Temperature:
(75°F)	(150°F)	(300°F)	(400°F)	(1000°F)	(2000°F)
+1.8/-1.1	+1.7/-1	+1.8/-1.1	+1.9/-0.8	+1.8/-0.5	+2.5/-0.8

Measurement Uncertainty: ± 0.2%

Verification Performed by:

Mike Dey

Manager Fire Resistance

Verification Approved by:

Javier Trevino

Manager of Special Projects



Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): ____75.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	74.7	-0.3	101	75.0	0.0	201	74.5	-0.5
2	74.7	-0.3	102	75.0	0.0	202	74.5	-0.5
3	74.7	-0.3	103	75.0	0.0	203	74.5	-0.5
4	74.7	-0.3	104	75.0	0.0	204	74.5	-0.5
5	74.7	-0.3	105	75.0	0.0	205	74.7	-0.3
6	74.7	-0.3	106	75.0	0.0	206	74.7	-0.3
7	74.8	-0.2	107	75.2	0.2	207	74.8	-0.2
8	74.8	-0.2	108	75.2	0.2	208	74.8	-0.2
9	75.0	0.0	109	75.4	0.4	209	75.0	0.0
10	75.2	0.2	110	75.5	0.5	210	75.2	0.2
11	74.5	-0.5	111	75.0	0.0	211	74.5	-0.5
12	74.3	-0.7	112	75.0	0.0	212	74.5	-0.5
13	74.5	-0.5	113	75.4	0.4	213	74.5	-0.5
14	74.5	-0.5	114	75.4	0.4	214	74.5	-0.5
15	74.5	-0.5	115	75.4	0.4	215	74.5	-0.5
16	74.5	-0.5	116	75.4	0.4	216	74.7	-0.3
17	74.5	-0.5	117	75.5	0.5	217	74.7	-0.3
18	74.5	-0.5	118	75.5	0.5	218	74.7	-0.3
19	74.7	-0.3	119	75.5	0.5	219	74.8	-0.2
20	75.0	0.0	120	75.7	0.7	220	75.2	0.2
21	74.5	-0.5	121	75.5	0.5	221	73.9	-1.1
22	74.5	-0.5	122	75.5	0.5	222	74.1	-0.9
23	74.5	-0.5	123	75.4	0.4	223	74.3	-0.7
24	74.5	-0.5	124	75.5	0.5	224	74.3	-0.7
25	74.5	-0.5	125	75.5	0.5	225	74.3	-0.7
26	74.7	-0.3	126	75.5	0.5	226	74.5	-0.5
27	74.7	-0.3	127	75.5	0.5	227	74.5	-0.5
28	74.8	-0.2	128	75.5	0.5	228	74.5	-0.5
29	75.0	0.0	129	75.7	0.7	229	74.7	-0.3
30	75.2	0.2	130	76.1	1.1	230	75.0	0.0
31	74.5	-0.5	131	75.0	0.0	231	74.3	-0.7
32	74.5	-0.5	132	74.8	-0.2	232	74.3	-0.7
33	74.5	-0.5	133	74.8	-0.2	233	74.3	-0.7
34	74.5	-0.5	134	74.8	-0.2	234	74.3	-0.7
35	74.5	-0.5	135	75.0	0.0	235	74.5	-0.5
36	74.7	-0.3	136	75.0	0.0	236	74.5	-0.5
37	74.5	-0.5	137	75.2	0.2	237	74.5	-0.5
38	74.5	-0.5	138	75.2	0.2	238	74.7	-0.3
39	74.8	-0.2	139	75.4	0.4	239	74.8	-0.2
40	75.2	0.2	140	75.7	0.7	240	75.2	
41	73.2	-1.1	141	75.0		240	1	0.2
42	73.9	-1.1	141	75.0	0.0	242	74.8	-0.2
43	73.9	-0.9	142	75.0		242	74.7	-0.3
44	74.1	-0.9	143	75.0	0.0	243	74.8	-0.2
45	74.1	-0.9	144	75.0	0.0	244	74.8	-0.2
	-				11/2/1/2/2/2/2/2/2/2/2/2/2/2/2/2/2/2/2/		75.0	
46	74.3	-0.7	146	75.0	0.0	246	75.0	0.0
1192	74.1	-0.9	147	75.0	0.0	247	75.2	0.2
48	74.5	-0.5	148	75.0	0.0	248	75.2	0.2
49	74.5	-0.5	149	75.0	0.0	249	75.2	0.2
50	75.0	0.0	150	75.0	0.0	250	75.2	0.2
51	76.1	1.1	151	75.0	0.0	251	74.7	-0.3
52	76.3	1.3	152	74.8	-0.2	252	74.5	-0.5
53 54	76.3 76.3	1.3	153 154	74.8 74.8	-0.2	253 254	74.5 74.5	-0.5 -0.5

Page 384

55	76.3	1.3	155	75.0	0.0	255	74.5	-0.5
56	76.3	1.3	156	75.0	0.0	256	74.8	-0.2
57	76.3	1.3	157	75.0	0.0	257	74.8	-0.2
58	76.3	1.3	158	75.2	0.2	258	74.8	-0.2
59	76.5	1.5	159	75.2	0.2	259	74.8	-0.2
60	76.6	1.6	160	75.6	0.6	260	75.2	0.2
61	76.6	1.6	161	74.7	-0.3	261	74.7	-0.3
62	76.5	1.5	162	74.7	-0.3	262	74.7	-0.3
63	76.5	1.5	163	74.7	-0.3	263	74.8	-0.2
64	76.5	1.5	164	74.7	-0.3	264	74.7	-0.3
65	76.6	1.6	165	74.7	-0.3	265	74.8	-0.2
66	76.8	1.8	166	75.0	0.0	266	74.8	-0.2
67	76.8	1.8	167	75.0	0.0	267	74.8	-0.2
68	76.6	1.6	168	75.0	0.0	268	75.2	0.2
69	75.0	0.0	169	75.2	0.2	269	75.2	0.2
70	75.0	0.0	170	75.4	0.4	270	75.4	0.4
71	76.1	1.1	171	74.5	-0.5	271	75.0	0.0
72	76.5	1.5	172	74.3	-0.7	272	75.0	0.0
73	76.3	1.3	173	74.5	-0.5	273	75.0	0.0
74	76.3	1.3	174	74.5	-0.5	274	75.0	0.0
75	76.3	1.3	175	74.5	-0.5	275	75.2	0.2
76	76.1	1.1	176	74.5	-0.5	276	75.2	0.2
77	76.3	1.3	177	74.8	-0.2	277	75.2	0.2
78	76.3	1.3	178	74.8	-0.2	278	75.2	0.2
79	76.3	1.3	179	74.8	-0.2	279	75.4	0.4
80	76.6	1.6	180	75.0	0.0	280	75.7	0.7
81	76.3	1.3	181	74.8	-0.2	281	74.5	-0.5
82	76.1	1.1	182	74.8	-0.2	282	74.5	-0.5
83	76.3	1.3	183	74.8	-0.2	283	74.5	-0.5
84	76.3	1.3	184	74.8	-0.2	284	74.5	-0.5
85	76.1	1.1	185	74.8	-0.2	285	74.5	-0.5
86	76.1	1.1	186	75.0	0.0	286	74.7	-0.3
87	76.3	1.3	187	75.2	0.2	287	74.7	-0.3
88	76.3	1.3	188	75.2	0.2	288	74.7	-0.3
89	76.5	1.5	189	75.4	0.4	289	74.8	-0.2
90	76.6	1.6	190	75.7	0.7	290	75.2	0.2
91	76.3	1.3	191	74.8	-0.2	291	74.3	-0.7
92	76.3	1.3	192	74.7	-0.3	292	74.5	-0.5
93	76.3	1.3	193	74.8	-0.2	293	74.5	-0.5
94	76.3	1.3	194	74.8	-0.2	294	74.7	-0.3
95	76.3	1.3	195	74.8	-0.2	295	74.7	-0.3
96	76.5	1.5	196	74.8	-0.2	296	74.7	-0.3
97	76.3	1.3	197	75.0	0.0	297	75.0	0.0
98	76.3	1.3	198	75.0	0.0	298	75.0	0.0
99	76.3	1.3	199	75.0	0.0	299	75.0	0.0
100	76.3	1.3	200	75.0	0.0	300	75.0	0.0

Range for 75°F Signal: +1.8/-1.1
Allowable range: ±1.8

Within specification for this temperature?

Performed by:

Mgr. Fire Resistance

Title

Approved by:

Title Date

Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): 150.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	149.7	-0.3	101	150.1	0.1	201	149.7	-0.3
2	149.7	-0.3	102	150.1	0.1	202	149.5	-0.5
3	149.7	-0.3	103	150.1	0.1	203	149.5	-0.5
4	149.7	-0.3	104	150.1	0.1	204	149.5	-0.5
5	149.7	-0.3	105	150.1	0.1	205	149.5	-0.5
6	149.7	-0.3	106	150.1	0.1	206	149.7	-0.3
7	149.7	-0.3	107	150.2	0.2	207	149.7	-0.3
8	149.9	-0.1	108	150.2	0.2	208	149.9	-0.1
9	149.9	-0.1	109	150.4	0.4	209	150.1	0.1
10	150.3	0.3	110	150.6	0.6	210	150.3	0.3
11	149.4	-0.6	111	150.1	0.1	211	149.4	-0.6
12	149.4	-0.6	112	150.1	0.1	212	149.4	-0.6
13	149.4	-0.6	113	150.1	0.1	213	149.5	-0.5
14	149.4	-0.6	114	150.1	0.1	214	149.4	-0.6
15	149.5	-0.5	115	150.2	0.2	215	149.5	-0.5
16	149.5	-0.5	116	150.2	0.2	216	149.7	-0.3
17	149.7	-0.3	117	150.4	0.4	217	149.7	-0.3
18	149.7	-0.3	118	150.4	0.4	218	149.7	-0.3
19	149.7	-0.3	119	150.6	0.6	219	149.7	-0.3
20	149.9	-0.1	120	151.0	1.0	220	149.9	-0.1
21	149.4	-0.6	121	150.6	0.6	221	149.0	-1.0
22	149.4	-0.6	122	150.6	0.6	222	149.2	-0.8
23	149.4	-0.6	123	150.2	0.2	223	149.2	-0.8
24	149.4	-0.6	124	150.2	0.2	224	149.4	-0.6
25	149.4	-0.6	125	150.6	0.6	225	149.4	-0.6
26	149.5	-0.5	126	150.6	0.6	226	149.4	-0.6
27	149.4	-0.6	127	150.6	0.6	227	149.4	-0.6
28	149.5	-0.5	128	150.6	0.6	228	149.5	-0.5
29	149.7	-0.3	129	150.8	0.8	229	149.5	-0.5
30	149.7	-0.3	130	151.1	1.1	230	149.9	-0.1
31	149.5	-0.5	131	150.1	0.1	231	149.4	-0.6
32	149.5	-0.5	132	150.1	0.1	232	149.4	-0.6
33	149.5	-0.5	133	150.1	0.1	233	149.4	-0.6
34	149.7	-0.3	134	150.1	0.1	234	149.4	-0.6
	149.5		135	150.1	0.1	235	149.5	-0.5
35	149.5	-0.5 -0.3	136	150.1	0.1	236	149.5	-0.5
36 37	149.7	-0.3	137	150.4	0.4	237	149.5	-0.5
5176163	-	-0.3	138	150.4	0.4	238	149.5	-0.5
38	149.9		139	150.4	0.6	239	149.7	-0.3
39	149.9	-0.1	140	150.8	0.8	240	150.1	0.1
40	150.1	0.1		150.1	0.0	241	149.9	-0.1
41	149.0	-1.0	141	149.9		242	149.7	-0.3
42	149.0	-1.0	142		-0.1	242	149.7	-0.3
43	149.0	-1.0	143	150.1	0.1	243	149.7	-0.3
44	149.0	-1.0	144	150.1	0.1	244	149.7	-0.3
45	149.2	-0.8	145	150.1	0.1		30.000	(2) II
46	149.4	-0.6	146	150.1	0.1	246	150.1	0.1
47	149.2	-0.8	147	150.1	0.1	247	150.3	0.3
48	149.4	-0.6	148	150.1	0.1	248	150.3	0.3
49	149.4	-0.6	149	150.1	0.1	249	150.3	0.3
50	149.4	-0.6	150	150.1	0.1	250	150.3	0.3
51	150.8	0.8	151	149.9	-0.1	251	149.5	-0.5
52	150.8	0.8	152	149.7	-0.3	252	149.5	-0.5
53	150.8	0.8	153	149.7	-0.3	253	149.5	-0.5
54	151.0	1.0	154	149.7	-0.3	254	149.5	-0.5

Page 386

55	151.0	1.0	155	149.9	-0.1	255	149.7	-0.3
56	151.0	1.0	156	150.1	0.1	256	149.5	-0.5
57	151.2	1.2	157	150.1	0.1	257	149.7	-0.3
58	151.2	1.2	158	150.1	0.1	258	149.7	-0.3
59	151.3	1.3	159	150.3	0.3	259	150.1	0.1
60	151.3	1.3	160	150.4	0.4	260	150.3	0.3
61	150.6	0.6	161	149.7	-0.3	261	149.7	-0.3
62	151.0	1.0	162	149.5	-0.5	262	149.7	-0.3
63	151.2	1.2	163	149.5	-0.5	263	149.7	-0.3
64	151.3	1.3	164	149.7	-0.3	264	149.7	-0.3
65	151.3	1.3	165	149.7	-0.3	265	149.7	-0.3
66	151.3	1.3	166	149.7	-0.3	266	149.9	-0.1
	151.3	1.3	167	149.7	-0.3	267	149.9	-0.1
67	_	1.7	168	149.9	-0.1	268	149.9	-0.1
68	151.7		169	150.1	0.1	269	150.1	0.1
69	151.7	1.7		150.4	0.4	270	150.3	0.3
70	151.7	1.7	170			271	149.9	-0.1
71	151.2	1.2	171	149.4	-0.6	272	149.9	-0.1
72	151.2	1.2	172	149.4	-0.6	273	149.9	-0.1
73	151.2	1.2	173	149.4	-0.6			-0.1
74	151.2	1.2	174	149.4	-0.6	274	149.9	
75	151.3	1.3	175	149.5	-0.5	275	150.1	0.1
76	151.2	1.2	176	149.5	-0.5	276	150.1	0.1
77	151.3	1.3	177	149.7	-0.3	277	150.1	0.1
78	151.3	1.3	178	149.7	-0.3	278	150.1	0.1
79	151.3	1.3	179	149.7	-0.3	279	150.3	0.3
80	151.7	1.7	180	150.1	0.1	280	150.4	0.4
81	151.3	1.3	181	150.1	0.1	281	149.4	-0.6
82	151.2	1.2	182	150.1	0.1	282	149.4	-0.6
83	151.0	1.0	183	150.1	0.1	283	149.4	-0.6
84	151.2	1.2	184	150.1	0.1	284	149.4	-0.6
85	151.0	1.0	185	150.1	0.1	285	149.4	-0.6
86	151.2	1.2	186	150.1	0.1	286	149.5	-0.5
87	151.3	1.3	187	150.3	0.3	287	149.7	-0.3
88	151.3	1.3	188	150.3	0.3	288	149.7	-0.3
89	151.5	1.5	189	150.4	0.4	289	149.7	-0.3
90	151.5	1.5	190	150.8	0.8	290	150.1	0.1
91	151.3	1.3	191	149.7	-0.3	291	149.4	-0.6
92	151.3	1.3	192	149.7	-0.3	292	149.4	-0.6
93	151.3	1.3	193	149.7	-0.3	293	149.4	-0.6
94	151.3	1.3	194	149.7	-0.3	294	149.4	-0.6
95	151.3	1.3	195	149.9	-0.1	295	149.5	-0.5
100000	151.3	1.3	196	149.9	-0.1	296	149.7	-0.3
96	151.3	1.3	197	149.9	-0.1	297	149.7	-0.3
97			198	150.1	0.1	298	149.7	-0.3
98	151.3	1.3	198	150.1	0.1	299	149.7	-0.3
99	151.3 151.3	1.3	200	150.1	0.1	300	149.7	-0.3

Range for 150°F Signal: +1.7/-1 Allowable range: ± 1.8

Within specification for this tempera	ture? Yes	
Performed by: Why Deg	Mgr. Fire Resistance	2/25/05
	Title	Date
Approved by:		

Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): 300.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	299.5	-0.5	101	300.0	0.0	201	299.5	-0.5
2	299.5	-0.5	102	300.0	0.0	202	299.5	-0.5
3	299.5	-0.5	103	300.0	0.0	203	299.5	-0.5
4	299.5	-0.5	104	300.0	0.0	204	299.5	-0.5
5	299.5	-0.5	105	300.0	0.0	205	299.5	-0.5
6	299.5	-0.5	106	300.0	0.0	206	299.8	-0.2
7	299.7	-0.3	107	300.0	0.0	207	299.8	-0.2
8	299.7	-0.3	108	300.0	0.0	208	299.8	-0.2
9	299.8	-0.2	109	300.2	0.2	209	300.0	0.0
10	300.2	0.2	110	300.5	0.5	210	300.2	0.2
11	299.5	-0.5	111	300.0	0.0	211	299.5	-0.5
12	299.1	-0.9	112	300.0	0.0	212	299.3	-0.7
13	299.3	-0.7	113	300.2	0.2	213	299.5	-0.5
14	299.3	-0.7	114	300.2	0.2	214	299.5	-0.5
15	299.3	-0.7	115	300.4	0.4	215	299.5	-0.5
16	299.3	-0.7	116	300.2	0.2	216	299.5	-0.5
17	299.5	-0.5	117	300.4	0.4	217	299.5	-0.5
18	299.5	-0.5	118	300.4	0.4	218	299.5	-0.5
19	299.5	-0.5	119	300.5	0.5	219	299.8	-0.2
20	299.8	-0.2	120	300.7	0.7	220	300.0	0.0
21	299.5	-0.5	121	300.4	0.4	221	299.1	-0.9
22	299.3	-0.7	122	300.2	0.2	222	299.1	-0.9
	299.3		123	300.0	0.0	223	299.3	-0.7
23	-	-0.7	123	300.0	0.0	224	299.3	-0.7
24	299.5	-0.5	125	300.4	0.4	225	299.3	-0.7
25	299.5	-0.5			0.4	226	299.3	-0.7
26	299.5	-0.5	126	300.4		227	299.5	-0.5
27	299.5	-0.5	127	300.5	0.5		_	-0.5
28	299.5	-0.5	128	300.7	0.7	228	299.5	
29	299.5	-0.5	129	300.7	0.7	229	299.5 299.8	-0.5
30	299.8	-0.2	130	301.1	1.1	230		-0.2
31	299.7	-0.3	131	300.0	0.0	231	299.3	-0.7
32	299.7	-0.3	132	299.8	-0.2	232	299.3	-0.7
33	299.5	-0.5	133	299.8	-0.2	233	299.3	-0.7
34	299.5	-0.5	134	299.8	-0.2	234	299.5	-0.5
35	299.5	-0.5	135	299.8	-0.2	235	299.5	-0.5
36	299.5	-0.5	136	299.8	-0.2	236	299.5	-0.5
37	299.7	-0.3	137	300.0	0.0	237	299.5	-0.5
38	299.7	-0.3	138	300.0	0.0	238	299.5	-0.
39	299.8	-0.2	139	300.4	0.4	239	299.8	-0.2
40	300.2	0.2	140	300.7	0.7	240	300.0	0.0
41	299.1	-0.9	141	299.8	-0.2	241	299.8	-0.2
42	298.9	-1.1	142	299.8	-0.2	242	299.7	-0.3
43	298.9	-1.1	143	300.0	0.0	243	299.8	-0.2
44	299.1	-0.9	144	300.0	0.0	244	299.8	-0.2
45	299.1	-0.9	145	300.0	0.0	245	300.0	0.0
46	299.3	-0.7	146	300.0	0.0	246	300.2	0.2
47	299.3	-0.7	147	300.0	0.0	247	300.2	0.2
48	299.5	-0.5	148	300.0	0.0	248	300.2	0.2
49	299.5	-0.5	149	300.0	0.0	249	300.2	0.2
50	300.6	0.6	150	299.8	-0.2	250	300.2	0.2
51	300.6	0.6	151	299.8	-0.2	251	299.5	-0.5
52	300.6	0.6	152	299.8	-0.2	252	299.5	-0.5
53	300.6	0.6	153	299.8	-0.2	253	299.5	-0.5
54	300.7	0.7	154	299.8	-0.2	254	299.5	-0.5
55	300.7	0.7	155	299.8	-0.2	255	299.5	-0.5
56	300.7	0.6	156	299.8	-0.2	256	299.5	-0.5

Page 388

57	300.7	0.7	157	300.0	0.0	257	299.7	-0.3
58	300.9	0.9	158	300.2	0.2	258	299.7	-0.3
59	301.1	1.1	159	300.2	0.2	259	300.0	0.0
60	301.3	1.3	160	300.4	0.4	260	300.2	0.2
61	301.3	1.3	161	299.5	-0.5	261	299.5	-0.5
62	301.3	1.3	162	299.5	-0.5	262	299.5	-0.5
63	301.1	1.1	163	299.5	-0.5	263	299.5	-0.5
64	301.1	1.1	164	299.5	-0.5	264	299.7	-0.3
65	301.3	1.3	165	299.7	-0.3	265	299.8	-0.2
66	301.3	1.3	166	299.7	-0.3	266	299.8	-0.2
67	301.3	1.3	167	299.8	-0.2	267	300.0	0.0
68	301.3	1.3	168	300.0	0.0	268	300.0	0.0
69	301.5	1.5	169	300.2	0.2	269	300.2	0.2
70	301.8	1.8	170	300.4	0.4	270	300.4	0.4
71	301.1	1.1	171	299.1	-0.9	271	299.8	-0.2
72	300.9	0.9	172	299.3	-0.7	272	299.8	-0.2
73	301.1	1.1	173	299.3	-0.7	273	299.8	-0.2
74	301.1	1.1	174	299.3	-0.7	274	299.8	-0.2
75	301.3	1.3	175	299.3	-0.7	275	300.0	0.0
76	301.1	1.1	176	299.5	-0.5	276	300.0	0.0
77	301.3	1.3	177	299.5	-0.5	277	300.2	0.2
78	301.3	1.3	178	299.5	-0.5	278	300.2	0.2
79	301.5	1.5	179	299.7	-0.3	279	300.4	0.4
80	301.8	1.8	180	300.2	0.2	280	300.7	0.7
81	301.3	1.3	181	299.8	-0.2	281	299.3	-0.7
82	301.3	1.3	182	299.7	-0.3	282	299.3	-0.7
83	301.3	1.3	183	299.8	-0.2	283	299.3	-0.7
84	301.3	1.3	184	300.0	0.0	284	299.3	-0.7
85	301.1	1.1	185	300.0	0.0	285	299.5	-0.5
86	301.3	1.3	186	300.0	0.0	286	299.5	-0.5
87	301.3	1.3	187	300.2	0.2	287	299.5	-0.5
88	301.3	1.3	188	300.2	0.2	288	299.5	-0.5
89	301.3	1.3	189	300.4	0.4	289	299.7	-0.3
90	301.6	1.6	190	300.7	0.7	290	300.0	0.0
91	301.3	1.3	191	299.7	-0.3	291	299.3	-0.7
92	301.3	1.3	192	299.7	-0.3	292	299.3	-0.7
93	301.3	1.3	193	299.7	-0.3	293	299.5	-0.5
94	301.3	1.3	194	299.7	-0.3	294	299.5	-0.5
95	301.3	1.3	195	299.8	-0.2	295	299.7	-0.3
96	301.3	1.3	196	299.8	-0.2	296	299.7	-0.3
97	301.3	1.3	197	299.8	-0.2	297	299.8	-0.2
98	301.3	1.3	198	299.8	-0.2	298	299.7	-0.3
99	301.3	1.3	199	299.8	-0.2	299	299.7	-0.3
100	301.3	1.3	200	299.8	-0.2	300	299.7	-0.3

Range for 300°F Signal: +1.8/-1.1Allowable range ± 1.9

Within specification for this temperature?

Yes

Performed by:

M. D.

Mgr. Fire Resistance Title

2/25/05

Approved by:

Mgroy

Date

Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): 400.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	399.6	-0.4	101	400.3	0.3	201	399.7	-0.3
2	399.6	-0.4	102	400.1	0.1	202	399.6	-0.4
3	399.6	-0.4	103	400.1	0.1	203	399.6	-0.4
4	399.6	-0.4	104	400.3	0.3	204	399.6	-0.4
5	399.6	-0.4	105	400.3	0.3	205	399.6	-0.4
6	399.6	-0.4	106	400.3	0.3	206	399.7	-0.3
7	399.6	-0.4	107	400.3	0.3	207	399.9	-0.1
8	399.6	-0.4	108	400.4	0.4	208	399.9	-0.1
9	399.7	-0.3	109	400.4	0.4	209	400.3	0.3
10	399.9	-0.1	110	400.6	0.6	210	400.3	0.3
11	399.2	-0.8	111	400.1	0.1	211	399.4	-0.6
12	399.2	-0.8	112	400.1	0.1	212	399.6	-0.4
13	399.2	-0.8	113	400.3	0.3	213	399.6	-0.4
14	399.4	-0.6	114	400.3	0.3	214	399.6	-0.4
15	399.4	-0.6	115	400.4	0.4	215	399.6	-0.4
16	399.4	-0.6	116	400.4	0.4	216	399.7	-0.3
17	399.4	-0.6	117	400.6	0.6	217	399.7	-0.3
	399.4	-0.6	118	400.6	0.6	218	399.7	-0.3
18		-0.4	119	400.8	0.8	219	399.9	-0.
19	399.6		120	400.8	0.8	220	400.1	0.1
20	399.7	-0.3		400.8	0.8	221	399.4	-0.6
21	399.4	-0.6	121	400.6	0.6	222	399.4	-0.6
22	399.4	-0.6				223	399.2	-0.6
23	399.2	-0.8	123	400.4	0.4	224	399.4	-0.6
24	399.2	-0.8	124	400.4	0.4		399.4	-0.6
25	399.4	-0.6	125	400.6	0.6	225	399.4	1277
26	399.4	-0.6	126	400.6	0.6	226	_	-0.6
27	399.6	-0.4	127	400.6	0.6	227	399.6	-0.4
28	399.6	-0.4	128	400.6	0.6	228	399.6	-0.4
29	399.6	-0.4	129	400.8	0.8	229	399.7	-0.3
30	399.7	-0.3	130	401.2	1.2	230	400.1	0.1
31	399.6	-0.4	131	400.1	0.1	231	399.6	-0.4
32	399.4	-0.6	132	400.1	0.1	232	399.6	-0.4
33	399.4	-0.6	133	400.1	0.1	233	399.6	-0.4
34	399.6	-0.4	134	400.1	0.1	234	399.6	-0.4
35	399.6	-0.4	135	400.1	0.1	235	399.6	-0.4
36	399.6	-0.4	136	400.1	0.1	236	399.6	-0.4
37	399.6	-0.4	137	400.3	0.3	237	399.6	-0.4
38	399.9	-0.1	138	400.3	0.3	238	399.6	-0.4
39	399.9	-0.1	139	400.4	0.4	239	399.7	-0.3
40	400.3	0.3	140	400.6	0.6	240	400.3	0.3
41	399.4	-0.6	141	400.1	0.1	241	399.9	-0.
42	399.4	-0.6	142	399.9	-0.1	242	399.9	-0.
43	399.4	-0.6	143	400.1	0.1	243	399.9	-0.
44	399.4	-0.6	144	400.1	0.1	244	399.9	-0.
45	399.4	-0.6	145	400.1	0.1	245	400.1	0.1
46	399.4	-0.6	146	400.1	0.1	246	400.3	0.3
47	399.4	-0.6	147	400.1	0.1	247	400.3	0.3
48	399.6	-0.4	148	400.1	0.1	248	400.5	0.5
49	399.6	-0.4	149	400.1	0.1	249	400.5	0.5
50	399.6	-0.4	150	400.1	0.1	250	400.5	0.5
51	400.8	0.8	151	399.9	-0.1	251	399.6	-0.4
52	400.8	0.8	152	399.7	-0.3	252	399.6	-0.4
53	400.8	0.8	153	399.7	-0.3	253	399.6	-0.4
54	400.8	0.8	154	399.7	-0.3	254	399.6	-0.4

Page 390

55	400.8	0.8	155	400.1	0.1	255	399.6	-0.4
56	401.0	1.0	156	399.9	-0.1	256	399.6	-0.4
57	401.0	1.0	157	400.1	0.1	257	399.6	-0.4
58	401.2	1.2	158	400.1	0.1	258	399.7	-0.3
59	401.2	1.2	159	400.3	0.3	259	399.9	-0.1
60	401.4	1.4	160	400.6	0.6	260	400.3	0.3
61	401.4	1.4	161	399.7	-0.3	261	399.6	-0.4
62	401.2	1.2	162	399.6	-0.4	262	399.6	-0.4
63	401.2	1.2	163	399.6	-0.4	263	399.7	-0.3
64	401.2	1.2	164	399.7	-0.3	264	399.6	-0.4
65	401.4	1.4	165	399.7	-0.3	265	399.7	-0.3
66	401.4	1.4	166	399.7	-0.3	266	399.7	-0.3
	401.4	1.5	167	399.9	-0.1	267	399.9	-0.1
67	401.5	1.5	168	400.3	0.3	268	400.1	0.1
68	-	1.7	169	400.3	0.3	269	400.3	0.3
69	401.7		170	400.3	0.3	270	400.5	0.5
70	401.1	1.1		399.6	-0.4	271	399.7	-0.3
71	401.2	1.2	171 172	399.4	-0.4	272	399.7	-0.3
72	401.2	1.2		399.6	-0.4	273	399.7	-0.3
73	401.2	1.2	173		-0.4	274	399.7	-0.3
74	401.2	1.2	174	399.6		275	400.1	0.1
75	401.4	1.4	175	399.6	-0.4	276	400.1	0.1
76	401.4	1.4	176	399.6	-0.4		400.1	0.3
77	401.4	1.4	177	399.7	-0.3	277	400.3	0.3
78	401.4	1.4	178	399.7	-0.3	278	400.5	0.5
79	401.5	1.5	179	399.9	-0.1	279	_	
80	401.9	1.9	180	400.3	0.3	280	400.6	0.6
81	401.4	1.4	181	399.9	-0.1	281	399.4	-0.6
82	401.2	1.2	182	399.7	-0.3	282	399.4	-0.6
83	401.2	1.2	183	399.6	-0.4	283	399.4	-0.6
84	401.4	1.4	184	399.7	-0.3	284	399.6	-0.4
85	401.4	1.4	185	399.7	-0.3	285	399.6	-0.4
86	401.4	1.4	186	399.9	-0.1	286	399.6	-0.4
87	401.4	1.4	187	399.9	-0.1	287	399.7	-0.3
88	401.4	1.4	188	400.3	0.3	288	399.9	-0.1
89	401.5	1.5	189	400.3	0.3	289	399.9	-0.1
90	401.9	1.9	190	400.6	0.6	290	400.1	0.1
91	401.4	1.4	191	399.6	-0.4	291	399.4	-0.6
92	401.4	1.4	192	399.6	-0.4	292	399.4	-0.6
93	401.4	1,4	193	399.6	-0.4	293	399.6	-0.4
94	401.4	1.4	194	399.6	-0.4	294	399.6	-0.4
95	401.4	1.4	195	399.6	-0.4	295	399.6	-0.4
96	401.5	1.5	196	399.7	-0.3	296	399.6	-0.4
97	401.4	1.4	197	399.7	-0.3	297	399.7	-0.3
98	401.4	1.4	198	399.7	-0.3	298	399.9	-0.1
99	401.4	1.4	199	399.7	-0.3	299	399.9	-0.1
100	401.4	1.4	200	399.6	-0.4	300	399.9	-0.1

Range for 400°F Signal: +1.9/-0.8
Allowable range: ±2.0
Within specification for this temperature?

Yes

Performed by:

Approved by:

Mgr. Fire Resistance Title 2/25/05 Date

Date

Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): 1000.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	999.7	-0.3	101	1000.0	0.0	201	1000.0	0.0
2	999.5	-0.5	102	1000.0	0.0	202	1000.0	0.0
3	999.5	-0.5	103	1000.0	0.0	203	1000.0	0.0
4	999.7	-0.3	104	1000.0	0.0	204	1000.0	0.0
5	999.7	-0.3	105	1000.0	0.0	205	1000.2	0.2
6	999.7	-0.3	106	1000.0	0.0	206	1000.4	0.4
7	999.9	-0.1	107	1000.0	0.0	207	1000.4	0.4
8	999.9	-0.1	108	1000.0	0.0	208	1000.4	0.4
9	1000.0	0.0	109	1000.2	0.2	209	1000.6	0.6
10	1000.2	0.2	110	1000.4	0.4	210	1000.6	0.6
11	999.5	-0.5	111	999.8	-0.2	211	999.9	-0.1
12	999.5	-0.5	112	999.8	-0.2	212	999.9	-0.1
13	999.5	-0.5	113	1000.0	0.0	213	999.9	-0.1
14	999.5	-0.5	114	1000.0	0.0	214	999.9	-0.1
15	999.5	-0.5	115	1000.2	0.2	215	999.9	-0.1
	999.5		116	1000.2	0.2	216	1000.0	0.0
16	- -1 1	-0.5	117	1000.2	0.4	217	1000.0	0.0
17	999.5	-0.5		_	0.4	218	1000.0	0.0
18	999.7	-0.3	118	1000.4	0.4	219	1000.0	0.2
19	999.7	-0.3		11/17/2016		220	1000.6	0.6
20	999.9	-0.1	120	1000.6	0.6	221	999.7	-0.3
21	999.5	-0.5	121	1000.4	0.4	222	999.7	-0.3
22	999.5	-0.5	122	1000.2	0.2			
23	999.5	-0.5	123	1000.0	0.0	223	999.9	-0.1
24	999.5	-0.5	124	1000.0	0.0	224	999.9	-0.1
25	999.5	-0.5	125	1000.4	0.4	225	999.9	-0.1
26	999.5	-0.5	126	1000.4	0.4	226	999.9	-0.1
27	999.5	-0.5	127	1000.4	0.4	227	999.9	-0.1
28	999.7	-0.3	128	1000.6	0.6	228	999.9	-0.1
29	999.7	-0.3	129	1000.6	0.6	229	1000.0	0.0
30	1000.0	0.0	130	1000.9	0.9	230	1000.2	0.2
31	1000.0	0.0	131	999.8	-0.2	231	999.7	-0.3
32	999.7	-0.3	132	999.7	-0.3	232	999.7	-0.3
33	999.9	-0.1	133	999.7	-0.3	233	999.9	-0.1
34	999.9	-0.1	134	999.8	-0.2	234	999.9	-0.1
35	999.9	-0.1	135	1000.0	0.0	235	1000.0	0.0
36	999.9	-0.1	136	999.8	-0.2	236	1000.0	0.0
37	1000.0	0.0	137	1000.0	0.0	237	1000.0	0.0
38	1000.0	0.0	138	1000.2	0.2	238	1000.2	0.2
39	1000.0	0.0	139	1000.2	0.2	239	1000.4	0.4
40	1000.4	0.4	140	1000.6	0.6	240	1000.6	0.6
41	999.5	-0.5	141	999.8	-0.2	241	1000.4	0.4
42	999.5	-0.5	142	999.7	-0.3	242	1000.2	0.2
43	999.5	-0.5	143	999.8	-0.2	243	1000.2	0.2
44	999.5	-0.5	144	999.7	-0.3	244	1000.2	0.2
45	999.7		145	999.7	-0.3	245	1000.4	0.4
27.35.01	999.7	-0.3	146	999.7	-0.3	246	1000.2	0.2
46		Transmission.	147	999.8	-0.2	247	1000.4	0.4
47	999.7	-0.3	148	999.8	-0.2	248	1000.6	0.6
48	999.7	-0.3		1001.8	1.8	249	1000.6	0.6
49	999.7	-0.3	149	1001.8		250	1000.6	0.6
50	999.7	-0.3	150		1.8		1000.0	0.0
51	1000.6	0.6	151	1000.2	0.2	251	_	
52	1000.6	0.6	152	1000.0	0.0	252	999.7	-0.3
53	1000.8	0.8	153	1000.0	0.0	253	999.7	-0.3
54	1000.8	0.8	154	1000.0	0.0	254	999.9	-0.
55	1000.9	0.9	155	1000.0	0.0	255	1000.0	0.0
56	1000.9	0.9	156	1000.2	0.2	256	1000.0	0.0

Page 392

57	1000.9	0.9	157	1000.4	0.4	257	1000.0	0.0
58	1000.9	0.9	158	1000.6	0.6	258	1000.0	0.0
59	1001.1	1.1	159	1000.6	0.6	259	1000.0	0.0
60	1001.3	1.3	160	1000.9	0.9	260	1000.6	0.6
61	1001.5	1.5	161	1000.0	0.0	261	1000.0	0.0
62	1001.3	1.3	162	1000.0	0.0	262	999.9	-0.1
63	1001.3	1.3	163	1000.0	0.0	263	1000.0	0.0
64	1001.3	1.3	164	1000.0	0.0	264	1000.0	0.0
65	1001.5	1.5	165	1000.0	0.0	265	1000.2	0.2
66	1001.3	1.3	166	1000.0	0.0	266	1000.2	0.2
67	1001.3	1.3	167	1000.0	0.0	267	1000.2	0.2
68	1001.5	1.5	168	1000.2	0.2	268	1000.4	0.4
69	1001.7	1.7	169	1000.4	0.4	269	1000.6	0.6
70	1001.8	1.8	170	1000.6	0.6	270	1000.6	0.6
71	1001.1	1.1	171	999.7	-0.3	271	1000.0	0.0
72	1001.1	1.1	172	999.7	-0.3	272	1000.0	0.0
73	1001.1	1.1	173	999.9	-0.1	273	1000.0	0.0
74	1001.1	1.1	174	999.9	-0.1	274	1000.0	0.0
75	1001.1	1.1	175	999.7	-0.3	275	1000.0	0.0
76	1001.3	1.3	176	999.9	-0.1	276	1000.0	0.0
77	1001.5	1.5	177	1000.0	0.0	277	1000.2	0.2
78	1001.5	1.5	178	1000.0	0.0	278	1000.2	0.2
79	1001.5	1.5	179	1000.2	0.2	279	1000.6	0.6
80	1001.8	1.8	180	1000.6	0.6	280	1000.6	0.6
81	1001.5	1.5	181	1000.6	0.6	281	999.5	-0.5
82	1001.3	1.3	182	1000.4	0.4	282	999.5	-0.5
83	1001.3	1.3	183	1000.6	0.6	283	999.5	-0.5
84	1001.3	1.3	184	1000.6	0.6	284	999.5	-0.5
85	1001.3	1.3	185	1000.6	0.6	285	999.5	-0.5
86	1001.3	1.3	186	1000.6	0.6	286	999.5	-0.5
87	1001.3	1.3	187	1000.6	0.6	287	999.7	-0.3
88	1001.5	1.5	188	1000.8	0.8	288	999.7	-0.3
89	1001.5	1.5	189	1000.9	0.9	289	999.9	-0.1
90	1001.7	1.7	190	1001.1	1.1	290	1000.0	0.0
91	1001.5	1.5	191	1000.2	0.2	291	999.5	-0.5
92	1001.1	1.1	192	1000.2	0.2	292	999.7	-0.3
93	1001.3	1.3	193	1000.2	0.2	293	999.7	-0.3
94	1001.3	1.3	194	1000.4	0.4	294	999.7	-0.3
95	1001.5	1.5	195	1000.6	0.6	295	999.7	-0.3
96	1001.5	1.5	196	1000.6	0.6	296	999.7	-0.3
97	1001.5	1.5	197	1000.6	0.6	297	999.7	-0.3
98	1001.5	1.5	198	1000.6	0.6	298	999.7	-0.3
99	1001.5	1.5	199	1000.6	0.6	299	999.7	-0.3
100	1001.5	1.5	200	1000.6	0.6	300	999.7	-0.3

Range for 1000°F Signal: +1.8/-0.5
Allowable range: ±2.3
Within specification for this temperature?

Yes

Performed by:



Mgr. Fire Resistance Title 2/25/05 Date

Approved by:

Title

Date

Serial No.: 48JF0082

Calibrator Used: SNT156701

Temperature Setting (°F): 2000.0

hannel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1999.8	-0.2	101	1999.7	-0.3	201	2000.7	0.7
2	1999.6	-0.4	102	1999.7	-0.3	202	2000.7	0.7
3	1999.4	-0.6	103	1999.7	-0.3	203	2000.7	0.7
4	1999.6	-0.4	104	1999.7	-0.3	204	2000.7	0.7
5	1999.6	-0.4	105	1999.9	-0.1	205	2000.7	0.7
6	1999.6	-0.4	106	1999.9	-0.1	206	2000.8	0.8
7	1999.8	-0.2	107	2000.1	0.1	207	2001.0	1.0
8	1999.8	-0.2	108	2000.1	0.1	208	2001.0	1.0
9	1999.9	-0.1	109	2000.3	0.3	209	2001.2	1.2
10	2000.3	0.3	110	2000.6	0.6	210	2001.6	1.6
11	1999.4	-0.6	111	1999.7	-0.3	211	2000.7	0.7
12	1999.2	-0.8	112	1999.7	-0.3	212	2000.7	0.7
13	1999.2	-0.8	113	1999.9	-0.1	213	2000.7	0.7
14	1999.4	-0.6	114	1999.9	-0.1	214	2000.8	0.8
15	1999.4	-0.6	115	1999.9	-0.1	215	2000.8	0.8
16	1999.4	-0.6	116	2000.1	0.1	216	2000.8	0.8
17	1999.4	-0.6	117	2000.1	0.1	217	2001.0	1.0
	1999.4	-0.6	118	2000.3	0.3	218	2001.0	1.0
18	1999.4	-0.6	119	2000.5	0.5	219	2001.0	1.0
19	-	-0.1	120	2000.6	0.6	220	2001.2	1.2
20	1999.9	-0.8	121	2000.1	0.1	221	2000.5	0.5
21	1999.2	-0.8	122	2000.1	0.1	222	2000.5	0.5
22	_		123	1999.7	-0.3	223	2000.7	0.7
23	1999.2	-0.8	124	1999.7	-0.3	224	2000.7	0.7
24	1999.2	-0.8	125	2000.3	0.3	225	2000.7	0.7
25	1999.6	-0.4	126	2000.3	0.3	226	2000.7	0.7
26	1999.6	-0.4		2000.5	0.5	227	2000.7	0.7
27	1999.6	-0.4	127	2000.6	0.6	228	2000.7	0.7
28	1999.8	-0.2	128	2000.6	0.6	229	2001.0	1.0
29	1999.9	-0.1	129	2001.0	1.0	230	2001.0	1.0
30	2000.1	0.1	130	_		231	2000.7	0.7
31	2000.1	0.1	131	1999.9	-0.1	232	2000.7	0.7
32	2000.1	0.1	132	1999.7	-0.3	233	2000.7	0.7
33	2000.3	0.3	133	1999.7	-0.3		2000.7	0.7
34	2000.3	0.3	134	1999.9	-0.1	234		0.8
35	2000.3	0.3	135	1999.7	-0.3	235	2000.8	0.0
36	2000.3	0.3	136	1999.7	-0.3	236		1.0
37	2000.5	0.5	137	2000.1	0.1	237	2001.0	
38	2000.7	0.7	138	2000.1	0.1	238	2001.0	1.0
39	2000.7	0.7	139	2000.3	0.3	239	2001.0	1.0
40	2000.8	0.8	140	2000.6	0.6	240	2001.2	1.3
41	1999.9	-0.1	141	1999.7	-0.3	241	2000.7	0.
42	1999.9	-0.1	142	1999.7	-0.3	242	2000.7	0.
43	1999.9	-0.1	143	1999.7	-0.3	243	2000.7	0.
44	1999.9	-0.1	144	1999.7	-0.3	244	2000.7	0.
45	1999.9	-0.1	145	1999.7	-0.3	245	2000.8	
46	1999.9	-0.1	146	1999.7	-0.3	246	2000.8	0.1
47	1999.9	-0.1	147	1999.7	-0.3	247	2001.0	1.0
48	2000.1	0.1	148	1999.9	-0.1	248	2001.0	1.0
49	2000.1	0.1	149	1999.9	-0.1	249	2001.0	1.
50	2000.1	0.1	150	1999.9	-0.1	250	2001.0	1.
51	2000.7	0.7	151	2000.7	0.7	251	2000.1	0.
52	2000.7	0.7	152	2000.7	0.7	252	1999.9	-0.
53	2000.7	0.7	153	2000.7	0.7	253	2000.1	0.
54	2000.7	0.7	154	2000.7	0.7	254	2000.3	0.
	2000.7	0.8	155	2000.8	0.8	255	2000.5	0.
55 56	2000.8	0.7	156	2000.8	0.8	256	2000.5	0.

Page 394

57	2000.7	0.7	157	2001.0	1.0	257	2000.7	0.7
58	2000.8	0.8	158	2001.0	1.0	258	2000.7	0.7
59	2001.0	1.0	159	2001.0	1.0	259	2000.7	0.7
60	2001.2	1.2	160	2001.4	1.4	260	2000.8	0.8
61	2001.7	1.7	161	2000.7	0.7	261	2000.3	0.3
62	2001.6	1.6	162	2000.5	0.5	262	2000.1	0.1
63	2001.6	1.6	163	2000.5	0.5	263	2000.1	0.1
64	2001.6	1.6	164	2000.7	0.7	264	2000.3	0.3
65	2001.7	1.7	165	2000.7	0.7	265	2000.5	0.5
66	2001.7	1.7	166	2000.7	0.7	266	2000.7	0.7
67	2001.7	1.7	167	2000.8	8.0	267	2000.7	0.7
68	2001.7	1.7	168	2001.0	1.0	268	2000.7	0.7
69	2002.1	2.1	169	2001.0	1.0	269	2000.8	0.8
70	2002.5	2.5	170	2001.2	1.2	270	2001.0	1.0
71	2001.6	1.6	171	2000.3	0.3	271	1999.9	-0.1
72	2001.7	1.7	172	2000.3	0.3	272	2000.1	0.1
73	2001.6	1.6	173	2000.3	0.3	273	2000.1	0.1
74.	2001.6	1.6	174	2000.5	0.5	274	2000.1	0.1
75	2001.6	1.6	175	2000.7	0.7	275	2000.3	0.3
76	2001.6	1.6	176	2000.7	0.7	276	2000.3	0.3
77	2001.7	1.7	177	2000.7	0.7	277	2000.3	0.3
78	2001.7	1.7	178	2000.7	0.7	278	2000.3	0.3
79	2001.7	1.7	179	2000.8	0.8	279	2000.7	0.7
80	2002.1	2.1	180	2001.0	1.0	280	2000.8	0.8
81	2001.6	1.6	181	2001.0	1.0	281	1999.4	-0.6
82	2001.6	1.6	182	2001.0	1.0	282	1999.6	-0.4
83	2001.6	1.6	183	2001.0	1.0	283	1999.6	-0.4
84	2001.6	1.6	184	2001.0	1.0	284	1999.8	-0.2
85	2001.6	1.6	185	2001.0	1.0	285	1999.8	-0.2
86	2001.6	1.6	186	2001.0	1.0	286	1999.8	-0.2
87	2001.7	1.7	187	2001.4	1.4	287	1999.9	-0.1
88	2001.7	1.7	188	2001.4	1.4	288	1999.9	-0.1
89	2001.7	1.7	189	2001.7	1.7	289	1999.9	-0.1
90	2002.1	2,1	190	2002.1	2.1	290	2000.1	0.1
91	2001.6	1.6	191	2001.0	1.0	291	1999.4	-0.6
92	2001.6	1.6	192	2001.0	1.0	292	1999.4	-0.6
93	2001.6	1.6	193	2001.0	1.0	293	1999.6	-0.4
94	2001.4	1.4	194	2001.0	1.0	294	1999.8	-0.2
95	2001.6	1.6	195	2001.0	1.0	295	1999.8	-0.2
96	2001.6	1.6	196	2001.0	1.0	296	1999.9	-0.1
97	2001.6	1.6	197	2001.0	1.0	297	1999.9	-0.1
98	2001.6	1.6	198	2001.2	1.2	298	2000.1	0.1
99	2001.6	1.6	199	2001.2	1.2	299	2000.1	0.1
100	2001.6	1.6	200	2001.2	1.2	300	2000.1	0.1

Range for 2000°F Signal: +2.5/-0.8

Allowable range: ±2.8
Within specification for this temperature?

Yes

Performed by:

Mgr. Fire Resistance Title

2/25/05

Approved by:

Date

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 FAX 210-635-8101 800-966-5253

Certificate of Verification

Certification No.:

92142

Verification Date:

02/25/2005

Reverification Date:

08/25/2005

Manufacturer:

Yokogawa

Model No.:

100 Channel DAU

Serial No.:

99LE004

Equipment Description: 100 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Verification Sources:

TEGAM Model 840-A, SN: T-156701.

Calibration due 07/26/2005

PERFORMANCE:

Temperature: (75°F)	Temperature: (150°F)	Temperature: (300°F)	Temperature: (400°F)	Temperature: (1000°F)	Temperature: (2000°F)
+0.7/-1.1	+0.4/-1.2	+0.7/-1.2	+0.6/-1.2	+0.8/-0.7	+1.6/-0.6

Verification Performed by:

Mike Dey

Manager of Fire Resistance

Verification Approved by:

Javier Trevino

Manager of Special Projects



Serial No.: 99-LE-004

Within specs?

Calibrator Used: SNT156701

Performed by: Mike Dey
Title: Mgr. Dept. 2

Temperature Setting (°F): 75.0

Approved by

2/25/05 Date:

hannel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	75.2	0.2	51	73.9	-1.1
2	74.8	-0.2	52	73.9	-1.1
3	74.8	-0.2	53	73.9	-1.1
4	75.0	0.0	54	73.9	-1.1
5	74.8	-0.2	55	73.9	-1.1
6	75.0	0.0	56	74.1	-0.9
7	75.0	0.0	57	74.1	-0.9
8	75.2	0.2	58	74.3	-0.7
9	75.2	0.2	59	74.3	-0.7
10	75.7	0.7	60	74.5	-0.5
11	74.7	-0.3	61	74.8	-0.2
12	74.5	-0.5	62	74.5	-0.5
13	74.5	-0.5	63	74.5	-0.5
14	74.5	-0.5	64	74.5	-0.5
15	74.5	-0.5	65	74.7	-0.3
16	74.5	-0.5	66	74.8	-0.2
17	74.5	-0.5	67	75.0	0.0
18	74.7	-0.3	68	75.0	0.0
19	74.8	-0.2	69	75.2	0.2
20	75.4	0.4	70	75.6	0.6
21	74.8	-0.2	71	74.5	-0.5
22	74.7	-0.3	72	74.3	-0.7
23	74.7	-0.3	73	74.3	-0.7
24	74.7	-0.3	74	74.5	-0.5
25	74.7	-0.3	75	74.5	-0.5
26	74.8	-0.2	76	74.5	-0.5
27	74.8	-0.2	77	74.7	-0.3
28	75.0	0.0	78	74.7	-0.3
29	75.2	0.2	79	74.8	-0.2
30	75.6	0.6	80	75.2	0.2
31	74.5	-0.5	81	74.5	-0.5
32	74.5	-0.5	82	74.3	-0.7
33	74.5	-0.5	83	74.3	-0.7
34	74.5	-0.5	84	74.5	-0.5
35	74.5	-0.5	85	74.5	-0.5
36	74.5	-0.5	86	74.5	-0.5
37	74.5	-0.5	87	74.7	-0.3
38	74.5	-0.5	88	74.7	-0.3
39	74.8	-0.2	89	74.8	-0.2
40	75.4	0.4	90	75.2	0.2
41	74.7	-0.3	91	74.1	-0.9
42	74.5	-0.5	92	74.1	-0.9
43	74.7	-0.3	93	74.1	-0.9
44	74.7	-0.3	94	74.1	-0.9
45	74.7	-0.3	95	74.1	-0.9
46	74.8	-0.2	96	74.1	-0.9
47	74.8	-0.2	97	74.3	-0.7
275	74.8	-0.2	98	74.3	-0.7
48	75.2		99	74.5	-0.5
49 50	75.6	0.2	100	74.7	-0.3

+0.7/-1.1 Range of 75°F Readings:

Allowable limits

Lower

Upper

73.2

76.8 (±1.8)

Serial No.: 99-LE-004

Calibrator Used: SNT156701

Temperature Setting (°F): __150.0

Within specs? (Yes/No

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:

Date:

hannel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	150.1	0.1	51	149.0	-1.0
2	149.9	-0.1	52	148.8	-1.2
3	149.9	-0.1	53	148.8	-1.2
4	149.9	-0.1	54	149.0	-1.0
5	149.9	-0.1	55	149.0	-1.0
6	149.9	-0.1	56	149.0	-1.0
7	150.1	0.1	57	149.2	-0.8
8	150.3	0.3	58	149.4	-0.6
9	150.3	0.3	59	149.4	-0.6
10	150.4	0.4	60	149.7	-0.3
11	149.5	-0.5	61	149.9	-0.1
12	149.5	-0.5	62	149.5	-0.5
13	149.4	-0.6	63	149.5	-0.5
14	149.4	-0.6	64	149.7	-0.3
15	149.5	-0.5	65	149.7	-0.3
16	149.5	-0.5	66	149.7	-0.3
17	149.5	-0.5	67	149.9	-0.1
18	149.7	-0.3	68	149.9	-0.1
19	149.9	-0.1	69	150.1	0.1
20	150.3	0.3	70	150.4	0.4
21	149.7	-0.3	71	149.4	-0.6
22	149.7	-0.3	72	149.4	-0.6
23	149.7	-0.3	73	149.2	-0.8
24	149.7	-0.3	74	149.4	-0.6
25	149.7	-0.3	75	149.4	-0.6
26	149.7	-0.3	76	149.4	-0.6
27	149.9	-0.1	77	149.5	-0.5
28	149.9	-0.1	78	149.7	-0.3
29	150.1	0.1	79	149.7	-0.3
30	150.4	0.4	80	150.3	0.3
31	149.7	-0.3	81	149.4	-0.6
32	149.5	-0.5	82	149.4	-0.6
33	149.5	-0.5	83	149.4	-0.6
34	149.5	-0.5	84	149.4	-0.6
35	149.5	-0.5	85	149.4	-0.6
36	149.7	-0.3	86	149.5	-0.5
37	149.7	-0.3	87	149.5	-0.5
38	149.7	-0.3	88	149.7	-0.3
39	149.7	-0.3	89	149.7	-0.3
40	150.3	0.3	90	150.3	0.3
41	149.7	-0.3	91	149.2	-0.8
			92	149.0	-1.0
42	149.5 149.5	-0.5 -0.5	93	149.0	-1.0
		-0.3	93	149.2	-0.8
44	149.7	1.0	-	149.4	
45	149.7	-0.3	95	-	-0.6
46	149.7	-0.3	96	149.0 149.4	-1.0
47	149.7	-0.3	97	-	-0.6
48	149.7	-0.3	98	149.4	-0.6
49 50	149.9 150.3	-0.1	99 100	149.5 149.7	-0.5 -0.3

Range of 150°F Readings: +0.4/-1.2

Allowable limits

Lower 148.2 Upper

151.8 (±1.8)

Serial No.: 99-LE-004

Calibrator Used: SNT156701

Temperature Setting (°F): 300.0

Within	specs?	Yes/No
	3146 93	1 /

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	300.2	0.2	51	298.8	-1.2
2	299.8	-0.2	52	298.8	-1.2
3	299.8	-0.2	53	298.8	-1.2
4	299.8	-0.2	54	298.8	-1.2
5	299.7	-0.3	55	298.9	-1.1
6	299.8	-0.2	56	298.9	-1.1
7	300.0	0.0	57	298.9	-1.1
8	300.0	0.0	58	299.1	-0.9
9	300.2	0.2	59	299.3	-0.7
10	300.7	0.7	60	299.5	-0.5
11	299.5	-0.5	61	299.7	-0.3
12	299.3	-0.7	62	299.5	-0.5
13	299.3	-0.7	63	299.5	-0.5
14	299.5	-0.5	64	299.5	-0.5
15	299.3	-0.7	65	299.7	-0.3
16	299.5	-0.5	66	299.7	-0.3
17	299.5	-0.5	67	299.7	-0.3
18	299.5	-0.5	68	300.0	0.0
19	299.8	-0.2	69	300.2	0.2
20	300.2	0.2	70	300.4	0.4
21	300.0	0.0	71	299.3	-0.7
22	299.7	-0.3	72	299.3	-0.7
23	299.7	-0.3	73	299.3	-0.7
24	299.7	-0.3	74	299.1	-0.9
25	299.7	-0.3	75	299.5	-0.5
26	299.7	-0.3	76	299.5	-0.5
27	299.8	-0.2	77	299.5	-0.5
28	300.0	0.0	78	299.7	-0.3
29	300.2	0.2	79	299.8	-0.2
30	300.6	0.6	80	300.2	0.2
31	299.5	-0.5	81	299.3	-0.7
32	299.5	-0.5	82	299.3	-0.7
33	299.5	-0.5	83	299.1	-0.9
34	299.3	-0.7	84	299.3	-0.7
35	299.5	-0.5	85	299.5	-0.5
36	299.5	-0.5	86	299.3	-0.7
37	299.5	-0.5	87	299.5	-0.5
38	299.7	-0.3	88	299.5	-0.5
39	299.7	-0.3	89	299.7	-0.3
40	300.2	0.2	90	300.0	0.0
41	299.5	-0.5	91	298.9	-1.1
42	299.5	-0.5	92	298.9	-1.1
43	299.5	-0.5	93	298.9	-1.1
44	299.5	-0.5	94	298.9	-1.1
	299.5	-0.5	95	299.1	-0.9
45			96	299.1	-0.9
46	299.5	-0.5	96	299.1	-0.9
47	299.5	-0.5			
48	299.7	-0.3	98	299.1 299.3	-0.9
49 50	300.0 300.2	0.0	100	299.3	-0.7

Lower 298.1 Upper

Allowable limits

301.9 (±1.9)

Serial No.: 99-LE-004

Performed by: _ Calibrator Used: SNT156701

Temperature Setting (°F): 400.0

Title:	Mgr. Dept. 2
Approved by: (may of

Date: 2/25/05

Mike Dey

Within specs?

eading (°F)	+/-
399.0	-1.0
398.8	-1.2
398.8	-1.2
399.0	-1.0
399.0	-1.0
399.0	-1.0
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.6	-0.4
399.9	-0.1
399.6	-0.4
399.6	-0.4
399.6	-0.4
399.6	-0.4
399.9	-0.1
400.1	0.1
400.1	0.1
400.1	0.1
400.6	0.6
399.6	-0.4
399.4	-0.6
399.4	-0.6
399.6	-0.4
399.6	-0.4
399.6	-0.4
399.7	-0.3
399.7	-0.3
400.1	0.1
400.3	0.3
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.6	-0.4
399.6	-0.4
399.6	-0.4
399.7	-0.3
400.3	0.3
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.4	-0.6
399.4	-0.6
	-0.6
	-0.4
200000000000000000000000000000000000000	-0.4
	-0.4
	-0.4
	399.4 399.6 399.4 399.6 399.9

Lower

Upper

398.0

Allowable limits

402.0 (±2.0)

Serial No.: 99-LE-004

Calibrator Used: SNT156701 Perfor

Temperature Setting (°F): 1000.0

Within specs? Yes/No

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1000.4	0.4	51	999.5	-0.5
2	1000.2	0.2	52	999.5	-0.5
3	1000.2	0.2	53	999.5	-0.5
4	1000.2	0.2	54	999.5	-0.5
5	1000.2	0.2	55	999.5	-0.5
6	1000.2	0.2	56	999.5	-0.5
7	1000.2	0.2	57	999.5	-0.5
8	1000.4	0.4	58	999.7	-0.3
9	1000.6	0.6	59	999.7	-0.3
10	1000.8	0.8	60	999.9	-0.1
11	999.7	-0.3	61	1000.0	0.0
12	999.7	-0.3	62	999.9	-0.1
13	999.7	-0.3	63	999.9	-0.1
14	999.7	-0.3	64	999.7	-0.3
15	999.7	-0.3	65	1000.0	0.0
16	999.7	-0.3	66	1000.0	0.0
17	999.7	-0.3	67	1000.0	0.0
18	999.9	-0.1	68	1000.2	0.2
19	1000.0	0.0	69	1000.6	0.6
20	1000.6	0.6	70	1000.6	0.6
21	1000.0	0.0	71	999.7	-0.3
22	999.9	-0.1	72	999.7	-0.3
23	999.7	-0.3	73	999.7	-0.3
24	1000.0	0.0	74	999.7	-0.3
25	999.9	-0.1	75	999.9	-0.1
26	999.9	-0.1	76	1000.0	0.0
27	1000.0	0.0	77	1000.0	0.0
28	1000.0	0.0	78	1000.0	0.0
29	1000.0	0.0	79	1000.2	0.2
30	1000.6	0.6	80	1000.6	0.6
31	1000.0	0.0	81	999.7	-0.3
32	999.7	-0.3	82	999.5	-0.5
33	999.7	-0.3	83	999.5	-0.5
34	999.9	-0.1	84	999.7	-0.3
35	999.7	-0.3	85	999.7	-0.3
36	999.7	-0.3	86	999.7	-0.3
37	999.9	-0.1	87	999.9	-0.1
38	999.9	-0.1	88	999.9	-0.1
39	999.9	-0.1	89	999.9	-0.1
40	1000.6	0.6	90	1000.2	0.2
41	999.7	-0.3	91	999.5	-0.5
42	999.7	-0.3	92	999.3	-0.7
43	999.7	-0.3	93	999.3	-0.7
44	999.7	-0.3	94	999.5	-0.5
45	999.9	-0.1	95	999.5	-0.5
46	999.9	-0.1	96	999.5	-0.5
47	999.9	-0.1	97	999.7	-0.3
48	1000.0	0.0	98	999.5	-0.5
49	1000.0	0.0	99	999.9	-0.1
50	1000.2	0.2	100	1000.0	0.0

Upper

limite

1002.3 (±2.3)

Lower

997.7

Range of 2000°F Readings: +0.8/-0.7

Allowable limits

Serial No.: 99-LE-004

Calibrator Used: SNT156701

Temperature Setting (°F): 2000.0

Within specs?

Performed by: ___

Mike Dey

Title: Mgr. Dept. 2

Approved by: 7

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	2001.0	1.0	51	1999.8	-0.2
2	2000.7	0.7	52	1999.4	-0.6
3	2000.7	0.7	53	1999.4	-0.6
4	2000.7	0.7	54	1999.6	-0.4
5	2000.7	0.7	55	1999.6	-0.4
6	2000.7	0.7	56	1999.8	-0.2
7	2000.8	0.8	57	1999.8	-0.2
8	2000.8	0.8	58	1999.9	-0.1
9	2001.0	1.0	59	1999.9	-0.1
10	2001.6	1.6	60	2000.3	0.3
11	2000.3	0.3	61	2000.3	0.3
12	2000.1	0.1	62	1999.9	-0.1
13	2000.1	0.1	63	2000.1	0.1
14	2000.1	0.1	64	2000.1	0.1
15	2000.1	0.1	65	2000.1	0.1
16	2000.3	0.3	66	2000.3	0.3
17	2000.5	0.5	67	2000.7	0.7
18	2000.5	0.5	68	2000.7	0.7
19	2000.5	0.5	69	2000.7	0.7
20	2001.0	1.0	70	2001.0	1.0
21	2000.7	0.7	71	2000.7	0.7
22	2000.5	0.5	72	2000.3	0.3
23	2000.3	0.3	73	2000.3	0.3
24	2000.3	0.3	74	2000.5	0.5
25	2000.5	0.5	75	2000.5	0.5
26	2000.5	0.5	76	2000.7	0.7
27	2000.7	0.7	77	2000.7	0.7
28	2000.7	0.7	78	2000.7	0.7
29	2000.8	0.8	79	2000.8	0.8
30	2001.2	1.2	80	2001.2	1.2
31	2000.1	0.1	81	1999.4	-0.6
32	2000.1	0.1	82	1999.4	-0.6
33	2000.1	0.1	83	1999.4	-0.6
34	1999.9	-0.1	84	1999.4	-0.6
35	2000.1	0.1	85	1999.4	-0.6
36	2000.1	0.1	86	1999.6	-0.4
37	2000.1	0.1	87	1999.6	-0.4
38	2000.3	0.3	88	1999.8	-0.2
39	2000.5	0.5	89	1999.9	-0.1
40	2000.8	0.8	90	2000.1	0.1
41	1999.9	-0.1	91	1999.8	-0.2
42	1999.6	-0.4	92	1999.6	-0.4
43	1999.8	-0.2	93	1999.6	-0.4
44	1999.9	-0.1	94	1999.8	-0.2
45	1999.9	-0.1	95	1999.8	-0.2
46	1999.9	-0.1	96	1999.8	-0.2
47	1999.9	-0.1	97	1999.9	-0.1
48	1999.9	-0.1	98	1999.9	-0.1
49	2000.3	0.3	99	1999.9	-0.1
50	2000.7	0.7	100	2000.3	0.3

Lower

Upper

Range of 2000°F Readings: +1.6/-0.6 Allowable limits

1997.2

2002.8 (±2.8)

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 FAX 210-635-8101 800-966-5253

Certificate of Verification

Certification No.:

92141

Verification Date:

02/25/2005

Reverification Date:

08/25/2005

Manufacturer:

Yokogawa

Model No.:

100 Channel DAU

Serial No.:

99LE006

Equipment Description: 100 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Calibration Sources:

TEGAM Model 840-A, SN: T-156701.

Calibration due 07/26/2005.

DEDECRMANCE.

LILL OIL	THE OTHER TOPS					
Temperature: (75°F) +1.1/-0.5	Temperature: (150°F) +1.2/-0.5	Temperature: (300°F) +0.9/-0.7	Temperature: (400°F) +1.2/-0.6	Temperature: (1000°F) +1.3/-0.5	Temperature: (2000°F) +1.7/-1.1	

Verification Performed by:

Manager of Fire Resistance

Verification Approved by:

Javier Trevino

Manager of Special Projects



Serial No.: 99-LE-006

Performed by: ___Mike Dey

Title: Mgr, Dept. 2

Temperature Setting (°F): 75.0

Calibrator Used: SNT156701

Approved by: Title: Mgr 04

Within specs?

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	75.6	0.6	51	74.7	-0.3
2	75.6	0.6	52	74.7	-0.3
3	75.6	0.6	53	74.8	-0.2
4	75.2	0.2	54	74.5	-0.5
5	75.0	0.0	55	74.5	-0.5
6	75.0	0.0	56	74.5	-0.5
7	75.2	0.2	57	74.5	-0.5
8	75.0	0.0	58	74.5	-0.5
9	75.0	0.0	59	74.5	-0.5
10	75.2	0.2	60	74.5	-0.5
11	75.4	0.4	61	75.2	0.2
12	75.6	0.6	62	75.2	0.2
13	75.6	0.6	63	75.2	0.2
14	75.2	0.2	64	75.0	0.0
15	75.2	0.2	65	75.0	0.0
16	75.0	0.0	66	75.0	0.0
17	75.0	0.0	67	74.8	-0.2
18	75.0	0.0	68	74.8	-0.2
19	74.8	-0.2	69	75.0	0.0
20	75.0	0.0	70	75.0	0.0
21	75.2	0.2	71	75.4	0.4
22	75.4	0.4	72	75.6	0.6
23	75.4	0.4	73	75.6	0.6
24	75.2	0.2	74	75.2	0.2
25	75.0	0.0	75	75.2	0.2
26	75.0	0.0	76	75.2	0.2
27	75.0	0.0	77	75.2	0.2
28	74.8	-0.2	78	75.2	0.2
29	75.2	0.2	79	75.2	0.2
30	75.2	0.2	80	75.2	0.2
31	75.0	0.0	81	75.4	0.4
32	75.0	0.0	82	75.2	0.2
33	75.0	0.0	83	75.2	0.2
34	74.8	-0.2	84	75.0	0.0
35	75.0	0.0	85	75.0	0.0
36	75.0	0.0	86	74.8	-0.2
37	75.0	0.0	87	74.8	-0.2
38	74.8	-0.2	88	74.8	-0.2
39	75.2	0.2	89	75.0	0.0
40	75.2	0.2	90	75.2	0.2
41	75.2	0.2	91	74.5	-0.5
42	75.4	0.4	92	74.8	-0.2
43	75.7	0.7	93	74.8	-0.2
44	75.2	0.2	94	74.5	-0.5
45	75.2	0.2	95	74.7	-0.3
46	75.2	0.2	96	76.1	1.1
47	75.2	0.2	97	74.7	-0.3
48	75.0	0.0	98	74.8	-0.2
49	75.0	0.0	99	74.8	-0.2
50	75.2	0.2	100	74.8	-0.2

Lower

Upper

Range of 75°F Readings:

+1.1/-0.5

Allowable limits

73.2

76.8 (±1.8)

Serial No.: 99-LE-006

Calibrator Used: SNT156701

Temperature Setting (°F): 150.0

		10
Within	specs?	(Yes/No

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:
Title: MgC 04

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	150.4	0.4	51	149.7	-0.3
2	150.4	0.4	52	149.7	-0.3
3	150.4	0.4	53	149.7	-0.3
4	150.1	0.1	54	149.5	-0.5
5	150.1	0.1	55	149.5	-0.5
6	149.9	-0.1	56	149.5	-0.5
7	149.9	-0.1	57	149.5	-0.5
8	149.9	-0.1	58	149.5	-0.5
9	149.9	-0.1	59	149.5	-0.5
10	149.9	-0.1	60	149.5	-0.5
11	150.4	0.4	61	149.9	-0.1
12	150.4	0.4	62	149.9	-0.1
13	150.4	0.4	63	149.7	-0.3
14	150.3	0.3	64	149.7	-0.3
15	150.1	0.1	65	149.7	-0.3
16	150.1	0.1	66	149.5	-0.5
17	150.1	0.1	67	149.5	-0.5
18	149.9	-0.1	68	149.7	-0.3
19	149.9	-0.1	69	149.5	-0.5
20	150.1	0.1	70	149.5	-0.5
21	150.1	0.1	71	150.3	0.3
22	150.3	0.3	72	150.3	0.3
23	150.1	0.1	73	150.3	0.3
24	149.7	-0.3	74	150.1	0.1
25	149.7	-0.3	75	150.1	0.1
26	149.7	-0.3	76	149.9	-0.1
27	149.7	-0.3	77	150.1	0.1
28	149.7	-0.3	78	150.1	0.1
29	149.7	-0.3	79	149.9	-0.1
30	149.9	-0.1	80	150.1	0.1
31	150.3	0.3	81	149.9	-0.1
32	150.3	0.3	82	149.9	-0.1
33	150.3	0.3	83	149.7	-0.3
34	150.1	0.1	84	149.7	-0.3
35	149.9	-0.1	85	149.7	-0.3
36	149.9	-0.1	86	149.5	-0.5
37	149.9	-0.1	87	149.5	-0.5
38	149.9	-0.1	88	149.5	-0.5
39	149.7	-0.3	89	149.7	-0.3
40	150.1	0.1	90	149.9	-0.1
41	150.3	0.3	91	149.7	-0.3
42	150.4	0.4	92	149.7	-0.3
43	150.3	0.3	93	149.7	-0.3
44	150.3	0.3	94	149.5	-0.5
45	150.1	0.1	95	149.5	-0.5
46	150.1	0.1	96	151.2	1.2
47	149.9	-0.1	97	149.7	-0.3
48	150.1	0.1	98	149.7	-0.3
49	149.9	-0.1	99	149.7	-0.3
50	149.9	-0.1	100	149.9	-0.1

Lower Upper 148.2 151.8 (±1.8)

Allowable limits

Serial No.: 99-LE-006

Calibrator Used: SNT156701

Temperature Setting (°F): 300.0

Within specs?

Performed by: __Mike Dey

Title: Mgr. Dept. 2

Approved by:

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	300.2	0.2	51	299.5	-0.5
2	300.2	0.2	52	299.5	-0.5
3	300.2	0.2	53	299.7	-0.3
4	299.8	-0.2	54	299.5	-0.5
5	299.8	-0.2	55	299.3	-0.7
6	299.7	-0.3	56	299.5	-0.5
7	299.7	-0.3	57	299.5	-0.5
8	299.7	-0.3	58	299.5	-0.5
9	299.7	-0.3	59	299.5	-0.5
10	299.8	-0.2	60	299.5	-0.5
11	300.2	0.2	61	299.8	-0.2
12	300.2	0.2	62	299.8	-0.2
13	300.4	0.4	63	299.8	-0.2
14	300.2	0.2	64	299.5	-0.5
15	300.2	0.2	65	299.5	-0.5
16	300.0	0.0	66	299.5	-0.5
17	300.0	0.0	67	299.5	-0.5
18	299.8	-0.2	68	299.5	-0.5
19	300.0	0.0	69	299.5	-0.5
20	300.0	0.0	70	299.7	-0.3
21	300.2	0.2	71	300.2	0.2
22	300.2	0.2	72	300.2	0.2
23	300.2	0.2	73	300.2	0.2
24	300.0	0.0	74	299.8	-0.2
25	299.8	-0.2	75	299.8	-0.2
26	299.8	-0.2	76	299.8	-0.2
27	299.8	-0.2	77	299.7	-0.3
28	299.8	-0.2	78	299.8	-0.2
29	300.0	0.0	79	299.7	-0.3
30	300.0	0.0	80	299.8	-0.2
31	300.2	0.2	81	299.5	-0.5
32	300.4	0.4	82	299.5	-0.5
33	300.4	0.4	83	299.5	-0.5
34	300.2	0.2	84	299.5	-0.5
35	300.0	0.0	85	299.5	-0.5
36	300.0	0.0	86	299.5	-0.5
37	299.8	-0.2	87	299.5	-0.5
38	299.8	-0.2	88	299.5	-0.5
39	300.0	0.0	89	299.5	-0.5
40	300.0	0.0	90	299.5	-0.5
41	300.0	0.0	91	299.5	-0.5
42	300.4	0.4	92	299.7	-0.3
43	300.4	0.4	93	299.5	-0.5
44	300.0	0.0	94	299.5	-0.5
45	300.0	0.0	95	299.5	-0.5
46	299.8	-0.2	96	300.9	0.9
47	299.8	-0.2	97	299.5	-0.5
48	299.8	-0.2	98	299.7	-0.3
49	299.8	-0.2	99	299.7	-0.3
50	299.8	-0.2	100	299.7	-0.3

Range of 300°F Readings: +0.9/-0.7

Allowable limits

Lower 298.1 Upper

.1 301.9 (±1.9)

Serial No.: 99-LE-006

Performed by: Calibrator Used: SNT156701

Temperature Setting (°F): 400.0

Approved	by:	4	-)	
	Title:	n	5r 0	F	

Date: 2/25/05

Title: Mgr. Dept. 2

Mike Dey

Within specs?

Reading (°F) Channel No. Reading (°F) Channel No. 399.6 -0.4 400.3 52 399.6 -0.4 400.3 0.3 2 3 400.3 0.3 53 399.6 -0.4 4 399.9 -0.1 54 399.6 -0.4399.4 -0.6 55 399.7 -0.3 5 399.6 -0.4 56 399.6 6 -0.4399.7 -0.3 57 399.6 399.6 -0.4 58 8 399.6 -0.49 399.6 -0.459 399.6 60 399.6 -0.410 399.7 -0.311 400.5 0.5 61 399.9 -0.1 399.9 -0.112 400.3 0.3 62 63 399.9 -0.1400.5 0.5 13 400.3 399.6 14 0.3 -0.4 399.6 15 399.9 65 -0.1 399.6 -0.4 66 399.9 16 399.6 -0.4 17 399.9 -0.1 67 399.9 -0.1 68 399.6 -0.418 -0.4399.6 19 399.7 -0.369 399.6 -0.4 400.1 70 20 0.1 399.9 400.3 0.3 71 21 400.3 72 400.3 0.3 22 0.3 73 400.3 400.3 -0.3 74 399.7 24 400.1 25 399.9 -0.1 75 399.7 -0.3 399.7 76 399.7 -0.326 399.6 -0.477 27 399.9 -0.1399.7 -0.378 399.6 -0.428 399.6 399.9 -0.129 399.6 -0.4 399.9 80 30 399.6 -0.4 81 31 400.3 0.5 82 399.9 -0.1 32 400.5 33 400.3 0.3 83 399.7 -0.3399.6 -0.434 400.3 0.3 84 399.6 -0.4 85 399.9 35 -0.1399.6 -0.4 399.9 -0.186 36 399.9 87 399.6 -0.437 -0.4 399.9 88 399.6 -0.3 399.7 39 399.9 89 90 399.9 -0.1400.3 0.3 40 400.1 0.1 91 399.6 -0.441 92 399.7 -0.342 400.5 0.5 93 399.7 -0.3400.5 0.5 43 399.9 0.1 94 399.6 -0.4 44 -0.4 399.9 95 399.6 45 96 401.2 1.2 399.9 47 399.7 -0.3 97 399.9 -0.198 399.9 -0.148 399.7 -0.349 399.9 -0.199 399.9 -0.1399.9 100 -0.150 399.7 -0.3

Lower

Upper

398.0

402.0 (±2.0)

Range of 400°F Readings: +1.2/-0.6

Allowable limits

Serial No.: 99-LE-006

Within specs? Yes/N

Calibrator Used: SNT156701

Performed by: Mike Dey
Title: Mgr. Dept. 2

Temperature Setting (°F): 1000.0

Approved by:

Date:	2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	999.9	-0.1	51	999.5	-0.5
2	1000.0	0.0	52	999.7	-0.3
3	1000.0	0.0	53	999.7	-0.3
4	999.7	-0.3	54	999.5	-0.5
5	999.7	-0.3	55	999.5	-0.5
6	999.5	-0.5	56	999.5	-0.5
7	999.5	-0.5	57	999.5	-0.5
8	999.7	-0.3	58	999.7	-0.3
9	999.5	-0.5	59	999.5	-0.5
10	999.5	-0,5	60	999.5	-0.5
11	1000.2	0.2	61	999.9	-0.1
12	1000.2	0.2	62	1000.0	0.0
13	1000.2	0.2	63	1000.0	0.0
14	1000.0	0.0	64	999.7	-0.3
15	1000.0	0.0	65	999.7	-0.3
16	1000.0	0.0	66	999.9	-0.1
17	999.9	-0.1	67	999.7	-0.3
18	999.7	-0.3	68	999.7	-0.3
19	999.9	-0.1	69	999.7	-0.3
20	1000.0	0.0	70	999.7	-0.3
21	1000.6	0.6	71	999.9	-0.1
22	1000.8	0.8	72	999.9	-0.1
23	1000.6	0.6	73	1000.0	0.0
24	1000.4	0.4	74	999.7	-0.3
25	1000.6	0.6	75	999.5	-0.5
26	1000.6	0.6	76	999.7	-0.3
27	1000.4	0.4	77	999.7	-0.3
28	1000.4	0.4	78	999.5	-0.5
29	1000.6	0.6	79	999.5	-0.5
30	1000.6	0.6	80	999.7	-0.3
31	1000.0	0.0	81	999.7	-0.3
32	1000.2	0.2	82	999.7	-0.3
33	1000.4	0.4	83	999.7	-0.3
34	1000.0	0.0	84	999.7	-0.3
35	999.9	-0.1	85	999.5	-0.5
36	1000.0	0.0	86	999.5	-0.5
37	999.9	-0.1	87	999.5	-0.5
38	999.9	-0.1	88	999.5	-0.5
39	1000.0	0.0	89	999.5	-0.5
40	1000.0	0.0	90	999.7	-0.3
41	1000.2	0.2	91	999.9	-0.1
42	1000.4	0.4	92	1000.0	0.0
43	1000.6	0.6	93	999.9	-0.1
44	1000.2	0.2	94	999.9	-0.1
45	1000.0	0.0	95	1000.0	0.0
46	1000.0	0.0	96	1001.3	1.3
47	1000.0	0.0	97	1000.0	0.0
48	1000.0	0.0	98	1000.0	0.0
49	1000.0	0.0	99	1000.0	0.0
50	1000.0	0.0	100	1000.0	0.0

Lower

Upper

Range of 2000°F Readings: +1.3/-0.5

Allowable limits

997.7

1002.3 (±2.3)

Serial No.: 99-LE-006

Calibrator Used: SNT156701

Temperature Setting (°F): 2000.0

Within specs?

Performed by: _

Mike Dey

Title: Mgr. Dept. 2

Approved by:

Date: 2/25/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1999.4	-0.6	51	1999.8	-0.2
2	1999.4	-0.6	52	1999.9	-0.1
3	1999.4	-0.6	53	1999.9	-0.1
4	1999.0	-1.0	54	1999.6	-0.4
5	1998.9	-1.1	55	1999.8	-0.2
6	1999.0	-1.0	56	1999.9	-0.1
7	1999.0	-1.0	57	1999.8	-0.2
8	1998.9	-1.1	58	1999.8	-0.2
9	1998.9	-1.1	59	1999.8	-0.2
10	1999.2	-0.8	60	1999.8	-0.2
11	2000.1	0.1	61	2000.1	0.1
12	2000.3	0.3	62	2000.1	0.1
13	2000.3	0.3	63	2000.1	0.1
14	1999.9	-0.1	64	1999.9	-0.1
15	1999.9	-0.1	65	1999.9	-0.1
16	1999.9	-0.1	66	1999.9	-0.1
17	1999.9	-0.1	67	1999.9	-0.1
18	1999.9	-0.1	68	1999.9	-0.1
19	1999.8	-0.2	69	1999.9	-0.1
20	1999.9	-0.1	70	1999.9	-0.1
21	2001.2	1.2	71	1999.2	-0.8
22	2001.4	1.4	72	1999.6	-0.4
23	2001.4	1.4	73	1999.4	-0.6
24	2001.2	1.2	74	1999.2	-0.8
25	2001.0	1.0	75	1999.2	-0.8
26	2001.0	1.0	76	1999.0	-1.0
27	2001.0	1.0	77	1999.2	-0.8
28	2001.0	1.0	78	1999.2	-0.8
29	2001.0	1.0	79	1999.0	-1.0
30	2001.2	1.2	80	1999.0	-1.0
31	1999.9	-0.1	81	1999.4	-0.6
32	2000.1	0.1	82	1999.4	-0.6
33	2000.1	0.1	83	1999.4	-0.6
34	1999.9	-0.1	84	1999.2	-0.8
35	1999.9	-0.1	85	1999.2	-0.8
36	1999.8	-0.2	86	1999.2	-0.8
37	1999.8	-0.2	87	1999.2	-0.8
38	1999.9	-0.1	88	1999.2	-0.8
39	1999.9	-0.1	89	1999.2	-0.8
40	1999.9	-0.1	90	1999.4	-0.6
41	1999.9	-0.1	91	2000.1	0.1
42	2000.1	0.1	92	2000.5	0.5
43	2000.1	0.5	93	2000.5	0.5
44	1999.9	-0.1	94	2000.1	0.1
45	1999.8	-0.1	95	2000.1	0.3
45	1999.9	-0.1	96	2000.3	1.7
10000	1999.8	-0.1	97	2000.5	0.5
47		-0.2	98	2000.3	0.7
48	1999.8	200	99	2000.7	0.7
49 50	1999.9 1999.8	-0.1	100	2000.7	0.7

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 FAX 210-635-8101 800-966-5253

Certificate of Verification

Certification No.:

92147

Verification Date:

03/11/2005

Re-verification Date:

09/11/2005

Manufacturer:

Yokogawa

Model No.:

300 Channel DAU-

Serial No.:

48JF0082

Equipment Description:

300 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Calibration Sources:

Tegam T-207318 due: 05/03/2005

PERFORMANCE:

Temperature: (75°F)	Temperature: (150°F)	Temperature: (300°F)	Temperature: (400°F)	Temperature: (1000°F)	Temperature: (2000°F)
1.3/-0.3	1.2/-0.3	1.3/-0.5	+1.2/-0.4	1.3/-0.1	1.7/-0.8

Measurement Uncertainty: ±0.2%

Verification Performed by:

Verification Approved by:

Mike Dey

Manager Fire Resistance

Deg Priest

President/Chief Technical Officer



Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): ____75.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	75.4	0.4	101	75.2	0.2	201	74.8	-0.2
2	75.2	0.2	102	75.2	0.2	202	75.2	-0.2
3	75.2	0.2	103	75.2	0.2	203	75.4	0.2
4	75.2	0.2	104	75.0	0.0	204	75.4	0.4
5	75.2	0.2	105	75.0	0.0	205	75.2	0.4
6	75.2	0.2	106	75.0	0.0	206	75.4	0.2
7	75.2	0.2	107	75.4	0.4	207	75.4	0.4
8	75.4	0.4	108	75.0	0.0	208	75.4	0.4
9	75.4	0.4	109	75.4	0.4	209	75.4	0.4
10	75.7	0.7	110	75.7	0.7	210	75.2	0.4
11	75.2	0.2	111	75.2	0.2	211	75.4	0.2
12	75.2	0.2	112	75.4	0.4	212	75.4	0.4
13	75.2	0.2	113	75.7	0.7	213	75.2	0.4
14	75.2	0.2	114	75.7	0.7	214	75.2	0.2
15	75.2	0.2	115	75.7	0.7	215	75.2	0.2
16	75.2	0.2	116	75.7	0.7	216	75.2	0.2
17	75.2	0.2	117	75.7	0.7	217	75.4	0.2
18	75.2	0.2	118	75.7	0.7	218	75.2	0.4
19	75.4	0.4	119	75.7	0.7	219	75.4	0.2
20	75.7	0.7	120	75.9	0.9	220	75.6	0.4
21	75.2	0.2	121	75.6	0.6	221	74.7	0.6
22	75.2	0.2	122	75.6	0.6	222	74.8	-0.3
23	75.2	0.2	123	75.4	0.4	223	74.8	-0.2
24	75.2	0.2	124	75.6	0.6	224	74.8	-0.2
25	75.4	0.4	125	75.7	0.7	225	75.0	-0.2
26	75.4	0.4	126	75.6	0.6	226	75.2	
27	75.6	0.6	127	75.7	0.7	227	75.2	0.0
28	75.6	0.6	128	75.7	1975-7-30	228	75.2	7.22 16.1
29	75.7	0.7	129	75.9	0.7	229	75.4	0.2
30	75.9		130	76.3				
977 8 11	1	0.9			1.3	230	75.7	0.4
31	75.6	0.6	131	75.2	0.2	231	75.2	0.7
32	75.6	0.6	132	75.2	0.2	232	75.2	0.2
33	75.6	0.6	133	75.2	0.2	233	75.2	0.2
34	75.6	0.6	134	75.2	0.2	234	75.4	0.2
35	75.4	0.4	135	75.4	0.4	235	75.4	0.4
36	75.6	0.6	136	75.2	0.2	236	75.4	0.4
37	75.7	0.7	137	75.2	0.2	237	75.4	0.4
38	75.7	0.7	138	75.4	0.4	238	75.6	0.4
39	75.7	0.7	139	75.6	0.6	239	75.7	0.6
40	75.9	0.9	140	75.7	0.7	240	75.7	0.7
41	75.0	0.0	141	75.2	0.2	241	75.6	0.7
42	75.0	0.0	142	75.0	0.0	242	75.6	0.6
43	75.2	0.2	143	75.2	0.2	243	75.4	0.6
44	75.2	0.2	144	75.2	0.2	244	75.6	0.4
45	75.2	0.2	145	75.2	0.2	245	75.6	0.6
46	75.2	0.2	146	75.2	0.2	246	75.6	0.6
47	75.4	0.4	147	75.4	0.4	247	75.7	0.6
48	75.6	0.6	148	75.6	0.6	248	75.9	0.7
49	75.2	0.2	149	75.6	0.6	249	75.7	0.9
50	75.7	0.7	150	75.7	0.7	250	76.1	0.7
51	74.8	-0.2	151	75.6	0.6	251	75.0	1.1
52	75.2	0.2	152	75.6	0.6	252	75.0	0.0
53	75.2	0.2	153	75.6	0.6	253	75.0	0.0
54	75.2	0.2	154	75.7	0.7	254	75.2	0.0

Page 411

55	75.2	0.2	155	75.7	0.7	255	75.2	0.2
56	75.2	0.2	156	75.7	0.7	256	75.2	0.2
57	75.2	0.2	157	75.7	0.7	257	75.2	0.2
58	75.4	0.4	158	75.7	0.7	258	75.4	0.2
59	75.6	0.6	159	76.1	1.1	259	75.6	0.4
60	75.7	0.7	160	76.3	1.3	260	75.9	0.6
61	75.6	0.6	161	75.6	0.6	261	75.4	0.9
62	75.4	0.4	162	75.7	0.7	262	75.4	0.4
63	75.4	0.4	163	75.6	0.6	263	75.4	0.4
64	75.4	0.4	164	75.7	0.7	264	75.4	0.4
65	75.6	0.6	165	75.7	0.7	265	75.4	0.4
66	75.6	0.6	166	75.7	0.7	266	75.4	0.4
67	75.6	0.6	167	75.9	0.9	267	75.6	0.4
68	75.7	0.7	168	75.9	0.9	268	75.7	0.6
69	75.7	0.7	169	76.1	1.1	269	75.7	0.7
70	75.9	0.9	170	76.3	1.3	270	75.7	0.7
71	75.2	0.2	171	75.2	0.2	271	75.4	0.7
72	75.2	0.2	172	75.2	0.2	272	75.2	0.4
73	75.2	0.2	173	75.4	0.4	273	75.4	0.2
74	75.2	0.2	174	75.4	0.4	274	75.4	0.4
7.5	75.6	0.6	175	75.2	0.4	275	75.6	0.4
			176		0.4	276	75.6	0.6
76 77	75.6 75.6	0.6	176	75.4 75.4	0.4	277	75.7	0.6
		0.6						
78	75.6	0.6	178	75.6	0.6	278	75.7	0.7
79	75.7	0.7	179	75.7	0.7	279	75.7	0.7
80	75.9	0.9	180	75.9	0.9	280	75.9	0.7
81	75.4	0.4	181	75.4	0.4	281	74.7	0.9
82	75.4	0.4	182	75.4	0.4	282	74.8	-0.3
83	75.6	0.6	183	75.4	0.4	283	75.0	-0.2
84	75.6	0.6	184	75.6	0.6	284	74.8	0.0
85	75.6	0.6	185	75.6	0.6	285	75.2	-0.2
86	75.6	0.6	186	75.6	0.6	286	75.2	0.2
87	75.6	0.6	187	75.7	0.7	287	75.2	0.2
88	75.7	0.7	188	75.7	0.7	288	75.2	0.2
89	75.7	0.7	189	75.7	0.7	289	75.4	0.2
90	75.9	0.9	190	76.1	1.1	290	75.7	0.4
91	75.4	0.4	191	75.0	0.0	291	74.8	0.7
92	75.4	0.4	192	75.0	0.0	292	75.0	-0.2
93	75.2	0.2	193	75.0	0.0	293	75.2	0.0
94	75.2	0.2	194	75.2	0.2	294	75.2	0.2
95	75.4	0.4	195	75.4	0.4	295	75.2	0.2
96	75.4	0.4	196	75.4	0.4	296	75.2	0.2
97	75.4	0.4	197	75.2	0.2	297	75.2	0.2
98	75.7	0.7	198	75.4	0.4	298	75.6	0.2
99	75.7	0.7	199	75.4	0.4	299	75.2	0.6
100	75.9	0.9	200	75.7	0.7	300	75.7	0.2

Range for 75°F Signal: +1.3/-0.3 Allowable range: ± 1.8

Within specification for this temp	perature? Yes	
Performed by:	MD	
	Mgr. Fire Resistance	3/11/05
	Title	Date
Approved by:	0 . 1 +	3/. /
Algrand	Tresident	/11/05

Title

Date

Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): __150.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	150.3	0.3	101	150.1	0.1	201	150.1	0.1
2	150.3	0.3	102	150.3	0.3	202	150.1	0.1
3	150.1	0.1	103	150.3	0.3	203	150.1	0.1
4	150.1	0.1	104	150.3	0.3	204	150.1	0.1
5	150.3	0.3	105	150.3	0.3	205	150.1	0.1
6	150.3	0.3	106	150.4	0.4	206	150.3	0.3
7	150.3	0.3	107	150.6	0.6	207	150.3	0.3
8	150.3	0.3	108	150.6	0.6	208	150.3	0.3
9	150.4	0.4	109	150.8	0.8	209	150.3	0.3
10	150.8	0.8	110	151.0	1.0	210	150.8	0.8
11	150.3	0.3	111	150.3	0.3	211	149.9	-0.1
12	150.3	0.3	112	150.3	0.3	212	149.9	-0.1
13	150.1	0.1	113	150.3	0.3	213	149.9	-0.1
14	150.3	0.3	114	150.3	0.3	214	149.9	-0.1
15	150.1	0.1	115	150.3	0.3	215	149.9	-0.1
16	150.3	0.3	116	150.4	0.4	216	150.3	0.3
17	150.3	0.3	117	150.4	0.4	217	150.3	0.3
18	150.3	0.3	118	150.6	0.6	218	150.3	0.3
19	150.3	0.3	119	150.8	0.8	219	150.4	0.4
20	150.6	0.6	120	151.0	1.0	220	150.8	0.8
21	150.3	0.3	121	150.6	0.6	221	149.7	-0.3
22	150.1	0.1	122	150.4	0.4	222	149.9	-0.1
23	150.1	0.1	123	150.4	0.4	223	149.9	-0.1
24	150.3	0.3	124	150.4	0.4	224	149.9	-0.1
25	150.3	0.3	125	150.4	0.4	225	150.1	0.1
26	150.4	0.4	126	150.4	0.4	226	150.1	0.1
27	150.4	0.4	127	150.6	0.6	227	150.1	0.1
28	150.4	0.4	128	150.6	0.6	228	150.3	0.3
29	150.6	0.6	129	150.6	0.6	229	150.3	0.3
30	150.8	0.8	130	150.8	0.8	230	150.8	0.8
31	150.4	0.4	131	149.9	-0.1	231	150.1	0.0
32	150.4	0.4	132 133	149.9 149.9	-0.1	232	150.1 150.3	0.1
	150.4	0.4	134	-	-0.1	234		
34	150.4	0.4		150.1	0.1		150.3	0.3
35	150.4	0.4	135	150.1	0.1	235	150.3	0.3
36	150.6	0.6	136	150.1	0.1	236	150.3	0.3
37	150.6	0.6	137	150.3	0.3	237	150.3	0.3
38	150.8	8.0	138	150.3	0.3	238	150.3	0.3
39	150.8	0.8	139	150.3	0.3	239	150.6	0.6
40	151.2	1.2	140	150.6	0.6	240	150.8	0.8
41	150.3	0.3	141	149.9	-0.1	241	150.6	0.6
42	150.3	0.3	142	150.1	0.1	242	150.4	0.4
43	150.1	0.1	143	150.1	0.1	243	150.6	0.6
44	150.3	0.3	144	150.1	0.1	244	150.4	0.4
45	150.3	0.3	145	150.3	0.3	245	150.8	0.8
46	150.3	0.3	146	150.3	0.3	246	150.8	0.8
47	150.3	0.3	147	150.3	0.3	247	150.8	0.8
48	150.4	0.4	148	150.4	0.4	248	150.8	0.8
49	150.4	0.4	149	150.4	0.4	249	150.8	0.8
50	150.6	0.6	150	150.6	0.6	250	151.2	1.2
51	149.9	-0.1	151	150.4	0.4	251	150.4	0.4
52	149.9	-0.1	152	150.4	0.4	252	150.8	0.8
53	150.1	0.1	153	150.4	0.4	253	149.7	-0.3
54	150.1	0.1	154	150.3	0.3	254	149.9	-0.1

Page 413

55	150.3	0.3	155	150.4	0.4	255	149.9	-0.1
56	150.3	0.3	156	150.4	0.4	256	149.9	-0.1
57	150.3	0.3	157	150.4	0.4	257	150.1	0.1
58	150.4	0.4	158	150.6	0.6	258	150.1	0.1
59	150.6	0.6	159	150.8	0.8	259	150.1	0.1
60	150.8	0.8	160	151.0	1.0	260	150.3	0.3
61	150.4	0.4	161	150.3	0.3	261	150.3	0.3
62	150.3	0.3	162	150.3	0.3	262	150.8	0.8
63	150.3	0.3	163	150.3	0.3	263	150.8	0.8
64	150.3	0.3	164	150.3	0.3	264	149.9	-0.1
65	150.3	0.3	165	150.4	0.4	265	150.1	0.1
66	150.4	0.4	166	150.4	0.4	266	150.1	0.1
67	150.4	0.4	167	150.6	0.6	267	150.1	0.1
68	150.6	0.6	168	150.6	0.6	268	150.3	0.3
69	150.8	0.8	169	150.8	0.8	269	150.3	0.3
70	151.0	1.0	170	151.0	1.0	270	150.8	0.8
71	150.3	0.3	171	149.9	-0.1	271	150.8	0.8
72	150.3	0.3	172	149.9	-0.1	272	150.1	0.1
73	150.3	0.3	173	150.1	0.1	273	150.1	0.1
74	150.3	0.3	174	150.1	0.1	274	150.1	0.1
75	150.3	0.3	175	150.3	0.3	275	150.4	0.4
76	150.4	0.4	176	150.3	0.3	276	150.4	0.4
77	150.4	0.4	177	150.3	0.3	277	150.4	0.4
78	150.4	0.4	178	150.4	0.4	278	150.4	0.4
79	150.4	0.6	179	150.6	0.6	279	150.8	0.8
80	150.8	0.8	180	150.8	0.8	280	151.0	1.0
81		0.3	181	150.8	0.8	281	149.7	-0.3
82	150.3 150.1	0.3	182	150.3	0.3	282	149.7	-0.3
		0.3		150.3	0.3	283	149.7	-0.1
83	150.3		183	ALL ALL STATE OF THE PARTY OF T	0.3			
84	150.3	0.3	184	150.3		284	149.9	-0.1
85	150.3	0.3	185	150.3	0.3	285	150.1	200
86	150.3	0.3	186	150.4	0.4	286	150.1	0.1
87	150.3	0.3	187	150.4	0.4	287	150.1	0.1
88	150.4	0.4	188	150.4	0.4	288	150.1	0.1
89	150.4	0.4	189	150.6	0.6	289	150.3	0.3
90	150.8	0.8	190	151.0	1.0	290	150.6	0.6
91	150.3	0.3	191	150.1	0.1	291	149.7	-0.3
92	150.3	0.3	192	150.1	0.1	292	149.7	-0.3
93	150.3	0.3	193	150.3	0.3	293	149.9	-0.1
94	150.4	0.4	194	150.3	0.3	294	150.1	0.1
95	150.4	0.4	195	150.3	0.3	295	150.1	0.1
96	150.4	0.4	196	150.3	0.3	296	150.1	0.1
97	150.4	0.4	197	150.4	0.4	297	150.1	0.1
98	150.4	0.4	198	150.4	0.4	298	150.3	0.3
99	150.4	0.4	199	150.6	0.6	299	150.3	0.3
100	150.8	0.8	200	150.8	0.8	300	150.8	0.8

Range for 150°F Signal: +1.2/-0.3Allowable range: ± 1.8

Performed by:

Mgr. Fire Resistance
Title

Approved by:

3/11/05
Date

Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): 300.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	300.2	0.2	101	299.8	-0.2	201	300.0	0.0
2	300.2	0.2	102	299.8	-0.2	202	300.0	0.0
3	300.0	0.0	103	300.2	0.2	203	300.0	0.0
4	300.2	0.2	104	300.2	0.2	204	300.2	0.2
5	300.2	0.2	105	300.2	0.2	205	300.2	0.2
6	300.2	0.2	106	300.2	0.2	206	300.2	0.2
7	300.2	0.2	107	300.2	0.2	207	300.4	0.4
8	300.4	0.4	108	300.4	0.4	208	300.4	0.4
9	300.6	0.6	109	300.4	0.4	209	300.6	0.6
10	300.7	0.7	110	300.7	0.7	210	300.7	0.7
11	300.2	0.2	111	300.0	0.0	211	299.8	-0.2
12	300.2	0.2	112	300.0	0.0	212	299.8	-0.2
13	300.2	0.2	113	300.2	0.2	213	300.0	0.0
14	300.2	0.2	114	300.2	0.2	214	300.0	0.0
15	300.2	0.2	115	300.2	0.2	215	300.0	0.0
16		0.2	116	300.2	0.2	216	300.2	0.2
	300.2			-			-l 1-	
17	300.2	0.2	117	300.4	0.4	217	300.2	0.2
18	300.2	0.2	118	300.4	0.4	218	300.2	0.2
19	300.4	0.4	119	300.6	0.6	219	300.2	0.2
20	300.6	0.6	120	300.7	0.7	220	300.6	0.6
21	300.2	0.2	121	300.4	0.4	221	299.5	-0.5
22	300.2	0.2	122	300.2	0.2	222	299.7	-0.3
23	300.2	0.2	123	300.2	0.2	223	299.7	-0.3
24	300.2	0.2	124	300.2	0.2	224	299.7	-0.3
25	300.2	0.2	125	300.4	0.4	225	300.0	0.0
26	300.4	0.4	126	300.4	0.4	226	300.2	0.2
27	300.6	0.6	127	300.6	0.6	227	300.2	0.2
28	300.2	0.2	128	300.7	0.7	228	300.2	0.2
29	300.2	0.2	129	300.7	0.7	229	300.4	0.4
30	300.2	0.2	130	300.9	0.9	230	300.7	0.7
31	300.2	0.2	131	300.0	0.0	231	300.0	0.0
32	300.6	0.6	132	299.8	-0.2	232	300.0	0.0
33	300.4	0.4	133	299.8	-0.2	233	299.8	-0.2
34	300.6	0.6	134	300.0	0.0	234	300.0	0.0
35	300.6	0.6	135	300.0	0.0	235	300.0	0.0
36	300.6	0.6	136	300.2	0.2	236	300.2	0.2
37	300.4	0.4	137	300.2	0.2	237	300.2	0.2
38	300.4	0.6	138	300.2	0.2	238	300.2	0.2
39	300.7	0.7	139	300.2	0.2	239	300.6	0.6
40	300.7	1.1	140	300.6	0.6	240	300.7	0.7
	300.2	0.2	141	299.8	-0.2	241	300.7	0.2
41			141	299.8	-0.2	242	300.2	0.2
	300.2	0.2						
43	300.2	0.2	143	300.0	0.0	243	300.2	0.2
44	300.2	0.2	144	300.0	0.0	244	300.2	0.2
45	300.2	0.2	145	300.0	0.0	245	300.4	0.4
46	300.2	0.2	146	300.0	0.0	246	300.4	0.4
47	300.2	0.2	147	300.2	0.2	247	300.6	0.6
48	300.4	0.4	148	300.2	0.2	248	300.7	0.7
49	300.6	0.6	149	300.4	0.4	249	300.7	0.7
50	300.7	0.7	150	300.6	0.6	250	301.3	1.3
51	299.8	-0.2	151	300.4	0.4	251	300.2	0.2
52	299.8	-0.2	152	300.4	0.4	252	300.0	0.0
53	299.8	-0.2	153	300.4	0.4	253	300.2	0.2
54	300.0	0.0	154	300.4	0.4	254	300.2	0.2
55	300.0	0.0	155	300.6	0.6	255	300.2	0.2
56	300.2	0.2	156	300.4	0.4	256	300.2	0.2

Page 415

57	300.2	0.2	157	300.6	0.6	257	300.2	0.2
58	300.2	0.2	158	300.7	0.7	258	300.2	0.2
59	300.4	0.4	159	300.7	0.7	259	300.4	0.4
60	300.7	0.7	160	301.1	1.1	260	300.7	0.7
61	300.2	0.2	161	300.4	0.4	261	300.0	0.0
62	300.2	0.2	162	300.4	0.4	262	300.2	0.2
63	300.2	0.2	163	300.4	0.4	263	300.2	0.2
64	300.2	0.2	164	300.4	0.4	264	300.2	0.2
65	300.4	0.4	165	300.4	0.4	265	300.2	0.2
66	300.4	0.4	166	300.6	0.6	266	300.2	0.2
67	300.6	0.6	167	300.6	0.6	267	300.4	0.4
68	300.6	0.6	168	300.7	0.7	268	300.6	0.6
69	300.7	0.7	169	300.7	0.7	269	300.7	0.7
70	300.7	0.7	170	301.3	1.3	270	301.1	1.1
71	300.2	0.2	171	300.0	0.0	271	300.2	0.2
72	300.2	0.2	172	300.0	0.0	272	300.0	0.0
73	300.2	0.2	173	300.2	0.2	273	300.2	0.2
74	300.2	0.2	174	300.2	0.2	274	300.2	0.2
75	300.4	0.4	175	300.2	0.2	275	300.2	0.2
76	300.4	0.4	176	300.2	0.2	276	300.2	0.2
77	300.4	0.4	177	300.2	0.2	277	300.4	0.4
78	300.4	0.4	178	300.2	0.2	278	300.4	0.4
79	300.7	0.7	179	300.4	0.4	279	300.4	0.4
80	300.9	0.9	180	300.7	0.7	280	300.7	0.7
81	300.2	0.2	181	300.4	0.4	281	299.7	-0.3
82	300.2	0.2	182	300.2	0.2	282	299.8	-0.2
83	300.4	0.4	183	300.2	0.2	283	299.7	-0.3
84	300.4	0.4	184	300.2	0.2	284	299.8	-0.2
85	300.4	0.4	185	300.4	0.4	285	300.0	0.0
86	300.4	0.4	186	300.4	0.4	286	300.2	0.2
87	300.6	0.6	187	300.6	0.6	287	300.2	0.2
88	300.6	0.6	188	300.6	0.6	288	300.2	0.2
89	300.7	0.7	189	300.7	0.7	289	300.4	0.4
90	300.9	0.9	190	301.1	1.1	290	300.7	0.7
91	300.2	0.2	191	300.2	0.2	291	299.7	-0.3
92	300.2	0.2	192	300.2	0.2	292	299.8	-0.2
93	300.2	0.2	193	300.2	0.2	293	300.0	0.0
94	300.2	0.2	194	300.2	0.2	294	300.0	0.0
95	300.2	0.2	195	300.2	0.2	295	300.0	0.0
96	300.2	0.2	196	300.2	0.2	296	300.2	0.2
97	300.4	0.4	197	300.4	0.4	297	300.2	0.2
98	300.6	0.6	198	300.4	0.4	298	300.4	0.4
99	300.4	0.4	199	300.6	0.6	299	300.4	0.4
100	300.7	0.7	200	300.7	0.7	300	300.7	0.7

Range for 300°F Signal: +1.3/-0.5
Allowable range ±1.9

Within specification for this tempera	ature? Yes	
Performed by:	MU	
	Mgr. Fire Resistance	3/11/05
	Title	Date
Approved by:		3/ /
Wighen	President	7/11/bJ

Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): 400.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	400.3	0.3	101	400.1	0.1	201	400.3	0.3
2	400.3	0.3	102	400.3	0.3	202	400.3	0.3
3	400.1	0.1	103	400.3	0.3	203	400.3	0.3
4	400.1	0.1	104	400.3	0.3	204	400.3	0.3
5	400.1	0.1	105	400.3	0.3	205	400.3	0.3
6	400.3	0.3	106	400.3	0.3	206	400.5	0.5
7	400.3	0.3	107	400.3	0.3	207	400.6	0.6
8	400.3	0.3	108	400.3	0.3	208	400.8	0.8
9	400.3	0.3	109	400.5	0.5	209	400.8	0.8
10	400.6	0.6	110	400.6	0.6	210	400.8	0.8
11	400.1	0.1	111	400.1	0.1	211	399.9	-0.
12	400.1	0.1	112	400.3	0.3	212	400.1	0.1
13	399.9	-0.1	113	400.3	0.3	213	400.1	0.1
	400.1	0.1	114	400.3	0.3	214	400.1	0.1
14 15	400.1	0.1	115	400.5	0.5	215	400.1	0.1
5.0352	_	0.1	116	400.6	0.6	216	400.3	0.3
16	400.1		117	400.6	0.6	217	400.3	0.3
17	400.1	0.1		400.8	0.8	218	400.3	0.3
18	400.3	0.3	118	_		219	400.3	0.3
19	400.3	0.3	119	400.8	0.8		400.6	0.6
20	400.5	0.5	120	400.8	0.8	220	399.7	-0.3
21	400.1	0.1	121	400.5	0.5	222	399.9	
22	400.1	0.1	122	400.5	0.5	7.50.000		-0.1
23	400.3	0.3	123	400.3	0.3	223	400.1	0.1
24	400.3	0.3	124	400.3	0.3	224	400.1	0.1
25	400.5	0.5	125	400.3	0.3	225	400.1	0.1
26	400.1	0.1	126	400.3	0.3	226	400.1	0.1
27	400.1	0.1	127	400.5	0.5	227	400.3	0.3
28	400.3	0.3	128	400.6	0.6	228	400.3	0.3
29	400.3	0.3	129	400.8	0.8	229	400.5	0.5
30	400.3	0.3	130	401.0	1.0	230	400.6	0.6
31	400.5	0.5	131	399.9	-0.1	231	400.3	0.3
32	400.3	0.3	132	399.9	-0.1	232	400.1	0.1
33	400.3	0.3	133	399.9	-0.1	233	400.3	0.3
34	400.3	0.3	134	399.9	-0.1	234	400.3	0.3
35	400.3	0.3	135	399.9	-0.1	235	400.3	0.3
36	400.5	0.5	136	399.9	-0.1	236	400.3	0.3
37	400.5	0.5	137	399.9	-0.1	237	400.5	0.5
38	400.6	0.6	138	400.1	0.1	238	400.5	0.5
39	400.8	0.8	139	400.3	0.3	239	400.6	0.6
40	400.8	0.8	140	400.5	0.5	240	400.8	0.8
41	399.9	-0.1	141	399.7	-0.3	241	400.3	0.3
42	399.9	-0.1	142	399.7	-0.3	242	400.3	0.3
43	399.9	-0.1	143	399.9	-0.1	243	400.3	0.3
44	400.1	0.1	144	399.9	-0.1	244	400.3	0.3
45	400.1	0.1	145	399.9	-0.1	245	400.3	0.3
46	400.1	0.1	146	400.1	0.1	246	400.5	0.5
47	400.1	0.1	147	400.1	0.1	247	400.6	0.6
48	400.3	0.3	148	400.3	0.3	248	400.6	0.6
49	400.3	0.3	149	400.3	0.3	249	401.2	1.2
50	400.6	0.6	150	400.6	0.6	250	401.2	1.2
51	399.7	-0.3	151	400.5	0.5	251	400.1	0.1
52	399.9	-0.1	152	400.3	0.3	252	400.1	0.1
53	400.1	0.1	153	400.3	0.3	253	400.1	0.1
54	400.1	0.1	154	400.5	0.5	254	400.3	0.3

Page 417

55	400.1	0.1	155	400.5	0.5	255	400.3	0.3
56	400.3	0.3	156	400.6	0.6	256	400.3	0.3
57	400.3	0.3	157	400.6	0.6	257	400.5	0.5
58	400.3	0.3	158	400.6	0.6	258	400.6	0.6
59	400.5	0.5	159	400.6	0.6	259	400.6	0.6
60	400.6	0.6	160	400.8	0.8	260	400.8	0.8
61	400.6	0.6	161	400.3	0.3	261	400.3	0.3
62	400.3	0.3	162	400.3	0.3	262	400.3	0.3
63	400.3	0.3	163	400.3	0.3	263	400.3	0.3
64	400.3	0.3	164	400.3	0.3	264	400.3	0.3
65	400.3	0.3	165	400.5	0.5	265	400.3	0.3
66	400.3	0.3	166	400.6	0.6	266	400.3	0.3
67	400.5	0.5	167	400.6	0.6	267	400.5	0.5
68	400.6	0.6	168	400.8	0.8	268	400.6	0.6
	400.8	0.8	169	400.8	0.8	269	400.8	0.8
69	_	0.8	170	401.0	1.0	270	400.8	0.8
70	400.8			399.7	-0.3	271	400.3	0.3
71	400.3	0.3	171	399.9	-0.3	272	400.3	0.3
72	400.3	0.3	172	22.22.22.22.2		273	400.3	0.3
73	400.3	0.3	173	399.9	-0.1	274	400.3	0.3
74	400.5	0.5	174	400.1	0.1	275	400.5	0.5
75	400.3	0.3	175	400.3	0.3			
76	400.3	0.3	176	400.3	0.3	276	400.5	0.5
77	400.5	0.5	177	400.3	0.3	277	400.5	0.5
78	400.6	0.6	178	400.3	0.3	278	400.6	0.6
79	400.6	0.6	179	400.6	0.6	279	400.6	0.6
80	401.0	1.0	180	400.8	0.8	280	400.8	0.8
81	400.3	0.3	181	400.5	0.5	281	399.6	-0.4
82	400.3	0.3	182	400.3	0.3	282	399.6	-0.4
83	400.5	0.5	183	400.3	0.3	283	399.7	-0.3
84	400.5	0.5	184	400.5	0.5	284	399.9	-0.1
85	400.5	0.5	185	400.5	0.5	285	399.9	-0.1
86	400.5	0.5	186	400.6	0.6	286	400.1	0.1
87	400.6	0.6	187	400.6	0.6	287	400.3	0.3
88	400.6	0.6	188	400.8	0.8	288	400.3	0.3
89	400.8	0.8	189	400.8	0.8	289	400.3	0.3
90	400.8	0.8	190	401.2	1.2	290	400.6	0.6
91	400.5	0.5	191	400.3	0.3	291	399.7	-0.3
92	400.3	0.3	192	400.3	0.3	292	399.7	-0.3
93	400.3	0.3	193	400.3	0.3	293	399.7	-0.3
94	400.3	0.3	194	400.3	0.3	294	399.9	-0.1
95	400.3	0.3	195	400.3	0.3	295	399.9	-0.1
96	400.5	0.5	196	400.3	0.3	296	400.1	0.1
97	400.5	0.5	197	400.5	0.5	297	400.3	0.3
98	400.8	0.8	198	400.6	0.6	298	400.3	0.3
99	400.8	0.8	199	400.6	0.6	299	400.3	0.3
100	401.0	1.0	200	400.8	0.8	300	400.6	0.6

Range for 400°F Signal: +1.2/-0.4
Allowable range: ±2.0
Within specification for this temperature?

Performed by:

Performed by:

Mgr. Fire Resistance 3/11/05
Title Date

Approved by:

President

3/11/05 Date 05

Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): 1000.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
11	999.0	-1.0	101	1000.0	0.0	201	1000.4	0.4
2	999.0	-1.0	102	1000.0	0.0	202	1000.4	0.4
3	999.0	-1.0	103	1000.0	0.0	203	1000.4	0.4
4	999.5	-0.5	104	1000.2	0.2	204	1000.4	0.4
5	999.7	-0.3	105	1000.4	0.4	205	1000.4	0.4
6	999.7	-0.3	106	1000.4	0.4	206	1000.4	0.4
7	999.9	-0.1	107	1000.6	0.6	207	1000.6	0.6
8	1000.0	0.0	108	1000.6	0.6	208	1000.6	0.6
9	1000.2	0.2	109	1000.6	0.6	209	1000.8	0.8
10	1000.6	0.6	110	1000.9	0.9	210	1000.9	0.9
11	999.9	-0.1	111	1000.2	0.2	211	1000.0	0.0
12	999.7	-0.3	112	1000.4	0.4	212	1000.0	0.0
13	999.9	-0.1	113	1000.4	0.4	213	1000.0	0.0
14	999.9	-0.1	114	1000.4	0.4	214	1000.2	0.2
15	999.9	-0.1	115	1000.6	0.6	215	1000.2	0.2
16	999.7	-0.3	116	1000.6	0.6	216	1000.2	0.2
17	999.9	-0.1	117	1000.6	0.6	217	1000.2	0.2
18	999.9	-0.1	118	1000.8	0.8	218	1000.4	0.4
19	1000.0	0.0	119	1000.9	0.9	219	1000.6	0.6
		DATE 250	120	1000.9	0.9	220	1000.6	0.6
20	1000.0	0.0		1000.9	0.6	221	999.9	-0.1
21	999.9	-0.1	121	1000.6		222	1000.0	0.0
22	999.7	-0.3	122	-	0.4		1000.0	0.0
23	999.7	-0.3	123	1000.2		223		107727.72
24	999.9	-0.1	124	1000.4	0.4	224	1000.0	0.0
25	999.9	-0.1	125	1000.6	0.6	225	1000.0	0.0
26	999.7	-0.3	126	1000.6	0.6	226	1000.0	0.0
27	999.9	-0.1	127	1000.6	0.6	227	1000.0	0.0
28	999.9	-0.1	128	1000.6	0.6	228	1000.2	0.2
29	1000.0	0.0	129	1000.8	8.0	229	1000.4	0.4
30	1000.0	0.0	130	1000.9	0.9	230	1000.6	0.6
31	1000.0	0.0	131	1000.0	0.0	231	1000.0	0.0
32	1000.0	0.0	132	1000.0	0.0	232	1000.2	0.2
33	1000.2	0.2	133	1000.0	0.0	233	1000.4	0.4
34	1000.4	0.4	134	1000.0	0.0	234	1000.4	0.4
35	1000.4	0.4	135	1000.0	0.0	235	1000.6	0.6
36	1000.4	0.4	136	1000.0	0.0	236	1000.6	0.6
37	1000.6	0.6	137	1000.2	0.2	237	1000.6	0.6
38	1000.6	0.6	138	1000.4	0.4	238	1000.9	0.9
39	1000.6	0.6	139	1000.4	0.4	239	1000.4	0.4
40	1000.9	0.9	140	1000.6	0.6	240	1000.2	0.2
41	1000.0	0.0	141	1000.0	0.0	241	1000.2	0.2
42	999.9	-0.1	142	1000.0	0.0	242	1000.2	0.2
43	1000.0	0.0	143	1000.0	0.0	243	1000.2	0.2
44	1000.0	0.0	144	1000.0	0.0	244	1000.4	0.4
45	1000.0		145	1000.0	0.0	245	1000.4	0.4
46	1000.0	0.0	146	1000.0	0.0	246	1000.2	0.2
47	1000.0	0.0	147	1000.2	0.2	247	1000.2	0.2
48	1000.2	0.2	148	1000.6	0.6	248	1000.2	0.2
49	1000.6	0.6	149	1000.6	0.6	249	1000.8	0.8
50	1000.6	0.6	150	1000.6	0.6	250	1001.1	1.1
	999.7		151	1000.4	0.4	251	1000.2	0.2
51		-0.3	152	1000.4	0.4	252	1000.2	0.2
52	999.9	-0.1	-			253	1000.2	0.4
53	1000.0	0.0	153	1000.4	0.4		1000.4	0.4
54	1000.0	0.0	154	1000.2	0.2	254	1000.4	
55 56	1000.0	0.0	155 156	1000.4	0.4	255 256	1000.4	0.4

Page 419

57	1000.2	0.2	157	1000.4	0.4	257	1000.4	0.4
58	1000.4	0.4	158	1000.6	0.6	258	1000.6	0.6
59	1000.4	0.4	159	1000.6	0.6	259	1000.6	0.6
60	1000.6	0.6	160	1000.9	0.9	260	1000.8	0.8
61	1000.6	0.6	161	1000.4	0.4	261	1000.0	0.0
62	1000.4	0.4	162	1000.4	0.4	262	1000.0	0.0
63	1000.4	0.4	163	1000.4	0.4	263	1000.2	0.2
64	1000.4	0.4	164	1000.6	0.6	264	1000.2	0.2
65	1000.4	0.4	165	1000.6	0.6	265	1000.4	0.4
66	1000.6	0.6	166	1000.6	0.6	266	1000.4	0.4
67	1000.6	0.6	167	1000.6	0.6	267	1000.6	0.6
68	1000.6	0.6	168	1000.6	0.6	268	1000.6	0.6
69	1000.9	0.9	169	1000.6	0.6	269	1000.6	0.6
70	1000.9	0.9	170	1000.9	0.9	270	1000.9	0.9
71	1000.6	0.6	171	999.9	-0.1	271	1000.0	0.0
72	1000.4	0.4	172	1000.0	0.0	272	1000.0	0.0
73	1000.4	0.6	173	1000.0	0.0	273	1000.0	0.0
74	1000.4	0.4	174	1000.2	0.2	274	1000.0	0.0
75	1000.4	0.8	175	1000.2	0.2	275	1000.0	0.0
	1000.6	0.6	176	1000.4	0.4	276	1000.0	0.0
76 77	1000.8	0.8	177	1000.4	0.6	277	1000.2	0.2
	1000.8	0.8	178	1000.6	0.6	278	1000.2	0.2
78		0.9	179	1000.6	0.6	279	1000.6	0.6
79	1000.9	0.9	180	1000.0	0.9	280	1000.8	0.8
80		0.4	181	1000.6	0.6	281	999.7	-0.3
81	1000.4		182	1000.6	0.6	282	999.7	-0.3
82	1000.4	0.4			0.6	283	999.7	-0.3
83	1000.4	0.4	183	1000.6		284	999.9	-0.1
84	1000.4	0.4	184		0.6	285	999.9	-0.1
85	1000.6	0.6	185	1000.6			999.9	-0.1
86	1000.6	0.6	186	1000.8	0.8	286	1000.0	
87	1000.6	0.6	187	1000.6	0.6	287		0.0
88	1000.6	0.6	188	1000.8	8.0	288	1000.0	0.0
89	1000.9	0.9	189	1000.9	0.9	289	1000.0	
90	1000.9	0.9	190	1001.3	1.3	290	1000.4	0.4
91	1000.4	0.4	191	1000.6	0.6	291	999.7	-0.3
92	1000.4	0.4	192	1000.4	0.4	292	999.7	-0.3
93	1000.6	0.6	193	1000.6	0.6	293	999.9	-0.1
94	1000.6	0.6	194	1000.6	0.6	294	1000.0	0.0
95	1000.6	0.6	195	1000.6	0.6	295	1000.0	0.0
96	1000.6	0.6	196	1000.6	0.6	296	1000.0	0.0
97	1000.6	0.6	197	1000.8	0.8	297	1000.0	0.0
98	1000.6	0.6	198	1000.9	0.9	298	1000.2	0.2
99	1000.6	0.6	199	1000.9	0.9	299	1000.0	0.0
100	1000.9	0.9	200	1001.1	1.1	300	1000.4	0.4

Range for 1000°F Signal: +1.3/-1
Allowable range: ±2.3
Within specification for this temperature?

Performed by:

Mgr. Fire Resistance
Title

Approved by:

Serial No.: 48JF0082

Calibrator Used: T-207318

Temperature Setting (°F): 2000.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1999.8	-0.2	101	2000.7	0.7	201	2000.7	0.7
2	1999.8	-0.2	102	2000.7	0.7	202	2000.7	0.7
3	1999.6	-0.4	103	2000.7	0.7	203	2000.7	0.7
4	1999.6	-0.4	104	2000.7	0.7	204	2000.7	0.7
5	1999.6	-0.4	105	2000.7	0.7	205	2000.8	0.8
6	1999.8	-0.2	106	2000.7	0.7	206	2001.0	1.0
7	1999.8	-0.2	107	2000.8	0.8	207	2001.0	1.0
8	1999.8	-0.2	108	2000.8	0.8	208	2001.0	1.0
9	1999.9	-0.1	109	2001.0	1.0	209	2001.4	1.4
10	2000.3	0.3	110	2001.0	1.0	210	2001.4	1.4
11	1999.6	-0.4	111	2000.7	0.7	211	2000.7	0.7
12	1999.6	-0.4	112	2000.7	0.7	212	2000.7	0.7
13	1999.4	-0.6	113	2000.7	0.7	213	2000.7	0.7
14	1999.8	-0.2	114	2000.8	0.8	214	2000.7	0.7
15	1999.8	-0.2	115	2000.8	0.8	215	2000.7	0.7
16	1999.8	-0.2	116	2001.0	1.0	216	2000.7	0.7
	1999.8	-0.2	117	2001.0	1.0	217	2000.7	0.7
17		-0.2	118	2001.0	1.2	218	2000.7	0.7
18	1999.8 1999.8	-0.2	119	2001.4	1.4	219	2000.7	0.7
19				2001.4	1.6	220	2001.0	1.0
20	1999.9	-0.1	120	2000.7	0.7	221	2000.3	0.3
21	1999.4	-0.6	121	100707000000000000000000000000000000000				
22	1999.4	-0.6	122	2000.7	0.7	222	2000.3	0.3
23	1999.4	-0.6	123	2000.5	0.5	223	2000.5	0.5
24	1999.6	-0.4	124	2000.7	0.7	224	2000.5	0.5
25	1999.8	-0.2	125	2000.7	0.7	225	2000.5	0.5
26	1999.8	-0.2	126	2000.7	0.7	226	2000.5	0.5
27	1999.8	-0.2	127	2000.8	0.8	227	2000.7	0.7
28	1999.9	-0.1	128	2001.0	1.0	228	2000.7	0.7
29	1999.4	-0.6	129	2001.0	1.0	229	2000.8	0.8
30	1999.4	-0.6	130	2001.4	1.4	230	2001.0	1.0
31	2000.5	0.5	131	2000.5	0.5	231	2000.7	0.7
32	2000.5	0.5	132	2000.3	0.3	232	2000.7	0.7
33	2000.5	0.5	133	2000.3	0.3	233	2000.8	0.8
34	2000.3	0.3	134	2000.3	0.3	234	2000.8	0.8
35	2000.5	0.5	135	2000.3	0.3	235	2000.8	0.8
36	2000.5	0.5	136	2000.3	0.3	236	2001.0	1.0
37	2000.7	0.7	137	2000.3	0.3	237	2001.0	1.0
38	2000.7	0.7	138	2000.5	0.5	238	2001.0	1.0
39	2000.7	0.7	139	2000.7	0.7	239	2001.0	1.0
40	2001.0	1.0	140	2000.8	0.8	240	2001.4	1.4
41	2000.1	0.1	141	2000.1	0.1	241	2000.7	0.7
42	2000.1	0.3	142	2000.1	0.1	242	2000.7	0.7
43	2000.1	0.1	143	2000.3	0.3	243	2000.3	0.3
43	2000.1	0.5	144	2000.5	0.5	244	2000.5	0.5
45	2000.5	0.5	145	2000.5	0.5	245	2000.7	0.7
1000		70.000	146	2000.5	0.5	246	2000.7	0.7
46	2000.5	0.5	147	2000.5	0.5	247	2000.7	0.7
47	2000.5	0.5		-		248	2000.7	0.7
48	2000.5	0.5	148	2000.7	0.7	248	2000.8	1.0
49	2000.5	0.5	149	2000.7	0.7	The second second	T	
50	2000.7	0.7	150	2001.0	1.0	250	2001.2	1.2
51	1999.9	-0.1	151	2000.5	0.5	251	2000.1	0.1
52	1999.9	-0.1	152	2000.5	0.5	252	1999.9	-0.
53	1999.9	-0.1	153	2000.3	0.3	253	1999.9	-0.
54	1999.9	-0.1	154	2000.5	0.5	254	2000.1	0.
55	2000.1	0.1	155	2000.7	0.7	255	2000.1	0.1
56	2000.3	0.3	156	2000.7	0.7	256	2000.3	0.3

Page 421

57	2000.5	0.5	157	2000.7	0.7	257	2000.3	0.3
58	2000.7	0.7	158	2000.7	0.7	258	2000.7	0.7
59	2000.7	0.7	159	2001.0	1.0	259	2000.7	0.7
60	2000.8	0.8	160	2001.2	1.2	260	2000.8	0.8
61	2000.8	0.8	161	2000.7	0.7	261	2000.1	0.1
62	2000.7	0.7	162	2000.7	0.7	262	2000.1	0.1
63	2000.7	0.7	163	2000.7	0.7	263	2000.1	0.1
64	2000.7	0.7	164	2000.7	0.7	264	2000.1	0.1
65	2000.7	0.7	165	2000.7	0.7	265	2000.1	0.1
66	2000.7	0.7	166	2000.7	0.7	266	2000.3	0.3
67	2000.8	0.8	167	2000.7	0.7	267	2000.3	0.3
68	2001.0	1.0	168	2000.8	0.8	268	2000.5	0.5
69	2001.0	1.0	169	2001.0	1.0	269	2000.7	0.7
70	2001.4	1.4	170	2001.2	1.2	270	2001.0	1.0
71	2000.7	0.7	171	2000.1	0.1	271	1999.9	-0.1
72	2000.8	0.8	172	2000.1	0.1	272	1999.9	-0.1
73	2000.8	0.8	173	2000.3	0.3	273	1999.9	-0.1
74	2001.0	1.0	174	2000.3	0.3	274	1999.9	-0.1
75	2000.8	0.8	175	2000.5	0.5	275	1999.9	-0.1
76	2001.0	1.0	176	2000.5	0.5	276	2000.1	0.1
77	2000.8	0.8	177	2000.5	0.5	277	1999.9	-0.1
78	2001.0	1.0	178	2000.7	0.7	278	2000.1	0.1
79	2001.0	1.0	179	2000.8	0.8	279	2000.3	0.3
80	2001.4	1.4	180	2001.0	1.0	280	2000.7	0.7
81	2000.7	0.7	181	2001.2	1.2	281	1999.2	-0.8
82	2000.7	0.7	182	2001.0	1.0	282	1999.2	-0.8
83	2000.8	0.8	183	2001.0	1.0	283	1999.4	-0.6
84	2000.8	0.8	184	2001.2	1.2	284	1999.4	-0.6
85	2000.8	0.8	185	2001.2	1.2	285	1999.6	-0.4
86	2001.0	1.0	186	2001.2	1.2	286	1999.6	-0.4
87	2001.0	1.0	187	2001.4	1.4	287	1999.6	-0.4
88	2000.8	0.8	188	2001.4	1.4	288	1999.6	-0.4
89	2001.0	1.0	189	2001.6	1.6	289	1999.9	-0.1
90	2001.2	1.2	190	2001.7	1.7	290	1999.9	-0.1
91	2000.7	0.7	191	2001.0	1.0	291	1999.2	-0.8
92	2000.7	0.7	192	2001.0	1.0	292	1999.2	-0.8
93	2000.7	0.7	193	2001.0	1.0	293	1999.2	-0.8
94	2000.7	0.7	194	2001.0	1.0	294	1999.4	-0.6
95	2000.7	0.7	195	2001.0	1.0	295	1999.6	-0.4
96	2000.7	0.7	196	2001.2	1.2	296	1999.6	-0.4
97	2000.8	0.8	197	2001.4	1.4	297	1999.8	-0.2
98	2001.0	1.0	198	2001.4	1.4	298	1999.9	-0.1
99	2001.0	1.0	199	2001.4	1.4	299	1999.9	-0.1
100	2001.4	1.4	200	2001.6	1.6	300	2000.3	0.3

Range for 2000°F Signal: +1.7/-0.8

Allowable range: ±2.8

Within specification for this temperature?

Performed by:

Mgr. Fire Resistance

Title

Approved by:

Approved

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 FAX 210-635-8101 800-966-5253

Certificate of Verification

Certification No.:

92145

Verification Date:

03/11/2005

Reverification Date:

09/11/2005

Manufacturer:

Yokogawa

Model No.:

100 Channel DAU

Serial No.:

99LE004

Equipment Description: 100 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Verification Sources:

TEGAM Model 840-A, SN: T-207318.

Calibration due 05/03/2005

DEBEORMANCE.

Temperature: (75°F)	Temperature: (150°F)	Temperature: (300°F)	Temperature: (400°F)	Temperature: (1000°F)	Temperature: (2000°F)
+1.3/-0.2	+1.3/-0.1	+1.3/-0.3	+1/-0.3	++1.1/-0.3	+1.2/-0.2

Verification Performed by:

Mike Dey

Manager of Fire Resistance

Verification Approved by:

Deg Priest

President/Chief Technical Officer



Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): 75.0

Within specs?

Performed by: Mike Dey
Title: Mgr. Dept. 2

Date: 3/11/05

Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
75.7	0.7	51	75.0	0.0
75.7	0.7	52	75.2	0.2
75.7	0.7	53	75.0	0.0
75.7	0.7	54	75.0	0.0
75.7	0.7	55	75.2	0.2
75.9	0.9	56	75.2	0.2
75.7	0.7	57	75.2	0.2
75.7	0.7	58	75.2	0.2
75.9	0.9	59	75.4	0.4
76.3	1.3	60	75.4	0.4
75.6	0.6	61	75.7	0.7
75.4	0.4	62	75.4	0.4
75.4	0.4	63	75.4	0.4
75.2	0.2	64	75.4	0.4
	0.4	65	75.4	0.4
75.6	0.6	66	75.4	0.4
-	0.2	67	75.6	0.6
-		68	75.6	0.6
-			75.7	0.7
			76.1	1.1
				0.4
⊣ ⊢			_	0.2
			-	0.2
⊣ ⊢			_	0.2
-			⊣	0.2
_			-	0.2
	1990.00		_	0.4
				0.4
			_	0.4
- Santing 1991 -			_	0.7
			100,000	0.4
			-	0.2
_				0.2
-			_	0.2
-				0.2
_			_	0.4
			_	0.4
_				0.6
	17.000		-	0.6
-				0.0
			-	-0.2
				71.50- 70.707
			_	-0.2
-		-	_	-0.2
-			_	
-			_	0.2
-			_	0.0
	170.01 270.0		_	0.2
-				0.2
75.7 75.7	0.7	100	75.2 75.2	0.2
	75.7 75.7 75.7 75.7 75.9 75.7 75.9 76.3 75.6 75.4 75.4 75.2 75.4	75.7	75.7	75.7 0.7 52 75.2 75.7 0.7 53 75.0 75.7 0.7 54 75.0 75.7 0.7 55 75.2 75.9 0.9 56 75.2 75.7 0.7 57 75.2 75.7 0.7 58 75.2 75.9 0.9 59 75.4 76.3 1.3 60 75.4 75.6 0.6 61 75.7 75.4 0.4 62 75.4 75.4 0.4 63 75.4 75.4 0.4 65 75.4 75.4 0.4 65 75.4 75.6 0.6 66 75.4 75.7 0.7 69 75.7 75.9 0.9 70 76.1 75.7 0.7 71 75.4 75.6 0.6 72 75.2 75.6 0.6 75 </td

Range of 75°F Readings:

+1.3/-0.2

Allowable limits

Lower

Upper

73.2

76.8 (±1.8)

Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): 150.0

Within specs? Yes/No

Performed by: Mike Dey

Title: Mgr. Dept. 2

Approved by: Title: President

Date: 3/11/05

annel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	151.0	1.0	51	150.1	0.1
2	150.8	0.8	52	149.9	-0.1
3	150.8	0.8	53	149.9	-0.1
4	150.8	0.8	54	150.1	0.1
5	150.8	0.8	55	150.1	0.1
6	150.8	0.8	56	150.1	0.1
7	150.8	0.8	57	150.1	0.1
8	151.0	1.0	58	150.3	0.3
9	151.0	1.0	59	150.3	0.3
10	151.3	1.3	60	150.4	0.4
11	150.6	0.6	61	150.6	0.6
12	150.3	0.3	62	150.3	0.3
13	150.3	0.3	63	150.3	0.3
14	150.3	0.3	64	150.3	0.3
15	150.3	0.3	65	150.3	0.3
16	150.3	0.3	66	150.4	0.4
17	150.4	0.4	67	150.6	0.6
18	150.4	0.4	68	150.4	0.4
19	150.6	0.6	69	150.6	0.6
20	150.8	0.8	70	150.8	0.8
21	150.6	0.6	71	150.3	0.3
22	150.4	0.4	72	149.9	-0.1
23	150.3	0.3	73	149.9	-0.1
24	150.4	0.4	74	150.1	0.1
25	150.4	0.4	75	150.1	0.1
26	150.4	0.4	76	150.1	0.1
27	150.6	0.6	77	150.3	0.3
28	150.6	0.6	78	150.3	0.3
29	150.8	0.8	79	150.3	0.3
30	151.0	1.0	80	150.6	0.6
31	150.8	0.8	81	150.3	0.3
32	150.4	0.4	82	150.3	0.3
33	150.3	0.3	83	150.3	0.3
34	150.4	0.4	84	150.3	0.3
35	150.4	0.4	85	150.3	0.3
36	150.3	0.3	86	150.3	0.3
37	150.3	0.3	87	150.4	0.4
38	150.4	0.4	88	150.4	0.4
39	150.6	0.6	89	150.6	0.6
40	150.8	0.8	90	150.8	0.8
41	150.6	0.6	91	150.1	0.1
42	150.3	0.3	92	149.9	-0.1
43	150.3	0.3	93	149.9	-0.1
107251		0.4	94	150.1	0.1
44	150.4	0.4	95	150.3	0.3
45	150.4	0.4	96	150.1	0.1
46	150.4			150.1	0.3
47	150.6	0.6	97	150.3	0.3
48	150.6	0.6	98	150.3	0.3
49 50	150.6 151.0	1.0	100	150.5	0.6

Lower

Upper

Range of 150°F Readings: +1.3/-0.1

Allowable limits

148.2

151.8 (±1.8)

Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): __300.0

Within specs? Yes/No

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:

Title: Presi

Date: 3/11/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	300.7	0.7	51	299.8	-0.2
2	300.7	0.7	52	299.7	-0.3
3	300.7	0.7	53	299.8	-0.2
4	300.7	0.7	54	299.8	-0.2
5	300.7	0.7	55	299.8	-0.2
6	300.7	0.7	56	300.0	0.0
7	300.7	0.7	57	300.0	0.0
8	300.7	0.7	58	300.0	0.0
9	301.1	1.1	59	300.2	0.2
10	301.3	1.3	60	300.4	0.4
11	300.6	0.6	61	300.4	0.4
12	300.4	0.4	62	300.2	0.2
13	300.4	0.4	63	300.2	0.2
14	300.6	0.6	64	300.2	0.2
15	300.4	0.4	65	300.2	0.2
16	300.4	0.4	66	300.2	0.2
17	300.4	0.4	67	300.2	0.2
18	300.6	0.6	68	300.4	0.4
19	300.6	0.6	69	300.6	0.6
20	300.9	0.9	70	300.7	0.7
21	300.4	0.4	71	300.2	0.2
22	300.2	0.2	72	300.2	0.2
23	300.4	0.4	73	300.0	0.0
24	300.2	0.2	74	300.0	0.0
25	300.4	0.4	75	300.2	0.2
26	300.4	0.4	76	300.2	0.2
27	300.4	0.4	77	300.0	0.0
28	300.6	0.6	78	300.2	0.2
29	300.7	0.7	79	300.2	0.2
30	300.9	0.9	80	300.4	0.4
31	300.6	0.6	81	300.2	0.2
32	300.4	0.4	82	300.2	0.2
33	300.4	0.4	83	300.2	0.2
34	300.4	0.4	84	300.2	0.2
35	300.2	0.2	85	300.2	0.2
36	300.4	0.4	86	300.2	0.2
37	300.4	0.4	87	300.2	0.2
38	300.4	0.4	88	300.2	0.2
39	300.6	0.6	89	300.4	0.4
40	300.7	0.7	90	300.7	0.7
41	300.4	0.4	91	299.8	-0.2
42	300.2	0.2	92	299.8	-0.2
43	300.2	0.2	93	299.8	-0.2
44	300.2	0.4	94	299.8	-0.2
	300.4	0.4	95	299.8	-0.2
45	300.4	0.4	96	300.0	0.0
46	-			300.0	0.0
47	300.6	0.6	97	300.0	0.0
48	300.4	0.4	98	300.0	0.0
49 50	300.6	0.6	100	300.2	0.4

Lower

Upper

Range of 300°F Readings: +1.3/-0.3

Allowable limits

298.1

301.9 (±1.9)

Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): 400.0

Within specs?

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by: Title:

Date: 3/11/05

hannel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	400.8	0.8	51	399.7	-0.3
2	400.8	0.8	52	399.7	-0.3
3	400.6	0.6	53	399.7	-0.3
4	400.8	0.8	54	399.7	-0.3
5	400.8	0.8	55	399.9	-0.1
6	400.6	0.6	56	399.9	-0.1
7	400.8	0.8	57	399.9	-0.1
8	400.8	0.8	58	400.1	0.1
9	400.8	0.8	59	400.3	0.3
10	401.0	1.0	60	400.3	0.3
11	400.5	0.5	61	400.6	0.6
12	400.3	0.3	62	400.3	0.3
13	400.3	0.3	63	400.3	0.3
14	400.3	0.3	64	400.3	0.3
15	400.3	0.3	65	400.3	0.3
16	400.3	0.3	66	400.3	0.3
17	400.3	0.3	67	400.3	0.3
18	400.5	0.5	68	400.3	0.3
19	400.5	0.5	69	400.5	0.5
20	400.8	0.8	70	400.8	0.8
21	400.3	0.3	71	400.3	0.3
22	400.3	0.3	72	399.9	-0.1
23	400.1	0.1	73	399.9	-0.1
24	400.3	0.3	74	400.1	0.1
25	400.3	0.3	75	400.1	0.1
26	400.3	0.3	76	400.1	0.1
27	400.3	0.3	77	400.3	0.3
28	400.5	0.5	78	400.1	0.1
29	400.5	0.5	79	400.3	0.3
	400.8	0.8	80	400.6	0.6
30	400.5	0.5	81	400.3	0.3
31	400.5	0.5	82	400.3	0.3
32	400.3	0.3	83	400.3	0.3
33	-	0.3	84	400.1	0.1
34	400.3		85	400.3	0.3
35	400.5	0.5	86	400.3	0.3
36	400.3			400.3	0.3
37	400.3	0.3	87	400.3	0.3
38	400.5	0.5	88	400.5	0.5
39	400.6	0.6	89	_	
40	400.8	0.8	90	400.8	0.8
41	400.3	0.3	91	399.9	-0.1
42	400.3	0.3	92	399.9	-0.1
43	400.3	0.3	93	399.7	-0.3
44	400.3	0.3	94	399.9	-0.1
45	400.3	0.3	95	400.1	0.1
46	400.3	0.3	96	399.9	-0.1
47	400.3	0.3	97	400.1	0.1
48	400.5	0.5	98	400.3	0.3
49	400.6	0.6	99	400.3	0.3
50	400.6	0.6	100	400.3	0.3

Lower

Upper

Range of 400°F Readings: +1/-0.3

Allowable limits

398.0

402.0 (±2.0)

Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): 1000.0

Within specs? Yes/N

Performed by: Mike Dey MJ
Title: Mgr. Dept. 2

Approved by:

Date: 3/11/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1000.9	0.9	51	999.9	-0.1
2	1000.8	0.8	52	999.9	-0.1
3	1000.6	0.6	53	999.7	-0.3
4	1000.8	0.8	54	999.9	-0.1
5	1000.8	0.8	55	999.9	-0.1
6	1000.6	0.6	56	999.9	-0.1
7	1000.9	0.9	57	1000.0	0.0
8	1000.9	0.9	58	1000.0	0.0
9	1000.9	0.9	59	1000.0	0.0
10	1001.1	1.1	60	1000.2	0.2
11	1000.6	0.6	61	1000.6	0.6
12	1000.2	0.2	62	1000.2	0.2
13	1000.2	0.2	63	1000.2	0.2
14	1000.4	0.4	64	1000.2	0.2
15	1000.2	0.2	65	1000.0	0.0
16	1000.2	0.2	66	1000.2	0.2
17	1000.4	0.4	67	1000.4	0.4
18	1000.4	0.4	68	1000.4	0.4
19	1000.6	0.6	69	1000.6	0.6
20	1000.8	0.8	70	1000.8	0.8
21	1000.6	0.6	71	1000.0	0.0
22	1000.2	0.2	72	1000.0	0.0
23	1000.4	0.4	73	1000.0	0.0
24	1000.6	0.6	74	1000.0	0.0
25	1000.4	0.4	75	1000.0	0.0
26	1000.6	0.6	76	1000.0	0.0
27	1000.6	0.6	77	1000.0	0.0
28	1000.6	0.6	78	1000.0	0.0
29	1000.6	0.6	79	1000.2	0.2
30	1000.9	0.9	80	1000.6	0.6
31	1000.6	0.6	81	1000.0	0.0
32	1000.2	0.2	82	1000.0	0.0
33	1000.4	0.4	83	1000.0	0.0
34	1000.4	0.4	84	1000.0	0.0
35	1000.2	0.2	85	1000.0	0.0
36	1000.2	0.2	86	1000.0	0.0
37	1000.4	0.4	87	1000.2	0.2
38	1000.2	0.2	88	1000.2	0.2
39	1000.4	0.4	89	1000.2	0.2
40	1000.8	0.8	90	1000.6	0.6
41	1000.2	0.2	91	1000.0	0.0
42	1000.0	0.0	92	999.7	-0.3
43	1000.0	0.0	93	999.7	-0.3
44	1000.0	0.0	94	1000.0	0.0
45	1000.0	0.0	95	1000.0	0.0
46	1000.0	0.0	96	1000.0	0.0
47	1000.0	0.2	97	1000.0	0.0
48	1000.2	0.2	98	1000.0	0.0
1107.50	1000.2	0.2	99	1000.0	0.2
49 50	1000.2	0.6	100	1000.2	0.4

Lower

Upper

Range of 2000°F Readings: +1.1/-0.3

Allowable limits

997.7

1002.3 (±2.3)

Serial No.: 99-LE-004

Calibrator Used: T-207318

Temperature Setting (°F): 2000.0

Within specs?

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by:

Title:

Date: 3/11/05

hannel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	2000.8	0.8	51	1999.9	-0.1
2	2000.8	0.8	52	1999.9	-0.1
3	2000.8	0.8	53	1999.9	-0.1
4	2000.7	0.7	54	1999.9	-0.1
5	2000.8	0.8	55	1999.9	-0.1
6	2000.8	0.8	56	1999.9	-0.1
7	2000.7	0.7	57	1999.9	-0.1
8	2000.8	0.8	58	2000.1	0.1
9	2001.0	1.0	59	2000.1	0.1
10	2001.2	1.2	60	2000.3	0.3
11	2000.7	0.7	61	2000.7	0.7
12	2000.5	0.5	62	2000.3	0.3
13	2000.5	0.5	63	2000.3	0.3
14	2000.3	0.3	64	2000.3	0.3
15	2000.5	0.5	65	2000.3	0.3
16	2000.7	0.7	66	2000.3	0.3
17	2000.5	0.5	67	2000.3	0.3
18	2000.7	0.7	68	2000.5	0.5
19	2000.7	0.7	69	2000.5	0.5
20	2000.8	0.8	70	2001.0	1.0
21	2000.7	0.7	71	2000.7	0.7
22	2000.7	0.7	72	2000.5	0.5
23	2000.7	0.7	73	2000.3	0.3
24	2000.7	0.7	74	2000.5	0.5
25	2000.7	0.7	75	2000.5	0.5
26	2000.7	0.7	76	2000.5	0.5
27	2000.7	0.7	77	2000.5	0.5
28	2000.7	0.7	78	2000.7	0.7
29	2001.0	1.0	79	2000.7	0.7
30	2001.0	1.0	80	2000.8	0.8
31	2000.5	0.5	81	1999.9	-0.1
32	2000.3	0.3	82	1999.8	-0.2
33	2000.3	0.3	83	1999.8	-0.2
34	2000.3	0.3	84	1999.8	-0.2
35	2000.5	0.5	85	1999.9	-0.1
36	2000.5	0.5	86	1999.9	-0.1
37	2000.3	0.3	87	1999.9	-0.1
38	2000.3	0.3	88	1999.9	-0.1
39	2000.7	0.7	89	2000.1	0.1
40	2000.7	0.7	90	2000.3	0.3
41	2000.3	0.3	91	1999.9	-0.1
42	2000.1	0.1	92	1999.9	-0.1
43	2000.1	0.1	93	1999.9	-0.1
44	1999.9	-0.1	94	1999.9	-0.1
45	2000.1	0.1	95	1999.9	-0.1
46	2000.3	0.3	96	2000.1	0.1
47	2000.3	0.3	97	2000.1	0.1
48	2000.3	0.3	98	2000.3	0.3
49	2000.5	0.5	99	2000.5	0.5
50	2000.7	0.7	100	2000.7	0.7

Lower

Upper

Range of 2000°F Readings: +1.2/-0.2

Allowable limits

1997.2

2002.8 (±2.8)

Omega Point Laboratories, Inc.

16015 Shady Falls Road Elmendorf, Texas 78112 800-966-5253 FAX 210-635-8101

Certificate of Verification

Certification No.:

92146

Verification Date:

03/11/2005

Reverification Date:

09/11/2005

Manufacturer:

Yokogawa

Model No.:

100 Channel DAU

Serial No.:

99LE006

Equipment Description: 100 Channel Data Acquisition System with

YOKOGAWA Darwin Series

Calibration Sources:

TEGAM Model 840-A, SN: T-207318.

Calibration due 05/03/2005.

PERFORMANCE:

Temperature:	Temperature:	Temperature:	Temperature:	Temperature:	Temperature:
(75°F)	(150°F)	(300°F)	(400°F)	(1000°F)	(2000°F)
+1.6/-0	+1.3/-0.3	+1.3/-0.3	+1.4/-0.3	+1.3/-0.3	+1.7/-0.6

Verification Performed by:

Manager of Fire Resistance

Verification Approved by:

Deg Priest

President/Chief Technical Officer



Serial No.: 99-LE-006

Calibrator Used: T-207318 Performed by: Mike Dey Mi

Temperature Setting (°F): ____75.0

Approved	by:	DP
	Title:	

Date: 3/11/05

Title: Mgr. Dept. 2

Within specs?

Channel No. Reading (°F) Channel No. Reading (°F) 1.5 0.2 51 2 76.3 1.3 52 75.6 0.6 3 76.6 1.6 53 75.6 0.6 4 75.9 0.9 54 75.0 0.0 75.7 75.0 56 6 75.7 75.0 75.7 0.7 57 75.0 0.0 8 75.7 0.7 58 75.0 0.0 9 75.9 0.9 59 75.0 0.0 60 75.2 0.2 10 76.3 1.3 61 75.7 0.7 11 75.7 0.7 12 76.3 62 75.9 13 76.5 1.5 63 75.9 0.7 0.6 14 64 75.6 75.7 15 75.7 0.7 65 75.6 0.6 16 75.6 0.6 66 75.6 0.6 17 75.6 0.6 67 75.6 0.6 68 75.6 0.6 18 75.6 0.6 19 75.7 0.7 69 75.7 0.7 75.9 70 75.9 0.9 75.9 75.7 0.7 21 71 0.7 72 1.3 22 75.7 76.3 73 1.1 23 76.1 1.1 76.1 24 75.7 0.7 74 75.4 0.4 75.6 0.6 25 75.4 0.4 75 0.4 76 75.4 0.4 75.4 26 27 75.6 77 75.6 75.6 78 75.6 79 0.4 29 75.7 75.4 0.7 30 75.7 0.7 80 75.7 31 75.7 0.7 81 75.2 0.2 32 76.3 1.3 82 75.6 0.6 0.6 33 76.3 1.3 83 75.6 75.6 0.6 84 75.2 0.2 34 35 75.4 0.4 85 75.2 75.2 0.2 36 75.4 86 75.2 0.2 87 37 75.4 0.2 38 75.4 0.4 88 75.2 39 75.6 0.6 89 75.2 0.2 90 40 75.7 0.7 75.6 0.6 41 0.9 91 75.4 0.4 75.9 42 76.5 1.5 92 75.7 0.7 43 76.5 93 75.7 0.4 94 44 75.7 75.4 0.7 95 75.7 0.7 45 75.7 46 75.7 0.7 96 75.6 0.6 47 75.7 0.7 97 75.7 0.7 98 0.7 48 75.6 0.6 75.7 49 99 0.7 75.7 0.7 75.7 0.7 50 76.1 1.1 100 75.7

Lower Upper

73.2

Allowable limits

76.8 (±1.8)

Serial No.: 99-LE-006

Within specs? Performed by: Mike Dey

Calibrator Used: T-207318

Title: Mgr. Dept. 2

Approved by:

Date: 3/11/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	151.3	1.3	51	150.1	0.1
2	151.3	1.3	52	150.3	0.3
3	151.3	1.3	53	150.3	0.3
4	150.6	0.6	54	149.9	-0.1
5	150.6	0.6	55	149.9	-0.1
6	150.6	0.6	56	149.7	-0.3
7	150.6	0.6	57	149.7	-0.3
8	150.8	0.8	58	149.9	-0.1
9	150.8	0.8	59	149.9	-0.1
10	151.0	1.0	60	150.1	0.1
11	151.0	1.0	61	150.8	0.8
12	151.3	1.3	62	150.8	0.8
13	151.3	1.3	63	150.8	0.8
14	150.8	0.8	64	150.4	0.4
15	150.8	0.8	65	150.4	0.4
16	150.6	0.6	66	150.4	0.4
17	150.6	0.6	67	150.4	0.4
18	150.8	0.8	68	150.4	0.4
19	150.8	0.8	69	150.4	0.4
20	151.0	1.0	70	150.8	0.8
21	150.6	0.6	71	150.8	0.8
22	151.0	1.0	72	151.0	1.0
23	151.0	1.0	73	151.0	1.0
24	150.3	0.3	74	150.6	0.6
25	150.4	0.4	75	150.4	0.4
26	150.4	0.4	76	150.6	0.6
27	150.3	0.3	77	150.4	0.4
28	150.4	0.4	78	150.6	0.6
29	150.6	0.6	79	150.4	0.4
30	150.8	0.8	80	150.8	0.8
31	150.6	0.6	81	150.3	0.3
32	151.0	1.0	82	150.4	0.4
33	151.0	1.0	83	150.3	0.3
34	150.4	0.4	84	150.1	0.1
35	150.3	0.3	85	150.1	0.1
36	150.4	0.4	86	150.1	0.1
37	150.3	0.3	87	150.1	0.1
38	150.3	0.3	88	150.3	0.3
39	150.6	0.6	89	150.3	0.3
40	150.6	0.6	90	150.4	0.4
41	150.8	0.8	91	150.4	0.4
42	151.3	1.3	92	150.4	0.4
43	151.3	1.3	93	150.6	0.6
44	150.6	0.6	94	150.4	0.4
45	150.6	0.6	95	150.4	0.4
46	150.4	0.4	96	150.4	0.4
47	150.4	0.4	97	150.6	0.6
	150.4	0.6	98	150.6	0.6
48	150.6	0.6	99	150.6	0.6
50	150.8	0.8	100	150.8	0.8

Lower

Upper

Range of 150°F Readings: +1.3/-0.3

Allowable limits

148.2

151.8 (±1.8)

Serial No.: 99-LE-006

Calibrator Used: T-207318

Temperature Setting (°F): 300.0

Mithin	enoce?
VVIUIIII	specs?

Performed by: Mike Dey

Title: Mgr. Dept. 2

Approved by: Title:

Date: 3/11/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	301.1	1.1	51	300.0	0.0
2	301.3	1.3	52	300.2	0.2
3	301.3	1.3	53	300.2	0.2
4	300.7	0.7	54	299.7	-0.3
5	300.2	0.2	55	299.7	-0.3
6	300.2	0.2	56	299.8	-0.2
7	300.6	0.6	57	299.7	-0.3
8	300.6	0.6	58	299.8	-0.2
9	300.6	0.6	59	300.0	0.0
10	300.9	0.9	60	300.0	0.0
11	300.7	0.7	61	300.6	0.6
12	301.1	1.1	62	300.7	0.7
13	301.3	1.3	63	300.7	0.7
14	300.6	0.6	64	300.4	0.4
15	300.4	0.4	65	300.2	0.2
16	300.4	0.4	66	300.4	0.4
17	300.2	0.2	67	300.2	0.2
18	300.4	0.4	68	300.6	0.6
19	300.4	0.4	69	300.6	0.6
20	300.7	0.7	70	300.7	0.7
21	300.4	0.4	71	300.6	0.6
22	300.9	0.9	72	301.1	1.1
23	300.7	0.7	73	300.9	0.9
24	300.2	0.2	74	300.2	0.2
25	300.2	0.2	75	300.4	0.4
26	300.2	0.2	76	300.2	0.2
27	300.2	0.2	77	300.2	0.2
28	300.2	0.2	78	300.4	0.4
29	300.2	0.2	79	300.4	0.4
30	300.6	0.6	80	300.6	0.6
31	300.7	0.7	81	300.0	0.0
32	300.7	0.9	82	300.2	0.2
	300.9	0.9	83	300.2	0.2
33 34	300.4	0.4	84	300.0	0.0
	300.4	0.2	85	300.0	0.0
35	300.2	0.2	86	299.8	-0.2
36 37	300.2	0.2	87	300.0	0.0
	300.2	0.2	88	300.0	0.0
38	300.2	0.2	89	300.0	0.0
39	300.2	0.6	90	300.2	0.2
40	300.6	0.7	91	300.2	0.2
41		0.9	92	300.6	0.6
42	300.9		93	300.6	0.6
43	301.1	1.1	94	300.2	0.2
44	300.7	0.7		300.4	0.4
45	300.2	0.2	95	300.4	0.4
46	300.4	0.4	96	_	0.6
47	300.4	0.4	97	300.6	0.7
48	300.4	0.4	98	300.7	0.7
49	300.6	0.6	99	300.7	
50	300.7	0.7	100	300.7	0.7

Lower

Upper

Range of 300°F Readings: +1.3/-0.3

Allowable limits

298.1

301.9 (±1.9)

Serial No.: 99-LE-006

Calibrator Used: T-207318

Performed by: Mike Dey
Title: Mgr. Dept. 2

Approved by: Title:

Within specs? Yes/No

Date: 3/11/05

Temperature	Setting	(°F):	400.0

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	401.0	1.0	51	399.9	-0.1
2	401.4	1.4	52	400.3	0.3
3	401.4	1.4	53	400.3	0.3
4	400.6	0.6	54	399.7	-0.3
5	400.3	0.3	55	399.7	-0.3
6	400.5	0.5	56	399.7	-0.3
7	400.5	0.5	57	399.7	-0.3
8	400.5	0.5	58	399.7	-0.3
9	400.6	0.6	59	399.7	-0.3
10	400.8	0.8	60	399.9	-0.1
11	400.8	0.8	61	400.8	0.8
12	401.4	1.4	62	401.0	1.0
13	401.4	1.4	63	400.8	0.8
14	400.6	0.6	64	400.5	0.5
15	400.6	0.6	65	400.5	0.5
16	400.6	0.6	66	400.5	0.5
17	400.5	0.5	67	400.3	0.3
18	400.5	0.5	68	400.5	0.5
19	400.8	0.8	69	400.5	0.5
20	400.8	0.8	70	401.0	1.0
21	400.6	0.6	71	400.6	0.6
22	400.8	0.8	72	400.8	0.8
23	400.8	0.8	73	400.8	0.8
24	400.3	0.3	74	400.3	0.3
25	400.3	0.3	75	400.3	0.3
26	400.3	0.3	76	400.3	0.3
27	400.3	0.3	77	400.3	0.3
28	400.3	0.3	78	400.3	0.3
29	400.5	0.5	79	400.3	0.3
30	400.6	0.6	80	400.6	0.6
31	400.5	0.5	81	400.1	0.1
32	401.0	1.0	82	400.3	0.3
33	401.0	1.0	83	400.3	0.3
34	400.3	0.3	84	400.1	0.1
35	400.3	0.3	85	399.9	-0.1
36	400.3	0.3	86	400.1	0.1
37	400.3	0.3	87	399.9	-0.1
38	400.3	0.3	88	399.9	-0.1
39	400.3	0.3	89	400.3	0.3
40	400.5	0.5	90	400.3	0.3
41	400.5	0.5	91	400.3	0.3
42	401.2	1.2	92	400.5	0.5
43	401.4	1.4	93	400.5	0.5
44	400.5	0.5	94	400.3	0.3
45	400.5	0.5	95	400.5	0.5
46	400.5	0.5	96	400.5	0.5
47	400.3	0.3	97	400.5	0.5
48	400.3	0.3	98	400.6	0.6
49	400.5	0.5	99	400.6	0.6
50	400.8	0.8	100	400.5	0.5

Lower Upper 402.0 (±2.0) 398.0

Serial No.: 99-LE-006

Calibrator Used: T-207318

Performed by: Mike Dey Mgr. Dept. 2

Date: 3/11/05

Within specs? Yes/No

Temperature Setting (°F): 1000.0 Approved by:

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	1000.9	0.9	51	1000.0	0.0
2	1000.9	0.9	52	1000.2	0.2
3	1000.9	0.9	53	1000.2	0.2
4	1000.4	0.4	54	1000.0	0.0
5	1000.4	0.4	55	999.7	-0.3
6	1000.2	0.2	56	999.7	-0.3
7	1000.2	0.2	57	999.7	-0.3
8	1000.4	0.4	58	999.9	-0.1
9	1000.4	0.4	59	999.7	-0.3
10	1000.6	0.6	60	1000.0	0.0
11	1000.6	0.6	61	1000.6	0.6
12	1000.9	0.9	62	1000.7	0.7
13	1000.8	0.8	63	1000.9	0.9
14	1000.4	0.4	64	1000.4	0.4
15	1000.2	0.2	65	1000.0	0.0
16	1000.2	0.2	66	1000.2	0.2
17	1000.4	0.4	67	1000.4	0.4
18	1000.4	0.4	68	1000.2	0.2
19	1000.4	0.4	69	1000.4	0.4
20	1000.6	0.6	70	1000.8	0.8
21	1000.8	0.8	71	1000.6	0.6
22	1001.3	1.3	72	1000.8	0.8
23	1001.1	1.1	73	1000.8	0.8
24	1000.6	0.6	74	1000.2	0.2
25	1000.6	0.6	75	1000.0	0.0
26	1000.6	0.6	76	1000.0	0.0
27	1000.6	0.6	77	1000.0	0.0
28	1000.6	0.6	78	1000.0	0.0
29	1000.8	0.8	79	1000.2	0.2
30	1000.9	0.9	80	1000.4	0.4
31	1000.6	0.6	81	999.9	-0.1
32	1000.8	0.8	82	1000.0	0.0
33	1000.6	0.6	83	1000.0	0.0
34	1000.2	0.2	84	999.7	-0.3
35	1000.2	0.2	85	999.9	-0.1
36	1000.0	0.0	86	999.7	-0.3
37	1000.0	0.0	87	999.7	-0.3
38	1000.2	0.2	88	999.9	-0.1
39	1000.2	0.2	89	999.9	-0.1
40	1000.4	0.4	90	1000.0	0.0
41	1000.6	0.6	91	1000.4	0.4
42	1000.9	0.9	92	1000.4	0.4
43	1000.9	0.9	93	1000.6	0.6
44	1000.2	0.2	94	1000.4	0.4
45	1000.2	0.2	95	1000.4	0.4
46	1000.0		96	1000.6	0.6
47	1000.2	1 10 10 10 10 10 10	97	1000.6	0.6
48	1000.2		98	1000.6	0.6
49	1000.0		99	1000.6	0.6
50	1000.6	0.6	100	1000.6	0.6

Upper Lower 997.7 1002.3 (±2.3)

Serial No.: 99-LE-006

Calibrator Used: T-207318

Temperature Setting (°F): 2000.0

Mithin	specs?	Yes/No
AAICUIII	specs:	163/140

Title:

Performed by: Mike Dey Title: Mgr. Dept. 2

Approved by:

Date: 3/11/05

Channel No.	Reading (°F)	+/-	Channel No.	Reading (°F)	+/-
1	2000.1	0.1	51	1999.9	-0.1
2	2000.3	0.3	52	2000.5	0.5
3	2000.3	0.3	53	2000.5	0.5
4	1999.8	-0.2	54	1999.9	-0.1
5	1999.4	-0.6	55	1999.9	-0.1
6	1999.6	-0.4	56	1999.9	-0.1
7	1999.6	-0.4	57	1999.9	-0.1
8	1999.6	-0.4	58	1999.9	-0.1
9	1999.9	-0.1	59	1999.9	-0.1
10	2000.1	0.1	60	2000.1	0.1
11	2000.7	0.7	61	2000.7	0.7
12	2001.0	1.0	62	2000.6	0.6
13	2001.0	1.0	63	2000.8	0.8
14	2000.3	0.3	64	2000.3	0.3
15	2000.3	0.3	65	2000.3	0.3
16	2000.3	0.3	66	2000.5	0.5
17	2000.3	0.3	67	2000.1	0.1
18	2000.3	0.3	68	2000.3	0.3
19	2000.5	0.5	69	2000.5	0.5
20	2000.7	0.7	70	2000.7	0.7
21	2001.6	1.6	71	2000.3	0.3
22	2001.7	1.7	72	2000.7	0.7
23	2001.7	1.7	73	2000.5	0.5
24	2001.2	1.2	74	1999.9	-0.1
25	2001.0	1.0	75	1999.9	-0.1
26	2001.2	1.2	76	1999.9	-0.1
27	2001.2	1.2	77	1999.9	-0.1
28	2001.2	1.2	78	1999.9	-0.1
29	2001.4	1.4	79	1999.9	-0.1
30	2001.7	1.7	80	2000.1	0.1
31	2000.3	0.3	81	1999.9	-0.1
32	2000.7	0.7	82	1999.9	-0.1
33	2000.8	0.8	83	2000.1	0.1
34	2000.1	0.1	84	1999.6	-0.4
35	1999.9	-0.1	85	1999.6	-0.4
36	1999.9	-0.1	86	1999.8	-0.2
37	1999.9	-0.1	87	1999.6	-0.4
38	1999.9	-0.1	88	1999.8	-0.2
39	2000.1	0.1	89	1999.9	-0.1
40	2000.5	0.5	90	2000.1	0.1
41	2000.5	0.5	91	2000.7	0.7
42	2000.7	0.7	92	2000.7	0.7
43	2001.0	1.0	93	2000.7	0.7
44	2000.3	0.3	94	2000.7	0.7
45	2000.1	0.1	95	2000.7	0.7
46	2000.3	0.3	96	2000.7	0.7
47	2000.1	0.1	97	2000.8	0.8
48	1999.9	-0.1	98	2001.0	1.0
49	2000.3	0.3	99	2000.8	0.8
50	2000.5	0.5	100	2001.0	1.0

Lower

Upper

Range of 2000°F Readings: +1.7/-0.6 Allowable limits

1997.2

2002.8 (±2.8)

Q/A RECEIVING REPORT

CLIENT/PROJECT NAME NAMO (CO TOWN CLIENT/PROJECT NUMBER_ PROJECT LOCATION RECEIVED FROM

REPORT NUMBER 2435 DATE INSPECTED DATE RECEIVED. INSPECTED BY:

1						-			No.	6.0	CHEST HARM		-	- 11 WAL	POLITICAL PROPERTY.	-	-	
			DI	al	In	di	cat	Tor	, ,) (. 5	W:	013	2=	32	85		
1		REMARKS	w	as	D	lei	301	nd	1	es	ai	7	- 21	20,	Æ	ag	e A	36
1		REM	1	M 0	٨٨٨	8	0			1								')
()					7 7 7													
2		ect		· · · · · · · · · · · · · · · · · · ·	- Allander	a-sunciasa		TE POOR SOLE				Levisialista			- Carlo			*
	NOE	1 Reject																
	ACCEPTANCE	t Hol																
0 1 10	ACC	Accept Hold	\times		\times		×		×		X		\times		\times		×	
וואסו בי	CONTAINER	INTEGRITY	8		Good	-	3		Q		Q		QQ		3		Q	
			0		\$		9		Q		4		0		9		0	
-	SAFETY	N/A	2		っ		2		4		7		5		7		7	
					~ 入				7				_		4		_	
	D CERT.				_		>				>							
	CONID	N/N	>				>		>		>		>		>		>	
		a	~		8		0		2		991		6		8		0	
		I.D. NO.	2313		23138		市		98LEDO		2/6		76		465		5700109	
		=	6		5		99 LECO		99		013021466		34376		6024650		570	
		B.O.	D		Ø		Ø		Ø		0		0		Ø		8	ALC: HELDER
	QUANTITY	-	2		-				_				7		7		_	
	QUAI	Order Rec'd	ر						_						_		_	-
			0		0	-	9	-	0		0		8		A		0	
		P.O . NO.	143579		143570		357		357		143570 1		357		357		357	
		P.(7		14		14		4		4		14.		14		7	1.5
		7					prosept grassof		Preserve 143570		3		37		3		rote	
		ITEM DESCRIPTION	i		13		Prese	2	39	0	cut	8	2		740	21	H	
-		SCA	Se Se)	7	0	20) =	304)	john		200		9		THE	
		M DE) se		3		8		1 1		. X		3		£.	١	9	
Annual selections		E	2009 Weight	>	200 a Weight	0	120001-0		0-100ps		5" dial indication		0-1000 Ub. Irad Cell 143570		6" di gital calipar, 14357 P		dictal Multimoter 143570)
- Control			2		3		0		0		-50		0		-0		d.	





PURCHASE OPAGEP437

14357Q

Date: 04/19/2004

Page: 1 of 1

Order From:

SSC Lab Division

7715 Distribution Dr.

Little Rock

AR

72209

501-562-2900/888-278-9292

Deliver to:

Omega Point Laboratories, Inc

16015 Shady Falls Road

Elmendorf

TX

78112

(210) 635-8100

Vendor No:

Your Item Number Item Description	Our Reference	Qty Ordered	Units	Unit Cost	Extension
0-100psi Pressure Gage SN:99LE001	001	1.00	Each	\$45.00	\$45.00
0-100psi Pressure Gage SN: 98LE001	002	1.00	Each	\$75.00	\$75.00
Dial Indicator SN: 013021466	003	1.00	Each	\$20.00	\$20.00
Dial Indicator SN: 013232851 Calibration&Repair	004	1.00	Each	\$120.00	\$120.00
Load Cell 1k pound SN: 343765 Calibration & Repair	005	1.00	Each	\$175.00	\$175.00
Digital Multimeter SN: 5700109 Calibration & Repair	006	1.00	Each	\$100.00	\$100.00
Digital Caliper SN:6Q-2465-04	007	1.00	Each	\$70.00	\$70.00
200g Weight—SN: 23137	008	1.00	Each	\$10.00	\$10.00
200g Weight—SN: 23138	009	1.00	Each	\$10.00	\$10.00
CALIBRATION CERT. REQUIREMENTS 1. Statement of NIST traceability 2. NIST test or I.D. number 3. As Found 4. As Left Values	Uncertainties of calibration measurements	7. Calibration certificates must show accreditation to ISO/IEC 17025	Purchasing	ial Instructions g Specification Requirements oval 454	is for Qualit

Please Quote Purchase Order Number on all correspondence.

Special Instructions: Please include Certificate of Conformance to attached Specification Sheet and Calibration Data traceable to NIST.

Subtotal:

\$620.00

Freight: Tax Amount:

Total Value:

0.00

\$620.00

080



VENDOR PURCHASING SPECIFICATION AND

QUALITY ASSURANCE REQUIREMENTS

		Vendor: 55C Hab Divisu
		Purchase Order No. 14357 Q
this p	rocure	llowing Quality Assurance requirements shall be incorporated as conditions to ment when corresponding box is marked. Failure to comply with any specified may result in rejection and/or return of shipment at seller's expense.
1.0	QUAL	ITY PROGRAM
	X	Seller shall furnish all items on this Purchase Order in accordance with Quality Program approved by Buyer.
2.0	Qualit	y Verification
	When	additional quality verification activities are required as a condition to this rement, invoices will not be paid until satisfactory completion of such activities.
	X	Receiving Inspection- Buyer shall inspect items upon receipt to verify compliance with purchase order requirements. Rejected items shall be returned at seller's expense.
		Independent Laboratory Tests- Samples of materials furnished shall be tested independently for conformance to specification requirements prior to final acceptance. Rejected materials shall be returned at seller's expense.
	X	Document Review- Final acceptance shall be based on satisfactory review or required certifications and other supporting documents.
3.0	CERT	TIFICATIONS
	furnis not b	certifications are required as a condition to this procurement, the seller shall hone reproducible copy either with or prior to each shipment. Shipments will e accepted and invoices will not be paid until certifications are in buyer's ession.
		Certificate of Compliance/Conformance Required – Certification that materials and /or services comply with purchase order requirements. Certification shall reference purchase order number and traceability numbers (when applicable).
		Certified Test Report Required – Certification that material complies with applicable material specification (s) and the purchase order. Include actual results of required tests.



National Bureau of Standards. (NIST, Nat'l Inst. of Science & Technology). AUDITS/RIGHT OF ACCESS The buyer reserves the right to audit your facility to verify compliance wire purchase order, code and specification requirements with (10) days notice, Shipments shall only originate form facilities approved by the buyer. Buyer reserves the right to inspect any or all work included in this order is seller's facility with as early notice as practicable. IDENTIFICATION Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulation Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading are										
The buyer reserves the right to audit your facility to verify compliance wir purchase order, code and specification requirements with (10) days notice, Shipments shall only originate form facilities approved by the buyer. Buyer reserves the right to inspect any or all work included in this order is seller's facility with as early notice as practicable. IDENTIFICATION Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.		X	Certificate of Calibration Required - Certification shall be traceable to National Bureau of Standards. (NIST, Nat'l Inst. of Science & Technology).							
purchase order, code and specification requirements with (10) days notice, Shipments shall only originate form facilities approved by the buyer. Buyer reserves the right to inspect any or all work included in this order seller's facility with as early notice as practicable. IDENTIFICATION Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. Thidentification number shall be traceable to certifications and packing lists. OCFR,PART 21 The material, equipment and/or services to be furnished under this purchas order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading ar	4.0	AUDI	TS/RIGHT OF ACCESS							
Buyer reserves the right to inspect any or all work included in this order seller's facility with as early notice as practicable. 5.0 IDENTIFICATION Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) 7.0 PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.		X	The buyer reserves the right to audit your facility to verify compliance with purchase order, code and specification requirements with (10) days notice,							
seller's facility with as early notice as practicable. IDENTIFICATION Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchas order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwis prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading ar		X	Shipments shall only originate form facilities approved by the buyer.							
Seller shall identify each item with a unique traceability number by physic marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or otherwise prepared for shipment to prevent damage during handling and shippin wherever practical, equipment shall be palletized for ease of unloading and			Buyer reserves the right to inspect any or all work included in this order at seller's facility with as early notice as practicable.							
marking or tagging. Traceability numbers shall be traceable to certification and packing lists. Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or othe deleterious material. All materials and equipment shall be suitable crated, boxed or otherwis prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading ar	5.0	IDEN	TIFICATION							
identification number shall be traceable to certifications and packing lists. 10CFR,PART 21 The material, equipment and/or services to be furnished under this purchas order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shall be free from all foreign substance such as dirt, oil, grease or other deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and			Seller shall identify each item with a unique traceability number by physical marking or tagging. Traceability numbers shall be traceable to certifications and packing lists.							
The material, equipment and/or services to be furnished under this purchas order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) 7.0 PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shall be free from all foreign substance such as dirt, oil, grease or other deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.		X	Seller shall identify each container with a unique identification number. The identification number shall be traceable to certifications and packing lists.							
order are involved in the testing of basic components of a Nuclear Regulato Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance) 7.0 PACKING/SHIPPING All materials shall be packaged in air tight, moisture free containers and shad be free from all foreign substance such as dirt, oil, grease or otherwise deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.	6.0	10CF	10CFR,PART 21							
All materials shall be packaged in air tight, moisture free containers and shabe free from all foreign substance such as dirt, oil, grease or other deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.			The material, equipment and/or services to be furnished under this purchase order are involved in the testing of basic components of a Nuclear Regulatory Commission (NRC) licensed facility. Accordingly, the seller is subject to the provisions of 10 CFR, Part 21 (Reporting of Defects and Noncompliance)							
be free from all foreign substance such as dirt, oil, grease or otherwise deleterious material. All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading and shippin wherever practical.	7.0	PAC	KING/SHIPPING							
prepared for shipment to prevent damage during handling and shippin Wherever practical, equipment shall be palletized for ease of unloading ar		X	All materials shall be packaged in air tight, moisture free containers and shall be free from all foreign substance such as dirt, oil, grease or other deleterious material.							
purchase order number.			All materials and equipment shall be suitable crated, boxed or otherwise prepared for shipment to prevent damage during handling and shipping. Wherever practical, equipment shall be palletized for ease of unloading and storage at destination. Each container shall be clearly marked with buyer's purchase order number.							
QUALITY ASSURANCE APPROVAL DATE 4/19/04	QUA	LITY A	SSURANCE APPROVAL DATE 4/19/04							



SSC LAB DIVISION a Division of System Scale Corporation

CERTIFICATE NO:

Page 1 of 1

36283-0003



Cert. #1754.01 Calibration Laboratory ISO / IEC / 17025

CERTIFICATE OF CALIBRATION

SSC LAB DIVISION certifies that this instrument conforms to original manufacturers specifications or to tolerances indicated below and has been calibrated using standards with accuracies traceable to a National Measurement Institute, or to accepted values of natural physical constants, or have been derived by ratio techniques. This certificate complies with ISO/IEC 17025 & ANSI Z540. Unless otherwise stated, the M& TE for which this certificate is issued, based on interpretation of data, was found to meet the required specification. Reported uncertainty represents expanded uncertainty at approximately 95% confidence level, coverage factor of k=2.


Customer:	OMEGA POINT LAB.	Date Received:	4/21/04	
Location:	16015 SHADY FALLS RD.	Date of Issue/Calibration: 04/22/2004		
	ELMENDORF TX 78112	Next Calibration Due:	04/22/2005	
P.O. #:	14357Q	Metrologist:	Sean Rainey	
Manufacturer:	McDANIEL CONTROLS INC.	Model:	316SS	
Nomenclature:	GAGE- PRESSURE	Serial Number:	99LE001	
Range:	0-100 PSI	Equipment ID:	99LE001	
Calibration Data		Temp 68°F Hum	idity 38%	

Calibration Accuracy: ± 2.5% FULL SCALE

Note: if the AS LEFT column is blank, no adjustments were required.

Note: Many factors may cause out of calibration condition prior to due date. The Calibration interval has been specified by the Customer. Current procedures and methods utilized by SSC Lab Division are approved by the Customer.

APPLIED 25 LBS	<u>AS FOUND</u> 25.78	AS LEFT 25.78	UNCERTAINTY 2.9	PROCEDURE # NA17-20MP-06
50 LBS	51.24	51.24	2.9	
75 LBS	76.38	76.38	2.9	
100 LBS	101.72	101.72	2.9	
STANDARDS(S	S) USED			4.32
<u>Identification</u>		Calibration	Expiration	Traceability
Number	Description	<u>Date</u>	<u>Date</u>	Number
SSC30LD029	CALIBRATOR- PRESSURE	7/30/2003	7/30/2004	33426-0044
SSC30LD048	TRANSDUCER- PRESSURE	8/11/2003	8/11/2004	1000154760



Gary Mc Court

Gary McCourt Chief Metrology Engineer

Q/A RECEIVING REPORT

CLIENT/PROJECT NAME DIME CO FOLLY HALL
CLIENT/PROJECT NUMBER OPC EQUILORMEN
RECEIVED FROM ON OMEGA Point Labs

Γ			R	200		10/	1) :	3 K		M	9/2	RI	0#2	470	21	Pa	ige	44 heg	1
	OLIVION	מאחא	SA	200														56	
	MIG	ואוםרו	ar		DI	25	65	6	58	a	M	d	Ot	54	05	106	0	,	
			F	0.	. (1	08	7	pl	e	to		Alexandra de la compansión de la compans	V 2. 12.	25,035		. I ever-			
	3	Reject										,							
	ACCEPTANCE	Accept Hold																	
		Accep	\sim																
CONTAINE	INTEGRITY		Cod																
SAFETY	RELATED	NV	Z																
	REC'D		>																
CON'tD	MATL	N/L	>																
	I.D. NO.		KK-FB/FB-24	D															
2		- 1	D	/															
EIFIAALIO	COANTIL	Order Rec'd B.O	15, 18,						1		+								
	P.O. NO.	寸	145610																
	ITEM DESCRIPTION		drenglass.	Telline	,														





PURCHASE OF AGE 442

145610

Date: 09/16/2004

Page: 1 of 1

Order From: PMC

680 Hayward Street

Manchester

03103

603-622-3500

Deliver to: Omega Point Laboratories, Inc

16015 Shady Falls Road

Elmendorf

TX

78112

(210) 635-8100

Vendor No: 0024

Your Item Number Item Description	Our Reference	Qty Ordered	Units	Unit Cost	Extension
Fiberglass TC Wire KK-FB/FB-24	001	15,000	Feet	\$218.00	\$3270.00
Calibration Services	002	1.00	Each	\$207.00	\$207.00

Received 3,140 feet 9-27-04 8

"See Special Instructions Regarding Purchasing Specifications for Quality

Assurance Requirements."

QA Approval_ TO Date

Please Quote Purchase Order Number on all correspondence.

Special Instructions: Please include Certificate of Conformance to attached Specification Sheet and Calibration Data traceable to NIST.

Subtotal: Freight:

Tax Amount: Total Value:

\$3477.00 0.00 0.00

\$3477.00

OMEGA POINT LABORATORIES MATERIAL PURCHASING SPECIFICATIONS

SPECIFICATIO	N NUMBER:	MS-14561	2-0PL
VENDOR:		PMC Corporati	on
ITEM NO.	VENDOR PROD	DUCT NUMBER F	PRODUCT DESCRIPTION
And wouldn't by Andrews	KK-TA/TA-24	<u>I</u>	eflon Coated Thermocouple Wire
1.	KK-FB/FB-24	E	iberglas Braided Thermocouple Wire
	KK-TE/TE-24	<u>E</u>	EP Insulated Thermocouple Wire
below: TEST		DESCRIPTION '	SPECIFICATION RANGES MIN MAX.
ASTM E220-	96 Std. Te	est Method for Calibration o	of Temp. Range +32°F to +545°F
MOTIVI ELLO	Thermo	ocouples by Comparison	Special Limits of Error ±2% °F
	(Chrom	nel/Alumel wire alloy)	Temp. Range +545°F to +2300°F Special Limits of Error ± .4%
ASTM E220-		est Method for Calibration o occuples by Comparison	of Temp. Range -85°F to +270°F Special Limits of Error ±.9%°F
	(Сорре	er/Constantan wire alloy)	Temp. Range +270°F to +660°F Special Limits of Error ±.4%

QUALITY ASSURANCE REQUIREMENTS

1.0 QUALITY PROGRAM

Seller shall furnish this item in accordance with Quality Program approved by Omega Point Laboratories. Material specified herein is to be produced and tested in accordance with vendor quality standards, methods, guidelines and manufacturing instructions as defined in that Quality Program.

2.0 QUALITY VERIFICATION

<u>Receiving Inspection</u> - Buyer shall inspect items upon receipt to verify compliance with purchase order requirements. Rejected items shall be returned at seller's expense.

<u>Document Review</u> - Final acceptance shall be based on satisfactory review of required certifications and/or supporting documents.

3.0 CERTIFICATIONS

- Certification that supplied materials comply with this material specification and listing Critical Characteristics shall be provided. This certificates shall reference Omega Point Labs purchase order number and specification number for all material furnished under this specification. This Certification shall be signed by the appropriate vendor representative.
- 3.2 The material furnished under this specification shall be a product that complies with the following:
 - 3.2.1 Has been tested and passed all tests specified herein.
 - 3.2.2 Manufacturing methods for this material have not changed. Vendor will advise Omega Point in writing of any changes in the manufacturing prior to material manufacture.
 - 3.2.3 Raw materials used in the manufacture of this material meet Vendor specifications.

4.0 AUDITS/RIGHTS OF ACCESS

Omega Point Labs reserves the right to audit your facility to verify compliance with the purchase order and specification requirements with a minimum ten (10) day notice.

5.0 IDENTIFICATION

Seller shall identify each item with a unique traceability number by physical marking or tagging. These identification numbers shall be traceable to certifications and packing lists.

6.0 PACKING/SHIPPING

All materials shall be packaged in air tight, moisture free containers and shall be free of foreign substances such as dirt, oil, grease or other deleterious materials.

All materials shall be suitably crated, boxed or otherwise prepared for shipment to prevent damage during handling and shipping.

QUALITY ASSURANCE APPROVAL:

Title (VA A)

Date 9-16-04

AVL Verification

Class: A



PMC A DIVISION OF ROCKBESTOS-SURPRENANT CABLE COPPARE 445 680 HAYWARD STREET, MANCHESTER, NH 03103 (603) 622-3500 SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY FAX (800) 639-5701

CERTIFICATE OF CALIBRATION SPOOL # 00565655

TO:

OMEGA POINT LABS, INC. 16015 SHADY FALLS ROAD ELMENDORF, TX 78112

USA

Date: 10/16/04 Cust PO#: 14561Q JOB # PSO067407-3

CALIBRATION RESULTS ARE TRACEABLE TO THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) AND MEET SPECIAL LIMITS DEVIATION TOLERANCES AS DEFINED IN ISA MC96.1 (FORMERLY ANSI) AND ASTM E 230-03. MS-14561Q-OPL.

TEST RESULTS FOR:

PMC P/N: KK-FB/FB-24

Total Footage:

1520'

Test Temperature (°F)	Inside End	Outside End
200°	-1.3	-0.8
400°	-1.2	-1.7
600°	-2.0	-1.2
800°	-2.0	-1.5
1000°	+0.9	+1.4

Calibration Certhicals Acceptance liem Flor Sass SN 00565655 NIST Traceability Adequate As Found / As left Values QA 4 Calibration Date Sufficient Eng. Tolerance Range Adequate CA QA10-25-68 Date of Review Eng. Dept Mgr. OPL QA/QC Dept

REPORTED RESULTS ARE DEVIATIONS FROM TEST TEMPERATURES. FOR CORRECTION FACTORS REVERSE THE SIGNS.

THE MATERIAL REFERENCED ABOVE HAS BEEN CALIBRATED UTILIZING TECHNIQUES CONSISTENT WITH THE GUIDELINES SET FORTH IN ANSI Z540-1 AND ASTM E-220-02. THIS IS TO CERTIFY THE MATERIAL FURNISHED ON THIS SHIPMENT ARE IN CONFORMANCE WITH THE REQUIREMENTS, SPECIFICATIONS, AND DRAWINGS OF THE ABOVE REFERENCED CUSTOMER PURCHASE ORDER. INSPECTION AND TEST RECORDS ARE ON FILE AND AVAILABLE FOR CUSTOMER REVIEW.

SECONDARY STANDARD THERMOCOUPLE: TYPE K

REEL # POS LEG: 00534834 REEL # NEG LEG: 00534833 CALIBRATION DATE: 3/17/00

EDC 100RC SERIAL # 15075

(SINGLE USE THERMOCOUPLE FROM

263094B&D

NIST # 811/267966-03 DUE: 12/17/2005

NIST #: 263094C&A

CALIBRATED REEL)

TYPE T STANDARD REEL # 25926 & 26369 NIST # 258779B

DIGITAL VOLT METER

MODEL: KAYE INSTRUMENTS: X1525S

SERIAL # 306172

CALIBRATION DUE DATE: 01/30/2005

ICE POINT THERMOCOUPLE REFERENCE MODEL, KAYE INSTRUMENTS: K-170-SP

SERIAL #: 306179

CALIBRATION DUE DATE: 01/30/2005

QUALITY ASSURANCE TECHNICIAN



PMC A DIVISION OF ROCKBESTOS-SURPRENANT CABLE COPPAGE 446
680 HAYWARD STREET, MANCHESTER, NH 03103 (603) 622-3500
SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY FAX (800) 639-5701

CERTIFICATE OF CALIBRATION SPOOL # 00565656

TO:

OMEGA POINT LABS, INC. 16015 SHADY FALLS ROAD ELMENDORF, TX 78112

USA

Date: 10/16/04 Cust PO#: 14561Q JOB # PSO067407-3

CALIBRATION RESULTS ARE TRACEABLE TO THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) AND MEET SPECIAL LIMITS DEVIATION TOLERANCES AS DEFINED IN ISA MC96.1 (FORMERLY ANSI) AND ASTM E 230-03. MS-14561Q-OPL.

TEST RESULTS FOR:

PMC P/N: KK-FB/FB-24

Total Footage:

1555'

Test Temperature (°F)	Inside End	Outside End
200°	-1.4	-0.9
400°	-1.2	-1.7
600°	-2.0	-1.7
800°	-2.0	-1.6
1000°	+0.9	+1.8

Calibration Certificate Accordance

Item Struck Stan CUUITO

SN 005 6 5066

NIST Traceability Adequate CA Fing Find Calibration Date Sufficient CA Fing Find Calibration Date Sufficient CA Fing Find Calibration Date of Review CAID Sept Fing 19/24/00

OPL CAYOC Dept Find Dept Mgs

REPORTED RESULTS ARE DEVIATIONS FROM TEST TEMPERATURES. FOR CORRECTION FACTORS REVERSE THE SIGNS.

THE MATERIAL REFERENCED ABOVE HAS BEEN CALIBRATED UTILIZING TECHNIQUES CONSISTENT WITH THE GUIDELINES SET FORTH IN ANSI Z540-1 AND ASTM E-220-02. THIS IS TO CERTIFY THE MATERIAL FURNISHED ON THIS SHIPMENT ARE IN CONFORMANCE WITH THE REQUIREMENTS, SPECIFICATIONS, AND DRAWINGS OF THE ABOVE REFERENCED CUSTOMER PURCHASE ORDER. INSPECTION AND TEST RECORDS ARE ON FILE AND AVAILABLE FOR CUSTOMER REVIEW.

SECONDARY STANDARD THERMOCOUPLE: TYPE K

REEL # POS LEG: 00534834 REEL # NEG LEG: 00534833

CALIBRATION DATE: 3/17/00

DIGITAL VOLT METER

MODEL: KAYE INSTRUMENTS: X1525S

SERIAL # 306172

CALIBRATION DUE DATE: 01/30/2005

ICE POINT THERMOCOUPLE REFERENCE MODEL, KAYE INSTRUMENTS: K-170-SP

SERIAL #: 306179

CALIBRATION DUE DATE: 01/30/2005

NIST #: 263094C&A

263094B&D

(SINGLE USE THERMOCOUPLE FROM

CALIBRATED REEL)

EDC 100RC SERIAL # 15075

NIST # 811/267966-03

DUE: 12/17/2005

TYPE T STANDARD REEL # 25926 & 26369 NIST # 258779B

QUALITY ASSURANCE TECHNICIAN

DATE



PMC A DIVISION OF ROCKBESTOS-SURPRENANT CABLE CORPAGE 447 680 HAYWARD STREET, MANCHESTER, NH 03103 (603) 622-3500 SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY FAX (800) 639-5701

CERTIFICATE OF CALIBRATION SPOOL # 00565657

TO:

OMEGA POINT LABS, INC. 16015 SHADY FALLS ROAD ELMENDORF, TX 78112

USA

Date: 10/16/04 Cust PO#: 14561Q JOB # PSO067407-3

CALIBRATION RESULTS ARE TRACEABLE TO THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) AND MEET SPECIAL LIMITS DEVIATION TOLERANCES AS DEFINED IN ISA MC96.1 (FORMERLY ANSI) AND ASTM E 230-03. MS-14561Q-OPL.

TEST RESULTS FOR:

PMC P/N: KK-FB/FB-24

Total Footage:

1315'

Test Temperature (°F)	Inside End	Outside End
200°	-1.1	-0.3
400°	-1.0	-1.9
600°	-2.3	-1.3
800°	-2.3	-1.9
1000°	+0.5	+1.1

Calibration Certificate Acceptants. Fiberglass 0056565 NIST Traceability Adequate 0A 4 As Found / As left Values Eng Calibration Date Sufficient QA_ Eng. Tolerance Range Adequate QA Eng Date of Review 0A6-25-04 Eng. 10/20 OPL DAVOC Dept Eng./Dept. Mgc.

REPORTED RESULTS ARE DEVIATIONS FROM TEST TEMPERATURES. FOR CORRECTION FACTORS REVERSE THE SIGNS.

THE MATERIAL REFERENCED ABOVE HAS BEEN CALIBRATED UTILIZING TECHNIQUES CONSISTENT WITH THE GUIDELINES SET FORTH IN ANSI Z540-1 AND ASTM E-220-02. THIS IS TO CERTIFY THE MATERIAL FURNISHED ON THIS SHIPMENT ARE IN CONFORMANCE WITH THE REQUIREMENTS, SPECIFICATIONS, AND DRAWINGS OF THE ABOVE REFERENCED CUSTOMER PURCHASE ORDER. INSPECTION AND TEST RECORDS ARE ON FILE AND AVAILABLE FOR CUSTOMER REVIEW.

SECONDARY STANDARD THERMOCOUPLE: TYPE K

REEL # POS LEG: 00534834 REEL # NEG LEG: 00534833

CALIBRATION DATE: 3/17/00

DIGITAL VOLT METER

MODEL: KAYE INSTRUMENTS: X1525S

SERIAL # 306172

CALIBRATION DUE DATE: 01/30/2005

ICE POINT THERMOCOUPLE REFERENCE MODEL, KAYE INSTRUMENTS: K-170-SP

SERIAL #: 306179

CALIBRATION DUE DATE: 01/30/2005

NIST #: 263094C&A 263094B&D

(SINGLE USE THERMOCOUPLE FROM

CALIBRATED REEL)

EDC 100RC SERIAL # 15075 NIST # 811/267966-03

DUE: 12/17/2005

TYPE T STANDARD REEL # 25926 & 26369 NIST # 258779B

QUALITY ASSURANCE TECHNICIAN

DATE



PMC A DIVISION OF ROCKBESTOS-SURPRENANT CABLE CORPAGE 448 680 HAYWARD STREET, MANCHESTER, NH 03103 (603) 622-3500 SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY FAX (800) 639-5701

CERTIFICATE OF CALIBRATION SPOOL # 00565658

TO:

OMEGA POINT LABS, INC. 16015 SHADY FALLS ROAD ELMENDORF, TX 78112

USA

Date: 10/16/04 Cust PO#: 14561Q JOB # PSO067407-3

CALIBRATION RESULTS ARE TRACEABLE TO THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) AND MEET SPECIAL LIMITS DEVIATION TOLERANCES AS DEFINED IN ISA MC96.1 (FORMERLY ANSI) AND ASTM E 230-03. MS-14561Q-OPL.

TEST RESULTS FOR:

PMC P/N: KK-FB/FB-24

Total Footage:

3685'

Test Temperature (°F)	Inside End	Outside End
200°	-1.5	-0.6
400°	-1.9	-0.8
600°	-2.0	-1.4
800°	-1.9	-0.8
1000°	+0.1	+1.2

Calibration Certificate Acceptance
Hom Diverdas TO Illiso
BN 00563658
NIST Traceability Adequate OA C Food
As Found / As left Values QA & Eng
Calibration Date Sufficient CA Eng. Tolerance Range Adequate CA Communication Calibration Date Sufficient CA Communication Calibration Calibration Date Sufficient CA Communication Calibration Cal
Date of Review QAID-25-040 Eng. 10/20/00
A 201
ADI CALOR
OPL QA/QC Dept. Eng/Dept. Mgr.

REPORTED RESULTS ARE DEVIATIONS FROM TEST TEMPERATURES. FOR CORRECTION FACTORS REVERSE THE SIGNS.

THE MATERIAL REFERENCED ABOVE HAS BEEN CALIBRATED UTILIZING TECHNIQUES CONSISTENT WITH THE GUIDELINES SET FORTH IN ANSI Z540-1 AND ASTM E-220-02. THIS IS TO CERTIFY THE MATERIAL FURNISHED ON THIS SHIPMENT ARE IN CONFORMANCE WITH THE REQUIREMENTS, SPECIFICATIONS, AND DRAWINGS OF THE ABOVE REFERENCED CUSTOMER PURCHASE ORDER. INSPECTION AND TEST RECORDS ARE ON FILE AND AVAILABLE FOR CUSTOMER REVIEW.

SECONDARY STANDARD THERMOCOUPLE: TYPE K

REEL # POS LEG: 00534834

REEL # NEG LEG: 00534833 CALIBRATION DATE: 3/17/00

NIST #: 263094C&A 263094B&D

(SINGLE USE THERMOCOUPLE FROM

CALIBRATED REEL)

DIGITAL VOLT METER

MODEL: KAYE INSTRUMENTS: X1525S

SERIAL # 306172

CALIBRATION DUE DATE: 01/30/2005

EDC 100RC SERIAL # 15075 NIST # 811/267966-03 DUE: 12/17/2005

TYPE T STANDARD

ICE POINT THERMOCOUPLE REFERENCE MODEL, KAYE INSTRUMENTS: K-170-SP

SERIAL #: 306179

CALIBRATION DUE DATE: 01/30/2005

REEL # 25926 & 26369 NIST # 258779B



PMC A DIVISION OF ROCKBESTOS-SURPRENANT CABLE CORPAGE 449 680 HAYWARD STREET, MANCHESTER, NH 03103 (603) 622-3500 SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY FAX (800) 639-5701

CERTIFICATE OF CALIBRATION SPOOL # 00565660

TO:

OMEGA POINT LABS, INC. 16015 SHADY FALLS ROAD ELMENDORF, TX 78112

USA

Date: 10/16/04 Cust PO#: 14561Q JOB # PSO067407-3

CALIBRATION RESULTS ARE TRACEABLE TO THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) AND MEET SPECIAL LIMITS DEVIATION TOLERANCES AS DEFINED IN ISA MC96.1 (FORMERLY ANSI) AND ASTM E 230-03. MS-14561Q-OPL.

TEST RESULTS FOR:

PMC P/N: KK-FB/FB-24

Total Footage:

4400'

Test Temperature (°F)	Inside End	Outside End
200°	-1.2	-0.4
400°	-1.5	-1.0
600°	-2.1	-1.7
800°	-2.1	-1.0
1000°	+0.5	+1.6

Calibration Certificate Accepta Filmersla 00565867 NIST Traceability Adequate As Found / As left Values OA QA Eng Calibration Date Sufficient Tolerance Range Adequate QA QA16-25-00 Date of Review OPL GAVOC Dept

REPORTED RESULTS ARE DEVIATIONS FROM TEST TEMPERATURES. FOR CORRECTION FACTORS REVERSE THE SIGNS.

THE MATERIAL REFERENCED ABOVE HAS BEEN CALIBRATED UTILIZING TECHNIQUES CONSISTENT WITH THE GUIDELINES SET FORTH IN ANSI Z540-1 AND ASTM E-220-02. THIS IS TO CERTIFY THE MATERIAL FURNISHED ON THIS SHIPMENT ARE IN CONFORMANCE WITH THE REQUIREMENTS, SPECIFICATIONS, AND DRAWINGS OF THE ABOVE REFERENCED CUSTOMER PURCHASE ORDER. INSPECTION AND TEST RECORDS ARE ON FILE AND AVAILABLE FOR CUSTOMER REVIEW.

SECONDARY STANDARD THERMOCOUPLE: TYPE K

00534834 REEL # POS LEG: REEL # NEG LEG: 00534833 CALIBRATION DATE: 3/17/00

DIGITAL VOLT METER

MODEL: KAYE INSTRUMENTS: X1525S

SERIAL # 306172

CALIBRATION DUE DATE: 01/30/2005

ICE POINT THERMOCOUPLE REFERENCE MODEL, KAYE INSTRUMENTS: K-170-SP

SERIAL #: 306179

CALIBRATION DUE DATE: 01/30/2005

NIST #: 263094C&A 263094B&D

(SINGLE USE THERMOCOUPLE FROM

CALIBRATED REEL)

FDC 100RC SERIAL # 15075 NIST # 811/267966-03

DUE: 12/17/2005

TYPE T STANDARD REEL # 25926 & 26369 NIST # 258779B

ASSURANCE TECHNICIAN



PMC Division of RSCC

680 Hayward Street Manchester, NH 03103 Tel: (603) 622-3500 Fax: (603) 622-7023 **0000146332** Page 450

SPECIALIZING IN WIRE & CABLE FOR THE SENSOR INDUSTRY

DELIVERY NOTE

DELIVERY TO

OMEGA POINT LABS 16015 SHADY FALLS ROAD ELMENDORF, TX 78112 USA

Attention: CLEDA

SHIPMENT:	OUR ORDER:	DATE:	CUSTOMER PO:	CONTACT:
0000146332	PSO067407	Oct 18 2004	14561Q	CLEDA
ACCOUNT:	FOB:	SHIP VIA:	TRACKER#:	PAGE:
OMEG01	Manchester,NH	UPS GROUND		1

01	Manchester,NH	UF3 GRUC							
ITEM		UO	vi Q	ГΥ	QTY SHIPPED	QTY B/O			
Spool #: 0056	65655 00565656 00565		Г	12,000	12,475	0			
CALIBRATIO Spool #:	N CHARGE	EAG	Н	1	1	0			
	ITEM KK-FB/FB-24 Spool #: 0056 00565658 005 CALIBRATIO	ITEM KK-FB/FB-24 Spool #: 00565655 00565656 00565 00565658 00565660 CALIBRATION CHARGE	ITEM UOI KK-FB/FB-24 Spool #: 00565655 00565656 00565657 00565658 00565660 CALIBRATION CHARGE EAC	ITEM UOM QT KK-FB/FB-24 Spool #: 00565655 00565656 00565657 00565658 00565660 CALIBRATION CHARGE EACH	ITEM	ITEM			

Q/A RECEIVING REPORT

CLIENT/PROJECT NAME SANDIA National Jally REPORT NUMBER 2689 DATE INSPECTED. HT 265 DATE RECEIVED INSPECTED BY: CLIENT/PROJECT NUMBER 14790 - 123263 -Omega Point Lab DODOLA RECEIVED FROM IND PROJECT LOCATION

				Dece 151
				Page 451
REMARKS				
REM/			R	
Beiect				
TANCE				
ACCEPTANCE Accept Hold P	>		\sim	
CONTAINER	Good		8	
SAFETY RELATED Y/N	Z	7	2	
CERT REC'D X/N	>	×	>	
CON'tD MATL Y/N	>	>	>	
I.D. NO.	C4x5.4	C5x6.7	10GA X 73.000"	
C		0	Ø I	
QUANTITY der Rec'd	20	Q		
QUANTITY Order Rec'd B.O.	30		4	
P.O . NO.	14674Q 30 30 Q	01 94041	M2749 12 13	
ITEM DESCRIPTION	a ahannel 4x5.4	a channel	16ga X (Sheets)	





PURCHASE ORDER 14674Q Pag Page 452

Date: 01/04/2005 Page: 1 of 1

Order From:

Texas Specialty Steel

12270 Hwy. 181 S

San Antonio

TX 78223

210-633-0047

Deliver to:

Omega Point Laboratories, Inc

16015 Shady Falls Road

Elmendorf

TX

78112

(210) 635-8100

Vendor No:

Your Item Number Item Description	Our Reference	Qty Ordered	Units	Unit Cost	Extension
C Channel C4x5.4x20'	001	10	Each	\$44.55	\$445.50
C Channel C5x6.7x20'	002	30	Each	\$55.28	\$1,658.40
10 ga.72" x 144" HR Sheets	003	12	Each	\$243.00	\$2,916.00

"See Special Instructions Regarding Purchasing Specifications for Quality Assurance Requirements.

QA Approval___

Date

Please Quote Purchase Order Number on all correspondence. Please certify that the items supplied conform to applicable standards and specifications.

Subtotal: Freight: \$5,019.90 0.00

Tax Amount: Total Value:

338.84 \$5,358.74

Design	Name of Street
8	6
2	12
	5

TEXAS SPECIALTY STEEL

12270 Hwy 181 So. San Antonio, Texas 78223 (210) 633-0047 Fax 633-2344

SALES ORDER 5960 Page 453

DELIVER TO:

600	Vro)
u	NU

DATE ORDERED	14674 Q DATE SHIPPED SHIPPED VIA	00 1	.O.B. SA	5.5
QUANTITY	DESCRIPTION	WEIGHT	PRICE	TOTAL
30	1 +x54 Chan 20'	108 20	44.55eu	1336.5
10	5x62 chas 20'	13424	55.28 eu	552.80
12	10ga 6 X 12 ILR Sheets	405# Ric	243000	2916,0
1	0			
				4805.3
			TAK	324.3
	MTR riginars			5129.60
	0			
	\$25.00 Service Charge For Returned Checks			
	TAXABLE NON-TAXABLE			



BAYOU STEEL CORPORATION

MATERIAL CERTIFICATION REPORT

LA PLACE, LOUISIANA 70069-1156 P.O. BOX 5000 Telephone (985) 652-4900 RIVER ROAD

ASTM A6 ACCORDANCE *FESTED IN* WITH

48 CHANNELS HEAT NO. 28136 Length 20'0" NVOICE NO. PRODUCT

Pcs

DATE 11/30/04 Cust 0-3300 -0184 SIZE C 4 X 5.4 GRADE A36 -01

PO:0663288 03 24 Prod Id:0126441

000HHM0007H 00 F	CHEMICAL ANALYSIS ANALYSIS S S C C C C C C C C C C C C C C C C	AL IS	111	014	221	17	17	LO	000	0				_
------------------	--	----------	-----	-----	-----	----	----	----	-----	---	--	--	--	---

		no. Management		_		-	_	_		_	1 1	7	£ 1	7
		MPa	MPa	8	E	ъ		sq mm	%	7		GRAIN	HARDI	GRAIN
2	METRIC	313	460	31.0 %	203							38		
TEST 2	IMPERIAL	45,448 PSI	645 PSI	31.0%	.E.	P		ui bs	%	ft-ibs		INTERNAL CLEANLINESS		
	=							mm	%			INTERN	IITY	FREQUENCY
	METRIC	320 MPa	458 MP	33.0 %	203 mm	D		sd	%	ד			SEVERITY	FREQU
TEST 1				_		_		c		28		METRIC	7	O
	IMPERIAL	363 PSI	66,399 PSI	3.0 %	.⊑ 00	О		sq	%	ft-lbs		~	80	
	=	46,	99	m		-	_	_	_			IMPERIAL	fr·lbs	ı
ICAL	TIES					85	"		A					
MECHANICAL	PROPERTIES	YIELD STRENGTH	TENSILE STRENGTH	ELONGATION	GUAGE LENGTH	BEND TEST DIAMETER	BEND TEST RESULTS	SPECIMEN AREA	REDUCTION OF AREA	IMPACT STRENGTH		IMPACT STRENGTH	AVERAGE	TEST TEMP
_				_	_		_		_			_	_	_
HEMICAL	NALYSIS	.11	.78	.014	.02	.21	.31	.17	.17	.056	000	000.		
S	AN		_			-	5			0	9			

sq mm

8

ft-lbs sq in

8

MPa

PS:

METRIC

IMPERIAL

TEST 3

% E

% ⊆

P

SA36 Specs: ASME Customer Grade & "NO WELD REPAIR"

5 B

A709 GRADE 36

RATING

RIENTATION **EST TEMP**

REDUCTION RATIO

GRAIN PRACTICE

GRAIN SIZE HARDNESS

SPECIFICATIONS REPORTED ABOVE. ALL STEEL IS ELECTRIC FURNACE MELTED, MANUFACTURED, PROCESSED, AND TESTED IN THE U.S.A WITH SATISFACTORY RESULTS, AND IS FREE I HEREBY CERTIFY THAT THE MATERIAL TEST RESULTS PRESENTED HERE ARE FROM THE REPORTED HEAT AND ARE CORRECT. ALL TESTS WERE PERFORMED IN ACCORDANCE TO THE OF MERCURY CONTAMINATION IN THE PROCESS.

NOTARIZED UPON REQUEST:

SWORN TO AND SUBSCRIBED BEFORE ME IN AND FOR ST. JOHN PARISH ON THIS

DAY OF

SIGNED TIMOTHY R. WEIDE, QUALITY ASSURANCE MANAGER OF DIRECT ANY QUESTIONS OR NECESSARY CLARIFICATIONS CONCERNING

THIS REPORT TO THE SALES DEPARTMENT.

Jeanne M. Buffington, # 60493, Notary Public

1-800-535-7692 (USA)



BAYOU STEEL CORPORATION

MATERIAL CERTIFICATION REPORT

LA PLACE, LOUISIANA 70069-1156 P.O. BOX 5000 Telephone (985) 652-4900 RIVER ROAD

ASTM A6 ACCORDANCE *LESTED IN* WITH

36 CHANNELS 23960 Length PRODUCT HEAT NO. INVOICE NO.

DATE 06/01/04
Cust 0-3300 -0184
GRADE A36 -01
SIZE C 5 X 6.7

PCS

Po:0661120 03 24 Prod Id:0127721

	5:	_	回 回 回	छ	BE	BEI	SP	RE		0		1	AV	2	A O H
CHEMICAL	단	9	-						En	0	H				
A A	U.	Š	۵	S	S	Cu	Z	ర	Mo	CP	>	8	A	Sn	z

	0	m	-		-			Γ	-	_
)	00.	H								
	CP	>	æ	A	Sn	z	ij	-	ວ	П

Tribs	GRAIN SIZE	HARDNESS	GRAIN PRACTICE	REDITCTION BATTO
0			0	
	INTERNAL CLEANLINESS	SEVERITY	FREQUENCY	RATING
	METRIC	٦	O	
	IMPERIAL	ft·lbs	ш	
	IMPACT STRENGTH	AVERAGE	TEST TEMP	ORIENTATION

sq mm

sq in

sq mm

8

sq in

% wur

sq in ft-lbs

%

DUCTION OF AREA

ECIMEN AREA

PACT STRENGTH

MPa % E О

PSI PSI 8 Ē 0

MPa 519 MPa

367

PSI

53,298

362 MPa 512 MPa

PSI PSI

52,522 74,321 31.0

NSILE STRENGTH

LD STRENGTH

8 2.

8

Р

ND TEST DIAMETER ND TEST RESULTS

AGE LENGTH

UNGATION

8 .⊆

mm %

31.0

mm 8

26.0

O

METRIC

IMPERIAL

METRIC

IMPERIAL

METRIC

IMPERIAL

TEST 1

MECHANICAL PROPERTIES

TEST 2

TEST 3

Specs: ASME SA36 Grade & REPAIR" "NO WELD

36 A709 GRADE

SPECIFICATIONS REPORTED ABOVE. ALL STEEL IS ELECTRIC FURNACE MELTED, MANUFACTURED, PROCESSED, AND TESTED IN THE U.S.A WITH SATISFACTORY RESULTS, AND IS FREE I HEREBY CERTIFY THAT THE MATERIAL TEST RESULTS PRESENTED HERE ARE FROM THE REPORTED HEAT AND ARE CORRECT. ALL TESTS WERE PERFORMED IN ACCORDANCE TO THE OF MERCURY CONTAMINATION IN THE PROCESS.

NOTARIZED UPON REQUEST:

SWORN TO AND SUBSCRIBED BEFORE ME IN AND FOR ST. JOHN DAY OF PARISH ON THIS

٠		
ı		
ı		
П		
:		
٠.		
-		
ı		
ſ.		
ŧ.		
l		
1		
ı		
ı		
ı		
1		
1		
ı		
ŀ		
ı		
L		
ļ		
•		
5		
ř.		
9		
Ũ.		
1		
ı		
ŀ		
ì		

SIGNED TIMOTHY R. WADE, QUALITY ASSURANCE MANAGER

DIRECT ANY QUESTIONS OR NECESSARY CLARIFICATIONS CONCERNING

THIS REPORT TO THE SALES DEPARTMENT.

Jeanne M. Buffington, # 60493, Notary Public

1-800-535-7692 (USA)

Tel: 205-599-8000 Fax: 205 599-8131

	CERTIFICATE	ICATE	Of	of ANALYSIS	and	TESTS	C	No. to	
Part No 86382 HR COIL ASTMA	3826/0617501 TMA1011 COMM	T# C					4		130ct04
0 GA. X 7		1			-			Pcs	Wgt
Heat Number								26	10,530
1984	Tag No 445062						ý	PC SI	Wa+
	I	L= <us< td=""><td>EL EL</td><td>EEL > /VESS</td><td>L= < M</td><td>L=<us steel="">/VESSL=<mp951019>/CNTRY=<usa>/REV=<04-03></usa></mp951019></us></td><td>?Y= < USA > ,</td><td>/REV=<04</td><td>03 \ 60-</td></us<>	EL EL	EEL > /VESS	L= < M	L= <us steel="">/VESSL=<mp951019>/CNTRY=<usa>/REV=<04-03></usa></mp951019></us>	?Y= < USA > ,	/REV=<04	03 \ 60-
Heat Number 61984C	0.50	* Che	nic 0.3	Chemical Analysis Mn=0.3400 P=0.0110	is *	4 II			
	#1=0.05	0540				2-0.020 Cn=0.0500 Cn=0.0500	1.0050 Ct	1=0.0500	

THIS IS TO CERTIFY THAT THE PRODUCT DESCRIBED HEREIN WAS SAMPLED AND TESTED IN ACCORDANCE WITH THE SPECIFICATION, TO OUR KNOWLEDGE, AND FULFILLS REQUIREMENTS IN SUCH RESPECT.

METRIC

IMPERIAL

TEST 3

TEST 2

IMPERIAL

METRIC

IMPERIAL

TEST 1

MECHANICAL PROPERTIES MPa

SS EM

PSI & E P

36.0 % 203 mm 480 MPa 331 MPa METRIC

.5

EE

c

B

8

36.0

47,994 PSI 69,642 PSI 36.0 %

MPa

333

PSI PSI

48,344 F 70,206 F 36.0

ъ

sq mm

sqin %

84 mm

sq fn % ft-lbs

sq min

sq in

R

87

Page

BAYOU STEEL CORPORATION

MATERIAL CERTIFICATION REPORT

LA PLACE, LOUISIANA 70069-1156 · RIVER ROAD P.O. BOX 5000

Telephone (985) 652-4900

CHANNELS PRODUCT INVOICE NO.

ASTM A6

ACCORDANCE **TESTED IN**

WITH

DATE 03/25/04 Cust 0-3300 -0184 SIZE C 5 X 6.7 GRADE A36 -01 Pcs

36

HEAT NO. 23149 Length 40'0"

Pro: 0660119 03 24 Prod Id: 0128041

871-2402

BEND TEST DIAMETER REDUCTION OF AREA BEND TEST RESULTS IMPACT STRENGTH **TENSILE STRENGTH** MPACT STRENGTH SPECIMEN AREA GUAGE LENGTH ORIENTATION ELONGATION TEST TEMP AVERAGE .14 .88 .015 .000 ANALYSIS CHEMICAL

Customer "NO WELD 5 5

Grade & Specs: ASME SA36 REPAIR"

A709 GRADE 36

REDUCTION RATIO GRAIN PRACTICE

GRAIN SIZE

INTERNAL CLEANLINESS

FREQUENCY

70

r.lbs F

METRIC

IMPERIAL

RATING

SEVERITY

HARDNESS

SPECIFICATIONS REPORTED ABOVE, ALL STEEL IS ELECTRIC FURNAGE MELTED, MANUFACTURED, PROCESSED, AND TESTED IN THE U.S.A WITH SATISFACTORY RESULTS, AND IS FREE I HEREBY CERTIFY THAT THE MATERIAL TEST RESULTS PRESENTED HERE ARE FROM THE REPORTED HEAT AND ARE CORRECT. ALL TESTS WERE PERFORMED IN ACCORDANCE TO THE OF MERCURY CONTAMINATION IN THE PROCESS.

NOTARIZED UPON REQUEST:

SWORN TO AND SUBSCRIBED BEFORE ME IN AND FOR ST. JOHN DAY OF PARISH ON THIS

FIMOTHY R. WHITE, QUALITY ASSURANCE MANAGER SIGNED

DIRECT ANY QUESTIONS OR NECESSARY CLARIFICATIONS CONCERNING 457 THIS REPORT TO THE SALES DEPARTMENT

1-800-535-7692 (USA)

Jeanne M. Bulfington, # 60493, Notary Public

ZI0633Z344

15:10 0002/10/10

Q/A RECEIVING REPORT

CLIENT/PROJECT NAME SANVALO NAT'L FALLA REPR ALIENT/PROJECT NUMBER 14796-123263,64465 DATE RECEIVED FROM SANCTIC NAT'L FALLA DATE PROJECT LOCATION OMEGA POINT LABS

A DATE RECEIVED 3-4-05
DATE INSPECTED BY:

		KS	R	lc	٠.	v	in	S	Du	li (7				F	ag	e 4	58
	1	REMARKS	_															
-	ACCEPTANCE	Accept Hold Reject																
	INTEGRITY ACCE	Accep	X		× 000		Soa X		X		Sees /	*0) Jan	0.				
-	RELATED IN	_	N		N		2		N		N		N		1			
Tag	(EC'D	N.	Z		×		2		Z		7		2					
Colling	MATL	X X	λ		\searrow		>		×		\succ		>					
	(I.D. NO.	248809-12-14451R		248PO9-36-1441-5TR		48-12-90 VB4		4036-90V134		119544		11341D					
	>	B.O.	Ø		Ø	ri.	Ø		Ø	33-4-00	0		0	,				
	QUANTITY	Order Rec'd B.O	3		3		7		4	,	*		7					
	ğ	Order	Ø		Ø		0		Ø		8	,	Ø					
	1	P.O . NO.	XX		M		NA		NA		NA		NA					
		ITEM DESCRIPTION	dabletraus 12"	9	aulilitray 36"	Ð	"E1 -09b		900 - 36"		Splice Plates	,	Splice Plates					



PACKING LIST

SHIPPING ORDER NO. 80770500001

Page 459

1

COOPER B-Line 509 West Monroe Street Highland, Illinois 62249-0326, U.S.A. 024012438

SOLD TO:

BORDER STATES ELECTRIC PO BOX 2767

FARGO ND 581082767

000072721

SHIP TO:

OMEGA POINT LABS 16015 SHADY FALLS ROAD

ELMENDORF TX 78112

ATTN: RECEIVING

SHIP FROM	SHIP DATE	SHIP VIA	BILL OF LADING	WEIGHT	FREIGHT TERMS
RENO	3/02/05	PRECISION AIR C	01256739	501.00	CHARGE

CST PO:	55004					PHONE: 7012935833
ORDERED	DUE	SHIPPED	BACKORDER	UNIT	LINE	DESCRIPTION
		* * * * * * * *	CONTA CAN S PER S FOR V CONFI	HIP TEVE ALUE RM W	EARL AT OF ITH	* * * * * * * * * * * * * * * * * * *
3	3	3		PC		248P09-12-144 ST SC 78101162149
3	3	3		PC		248P09-36-144 ST SC V 78101162454
2	2	2		PC		4P-12-90VI24 VRT I/S V 78101162189
2	2	2		PC		4P-36-90VI24 VRT I/S 78101162491
10	10	10		PR	5	9ZN-8004 SPLICE PLT 78101126314

ANY SHORTAGE OR DAMAGE MUST BE REPORTED TO CUSTOMER SERVICE AT 618.654.2184 WITHIN TEN (10) DAYS FROM DATE OF SHIPMENT.

THIS MEMORANDUM is an acknowledgment that a Bill of Lading has been issued and is not the Original Bill of Lading nor a copy or duplicate, covering the property named herein, and is intended solely for filing or record.

RECEIVED, subject to the classifications and tariffs in effect on the date of the receipt by the carrier of the property described in the Original Bill of Lading, the property described below, in apparent good order, except as noted (contents of packages unknown), marked consigned, and destined es indicated below, which said they are also destinated in the original Bill of Lading, and the property described below, in apparent good or order, except as noted (contents of packages unknown), marked consigned, and destined es indicated below, which said they are also destination, for its route, otherwise to deliver to another carrier on or corporation in possession of the property under the contract lagrees to carry to its usual place of delivery at said destination, if on its route, otherwise to deliver to another carrier on the route to said destination, and as to each party at any time interested in all or any of said property, that every service to be performed hereunder shall be subject to all the terms and conditions of the Uniform Domestic Straight Bill of Lading set torth (1) in Official, Southern, Western and Illinois Freight Classifications in the Hereof, if this is a rail or a rail-water shipment.

Bilipper herety certifies that he is familiar was not conditions are hereby agreed to by the shipment.

B/L NO.

SHIPPER'S NO. 5 07 90 5

	governs the transportation of this shipment, and the said terms and condition FROM COOPER	is are hereby agreed to by the shipper and accepted for himself and his assigns B-Line	NAME OF CARRIER		age 460
Consigned (OMEDA POINT LABS		(Mail or street address of collete SSOO #149 RK1 RECEIV		or purposes of notification only.)
est'n	ELMENDORF TX 78112				
oute lel'ng Carr.	PRECISION AIR C	Car or Ve	ehicle Initials		No.
BER GES	OF ARTICLE	GE, DESCRIPTION ES, SPECIAL EXCEPTIONS	*WEIGHT (SUBJECT TO CORRECTION)	CLASS OR RATE	
1	Bundles ofPcs. Single Pcs. CartonPcs. Crates Skids Cartons	Channels, NOI Iron or Steel Item No. 104850 Braces, Brackets NOI, Iron or Steel 3/16" Thick or Thicker Item No. 104600	258	8.0	Subject to Section 7 of conditions of applicable bill of lading, if this shipment is to be delivered to the consignee without recourse on the consignor, the consignor shall sign the following statement: The carrier shall not make delivery of this shipment without payment of freight and all other lawful charges. COOPER B-Line
	Bundle ofPcs. Single Pcs. Bundles ofPcs. Curved Fitting Single Pcs. Curved Fitting	Cable Racks; Trays Troughs or Cable Way Aluminum Straight Section and Curved Fittings. Item No. 61220 - Sub 2			(Signature of Consignor) If charges are to be prepaid, write or stamp here, "To be Prepaid."
3.	Bundles ofPcs. Single Pcs. Bundles ofPcs Curved Fittings Single Pcs. Curved Fitting	Cable Racks, Trays Troughs or Cable Way Steel 16 Gauge or Thicker Straight Sections and Curved Fittings Item No. 61220 - Sub 1	47.6M	6.0	Received \$ to
	Crates Skids Cartons	Clips, Fasteners or Mounts, Steel, 94230			apply in prepayment of the charges on the property described hereon.
	7 TOTAL PCS.	8014 - 1	8 9		
	DELIVERY DATE 03/04				Agent or Cashier.

Collect On Delivery \$

and Remit to

C.O.D. CHARGES TO BE PAID BY

City State

医具造品的复数医检查法医电压医生产医定应

Shipper Consignee

(The signature here acknowledges only the amount prepaid.)

Charges Advanced:

\$

* If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's or shipper's weight."

NOTE-Where the rate is dependent on value, shipper's are required to state specifically in writing the agreed or declared value of the property. The agreed or declared value of the property is hereby specifically stated by the shipper to be not exceeding

The Fibre Boxes used for this shipment conform to the specifications set forth in the box maker's certificate thereon, and all other requirements of Consolidated Freight Classification.



Airgroup - DFW PO Box 3627

Bellevue, WA 98009-3627 Tel: 817-481-0970 Fax: 817-488-6583 www.airgroup.com

HAWB #

Origin Destination

Pick Up Date

: BY 03/04/2005 Deliv Date

COD

Charges

: Third Party

: 129000584

Page 461

: 03/03/2005

Shipment #

Domestic HAWB

JIGHT E BUSINESS CARPENTER FRWY STE	WORLDWIDE FLIGH						Shipper					
5063	1925 W JOHN CAR 450 IRVING, TX 7506 Attn: Tel: Ref #	ι,	FISCHER DI	AA C/O LSG SI 18950 COLONE HOUSTON, TX Attn: CECELIA Tel: 281-443 Ref #		E POINT 75211	NNACLE	AA C/O (3801 PIN COCKRELI Attn: Tel: Ref #				
-a. 11		Closing	Between	Deliver By	Closing	Between	ready	Pick Up R				
TSA U			-	03/04/2005		12		03/03/				
						ctions	Instruc	Special I				
Width Height	Length		Description		rected		A	Diagon				
0 40.00 19.0	48.00		97 		eight eight	eight W	W	Pieces				
			AMILE STATE OF THE STATE OF			.00 LB	266	1				
Section 1988			IPMENT	SH								
	LB	188.0				.00 LB	266	1				
Rate Amount	Qty I		ption	Descri		rge	Cha					
\$0.0		ARGES	OTAL CH	T								
ed Value	Total Declared V											
nsignee Signature	Consig	ture	Jp Driver Signa	Pick-l	re	hipper Signatur	SI					
Time Pcs	Date Tin	Pcs	Time	Date	Pcs	Time		Date				
hipment received in good order unless note	Exceptions (Shipmer	ander unless noted	pment received in good	Fixentians		pment received in good						
nsignee Signatu	Consig	ture		Pick-U	Shipper Signature Date Time Pcs Date							

Q/A RECEIVING REPORT

REPORT NUMBER 069 DATE INSPECTED CLIENT/PROJECT NUMBER 14790-123263-264+265 DATE RECEIVED RECEIVED FROM SANDLO NALL RALLA DATE INSPECTED INSPECTED BY: CLIENT/PROJECT NAME Sandia Nathing Jolla Omega Point Labs PROJECT LOCATION

		1						and the order	4.5		 	Pad	ge 4	162	
- Constitution of the Cons		R	ece	iv	i	g	Q	nl	5				J =		
	REMARKS								0						
	REM										21				
100000	Doio C									and a Contractor					
CINC															
HONG TO SOM	Accept Hold								_						
	1 4														
CONTAINER	INTEG	See													
SAFETY	Y/N	7							_						
_															
	X/N X/N										-				
CON't	MATL	>	3					~							
		()·()	X X	शुंख के	AS			3612	4ED						
	I.D. NO.	8.	9-66	79-6	000			- bLa	500 N						
	=	C1-6100-P101-P0	A-1019-9121-12	541D-91D14-9124-3	A-1200-AS		NA	09-1279-00123	#33500 NA						
			- Q	18	Ø	Ø	B	0	B	-					
Y LI LI	Apr Bec'd	*	M	50	13	6		4	200						
-	Order Bec'd a	Ø	, 80	Ø	Ø	8	Ø	Ø	Ø						
Г			-					U							
BOUNDALING	P.O. NO.	AN AN	AZ	1	NA.	NA	NA	NA	NA				+		
		2	Day of	33	b +3	de	alle	>							
	NOIL	No to	35	46	July Struct	eltu	25-02	, 5	Sec	_					
	ITEM DESCRIPTION	Cal	hur	חשתה	12.0	2 ste	dux	13	3						
	A DES	3	200	ide e	101	SAN	-Jan	Supi	8#						
	ITEN	12 " wiede calletan	LANA	36 junido eureve tra	Unistruit struct	a" square steettube	Got of Mandimare-Trans	36" Calletotray	Baro#8 Copper						
		10	= 0	3	3	4	8	36	0						



Q/A RECEIVING REPORT

AND REPORT NUMBER ALL DATE INSPECTED CLIENT/PROJECT NUMBER 14790 -123343-3644365 DATE RECEIVED INSPECTED BY: Omega Point Labs Sandia Na CLIENT/PROJECT NAME SAWOL A PROJECT LOCATION RECEIVED FROM

		D	۸ ۶	^ .		m) .		*			⊃ag	je 4	63	
(TKS	X)V	m	30	ne	0								
i	HEMAHKS											+:					
IJ.	Reject																
ACCEPTANCE	Accept Hold																
	Accept	\times															×
CONTAINER		Good															See
SAFETY	Y/N	Z															Z
CERT REC'D	N K	1															
CON'tD MATL	N/Y	>				>			\$0					-1485		_	>
2	.D. NO.	BWAS 1"	APA LB-7	NA	11 FM7 370	3W40 2/2" F-104583S	4PB-18-17FM7	MA	870 2/2- Egelner	3WA6 4" E-104582S	APF"4 107	NA	4 PP 976 3/2"-4" FM7	188331 8598	E-3215271	X	5-52152-H 3WAB 4"9DDE0
>	B.O.		Ø	Ø	, D	, Q	Ø	Q	0	·Ø	0	A	10	B	0	10	0
QUANTITY	Order Rec'd B.O.	6	5	1	Ŋ	5	20	12	5	4	70	6	15	4	5	S	4
Ø	Order	Ø	Ø	Ø	Ø	Q	0	Ø	Ø	Ø	Ø	0	Ø	Ø	Ø	Ø	Ø
(F.O. NO.	NA NA	NA	₹ ×	NA	M	NA	NA	NA	NA	NA	NA	NA	NA	NA	r NA	r NA
	ILEM DESCRIPTION	1"gally. anduit	1" Conduit bodies	1" rendint gastet	1" ster) where	D.S " galer. Comput	a.s." conduit bodies	a.s." undint anapoth	2.5" April Correra	4" an lis. andwit	4" conduit bodies	4" condint gospeth	4" steel covers	18"X 24"X8" Juneticon	90°-1" amdint albust NA	90° - 2.5" Condint eller	90°-4" conduit elbans NA



RR#2691

alda

Sanuia ivational Laboratories For the U.S. Department of Energy 1515 Eubank SE Albuquerque, NM, 87123

SHIPPER Commercial Invoice

Status: Approved

Ship to:

Omega Point Laboratories

16015 Shady Falls Road

SA

Form filled out by:

WYANT, FRANCIS J.

Phone:

Date Prepared:

2005-1-10 FRANK

Requester:

WYANT, FRANCIS J.

Phone:

5058445682

TX 78112

United States

Elmendorf

RMA# or RGA#

Deg Priest

Deliver to: Phone:

(210) 635-8100

Building:

Room:

Mail Stop:

Company:

Omega Point Laboratories

Department:

Address Type:

Unclassified

Date Due at Destination:

1/16/2005 No

Production Related:

Origination Site:

5058445682

Org. #:

06861

For Shipment Processing Use

Date Shipped:

Carrier:

None Selected

Mode:

None Selected

Bill of Lading No .:

Total # of Pkgs:

0

Total Weight:

0.0 lbs

Total Cubic Dim:

0.0

Advance Notification

Contacted Yes No

Name and Phone:

741 Number:

ATS:

TID Numbers:

RCT Initial/Dates

Reason/Authority: To be Consumed in Testing / Incorporate into End Product

Return Date: NONE

Authority Number:

If shipping controlled property to a new Sandia location

Freight Charge Payment: Sandia Pays

Destination Bldg:

Room:

Project: 73766

Task: 01.08

Carrier: NONE

If shipping to international destination:

Import duties and taxes will be paid by my project/task: I

Account:

Export Authorization:

No freight charge reason: NONE

Is material being shipped from the Shipping Department building or the 6000 Igloo? No

Shipment Comments: Shipping container located at the TEAMS (old TOSI Site). Contact Chuck Girard (cell: 459-8181) for pick

Transportation Pickup Requested: Yes

Questions about pickup call Dispatcher 844-1448 non-hazardous materials, 844-2556 hazardous materials.

Shipper's Export Declaration prepared:

Land star Invay 805-8828 or 646-0412

Total Shipment Quantity and Value: 1 \$6,000.00

Line Item #	Description/Comments For temporary transfer of items to international destinations, include item Manufacturer's Name, Category Domestic or Foreign, and Serial Number.	Classification Category/ level	Qty	Unit	Unit Value	T
1	Description: One shipping container containing the following items: 120 ft 1-in galvanized conduit, 5 1-in conduit bodies, 5 1-in conduit gaskets, 5 1-in steel covers; 120 ft 2.5-in galvanized conduit, 5 2.5-in conduit bodies, 5 2.5-in conduit gaskets, 5 2.5-in steel covers; 120 ft 4-in galvanized conduit, 5 4-in conduit bodies, 5 4-in conduit gaskets, 5 4-in steel covers; 4 18 x 24 x 8 junction boxes; 5 90-degree 1-in conduit elbows; 5 90-degree 2.5-in conduit elbows; 5 90-degree 4-in conduit elbows; 48-ft of 12-in wide cable trays; 48-ft of 36-in wide cable trays; 3 12-in inside curves; 3 36-in inside curves; 130 ft of Unistrut; 20 ft of 2-in square steel tube; Box of hardware for cable trays Comments: These items will be used in a series of destructive tests and will not be returned to Sandia following use.		1	EACH	\$6,000.00	\$

	S	Complete Control			Telling of	Dimer	sions	
	-	Ta	VV. 1. 1.4	Y	lw -	Н	D	Cubic Fe
Quantity	Type	Contents	Weight	L	AA .	EX	D	Cubic Fe

Combination to Lock on Shipping Container:

Turn right 3 times. Stop at 6 Turn left past 6 Stop at 8 Turn right to 26 Sandia National Laboratories

For the U.S. Department of Energy

1515 Eubank SE

Albuquerque, NM, 87123

Ship to:

Omega Point Laboratories, Inc

16015 Shady Falls Road

Elmendorf

TX 78112-9784

United States

RMA# or RGA#

Deliver to:

Deggary N. Priest

Phone:

210-635-8100

Building:

Room:

Mail Stop:

Company:

Omega Point Laboratories

Department:

Address Type:

Unclassified

Date Due at Destination:

2/27/2005

Production Related:

No

SHIPPER

45687

Commercial Invoice

Status: Waiting for Approval

Origination Site:

SA

Form filled out by:

WALLACE, SAMUEL T.

Phone:

5058440225

Date Prepared:

2005-1-27

Requester:

WALLACE, SAMUEL T.

Phone:

5058440225

Org. #:

06113

For Shipment Processing Use

Date Shipped:

Carrier:

None Selected

Mode:

None Selected

Contacted Yes No

Bill of Lading No.:

Total # of Pkgs:

0

Total Weight:

0.0 lbs

Total Cubic Dim:

0.0

Advance Notification

0.0

Auvance Notification

Name and Phone:

741 Number:

ATS:

TID Numbers:

RCT Initial/Dates

Reason/Authority: Analysis / Evaluation / Testing

Return Date: NONE

Authority Number:

Freight Charge Payment: Sandia Pays

If shipping controlled property to a new Sandia location

Destination Bldg:

Room:

Project: 73766

Task: 01.03

Account:

Carrier: NONE

If shipping to international destination:

Import duties and taxes will be paid by my project/task:

Export Authorization:

No freight charge reason: NONE

Is material being shipped from the Shipping Department building or the 6000 Igloo? Yes

Shipment Comments: my repack items, if needed

Transportation Pickup Requested: Yes

Questions about pickup call Dispatcher 844-1448 non-hazardous materials, 844-2556 hazardous materials.

Shipper's Export Declaration prepared:

Total Shipment Quantity and Value:	46	\$9, Rage 467

Line Item#	Description/Comments For temporary transfer of items to international destinations, include item Manufacturer's Name, Category Domestic or Foreign, and Serial Number.	Classification Category/level	Qty	Unit	Unit Value	Total \$
1	Description: Thermocouples Comments:	Unclassified	46	EACH	\$200.00	\$9,200.0

				Dimensions					
Quantity	Type	Contents	Weight	L	W	Н	D	Cubic Feet	



Operated for the U.S. Department of Energy by Sandia Corporation

Albuquerque, New Mexico 87185-0706

Tel (505) 844-2464, FAX (505) 844-0240 Internet: bllevin@sandia.gov

January 27, 2005

Deggary N. Priest, President Omega Point Laboratories, Inc. 16015 Shady Falls Road Elmendorf, TX 78112-9784 (210) 635-8100

Re: Quick Disconnect Thermocouples

Dear Deg,

Please find the forty-six thermocouples enclosed for installation and insulation thermal testing of the junction boxes. The Primary Standards Laboratory at SNL verified calibration of each of the thermocouples and have provided a certificate of uncertainty over a range of 70°F to 1000°F for each thermocouple. Please find enclosed copies of these certificates along with calibration stickers. Each sticker can be attached to its associated thermocouple near the connector end following the test to minimize interference during assembly and testing.

Yours truly,

Sure

Bruce L. Levin

BLL/bll Copy: file

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 469

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

File No. 51536 *LIMITED*

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL / NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105003

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 470

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51537 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

a Jans

Date received: 01/14/05 Dates tested: 01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 471

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

File No. 51538

LIMITED

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 472

File No. 51539

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

a. Douch Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 473

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51540 *LIMITED*

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified: Expires:

January 18, 2005

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

a. South

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Page 474

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51541 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified: Expires:

January 18, 2005

January 18, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested: 01/18/05

Date received: 01/14/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Page 475

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51542 *LIMITED*

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: 40% ± 10%

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05

for the scope of accreditation under Lab Code 105002

Page 476

File No. 51543

LIMITED

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL / NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/18/05 Page 1 of 2

CLIENT/PROJECT NAME SAMOLIA NATILALISPL CLIENT/PROJECT NUMBER 14790-125263, 6446

BEPORT NUMBER 2695 . 14790/0PC DATE RECEIVED 278 2-1-65

DATE RECEIVED_

	REMARKS		To's sent to Sandia to Calibration															
2-1-05			To's sent to Sandia for Calibration Using Transmittal # 1126 dated 1/11/05															
					<u> </u>													
												4-11111		- III - SA	1 500010			-
	Щ	Reject																
DATE INSPECTED_INSPECTED BY:	ACCEPTANCE	Accept Hold																
		Accept		\searrow														
	CONTAINER			600														
RECEIVED FROM Sandia Natil Lalis PROJECT LOCATION Omega Point Labs	SAFETY RELATED Y/N			7														
	CERT REC'D X/N			~				\vdash	-			_						_
	CON'tD CE			_					-									
	OC W			48	K.				\vdash									
	I.D. NO.			116-12	though 46													
				KQIN-116-144	SN: 1													
	>	B.O.		Q	-													
	QUANTITY	Order Rec'd B.O		46														
	ठ	Order		46														
	P.O. NO.			4														
			-															
WAO RATONIU	ITEM DESCRIPTION			33														
				och och	-													
				N S														
All				Shermorouples														



Page 478

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51544

LIMITED

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/18/05

File No. 51544

Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 479

File No. 51545

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

January 18, 2006 Expires:



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 480

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51546 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested:

Date received: 01/14/05 01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 481

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51547 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 482

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

File No. 51548 *LIMITED*

Serial No.

13

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Page 483

File No. 51549

LIMITED

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05

Dates tested: 01/18/05

for the scope of accreditation under Lab Code 105002

File No. 51549

Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 484

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51550 *LIMITED*

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL / NM

Certified: Expires:

January 18, 2005

January 18, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05

File No. 51550

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/18/05 Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 485

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51551 *LIMITED*

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006

Humidity: $40\% \pm 10\%$

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02

Approved by: L.J. Aze√edo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/18/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 486

File No. 51552

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/18/05 Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 487

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51553 *LIMITED*

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified: Expires:

January 18, 2005

January 18, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Page 488

File No. 51554

LIMITED

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No. Procedure No.

Lab Conditions:

CP - TC (07/22/98)

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005 January 18, 2006

Expires:

Humidity: $40\% \pm 10\%$

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

> Uncertainty Range TC Type

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/18/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Page 489

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51555 *LIMITED*

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 18, 2005

Expires:

January 18, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

a Saint Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 01/18/05 Dates tested:

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/18/05

File No. 51555

Page 1 of 2

Page 490

File No. 51556

LIMITED

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified: Expires:

January 26, 2005

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05 Page 1 of 2

Page 491

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51557

LIMITED

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: 40% ± 10%

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

File No. 51557

Page 1 of 2

Page 492

File No. 51558

LIMITED

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

January 26, 2006 Expires:

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 493 CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

CP - TC (07/22/98)

Procedure No. Lab Conditions:

Temperature:

23 °C ± 2 °C

File No. 51559 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Page 1 of 2

Copy to: Submitting organization

Department 02541 file

a. Sans

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05

File No. 51559

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 494

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51560

LIMITED

Model No.

KQIN-116-144

Serial No.

25

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05 Page 1 of 2 File No. 51560

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 495

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

26

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51561 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 496

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51562 *LIMITED*

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested: 01/26/05

Date received: 01/14/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 497

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51563 *LIMITED*

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: 40% ± 10%

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 498

File No. 51564

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: 23 °C ± 2 °C

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested: 01/26/05

Date received: 01/14/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 499

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51565 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested:

Date received: 01/14/05 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05 Page 1 of 2 File No. 51565

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 500

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51566 *LIMITED*

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

Humidity: $40\% \pm 10\%$

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 501

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

LIMITED

File No. 51567

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

File No. 51567

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05 Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 502

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51568 *LIMITED*

Model No. Serial No.

KQIN-116-144

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Uncertainty

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 503

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

34

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51569 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 504

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

35

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51570 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL / NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 505

File No. 51571

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 506

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

37

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51572 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 507

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51573 *LIMITED*

Model No.

KQIN-116-144 38

Serial No. Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 508

CERTIFICATE

THERMOCOUPLE TYPE K - STD

File No. 51574 *LIMITED*

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Dates tested: 01/26/05

Date received: 01/14/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 509

File No. 51575

LIMITED

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

40

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 0254

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 510

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51576 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 511

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

File No. 51577 *LIMITED*

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

January 26, 2006 Expires:

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

> Uncertainty TC Type Range

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05 Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05 File No. 51577 Page 1 of 2

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 512

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51578 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 513

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

Serial No.

Procedure No.

CP-TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51579 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested: 01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 514

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KOIN-116-144

Serial No.

45

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

File No. 51580 *LIMITED*

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006

The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program for the scope of accreditation under Lab Code 105002

01/26/05

Sandia National Laboratories, Albuquerque, New Mexico 87185-0665

Page 515

CERTIFICATE

THERMOCOUPLE TYPE K - STD

Model No.

KQIN-116-144

File No. 51581 *LIMITED*

Serial No.

46

Procedure No.

CP - TC (07/22/98)

Lab Conditions:

Temperature: $23 \, ^{\circ}\text{C} \pm 2 \, ^{\circ}\text{C}$

Humidity: $40\% \pm 10\%$

Submitted by:

Organization 06113

SNL/NM

Certified:

January 26, 2005

Expires:

January 26, 2006



The thermocouple was calibrated over the temperature range of 71 °F to 1000 °F by comparison with a Standard Platinum Resistance Thermometer (SPRT). The thermocouple was calibrated in the 9122 Dry Well, with an immersion of 6 inches. The probe mV output was measured with an 8508A Fluke Multimeter. Both the SPRT and the Multimeter have calibrations that are traceable to the National Institute of Standards and Technology (NIST) or to intrinsic standards. The thermocouple type, temperature range calibrated over and the uncertainty of a confidence level of k=2 is as follows:

TC Type

Range

Uncertainty

K

70 °F to 1000 °F

 \pm (4 °F or 0.75% of reading) (whichever is greater)

NOTES: The tolerance statement applies only to the thermocouple, and does not include any instrument used by the owner to measure it.

The results relate only to the items tested or calibrated.

Metrologist: A. Sanchez, 02541

Approved by: L.J. Azevedo, 02541

Manager

Copy to: Submitting organization

Department 02541 file

Date received: 01/14/05 Dates tested:

01/26/05

Accredited by the National Voluntary Laboratory Accreditation Program

01/26/05

MEASUREMENTS STANDARDS PROGRAM SANDIA NATIONAL LABORATORIES Albuquerque, New Mexico

<u>General Traceability Statement</u>: Values and the associated uncertainties supplied by the Measurements Standards Program (MSP) are traceable to one or more of the following:

- The values of the units (either base or derived) maintained and disseminated by the National Institute of Standards and Technology (United States of America) or, in special cases and where appropriate, to the National Standards Laboratory of another nation;
- 2. The accepted value(s) of fundamental physical phenomena (intrinsic standards);
- 3. Ratio(s) or other non-maintained standards established by either a self-calibration and/or a direct calibration technique;
- 4. Standards maintained and disseminated by the MSP in special cases and where warranted;
- 5. Values and uncertainties arising from participation in a National Measurement System.

Because of inherent complexity in the calibration process and the uncertainty contribution by both standards and calibrating instruments, traceability always requires evaluation of a "traceability tree." A "traceability tree" analysis can be assembled for a specific calibration and valid for a particular and specific point in time. The "traceability tree" will include copies of relevant certificates and reports, excerpted as appropriate for brevity. However, the cost of preparation of the "traceability tree" will be charged to the requester.

- Note 1: This certificate or report shall not be reproduced except in full without the advance written approval of the Measurement Standards Program at Sandia National Laboratories.
- Note 2: For National Voluntary Laboratory Accreditation Program (NVLAP) accredited capabilities, the MSP at Sandia National Laboratories is accredited by NVLAP for the specific scope of accreditation under Laboratory Code 105002. This certificate or report shall not be used by the customer to claim product endorsement by NVLAP or any agency of the U. S. Government.
- Note 3: The as received condition of the standard, set of standards, or measurement equipment described herein was as expected, unless otherwise noted in the body of the certificate or report.

General.Doc 3/10/96, Revision 2 Appendix H

PHOTOGRAPHS







#1: Deck under construction.



#2: Assembling conduits.



#3: Conduit 1A.



#4: LB on conduit 1A.



#5: LB on conduit 1A.



#6: Conduit 1B.





#7: LB on conduit 1B.



#9: Conduit 1C.



#11: LB on conduit 1F.



#8: LB on conduit 1B.



#10: LB on conduit 1C.



#12: LB on conduit 1C.





#13: Conduit 1D.





#15: LB on conduit 1D.



#16: LB on conduit 1D.



#17: Conduit 1E.



#18: LB on conduit 1E.





#19: Conduit 1F.



#20: Support 1G.



#21: Support 1H.



#22: JB attachment welds.



#23: Junction box.



#24: Junction box.





#25: JB thermocouples.



#26: JB with supports.



#27: Typical TC attachments.



#28: Typical deck penetration.



#29: Joint on conduit 1A.




#30: Cladding conduit 1A.





#31: Cladding conduit 1B.



#32: Cladding the LB on conduit 1B.



#33: Conduit 1B completed.



#34: Conduit 1B joint cover.



#35: Cladding LB on conduit 1C.



#36: Cladding LB on conduit 1C.






#37: Cladding overlap on conduit 1C.



#38: Banding overlap on conduit 1C.



#39: Cladding elbow on conduit 1D.



#40: Cladding LB on conduit 1D.



#41: Conduit 1D completed.



#42: Cladding LB on conduit 1E.





#43: Cladding LB on conduit 1E.



#44: Cladding elbow on conduit 1F.



#45: Cladding elbow on conduit 1F.



#46: Cladding overlap on conduit 1F.



#47: Cladding support 1G.



#48: Stuffing at end of 1G.





#49: Cladding support 1H.



#50: Support 1H completed.



#51: 1H end details.



#52: Cladding Junction Box.



#53: Cladding sides of JB.



#54: Cladding JB supports.





#55: Stitching seams on JB insulation.



#56: Cladding conduit 1A.



#57: Conduits 1A & 1E completed.



#58: Conduits 1A & 1E completed.



#59: Conduits 1B & 1F completed.



#60: Conduits 1B & 1F completed.





#61: Conduit 1B completed.



#62: Conduit 1C completed.



#63: Conduit 1C completed.



#64: Conduit 1D completed.



#65: Bottom view of conduit 1D.



#66: Support 1G completed.





#67: Support 1G completed.



#68: Support 1H completed.



#69: Support 1H completed.



#70: JB completed.



#71: JB completed.



#72: Lifting specimen onto furnace.





#73: Lowering onto furnace.



#74: Lowering onto furnace.



#75: Lowering onto furnace.



#76: Test specimen.



#77: Test specimen.



#78: Test specimen.





#79: Test furnace overhead view.



#80: Top surface of specimen.



#81: Top surface of specimen.



#82: Typical furnace TC.



#83: Furnace TC next to conduit E.



#84: Furnace TCs.





#85: Specimens inside furnace.



#86: Specimens inside furnace.



#87: Top side, conduit 1A.



#88: Top side, conduit 1C.



#89: Top side, conduit 1D.



#90: Top side, conduits 1F & 1B.





#91: Top side, item 1G.



#92: Top side, conduit 1F.



#93: Top side, conduit 1B.



#94: Top side, junction box.



#95: Start of test.



#96: QA team during test.







#97: End of test.



#98: Lifting specimen from furnace.




#99: Specimen after fire test.



#100: Specimen after fire test.



#101: Gap in conduit 1A.



#102: Gap in conduit 1A.







#103: Junction box still hot.



#104: Gap in conduit 1A insulation.



#105: Conduit 1C hot.



#106: Conduit 1C hot.



#107: Opening in conduit 1D.



#108: Item 1G hot.





#109: Item 1H hot.



110: Junction box hot.



#111: JB support cover gap.



#112: Conduits 1B & 1F hot.



#113: Specimen ready for hose stream.



#114: Adjusting nozzle flow.





#115: Hose stream test.



#116: Hose stream test.



#117: Hose stream test.



#118: Items 1A & 1E after hose stream.



#119: Items 1A & 1E after hose stream.



#120: Items 1A & 1E after hose stream.





#121: Items 1B & 1F after hose stream.



122: Items 1B & 1F after hose stream.



#123: Items 1B & 1F after hose stream.



#124: Items 1B & 1F after hose stream.



#125: Item 1C after hose stream.



#126: Item 1D after hose stream.





#127: Item 1G after hose stream.



#128: Items 1G & 1H after hose stream.



#129: Item 1H after hose stream.



#130: JB after hose stream.



#131: JB supports after hose stream.



#132: JB with insulation removed.





#133: Conduit 1D after hose stream.



#134: Conduit 1A with collar removed.



#135: Conduit 1A gap.



#136: 2.5" gap in conduit 1A after collar was removed.



#137: Gap on 1A with collar removed.



#138: Conduit 1A with insulation off.





#139: Conduit 1A LB with insulation off.



#140: Open joint on conduit 1B.



#141: Conduit 1B joint at LB.



#142: Gap under collar on conduit 1B.



#143: Gap in conduit 1C.



#144: Conduit 1C with insulation off.





#145: Open joint in conduit 1D.



#146: Conduit 1E with collar removed.



#147: Conduit 1E with collar removed.



#148: Conduit 1E with insulation removed.



#149: Open overlap joint on 1F.

