

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE	FREQUENCY
<p>SR 3.6.1.3.11 -----NOTES----- Only required to be met in MODES 1, 2, and 3. -----</p> <p>Verify the combined leakage rate for all secondary containment bypass leakage paths is ≤ 9 scfh when pressurized to $\geq P_a$.</p>	<p>In accordance with the Primary Containment Leakage Rate Testing Program.</p>
<p>SR 3.6.1.3.12 -----NOTES----- Only required to be met in MODES 1, 2, and 3. -----</p> <p>Verify leakage rate through each MSIV is ≤ 100 scfh and ≤ 300 scfh for the combined leakage including the leakage from the MS Line Drains when the MSIVs are tested at ≥ 22.5 psig or P_a and the MS Line Drains are tested at P_a.</p>	<p>In accordance with the Primary Containment Leakage Rate Testing Program.</p>

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE	FREQUENCY
SR 3.6.1.3.10 Remove and test the explosive squib from each shear isolation valve of the TIP System.	24 months on a STAGGERED TEST BASIS
SR 3.6.1.3.11 -----NOTES----- Only required to be met in MODES 1, 2, and 3. ----- Verify the combined leakage rate for all secondary containment bypass leakage paths is ≤ 9 scfh when pressurized to $\geq P_a$.	In accordance with the Primary Containment Leakage Rate Testing Program.
SR 3.6.1.3.12 -----NOTES----- Only required to be met in MODES 1, 2, and 3. ----- Verify leakage rate through each MSIV is ≤ 100 scfh and ≤ 300 scfh for the combined leakage including the leakage from the MS Line Drains, when the MSIVs are tested at ≥ 22.5 psig or P_a and the MS Line Drains are tested at P_a .	In accordance with the Primary Containment Leakage Rate Testing Program.

(continued)