



South Texas Project Electric Generating Station P.O. Box 289 Wadsworth, Texas 77483


April 3, 2001  
NOC-AE-01001068  
File No.: G21.02  
10CFR50.36  
STI: 31264480

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
Washington, DC 20555-0001

South Texas Project  
Unit 2  
Docket No. STN 50-499  
Unit 2 Cycle 9 Core Operating Limits Report

In accordance with Technical Specification 6.9.1.6.d, the attached Core Operating Limits Report is submitted for South Texas Project Unit 2 Cycle 9. The report is identified as revision 1, but there are no technical changes from the original report. Revision 0 was issued for internal use by the South Texas Project. Revision 1 only reconstructed some of the figures to improve the quality of the graphics.

If there are any questions concerning this report, please contact Mr. A. W. Harrison at (361) 972-7298, or me at (361) 972-7795.

  
for David A. Leazar  
Director,  
Nuclear Fuel & Analysis

kaw

Attachment: Unit 2 Cycle 9 Core Operating Limits Report

cc: Licensing Library  
RMS (w/o attachment)

A001

cc:

Ellis W. Merschoff  
Regional Administrator, Region IV  
U.S. Nuclear Regulatory Commission  
611 Ryan Plaza Drive, Suite 400  
Arlington, Texas 76011-8064

John A. Nakoski  
Addressee Only  
U. S. Nuclear Regulatory Commission  
Project Manager, Mail Stop OWFN/7-D-1  
Washington, DC 20555-0001

Mohan C. Thadani  
Addressee Only  
U. S. Nuclear Regulatory Commission  
Project Manager, Mail Stop OWFN/7-D-1  
Washington, DC 20555

Cornelius F. O'Keefe  
c/o U. S. Nuclear Regulatory Commission  
P. O. Box 910  
Bay City, TX 77404-0910

A. H. Gutterman, Esquire  
Morgan, Lewis & Bockius  
1800 M. Street, N.W.  
Washington, DC 20036-5869

M. T. Hardt/W. C. Gunst  
City Public Service  
P. O. Box 1771  
San Antonio, TX 78296

A. Ramirez/C. M. Canady  
City of Austin  
Electric Utility Department  
721 Barton Springs Road  
Austin, TX 78704

Jon C. Wood  
Matthews & Branscomb  
112 East Pecan, Suite 1100  
San Antonio, Texas 78205-3692

Institute of Nuclear Power  
Operations - Records Center  
700 Galleria Parkway  
Atlanta, GA 30339-5957

Richard A. Ratliff  
Bureau of Radiation Control  
Texas Department of Health  
1100 West 49th Street  
Austin, TX 78756-3189

R. L. Balcom/D. G. Tees  
Reliant Energy, Inc.  
P. O. Box 1700  
Houston, TX 77251

C. A. Johnson/R. P. Powers  
AEP - Central Power and Light Company  
P. O. Box 289, Mail Code: N5012  
Wadsworth, TX 77483

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
Washington, D.C. 20555-0001



**SOUTH TEXAS PROJECT  
ELECTRIC GENERATING STATION  
UNIT 2 CYCLE 9  
CORE OPERATING LIMITS REPORT**

March 2001

## 1.0 CORE OPERATING LIMITS REPORT

This Core Operating Limits Report for STPEGS Unit 2 Cycle 9 has been prepared in accordance with the requirements of Technical Specification 6.9.1.6. The core operating limits have been developed using the NRC-approved methodologies specified in Technical Specification 6.9.1.6.

The Technical Specifications affected by this report are:

- |    |           |  |
|----|-----------|--|
| 1) | 2.1       | SAFETY LIMITS                            |
| 2) | 2.2       | LIMITING SAFETY SYSTEM SETTINGS          |
| 3) | 3/4.1.1.3 | MODERATOR TEMPERATURE COEFFICIENT LIMITS |
| 4) | 3/4.1.3.5 | SHUTDOWN ROD INSERTION LIMITS            |
| 5) | 3/4.1.3.6 | CONTROL ROD INSERTION LIMITS             |
| 6) | 3/4.2.1   | AFD LIMITS                               |
| 7) | 3/4.2.2   | HEAT FLUX HOT CHANNEL FACTOR             |
| 8) | 3/4.2.3   | NUCLEAR ENTHALPY RISE HOT CHANNEL FACTOR |
| 9) | 3/4.2.5   | DNB PARAMETERS                           |

## 2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in Section 1.0 are presented below.

COLR Section 2.8 provides for an alternate Minimum Measured Reactor Coolant System Flow limit consistent with plugging up to 10% of steam generator tubes and Departure from Nucleate Boiling (DNB) requirements. When using the alternate minimum flow limit, the  $T_{avg}$  limit is reduced. The setpoint and constant values for OPAT and OTAT are also revised accordingly when this alternate mode of operation is entered.

### 2.1 SAFETY LIMITS (Specification 2.1):

- 2.1.1 The combination of THERMAL POWER, pressurizer pressure, and the highest operating loop coolant temperature ( $T_{avg}$ ) shall not exceed the limits shown in Figure 1, or in Figure 2 when operating under alternate operating criteria consistent with reduced Reactor Coolant System Flow as addressed in COLR Section 2.8.

## 2.2 LIMITING SAFETY SYSTEM SETTINGS (Specification 2.2):

2.2.1 The Loop design flow for Reactor Coolant Flow-Low is 95,400 gpm (or 92,500 gpm for alternate operation with reduced RCS flow).

2.2.2 The Over-temperature  $\Delta T$  and Over-power  $\Delta T$  setpoint parameter values are listed below:

### Over-temperature $\Delta T$ Setpoint Parameter Values

- $\tau_1$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_1 = 8$  sec
- $\tau_2$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_2 = 3$  sec
- $\tau_3$  measured reactor vessel  $\Delta T$  lag time constant,  $\tau_3 = 0$  sec
- $\tau_4$  measured reactor vessel average temperature lead/lag time constant,  $\tau_4 = 28$  sec
- $\tau_5$  measured reactor vessel average temperature lead/lag time constant,  $\tau_5 = 4$  sec
- $\tau_6$  measured reactor vessel average temperature lag time constant,  $\tau_6 = 0$  sec
- $K_1$  Overtemperature  $\Delta T$  reactor trip setpoint,  $K_1 = 1.14$  or  $K_1 = 1.13$  for alternate operation with reduced RCS flow
- $K_2$  Overtemperature  $\Delta T$  reactor trip setpoint  $T_{avg}$  coefficient,  $K_2 = 0.028/^\circ F$
- $K_3$  Overtemperature  $\Delta T$  reactor trip setpoint pressure coefficient,  $K_3 = 0.00143/\text{psig}$
- $T'$  Nominal full power  $T_{avg}$ ,  $T' \leq 590.0$   $^\circ F$  (including alternate operation with reduced RCS flow)
- $P'$  Nominal RCS pressure,  $P' = 2235$  psig
- $f_1(\Delta I)$  is a function of the indicated difference between top and bottom detectors of the power-range neutron ion chambers; with gains to be selected based on measured instrument response during plant startup tests such that;
  - (1) For  $q_t - q_b$  between -70% and +8%, or +6% for alternate operation with reduced RCS flow,  $f_1(\Delta I) = 0$ , where  $q_t$  and  $q_b$  are percent RATED THERMAL POWER in the top and bottom halves of the core respectively, and  $q_t + q_b$  is total THERMAL POWER in percent of RATED THERMAL POWER;
  - (2) For each percent that the magnitude of  $q_t - q_b$  exceeds -70%, the  $\Delta T$  Trip Setpoint shall be automatically reduced by 0.0% of its value at RATED THERMAL POWER; and
  - (3) For each percent that the magnitude of  $q_t - q_b$  exceeds +8%, or +6% for alternate operation with reduced RCS flow, the  $\Delta T$  Trip Setpoint shall be automatically reduced by 2.65% of its value at RATED THERMAL POWER.



### Over-power $\Delta T$ Setpoint Parameter Values

- $\tau_1$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_1 = 8$  sec
- $\tau_2$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_2 = 3$  sec
- $\tau_3$  measured reactor vessel  $\Delta T$  lag time constant,  $\tau_3 = 0$  sec
- $\tau_6$  measured reactor vessel average temperature lag time constant,  $\tau_6 = 0$  sec
- $\tau_7$  Time constant utilized in the rate-lag compensator for  $T_{avg}$ ,  $\tau_7 = 10$  sec
- $K_4$  Overpower  $\Delta T$  reactor trip setpoint,  $K_4 = 1.08$  or  $K_4 = 1.07$  for alternate operation with reduced RCS flow)
- $K_5$  Overpower  $\Delta T$  reactor trip setpoint  $T_{avg}$  rate/lag coefficient,  $K_5 = 0.02/^{\circ}\text{F}$  for increasing average temperature, and  $K_5 = 0$  for decreasing average temperature
- $K_6$  Overpower  $\Delta T$  reactor trip setpoint  $T_{avg}$  heatup coefficient  $K_6 = 0.002/^{\circ}\text{F}$  for  $T > T''$  and,  $K_6 = 0$  for  $T \leq T''$
- $T''$  Indicated full power  $T_{avg}$ ,  $T'' \leq 590.0$   $^{\circ}\text{F}$  (including alternate operation with reduced RCS flow)
- $f_2(\Delta I) = 0$  for all  $(\Delta I)$

### 2.3 MODERATOR TEMPERATURE COEFFICIENT (Specification 3.1.1.3):

- 2.3.1 The BOL, ARO, MTC shall be less positive than the limits shown in Figure 3.
- 2.3.2 The EOL, ARO, HFP, MTC shall be less negative than  $-6.12 \times 10^{-4} \Delta k/k/^{\circ}\text{F}$ .
- 2.3.3 The 300 ppm, ARO, HFP, MTC shall be less negative than  $-5.26 \times 10^{-4} \Delta k/k/^{\circ}\text{F}$  (300 ppm Surveillance Limit).

where: BOL stands for Beginning-of-Cycle Life  
 EOL stands for End-of-Cycle Life  
 ARO stands for All Rods Out  
 HFP stands for Hot Full Power (100% RATED THERMAL POWER)  
 HFP vessel average temperature is 590  $^{\circ}\text{F}$

### 2.4 ROD INSERTION LIMITS (Specification 3.1.3.5 and 3.1.3.6):

- 2.4.1 All banks shall have the same Full Out Position (FOP) of at least 249 steps withdrawn but not exceeding 259 steps withdrawn.
- 2.4.2 The Control Banks shall be limited in physical insertion as specified in Figure 4.
- 2.4.3 Individual Shutdown bank rods are fully withdrawn when the Bank Demand Indication is at the FOP and the Rod Group Height Limiting Condition for Operation is satisfied (T.S. 3.1.3.1).



## 2.5 AXIAL FLUX DIFFERENCE (Specification 3.2.1):

- 2.5.1 AFD limits as required by Technical Specification 3.2.1 are determined by CAOC Operations with an AFD target band of +5, -10%.
- 2.5.2 The AFD shall be maintained within the ACCEPTABLE OPERATION portion of Figure 5, as required by Technical Specifications.

## 2.6 HEAT FLUX HOT CHANNEL FACTOR (Specification 3.2.2):

- 2.6.1  $F_Q^{RTP} = 2.55$ .
- 2.6.2  $K(Z)$  is provided in Figure 6.
- 2.6.3 The  $F_{xy}$  limits for RATED THERMAL POWER ( $F_{xy}^{RTP}$ ) within specific core planes shall be:
- 2.6.3.1 Less than or equal to 2.102 for all cycle burnups for all core planes containing Bank "D" control rods, and
  - 2.6.3.2 Less than or equal to the appropriate core height-dependent value from Table 1 for all unrodded core planes.
  - 2.6.3.3  $PF_{xy} = 0.2$ .
- These  $F_{xy}$  limits were used to confirm that the heat flux hot channel factor  $F_Q(Z)$  will be limited by Technical Specification 3.2.2 assuming the most-limiting axial power distributions expected to result for the insertion and removal of Control Banks C and D during operation, including the accompanying variations in the axial xenon and power distributions, as described in WCAP-8385. Therefore, these  $F_{xy}$  limits provide assurance that the initial conditions assumed in the LOCA analysis are met, along with the ECCS acceptance criteria of 10 CFR 50.46.

For Unit 2 Cycle 9, the  $L(Z)$  penalty is not applied (i.e.,  $L(Z) = 1.0$  for all core elevations).

## 2.7 ENTHALPY RISE HOT CHANNEL FACTOR (Specification 3.2.3):

	<u>Standard Fuel</u> *	<u>VANTAGE 5H / RFA Fuel</u> **
2.7.1	WITHOUT RCS Loop-specific Temperature Calibrations:	
	$F_{\Delta H}^{RTP} = 1.46$	$F_{\Delta H}^{RTP} = 1.53$
	WITH RCS Loop-specific Temperature Calibrations:	
	$F_{\Delta H}^{RTP} = 1.49$	$F_{\Delta H}^{RTP} = 1.557$
2.7.2	$PF_{\Delta H} = 0.3$	$PF_{\Delta H} = 0.3$

\* Applies to fuel Region 5B.

\*\* Applies to fuel Regions 9A, 9B, 10A, 10B, 11A and 11B.



## 2.8 DNB PARAMETERS (Specification 3.2.5):

2.8.1 The following DNB-related parameters shall be maintained within the following limits\*\*\*\*:

- a. Reactor Coolant System  $T_{avg}$ ,  $\leq 595$  °F\*,  
(or  $\leq 593$ °F\* with reduced RCS flow of COLR 2.8.1.c)
- b. Pressurizer Pressure,  $> 2200$  psig\*\*,
- c. Minimum Measured Reactor Coolant System Flow:

Precision calorimetric RCS flow measurement

$\geq 392,300$  gpm\*\*\*

(or  $\geq 380,500$  gpm\*\*\* with reduced RCS  $T_{avg}$  of COLR 2.8.1.a)

OR

Elbow tap RCS flow measurement

$\geq 389,700$  gpm\*\*\*

(or  $\geq 377,800$  gpm\*\*\* with reduced RCS  $T_{avg}$  of COLR 2.8.1.a)

\* Includes a 1.9 °F measurement uncertainty per Reference 3.3.

\*\* Limit not applicable during either a Thermal Power ramp in excess of 5% of RTP per minute or a Thermal Power step in excess of 10% RTP. Includes a 10.7 psi measurement uncertainty as read on QDPS display per Reference 3.4.

\*\*\* Includes a 2.8% flow measurement uncertainty, which is supported by the safety analyses bases. Applicable to Model E and Delta 94 Steam Generators.

\*\*\*\* Includes a 2.1% flow measurement uncertainty, which is supported by evaluation to the safety analyses bases. Applicable to Model E Steam Generators.


\*\*\*\*\* A discussion of the processes to be used to take these readings is provided in the basis for Technical Specification 3.2.5

## 3.0 REFERENCES

- 3.1 Letter from R. A. Wiley (Westinghouse) to D. F. Hoppes (STPNOC), "South Texas Project Nuclear Operating Company, South Texas Project Electric Generating Station Unit 2 Cycle 9 Final Unbound Core Operating Limits Report (COLR)," 01TG-G-016 (ST-UB-NOC-01002113), March 2001.
- 3.2 NUREG-1346, Technical Specifications, South Texas Project Unit Nos. 1 and 2.
- 3.3 STPNOC Calculation ZC-7035, Rev. 1, "Loop Uncertainty Calculation for RCS  $T_{avg}$  Instrumentation," October 19, 1998.
- 3.4 STPNOC Calculation ZC-7032, Rev. 2, "Loop Uncertainty Calculation for Narrow Range Pressurizer Pressure Monitoring Instrumentation," October 17, 2000.



Figure 1  
Reactor Core Safety Limit - Four Loops in Operation



**Figure 2**  
**Reactor Core Safety Limit - Four Loops in Operation (Alternate)**




Figure 3  
MTC versus Power Level






Figure 4  
Control Rod Insertion Limits versus Power Level




Control Bank A is already withdrawn to Full Out Position. Fully withdrawn region shall be the condition where shutdown and control banks are at a position within the interval of 249 and  $\leq 259$  steps withdrawn, inclusive.

**Figure 5**  
**AFD Limits versus Rated Thermal Power**



**Figure 6**  
**K(Z) - Normalized  $F_Q(Z)$  versus Core Height**



**Table 1 (Part 1 of 2)**  
**Unrodded  $F_{xy}$  for Each Core Height\***  
**for Cycle Burnups Less Than 10,500 MWD/MTU**

<u>Core Height (Ft.)</u>	<u>Axial Point</u>	<u>Unrodded <math>F_{xy}</math> SGTP <math>\leq</math> 10%</u>	<u>Core Height (Ft.)</u>	<u>Axial Point</u>	<u>Unrodded <math>F_{xy}</math> SGTP <math>\leq</math> 10%</u>
14.00	1	4.516	6.80	37	1.912
13.80	2	3.851	6.60	38	1.906
13.60	3	3.186	6.40	39	1.904
13.40	4	2.521	6.20	40	1.903
13.20	5	2.216	6.00	41	1.902
13.00	6	2.025	5.80	42	1.902
12.80	7	2.047	5.60	43	1.902
12.60	8	2.041	5.40	44	1.905
12.40	9	2.035	5.20	45	1.909
12.20	10	2.020	5.00	46	1.915
12.00	11	1.998	4.80	47	1.923
11.80	12	1.982	4.60	48	1.931
11.60	13	1.975	4.40	49	1.933
11.40	14	1.973	4.20	50	1.931
11.20	15	1.969	4.00	51	1.925
11.00	16	1.965	3.80	52	1.920
10.80	17	1.958	3.60	53	1.917
10.60	18	1.952	3.40	54	1.913
10.40	19	1.946	3.20	55	1.908
10.20	20	1.943	3.00	56	1.896
10.00	21	1.937	2.80	57	1.878
9.80	22	1.934	2.60	58	1.847
9.60	23	1.935	2.40	59	1.809
9.40	24	1.934	2.20	60	1.770
9.20	25	1.932	2.00	61	1.755
9.00	26	1.931	1.80	62	1.748
8.80	27	1.932	1.60	63	1.747
8.60	28	1.931	1.40	64	1.742
8.40	29	1.934	1.20	65	1.749
8.20	30	1.937	1.00	66	1.782
8.00	31	1.943	0.80	67	1.930
7.80	32	1.945	0.60	68	2.339
7.60	33	1.945	0.40	69	2.877
7.40	34	1.940	0.20	70	3.416
7.20	35	1.932	0.00	71	3.954
7.00	36	1.921			

\* For Unit 2 Cycle 9, the L(Z) penalty is not applied (i.e., L(Z) = 1.0 for all core elevations).



**Table 1 (Part 2 of 2)**  
**Unrodded F<sub>xy</sub> for Each Core Height\***  
**for Cycle Burnups Greater Than or Equal to 10,500 MWD/MTU**

Core Height (Ft.)	Axial Point	Unrodded F <sub>xy</sub> SGTP ≤ 10%	Core Height (Ft.)	Axial Point	Unrodded F <sub>xy</sub> SGTP ≤ 10%
14.00	1	5.116	6.80	37	2.138
13.80	2	4.370	6.60	38	2.129
13.60	3	3.624	6.40	39	2.117
13.40	4	2.877	6.20	40	2.104
13.20	5	2.500	6.00	41	2.091
13.00	6	2.239	5.80	42	2.078
12.80	7	2.196	5.60	43	2.064
12.60	8	2.138	5.40	44	2.051
12.40	9	2.093	5.20	45	2.038
12.20	10	2.068	5.00	46	2.028
12.00	11	2.060	4.80	47	2.019
11.80	12	2.049	4.60	48	2.013
11.60	13	2.036	4.40	49	2.002
11.40	14	2.032	4.20	50	1.989
11.20	15	2.032	4.00	51	1.973
11.00	16	2.035	3.80	52	1.960
10.80	17	2.040	3.60	53	1.949
10.60	18	2.044	3.40	54	1.940
10.40	19	2.047	3.20	55	1.929
10.20	20	2.049	3.00	56	1.914
10.00	21	2.050	2.80	57	1.895
9.80	22	2.050	2.60	58	1.872
9.60	23	2.058	2.40	59	1.851
9.40	24	2.068	2.20	60	1.827
9.20	25	2.077	2.00	61	1.829
9.00	26	2.081	1.80	62	1.829
8.80	27	2.081	1.60	63	1.832
8.60	28	2.082	1.40	64	1.855
8.40	29	2.088	1.20	65	1.891
8.20	30	2.101	1.00	66	1.954
8.00	31	2.115	0.80	67	2.146
7.80	32	2.130	0.60	68	2.625
7.60	33	2.139	0.40	69	3.248
7.40	34	2.145	0.20	70	3.870
7.20	35	2.147	0.00	71	4.493
7.00	36	2.144			

\* For Unit 2 Cycle 9, the L(Z) penalty is not applied (i.e., L(Z) = 1.0 for all core elevations).