

SURVEILLANCE REQUIREMENTS (continued)

| SURVEILLANCE | FREQUENCY |
|--|--------------------------------------|
| <p>SR 3.8.1.2 -----NOTES-----</p> <ol style="list-style-type: none"> 1. Performance of SR 3.8.1.7 satisfies this SR. 2. All DG starts may be preceded by an engine prelube period and followed by a warmup period prior to loading. 3. A modified DG start involving idling and gradual acceleration to rated speed may be used for this SR as recommended by the manufacturer. When modified start procedures are not used, the time, voltage, and frequency tolerances of SR 3.8.1.7 must be met. 4. To ensure Operability of an AVR, it must have been aligned to the DG during the performance of SR 3.8.1.2 and SR 3.8.1.3 within the last 60 days, plus any allowance per SR 3.0.2. <p>-----</p> <p>Verify each DG starts from standby conditions and achieves:</p> <ol style="list-style-type: none"> a. Steady state voltage ≥ 4297 V and ≤ 4576 V; and b. Steady state frequency ≥ 59.7 Hz and ≤ 61.2 Hz. | <p>As specified in Table 3.8.1-1</p> |

(continued)

SURVEILLANCE REQUIREMENTS (continued)

| SURVEILLANCE | FREQUENCY |
|--|-------------------------------|
| <p>SR 3.8.1.3 -----NOTES-----</p> <ol style="list-style-type: none"> 1. DG loadings may include gradual loading as recommended by the manufacturer. 2. Momentary transients outside the load range do not invalidate this test. 3. This Surveillance shall be conducted on only one DG at a time. 4. This SR shall be preceded by, and immediately follow without shutdown, a successful performance of SR 3.8.1.2 or SR 3.8.1.7. 5. To ensure Operability of an AVR, it must have been aligned to the DG during the performance of SR 3.8.1.2 and SR 3.8.1.3 within the last 60 days, plus any allowance per SR 3.0.2. <p>-----</p> <p>Verify each DG is synchronized and loaded, and operates for ≥ 60 minutes at a load ≥ 4450 kW and ≤ 4700 kW.</p> | As specified in Table 3.8.1-1 |
| SR 3.8.1.4 Verify each day tank contains ≥ 30 inches of fuel oil. | 31 days |
| SR 3.8.1.5 Check for and remove accumulated water from each day tank. | 31 days |
| SR 3.8.1.6 Verify the fuel oil transfer system operates to transfer fuel oil from storage tank to the day tank. | 31 days |

(continued)

SURVEILLANCE REQUIREMENTS (continued)

| SURVEILLANCE | FREQUENCY |
|--|-----------|
| <p>SR 3.8.1.9 -----NOTE-----</p> <ol style="list-style-type: none"> 1. Credit may be taken for unplanned events that satisfy this SR. 2. To ensure Operability of an AVR, it must have been aligned to the DG during the performance of either SR 3.8.1.9, SR 3.8.1.10, or SR 3.8.1.19 within the last 24 months, plus any allowance per SR 3.0.2. <p>-----</p> <p>Verify each DG rejects a load greater than or equal to its associated single largest post-accident load, and:</p> <ol style="list-style-type: none"> a. Following load rejection, the frequency is ≤ 66.75 Hz; b. Within 4 seconds following load rejection, the voltage is ≥ 4297 V and ≤ 4576 V; and c. Within 4 seconds following load rejection, the frequency is ≥ 59.7 Hz and ≤ 61.2 Hz. | 24 months |
| <p>SR 3.8.1.10 -----NOTE-----</p> <ol style="list-style-type: none"> 1. Credit may be taken for unplanned events that satisfy this SR. 2. To ensure Operability of an AVR, it must have been aligned to the DG during the performance of either SR 3.8.1.9, SR 3.8.1.10, or SR 3.8.1.19 within the last 24 months, plus any allowance per SR 3.0.2. <p>-----</p> <p>Verify each DG, when connected to its bus in parallel with offsite power and operating with inductive loading that offsite power conditions permit, during and following a load rejection of ≥ 4450 kW and ≤ 4700 kW:</p> <ol style="list-style-type: none"> a. Does not trip; and b. Voltage is maintained ≤ 5450 V. | 24 months |

(continued)

SURVEILLANCE REQUIREMENTS (continued)

| SURVEILLANCE | FREQUENCY |
|---|------------------|
| <p>SR 3.8.1.19 -----NOTES-----</p> <ol style="list-style-type: none">1. All DG starts may be preceded by an engine prelube period.2. Credit may be taken for unplanned events that satisfy this SR.3. To ensure Operability of an AVR, it must have been aligned to the DG during the performance of either SR 3.8.1.9, SR 3.8.1.10, or SR 3.8.1.19 within the last 24 months, plus any allowance per SR 3.0.2. <p>-----</p> <p>Verify on an actual or simulated loss of offsite power signal in conjunction with actual or simulated ESF actuation signals:</p> <ol style="list-style-type: none">a. De-energization of emergency buses;b. Load shedding from emergency buses;c. DG auto-starts from standby condition and:<ol style="list-style-type: none">1. energizes permanently connected loads and resets the 4.16 kV bus undervoltage relay logic in ≤ 10 seconds;2. energizes auto-connected emergency loads through the programmed time interval load sequence;3. achieves steady state voltage ≥ 4297 V and ≤ 4576 V;4. achieves steady state frequency ≥ 59.7 Hz and ≤ 61.2 Hz; and5. supplies permanently connected and auto-connected emergency loads for ≥ 5 minutes. | <p>24 months</p> |

(continued)