

5.5 Programs and Manuals (continued)

5.5.16 Containment Leakage Rate Testing Program (continued)

b. Air lock testing acceptance criteria are:

1. Overall air lock leakage rate is $\leq 0.05 L_a$ when tested at $\geq P_a$.
2. For each door, leakage rate is $\leq 0.01 L_a$ when pressurized to ≥ 14.5 psig.

The provisions of SR 3.0.2 do not apply to the test frequencies in the Containment Leakage Rate Testing Program.

The provisions of SR 3.0.3 are applicable to the Containment Leakage Rate Testing Program.

5.6 Reporting Requirements (continued)

5.6.6 PAM Report

When a report is required by Condition B or G of LCO 3.3.10, "Post Accident Monitoring (PAM) Instrumentation," a report shall be submitted within the following 14 days. The report shall outline the preplanned alternate method of monitoring, the cause of the inoperability, and the plans and schedule for restoring the instrumentation channels of the Function to OPERABLE status.

5.6.7 Tendon Surveillance Report

Any abnormal degradation of the containment structure detected during the tests required by the Pre-Stressed Concrete Containment Tendon Surveillance Program shall be reported to the NRC within 30 days. The report shall include a description of the tendon condition, the condition of the concrete (especially at tendon anchorages), the inspection procedures, the tolerances on cracking, and the corrective action taken.

5.6.8 Steam Generator Tube Inspection Report

Within 15 days following the completion of each inservice inspection of steam generator tubes, the number of tubes plugged and/or repaired in each steam generator shall be reported to the Commission in a Special Report.

The complete results of the steam generator tube inservice inspection shall be submitted to the Commission in a Special Report within 12 months following completion of the inspection. This Special Report shall include:

- a. Number and extent of tubes inspected.
- b. Location and percent of wall-thickness penetration for each indication of an imperfection.
- c. Identification of tubes plugged and/or repaired.

Results of steam generator tube and sleeve inspections which fall into Category C-3 shall be reported in a Special Report to the Commission within 30 days and prior to resumption of plant operation and shall provide a description of investigations conducted to determine cause of the tube degradation and corrective measures taken to prevent recurrence.