

## ADMINISTRATIVE CONTROLS

---

### PROCESS CONTROL PROGRAM (Continued)

1. Sufficient information to support the change together with the appropriate analyses or evaluation justifying the change(s) and
  2. A determination that the change will maintain the overall conformance of the solidified waste product to existing requirements of Federal, State, or other applicable regulations.
- b. Shall become effective after the approval of the General Manager Plant Operations.

### 6.14 OFFSITE DOSE CALCULATION MANUAL (ODCM)

6.14.1 The ODCM shall be approved by the Commission prior to implementation.

6.14.2 Licensee-initiated changes to the ODCM:

- a. Shall be documented and records of reviews performed shall be retained as required by the Quality Assurance Program Manual. This document shall contain:
  1. Sufficient information to support the change together with the appropriate analyses or evaluations justifying the change(s) and
  2. A determination that the change will maintain the level of radioactive effluent control required pursuant to 10 CFR 20.1302, 40 CFR Part 190, 10 CFR 50.36a, and Appendix I to 10 CFR Part 50 and not adversely impact the accuracy or reliability of effluent, dose or setpoint calculations.
- b. Shall become effective after the approval of the General Manager Plant Operations.
- c. Shall be submitted to the Commission in the form of a complete, legible copy of the entire ODCM as a part of or concurrent with the Annual Radioactive Effluent Release Report for the period of the report in which any change to the ODCM was made. Each change shall be identified by markings in the margin of the affected pages, clearly indicating the area of the page that was changed, and shall indicate the date (e.g., month/year) the change was implemented.

### 6.15 CONTAINMENT LEAKAGE RATE TESTING PROGRAM

A program shall be established to implement the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J, Option B, as modified by approved exemptions. This program shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program," dated September 1995, except that the next Type A test performed after the May 12, 1991 Type A test shall be performed no later than May 11, 2006.