

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
<p>SR 3.6.1.7.1 -----NOTE----- RHR containment spray subsystems may be considered OPERABLE during alignment and operation for decay heat removal when below the RHR cut in permissive pressure in MODE 3 if capable of being manually realigned and not otherwise inoperable . ----- Verify each RHR containment spray subsystem manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position.</p>	<p>31 days</p>
<p>SR 3.6.1.7.2 Verify each RHR pump develops a flow rate of ≥ 3800 gpm on recirculation flow through the associated heat exchanger to the suppression pool.</p>	<p>In accordance with the Inservice Testing Program</p>
<p>SR 3.6.1.7.3 Verify each RHR containment spray subsystem automatic valve in the flow path actuates to its correct position on an actual or simulated automatic initiation signal.</p>	<p>18 months</p>
<p>SR 3.6.1.7.4 Verify each spray nozzle is unobstructed.</p>	<p>Following activities that could result in nozzle blockage.</p>