

March 28, 2002

Mr. Harold B. Ray
Executive Vice President
Southern California Edison Company
San Onofre Nuclear Generating Station
P.O. Box 128
San Clemente, CA 92674-0128

SUBJECT: SAN ONOFRE NUCLEAR GENERATING STATION (SONGS), UNIT 2 -
UPCOMING STEAM GENERATOR TUBE INSERVICE INSPECTION (TAC NO.
MB4659)

Dear Mr. Ray:

Inservice inspections of steam generator (SG) tubes play a vital role in assuring that adequate structural integrity of the tubes is maintained. As required by the plant Technical Specifications, reporting requirements range from submitting a special report, within 15 days following completion of each inservice inspection of SG tubes, that identifies the number of tubes plugged and/or repaired; to submitting a special report, within 12 months following completion of the inspection, that provides complete results of the SG tube inservice inspection. The special report containing the complete results shall include the following:

1. Number and extent of tubes inspected.
2. Location and percent of wall-thickness penetration for each indication of an imperfection.
3. Identification of tubes plugged and/or repaired.

A phone conference has been arranged with members of your staff to discuss the ongoing results of the SG tube inspections to be conducted during the upcoming SONGS Unit 2 refueling outage. This phone call will occur after the majority of the tubes have been inspected, but before the SG inspection activities have been completed. Enclosed is a list of discussion points to facilitate this phone conference.

H. Ray

- 2 -

In response to a recommendation made in the NRC's Indian Point 2 (IP2) Lessons Learned Task Group report, the NRC staff plans to document a brief summary of the conference call as well as any material that you may have provided to the NRC staff in support of the call.

Sincerely,

/RA/

L. Raghavan, Senior Project Manager, Section 2
Project Directorate IV
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket No. 50-362

Enclosure: As stated

cc w/encl: See next page

H. Ray

- 2 -

In response to a recommendation made in the NRC's Indian Point 2 (IP2) Lessons Learned Task Group report, the NRC staff plans to document a brief summary of the conference call as well as any material that you may have provided to the staff in support of the call.

Sincerely,

/RA/

L. Raghavan, Senior Project Manager, Section 2
Project Directorate IV
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket Nos. 50-361 and 50-362

Enclosure: As stated

cc w/encl: See next page

DISTRIBUTION

PUBLIC	PDIV-2 r/f
	RidsNrrDlpmLpdiv (S.Richards)
RidsNrrPMLRaghavan	RidsNrrLAMMcAllister
RidsNrrDripRorp (R.Dennig)	RidsAcrsAcnwMailCenter
RidsOgcRp	Ted Sullivan
CLauron	ZFu
RidsRgn4MailCenter (K. Kennedy, L. Hurley, D. Bujol)	

ACCESSION NO: ML020940039

OFFICE	PDIV-2/PM	PDIV-1/LA	EMCB	PDIV-2/SC
NAME	LRaghavan	MMcAllister	LLund for: ESullivan	JDonohew forSDembek
DATE	3/28/02	3/28/02	3/28/02	3/28/02

OFFICIAL RECORD COPY

STEAM GENERATOR TUBE INSPECTION DISCUSSION POINTS

PREPARED BY THE OFFICE OF NUCLEAR REACTOR REGULATION

SOUTHERN CALIFORNIA EDISON COMPANY

SAN ONOFRE NUCLEAR GENERATING STATION, UNIT 2

DOCKET NO. 50-362

The following discussion points have been prepared to facilitate the phone conference arranged to discuss the results of the SG tube inspections to be conducted during the upcoming SONGS, Unit 2 refueling outage. This phone call is scheduled to occur towards the end of the planned SG tube inspection interval, but before the unit exits its refueling outage.

It is our expectation that any significant results or relevant trends discussed during the phone conference, as well as any materials provided by your staff to assist us during the phone conference in the understanding of the SG tube results, will be included in one of the special reports required by the plant Technical Specifications.

1. Discuss whether any primary to secondary leakage existed in this unit prior to shutdown.
2. Discuss the results of secondary side hydrostatic tests.
3. For each steam generator (SG), provide a general description of areas examined, including the expansion criteria utilized and type of probe used in each area.
4. For analyzed eddy current results, describe bobbin indications [those not examined with rotating pancake coil (RPC)] and RPC/Plus Point/Cecco indications. Include the following information in the discussion: location, number, degradation mode, disposition, and voltages/depths/lengths of significant indications.
5. Describe repair/plugging plans for the SG tubes that meet the repair/plugging criteria.
6. Discuss the previous history of SG tube inspection results, including any "look backs" performed.
7. Discuss, in general, the new inspection findings.
8. Describe in-situ pressure test plans and results, if applicable and available, including tube selection criteria.
9. Describe tube pull plans and preliminary results, if applicable and available; include tube selection criteria.
10. Discuss the assessment of tube integrity for the previous operating cycle.
11. Discuss the assessment of tube integrity for next operating cycle .

12. Provide the schedule for SG-related activities during the remainder of the current outage.
13. Discuss what steps have been taken, or will be taken, in response to the lessons learned from the IP2 tube failure. In addition, please be prepared to discuss the following:
 - (a) Discuss the actions that are taken in response to identifying a new degradation mechanism,
 - (b) Discuss the actions taken to ensure that data noise levels are acceptable, and
 - (c) Address data quality issues and the need for criteria to address data quality.

San Onofre Nuclear Generating Station, Units 2 and 3

cc:

Mr. R. W. Krieger, Vice President
Southern California Edison Company
San Onofre Nuclear Generating Station
P. O. Box 128
San Clemente, CA 92674-0128

Mr. Douglas K. Porter
Southern California Edison Company
2244 Walnut Grove Avenue
Rosemead, CA 91770

Mr. David Spath, Chief
Division of Drinking Water and
Environmental Management
P. O. Box 942732
Sacramento, CA 94234-7320

Chairman, Board of Supervisors
County of San Diego
1600 Pacific Highway, Room 335
San Diego, CA 92101

Eileen M. Teichert, Esq.
Supervising Deputy City Attorney
City of Riverside
3900 Main Street
Riverside, CA 92522

Mr. Gary L. Nolff
Power Projects/Contracts Manager
Riverside Public Utilities
2911 Adams Street
Riverside, CA 92504

Regional Administrator, Region IV
U.S. Nuclear Regulatory Commission
611 Ryan Plaza Drive, Suite 400
Arlington, TX 76011-8064

Mr. Michael Olson
San Onofre Liaison
San Diego Gas & Electric Company
P.O. Box 1831
San Diego, CA 92112-4150

Mr. Steve Hsu
Radiologic Health Branch
State Department of Health Services
Post Office Box 942732
Sacramento, CA 94327-7320

Mr. Ed Bailey, Radiation Program Director
Radiologic Health Branch
State Department of Health Services
Post Office Box 942732 (MS 178)
Sacramento, CA 94327-7320

Resident Inspector/San Onofre NPS
c/o U.S. Nuclear Regulatory Commission
Post Office Box 4329
San Clemente, CA 92674

Mayor
City of San Clemente
100 Avenida Presidio
San Clemente, CA 92672

Mr. Dwight E. Nunn, Vice President
Southern California Edison Company
San Onofre Nuclear Generating Station
P.O. Box 128
San Clemente, CA 92674-0128

Mr. Robert A. Laurie, Commissioner
California Energy Commission
1516 Ninth Street (MS 31)
Sacramento, CA 95814