

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.7.7.1	Verify the CW header pressure is $\geq$ 30 psig.	12 hours
SR 3.7.7.2	Verify the Unit 3 City Water Header Supply Isolation Valves are open.	31 days
SR 3.7.7.3	Perform testing required by Inservice Testing Program for each valve needed to align CW to each AFW pump suction.	In accordance with the Inservice Testing Program