

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.6.1.3.6	Verify the isolation time of each MSIV is ≥ 3 seconds and ≤ 5 seconds.	In accordance with the Inservice Testing Program
SR 3.6.1.3.7	Verify each automatic PCIV actuates to the isolation position on an actual or simulated isolation signal.	24 months
SR 3.6.1.3.8	Verify each reactor instrumentation line EFCV actuates to the isolation position on an actual or simulated instrument line break signal.	24 months
SR 3.6.1.3.9	Remove and test the explosive squib from each shear isolation valve of the TIP System.	24 months on a STAGGERED TEST BASIS
SR 3.6.1.3.10	Verify leakage rate through any one main steam line is ≤ 100 scfh and through all four main steam lines is ≤ 400 scfh when tested at ≥ 25.0 psig.	In accordance with the Primary Containment Leakage Rate Testing Program
SR 3.6.1.3.11	Verify combined leakage rate through hydrostatically tested lines that penetrate the primary containment is within limits.	In accordance with the Primary Containment Leakage Rate Testing Program