

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.5.2.4	Verify ECCS piping is full of water.	31 days
SR 3.5.2.5	Verify each ECCS pump's developed head at the test flow point is greater than or equal to the required developed head.	In accordance with the Inservice Testing Program
SR 3.5.2.6	Deleted	
SR 3.5.2.7	Verify each ECCS automatic valve in the flow path actuates to the correct position on an actual or simulated actuation signal.	24 months
SR 3.5.2.8	Verify each ECCS pump starts automatically on an actual or simulated actuation signal.	24 months
SR 3.5.2.9	Verify each LPSI pump stops on an actual or simulated actuation signal.	24 months

(continued)