

### 3.4 REACTOR COOLANT SYSTEM (RCS)

#### 3.4.9 Pressurizer

LCO 3.4.9 The pressurizer shall be OPERABLE with:

- a. Pressurizer water level  $\leq 65.1\%$  in MODES 1 and 2, or  $\leq 84\%$  in MODE 3; and
- b. Two groups of pressurizer heaters OPERABLE with the capacity of each group  $\geq 150$  kW with each group powered from a different safeguards power train.

APPLICABILITY: MODES 1, 2, and 3.

#### ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Pressurizer water level not within limit.	A.1 Be in MODE 3. <u>AND</u>	6 hours
	A.2 Fully insert all rods. <u>AND</u>	6 hours
	A.3 Place Rod Control System in a condition incapable of rod withdrawal. <u>AND</u>	6 hours
	A.4 Be in MODE 4.	12 hours
B. One required group of pressurizer heaters inoperable.	B.1 Restore required group of pressurizer heaters to OPERABLE status.	72 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 3. <u>AND</u>	6 hours
	C.2 Be in MODE 4.	12 hours

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.4.9.1	Verify pressurizer water level is $\leq 65.1\%$ in MODES 1 and 2, or $\leq 84\%$ in MODE 3.	12 hours
SR 3.4.9.2	Verify capacity of each required group of pressurizer heaters is $\geq 150$ kW.	24 months