

From: Adams, Wade [Wade.Adams@orau.org]
Sent: Tuesday, January 24, 2012 2:18 PM
To: Kauffman, Laurie
Cc: Carter, Ted; Bailey, Erika; Vitkus, Tim
Subject: 2012-01-24 UNC Naval Letter Report
Attachments: 2040-SR-01-0.pdf

Laurie,

Per our discussion on January 23, 2012, you requested that the letter report issued on December 7, 2011 not be labeled as a draft report. I've revised the report to indicate that it is a letter report and not a draft or interim report. If you have any comments or concerns on this letter report, please let me know.

Sincerely,

Wade C. Adams

SNM-368

07000371

Wade C. Adams
Project Manager/Health Physicist
ORAU/ORISE/IEAV
P.O. Box 117, Mail Stop 19
1299 Bethel Valley Road
Oak Ridge, Tennessee 37831-0117
Voice: 865.576.0065
Mobile: 865.567.5674
Email: Wade.Adams@orau.org
Web: <http://www.orau.org/>

January 24, 2012

Ms. Laurie Kauffman
U.S. Nuclear Regulatory Commission
Division of Nuclear Materials Safety
475 Allendale Road
King of Prussia, PA 19406-1415

**SUBJECT: LETTER REPORT—INDEPENDENT CONFIRMATORY SURVEY
RESULTS OF SOILS ASSOCIATED WITH THE ARGYLE STREET
SEWER LINE AT THE UNITED NUCLEAR CORPORATION NAVAL
PRODUCTS SITE, NEW HAVEN, CONNECTICUT
DCN: 2040-SR-01-0**

Dear Ms. Kauffman:

Oak Ridge Institute for Science and Education (ORISE) personnel visited the United Nuclear Corporation (UNC) Naval Products site on three separate occasions during the months of October and November 2011. The purpose of these visits was to conduct confirmatory surveys of soils associated with the Argyle Street sewer line that was being removed.

Soil samples were collected from six different, judgmentally determined locations in the Argyle Street sewer trench. In addition to the six soil samples collected by ORISE, four replicate soil samples were collected by Cabrera Services, Inc. (CSI) for analysis by the ORISE laboratory. Replicate samples S0010 and S0011 were final status survey (FSS) bias samples; S0012 was an FSS systematic sample; and S0015 was a waste characterization sample. Six soil samples were also collected for background determination. Uranium-235 and uranium-238 concentrations were determined via gamma spectroscopy; the spectra were also reviewed for other identifiable photopeaks. Radionuclide concentrations for these soil samples are provided in Table 1.

Total uranium concentrations for the soil samples ranged from 0.70 to 22 picocuries per gram (pCi/g). The two soil samples with the highest concentrations of total uranium were collected from inside the sewer pipe. The pipe has since been removed. The remaining soil samples were below 3 pCi/g. All soil samples analyzed by the ORISE laboratory were below the derived concentration guideline level (DCGL_w) of 30 pCi/g for total uranium.

In addition to the replicate samples and the samples collected by ORISE, CSI submitted three soil samples for inter-laboratory* comparison analyses (Table 2). One sample was from the background reference area, one was from waste characterization efforts (material inside the sewer line), and one was a FSS sample. The inter-laboratory comparison analyses results between ORISE and CSI were in agreement, except for one sample collected in the reference area. Additional information will be requested by ORISE to explain the difference and will be presented in the final report. Additionally, since one of the samples analyzed was close to the DCGL_w and the results between ORISE and CSI were in agreement, ORISE is confident that CSI is able to accurately determine whether a given


* While the term "laboratory" is used, CSI analyzes soil samples with a portable gamma spectroscopy system.

sample is below the release criteria.

Once the Argyle Street sewer entered Shelton Avenue, the pipe did not follow the path as anticipated, therefore CSI decided to characterize the pipe and, if the analytical results met the release guidelines, abandon it in place. CSI personnel also collected sludge material from inside the pipe (samples mentioned previously), and smears were also collected at one foot intervals inside the pipe (at the 3, 6, 9 and 12 o'clock positions at each one foot interval); the distance inside the pipe was limited to what was easily accessible from the pipe openings at either end (approximately three feet). CSI personnel collected replicate smears for ORISE. Gross alpha activity ranged from 0 to 49 disintegrations per minute per one hundred square centimeters (dpm/100cm²) and gross beta activity ranged from -5 to 19 dpm/100cm². The complete results for the smears are provided in Table 3; ORISE has requested CSI's smear analysis and will make a comparison in the final report.

A full confirmatory survey report will follow after completion of all confirmatory survey activities. Please contact me at 865.574.6273, or Wade Adams at 865.576.0065, should you have any questions.

Sincerely,



Nick A. Altic
Health Physicist/Assistant Project Manager
Independent Environmental Assessment
and Verification

NAA:fr

Enclosure

c:

T. Carter, NRC/FSME/DWMEP/DD/SPT-85
S. Nesmith, NRC/TAPM/TWFN 8A23

Electronic distribution:

S. Roberts/ORISE	E. Bailey/ORISE
T. Vitkus/ORISE	W. Adams/ORISE

File/2040

Distribution approval and concurrence:	Initials
Technical Review	WCA
Laboratory Review	WBA
Quality Review	EB

**Table 1. Radionuclide Concentrations in Soil Samples
UNC Naval Products, New Haven, Connecticut**

Sample ID	Gamma Count Rate (cpm)		Radionuclide Concentrations (pCi/g)								
	Pre-sample	Post-sample	U-235		U-238		Total U ^a				
Reference Area Background Samples											
S0001	7,429	8,447	0.14	±	0.11 ^b	1.22	±	0.27	2.58	±	0.55
S0002	6,681	7,160	0.08	±	0.12	0.86	±	0.29	1.80	±	0.59
S0003	6,874	8,067	-0.04	±	0.13	0.56	±	0.20	1.08	±	0.42
S0004	6,540	7,651	0.03	±	0.11	0.40	±	0.23	0.83	±	0.47
S0005	7,639	8,375	-0.12	±	0.13	0.47	±	0.28	0.82	±	0.57
S0006	6,175	6,560	0.21	±	0.12	0.66	±	0.21	1.53	±	0.44
Argyle Street Sewer Line Samples											
S0007	9,786	11,194	0.00 ^c	±	0.11	0.40	±	0.25	0.80	±	0.51
S0008	9,244	9,774	0.06	±	0.11	0.57	±	0.17	1.20	±	0.36
S0009	7,274	8,430	0.03	±	0.09	0.54	±	0.38	1.11	±	0.77
S0013	4,259	4,536	0.04	±	0.12	0.40	±	0.33	0.84	±	0.67
S0014	4,250	4,309	0.04	±	0.12	0.55	±	0.21	1.14	±	0.44
S0016	4,312	4,788	0.01	±	0.11	0.43	±	0.30	0.87	±	0.61
Arglye Street Replicate Samples (Collected by CSI Personnel)											
S0010	--	--	0.04	±	0.12	0.33	±	0.04	0.70	±	0.14
S0011	--	--	0.08	±	0.13	0.40	±	0.18	0.88	±	0.38
S0012	--	--	0.00	±	0.10	0.79	±	0.43	1.58	±	0.87
S0015 ^d	--	--	0.78	±	0.10	0.61	±	0.25	22	±	3
Inter-laboratory Comparison Analyses Samples											
S0017 ^d	--	--	0.69	±	0.11	0.55	±	0.30	20	±	3
S0018	--	--	0.08	±	0.07	0.72	±	0.39	1.52	±	0.78
S0019	--	--	-0.01	±	0.12	0.24	±	0.21	0.47	±	0.44

^aTotal U was calculated as U-235 + (2*U-238) for natural U and U-238 + (28*U-235) for enriched uranium samples.

^bUncertainties represent the 95% confidence level, based on total propagated uncertainties.

^cZero values are due to rounding.

^dSamples contained enriched uranium.

**Table 2. Inter-Laboratory Comparison Analyses
UNC Naval Products, New Haven, Connecticut**

ORISE Sample ID	CSI Sample ID	Total U Reported (pCi/g)		
		ORISE	CSI	DER ^a
S0017	UNC-WCJ-SR-012	20 ± 3	21.80 ± 0.27	0.6
S0018	UNC-FSS-RA-012	1.52 ± 0.78	4.05 ± 0.07	3.2
S0019	UNC-FSS-SR-037B	0.47 ± 0.44	2.15 ± 2.24	0.7

^aAbsolute Relative Difference (DER) was calculated based on the formula in the Department of Energy Quality Systems for Analytical Services, Rev 2.7, and provides a way to determine if analytical results of duplicates are in agreement. A DER ≤ 3 means the duplicates are in agreement, 3 represents the 99% confidence level.

**Table 3. Smear Results For Argyle Street Sewer Pipes
UNC Naval Products, New Haven, Connecticut**

End of Pipe	Interval (ft)	Location (o'clock)	Smear ID	Smear Activity (dpm/100 cm ²)	
				Alpha	Beta
West	0-1	6	R0001	2	7
		9	R0002	0	3
		12	R0003	49	-1
		3	R0004	0	-5
	1-2	6	R0005	0	1
		9	R0006	2	1
		12	R0007	2	-4
		3	R0008	0	-1
	2-3	6	R0009	0	-1
		9	R0010	0	-4
		12	R0011	0	-2
		3	R0012	0	-1
	3-4	6	R0013	6	3
		9	R0014	4	-4
		12	R0015	0	-1
		3	R0016	0	-2
East	0-1	6	R0017	6	-2
		12	R0018	0	-3
	1-2	6	R0019	28	5
		12	R0020	0	-2
	2-3	6	R0021	30	19
		12	R0022	0	-1