


*Southern California Edison Company*



P. O. BOX 800  
2244 WALNUT GROVE AVENUE  
ROSEMEAD, CALIFORNIA 91770

K. P. BASKIN

NAGER, GENERATION ENGINEERING

May 16, 1979

TELEPHONE  
213-572-1401

Director of Nuclear Reactor Regulation  
Attention: Mr. R. L. Baer, Chief  
LWR Branch 2, DPM  
U. S. Nuclear Regulatory Commission  
Washington, D.C. 20555

Gentlemen:

Subject: Docket Nos. 50-361 and 50-362  
Seismic Qualification of Safety Related Equipment  
San Onofre Nuclear Generating Station, Units 2 and 3

In preparation for a site visit to San Onofre, Units 2 and 3, equipment seismic qualification summary information was requested by NRC letter dated January 11, 1979. In response to your information request concerning the items selected for review by the Seismic Qualification Review Team (SQRT), listed in Enclosure I, seven (7) copies of the requested information, Enclosure II, are provided.

It is our understanding that the SQRT site visit will be scheduled upon receipt of the enclosed seismic qualification summary information.

If you have any questions or comments concerning the enclosed information, please contact me.

Sincerely yours,

*KP Baskin*

Enclosures

Docket # 50-361  
7905210160  
5/16/79  
DOCUMENT  
FILE

BOO1  
SE  
1/7  
END TO:  
REG FILE BR(2)  
MECH SYS BR  
TAC SYS BR  
POWER SYS BR  
P.M.(2)

79052101601

*A*

ENCLOSURE I

SAN ONOFRE UNITS 2 AND 3 EQUIPMENT LIST  
FOR SQRT  
DOCKET NO. 50-361 AND 50-362

BOP EQUIPMENT

1. 4160 V Class 1E Switchgear
2. 480 V Class 1E Motor Control Centers
3. 125 V DC Class 1E Distribution Switchboard
4. 600 V Electrical Penetration
5. 125 V DC Batteries
6. Class 1E Battery Charger
7. Control Room Instrument Racks
8. Motor Operated Valve Inverters
9. Evacuation Shutdown Panel
10. Transmitters
11. Converters
12. Control Switches
13. Auxiliary Feed Pump Motor
14. Diesel Fuel Transfer Pump Motor
15. Solenoid Valves (Valcov)
16. Solenoid Valves (Target Rock)
17. Globe - Motor Operated Valves (W-K-M, 4 in., Limitorque SMB-000)
18. Gate-Motor Operated Valves ( 24 in., Walworth Alloyco)
19. HV-4714 Valve
20. HV-6200 Valve
21. 2PSV-8401 Valve
22. NSSS Auxiliary Relay Cabinet
23. Salt Water Cooling Pumps
24. Auxiliary Feedwater Pumps (Turbine Driven and Motor Driven)
25. Component Cooling Water Heat Exchanger

NSSS EQUIPMENT

1. Plant Protection System Cabinet
  - a. Nuclear Instrument
  - b. Core Protection Calculator Test Module
  - c. Matrix Test Module
  - d. Relay Card Rack
  - e. Bistable Control Panel
  - f. Actuation Reset Panel
  - g. Trip Path Panel
  - h. AC Distribution Panel
  - i. Power Supply Assembly
  - j. RPS Initiation Relay
  - k. Sola Transformer
  - l. Cabinet Cooler Assembly

79052101601

A



2. Auxiliary Protective Cabinet
  - A. CPC Mass Storage Unit
  - b. CPC/CEAC Central Processing Unit
  - c. CPC/CEAC Input/Output Chassis
  - d. CPC/CEAC Power Supply
  - e. CEA Position Isolation Amplifiers
  - f. Reactor Coolant Pump Singal Processor
  - g. In-Core Amplifiers
3. Reactor Trip Switchgear Cabinet
4. ESFAS Auxiliary Relay Cabinet
5. Process Instrument Rack
  - a. Controller
  - b. Current to Voltage Converter
  - c. Resistance to Voltage Converter
  - d. Alarm
  - e. Square Root Extractor
  - f. Summing
  - g. Contract Isolator
  - h. Power Isolator
  - i. Voltage to Current Converter
  - j. Power Supply
  - k. Power Distribtuion Module
  - l. Signal Distribution Module
  - m. Temperature Transmitter
6. Vital Bus Power Supply
7. Core Portection Calculator Operators Module
8. PPS Remote Control Module
9. Indicators
10. Controller
11. Recorder
12. Temperature Sensors
13. Pressure Transmitter
14. Differential Pressure Transmitters
15. Reactor Coolant Pump Speed Signal Sensor and Transmitter
16. Nuclear Instrument Detector

17. Nuclear Instrument Preamplifier
18. CEA Read Switch Position Transmitter
19. Magnetic Flow Detector
20. Magnetic Flow Transmitter
21. Containment Purge Isolation Detector
22. Containment Purge Isolation Transmitter
23. 3 HV 9323 Valve
24. 3 HV 9322 Valve
25. Charging Pump
26. Shutdown Heat Exchanger

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name 4160 V. Class 1E Switchgear

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: 5HK Quantity: 4  
3. Vendor: Gould/ITE Imperial  
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"  
5. Physical Description a. Appearance Cabinet Type-See App. "B"  
b. Dimensions See Appendix "B"  
c. Weight 46,017 pounds per switchgear assembly  
6. Location: Building: Control Area (Auxiliary Bldg.)  
Elevation: 50'-0"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Plug Weld, .72 Diam Holes in Swgr.  
base to embedded channels  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 5,13,31 & 44HZ F/B: 15,19,30 & 42HZ V: 23 & 27HZ  
9. a. Functional Description: Supplies 4.16 kV power to Class 1E motors and loadcenters  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both  
10. Pertinent Reference Design Specifications: S023-302-02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis:     X    

Test and/or Analysis by Test Performed by Wyle Lab., Analysis and  
Report No. ITE Imperial S0703-50395 done by ITE  
Bechtel Log No. S023-302-2-112-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
 (other, specify)
2. Required Response Spectra (attach the graphs): Appendix "C"
3. Required Acceleration in Each Direction: Appendix "C"
- S/S = 1.0g ZPA (SSE) F/B = 1.0g ZPA (SSE) V = 0.75g ZPA (SSE)

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☒ 20 SEC. dwell at  
res. freq. (See  
Test Proced.)
2. ☒ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE 6 SSE 6 Other 4 -0.36g sine  
sweep  
 (specify)
4. Frequency Range: 1-33 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
[ ] No See App. "D"
6. Input g-level Test at S/S = 2.0g F/B = 2.0g V = 1.0g
7. Laboratory Mounting:
1. ☒ Bolt (No. \*, Size \*) [ ] Weld (Length       ) [ ]
8. Functional operability verified: ☒ Yes [ ] No [ ] Not Applicable
9. Test Results including modifications made: Eqpt. Qualified, No Modifications
10. Other tests performed (such as fragility test, including results):
- See Appendix "A" for qualification of devices

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: 3000 AMP bus duct analysed for stresses and resonances. No resonance or over stress found
2. Method of Analysis: Bus Duct Only
- [ ] Static Analysis [ ] Equivalent Static Analysis  
[X] Dynamic Analysis [ ] Time-History  
[X] Response Spectrum
3. Model Type: [ ] 3D [ ] 2D [ ] 1D  
[ ] Finite Element [X] Beam [ ] Closed Form Solution
4. [ ] Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
[X] Hand Calculations
5. Method of Combining Dynamic Responses: [X] Absolute Sum [ ] SRSS  
[ ] Other: \_\_\_\_\_  
(specify)
6. Damping: 1% Basis for the damping used: Cust. Spec.
7. Support Considerations in the model: No relative motion between ends of duct.

\*Not available from the report.

8. Critical Structural Elements: Bus Duct Only

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic- Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	5' Bus Duct	See App. "B"	Short Circuit and Seismic	741.5psi	741.5 psi	14,000psi
	Vert. Elbows	See App. "B"	Short Circuit and Seismic	741.5psi	741.5 psi	14,000psi
	Bus Bar	See App. "B"	Short Circuit and Seismic	309.7psi	1904.8 psi	22,000psi
	2' Bus Duct	See App. "B"	Short Circuit and Seismic	3153psi	3153 psi	14,000psi
	15.88" Duct	See App. "B"	Short Circuit and Seismic	3152psi	3153 psi	14,000psi

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	Bus Bar, $1673.5 \times 10^{-6}$ in		None
	5' Bus Duct, $803. \times 10^{-6}$ in		None
	2' Bus Duct, $76.7 \times 10^{-6}$ in		None

appendix "A"

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 20 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. - Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
1	Circuit Breaker	5HK C-35231-777-03	-	-	.75V 1.0 H	R-09400 8.2.3-13A	0.8V 1.7H	Certified	4.1
2	Circuit Breaker	5HK C-35233-777-03	-	-	.75V 1.0H	R-09400 8.2.3-13A	0.8V 1.7H	Certified	4.1
8	Circuit Breaker	TYPE E EE3-B060	-	-	.75V 1.0H	Test Program 42686-1	1.5V 1.5H	Certified	4.15
	No Entry		-	-					
12	Circuit Breaker	Type E EE2-B030	-	-	.75V 1.0H	Test Program 42686-1	1.5V 1.5H	Certified	4.15
14	AC Ammeter	S73210220	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CD	3.5V 3.5H	Certified	4.15
15	AC Voltmeter	S73103310	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CC	3.5V 3.5H	Certified	4.15
16	AC Wattmeter	S73319311 I-T-E	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
17	AC VAR Meter	S73419314 I-T-E	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
18	Frequency Meter	S75501410 I-T-E	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
19	Ammeter Switch	SBM 10AA013	7V 6H	1.0 1.0	.75V 1.0H	R-09161-DI	5.0V 5.0H	Certified	4.15
20	Voltmeter Switch	SBM 10AA004	7V 6H	1.0 1.0	.75V 1.0H	R-09161-DI	5.0V 5.0H	Certified	4.15

302-2-112-1

34



TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 21 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. — Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
21	Control Switch	SB1 16SB1B9	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CS	5.0V 5.0H	Certified	4.15
22	Indicating Lamp	ET-16 0116B6708G3D	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AS	3.6V 5.0H	Certified	4.2
23	Indicating Lamp	ET-16 0116B6708G3E	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AS	3.6V 5.0H	Certified	4.6
24	Indicating Lamp	ET-16 0116B6708G3W	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AS	3.6V 5.0H	Certified	4.6
25	Current Transformer	MCS-25 401572-K2	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.9
26	Current Transformer	MCS-25 401572-K3	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.9
28	Current Transformer	MCS-25 401572-K6	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.9
29	Current Transformer	MC-5 401437-K7	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
30	Current Transformer	MCS-25 401572-K4	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.9
31	Current Transformer	MC-5 401437-K9	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
33	Current Transformer	MCB-5A 401024-T5	-	-	.75V 1.0H	Test Program 42686-3	1.2V 1.9H	Certified	4.12
34	Current Transformer	MCB-5AS 401048-T24	-	-	.75V 1.0H	Test Program 42686-3	1.2V 1.9H	Certified	4.12

209-7-112-1

35

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 22 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. - Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
35	Overcurrent Relay	CO-5 264C897A07	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.10-31-75	2.0V 2.0H	Certified	4.15
36	Current Transformer	MC-5 401437-K8	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
37	Overcurrent Relay	CO-11 1961504	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.3-26-76	2.0V 2.0H	Certified	4.15
38	Potential Transformer	JVM-3 643X94	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
	NO ENTRY								
40	Potential Transformer	JVM-3 643X94	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
	NO ENTRY								
42	P.T. Primary Fuse	EJ-1 9F60BBD001	-	-	.75V 1.0H	R-09400	0.8V 1.7H	Certified	4.15
43	Overcurrent Relay	CO-8 264C900A07	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.3-26-76	2.0V 2.0H	Certified	4.15
44	Overcurrent Relay	CO-8 264C900A05	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.3-26-76	2.0V 2.0H	Certified	4.15
45	Overcurrent Relay	CO-9 264C901A03	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.3-26-76	2.0V 2.0H	Certified	4.15
46	Motor Control Switch	SB-1 SIM to 16SB1CG15	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CS	5.0V 5.0H	Certified	4.15

1-011-0-008

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 23 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. -- Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
	NO ENTRY.								
49	Undervoltage Relay	SVF 1961843	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT.LET.3-26-76	2.12V 2.22H	Certified	4.15
50	Undervoltage Relay	CV2 1875516	7V 6H	1.0 1.0	.75V 1.0H	WESTINGHOUSE CERT. LET.2-17-76	2.02V 2.09H	Certified	4.15
51	Voltage Control O.C. Relay	IJCV 12IJCV51A13A	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AL	.8V 1.1H	Certified	4.15
52	Reverse Power Relay	ICW 12ICW51A3A	7V 6H	1.0 1.0	.75V 1.0H	G. E. CERT. LET.7-29-75	1.5V 5.0H	Certified	4.15
	NO ENTRY								
54	Underfreq. Relay	SDF-1 717B920A10	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
55	Undervoltage Relay	1AV 12IAV54E1A	7V 6H	1.0 1.0	.75V 1.0H	R-09161-BF	1.6V 2.2H	Certified	4.5
	NO ENTRY								
57	Loss of Field Relay	CEH 12CEH51A1A	7V 6H	1.0 1.0	.75V 1.0H	G.E. CERT.LET.2-3-76	1.6V 1.9H	Certified	4.15
58	Neg. Ph. Seq. O.C. Relay	INC 12INC77B3A	7V 6H	1.0 1.0	.75V 1.0H	G.E. CERT.LET.2-3-76	1.7V 3.0H	Certified	4.15
59	Gen. Diff. Relay	SBD 12SBD11A2A	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.19

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 24 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. — Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
60	Auxiliary Relay	HFA 12HFA51A47F	7V 6H	1.0 1.0	.75V 1.0H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
61	Auxiliary Relay	HFA 12HFA51A47F	7V 6H	1.0 1.0	.75V 1.0H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
62	Auxiliary Relay	HFA 12HFA51A47F	7V 6H	1.0 1.0	.75V 1.0H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
63	Auxiliary Relay	HFA 12HFA51A42H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
64	Auxiliary Relay	HFA 12HFA54E187H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
65	Auxiliary Relay	HFA 12HFA51A47F	7V 6H	1.0 1.0	.75V 1.0H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
66	Auxiliary Relay	HGA 12HGA11S54	7V 10H	1.0 1.6	.75V 1.6H	G.E. CERT.LET.7-29-75	5.0V 5.0H	Certified	4.15
67	Auxiliary Relay	HGA 12HGA11S52	7V 10H	1.0 1.6	.75V 1.6H	G.E. CERT.LET.7-29-75	5.0V 5.0H	Certified	4.15
68	Time Delay Relay	7000 7012 PD	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DR	5.0V 5.0H	Certified	4.15
69	Time Delay Relay	7000 7022 PC	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DR	5.0V 5.0H	Certified	4.15
70	Auxiliary Relay	HFA 12HFA51A42H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
71	Auxiliary Relay	HFA 12HFA51A47F	7V 6H	1.0 1.0	.75V 1.0H	Test Program 42686-1	1.5V 2.5H	Certified	4.15

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 25 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. - Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
72	Current Transducer	V2 606B230A09	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
73	Auxiliary Current Transformer	TA 400742-K23	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
74	Test Switch	ROTO 404	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
76	Resistor	MCOR (2) FR100-100	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
77	Resistor	MCOR AR200-1000	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CG	3.5V 3.5H	Certified	4.15
78	Resistor	MCOR AR100-1500	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
79	Resistor	MCOR AR100-2500	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
80A	Resistor	MCOR (1) FR160-250	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CH	3.5V 3.5H	Certified	4.15
80B	Resistor	(1) FR100-150	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
81	Resistor	MCOR AR50-300	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
82	Time Delay Relay	7000 7012 PC	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DR	5.0V 5.0H	Certified	4.15
83	Cable Lug	250 MCM YA29-2N	-	-	-	-	-	Certified	4.8

302-2-112-1

39

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 26 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. -- Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
	NO ENTRY								
	NO ENTRY								
89	Cable Lug	350 MCM YA31-2N	-	-	-	-	-	Certified	4.8
90	Cable Lug	500 MCM YA34-2N	-	-	-	-	-	Certified	4.8
91	Cable Lug	750 MCM YA39-2N	-	-	-	-	-	Certified	4.8
93	Auxiliary Transformer	Part No. 110507	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
94	Watt Transducer	20WS100 20WS101	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
95	VAR Transducer	20RS100 200RS101	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
96	Frequency Transducer	6284A 6284A-S	7V 10H	1.0 1.6	.75V 1.6H	R-09404-A	5.0V 5.0H	Certified	4.15
97	Voltage Transducer	VE2-841 606B229A09	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
98	Diode	GE-102L218G1-2	-	-	.75V 1.6H	Test Program 43250	3.0V 3.0H	Certified	4.16
99	Watthour Meter	DSW-63 SIM to 700X63G1	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16

302-2-112-1

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 27 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. - Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
100	Resistor	1-3/4 AAW/13A Leads	7V 9H	1.0 1.1	.75V 1.1H	R-09161-CI	3.5V 3.5H	Certified	4.15
102	Indicating Lamp	ET-16 0127B8108G2D	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AS	3.6V 5.0H	Certified	4.7
103	Lockout Relay	HEA 12HEA61B236X2	7V 6H	1.0 1.0	.75V 1.0H	R-09161-AJ	3.6V 5.0H	Certified	4.15
105	Ground Protect. Relay	IAV 12IAV51D2A	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
107	Test Switch	ROTO 808 8P.Curr	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
108	Test Switch	ROTO 660 6P.Pot	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
109	Test Switch	ROTO-1046 6P.Curr. 4P.Pot	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
110	Test Switch	ROTO 440-4P.Pot	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
111	Test Switch	ROTO 624-4P.Curr. 2P.Pot.	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
112	Test Switch	ROTO 606-6P.Curr.	-	-	.75V 1.0H	Test Program 43250	3.0V 3.0H	Certified	4.16
115	Test Switch	Knife SIM to A-1520	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CL	3.5V 3.5H	Certified	4.15
116	Test Switch	Knife SIM to A-1518	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CL	3.5V 3.5H	Certified	4.15

302-2-112-1

42

TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 28 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. - Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
117	Test Switch	Knife SIM to A-1458	7V 10H	1.0 1.6	.75V 1.6H	R-09161-CL	3.5V 3.5H	Certified	4.15
118	Test Switch	Knife SIM to A-1458	7V 10H	1.0 1.6	.75V 1.6H	R-09161-CL	3.5V 3.5H	Certified	4.15
119	Test Switch	Knife SIM to A-2206	7V 10H	1.0 1.6	.75V 1.6H	R-09161-CL	3.5V 3.5H	Certified	4.15
120	Test Switch	Knife A-1559	7V 10H	1.0 1.6	.75V 1.6H	R-09161-CL	3.5V 3.5H	Certified	4.15
121	Test Switch	Knife SIM to A-1513	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CL	3.5V 3.5H	Certified	4.15
122	Test Switch	Knife SIM to A-1512	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CL	3.5V 3.5H	Certified	4.15
123	Test Switch	Knife A-1453	7V 10H	1.0 1.6	.75V 1.6H	R-09161-CL	3.5V 3.5H	Certified	4.15
124	Test Switch	Knife A-1533	7V 6H	1.0 1.0	.75V 1.0H	R-09161-CL	3.5V 3.5H	Certified	4.15
126	Time Delay Relay	7000 7012 PCLL	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DZ	2.4V 2.4H	Certified	4.2
127	Push Button Switch	H32 H32BF1W(2)H32XNC	7V 6H	1.0 1.0	.75V 1.0H	R-09161-DS	5.0V 5.0H	Certified	4.15
128	Auxiliary Relay	HMA 12HMA11B6	7V 10H	1.0 1.6	.75V 1.6H	G.E. CERT.LET.7-29-75	3.5V 3.7H	Certified	4.11
129	Time Delay Relay	7000 7024PC	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DY	2.2V 2.2H	Certified	4.2

302-2-112-1



TABLE 1  
SEISMIC EVALUATION OF GROUP 1 RESALE COMPONENTS  
BUS 2A04 (I-T-E ITEM B)

SEISMIC CERTIFICATION REPORT  
I-T-E S.O. 703-50395  
Page 29 of 67

B/M Pc. No.	Device Description	Device Model or Catalog Number	Reference Accelerometers		Reqd. Accel. "g" Level	Device Documentation		Device Comments	
			No. — Dir.	Amp		Test Report Reference No.	Avail. "g" Level	Certification	Cert. Notes
130	Auxiliary Relay	HFA 12HFA51A42H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
131	Auxiliary Relay	HFA 12HFA51A42H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5V 2.5H	Certified	4.15
132	Time Delay Relay	7000 7012 PCL	7V 10H	1.0 1.6	.75V 1.6H	R-09161-DZ	2.4V 2.4H	Certified	4.2
133	Time Delay Relay	7000 7032 PDC	7V 10H	1.0 1.6	.75V 1.6H	R-09161-EA	2.8V 2.8H	Certified	4.2
113	Auxiliary Relay	HFA 12HFA51A49H	7V 10H	1.0 1.6	.75V 1.6H	Test Program 42686-1	1.5H 2.5H	Certified	4.15
	NO ENTRY								
	NO ENTRY								
	NO ENTRY								
	NO ENTRY								
	NO ENTRY								
	NO ENTRY								
	NO ENTRY								

302-2-112-1

Appendix "B"

## Appendix "C"

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLB LGH QJB

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-701

REV.

A 1/24/73

ACCELERATION ( $g$ 's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.1

.2

.3

.4

.5

.8

1

2

3

4

5

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:


WOB

JOB NO.  
1304-803


SKETCH NO.  
S023-SK-S-725

REV.  
A

ACCELERATION ( $g$ 's)



7-21-73





FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WOB

JOB NO.

1304-803


SKETCH NO.

8023-SK-S-739

REV.

A

ACCELERATION ( $g$ 's)




PERIOD (seconds)

7-24-73

## Appendix "D"



Figure 1



Comparison of customer's Horizontal RRS to the Front-to-Back  
 TRS of the SHK test specimen

Figure 2




Figure 2

Comparison of customer's Vertical RRS to the Vertical TRS of the SHK test specimen

Figure 3




Figure 3







Comparison of the customer's Horizontal RRS to the Side-to-Side TRS of the 5HK test specimen

79

202-2-112-1



2472



TOOL NUMBER

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

RECEIVED 6-29-77

DATE 6-29-77

BY [Signature]

FOR [Signature]

RECEIVED 6-29-77

DATE 6-29-77

BY [Signature]

FOR [Signature]

ITE ITEM B UNIT 2 BUS 2A04  
ITE ITEM D UNIT 2 BUS 2A06  
ITE ITEM G UNIT 3 BUS 3A04  
ITE ITEM J UNIT 3 BUS 3A06

SAN ONOFRE NUCLEAR GENERATING STATION  
(I-T-E CLASS 12)  
NUCLEAR SAFETY RELATED

5023-302-2-79-5 SCE #0361

STANDARD TOLERANCE INFO. ON DR. 82018 3 PL. DEC. \* 3 PL. DEC. \*  
TOLERANCES - UNLESS OTHERWISE SPECIFIED - OR FRAC.

INDOOR METAL-CLAD SWGR 5HK-550 3000A 4160V 3P, 3W, 60HZ  
BUS DUCT LAYOUT

SOLD TO: SOUTHERN CALIFORNIA EDISON  
FOR: SAN ONOFRE NUCLEAR GENERATING STATION UNIT 2 & 3

CUST. G-4103611 BY C. DEPAULIS CHD. T. Dunning APP. [Signature] SCALE 1/8" = 1'-0"  
S.O. 53-50395 DATE JUNE 26, 73 DATE JULY 3, 1975 DATE [Signature]

ITE Imperial Corporation 33-50395-D226 4

"THIS DRAWING IS THE PROPERTY OF I-T-E IMPERIAL CORPORATION AND CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION  
WHICH MUST NOT BE DUPLICATED, USED OR DISCLOSED OTHER THAN AS EXPRESSLY AUTHORIZED BY I-T-E."

FORM 174-6



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 480V Class IE Motor Control Center

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: Model 4 MCC Quantity: 14
3. Vendor: Square "D"
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"
5. Physical Description a. Appearance See Appendix "B"
- b. Dimensions See Appendix "B"
- c. Weight See Appendix "B"
6. Location: Building: Control Area (Auxiliary Bldg)
- Elevation: 50'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )
- ☒ Weld (Length 2-1/2" on 10" center)
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: 7, 18, 21Hz F/B: 26HZ V: 32Hz
9. a. Functional Description: Supplies 480V A.C. Power to Class 1E Motor Rated 50 H.P. & Lower
- b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: S023-302-4-2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Wyle Lab. 43220-1

Bechtel Log S023-302-4-2-55-3

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ N/A  
(other, specify)
2. Required Response Spectra (attach the graphs); See Appendix "C"
3. Required Acceleration in Each Direction:  
S/S = lg F/B = lg V = lg

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE \*5 SSE \*1 Other \_\_\_\_\_  
(specify)  
\*In each horizontal direction with vertical
4. Frequency Range: 1-35Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*\*  
See Appendix "D"
6. Input g-level Test at S/S = 3.2g F/B = 2.8g V = 1.6g

\*\*TRS exceeds RRS above 4 Hz and at all natural frequencies.

## 7. Laboratory Mounting:

1. ☐ Bolt (No.\_\_\_\_, Size\_\_\_\_) ☒ Weld (Length Tack-welded) ☐ \_\_\_\_\_  
 (Length not provided  
 in report)

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: The relay section door came open during exploratory search test in the F/B axis due to misalignment of the fastener screws. The mounting holes were relocated and the exploratory search test repeated without problems.

10. Other tests performed (such as fragility test, including results):

Component Functional Test

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

1. Description of Test including Results: \_\_\_\_\_

2. Method of Analysis:

☐ Static Analysis ☐ Equivalent Static Analysis

☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements:


A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---





## APPENDIX "A"

## APPENDIX "B"



PULLBOX					
1A2	2A8 MT-401	3A8 MT-401	4A8 MT-401	5A8 MT-401	6A8 MT-401
	2B22A8	3B22A8	4B22A8	5B22A8	6B22A8
	2CD	3CF	4CF	5CD	6CD
	2E 412			2E 401	2E 401
	2F 412	FC-401	FC-401	2F 401	2F 401
	2G 412			2G 401	2G 401
	2H 412	3H	4G	5G	6G
	2I 401	EC-401	FC-401	ED-401	FC-401
	2J 401	3J		2K 401	
	2L 401	EE-403	2M 401	5M	2N 401
	2O 401		2P 401	2Q 401	2R 401
	2S 401	2T 401	2U 401	2V 401	2W 401
	2X 401		2Y 401	2Z 401	

MCC NO. 287



NOT TO SCALE  
DIMENSIONS IN INCHES

S023-302-4-2-13-B SCE # 0354

MODEL 4 MOTOR CONTROL CENTER		CLASS 8999		SHIPPING DATA		65" HIGH 28" DEEP 96" WIDE 1900 LB WT		APPROVAL RECORDS	
NEMA WIRING CLASS II TYPE B		ENCLOSURE NEMA: 2		UNITS MOUNTED		FRONT OF BOARD ONLY		JOB TITLE SAN ONOFRE NUCLEAR GEN. STA. UNITS 2-3	
180 VOLTS 3 PHASE 3 WIRES 60 HERTZ 180 CONTROL VOLTS				TERMINALS MOUNTED		IN UNIT		JOB LOCATION SAN ONOFRE CALIFORNIA	
SUPPLY ENTERS SECTION: 1		TOP		TERMINAL TYPE		TRACK MOUNTED		ARCH ENGR S.C. EDISON	
INCOMING CABLE (LUG) SIZE: 760 MCM		NUMBER PER PHASE 2		STANDARD PAINT SPECIFICATIONS		ANSI 40		ELECTRICAL CONTRACTOR S.C. EDISON	
INCOMING "B" LINE PLANGED END - CATALOG NUMBER:				SPECIAL FINISH		ANSI 41 UNIT SADDLES TO BE YELLOW		N. REDRAWN	
GROUND (LUG) SIZE: 4-250 MCM		NEUTRAL (LUG) SIZE:		MATERIALS		ALL STRUCTURAL PARTS, UNITS, DOORS AND COVERS ARE OF CODE GAUGE STEEL		O. REDRAWN	
HORIZONTAL BUS: 600 AMPERES PER PHASE		TIN PLTD. CU.		REMARKS		SEE INTERCONNECTION DIA 12-02690-8A3.		BY JH 7-11-77	
VERTICAL BUS: 300 AMPERES PER PHASE		TIN PLTD. CU.		CUSTOMER		SOUTHERN CALIFORNIA EDISON CO.		MRR 10-26-77	
NEUTRAL, UNGROUND, 3 PHASE, 4 WIRE, HORIZONTAL ONLY		AMPERES		CUSTOMER ORDER NUMBER		11103542		NO KEY	
BRACED FOR 42,000 RMS SYMMETRICAL AMPS				SQUARE D FACTORY ORDER NUMBERS		12-02690-8		REVISIONS	
HORIZONTAL GROUND BUS: 600A COPPER 1/2" x 1/2" BUS BARS								BY DATE	
VERTICAL GROUND BUS:								DRAWN RICHTER	
								CHECKED LBH	
								SCALE N.T.S.	
								DATE 10-26-77	
								DWG NO 12-02690-8A1	
								SHEET 1 OF 3	

APPENDIX "B"

## APPENDIX "C"

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 .2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-701

REV.

A 1/24/73

ACCELERATION (g's)



FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

$T$  = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

QB wab

JOB NO.

1304-803


SKETCH NO.

S023-SK-737

REV.

A 7/24/73

ACCELERATION (g's)



7-24-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

LGH

QJB

Approved By:

wab

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-725

REV.  
A

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION (g's)

9

8

7

6

5

4

3

2

1

0

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.5

.8

1

2

3

4

5

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA AUX. BLDG.

Prepared By: Reviewed By: Approved By:

AL

FLG

LGH


WOB

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-739

REV.  
A

ACCELERATION ( $g$ 's)





## APPENDIX "D"

FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ / %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MIN IN USA

Acceleration (g peak)



Frequency (Hz)

AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 14


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 % ☒

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS F-B/V  
LOCATION NO. VCA  
TEST RUN NO. 14

FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.

Acceleration (g peak)



Frequency (Hz)

AXIS SS/V

LOCATION NO. HCA

TEST RUN NO. 44

Report No. 43220-1


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS SS/V

LOCATION NO. 1/CR

TEST RUN NO. 44


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☒ 2 %


46 7403

K-E LOGARITHMIC 9 X 3 CYCLES  
NEUTEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V  
LOCATION NO. HCA  
TEST RUN NO. 14


## FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐DAMPING ☐ 2 %

Frequency (Hz)


AXIS FB/VLOCATION NO. VCATEST RUN NO. 14

## FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐DAMPING ☒ 2 %AXIS SS/VLOCATION NO. HCATEST RUN NO. 44



## FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐DAMPING ☐ 2% ☒

AXIS SS/V

LOCATION NO. VCA

TEST RUN NO. 44

## FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐DAMPING ☒ 5%

AXIS FB/V


LOCATION NO. HCA

TEST RUN NO. 14

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☒ 5%



AXIS FB/V

LOCATION NO. VCA

TEST RUN NO. 14

FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 5% ☒

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFEL & ESSER CO. MADE IN GERMANY

Acceleration (g Peak)



Frequency (Hz)

AXIS SS/V

LOCATION NO. HCA

TEST RUN NO. 44

FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 5% ☒

46 7403

K&E LOGARITHMIC 9 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.

Acceleration (g Peak)



Frequency (Hz)

AXIS SS/V

LOCATION NO. VCA

TEST RUN NO. 44



# FORM NUMBERS

1. BP1, Y12-3, Y47, Y53-1, NON
2. BP1, FT, X1, Y47, Y76, Y53-1, Y53-2
3. BP1, FT1, X1, Y47, Y53-3, Y53-1, Y53-6
4. BP1, FT, X2, Y47, Y53-3, Y53-1, Y53-6
5. BP1, FT1, X2, Y47, Y53-3, Y53-1, Y53-6
6. BP1, Y47, Y53-2, Y53-1
7. BP1, BP1, Y47, Y53-2, Y53-1
8. BP1, FT1, X1, Y47, Y53-3, Y180, Y53-1, Y53-6
9. BP1, FT1, X1, Y47, Y76, Y53-1, Y53-2

STANDARD  
ORIGINAL FOR  
REGISTERED PRODUCTION

<p><b>IMPORTANT</b></p> <p>If the price or schedule is affected by this document approval, Buyer must be notified prior to fabrication or such claims are waived.</p> <p>Approval of documents involving calculation, analysis or test report is only an acceptance of the information used by the supplier. Supplier retains full responsibility for design.</p> <p>Approval of this document does not relieve the supplier from full responsibility for contract or purchase order requirements including, but not limited to, adequacy and suitability of materials and/or equipment represented thereon for the intended function.</p>	
<p>DATE: 11-11-76</p> <p>RECEIVED: 11-11-76</p>	<p>DOCUMENT STATUS:</p> <p>1. APPROVED - MANUFACTURER MAY PROCEED</p> <p>2. APPROVED EXCEPT AS NOTED - MAKE CHANGE</p> <p>3. AS APPROVED - MANUFACTURER MAY PROCEED</p> <p>4. NOT APPROVED - CORRECT AND RESUBMIT</p> <p>5. INFORMATION ONLY - DISTRIBUTION REQUIRED</p>

## UNIT MODIFICATIONS

- AR - GEN ELECTRIC #HFA51A 120V ALARM W/5 NORMALLY OPEN & 1 NORMALLY CLOSED.
- BP1 - WHITE PILOT LIGHT WHICH INDICATED CIRCUIT BREAKER TRIPPING.
- CR - 8501 G040 120V 60 HZ CONTROL RELAY.
- CSTAX - 8501 G040 120V 60 HZ CONTROL RELAY.
- CSTBX - 8501 G040 120V 60 HZ CONTROL RELAY.
- EF1 - 1 EXTRA TYPE FRN SECONDARY CONTROL FUSE.
- EF2 - 2 EXTRA TYPE FRN SECONDARY CONTROL FUSE.
- FT1 - EXTRA CAPACITY CONTROL CIRCUIT TRANSFORMER (480V/120V)
- NON - 800A FRAME NON-AUTOMATIC CIRCUIT INTERRUPTER.
- OC, RC - (1) 8501 1020-LL 120V 60 HZ MECHANICALLY HELD LATCHING RELAY.
- OR - 8501 G060 120V 60 HZ CONTROL RELAY.
- PN - RED NEON PILOT LIGHT IN DOOR TO INDICATE VOLTAGE ON THE LOAD SIDE OF THE CONTACTORS
- P37 - WHITE PILOT LIGHT IN DOOR TO INDICATE CONTROL CIRCUIT ON 120V 60 HZ
- RES - OHMITE DIVIDOM TYPE 210 CATALOG NO. 0378 2500 OHMS 25 WATTS RESISTOR.
- RES1 - OHMITE DIVIDOM TYPE 210 CATALOG NO. 0376 1500 OHMS 25 WATTS RESISTOR.
- RES2 - OHMITE TYPE 270 FIXED RESISTORS 400 OHMS 25 WATTS.
- RES3 - OHMITE DIVIDOM TYPE 210 CATALOG NO. 1163 2500 OHMS 160 WATTS RESISTOR.
- RT - 25 KVA 480-120V SINGLE PHASE 60 HZ AND SHALL MAINTAIN AN OUTPUT VOLTAGE OF 120V  $\pm$  1 PERCENT WITH 480V  $\pm$  10 PERCENT AND 60 HZ  $\pm$  5 PERCENT ON THE INPUT. OUTPUT SHALL BE SINUSOIDAL WITH THE TOTAL RMS HARMONIC CONTENT OF 5 PERCENT MAXIMUM. EACH REGULATING TRANSFORMER SHALL CONSIST OF A DRY-TYPE TRANSFORMER AND A LINE-VOLTAGE REGULATOR. THE DRY-TYPE TRANSFORMERS SHALL MEET THE SAME REQUIREMENTS AS THE 30 4W DISTRIBUTION TRANSFORMERS AND THE LINE-VOLTAGE REGULATOR SHALL BE SOLA NO. 33-16-325
- TR2 - ACSTAT TIMER CAT. NO. 7022ACXT W/1.5 TO 15 SEC. TIMING RANGE AND 1 N.O. INST. CONTACT
- TR - ACSTAT TIMER CAT. NO. 7022 ADX W/5 TO 50 SECOND TIME DELAY.
- TR1 - ACSTAT TIMER CAT. NO. 7022 ADX W/5 TO 50 SECOND TIME DELAY.
- X1 - 1 NORMALLY OPEN & 1 NORMALLY CLOSED AUXILIARY CONTACTS ON FULL VOLTAGE NON-REVERSING STARTER
- X2 - 2 NORMALLY OPEN & 2 NORMALLY CLOSED AUXILIARY CONTACTS ON FULL VOLTAGE REVERSING STARTER
- Y12-3 - BURNBY TYPE YA LONG BARREL LUG FOR COPPER CONDUCTORS USING GRADE 5 BOLTS #21401-28551
- Y53-1 - VSI-BLADE MOLDED CASE CIRCUIT BREAKER SUBSTITUTED FOR STANDARD BREAKER.
- Y53-2 - HIGH INTERRUPTING CAPACITY BREAKER, 1-75,000 TYPE, USED ON ALL BRANCH BREAKER UNITS.
- Y53-3 - MOTOR CIRCUIT PROTECTOR MAG-GARD (ADJUSTABLE MAGNETIC TRIP ONLY CIRCUIT BREAKER).
- Y53-6 - MAG-GARD BREAKER BUILT IN A HIGH INTERRUPTING FRAME
- Y141 - KIRK KEY INTERLOCK.
- Y180 - SPECIAL SEISMIC MODIFICATIONS SIZE 3 & 4 STARTERS.
- NAMEPLATE WITH BRASS SCREWS AND NUTS.
- 9080 KCB-1 TERMINAL BLOCKS.
- AMP RING TONGUE TERMINALS FOR ALL CONTROL WIRE CATALOG NO. 320627.
- RED #14 GAUGE SIS CONTROL WIRE AND GROUND WIRE.
- BRADY WIRE LABELS.
- WEATHER RESISTANT DIAGRAMS.
- ALL UNUSED CONTACTS ON RELAYS ETC. SHALL BE CONNECTED TO TERMINAL BLOCKS FOR FUTURE USE.
- XFR - TRIAD #F-18X 117 to 6.3 VOLT 6.0 AMPERES FILAMENT TYPE TRANSFORMERS.
- Y47 - GASKETED NEMA 1 ENCLOSURE
- Y35 - BREAKER UNIT WHICH FEEDS A DISTRIBUTION TRANSFORMER.
- C6 - ON-OFF SELECTOR SWITCH

## STRUCTURE MODIFICATIONS

- END CLOSING PLATES TO BE FURNISHED ON ALL SHIPPING SPLITS.
- OMEGA 3-566 SPACE HEATER ONE PER SECTION 720W 240V (OPERATING ON 180W 120V)
- SPECIAL FINISH ANSI 61 LIGHT GRAY, SADDLES TO RED OR YELLOW, DEPENDING ON WHICH MCC IS BEING BUILT.
- U2 - BUS BARRIERS FOR HORIZONTAL & VERTICAL BUS BARS
- U3 - PLASTIC CLOSING PLATES TO UNUSED PLUG-ON OPENINGS IN VERTICAL BUS BAR BARRIERS WITH EXTRA PLUGS LOCATED IN BARRIER COMPARTMENT.
- U5 - ADD WIRE GUARDS, GROMMETS & BLOCK OFFS TO ALL WIRE ACCESS PORTS BETWEEN UNITS & VERTICAL.
- U7 - PULL BOX ON TOP FOR CUT GOING CABLES WITH DRIP HOLD.
- U8 - HORIZONTAL GROUND BUS. (NOTE) EACH UNIT IS TO BE WIRED FROM GROUND ON SADDLE TO TERMINAL BLOCK & THEN TO GROUND BUS. GROUND BUS TO BE (4) 1/8 X 1 1/8.
- U11 - 42,000 AMPS SYMMETRICAL BUS BAR BRACING.
- U26 - STRUCTURES ARE MODIFIED FOR SEISMIC REQUIREMENTS.
- GASKETED REMOVABLE BACKPLATES

F. REV. SPACE FOR INFORMATION ON BASE CHANNEL MOUNTING HOLES SEE DRAWING C12-02690-A2

E. REVISED PER CUSTOMER ORDER UPDATING DATA - WCT-8/26/76

5023-302-4-2-270-2 SCE # 0354

REV.	DN	DATE	BY	REV.	DN	DATE	BY	SCALE	DRAWN	CHKD.	DATE	BY
A.	ADDED	FORMS						NTS	MRR	JLSC	2-24-76	
B.	DELETED	FORMS	OC AND RC AND ADDED FORM					DATA SCHEDULE				
C.	ADDED	FORM	TR2	JLSC	4/27/76			SUPERCEDES B12-02690-A1				
D.	CHANGED	FROM BI-METAL TO MELTING ALLOY SPRINGS	JLSC					RAWSTOCK 1/20/76				

PERU

B12-02690-2A1 PAGE 3 OF 3

SQUARE D COMPANY  
POWER EQUIPMENT  
GROUP

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 125 VDC Class 1E Distribution Switchboard

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: CBC-Special Quantity: 8
3. Vendor: GTE Sylvania
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"
5. Physical Description a. Appearance Floor Mounted Switchboard
- b. Dimensions 90"H x 36"W x 19-1/4"D
- c. Weight 2400 lbs
6. Location: Building: Control Area (Auxiliary Bldg)
- Elevation: 50'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )
- ☒ Weld (Length 2" Fillet, 6"O.C.)
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: \* F/B: \* V: \*
9. a. Functional Description: Distributes 125VDC power to Class 1E loads and panels
- b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: Spec. No. S023-302-5A

\*Results not furnished by GTE-Sylvania. Information requested.

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories #58026  
Bechtel Log S023-302-5A-20  
 (Name of Company of Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ NA  
 (other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "B"
3. Required Acceleration in Each Direction:  
 S/S = 1.0g F/B = 1.0g V = .75g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☐ random ☒ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE 5 SSE 1 Other None  
 (specify)  
Each horizontal direction with vertical
4. Frequency Range: 1.25 - 35 HZ
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No
6. Input g-level Test at S/S = 1.4 g F/B = 1.8 g V = 1.8 g



7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☒ Weld (Length 2" @ 6" O.C.)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: Contact chatter noted on over and under voltage alarm relays. Since both relays do not affect the safety function of the equipment, the contact chatter is acceptable.

10. Other tests performed (such as fragility test, including results):  
None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

1. Description of Test including Results:

2. Method of Analysis:

☐ Static Analysis ☐ Equivalent Static Analysis

☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# APPENDIX A

# APPENDIX B

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By: Reviewed By: Approved By:

AL

FLG LGH

WAB


WAB

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-725

REV.  
A

ACCELERATION ( $g$ 's)



PERIOD (seconds)

7-24-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-739

REV.

A

ACCELERATION (g's)



PERIOD (seconds)

7-24-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH QBS

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-701

REV.

A, 1/24/73

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

wab

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-737

REV.

A 7/24/72

ACCELERATION (g's)



PERIOD (seconds)

7-24-72







Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
 2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 600 V Electrical Penetration Assembly

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: E-2866 Quantity: 138
3. Vendor: Westinghouse Electric Corp
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description
  - a. Appearance See Appendix "A"
  - b. Dimensions See Appendix "A"
  - c. Weight 680 pounds
6. Location: Building: Penetration Room (Containment Wall)  
 Elevation: From 51'-0" through 87'-0"
7. Field Mounting Conditions ☒ Bolt (No. 16, Size 1-1/8")  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical)\*:  
 Outboard Box:  
 S/S: 18 Hz & above F/B: 18 Hz & above V: 18 Hz  
 Module: >33Hz in all 3 directions
9.
  - a. Functional Description: To allow passage of electrical wires through the containment while acting as a continuation of the containment vessel pressure boundary.
  - b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-304-1

\* Only the penetration outboard termination box and the penetration module were seismically tested. The other components were qualified by analysis. See Appendix "B".

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: See Appendix "B"

Analysis: See Appendix "B"

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by: Westinghouse: PEN-TR-76-31, PEN-TR-76-08  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:\*

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
  3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
  5. ☐ Combination of \_\_\_\_\_
  6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)
  2. Required Response Spectra (attach the graphs): See Appendix "C"
  3. Required Acceleration in Each Direction: N/A
- S/S = lg F/B = lg V = lg

VI. If Qualification by Test, then Complete:\*

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE N/A SSE N/A Other See App. "B"  
(specify)
4. Frequency Range: Box: 1 to 80 Hz  
Module: 5 to 50 Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS requested from vendor
6. Input g-level Test at Box: S/S = 3g F/B = 3g V = 3g  
Module: lg in each 3 directions
7. Laboratory Mounting: Box: Resting on the floor (portable shaker used)  
Module: Mounted in test fixture which is bolted to shake table
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_

\* Only the penetration outboard termination box and the penetration module were seismically tested. The other components were qualified by analysis. See Appendix "B".

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See Appendix "D"
10. Other tests performed (such as fragility test, including results):

Steam test, thermal cycling, pre-age 40 years at 70°C, radiation tested  $2.1 \times 10^2$  rads. A leak, allowed per IEEE 317, of  $<10^6$  cc developed.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: N/A
2. Method of Analysis: (See Appendix "B")
- ☒ Static Analysis ☐ Equivalent Static Analysis
- ☐ Dynamic Analysis ☐ Time-History
- ☐ Response Spectrum
3. Model Type: ☐ 3D ☒ 2D ☐ 1D
- ☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS
- ☐ Other: \_\_\_\_\_
- (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements:

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

See Appendix "E"

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

None

# APPENDIX "A"

## APPENDIX "B"



## APPENDIX "B"

EQUIPMENT QUALIFICATION METHOD:

Combination of test and analysis:

A. Tests performed were as follows:

1. Termination Box (outboard box only)
  - a. Termination Box Housing - tested for natural frequency only by portable shaker.
  - b. Terminal Strips Inside Termination Box - tested by portable shaker at terminal strip resonance frequency to 3g for 3 minutes.
2. Electrical Penetration Module - tested by single frequency sweep test, uniaxial, at 1g in each direction from 5 to 50' Hz.

B. The following components were structurally analyzed:

1. Hold-down bolts for outboard box and penetration.
2. Wiring and structures inside the termination box.
3. Bulkhead which supports the modules.
4. Hold-down bolts for inboard box (Note: The inboard box is considered as a nonpressure boundary. The box has an implosion disk which, during a LOCA, will open a hole in the box to prevent the differential pressure from exceeding a value which would collapse the box wall. The analysis was done to prove that the inboard box will maintain its structural integrity during a seismic event.)

## APPENDIX "C"

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61' 3"

Prepared By:

Reviewed By:

Approved By:

JWW KMS

LGH WLB

WLB JHE

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-641

REV.  
A

ACCELERATION ( $g$ 's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .06 .08 .1 2 3 4 5 1 2 3 4 5

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61' 3"

Prepared By

JWW KMS

Reviewed By

LGH JTH

Approved By

WAB *[signature]*

JOB NO.

1304-803

SKETCH NO.

8023-SKS-842

REV

A

ACCELERATION ( $g$ 's)

13

12

11

10

9

8

7

6

5

4

3

2

1

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

8

8-23-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$S_d = 10 T^2 S_a$   
 $S_d$  - DISPLACEMENT RESPONSE (INCHES)  
 $T$  - PERIOD (SEC.)  
 $S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
 AS PERCENT OF CRITICAL




BECHTEL POWER CORPORATION  
 LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
 SAN ONOFRE NUCLEAR GENERATING STATION  
 UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
 VERTICAL ACCELERATION RESPONSE  
 SPECTRA FOR CONTAINMENT  
 EXTERIOR SHELL ELEVATION 86'-6"

Prepared By: JWW KMS	Reviewed By: IGH JTS	Approved By: WAB J.E.
----------------------------	----------------------------	-----------------------------

JOB NO. 1304-803	SKETCH NO. S023-SK-S-643	REV. A
---------------------	-----------------------------	-----------



823-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 86'-6"

Prepared By

JWW

KMS

Reviewed By

LGH

WAB

Approved By

WAB

JOB NO

1304-803

SKETCH NO.

S023-SK-S-644

REV

A

ACCELERATION ( $g$ 's)

17

16

15

14

13

12

11

10

9

8

7

6

5

4

3

2

1

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.1

.2

.3

.4

.5

.8

1

2

3

4

5

8-23-73



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

$T$  - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61' 3"

Prepared By:

JWW KMS

Reviewed By:

LGH

Approved By:

WOB


JOB NO.  
1304-803

SKETCH NO.  
8023-SK-S-563

REV.

A

ACCELERATION ( $g$ 's)



823-73



FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61' 3"

Prepared By:

JWW KMS

Reviewed By:

LGH *[signature]*

Approved By:


Ward *[signature]*

JOB NO  
1304-803

SKETCH NO.  
8023-SK-5-884

REV.  
A

ACCELERATION (g's)



823-73

10

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 86'-5"

Prepared By:

JWW KMS

Reviewed By:

IGH LPS

Approved By:

WOLF Y/C

JOB NO.

1304-803

SKETCH NO.

5023-SK-S-865

REV.

A

ACCELERATION ( $g$ 's)

7

6

5

4

3

2

1

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01

.02

.03

.04

.06

.1

2

3

4

5

6

7

8

9

10

PERIOD (seconds)

8-25-73

//

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 85'-5"

Prepared By:

Reviewed By:

Approved By:

JWW KMS

LGH RPS

WDB YMC

JOB NO

SKETCH NO.


REV.

1304-803

8023-SK-5-666

A

ACCELERATION ( $g$ 's)



823-73

12

APPENDIX "D"

## APPENDIX "D"

Test results including modifications made:

1. TERMINATION BOX

The test results showed that the termination box assemblies are capable of withstanding the DBE without damage or loss of function.

2. ELECTRICAL PENETRATION MODULE

The prototype module which had a small leak rate (less than allowable per IEEE317,  $10^{-6}$  std. cc) after all previous tests, were monitored during vibration test. Unit was pressurized to 15 PSIG and during vibration test, no added loss of pressure through module or "O" rings was observed.

The absence of resonances and retention of pressure show that the module is not affected adversely by seismic vibration.


APPENDIX "E"

## APPENDIX "E"

CRITICAL STRUCTURAL ELEMENTS

<u>IDENTIFICATION</u>	<u>LOCATION</u>	<u>GOVERNING LAND</u>	<u>SEISMIC STRESS (PSI)</u>	<u>TOTAL STRESS (PSI)</u>	<u>STRESS ALLOW- ABLE (PSI)</u>
Electrical Penetration Assembly	Penetration (Aux. Bldg.) Elev. 51'-0" Through 87'-0"				
1. 16 Hold Down Bolts	Outboard Box and Penetration to Nozzle Flange	<ul style="list-style-type: none"> <li>•Containment</li> <li>•LOCA Pressure</li> <li>•Dead Loads</li> <li>•Seismic</li> <li>•Jet Force</li> </ul>	1,951	10,480	94,500
			287	1,395	27,500
2. Structures Inside Termination Box	Termination Box	<ul style="list-style-type: none"> <li>•Dead Load</li> <li>•Seismic</li> </ul>	470	940	27,000
3. Bulkhead	Penetration	<ul style="list-style-type: none"> <li>•Containment</li> <li>•LOCA Pressure</li> <li>•Dead Load</li> <li>•Seismic</li> </ul>	37	-	27,000
4. 16 Hold Down Bolts	Inboard Box to Nozzle Flange	<ul style="list-style-type: none"> <li>•Jet Force</li> <li>•Seismic</li> <li>•Dead Load</li> </ul>	2,170	9,125	94,000







Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 125 VDC Batteries

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 2GC-13 (4) Quantity: 8  
2GC-17 (4)  
(8)
3. Vendor: Exide
4. If the component is a cabinet or panel, name and model No. of the devices included:
5. Physical Description a. Appearance Two step rack  
 b. Dimensions 2GC-13-108" x 49" x 38"/2GC-17-145" x 49" x 38"  
 c. Weight
6. Location: Building: Control Bldg.  
 Elevation: 50'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ \*
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: \* F/B: \* V: \*
9. a. Functional Description: Provides 125 VDC Class 1E Power  
 b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-301-2

\* Seismic Qualification of this equipment has not been completed.

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: Exide Type 2GC-17'

Analysis: \_\_\_\_\_

Combination of Test and Analysis: Exide 2GC-13  
qualified by similarity to 2GC-17

Test and/or Analysis by Test/Analysis not complete  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): S023-SK-S-739, 725,  
NRIM 737, 701

3. Required Acceleration in Each Direction:

S/S = lg F/B = lg V = 0.75g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat ☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE 5\* SSE 1\* Other \_\_\_\_\_  
(specify)
4. Frequency Range: 1-33 Hz.
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No  
Test not completed

\*In each horizontal direction

6. Input g-level Test at S/S =   \*   F/B =   \*   V =   \*
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No.   , Size   ) ☒ Weld (Length   ) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: Tests are not complete,  
report expected January 1980.
10. Other tests performed (such as fragility test, including results):  
Radiation and thermal aging prior to seismic

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:


- [illegible]

\*Test not completed

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response Combination	Seismic Stress	Total Stress	Stress Allowable
----	-----------------------	-----------------	--	-------------------	-----------------	---------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WUB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-737

REV.

A 7/24/73

ACCELERATION ( $g$ 's)



7-24-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Class 1E Battery Charger

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: ARR130K300 Quantity: 9
3. Vendor: C&D Batteries
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"
5. Physical Description a. Appearance Cabinet  
b. Dimensions 48" W x 36" D x 78" H  
c. Weight 1700 lbs
6. Location: Building: Control Area (Auxiliary Bldg.)  
Elevation: 50'-0"
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1-1/2")  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 9 Hz. F/B: 8 Hz. V: 8 & 23 Hz.
9. a. Functional Description: Supplies 125 VDC to charge Class 1E station batteries.  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-301-3\*

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: By similarity  
to C and D Model ARR 130 K 400

Test and/or Analysis by Wyle Labs #43330-1  
Bechtel Log S023-301-3-44-0  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ N/A  
(other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "B"
3. Required Acceleration in Each Direction:  
S/S = 1.0g F/B = 1.0g V = 0.75g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE 10 Each Horizontal Direction with Vertical.  
SSE 2 Each Horizontal Direction with Vertical.  
Other N/A  
(Specify)
4. Frequency Range: 1-40 Hz See Appendix "C"
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*Lowest natural frequency is 8 Hz, TRS exceeds TRS above 4Hz



6. Input g-level Test at S/S = 2.0g F/B = 1.8g V = 1.3g
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 4, Size 1/2") ☐ Weld (Length) ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: Equipment not yet qualified.
10. Other tests performed (such as fragility test, including results):  
Component Functional tests. A parallel test is being performed by  
C&D on a 24 Amp ARR 130 AC 25F single phase charger. This unit is  
first radiated then seismically tested and is to be used for on-going  
qualification. Test results for the ARR 130 AC 25F charger are  
found in Bechtel vendor Log No. S023-301-3-67-1. The 25 Amp charger  
is constructed and uses materials similar to the ARR 130K 300  
charger.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: Not Applicable

1. Description of Test including Results: \_\_\_\_\_
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_
8. Critical Structural Elements: \_\_\_\_\_

A.	Identification	Location	Governing Load	Seismic	Total	Stress
			or Response			
			Combination	Stress	Stress	Allowable

B. <u>Max. Deflection</u>		<u>Location</u>	<u>Effect Upon Functional Operability</u>

## APPENDIX "A"

**CD BATTERIES**

DIVISION OF ELTRA CORPORATION

Manufacturers of Batteries and Automatic Chargers

3043 WALTON ROAD, PLYMOUTH MEETING, PENNA. 19462  
TELEPHONE: 215-828-9000 TELETYPE: 510-860-8436

DESIGN DATA

SHEET 1 OF 5

CUSTOMER:

ORDER #

7-30129

SHIP TO:

MODEL ARR13CK400

BATTERY CHARGER

SIZE: 48"Wx36"Dx78"H WEIGHT 2100 LBS NET MTG. FloorRATED AC INPUT 480 VAC DC OUTPUT 132/140 + 1/2 %RIPPLE 1% on Bat. (RMS) CURRENT LIMIT 115 % AMBIENT TEMP 50 °CEFFICIENCY: 90 % POWER FACTOR .55 TYPE OF CONTROL SCR

PROTECTION

AC INPUT CIRCUIT BREAKER (PART NO. JR-372 POLE 3 AMP 175 AUX CONTACT)  
DC OUTPUT CIRCUIT BREAKER (PART NO. JR-432 POLE 2 AMP 600 AUX CONTACT)  
DC FUSE RT-91 Amtrap 150A ANODE FUSE RT-91 Amtrap 150A  
CONTROL FUSE JL-85 1 AMP SURGE PROTECTOR JC-8 Cap. & 100 Ω 12W Res.AMMETER JM-103 0-500 KY21.1VOLTMETER JM-179 0-150 KY21.1RECTIFIER (PRV) 500VTIMER JR-376 (3Day)CONTROL WIRE SISPOWER CABLE Hypalon Jacket

ALARMS:

KBC-2911 Time DelayJR-367 Phase Loss MonitorJR-316 Disconnect RelayJL-131 Eq. Pilot LightKBC-2136A H.V.S.D.(2) MBC-1992 Load Sharing

TEST DATA REQUIRED:

DIELECTRIC TEST YESRIPPLE TEST YES (on battery only)CURRENT LIMIT TEST 115%NO LOAD TEST YESREGULATION TEST YESHEAT RUN N/RHOURS N/RLOAD N/ROTHER Seismic on Serial # ES7637**Eltra**

company

QCD614-1

FIGURE 4

5023-301-3-43-0

## APPENDIX "B"

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$S_d = 10 T^2 S_a$   
 $S_d$  - DISPLACEMENT RESPONSE (INCHES)  
 $T$  - PERIOD (SEC.)  
 $S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA Edison COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By: Reviewed By: Approved By:

AL

FLG LGH


WOB

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-725

REV.  
A

ACCELERATION ( $g$ 's)



PERIOD (seconds)

7-24-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WOB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-739

REV.

A

ACCELERATION (g's)



PERIOD (seconds)

7-24-73



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By: Reviewed By: Approved By:

AL

FLG LGH QBS


WAB

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-701

REV.  
A, 1/24/73

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

Wuf

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-737

REV.

A 7/24/73

ACCELERATION ( $g$ 's)



7-24-73

## APPENDIX "C"

# FULL SCALE SHOCK SPECTRUM (g Peak)

Page No. 49


Report No. 43330-1

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
NEUFEL & ESSER CO. MADE IN USA




AXIS FRONT-TO-BACK / VERTICAL

LOCATION NO. HCB

TEST RUN NO. 7

FULL SCALE SHOCK SPECTRUM (g Peak)  
1.0 ☐ 10 ☐ 100 ☒ 1000 ☐  
DAMPING ☐ 1 %

Page No. 50  
Report No. 43330-1



Frequency (Hz)

AXIS Front-to-Back/Vertical

LOCATION NO. YCR

TEST RUN NO. 7


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1%

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS SIDE-TO-SIDE/VERTICAL

LOCATION NO. HCR

TEST RUN NO. 17


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS SIDE-TO-SIDE / VERTICAL

LOCATION NO. YCA

TEST RUN NO. 14



# Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Main Control Panel - Sections 1-6 & 12-16

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: Custom Made Quantity: 1
3. Vendor: Circle AW Products Co.
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix A
5. Physical Description a. Appearance "W" shape cubicle
- b. Dimensions 107" H x 132" W x 72" deep (Section 3 only)
- c. Weight 5082 lbs (Section 3 only)
6. Location: Building: Control area in aux. bldg.
- Elevation: 30'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )
- ☒ Weld (Length 4" @ 7" O.C.)
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >33 HZ F/B: \*7.8HZ; \*17.5HZ\*\* V: >33 HZ
9. a. Functional Description: The controls and instrumentation for monitoring and operation of the plant equipment are housed in the main control panel
- b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: S023-502-5

\*Single Section

\*\*28 Hz Entire Panel. See VII 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Wyle Labs. Reports 54498-1 & 54498-2  
(Name of Company or Laboratory & Report No.)

V. Vibration Input: (For Section 3 only) The components were qualified independently. (See Appendix "A")

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "B"

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = lg F/B = lg V = 0.75g

VI. If Qualification by Test, then Complete: (Data applies to Section 3 only)

1. ☐ Single Frequency ☒ Multi-Frequency: ☐ random  
☐ sine beat  
☒ Random with Bi-axial  
Sine Beat super-imposed  
at specific frequencies
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 1 Other \_\_\_\_\_  
(specify)
4. Frequency Range: 1-35 HZ
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ \*No See Appendix "C"

\*TRS exceeds RRS above 2Hz and at natural frequencies.

6. Input g-level Test at S/S = 2g F/B = 2g V = 1.6g
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No.\_\_\_\_, Size\_\_\_\_) ☒ Weld (Length 2" @ 8" O.C. F&B) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☒ Not Applicable
9. Test Results including modifications made: Section 3 (2CR-50, 2CR-51 & 2CR-58) when tested was found to be structurally sound when subjected to seismic test program.
10. Other tests performed (such as fragility test, including results):  
None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: Frequency search in situ test was conducted on main control panel assembly and 28HZ was found at Section 1 and 33HZ was at Section 3 during insitu test.
2. Method of Analysis: Shipping Section 3 was modeled & verified by testing then the full "W" control panel was analyzed as a group.
- ☐ Static Analysis ☒ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☒ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: TRW systems groups "Two Dimensional and CDC Publication No. 86612000 Three Dimensional Frame Model Analysis Programs"  
 Frequency Range and No. of modes considered: 1-35 HZ Two (2)  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: N/A  
 (specify)
6. Damping: N/A Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: N/A

8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response Combination	Seismic Stress	Total Stress	Stress Allowable
	1)Stiffner Angle	Bottom	SSE	--	26,995	32,400
	2)Bolts	Support	SSE	--	24,022	82,800
	3)Stiffner Angle	Side of Section 1	SSE	--	27,047	32,400
	4)X-Bracing Angle	Bet. Plates	SSE	--	2,713	32,400
	5)Weld	&Bracing Angle	SSE	--	9,745	13,600

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	N/A		

## APPENDIX A



## CALCULATION SHEET

LAB 0816 11.70

SIGNATURE G. K. Napray DATE 2-15-79 CHECKED \_\_\_\_\_ DATE \_\_\_\_\_  
PROJECT SONGS 243 PROJECT JOB NO. 10079-003  
SUBJECT MAIN CONTROL ROOM PANEL SEISMIC QUAL SHEET 1 OF 1 SHEETS

APPENDIX "A"

ITEM NO	DESCRIPTION	TOTAL NO IN PANEL	VENDOR	MODEL	TYPICAL TESTED	IS EQUIPMENT FOR CLASS IE SERVICE OR SEISMIC	EQUIP QUALIFIED BY TEST/ANALYSIS	TEST "G"	REQUIRE G	TYPE OF INPUT USED	REPORT NO	REMARKS
1	BACK LIGHTED PUSH BUTTON SWITCHES	100	MASTER SPECIALTIES CO	10 H	4 POSITION VERTICAL SWITCH	CLASS IE	TYPICAL WAS TESTED REST WERE ANALYZED	5 G	3	SINE DWELL	5023-506-2-32-2 (MSC NO 058-1165-75A)	CONFIGURATIONS USED ON THIS PANEL ARE 2, 3 & 4 POSITIONS. THIS ITEM IS REFERRED TO AS CONTROL SWITCHES
2	KEY LOCKED SELECTOR SWITCHES	30	MASTER SPECIALTIES CO	PT	SELECTOR SWITCH WITH 4 LIGHTS	CLASS IE	TYPICALS TESTED OTHERS ANALYZED	5 G	3	SINE DWELL	5023-506-2-32-2 (MSC NO 058-1165-75B)	CONFIGURATION USED ON THIS - PANEL ARE SELECTOR SWITCHES WITH 2 LIGHTS. THIS ITEM ALSO REFERRED TO AS CONTROL SWITCHES
3	INDICATING LIGHT MODULES	89	MASTER SPECIALTIES CO	10 H	SEE REMARKS	CLASS IE	ANALYSIS	N/A	3	N/A	5023-505-5-22-1 (MSC NO 058-1166-75)	THE REPORT SHOWS THAT THESE ARE SIMILAR TO THOSE QUALIFIED IN 5023-506-2-32-2 AND HAVE NO RESONANCES BELOW 33 HZ
4	RECEIVER TYPE INDICATORS	4	SIGMA	9270	9270	CLASS IE	TEST	3.5 G	3	SINE BEAT	5023-505-7-10-2 (SIGMA NO 581-3)	
5	RECEIVER TYPE INDICATORS	8	SIGMA VIA CE	9270					3			CE REPORT REFERENCED PROVIDES COMPLETE SEISMIC QUALIFICATION DATA FOR CE SUPPLIED ITEMS
6	ESF BYPASS STATUS PANEL	2	MASTER SPECIALTIES CO	10 H	10 H	STRUCTURAL SEISMIC ONLY	TEST	3	3	SINE SWEEP	5023-506-2-63-0 (WYLE NO 58114)	
7	FLOODING INDICATION LIGHT MATRIX	2	MASTER SPECIALTIES CO	10 H	SEE REMARKS	CLASS IE	ANALYSIS	5 G	3	SINE DWELL	5023-505-5-22-1 (MSC NO 058-1166-75)	THE REPORT SHOWS THAT THESE ARE SIMILAR TO THOSE QUALIFIED IN 5023-506-2-32-2 AND HAVE NO RESONANCES BELOW 33 HZ
8	RECEIVER TYPE INDICATORS	8	SIGMA VIA CE	1136		CLASS IE			3			CE REPORT REFERENCED PROVIDES COMPLETE SEISMIC QUALIFICATION DATA FOR CE SUPPLIED ITEMS
9	MANUAL AND LOADING STATION	2	FOXBORO VIA CE			CLASS IE			3			
10	ANNUNCIATOR WINDOW BOXES	3	ROCHESTER INSTRUMENTS	5-14035		STRUCTURAL SEISMIC ONLY	ANALYSIS	5 G	3		5023-502-4-25-1 (INNOVATION TEL NO 7606-22)	STATIC ANALYSIS
									RECD BY SPZ. ACTUAL EXPERIENCE			CLASS IE IMPLIES THAT THE EQUIPMENT IS QUALIFIED FOR IE SERVICE. TOTAL NO IN PANEL MAY OR MAY NOT BE ALL CLASS IE


## APPENDIX B




# APPENDIX B

1 OF 2

FREQUENCY (cycles per second)





APPENDIX C  
(REPRESENTATIVE SAMPLES)

WYLE LABORATORIES

Report No. 54498-1

Customer JELCO Job No. 54498

Page No. 24 1 OF 2

Channel Identification: T/R 1 Trk. No. 1 Accel. No. 1

Transducer S/N 1171 Control (X)  Response ( )

Full Scale 100 G Cal Voltage 500 MVPK/ 1.0 G

Mode PRIMARY Specimen CONTROL PANEL

Operator Kno11 P/N 2CR-58,50,51 (\*3)

Date 6-16-76 Polarity + 0.5% Axis of Test X-Y


HORIZONTAL RESPONSE SPECTRA

2.0 Hz. in  $\phi$

ACCELERATION g's PEAK

QC Form Approval Ext

0.1



WYLE LABORATORIES

APPENDIX C  
(REPRESENTATIVE SAMPLE)

Report No. 54498-1

Customer JELCO

Job No. 54498

Page No. 25

Channel Identification: T/R 1 Trk. No. 2

Accel. No. 2 2 OF 2

Transducer S/N 103K Control (X),

Response ( )

Full Scale 100 G Cal Voltage 500 MVPK/ 1.0 G

Mode PRIMARY

Specimen CONTROL PANEL


Operator KNOV

P/N 2CR-58, 50, 51 (#3)

Date 6-16-76 Polarity + 0.5%

Axis of Test X-Y

VERTICAL RESPONSE SPECTRA

2.0 Hz. in  $\phi$ 

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Motor Operated Valve Inverters

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: INV502-3 Quantity: 4
3. Vendor: Elgar
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Cabinet  
b. Dimensions 70"H x 50"W x 24"D  
c. Weight 1500 lbs approx.
6. Location: Building: Control Area (Auxiliary Bldg.)  
Elevation: 50'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous 3/8")  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 29 HZ F/B: 13, 28, 35 HZ V: None found
9. a. Functional Description: 125VDC to 120 VAC inverter for Class 1E MOV power  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-301-6

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Labs #60005B

Bechtel Log S023-301-6-23-2, S023-301-6-3-2, S023-301-6-4-3

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "A"
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 1.0g F/B = 1.0g V = 0.75g

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random ☐ sine beat ☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE 5 Each horizontal direction with vert.  
SSE 1 Other None  
(specify)
4. Frequency Range: 1-35 HZ
5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

\*See Appendix "B"



6. Input g-level Test at S/S = 2.1g F/B = 2.1g V = 1.5g
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No.\_\_\_\_, Size\_\_\_\_) ☒ Weld (Length Continuous 3/8") ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: During the DBE in the X-Y axis the vertical exciter hit the stops, causing a fuse to blow.  
Fuse was replaced and test repeated with no change in the specimen.
10. Other tests performed (such as fragility test, including results):  
None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: Not Applicable

1. Description of Test including Results: \_\_\_\_\_
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response Combination	Seismic Stress	Total Stress	Stress Allowable
----	-----------------------	-----------------	--	-------------------	-----------------	---------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# APPENDIX "A"

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By: Reviewed By: Approved By:

AL

FLG LGH QB


WAB

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-701

REV.  
A 1/24/73

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9A, ELEVATION 50'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

QB

Approved By:

wab

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-737

REV.

A 7/24/72

ACCELERATION ( $g$ 's)



PERIOD (seconds)

7-24-72

## APPENDIX "B"

WYLE LABORATORIES

Report No. 58145

CUSTOMER ELCAR

Job No. 58145

Page No. 33

Full Scale 100 g

Accel. No. 1

Control (☒)

REVISION A  
Response ( )

Operator MEEHAN

Specimen 3 PHASE INVERTER


Date 6-1-77

Damping 1.5 %

Axis of Test HORIZ. X-Y

1<sup>ST</sup>  
DBE  
SD

RESPONSE SPECTRA





Report No.

CUSTOMER ELCAR

Job No. 58145

Page No.

34

Full Scale 100 g

Accel. No. 2

Control (5)

REVISION A  
Response ( )

Operator MEEHAN

Specimen 3 PHASE INVERTER


Date 6-1-77

Damping 185 %

Axis of Test VERT. X-Y

ST DBE

## RESPONSE SPECTRA



# WYLE LABORATORIES

56145

Report No. \_\_\_\_\_

35

CUSTOMER ECGAR

Job No. 56145

Page No. \_\_\_\_\_

Full Scale 100 g

Accel. No. 1

Control (✓) Response ( )

Operator MECHAN


Specimen 3 PHASE INVERTER

Date 6-1-77

Damping 5 %

Axis of Test WOBLE X-Y  
DBE #2

## RESPONSE SPECTRA



WYLE LABORATORIES

Report No. 58145

CUSTOMER ELCAR

Job No. 58145

Page No. 36

Full Scale 100 g

Accel. No. 2

Control (☒) Response ( )

Operator MEEHAN


Specimen 3 PHASE INVERTER

Date 6-1-77

Damping 5 %

Axis of Test VERT. X-Y  
DBE #2

RESPONSE SPECTRA



WYLE LABORATORIES

Report No. EC145

59

CUSTOMER ECAR

Job No. 58145

Page No. 59

Full Scale 100 g

Accel. No. 1

Control (☒) Response ( )

Operator MEEHAN


Specimen 3 PHASE ALUMINUM

Date 6-1-77

Damping 1.5 %

Axis of Test HORIZONTAL Z-Y  
DBE

RESPONSE SPECTRA





# WYLE LABORATORIES

Report No. 56145


CUSTOMER EKCAE Job No. 58145 Page No. 60

Full Scale 100 g Accel. No. 2 Control (✓) Response ( )

Operator MEERAN Specimen 3 PHASE INVERTER

Date 6-1-77 Damping 1.5 % Axis of Test VERT. 2-Y  
DBE

## RESPONSE SPECTRA



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2L-42 Remote Shutdown Panel

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: Custom Made Quantity: 2  
3. Vendor: Circle A. W.  
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix (A)  
5. Physical Description a. Appearance Rectangular Shape Cubicle  
b. Dimensions 90"H x 120"W x 42" Deep  
c. Weight 3500 lbs.  
6. Location: Building: Control Area in Aux. Bldg.  
Elevation: 45'-0"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length 2" per 5" o.c.)  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: \* F/B: 17.8, 28.6, 29.4Hz V: \*  
9. a. Functional Description: Control Room Evacuation Shutdown Panel  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: S023-502-5

\*Test of Panel 2CR-62 (Similar Panel) had no Resonance Frequencies Below 33Hz.

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: XX

Test and/or Analysis by Wyle Labs. Report #54498-3 and 54498.

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs); See Appendix B
3. Required Acceleration in Each Direction: For Devices See Appendix A  
S/S = 1g F/B = 1g V = 1g

VI. If Qualification by Test, then Complete: Test on similar panel 2CR-62. Device qualification by independent test.

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random ☒ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other 17 Random W/SB  
(specify)
4. Frequency Range: 1.25 to 35 Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No  
TRS exceeds RRS above 2 Hz and at natural frequencies. See  
Appendix "C"
6. Input g-level Test at S/S = 1.6g F/B = 1.6g V = 1.4g
7. Laboratory Mounting: Welded to 1" plate, plate bolted to table
  1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☒ Weld (Length 2" @ 8"o.c.) ☐ \_\_\_\_\_



8. Functional operability verified: ☒ Yes ☐ No ☒ Not Applicable  
DEVICES PANEL
9. Test Results including modifications made: Cabinet had resonance frequency 217.5Hz. No significant strain measured 2100 micro inch/inch. No modification required. Device operability test satisfactory.
10. Other tests performed (such as fragility test, including results):  
Devices had environmental testing.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: Devices tested, see Appendix (A). This panel is being qualified as similar to panel 2CR-62 (Wyle Labs. Report #54498) which was tested. First fundamental frequency measured in test was 17.5Hz.
2. Method of Analysis:  
☐ Static Analysis ☐ Equivalent Static Analysis  
☒ Dynamic Analysis ☐ Time-History  
☒ Response Spectrum
3. Model Type: ☒ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: TRW System Group Computer Program. Three Dimensional Frame Modal Analysis Program.  
CDC Publication #86612000
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☒ Other: Compared to test panel 2CR-62  
(specify)
6. Damping: N/A Basis for the damping used: N/A
7. Support Considerations in the model: Same as 2CR-62

## 8. Critical Structural Elements:

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NOTE: Panel 2CR-62 was tested. The analysis demonstrates the test of panel 2CR-62 also qualifies panel 2L-42 since the construction of the panels are similar and the frequency responses are comparable.

## APPENDIX (A)

## CALCULATION SHEET

12000 S. DOWNEY AVE. SUITE 9  
NORWALK, CALIFORNIA 90650

CALCULATION NO. \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_ CHECKED \_\_\_\_\_ DATE \_\_\_\_\_

PROJECT SONGS 293 PROJECT JOB NO. 10079-003

SUBJECT REMOTE SHUTDOWN PANEL SEISMIC DUAL SHEET 1 OF 1 SHEETS

## APPENDIX A

[illegible]

APPENDIX (B)  
(2 PAGES)

# APPENDIX (B)

1 OF 2

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 9, ELEVATION 50'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGM

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.


S023-SK-S-701

REV.

A 1/24/73

ACCELERATION (g's)







ATTACHMENT "C"

(2 PAGES)

WYLE LABORATORIES

ATTACHMENT "C"

Report No. 54498

1 OF 2

Customer JELCO

Job No. 54498

Page No. 39

Channel Identification: T/R 1

Trk. No. 1

Accel. No. 1

Transducer S/N 1143

Control (X).

Response ( )

Full Scale 100 G

Cal Voltage 500 MVPK/ 1.0

G

Mode PRIMARY

Specimen CONTROL PANEL

Operator MEEHAN


P/N 213CR-62 (UNIT 7)

Date 3/23/76

Polarity + Q 5%

Axis of Test Z-Y

## HORIZONTAL RESPONSE SPECTRA

2.0 Hz 1.0  $\phi$ 

WYLE LABORATORIES

Report No. 54498 2 OF 2

Customer JELCO Job No. 54498

Page No. 40

Channel Identification: T/R 1 Trk. No. 2

Accel. No. 2

Transducer S/N 1168 Control (X),

Response ( )

Full Scale 100 G Cal Voltage 500 MVPK/ 1.0 G

Mode PRIMARY

Specimen CONTROL PANEL

Operator MEEHAN

P/N 2/3CR-62 (UNIT 7)

Date 3/23/76 Polarity + Q 5%

Axis of Test Z-Y

VERTICAL RESPONSE SPECTRA

2.0 HZ IN Ø

ACCELERATION g's PEAK

QC Form Approval Ent

FREQUENCY HZ

5% DAMPING  
SONGS LAB  
RRS

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2FIT-4720-1 Transmitters

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: E13DM-1Sam2 Quantity: 4  
3. Vendor: Foxboro  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance See Appendix "A"  
b. Dimensions 13-1/4"H x 6-7/8"W  
c. Weight 25 lbs.  
6. Location: Building: Piping Tunnel - Outside Area  
Elevation: 17'-10"  
7. Field Mounting Conditions ☒ Bolt (No. 2, Size 1")  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: None Found F/B: 3.5 & 14Hz. V: 35Hz.  
9. a. Functional Description: Aux. feedwater to steam gen. E088  
flow transmitter  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: S023-504-1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro Report ET3-1091

Action Test Report #10486

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "B"
3. Required Acceleration in Each Direction:  
S/S = 1.0g F/B = 1.0g V = 1.0g

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat ☐ \_\_\_\_\_
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE 4 SSE 2 Other \_\_\_\_\_  
(specify)
4. Frequency Range: 1-35Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs) ☐ No  
Not Applicable
6. Input g-level Test at S/S = 10g F/B = 10g V = 10g  
See Appendix "C"
7. Laboratory Mounting: Not available (See Appendix "A")
  1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length) ☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See Appendix "C" and "D"
10. Other tests performed (such as fragility test, including results):

Radiation Test (Report #T3-1097), Pressure Integrity Test, Maximum Credible Accident (MCA) Test (Report #T3-1013)

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

- [illegible]

## 8. Critical Structural Elements: \_\_\_\_\_


A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---




# APPENDIX A

Figure No. 4  
Photographs  
of  
Test Units and Test Fixtures




E11GH-IINM2 X  
Gauge Pressure Transmitter




E11GM-ISAE2 X  
Gauge Pressure Transmitter

XMITTER TEST SPECIMEN, USED TO QUALIFY FOR PROJECT



E13DM-ISAMX ✓  
d/p Transmitter



E13DH-ISAM5 X  
d/p Transmitter

# APPENDIX B

# APPENDIX B

1 OF 2

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 2, ELEVATION 24'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LCH

Approved By:

WOB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-891

REV.

A 7/24/63

ACCELERATION (g's)



FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE (g's)
DAMPING VALUES  
AS PERCENT OF CRITICALBECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA Edison COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 2, ELEVATION 24'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

IGH

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-692

REV.

A 7/24/73

ACCELERATION (g's)

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5

# APPENDIX C

### 3.0 Summary and Conclusions

The four test transmitters operated without loss of function during all tests. The pressure integrity of all transmitters was maintained thru all tests.

Test results by unit are as follows:

E13DM PICKED AS REPRESENTATIVE ITEM.

Maximum calibration shifts following individual seismic runs of zero, span and the five check points were generally  $<0.5\%$ .

Output shifts in any plane during any test acceleration level were generally  $<-7.2\%$ . Output bandwidths were  $\pm 7.0\%$  in any plane or acceleration level.

Visual examination of the transmitter after all tests found no loose parts or screws.

The junction box assembly did not produce any amplified motions during the tests.

Process connectors were not used with the differential pressure transmitters during these tests. Signal connections were made directly into the transmitter bodies per the required fitting.

Where 5 sine beats are normally used under IEEE Std 344-1971 10 sine beats at each frequency were used in this test. Five sine beats at the test levels of 3.5 and 5.0g could be considered 1/2 SSE (Safety Shutdown Earthquakes) tests, therefore 10 sine beats would constitute two 1/2 SSE events at each level or four 1/2 SSE events. The 10g level could be considered an SSE event, therefore with 10 sine beats this would be equivalent to two SSE events. Viewed in this manner these units functioned through four 1/2 SSE and two SSE events at very high levels. Reference guideline IEEE 344-1971 Draft Revision 3, 2-13-74.

THE TRANSMITTER WERE TESTED FOR 3.5g, 5g AND 10g. THE ERROR IN THE TRANSMITTER OUTPUT AFTER 3.5g AND 5g TESTS WAS LESS THAN OR EQUAL TO THE SPECIFIED ERROR OF 0.5%.


THE ERROR IN THE TRANSMITTER OUTPUT AFTER 10g TEST WAS 0.55% WHICH IS 0.05% MORE THAN THE SPECIFIED ERROR.

THE TRANSMITTER MEETS THE REQUIREMENTS OF THE SPECIFICATION FOR ITS INTENDED USE.



# APPENDIX D

# APPENDIX D



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Electronic Converters in Panel 2L-188

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: 2ES-N Spec. 200 Quantity: 2  
3. Vendor: The Foxboro Co.  
4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"  
5. Physical Description a. Appearance Nested module for vertical rack mounting  
b. Dimensions 1-3/4" x 8-3/4" x 13-1/2"  
c. Weight ≈ 1 lb.  
6. Location: Building: Control Area In Aux. Bldg.  
Elevation: 30'-0"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length 3" per 3")  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 12 HZ; 18 HZ F/B: 22 HZ; 11 HZ V: 22 HZ  
9. a. Functional Description: Interface Cabinet for BOP 1E Instrumentation  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: S023-504-3

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro Test Reports T4-1025 & T3-1077  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "B"

3. Required Acceleration in Each Direction:

S/S = lg F/B = lg V = 0.75g

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat ☐ \_\_\_\_\_
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other App. "C"  
(specify)
4. Frequency Range: 1-35 HZ
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs) ☐ No N/A
6. Input g-level Test at S/S = 3.5g F/B = 3.5g V = 3.5g
7. Laboratory Mounting: \_\_\_\_\_
  1. ☒ Bolt (No. 6, Size .5" Dia) ☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_

- VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

1. Description of Test including Results: \_\_\_\_\_

2. Method of Analysis: \_\_\_\_\_

3. Model Type:    ☐ 3D                  ☐ 2D                  ☐ 1D  
                     ☐ Finite Element    ☐ Beam              ☐ Closed Form Solution

4. [ ] Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	-----------------------	---------------------	-------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## APPENDIX A



## CALCULATION SHEET

12400 E. IMPERIAL HWY  
NORWALK, CALIFORNIA 90650

**CALCULATION NO.**

**SIGNATURE**

DATE \_\_\_\_\_

**CHECKED**

DATE \_\_\_\_\_

2-14-79

PROJECT SONGS 283

JOB NO. 10079-003

SUBJECT CONVERTERS  
NISS PROCEED I/C BACK

SHEET 1 OF 1 SHEETS

APPENDIX 'A'

ITEM NO	DESCRIPTION	TOTAL NO IN PANEL	VENDOR	MODEL	TYPICAL TESTED	REPORT QUALIFIED FOR CLASS IE SERVICE AS START SERVICE	EDPT QUALIFIED BY TEST/ANALYSIS	TEST G	REQUIRE G	TYPE OF INPUT USED	REPORT NO	REMARKS
1	CURRENT TO VOLTAGE CONVERTER	6	FOXBORO	2AI-13V	2AI-13V	CLASS IE	TEST	3.56	1.26	SINE BEAT	5023-SOL-3-23-0 FOXBORO NO T2-1077 1023-SOL-3-2-2 FOXBORO NO T4-1025	THE 2 REPORTS QUALIFY THE RACK AND THE INSTRUMENTS MOUNTED INSIDE THE RACK
2	VOLTAGE TO CURRENT CONVERTER	4	FOXBORO	2AI-V2I	2AI-V2I	CLASS IE	TEST	3.56	1.26			
3	ALARM UNITS	6	FOXBORO	2AP+ALM-AR	2AP+ALM-AR	CLASS IE	TEST	3.56	1.26			
4	CONTACT OUTPUT ISOLATORS	2	FOXBORO	2AO-L2C-R	2AO-L2C-R	CLASS IE	TEST	3.56	1.26			
5	POWER DISTRIBUTION MODULES	3	FOXBORO	2AX+DPID	2AX+DPID	CLASS IE	TEST	3.56	1.26			
6	SIGNAL DISTRIBUTION MODULES	4	FOXBORO	2AX+DSP	2AX+DSP	CLASS IE	TEST	3.56	1.26			
7	SQUARE ROOT EXTRACTOR	2	FOXBORO	2AP+SBE	2AP+SBE	CLASS IE	TEST	3.56	1.26			
8	RESISTANCE TO CURRENT CONVERTER	2	FOXBORO	2AI-T2V	2AI-T2V	CLASS IE	TEST	3.56	1.26			
9	POWER DISTRIBUTION MODULE	2	FOXBORO	2AX+DPME	2AX+DPME	CLASS IE	TEST	3.56	1.26			
10	SIGNAL DISTRIBUTION MODULES	2	FOXBORO	2AX+DSI	2AX+DSI	CLASS IE	TEST	3.56	1.26			
												CLASS IE IMPLIES THAT THE EQUIPMENT IS QUALIFIED FOR IE SERVICE. TOTAL NO IN PANEL MAY OR MAY NOT BE ALL CLASS IE

## APPENDIX B

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)
DAMPING VALUES  
AS PERCENT OF CRITICALBECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

LGH

JDB

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

8023-SK-S-895

REV.

A 7/24/73

ACCELERATION ( $g$ 's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)
DAMPING VALUES  
AS PERCENT OF CRITICALBECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WJB

JOB NO.

1304-803

SKETCH NO.

8023-SK-S-686

REV.

A 7/24/72

ACCELERATION ( $g$ 's)

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.5

.8

1

2

3

4

5

## APPENDIX C

## APPENDIX C

10F2

Observations & Conclusions

In general all of the input/output and computing cards performed well, even at 10g's. Exceptions are stated below, along with other observations and comments. In reviewing these several exceptions, the endurance testing aspect of the test sequence should be kept in mind, from the standpoint that these occurrences took place among 38 functioning modules, each of which was subjected to more than 1000 ten-cycle sine beats of vibration.

1. The mechanical integrity of the 2ANU nests and mounting hardware appears to be adequate at 3.5g's, but it is evident that additional measures must be taken for use at 5.0g and 10g levels.

The nylon bushings on the mounting screws of the 2ANU nests and Power Supply are too soft and can be distorted by vibration to the point where the mounting screws become loose allowing the nests and power supply to slide in these mounting slots and/or rack opening.

The nest-to-rack mounting brackets on the nests containing 2AP modules as opposed to the nest containing the input/output modules held at acceleration levels of 5.0g's or less; but when tested at 10g acceleration level, the brackets flexed considerably (compounded by the problem listed above) causing one nest's brackets to develop cracks along the 90° bend.

The following design modifications are suggested for consideration:

- a. The use of all-metal locking hardware for mounting the nests.
  - b. Using holes instead of slots in the front of the mounting brackets in order to reduce the amount of side-play available.
  - c. Repositioning of the bracket-to-nest fastening hardware closer to the front of the nest in order to reduce the amount of side-play available.
  - d. Using a heavier-gauge steel for the mounting brackets.
  - e. Alteration of the design of the "pressed nuts" in the nest into which the mounting screws for the mounting brackets go would be desirable. In the present design the mounting bracket is kept from mounting flush to the nest by the lip on the "pressed nut" body. This allows flexing and eventually leads to failure of the fastener at 5 and 10g levels.
2. The mercury-wetted relays of the two 2AO-IPD-R's frequently chattered at various frequencies during all of the sine beat tests, and occasionally during the resonant searches at 0.4g's.
  3. Several one-of-a-kind problems were encountered. They are as follows:
    - a. Output spikes of up to -15% were observed on the output of the 2AP+SUM summer and 2AC+A5 controller of loop 2, group 1 at 3.5g's in the horizontal plane. At 5g's these spikes began appearing on the outputs of all the loop 2 units, but did not occur at any time from any of the units at 10g's.

504-3-23-0

#### 4.0 Observations & Conclusions (Cont.)

No output spikes were observed in the other, identical group of equipment (loop 1, group 1) during testing.

- b. Output A of the 2AO-L2C-R No. 2 failed at 20 Hz in the side-to-side plane @ 10g's. The fault was traced to two broken wires on the relay socket of K1.
- c. The 2AP+ALM-A No. 2 failed at 28 Hz in the side-to-side plane @ 5g's. The fault was traced to operational amplifier, U2 (LM301A).
- d. Diode CR2 (IN914) of the 2AP+SLM No. 1 failed (shorted) at 32 Hz in the vertical plane at 5g's. This caused the output to follow the low limit setting regardless of input signal level.
- e. One suitcase jumper fell out of its position on the 2AP+SGC No. 2, at 10g's in the side-to-side plane, and all of the other suitcase jumpers were found to be partially withdrawn from their pins at the completion of testing.
- f. At 3.5g's the alarm set point of one 2AP-ALM-AS shifted causing the output to fire.
- g. Cards 2AX+INT No. 1 and 2AX+ALM No. 2, repeatedly came from their 2AP modules during 5g and 10g tests. This occurred because the retaining clips on the cards did not line up with the holes in the 2AP modules. After completion of testing, inspection revealed that many of the cards which did not come out were held by only one retaining clip.

504-3-23-0



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HS-0227 B2 Control Switches

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 10H Series Quantity: 1
3. Vendor: Master Specialties Company
4. If the component is a cabinet or panel, name and model No. of the devices included: Not Applicable
5. Physical Description a. Appearance 1 x 4 Horiz. Display  
b. Dimensions 1.2"W x 3.785"H  
c. Weight 2 lbs. Approx.
6. Location: Building: Main Control Panel in Control Area.  
Auxiliary Bldg.  
Elevation: 34'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Screwed with Bezel Around
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >33Hz F/B: >33Hz V: >33Hz
9. a. Functional Description: Remote control of volume control tank outlet valve.  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-506-2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Master Specialties Company Report No. 058-1165-75B  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): N/A
3. Required Acceleration in Each Direction:  
S/S = 3g F/B = 3g V = 3g

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ sinusoidal dwell
2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: Sinusoidal Dwell @ Interger Frequencies 1 to 50 Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

\*Actual requirement (2g) per main control panel test. See circle AW report by Whole Lab. #54498-1 & 54498-2.

6. Input g-level Test at  $S/S = *(5g \text{ max.})$   $F/B = *(5g \text{ max.})$   $V = *(5g \text{ max.})$   
 \*(See Appendix "A")
7. Laboratory Mounting: (Used Std. Screw for Std. Field Mounting)
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_) ☒ Connected to  
book end type  
fixture
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See Appendix "B" The switches  
meet the requirements of the spec. for their intended service.
10. Other tests performed (such as fragility test, including results):  
Functional test - No switch lights failed to operate during the seismic  
testing. All switches operated correctly upon completion of testing.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: The testing consists of subjecting  
the specimens to a series of sinusoidal dwell tests in the frequency  
range of 1Hz to 50Hz biaxially. Prior to testing the specimens were  
wired to a chatter-transfer detector and the contacts were monitored for  
chatter of 10 micro seconds or greater during all testing. There was no  
structural degradation noted during or after testing
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: N/A  
 (specify)
6. Damping: N/A Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: None

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Base Plate		Seismic		10,139 psi	30,000 psi
	Switch		Seismic		37,171 psi	70,000 psi

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	N/A		


# APPENDIX A

# APPENDIX A

WYLE LABORATORIES Norco, California

FIGURE 3-1

## INPUT TEST LEVELS FOR THE BIAxIAL TESTING



APPENDIX B

**MSC<sup>®</sup>**

MASTER SPECIALTIES CO.  
1640 MONROVIA AVE.  
COSTA MESA, CALIFORNIA

## ENGINEERING TEST REPORT

REPORT NO. 058-1165-75B  
PAGE 21 OF 24  
DATE 10/14/75  
PREPARED BY K. Koch  
APPROVED BY L. Whitbeck  
DESC REPORT NO.

APPENDIX "B"

### 5.0 SUMMARY OF RESULTS

#### 5.1 SEISMIC VIBRATION TEST

- 5.1.1 Definition of a mechanical resonance is arbitrary, and is commonly set at a ratio of 2 to 1 (response to input) throughout industry in testing of this nature. There were no significant resonances over the frequency range of 1 to 35 Hz except at 27 Hz as indicated in Attachment V, pages 28 and 29, where the ratio reached 2.18 to 1. It should be noted that this small resonance was insignificant compared to the main resonance at 46 Hz, and that this was with covers removed: A condition that will not occur in actual application.
- 5.1.2 There was no evidence of structural damage.
- 5.1.3 There was no contact chatter exceeding 10 microseconds on the MSC 10H Series lighted pushbutton panel mounted switches except for one isolated incidence at <100 microseconds. This occurred on the Wyle "G" machine, which was exhibiting a considerable amount of "3rd-axis" vibration during this biaxial test. It is the opinion of Master Specialties that this chatter was due to the addition of the "3rd-axis" element in the vibration. This opinion is based further on the fact that in subsequent testing no chatter occurred on these units.
- 5.1.4 The lamps lighted and remained lighted before, during and after the seismic vibration tests.
- 5.1.5 All switches maintained their mechanical and electrical selection positions.
- 5.1.6 The normal mounting hardware retained the assemblies in the panels before, during, and after the seismic test.
- 5.1.7 The Micro Switch heavy duty oil-tight switches exhibited contact chatter and an open condition up to 1.3 milliseconds.

506-2-32-2



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Auxiliary Feedwater Pump Motor1. Scope: ☐ NSSS ☒ BOP2. Model Number: 3020SS6 Type AZ Quantity: 1/Unit3. Vendor: Byron Jackson (Pump)/Allis Chalmers (Motor)4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Horizontal 800 HP Motorb. Dimensions 83.62" Long x 47.25" in Dia.c. Weight 9700 lbs6. Location: Building: Storage Tank AreaElevation: 31'-8 5/16"7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1 1/4 Motor  
to Pump Baseplate)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >100 HZ F/B: 92.5 HZ V: >100 HZ9. a. Functional Description: Driver for Auxiliary Feedwater Pumpb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both 10. Pertinent Reference Design Specifications: S023-405-6 QCII  
Auxiliary Feedwater Pumps and Drivers

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: N/A

Analysis: Static

Combination of Test and Analysis: N/A

Analysis by Allis-Chalmers  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
5. ☒ Combination of Seismic & Operating  
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): S023-SK-S-986, 987, 988, 989
3. Required Acceleration in Each Direction: ZPA  
S/S = 1.2g F/B = 1.2g V = 1.3g

VI. If Qualification by Test, then Complete: N/A

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No. \_\_\_, Size \_\_\_) ☐ Weld (Length \_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results):  
\_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: \_\_\_\_\_ N/A
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☒ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: In-house program of the Rayleigh Principle  
Frequency Range and No. of modes considered: freq. >33 HS  
☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☒ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: N/A Basis for the damping used: Rigid
7. Support Considerations in the model: 2-shaft bearings (pinned supports)

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Motor Mounting Bolts	Between Pump Base- plate and Motor	Weight	Not Broken Out	Shear 2127 Tension Ø	10,000psi 20,000psi
	Bearing Reactions	Ends of Shaft	Rotor Offset	1074 lbs	2447lbs	2447 lbs

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	0.1067	Between Rotor and Stator	This is 24% of the deflection that would cause loss of function.

# APPENDIX A

100

50

25

10

5

2

2

$S_d = 10 T^2 S_a$   
 $S_d$  = DISPLACEMENT RESPONSE (INCHES)  
 $T$  = PERIOD (SEC.)  
 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONDENSATE AND REFUELING  
TANK ENCLOSURE STRUCTURE BASEMAT

Prepared By:	Reviewed By:	Approved By:
RC	AL/LGH	JFO'S
JOB NO. 10079-003	SKETCH NO. 5023-SK-S-986	REV. A

ACCELERATION ( $g$ 's)

14  
12  
10  
8  
6  
4  
2  
0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%


DAMPING = 5.0%

PERIOD (seconds)

0.01 0.02 0.03 0.04 0.06 0.08 0.1 2 3 4 6 8 1 2 3 4 5

11/4/77

FREQUENCY (cycles per second)



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Diesel Fuel Oil Transfer Pump Motor

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: AC Motor Frame 180 HP Type T Quantity: 8
3. Vendor: Pump (Goulds)/Motor (Westinghouse)
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Vertical Cylinder 1-HP Motor  
 b. Dimensions ≈10" Diameter x 15" Tall  
 c. Weight ≈10 lb. Motor Only
6. Location: Building: Diesel Fuel Oil Storage Tank Vault  
 Elevation: ≈26'-6"
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 3/8) Motor to Pump  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: None Provided F/B:  V:
9. a. Functional Description: Diesel Fuel Oil Pump Driver. Pump transfers fuel from storage tanks to day tanks.  
 b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both Emergency & Test Condition
10. Pertinent Reference Design Specifications: S023-405-12  
QC II Diesel Fuel Oil Transfer Pumps



III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: Static

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Westinghouse Electric (Log S023-405-12-38-0)  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Seismic and Operating
6. Method of combining RRS: ☒ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): S023-SK-S-756-B, 757-B
3. Required Acceleration in Each Direction:  
S/S = 3.0 F/B = 3.0 V = 2.0

VI. If Qualification by Test, then Complete: N/A

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No.\_\_\_\_, Size\_\_\_\_) ☐ Weld (Length\_\_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: \_\_\_\_\_ N/A
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_ N/A
- Frequency Range and No. of modes considered: \_\_\_\_\_ >33Hz
- ☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☒ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ N/A Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: Thrust Bearing at Bottom  
Guide Bearing at Top

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Bottom Bearing	Bottom of Motor	Seismic + Normal Oper- ating Load	270 lbs	390 lbs	3070 lbs
	Shaft	Center of Motor	Seismic + Normal Oper- ating Load	1721 psi	1855 psi	58,500 psi

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	0.00034 in.	Between stator and rotor	None, Allowable = 0.0212"

# APPENDIX A

86-95255

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZ. ACCEL. RESPONSE SPECTRA  
FOR MISCEL. EQUIP. AT GRADE

Prepared By:

H.W.

Reviewed By:

KMS LGH

Approved By:

WBB

JOB NO.

10079-003

SKETCH NO.

S023-SK-S-756

REV.

B

ACCELERATION (g's)

5

4

3

2

1

9% DAMPING

5% DAMPING

TO OBTAIN VERTICAL RESPONSE  
ACCELERATION MULTIPLY BY 0.75

.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-30-73 A

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-0352A Solenoid Valves

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: V52600-539 Quantity: 8  
3. Vendor: Valcor Engineering Corp.  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance 3/4" size, 2-way w/latching type operator  
b. Dimensions 12.61"H x 6.5"W  
c. Weight 21 lbs.  
6. Location: Building: Penetration Room  
Elevation: 37'-4-1/2"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >33Hz. F/B: >33Hz. V: >33Hz.  
9. a. Functional Description: Containment pressure sensing line isolation valve.  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: S023-507-4

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X (By Similarity)

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Valcor Test Report #V52600-539

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "A"
3. Required Acceleration in Each Direction:  
S/S = 0.9g F/B = 0.9g V = 0.9g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat ☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis Bi-Axial
3. No. of Qualification Tests: OBE Ten (10) SSE Six (6) Other \_\_\_\_\_  
(specify)
4. Frequency Range: 1-50Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No (See Appendix "B")  
TRS exceeds RRS above 3.5 Hz

6. Input g-level Test at S/S = 2.7g F/B = 2.7g V = 4.0g

7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_, Size \_\_) ☒ Weld (Length Continuous) ☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: By similarity and test, the subject valve performance or operation is not affected by acceleration level of 5gs min. and all structural resonances are greater than 33Hz.

10. Other tests performed (such as fragility test, including results):

Operability test - 5 times at 125 VDC.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

1. Description of Test including Results: \_\_\_\_\_

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

APPENDIX "A"  
(2 PAGES)

# ATTACHMENT "A"

1 OF 2

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

JWW K/S

Reviewed By:

LSV DB

Approved By:

WHS GLE

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-641

REV.

1

ACCELERATION (g's)

12

11

10

9

8

7

6

5

4

3

2

1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01

.02

.03

.04

.06

.1

.2

.3

.4

.6

.8

1

2


3

4

5

PERIOD (seconds)

8-23-73



ATTACHMENT "B"  
(4 PAGES)

105


Plotted by: Wm. CLAUDINSON  
Checked by: WJ

DAYTON T. BROWN INC.  
Testing Laboratories

Test Item: VALVES 2" #37  
Serial Number(s): 1 & 2  
Unit: Operational ☒ Non-operational ☐

1466 Enc I Pg 59

Lab Form D-24



Vibration Axis: X-Z  
Test Condition: RANDOM

DAMPING = 2.5%  
55E TEST  
SPECTRUM #2  
2.5% DAMPING  
SONGS 2+3 RRS

Pickup Serial Number: 459  
Pickup Location: CONT  
Pickup Sensing Axis: X

Pickup Sensitivity: 100.0  $\frac{mv \text{ peak}}{g \text{ peak}}$   
☐ Live ☒ Tape

Job Number: 401418-00-0000  
Date: 14 Oct 76  
Time: 1202

1 of 4

Relative db (20 db/decade)  
ATTACHMENT "B"  
Graph Number: 87

11/5

Plotted by: P. RANKIN

Checked by: \_\_\_\_\_




Test Item: VALUES 2" x 3/4"

Serial Number(s): 142

Unit: Operational ☒ Non-operational ☐

Vibration Axis: X-Z  
Test Condition: RANDOM



Relative db (20 db/decade)

Graph Number:

96

Pickup Serial Number: 459

Pickup Location: CONT

Pickup Sensing Axis: X

Pickup Sensitivity: 100.0  $\frac{mv \text{ peak}}{g \text{ peak}}$

☐ Live ☒ Tape

Job Number: 401418-00-000

Date: 14 OCT 76

Time: 1440

2 OF 4

1466 Enc 1 Pg 67


Lab Form D-24



Plotted by: R. RANKIN  
Checked by: WJB

DAYTON T. BROWN INC.  
Testing Laboratories

Test Item: VALVES 2" & 1"  
Serial Number(s): 1 & 2  
Unit: Operational ☒ Non-operational ☐



Pickup Serial Number: 457  
Pickup Location: CONT  
Pickup Sensing Axis: VERT

Pickup Sensitivity: 100.0  $\frac{mv \text{ peak}}{g \text{ peak}}$   
☐ Live ☒ Tape

Job Number: 401418-00-0000  
Date: 14 Oct 76  
Time: 1112

1466 Enc 1 Pg 53

Lab Form D-24

Relative db (20 db/decade)

Graph Number:

3 of 4



11/5

Plotted by: R. RANKIN


Checked by: NS

DAYTON T. BROWN INC.  
Testing Laboratories

Test Item: VALUES 2" & 3/4"

Serial Number(s): 142

Unit: Operational ☒ Non-operational ☐



Pickup Serial Number: 457

Pickup Location: CONT

Pickup Sensing Axis: VERT 2

Pickup Sensitivity: 100.0  $\frac{mv \text{ peak}}{g \text{ peak}}$

☐ Live ☒ Tape

Job Number: 401418-00-000

Date: 19 OCT 76

Time: 1600

1466 Enc I Pg 69

Lab Form D-24

Relative db (20 db/decade)

Graph Number:

4 of 4

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-0502 Solenoid Valves

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: 75G-002 Quantity: 54  
3. Vendor: Target Rock Corporation  
4. If the component is a cabinet or panel, name and model No. of the devices included: Not Applicable  
5. Physical Description a. Appearance 1" Y-Pattern, Globe Body  
b. Dimensions 15"H x 21"W  
c. Weight 42 lbs.  
6. Location: Building: Containment Bldg.  
Elevation: 34'-7"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: Jct. Box - 20Hz F/B: Jct. Box - 18 Hz V: Jct. Box - 33Hz  
Main Vlve. - 137.5Hz Mn. Vlve. - 137.5Hz Mn. Vlve. - 137.5Hz  
9. a. Functional Description: Containment atmosphere sample isolation valve.  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: S023-507-4.

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by TRC Report # 1674, TRC Report #1931A  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): N/A
3. Required Acceleration in Each Direction:  
S/S = 3g F/B = 3g V = 3g

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
1/2 Octave Intervals ☐ sine beat  
☒ Continuous sine  
(30 sec. @ ea.  
frequency)
2. ☐ Single Axis ☒ Multi-Axis Bi-Axial
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other N/A  
(specify)
4. Frequency Range: 1-35Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No  
Not Applicable

6. Input g-level Test at S/S = 4.5g F/B = 4.5g V = 4.5g  
and 8" double amplitude below 4hz.

7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_, Size \_\_) ☒ Weld (Length Continuous) ☒ Supported only by end connections

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See Appendix "A"

10. Other tests performed (such as fragility test, including results):

Aging, radiation, leak test, functional test

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

1. Description of Test including Results: \_\_\_\_\_

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response	Seismic	Total	Stress
			Combination	Stress	Stress	Allowable

B.	<u>Max. Deflection</u>	<u>Location</u>	Effect Upon Functional
			<u>Operability</u>

# APPENDIX A

PREPARED BY \_\_\_\_\_

CHECKED BY \_\_\_\_\_

APPROVED BY \_\_\_\_\_

**TARGET ROCK CORPORATION**  
EAST FARMINGDALE LONG ISLAND, N. Y.

PAGE 6 OF 10

REPORT 1827 *B*

PROJECT 75G

6.0

CONCLUSIONS

The tests and test results described herein demonstrates that the solenoid valves tested are capable of withstanding the extreme environs of both before and after accident simulation. The valve thus qualifies for use in both inside and outside containment applications. The valve design is mechanically rugged and ideally suited for the intended applications.

507-4-45-1

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-4712 Control Valve

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 70-28-2 Quantity: Four (4)
3. Vendor: W-K-M, ACF Industries, Inc.
4. If the component is a cabinet or panel, name and model  
No. of the devices included: N/A
5. Physical Description a. Appearance 4" Globe Body, Motor Operated  
b. Dimensions 23.5"H x 19"W x 22" Deep  
c. Weight 340 lbs.
6. Location: Building: Refueling Water Storage Tank Building  
Elevation: 45'-0"
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 26; 57Hz F/B: 19.5Hz V: 80; 97Hz
9. a. Functional Description: Aux. Feedwater Pump Discharge to Steam Generator  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: S023-507-5



III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Southwest Research Institute

Report #02-4958-002

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Hydrostatic & seismic loads.
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "A"

3. Required Acceleration in Each Direction:

S/S = .9g F/B = .9g V = .9g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis Bi-Axial

3. No. of Qualification Tests: OBE Five(5) SSE Two(2) Other \_\_\_\_\_  
Per each (specify)  
Horiz  
Direction

4. Frequency Range: 1-100 Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No

\*TRS exceeds RRS above 2-1/2 Hz and all natural frequencies.

6. Input g-level Test at S/S = APP B F/B = APP B V = APP B
7. Laboratory Mounting: \*
1. [ ] Bolt (No.       , Size       ) [ ] Weld (Length       ) [X] Pipe Circumference
8. Functional operability verified: [X] Yes [ ] No [ ] Not Applicable
9. Test Results including modifications made: See Appendix "C"
10. Other tests performed (such as fragility test, including results):  
Seat Leak Test - See Appendix "C"

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete: N/A

- [illegible]

\*Valve welded to flange. Flange bolted to bookends. Bookends bolted to shake table.

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# APPENDIX A

ATTACHMENT "A"

(2 PAGES)

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE (g's)
DAMPING VALUES  
AS PERCENT OF CRITICALBECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

JWW KMS

Reviewed By:

LSN Q3

Approved By:

W. J. Lee

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-641

REV.

L

ACCELERATION (g's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%


DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73



ATTACHMENT "B"

(2 PAGES)



# ATTACHMENT "B"




Figure 10-3. Horizontal Excitation at the Table, DBE, 5% Damping




Figure 10-4. Vertical Excitation at the Table, DBE, 5% Damping

507-5-1-264-0

ATTACHMENT "C"

## 8.0 Results and Conclusions

Section 10.0 shows the TRS's and RRS's for horizontal and vertical OBE's and DBE's at 5% damping. Section 11.0 contains copies of the SwRI laboratory data logs describing in detail the test performance. The salient feature of these tests is that at no time was hydro leakage greater than 33 cc's per hour. This is less than the requirement of 40 cc's per hour as given in the WKM Seismic qualification Procedural Outline referenced in Section 3.0. It should be pointed out that the valve was open and closed during test for every test, and leakage measured after each test without reseating the valve. Air seat leakage tests before and after testing indicated the maximum air seat leakage was 125 cc's per minute. This is well below the 164 cc's per minute given in the Air Seat Leak Test Specification referenced in Section 3.0. The valve shaft displaced normally during each OBE and DBE without any indication of hesitation for interrupted displacement. Because the time to open or close the valve was approximately 20 seconds, it was not possible to cycle the valve completely during each test. To demonstrate that actuation was normal, the valve was cycled as much as possible during test, alternately starting from an open and closed position for each test. To assure that actuation would be unaffected by the SSE levels, regardless of whether the valve was opening or closing, two SSE's were run. In SSE No. 1 the valve was open. In SSE No. 2 the valve was closed during test. No cracks or signs of structural failure were observed during or after the tests. Monitoring for functionality indicated that the valve behaved normally before, during and after all the tests.

Section 10.0 contains the resonant frequency search data. Resonant frequency searches were performed at 1/2 octave per minute sweep rate in the range 1 - 100 Hz. The input level for all axes, except the X-axis was .2 g's. The X-axis input level was reduced .1 g at the resonance found at 19.5 Hz to prevent potential prequalification test stressing of the valve. The plots show the following resonances: for the Y-axis excitation, 26 Hz and 57 Hz; for X-axis excitation, 19.5 Hz; for Z-axis excitation, 80 and 97 Hz. All resonant searches were performed for the valve open and the valve closed positions. The results showed no substantial change and resonant frequencies were obtained as a result of valve position.

Section 10.0 contains the Test Response Spectrum plots obtained for the OBE's and DBE's in both vertical and horizontal directions at the base of the motor operator. These TRS's may be used for a device qualification test in the future, in the event the motor operator is replaced.

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-9300 Control Valve

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: N9126-EMO-SP Quantity: Four (4)  
3. Vendor: Walworth Co., Aloyco  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance 24", Gate Valve, Motor Operated  
b. Dimensions 91"H x 39"W  
c. Weight 2860 lbs.  
6. Location: Building: Refueling Water Bldg. in Auxiliary Bldg.  
Elevation: 32'-0"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 13Hz F/B: 17Hz; 29Hz V: >33Hz  
9. a. Functional Description: Refueling Water Tank Outlet.  
b. Is the equipment required for ☐ Hot Standby ☒ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: S023-507-5

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Labs. Report # 44242-1

Walworth Report #223

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Seismic & Internal Pressure
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "A"

3. Required Acceleration in Each Direction:

S/S = 1.0 F/B = 1.0 V = 0.75

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis
3. No. of Qualification Tests: OBE Five(5) SSE One(1) Other -  
for each (specify)  
Horiz.  
direction
4. Frequency Range: 1-40Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No  
TRS exceeds RRS above 2.5 Hz and at natural frequencies.

See Appendix "B"

6. Input g-level Test at S/S = 3g F/B = 3g V = 3g
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No.\_\_\_\_, Size\_\_\_\_) ☒ Weld (Length\_\_\_\_) ☒ Bookends bolted to shake table
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: The specimen tested demonstrated sufficient - integrity to withstand, without compromise to structure or function, the prescribed seismic environment.
10. Other tests performed (such as fragility test, including results):  
Seat leak test.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: Not Applicable
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response Combination	Seismic Stress	Total Stress	Stress Allowable
----	-----------------------	-----------------	--	-------------------	-----------------	---------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	Effect Upon Functional Operability
----	------------------------	-----------------	---------------------------------------




ATTACHMENT "A"

# ATTACHMENT 'A'

FREQUENCY (cycles per second)

10F2



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 6, ELEVATION 37'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WMB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-898

REV.

A 7/24/73

ACCELERATION (g's)



PERIOD (seconds)

ATTACHMENT "B"

FULL SCALE SHOCK SPECTRUM (g Peak)

Page No. 44


Report No. 44242-1

ATTACHMENT "B"

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 5% ☒

1 OF 4



SPECIMEN \_\_\_\_\_

LOCATION NO. HCA

AXIS LONG/VERT

TEST RUN NO. 12

507-5-2-123-0

45


# FULL SCALE SHOCK SPECTRUM (g Peak)

Page No. 45  
Report No. 44242-1

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☒ 5%

2 OF 4



SPECIMEN \_\_\_\_\_

LOCATION NO. VCR

AXIS LONG/VERT

TEST RUN NO. 12

507-5-2-123-0

46


# FULL SCALE SHOCK SPECTRUM (g Peak)

Page No. 42  
Report No. 44242-1

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 2 ☒ 9/10

3 OF 4



SPECIMEN \_\_\_\_\_

LOCATION NO. HCA

AXIS LONG/VERT

TEST RUN NO. 12

507-5-2-123-0

43




# FULL SCALE SHOCK SPECTRUM (g Peak)

Page No. 43  
Report No. 44242-1

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☒ 2%

4 OF 4



SPECIMEN \_\_\_\_\_

LOCATION NO. VLA

AXIS LONG/VERT

TEST RUN NO. 12

507-5-2-123-0

44



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-4714 Control Valve

1. Scope: ☐ NSSS ☒ BOP  
2. Model Number: 7-4058-EP-SS-120 Quantity: Four (4)  
3. Vendor: Fisher Controls  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance 6" size, Motor Operated Valve  
b. Dimensions 65.12"H x 42.5"W  
c. Weight 1500 lbs. (Operator & Body)  
6. Location: Building: Aux Feedwater Tunnel  
Elevation: 17'-10"  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >52Hz F/B: >52Hz V: >52Hz  
9. a. Functional Description: Aux. Feedwater to Steam Gen. E088 Isolation Valve.  
b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: S023-503-7-1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Fisher Report #FQP-2A-8

Wyle Lab. Report #58271-2

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
 3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
 5. ☒ Combination of Seismic Load & Operating Load  
 6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS ☐ N/A  
 (other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "B"

3. Required Acceleration in Each Direction:

S/S = 0.8 F/B = 0.8 V = 0.9

VI. If Qualification by Test, then Complete: (Actuator Operability)

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis Bi-Axial
3. No. of Qualification Tests: OBE 0 SSE 18 Other \_\_\_\_\_  
 (specify)
4. Frequency Range: 1-60Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No  
TRS exceeds RRS above 2.7 Hz. See Appendix "A"

6. Input g-level Test at S/S = 2.9 F/B = 2.9 V = 2.4
7. Laboratory Mounting: (Valve welded to flange; flange bolted to table through bookends.)
1. ☐ Bolt (No. \_\_, Size \_\_) ☐ Weld (Length \_\_) ☒ Rigidly attached to test table
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: The seismic qualification documentation presented for this valve group meets the intent and requirements of the specification for its application.
10. Other tests performed (such as fragility test, including results):  
Aging, Radiation and Accident Condition (Wyle Labs. Report #58271-2.)

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then  
Complete:

- [illegible]

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Act. Yoke	Leg Stress	Static Seismic and Operational	*	8,518.3	26,250.0
	Bolts	Actuator to Bonnet	Static Seismic and Operational		28,002	60,000

\*Included in total stress

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	0.017	Node 1	None

# APPENDIX "A"

(4 PAGES)

# APPENDIX 'A'

1 OF 4

WYLE LABORATORIES

Report No. 58271-2

CUSTOMER FISHER CONTROLS

Job No. 58271

Page No. 153

Full Scale 100 g

Accel. No. 2

Control ( $\checkmark$ )

Response ( )

Operator MEEHAN

Specimen 0009


Date 6-20-78

Damping 1 %  
5%

Axis of Test Y-Z VERT

9TN554

## RESPONSE SPECTRUM



WYLE LABORATORIES

Report No. 58271-2

CUSTOMER FISHER CONTROLS

Job No. 58271

Page No. 175

Full Scale 100 g

Accel. No. 2

Control (↔) Response ( )

Operator MERHAN

Specimen 008


Date 6-21-79

Damping 1 %  
5 %

Axis of Test Y-Z VERT

18TH SSE

RESPONSE SPECTRUM



WYLE LABORATORIES

Report No. 58271-2

CUSTOMER FISHER CONTROLS Job No. 59271

Page No. 152


Full Scale 100 g Accel. No. 1 Control (✓) Response ( )

Operator MEEHAN Specimen 0008

Date 6-20-78 Damping 1 % 5 % Axis of Test X-Z Horiz

97N 556

RESPONSE SPECTRUM



503-7-1-924-0



WYLE LABORATORIES

Report No. 58271-2

CUSTOMER FISHER CONTROLS

Job No. 58271

Page No. 174

Full Scale 100 g

Accel. No. 1

Control (1) Response ( )

Operator MEEHAN

Specimen 0008


Date 6-21-78

Damping 1 %  
5-9

Axis of Test Y-Z NORM

18TH SSE

RESPONSE SPECTRUM



503-7-1-924-0

# APPENDIX "B"

(2 PAGES)

# APPENDIX "B"

1 OF 2

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 36'-0"

Prepared By:

JWW KMS

Reviewed By:

LGH QJB

Approved By:

WAB g/c

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-639

REV.

A

ACCELERATION ( $g$ 's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .06 .08 .1 2 3 4 .5 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE (g's)
DAMPING VALUES  
AS PERCENT OF CRITICALBECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 36'-0"

Prepared By:

JWW KMS

Reviewed By:

LGH

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-640

REV.

A

ACCELERATION (g's)

11

10

9

8

7

6

5

4

3

2

1

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5

823-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X

2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2HV-6200 Control Valve

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 7640 w/486-U-1-16-80 Actuator Quantity: Eight (8)
3. Vendor: Fisher Controls
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description
  - a. Appearance 30" Butterfly w/pneumatic operator
  - b. Dimensions 60.31"H x 81.67"W
  - c. Weight 1641 lbs. (Total Valve Assembly)
6. Location: Building: Intake Structure Area  
Elevation: 10'-0"
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1-1/4")  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S:  F/B: \*45.3Hz V:
9.
  - a. Functional Description: Saltwater Cooling Pump P-112, Discharge Control Valve
  - b. Is the equipment required for ☐ Hot Standby ☒ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: S023-507-2-1

\*Lowest frequency determined by analysis.

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: X (Static)

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Fisher Report #s CD-75-156; -161  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
5. ☒ Combination of Seismic and Operational  
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): Not Applicable
3. Required Acceleration in Each Direction: (Req'd by specification)  
S/S = 5g F/B = 5g V = 5g

VI. If Qualification by Test, then Complete:

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No. \_\_\_, Size \_\_\_) ☐ Weld (Length \_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NOTE: Resonant test was conducted and resonant frequency measured at 40.5Hz to qualification reports for equipment supplied by subvendors: (1) Sol. Valve Asco report #AQS-21678, (2) Limit Switch Namco report #EA-180
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: Fisher Seismic 4  
Frequency Range and No. of modes considered: N/A  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☒ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: N/A Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: Valve assumed horizontally mtd. on pipe with valve shaft mounted horizontal to simulate actual field mounting

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load</u>	<u>Seismic</u>	<u>Total</u>	<u>Stress</u>
			<u>or Response</u>			
			<u>Combination</u>	<u>Stress</u>	<u>Stress</u>	<u>Allowable</u>
	Steel	Elem. #20		-	13.2 ksi	27 ksi
	Steel	Elem. #46		-	16.1 ksi	27 ksi
	Bolts	Joint 4, Location B		-	31.9 ksi	94.5 ksi

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional</u>
	<u>0.033"</u>	<u>Node 33</u>	<u>Operability</u>
			None



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X

2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: 2PSV-8401 Relief Valve\*

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 6R10 HA-75-FN Quantity: 36
3. Vendor: Crosby Valve & Gage Company
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description
  - a. Appearance 6"x10" Size (See App. "A")
  - b. Dimensions 61.75" H x 34"W
  - c. Weight 1550 lbs.
6. Location: Building: Main Steam Isolation Valve Area  
Elevation: 42'-0"
7. Field Mounting Conditions ☒ Bolt (No. 12, Size 1-3/8) INLET  
(No. 16, Size 1") OUTLET  
☐ Weld (Length     )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 34 Hz. F/B: 36 Hz V: >35 Hz.
9. a. Functional Description: Safety Valve For  
Main Steam Service
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: S023-507-3

\* Vent Stacks are not installed.

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No  
Vent Stack Not Installed

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Crosby Report #5 3718, 3719

Crosby Report #5 EC-276 & EC-187

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): See Appendix "B"

3. Required Acceleration in Each Direction:

S/S = 5g F/B = 5g V = 5g

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ continuous sine

2. ☐ Single Axis ☒ Multi-Axis Bi-axial

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \* 3 Test Cycles  
(specify)

4. Frequency Range: 28, 32 & 35 Hz.

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

6. Input g-level Test at S/S = 5g F/B = 5g V = 5g

\* A Test Cycle is opening, reseating and pop lifting.

7. Laboratory Mounting: On Test Apparatus (See Appendix "A")
1. [X] Bolt (No. 12, Size 1-3/8") [ ] Weld (Length       ) [ ]                       
(No. 16, Size 1") [ ] Weld (Length       ) [ ]
8. Functional operability verified: [X] Yes [ ] No [ ] Not Applicable
9. Test Results including modifications made: The Ability of the subject Valve to operate before, during and after a simulated seismic disturbance has been demonstrated properly without irregularities in its performance and damage to its parts.
10. Other tests performed (such as fragility test, including results):
- Operability Test

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then  
Complete:

1. Description of Test including Results: With the Simulated Seismic Load applied, the valve was cycled 3 times following the test procedure.  
There was no evidence of unacceptable valve operation, instability or inconsistency in valve performance observed.
2. Method of Analysis:
- [ ] Static Analysis      [X] Equivalent Static Analysis
- [ ] Dynamic Analysis      [ ] Time-History  
                                [ ] Response Spectrum
3. Model Type:      [ ] 3D                      [ ] 2D                      [X] 1D
- [ ] Finite Element      [ ] Beam                  [ ] Closed Form Solution
4. [ ] Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- [X] Hand Calculations
5. Method of Combining Dynamic Responses: [ ] Absolute Sum    [X] SRSS  
  [ ] Other: \_\_\_\_\_  
  (specify)
6. Damping: N/A Basis for the damping used: N/A
7. Support Considerations in the model: Fixed

## 8. Critical Structural Elements:

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	PSI	PSI
					Total Stress	Stress Allowable
	Body	-	Operating & Seismic	-	8,302	17,500
	Inlet Stud	-	Hydrostatic & Opera-	-		
			ting & Seismic	-	20,681	25,000
	Bonnet Arm	-	Operating & Seismic	-	8,609	17,500


B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	N/A		

APPENDIX A

**CROSBY**

**CROSBY VALVE & GAGE COMPANY**  
WRENTHAM, MASS

APPENDIX A



Photograph 1. Valve and Loading Apparatus Installed in Test Area.

APPENDIX B

# APPENDIX "B"

1 OF 2

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

JWW K/S

Reviewed By:

LSV QB

Approved By:

WLB JRE

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-641

REV.

L

ACCELERATION (g's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%


.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73



FREQUENCY (cycles per second)



8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
 2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name NSSS Auxiliary Relay Cabinet

1. Scope: ☐ NSSS ☒ BOP  
 2. Model Number: N/A (Custom Made) Quantity: 4  
 3. Vendor: NMC Controls, Inc.  
 4. If the component is a cabinet or panel, name and model No. of the devices included: See Appendix "A"  
 5. Physical Description a. Appearance Cabinet with bays "A," "B", & Bay "A" & "B" - 156" Long, 56" Wide and 90" high.  
 b. Dimensions Bay "X" - 84" Long, 56" Wide and 90" High.  
 c. Weight 6858 Lbs.  
 6. Location: Building: Control Room (Auxiliary Bldg.)  
 Elevation: 30'-0"  
 7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length 6") Welds on  
☐  12-1/2" Centers  
 8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: None Below 35Hz F/B: 13.1, 20.7, 29.0Hz V: None Below 35Hz  
 9. a. Functional Description: Cabinet Houses Different Aux. Relays Switches & Resistors For The NSSS Systems.  
 b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both   
 10. Pertinent Reference Design Specifications: S023-306-1

Centers

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Test and/or Analysis by Analysis - 12461-2 Acton Lab. Test - 12888 & 12461-1  
(Name of Company or Laboratory & Report No.)  
Bechtel Log: S023-306-1-37

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
5. ☐ Combination of \_\_\_\_\_  
6. Method of combining RRS: ☐ Absolute Sum ☒ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): See Appendix "B"
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 1 F/B = 1 V = 1

VI. If Qualification by Test, then Complete:

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat  
☐ \_\_\_\_\_
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \* SSE \* Other \_\_\_\_\_  
(specify)
4. Frequency Range: 1-35 Hz
- \*5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
\_\_\_\_\_
6. Input g-level Test at S/S = 2g F/B = 2.0g V = 1.75g.
7. Laboratory Mounting: \_\_\_\_\_  
1. ☐ Bolt (No., Size) ☒ Weld (Length \*) ☐ \_\_\_\_\_

\* Information not given in the report.

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: Equipment Qualified  
No Modifications.
10. Other tests performed (such as fragility test, including results):

Component Functional Test

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: Bays "A" & "B" Tested on a shake Table and Verified that the Data necessary to show that mathematical model used for analysis of the cabinet is correct.
2. Method of Analysis:
- |  |   |
|--|---|
| <input type="checkbox"/> Static Analysis             | <input type="checkbox"/> Equivalent Static Analysis   |
| <input checked="" type="checkbox"/> Dynamic Analysis | <input type="checkbox"/> Time-History                 |
|  | <input checked="" type="checkbox"/> Response Spectrum |
3. Model Type: ☒ 3D ☐ 2D ☐ 1D
- ☒ Finite Element ☐ Beam ☒ Closed Form Solution
4. ☒ Computer Codes: MR1/Stardyne CDC 6600
- Frequency Range and No. of modes considered: 1-35 Hz, 7 Modes/5 of Significance
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☒ SRSS
- ☐ Other: \_\_\_\_\_  
(specify)
6. Damping: 4% Basis for the damping used: Reg. Guide 1.61
7. Support Considerations in the model: Fixed

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Panel Stiffness		Operational & Seismic	14,992	16,382	33,000
	Panel Relays		Operational & Seismic	2,864	4180	33,000

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	X1 = 0.002"		None
	X2 = 0.089"		
	X3 = 0.39"		

## APPENDIX "A"

EQUIPMENT TESTED

Seventeen (17) different panel mounted equipment were tested. The panel mounted equipment were divided into three groups, and each group was mounted to a test fixture and tested separately as a group. The groups were divided in the following manner:

GROUP A

<u>NMC NO.</u>	<u>DESCRIPTION</u>
1002202	MDR 131-1 P&B Relay
1002206	MDR 5060 P&B Relay
1002204	MDR 137-8 P&B Relay
1002207	MDR 5061 P&B Relay
1002205	MDR 138-7 P&B Relay
1002203	MDR 134-1 P&B Relay
-----	MDR 163-1 P&B Relay
222858	GE#CR15162 Terminal Block

GROUP B

224827	MTS-202B Ganged DPSW
1002210	Model 7014PD Agastat Relay
1002212	MF4122 P&B Relay
-----	MDR 141-1 Relay

GROUP C

233325	Ohmite 2.5K 2S W Resistor
223414	14K, 5W Fixed Resistor
238516	100K, 2W Variable Resistor

Report No. 12461-1



# CALCULATION SHEET

CALC. NO. \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_ CHECKED \_\_\_\_\_ DATE \_\_\_\_\_

PROJECT \_\_\_\_\_ JOB NO. \_\_\_\_\_

SUBJECT \_\_\_\_\_ SHEET \_\_\_\_\_ OF \_\_\_\_\_ SHEETS

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

APPENDIX "B"



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WOB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-895

REV.

A 7/24/73

ACCELERATION (g's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-696

REV.

A 7/24/72

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLB LGH

Approved By:

WUB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-719

REV.


A

ACCELERATION ( $g$ 's)



PERIOD (seconds)

7-24-73



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Salt Water Cooling Pumps

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 33 WX - 1-Stage, Vert. Quantity: 4/Unit
3. Vendor: Byron Jackson
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Vertical Cylinder
- b. Dimensions ≈42' Long x 3'-2" Diameter
- c. Weight 17,400 lb Total (Pump and Motor)
6. Location: Building: Intake Structure
- Elevation: + 9'-0"
7. Field Mounting Conditions ☒ Bolt (No. 16, Size 1-1/8)
- ☐ Weld (Length )
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- \*S/S: 22.6 F/B: 24.6, 27.2 V: 60.22
9. a. Functional Description: Pumps seawater through  
Tube side of component cooling water heat exchangers.
- b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown
- ☐ Both
10. Pertinent Reference Design Specifications: S023-405-3A  
QC II Saltwater Cooling Pumps

\* Other frequencies 33 Hz.

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: Dynamic

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Douglas B. Nickerson P.E.

Bechtel Log S023-405-3A-Z-3

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Seismic, Hydrodynamic, Dead Weight
6. Method of combining RRS: ☒ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): S023-SK-S-671-C, 672-C

3. Required Acceleration in Each Direction:

S/S = 1.18 F/B = 1.18 V = 0.64

VI. If Qualification by Test, then Complete: N/A

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No. \_\_\_, Size \_\_\_) ☐ Weld (Length \_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: \_\_\_\_\_ N/A
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☒ Dynamic Analysis ☐ Time-History  
☒ Response Spectrum
3. Model Type: ☐ 3D ☒ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: BMDAT, CANBM, MDLDF, STRESS  
Frequency Range and No. of modes considered: 1-1000Hz, 4 Modes  
☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☒ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: 1% Basis for the damping used: R.G. 1.61 None Specified
7. Support Considerations in the model: Trunion Loaded Flat Plate  
2-Seismic Restraints



8. Critical Structural Elements: See Appendix "B"

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Discharge Nozzle	Discharge of Pump	Pressure	Not Provided	137	275
	Motor Mounting Bolts	Connect Motor to Pump	Seismic & Normal Op.	13,499	13,576	27,000
	Bearings	Every 56 - 57"	Seismic & Normal Op.	0.69	0.69	20 = 30

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	0.00868"	Wear Rings	None Clearance = 0.00682 No. Binding



# APPENDIX A

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZ ACCEL RESPONSE SPECTRUM  
FOR INTAKE STRUCTURE

Prepared By:

RET/JKC

Reviewed By:

LGH DGB

Approved By:

JM (ES)

JOB NO.

1304-803

SKETCH NO.

5023-SK-5611

REV. 2-11-75

C

ACCELERATION (g's)

5

4

3

2

1

% DAMPING  
0  
1/2  
1  
2

TO OBTAIN VERTICAL RESPONSE  
ACCELERATION MULTIPLY BY 0.75

.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

# APPENDIX B

MATERIALS AND STRESS TABLE

<u>Item</u>	<u>Material</u>	<u>Allow. Stress</u>	<u>Calc. Stress (DBE)</u>	<u>Margin</u>	<u>Calc. Page</u>
Discharge Head					
Nozzle- Discharge	ANSI B16.5	275 psi Wkg. Press	137 psi	1.01	A1.10
Nozzle- Air Relief	ANSI B16.5	275 psi Wkg. Press	144	.91	A1.8
Shell	SB-169 CDA 614	18 000	2 229	5.81	A1.10
Base Plate	SB-169 CDA 614	18 000	3 152	4.71	A1.14
Cycl. Sep. Mtg. Bkt.	SB-169 CDA 614	18 000	521	High	A1.20
Cycl. Sep. Mtg. Bolts	SB-150 CDA 630	12 500	229	High	A1.21
Mounting Bolts	ASTM A-193 B8M	27 000	10 302	1.62	A1.16
Motor Mounting Bolts	ASTM A-193 B8M	27 000	13 576	.99	A1.17
Foundation Bolts	Unknown- Customer Furnished		9 830		A1.16
Column - Top Flange					
Flange	SB-169 CDA 614	18 000	6 157	1.92	A2.19
Hub	SB-169 CDA 614	18 000	4 993	2.61	A2.19
Bolts	SB-150 CDA 630	12 500	3 930	2.18	A2.19
Column - Maximum Stress Flange					
Flange	SB-169 CDA 614	18 000	6 319	1.85	A2.19
Hub	SB-169 CDA 614	18 000	5 125	2.51	A2.19
Bolts	SB-150 CDA 630	12 500	4 033	2.10	A2.19
Shaft Tube	SB-169 CDA 614	18 000	605	High	A3.22
Lineshaft	ASTM A-479 XM19	25 000	5 198	3.81	A4.3

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Auxiliary Feedwater Pumps

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: 4 x 6 x 9 D 8-Stage DVMX Quantity: 4
3. Vendor: Byron Jackson
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance 8-Stage Centrifugal Pump  
 b. Dimensions ≈90" x 46"  
 c. Weight ≈6500 lbs
6. Location: Building: Storage Tank Area  
 Elevation: 31' - 8-5/16"
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 1")  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: Turb. Driv. 232 Hz F/B: Turb. Driv. 266 Hz V: Turb. Driv. 626 Hz  
Mtr. Driv. 139 Hz Mtr. Driv. 159 Hz Mtr. Driv. 528 Hz
9. a. Functional Description: Provides feedwater to the steam generators during emergency conditions, hot standby.  
 b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: S023-405-6  
QCII Auxiliary Feedwater Pumps and Drivers.

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: Static

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Byron Jackson DC 1102 Rev. C

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
5. ☒ Combination of Nozzle, Dead Weight, Seismic  
6. Method of combining RRS: ☒ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)
2. Required Response Spectra (attach the graphs): S023-SK-S-986, 987, 988, 989
3. Required Acceleration in Each Direction: ZPA  
S/S = 1.2 F/B = 1.2 V = 1.3

VI. If Qualification by Test, then Complete: N/A

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No., Size) ☐ Weld (Length) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: \_\_\_\_\_ N/A
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☒ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: MULTISPAN, Lomakin  
Frequency Range and No. of modes considered: 33 Hz  
☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☒ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: N/A Basis for the damping used: ZPA (Rigid)
7. Support Considerations in the model: Pinned supports at the two end bearings and a spring support at the center.

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load	<u>Seismic</u>	<u>Total</u>	<u>Stress</u>
			or Response Combination			
				<u>Stress</u>	<u>Stress</u>	<u>Allowable</u>

See Appendix "B"

B.	<u>Max. Deflection</u>	<u>Location</u>	Effect Upon Functional
			<u>Operability</u>
	0.00261	Rotor	Min. Clearance = 0.006 No binding will occur.



# APPENDIX A

100 50 25 10 5 2 1 .5 .2

$S_d = 10 T^2 S_a$   
 $S_d$  = DISPLACEMENT RESPONSE (INCHES)  
 $T$  = PERIOD (SEC.)  
 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA Edison COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONDENSATE AND REFUELING  
TANK ENCLOSURE STRUCTURE BASEMAT

Prepared By:	Reviewed By:	Approved By:
RC	AL/LGH	JFO'S
JOB NO. 10075-003	SKETCH NO. S023-SK-S-956	REV. A

ACCELERATION ( $g$ 's)

14  
12  
10  
8  
6  
4  
2  
0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

0.01 0.02 0.03 0.04 0.06 0.08 0.1 2 3 4 6 8 1 2 3 4 5

11/4/77

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10^{-2} S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE (g's)
DAMPING VALUES  
AS PERCENT OF CRITICAL

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION (g's)

BECHTEL POWER CORPORATION  
LOS ANGELES DIVISIONSOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONDENSATE AND REFUELING  
TANK ENCLOSURE STRUCTURE BASEMAT

Prepared By:

BZ

Reviewed By:

AL/JGH

Approved By:

JFO'S

JOB NO.

10079-003

SKETCH NO.

5023-SK-S-987

REV.

A

.01

.02

.03

.04

.06

.1

2

3

4

5

8

1

2

3

4

5

APPENDIX B






FIGURE 3 TYPICAL PUMP FOOT

405-6-81-2

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Component Cooling Water Heat Exchanger

1. Scope: ☐ NSSS ☒ BOP
2. Model Number: N/A Quantity: 4
3. Vendor: Struthers Wells
4. If the component is a cabinet or panel, name and model No. of the devices included: Not Applicable
5. Physical Description a. Appearance Horizontal Cylinder with 3 support legs.
- b. Dimensions 48'-6" Overall Length by 63" OD
- c. Weight 178,000 lb. Flooded
6. Location: Building: Safety Equipment Bldg. (CCW HE & Rooms)  
Elevation: 8'-0"
7. Field Mounting Conditions ☒ Bolt (No. 12, Size 2")  
☐ Weld (Length )  
☒ Bolt (No. 4, Size 1.25" (Center Support))
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >33 Hz F/B: >33 Hz V: 31.3 pg 98
9. a. Functional Description: Single pass counter flow heat exchanger, transfers component cooling water system heat to the saltwater cooling system.
- b. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: S023-404-4  
QC II specification for component cooling water and spent fuel Pool Heat Exchangers.

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: N/A

Analysis: Yes Bechtel Log S023-404-4-79-2

Combination of Test and Analysis: N/A

Test and/or Analysis by Struthers Wells

No Report No., Order No. 1-74-06-32404

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Seismic, Nozzle, Dead Weight, Pressure
6. Method of combining RRS: ☒ Absolute Sum ☐ SRSS ☐ \_\_\_\_\_  
(other, specify)

2. Required Response Spectra (attach the graphs): S023-SK-S-929, 934, 943

3. Required Acceleration in Each Direction:

S/S = DBE = 1.0 F/B = DBE = 1.0 V = DBE = 1.0

VI. If Qualification by Test, then Complete: N/A

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_ Other \_\_\_\_\_  
(specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No



6. Input g-level Test at S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No., Size) ☐ Weld (Length) ☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: N/A
2. Method of Analysis: \_\_\_\_\_
- ☒ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☒ Response Spectrum
3. Model Type: ☒ 3D ☐ 2D ☐ 1D  
☒ Finite Element ☒ Beam ☐ Closed Form Solution
4. ☒ Computer Codes: TUSUP, TRESUP, ANSYS (Struthers Wells Proprietary)  
Frequency Range and No. of modes considered: 31.29 to 239.44 Hz, 5 Modes  
☒ Hand Calculations
5. Method of Combining Dynamic Responses: ☒ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: N/A Basis for the damping used: Lowest Freq. is on ZPA
7. Support Considerations in the model: Anchor and 2-Guides

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
	Anchor Bolt Stresses	Support A (Fixed)	Nozzle, Pres- sure Dead Weight Seismic	25,214 9,074	25,214 12,506	40K tension 15K shear.
	Shell	All	Nozzle, Pres- sure, Dead Weight and Seismic	15,153	23,530	30K
	Support Stress	Support A	Nozzle, Pres- sure, Dead Weight and Seismic	13,120	18,551	30K

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	+ 0.125 inch. (worst case)	Ends of heat exchanger	Deflection at Tube Sheets is $\cong$ 0.060 inches vertically.

# APPENDIX A

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.70



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
E-W HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 8'-0" OF  
SAFETY EQUIPMENT BUILDING

Prepared By:

JDC

Reviewed By:

KM JGH

Approved By:

WE

JOB NO.

10079-003


SKETCH NO.

S023-SK-S-929

REV.

A 4-16-75

ACCELERATION (g's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.70



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
N-S HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 8'-0" OF  
SAFETY EQUIPMENT BUILDING

Prepared By:

*JMC*

Reviewed By:

*K'nd KGH*

Approved By:


*WJG*

JOB NO.  
10079-003

SKETCH NO.  
S023-SK-S-934

REV.  
A 4-16-75

ACCELERATION (g's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 8'-0" OF  
SAFETY EQUIPMENT BUILDING  
(COMPONENT COOLING AREA)

Prepared By:

JPIC

Reviewed By:

Hand LGH

Approved By:

WLG

JOB NO.

10079-003

SKETCH NO.


S023-SK-S-043

REV.

B

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.60

ACCELERATION (g's)



APPENDIX B

# FROM STRUTHERS WELLS PROPOSAL No. 6828-L6 DATED Nov. 8, 1973

## 5.01.4 ENGINEERING DATA

### 5.01.4.1 Heat Exchanger Materials

Materials to be specified by ASME number.

Item	Component Cooling Water HX	Spent Fuel Pool HX
Shell	A-285-C	A-285-C
Shell Cover	---	---
Shell Mounting Support	A-36 or Eq.	A-36 or Eq.
Shell Flange: Front/Rear	---	---
Stationary Head/Channel	A-516-70	A-240 TP 304L
Channel Cover	A-516-70	A-240 TP 304L
Nozzles: Shell/Head	A-106-B	A-106-B/A-312
Nozzle Flanges: Shell/Head	A-105-II	A-105-II/A-240
Pass Partition	---	---
Channel Lining	Not Available	---
Tubes	B-111	A-249
Tube Plugs	B-164	A-479
Tube Sheet	B-402	A-240
Transverse Baffles/Support Tube Plates	A-36 or Eq.	A-36 or Eq.
Longitudinal Baffles	---	---
Tie Rods and Spacers	A-575-1020/A-214	A-575-1020/A-214
Impingement Plate	A-240 TP 304	A-240 TP 304
Lifting Lugs	A-515-70	A-515-70
Nuts and Bolts	A-193-B7	A-193-B7
Packing	---	---
Gasket	1330	Not Available
Cradle for Tube Bundle Removal	---	---



### 5.01.4.2 Physical Data

Item	Component Cooling Water HX	Spent Fuel Pool HX
Type: Front End Head	TEMA C	TEMA C
Horiz. Shell No. of	TEMA E	TEMA E
Passes	1	1
Rear End Head	TEMA C	TEMA C
Shell Outside Dia./Thickness	62" / 1/2"	28-3/4" / 3/8"
Shell Overall Length	38'-1 3/4"	16'-10 3/4"
Tube: Quantity/O.D./BWG	2956/3/4/18	490/3/4/22
Tube: Straight or U/Length EFF.	37'-6"	16'-8"
Tube: Stationary or Floating	---	---
Liquid Volume: Shell Side	420 Ft. <sup>3</sup>	46 Ft. <sup>3</sup>
Tube Side	460 Ft. <sup>3</sup>	33 Ft. <sup>3</sup>
Total Surface Area	22,062	1,624
Effective Surface Area	21,760	1,602
Minimum Clearance for Tube Replacement, Ft.-In.	38'-1 3/4"	16'-10 3/4"
Shell Connection: Size/ Rating/Facing	28"/150#/RF	12"/150#/RF
Channel Conn.: Size/Rating/ Facing	30"/150#/RF	10"/150#/RF
Dry Weight: 1. Shell	26,700	3,800
2. Tube Bundle*	78,800	7,500
Total Operating Weight	170,400	16,900
Shipping Dimensions and Weight	6'x8'x52'/106,300	4'x5'x21'/11,500
Manufacturer's/Size/Model No.	61-38N11-6H	28-17N11-6H

\* Not Removable

### 5.01.4.3 Data Sheets

Bidders shall complete the attached heat exchanger data sheets and fill in the blank spaces indicated by asterisks on S023-SK-M-330-A and S023-SK-M-332-A.

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Plant Protection System Cabinet

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 1  
3. Vendor: Electro Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: See attached sheet  
5. Physical Description a. Appearance 4 Bay Vertical Cabinet  
b. Dimensions 150" L x 54" W x 90" H  
c. Weight 13000#  
6. Location: Building: Control Area, Auxiliary Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 12, Size 1")  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 11, 32 F/B: 8.5  
V: Various 10-33  
9. a. Functional Description: Enclosure for modules of the PPS  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3001, Rev. 03,  
1370-ICE-3001, Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: With dummy loads

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics, Inc., QR-5330-1

Lab. - Wyle Laboratory Report 42836-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE 5 SSE 2  
Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS envelops RRS at natural frequencies

## 6. Input g-level Test at:

S/S = 1.15F/B = 1.35V = 0.85

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 12, Size 1") ☐ Weld (Length N/A)  
☐ \_\_\_\_\_8. Functional operability verified: ☐ Yes ☐ No ☒ Not Applicable9. Test Results including modifications made: See attaches sheet

10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:

1. Description of Test including Results: \_\_\_\_\_

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## II.4 Devices Included

Nuclear Instrument  
 CPC Test Module  
 Matrix Test Module  
 Relay Card Rack  
 Bistable Control Panel  
 Actuation Reset Panel  
 Trip Path Panel  
 AC Distribution Panel  
 Power Supply Panel  
 RPS Initiation Relay  
 Solenoid Transformer  
 Cabinet Cooler Assembly  
 Tested separately.

## VI. Test Results

NATURAL FREQUENCIES: VERTICAL	Various 10-33 Hz	SIDE / SIDE	11.32 Hz	FRONT / BACK	8.5 Hz
ELECTRICAL OPERATION	NA				
PHYSICAL INTEGRITY	Satisfactory with (1) loosening of power supply mounting screws and (2) slapping of cabinet doors; no other physical effects				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS	6,000 psi				
MAXIMUM EXTERIOR DEFLECTION	Less than 3/4 inch				
DYNAMIC LOAD TO MOUNTING	Not Calculated				
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES	Less than 2.1 to 1				

### VI. DISCUSSION

The Plant Protection System Cabinet was tested with equivalent dummy modules in place of functional electronic modules. During the full level (SSE) tests the mounting points of the supported (dummy) modules are monitored by accelerometers whose outputs were evaluated by spectrum analysis to yield the response spectra to which the functional modules must be qualified.

Lockwashers were incorporated as a design modification to the power supply mounting screws to prevent loosening.

The cabinet was tested without the door gaskets in place. Door gaskets are a standard feature on all production cabinets and will prevent door slapping.

# TEST RESPONSE SPECTRA

DATA SHEET No. 1

DATE November, 1973

REVISION No. 1

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION


☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)



# SCE Control Room Response Spectra

San Onofre station

SSE - vertical - 1% B




PPS Cabinets: minimum of two vertical tests



# SCE Control Room Response Spectra

San Onofre Station

SSE - Horizontal - 1% A



ft. Control: minimum of two horizontal tests (F/E 5/5)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Nuclear Instrument Safety Channels

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: ELE 304-3002 Quantity: 4  
3. Vendor: General Atomic  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Chassis-Rack Mounted  
b. Dimensions 10.8" x 24" x 24"  
c. Weight 70#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☐ Bolt (No. 2, Size 10-32)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 26, 33 F/B: 32 V: 29  
9. a. Functional Description: Provide neutrol flux level signal to PPS  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3006 Rev. 03  
1310-ICE-3006

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report 54406  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
[ ] \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.1g input F/B = 1.8g input V = 1.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
[ ] sine beat  
[ ] \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS envelops RRS at natural frequencies.

6. Input g-level Test at:  
S/S = 2.1 F/B = 2.5 V = 1.8
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 2, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☒ Slides
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES	VERTICAL	29 Hz	SIDE-SIDE	26.33 Hz	FRONT-BACK	32 Hz
ELECTRICAL OPERATION	Proper Operation Verified; Outputs monitored verified operation within specified limits					
PHYSICAL INTEGRITY	Intact; no physical effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

#### VI. DISCUSSION

During resonance survey the front panel resonated and a brace was attached. Test was continued verifying brace corrected problem. No other problems encountered. This brace has been incorporated into this generic design.

The Safety Drawer was mounted to the test fixture using drawer slides identical to those in the actual permanent mounting assembly. It was connected to a power source and to the preamplifier/filter assembly, located external to the test fixture, through five hundred feet of cable. The entire mounting arrangement was intended to closely duplicate the actual field installation. Prior to performing the seismic test, the assembly was calibrated to ensure proper circuit operation. All safety related functions of the drawer were monitored by the visicorder. These included the rate of change of power signal, the log power, calibrated linear sum and all three linear subchannel outputs. In addition, proper bistable operation was verified by monitoring the "15% bistable and "10-4% bistable on the visicorder.

The three linear subchannels received a simulated 200% power signal, from an external power source, which resulted in a ten volt output to the visicorder. The log power circuitry received a test input via the preamplifier, by placing the "LOG CALIBRATE" Switch, on the Safety Drawer front panel, in the "TEST 3" Position. This simulated a power level of approximately  $10^{-2}$ , and resulted in an output to the visicorder of approximately six volts. The  $10^{-4}$  bistable, which was energized during the test, and the 15% bistable, which was deenergized, each had a ten volt signal fed through the closed portions of their respective form C output contacts, to the visicorder input.

All monitored outputs behaved as specified prior to, during, and subsequent to the seismic test. In addition to monitoring the log output during the seismic test, the "LOG CALIBRATE" Switch was checked in all six test positions prior to and after testing. A Calibration Check was performed on the Drawer after testing, and proper operation verified.

# TEST RESPONSE SPECTRA

DATA SHEET No. 1a

DATE March, 1977

REVISION No. 01

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1%

J/N \_\_\_\_\_  
Page \_\_\_\_\_  
Date \_\_\_\_\_

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFEL & ESSER CO. MADE IN USA




FIGURE 11

PREDICTED COMPOSITE RESPONSE SPECTRA FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN #10)



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1%

J/N \_\_\_\_\_  
Page \_\_\_\_\_  
Date \_\_\_\_\_

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.


FIGURE 12

PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN #13)

## FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1%

J/N \_\_\_\_\_  
Page \_\_\_\_\_  
Date \_\_\_\_\_

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN #24)

## FULL SCALE SHOCK SPECTRUM (g Peak)


1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1%

J/N \_\_\_\_\_

Page \_\_\_\_\_

Date \_\_\_\_\_



Frequency (Hz)

FIGURE 14

PREDICTED COMPOSITE RESPONSE SPECTRA FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN #27)

Qualification Summary of Equipment

- I. Plant Name: San Onofre Units 2&3 Type:
1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: PPS CPC Test Module

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: NA Quantity: 4
3. Vendor: Electro-Mechanics
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Two section panel assembly
- b. Dimensions 24" x 11" x 8-3/4"
- c. Weight ≈30#
6. Location: Building: Control Area Auxiliary Building
- Elevation: 30 - 0
7. Field Mounting Conditions ☐ Bolt (No. 8, Size 1/4-20)
- ☐ Weld (Length )
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >40 F/B: >40 V: >40
9. a. Functional Description: Provides CPC interface
- for periodic off-line testing.
- b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: 00000-ICI-3001, Rev. 03
- 1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

-Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics Inc. QR-5330-1  
(Name of Company or Laboratory & Report No.)  
Lab - Wyle Laboratories Report No. 43386-1

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
[ ] \_\_\_\_\_  
(Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 2.4g input F/B = 2.4g V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
[ ] \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)
3. No. of Qualification Tests: OBE 5 SSE 2  
Other \_\_\_\_\_  
(Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at: S/S = 5.1 F/B = 5.8 V = 3.5
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 8, Size 1/4-20) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## VII TEST RESULTS

### V. RESULTS

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Performance as required; no output perturbations before during or after the test.	
PHYSICAL INTEGRITY	Intact; no physical effects.	
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		



# TEST RESPONSE SPECTRA

DATA SHEET No. 1b

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN USA



Frequency (Hz)

AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 37


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V


LOCATION NO. VCR

TEST RUN NO. 37

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %



AXIS SS/V

LOCATION NO. HCB

TEST RUN NO. 115


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V

LOCATION NO. VCP

TEST RUN NO. 45

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: PPS - Matrix Test Module1. Scope: ☒ NSSS ☐ BOP2. Model Number: None Quantity: 43. Vendor: Electro-Mechanics4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Two section moduleb. Dimensions 24" x 8" x 5-7/32"c. Weight ≅40#6. Location: Building: Control Area Aux. BldgElevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 8, Size 1/4-20)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >40 F/B: >40V: >409. a. Functional Description: Test system for matrices and trip pathsb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics, QR-5330-1  
Lab. - Wyle Laboratories, Report No. 43386-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Ax[Bi-axial]
3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:

S/S = 5.7

F/B = 5.4

V = 3.3

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 8, Size 1/4-20) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):  
 \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element ☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION See Below _____		
PHYSICAL INTEGRITY Intact; No physical effect _____		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

#### VI. DISCUSSION

The matrix test modules are used during preventative maintenance to test the six matrices within the PPS. These modules provide test output voltages to selectively energize and/or deenergize the appropriate matrix hold relays and the bistable dropout relays.

Matrix testing is accomplished by energizing a test power supply and depression of the module matrix test pushbutton. Actuation of this pushbutton will allow testing of that matrix and will prevent the remaining matrices from receiving their required test power.

Before, during, and after seismic excitation the matrix hold relays and bistable dropout relays were simulated and the matrix test module pushbutton output was continuously monitored.

During seismic excitation the only perturbation found was the chattering (1 millisecond duration) of the matrix test pushbutton normally closed contacts (NC). This is not considered a failure since the chatter will only prevent the matrices from being tested.

# TEST RESPONSE SPECTRA

DATA SHEET No. 1c  
DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN USA



Frequency (Hz)  
SS/V FB/V  
AXIS MTM & PS RR & ARP  
LOCATION NO. 1410  
TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFILL & ESSER CO. MILWAUKEE



Frequency (Hz)  
SSIX FSIX  
 AXIS MTM & PS RR & ARP  
 LOCATION NO. VCA  
 TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K·Σ LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

SS/V

FB/V

AXIS RR & ARP NTM & PS

LOCATION NO. HCP

TEST RUN NO. 68


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SSIV FBIV  
AXIS RR+ARP MTM+PS  
LOCATION NO. VCR  
TEST RUN NO. 68

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: PPS - Relay Card Rack

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Electro-Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Two section panel assembly  
b. Dimensions 24" x 27" x 21"  
c. Weight 400#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 10, Size 1/4-20)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >40 F/B: >40  
V: >40  
9. a. Functional Description: Enclosure for all relay card functions  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics Inc. QR-5330-1

Lab. - Wyle Laboratories, Report No. 43386-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

## 6. Input g-level Test at:

S/S = 5.2

F/B = 5.2

V = 4.1

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 10, Size 1/4-20) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis:

☐ Static Analysis☐ Dynamic Analysis☐ Equivalent Static Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element☐ Beam☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other:

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES	VERTICAL _____	SIDE - SIDE _____	FRONT - BACK _____
ELECTRICAL OPERATION	Performance as required; all relays energized and deenergized properly, without contact perturbations before, during and after the test.		
PHYSICAL INTEGRITY	Intact; no physical effects.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS _____			
MAXIMUM EXTERIOR DEFLECTION _____			
DYNAMIC LOAD TO MOUNTING _____			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____			
_____			
_____			

# TEST RESPONSE SPECTRA

DATA SHEET No. 1d

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V

LOCATION NO. VCP

TEST RUN NO. 8.3


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 76


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 ☒ 0.1 ☐ 0.01 ☐ 0.001

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V  
LOCATION NO. VCA  
TEST RUN NO. 76




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V  
LOCATION NO. HCA  
TEST RUN NO. 83

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: PPS - Bistable Control Panel

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Electro-Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Drawer Assembly  
b. Dimensions 24" x 26" x 21"  
c. Weight ≈400#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 10-32)  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >40 F/B: 30  
V: >40  
9. a. Functional Description: Enclosure for Bistable  
Differential Bistable, Variable Setpoint and Bypass Functions  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☒ Both \_\_\_\_\_  
10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro Mechanics Inc. QR-5330-1  
Lab. - Wyle Laboratories, Report No. 43386-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]
3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

## 6. Input g-level Test at:

S/S = 5.1

F/B = 5.4

V = 3.9

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 8, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES	VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Performance as required; no signal or contact perturbation; all circuit cards performed within specifications.		
PHYSICAL INTEGRITY	Satisfactory; vibration of a retaining rod caused the retaining rod screw to come loose. No other physical effects. See discussion Item 2 below.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

## 1. Functional Testing

- A. Variable Setpoint Card - The input signal to the card was simulated using a ramp generator. Increasing the input signal results in an increase in the trip setpoint output. Decreasing the input signal will result in the trip setpoint output remaining constant. While the input was decreased the reset function of the card was verified. A reset will result in the trip setpoint decreasing to a predetermined margin below the input signal.
  - B. Bistable and Differential Bistable Comparators - A simulated input signal was used to verify proper comparator function over its full range. This consisted of initiating comparator trips at various trip setpoints and monitoring the input and setpoint voltages and output contacts.
  - C. Trip Channel Bypass Switches - A voltage was applied via a loading resistor. The resulting voltage drop across the resistor was monitored to ensure proper switch operation. This verified that no inadvertant bypass would occur during the SSE.
  - D. Trip Channel Bypass Relays - These relays were energized and deenergized. The output contacts were continuously monitored to verify proper operation.
  - E. The above listed tests were performed prior to, during, and after seismic excitation. Evaluation of test data verified that all of these components functioned within their design specifications.
2. The bistable control panel retaining rod was taped in place to simulate a retaining clamp. Retaining clamps have been incorporated as a design modification to the bistable control panel.

1e.

# TEST RESPONSE SPECTRA

DATA SHEET No. 1e

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS S-S/V

LOCATION NO. HCA

TEST RUN NO. 92




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1% ☒

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS S-S/V

LOCATION NO. VCP

TEST RUN NO. 92


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEIFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V  
LOCATION NO. HCB  
TEST RUN NO. 94


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V

LOCATION NO. VCA

TEST RUN NO. 94

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: PPS Actuation Reset Panel

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: None Quantity: 4
3. Vendor: Electro-Mechanics
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Vertical panel
- b. Dimensions 3" x 3-3/4" x 30"
- c. Weight ≈20#
6. Location: Building: Control Area: Aux. Bldg.
- Elevation: 30'
7. Field Mounting Conditions ☒ Bolt (No. 10, Size 10-32)
- ☐ Weld (Length )
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >40 F/B: >40
- V: >40
9. a. Functional Description: Provides manual reset for RPS and ESF functions
- b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03
- 1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro Mechanics Inc., QR-5330-1  
Lab. - Wyle Laboratories, Report No. 43386-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

## 6. Input g-level Test at:

S/S = 5.3F/B = 4.9V = 3.5

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 10 , Size 10-32 ) ☐ Weld (Length \_\_\_\_\_)  
[ ] \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NAVII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NSSS 1f

NATURAL FREQUENCIES, VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION <u>Performed as required; no contact perturbations occurred before, during or after the test.</u>		
PHYSICAL INTEGRITY <u>Intact; No physical effects</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

VI. DISCUSSION



# TEST RESPONSE SPECTRA

DATA SHEET No. 1f  
DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUPAEL & ESSER CO. MADE IN USA



Frequency (Hz)  
SS/V FB/V  
AXIS NTM+PS RR & ARP  
LOCATION NO. 14.0  
TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN USA



Frequency (Hz)  
SSIV FRIV  
 AXIS MTM & PS RR & ARP  
 LOCATION NO. VCA  
 TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN USA



Frequency (Hz)  
SS/V FB/V  
 AXIS RR&ARP NTM&PS  
 LOCATION NO. HCR  
 TEST RUN NO. 68


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SSIV FBIV  
AXIS RR+ARP MTM & PS  
LOCATION NO. VCR  
TEST RUN NO. 68

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: PPS Trip Path Panel

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 8  
3. Vendor: Electro-Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Box-like assembly  
b. Dimensions 14-3/8" x 4-5/32" x 18"  
c. Weight ≈50#  
6. Location: Building: Control Area, Auxiliary Building  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/4-28)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 36 F/B: >40 V: >40  
9. a. Functional Description: Enclosure for RPS interposing and ESF initiation relays.  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICI-3001, Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics Inc. QR-5330-1

(Name of Company or Laboratory & Report No.)

Lab - Wyle Laboratories Report No. 43386-1

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.4g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE 5 SSE 1

Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at: S/S = 5.2 F/B = 5.6 V = 3.5
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 4, Size 1/4-28) ☐ Weld (Length \_\_\_\_\_)
- ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):
- NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis
- ☐ Dynamic Analysis ☐ Time-History
- ☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D
- ☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS
- ☐ Other: \_\_\_\_\_
- (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI TEST RESULTS

NATURAL FREQUENCIES	VERTICAL _____	SIDE - SIDE _____	FRONT - BACK _____
ELECTRICAL OPERATION	Performed as required; no contact perturbations before, during and after the tests.		
PHYSICAL INTEGRITY	Intact; no physical effect		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS _____			
MAXIMUM EXTERIOR DEFLECTION _____			
DYNAMIC LOAD TO MOUNTING _____			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____			

## VI. DISCUSSION

# TEST RESPONSE SPECTRA



DATA SHEET No. 1g

DATE MARCH 1977



SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL } TEST PLANE  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT) } RESPONSE DIRECTION  
☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)



☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL } TEST PLANE  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT) } RESPONSE DIRECTION  
☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)

AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 37


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V


LOCATION NO. VCR

TEST RUN NO. 37

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %



AXIS SS/V

LOCATION NO. HCB


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K.E. LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V

LOCATION NO. VCP

TEST RUN NO. 45

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. N555: CE 3. A/E: Bechtel BWR

II. Component Name: PPS - AC Distribution Panel

1. Scope: ☒ N555 ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Electro-Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Box-like assembly  
b. Dimensions 10" x 4" x 9"  
c. Weight ≈10#  
6. Location: Building: Control Area, Auxiliary Building  
Elevation: 30'  
7. Field Mounting Conditions ☐ Bolt (No. 2, Size 10-24)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 36 F/B: >40 V: >40  
9. a. Functional Description: Distribute 120 V AC  
to PPS channels.  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICI-3001, Rev. 03  
1370-ICE-3001 Rev. 01



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics Inc., QR-5330-1

(Name of Company or Laboratory & Report No.)

Lab - Wyle Laboratories Report No. 43386-1

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE 5 SSE 1

Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at: S/S = See TRS F/B = \_\_\_\_\_ V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 2, Size 10-24 X 3/4)
- ☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):
- NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis
- ☐ Dynamic Analysis ☐ Time-History
- ☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D
- ☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS
- ☐ Other: \_\_\_\_\_
- (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI.9 Test Results

NATURAL FREQUENCIES: VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Performed as required; No output signal perturbations.</u>		
PHYSICAL INTEGRITY <u>Intact; no physical effects.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

# TEST RESPONSE SPECTRA

DATA SHEET No. 1h

DATE MARCH 1977

SPECTRUM FULL SCALE:

ACCELERATION ☐ 10 g ☒ 100 g

FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN USA



Frequency (Hz)

AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 37


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




AXIS FB/V  
LOCATION NO. VCR  
TEST RUN NO. 37

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %



AXIS SS/V

LOCATION NO. HCB


TEST RUN NO. 115



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %



AXIS SS/V

LOCATION NO. VCP

TEST RUN NO. 45

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison CompanyPWR X2. NSSS: CE3. A/E: BechtelBWR II. Component Name: PPS Power Supply Panel1. Scope: ☒ NSSS ☐ BOP2. Model Number: None Quantity: 43. Vendor: Electro Mechanics4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Door with power supplies attachedb. Dimensions 27-3/4" x 4-1/2" x 66-1/4"c. Weight ≈700#6. Location: Building: Control Area: Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 25, Size 10-32)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >40F/B: 23V: >409. a. Functional Description: Provide dc power to PPS channelsb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☒ Both 10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanical Inc. QR-5330-1

Lab. - Wyle Laboratories, Report No. 43386-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

## 6. Input g-level Test at:

S/S = 4.9

F/B = 5.3

V = 3.5

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 25, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D ☐ 2D ☐ 1D☐ Finite Element ☐ Beam ☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES	VERTICAL _____	SIDE - SIDE _____	FRONT - BACK _____
ELECTRICAL OPERATION	Performed as required; See section VI (Discussion)		
PHYSICAL INTEGRITY	All power supplies remained structurally intact, See discussion below.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS _____			
MAXIMUM EXTERIOR DEFLECTION _____			
DYNAMIC LOAD TO MOUNTING _____			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____			

## VI DISCUSSION

1. During the half level tests three anomalies occurred and were corrected.

- A. Anomaly - The base of the power supply panel deflected which caused the power supply output signals to deviate.  
Correction - The base of the power supply panel was stiffened by bolting a section of angle iron to the bottom of the assembly and welding the angle iron to the test fixture floor and testing continued with no further problem.

An angle iron stiffening bracket has been incorporated as a design modification to the power supply panel.

- B. Anomaly - Wire chafing occurred in the vicinity of the power supply input fuses.  
Correction - The cable harness was found to be chafing on the fuse holders. The cable harness was pulled away and testing continued with the problem not re-occurring. Wire harness standoffs have been incorporated as a design modification to the power supply panel.

- C. Anomaly - Various screw and nuts loosened which did not effect power supply performance.  
Correction - Screws and nuts were periodically tightened during remainder of tests. As a final modification to the power supply panel, "Locktite" will be incorporated into the mounting hardware design.

# TEST RESPONSE SPECTRA

DATA SHEET No. 11  
DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SS/V FB/V  
AXIS NTM+PS RR & ARP  
LOCATION NO. 1420  
TEST RUN NO. 59



1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING 1 %



**LOGARITHMIC X 3 CYCLES**  
GUTHRIE'S ESSENCE CO. YALE, CT.

Frequency (Hz) SSIV FBIV  
 AXIS MTM & PS RR & ARP  
 LOCATION NO. VCA  
 TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUFEL & LESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SS/V FB/V  
AXIS RR & ARP NTM & PS  
LOCATION NO. HCP  
TEST RUN NO. 68


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SSIV FBIV  
AXIS RR&ARP MTM&PS  
LOCATION NO. VCR  
TEST RUN NO. 68

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: PPS Rotary Relay

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: MOR-170-1 Quantity: 4  
3. Vendor: Potter Brumfield  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Wall Mounted Relay  
b. Dimensions 4.19" x 4.19" x 5"  
c. Weight ≈3#  
6. Location: Building: Control Area, Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 2, Size 5/16-8)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 24 F/B: >40  
V: >40  
9. a. Functional Description: RPS initiations Relay  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro Mechanics Inc., QR-5330-1

Lab. - Wyle Laboratories, Report No. 43386-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:

$$S/S_0 = 5.3$$
$$F/B = \underline{\underline{4.9}}$$
$$V = \frac{1}{3.5}$$

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 2, Size 5/16-8) ☐ Weld (Length                     )  
                     Unistrut, Nut, Spring  
☐

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

## 2. Method of Analysis:

## [ ] Static Analysis

## [ ] Equivalent Static Analysis

[ ] Dynamic Analysis

[ ] Time-History

[ ] Response Spectrum

3. Model Type: ☐ 3D

[ ] 2D

[ ] 1D

☐ Finite Element    ☐ Beam

[ ] Closed Form Solution

#### 4. [ ] Computer Codes:

Frequency Range and No. of modes considered:

[.] Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other:

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION: <u>Performed as required; No contact malfunctions were detected during, before or after test</u>		
PHYSICAL INTEGRITY: <u>Intact; No physical effects.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

VI. DISCUSSION



# TEST RESPONSE SPECTRA

DATA SHEET No. 11

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
 FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SS/V FB/V  
AXIS MTM+PS RR & ARP  
LOCATION NO. 14.0  
TEST RUN NO. 59


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SSIV FBIV  
AXIS MM & PS RR & ARP  
LOCATION NO. VCA  
TEST RUN NO. 59


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SS/V FB/V  
AXIS RR & ARP NTM & PS  
LOCATION NO. HCP  
TEST RUN NO. 68


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.



Frequency (Hz)  
SSIV FBIV  
AXIS RR+ARP MTM+PS  
LOCATION NO. VCR  
TEST RUN NO. 68

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: PPS Sola Transformer1. Scope: ☒ NSSS ☐ BOP2. Model Number: 23-13-060-2 Quantity: 43. Vendor: Sola4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Rectangular Boxb. Dimensions 3-1/4" x 7" x 4-3/4"c. Weight ≈5#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 4, Size 10-32)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >33Hz F/B: >33HzV: >33Hz9. a. Functional Description: Isolates 120 Vac power to redundant cabinet cooler fansb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 00000-ICE-3001 Rev. 03  
1370-ICE-3001 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics, Inc. QR-5330-1

Lab. - Wyle Laboratories Report No. 43386-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1

Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

## 6. Input g-level Test at:

S/S = 5.2F/B = 5.3V = 4.1

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 4, Size 10-32 x 1/2) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:1. Description of Test including Results: N/A

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES: VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Performed as required; No output signal perturbations</u>		
PHYSICAL INTEGRITY <u>Intact; No physical effect</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

VI. DISCUSSION

1 R.

# TEST RESPONSE SPECTRA

DATA SHEET No. 1k

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

KE LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 76


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V  
LOCATION NO. VCA  
TEST RUN NO. 76


# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V


LOCATION NO. HCA

TEST RUN NO. 83

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 ☒ %



AXIS SS/V  
LOCATION NO. VCA  
TEST RUN NO. 8.3

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: PPS Cabinet Cooler Assembly

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Electro-Mechanics  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Trough Assembly  
b. Dimensions 24" x 26.6" x 7"  
c. Weight ≈30#  
6. Location: Building: Control Area, Auxiliary Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/4-20)  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >40 F/B: >40  
V: >40  
9. a. Functional Description: Ventilation of cabinet bay  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both \_\_\_\_\_  
10. Pertinent Reference Design Specifications: 00000-ICE-3001, Rev. 03  
1370-ICE-3001, Rev. 01



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Electro-Mechanics, Inc. QR-5330-1

Lab. - Wyle Laboratories, Report No. 43386-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 2.4g input F/B = 2.4g input V = 2.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:

S/S = 5.2

F/B = 5.3

V = 4.1

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 4, Size 1/4-20) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: N/A

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element

☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Performance as required; No perturbations, the fan and flow sensors operated before, during and after the test.	
PHYSICAL INTEGRITY		
Intact, no physical effects		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

VI. DISCUSSION

The air flow switch which was monitored is used only for annunciator purposes.

# TEST RESPONSE SPECTRA

DATA SHEET No. 11

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V

LOCATION NO. HCA

TEST RUN NO. 76


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS FB/V  
LOCATION NO. VCB  
TEST RUN NO. 76


FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K $\circ$ E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V  
LOCATION NO. HCA  
TEST RUN NO. 83




FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



AXIS SS/V

LOCATION NO. VCA

TEST RUN NO. 83

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
 2. NSSF: CE 3. A/E: Bechtel BWR

II. Component Name: Auxiliary Protective Cabinet

1. Scope: ☒ NSSF ☐ BOP  
 2. Model Number: None Quantity: 1  
 3. Vendor: Reliance Electric Company  
 4. If the component is a cabinet or panel, name and model No. of the devices included: Devices included in cabinet are those  
Listed as Items 2a - 2q in NSSF Equipment List.  
 5. Physical Description a. Appearance Vertical 4-bay cabinet  
 b. Dimensions 192" x 50" x 90" (L x W x H)  
 c. Weight 12000#  
 6. Location: Building: Control Area Auxiliary Building  
 Elevation: 30'  
 7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length 2-1/2" on 10" centers)  
☒ Length 5" on 10" centers front of  
Channel A and 1/3 Channel B  
 8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: 9.5, 29 F/B: 13.5, 27, 32 V: >40  
 9. a. Functional Description: Houses components in Plant  
Protection System  
 b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
 10. Pertinent Reference Design Specifications: 1370-ICE-3019 Rev. 0  
00000-ICE-3019 Rev. 0

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: Cabinet filled with Dummy Modules  
except for ventillation fan.

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Labs, 43482  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 1.0g input F/B = 1.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)
3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at: S/S = 3.5 F/B = 3.1 V = 1.9
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 20, Size 5/8-11 UNC)  
☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes Vent fans only  
☐ No \_\_\_\_\_ ☐ Not Applicable \_\_\_\_\_
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

VI.9 Test Results

NATURAL FREQUENCIES: VERTICAL	40 Hz	SIDE / SIDE	9.5, 29 Hz	FRONT / BACK	13.5, 27, 32 Hz
ELECTRICAL OPERATION	Fans operational except for one failure noted below. No other electrical malfunctions were noted.				
PHYSICAL INTEGRITY	During the testing a door switch vibrated loose.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS	3625 psi				
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

#### VI. DISCUSSION

One fan failed. Subsequent investigation indicated failure was from a loose set screw. All other fans were checked to verify that the same condition did not exist in those units.

One door switch vibrated loose. Subsequently, locking devices were placed on all door switches.

The cabinet was loaded with dummy modules to duplicate the in-service conditions.

TEST RESPONSE SPECTRA

DATA SHEET No. 5

DATE April 3, 1978

REVISION No. \_\_\_\_\_

SPECTRUM FULL SCALE:

ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION


☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)



# SCE Control Room Response Spectra

San Onofre Station

SSE - Horizontal - 1% A




Aux. Protective Cabinet: minimum of two horizontal tests  
(F/R & SS)



# SCE Control Room Response Spectra

San Onofre station

SSE - Vertical - 170A



Aux Protective Cabinet: minimum of two vertical tests

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: CPC Mass Storage Unit

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: None Quantity: 4
3. Vendor: Systems Engineering Laboratories
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Rack Mounted Chasis
- b. Dimensions 28" x 19" x 10-1/2"
- c. Weight 70 #
6. Location: Building: Control Area Aux. Bldg.
- Elevation: 30'
7. Field Mounting Conditions ☒ Bolt (No. 10, Size 10-32)
- ☐ Weld (Length )
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >40 F/B: 26
- V: 26
9. a. Functional Description: Facilitate periodic testing
- & maintenance
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown
- ☐ Both
10. Pertinent Reference Design Specifications: 00000-ICE-3004 Rev. 3
- 1370-ICE-3004, Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Systems Engineering Tabs; 524280-019  
Wyle Laboratories, Report 42915-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 1.4g input F/B = 1.4g input V = 1.3g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 7  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS exceeds RRS above 8Hz and at natural frequencies except at 25 and 40Hz horizontal.

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI.9. Test Results

NATURAL FREQUENCIES	VERTICAL	26 Hz	SIDE SIDE	25 Hz	FRONT BACK	None below 40 Hz
ELECTRICAL OPERATION	Performance as required - no degradation of input signal - post test diagnostics performed successfully.					
PHYSICAL INTEGRITY	Intact; no physical effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						


## VI. DISCUSSION

This equipment was subjected to seven (7) series of full-level sine-beat tests. The duration of each series (in each of two biaxial test directions) was 30 seconds. The frequency of each of the seven series was different. Based on the equipment natural frequencies, which were all determined to be above 25 Hz by the resonance survey, the test series involving the highest frequency sine-beats is sufficient for qualification. This test excited all equipment modes to ample acceleration levels, as indicated by the test response spectra on the reverse side of this sheet. The excitation frequencies of this test were 16 Hz in the horizontal direction and 8 Hz in the vertical direction.


REVISION No. 00

1 % CRITICAL DAMPING

**RESPONSE DIRECTION**



RESPONSE DIRECTION



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 ☒ 10 ☐ 100 ☐ 1000 ☐

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUTEL & ESSER CO. MADE IN U.S.A.




FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)



# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEITHLEY & ESSER CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
REYNOLDS & LINDSEY CO. MADE IN U.S.A.




FIGURE 15

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: CPC Central Processing Unit

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: System Engineering Laboratories  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Rack mounted chassis  
b. Dimensions 28" x 19" x 8"  
c. Weight 70#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 10-32)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 40 F/B: 30  
V: 30, 32  
9. a. Functional Description: Calculates and Compares Core Parameters with set limits, generates trip if limit exceeded.  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3004 Rev. 3  
1370-ICE-3004 Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by System Engineering Laboratories, 524280-019

Wyle Laboratories, 42915-1

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.4g input F/B = 1.4g input V = 1.3g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 7

Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS equals or exceeds RRS above 8Hz and at natural frequencies except at 25 and 40Hz.

6. Input g-level Test at:

S/S = 2.8

F/B = 2.6

V = 1.5

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 8, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element

☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

NATURAL FREQUENCIES	VERTICAL	30, 32 Hz	SIDE SIDE	None below 40 Hz	FRONT BACK	30 Hz
ELECTRICAL OPERATION	All features operated properly; no errors recorded					
PHYSICAL INTEGRITY	Intact; no physical effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (PLANCE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

#### VI. DISCUSSION

This equipment was subjected to seven (7) series of full-level sine-beat tests. The duration of each series (in each of two biaxial test directions) was 30 seconds. The frequency of each of the seven series was different. Based on the equipment natural frequencies, which were all determined to be above 25 Hz by the resonance survey, the test series involving the highest frequency sine-beats is sufficient for qualification. This test excited all equipment modes to ample acceleration levels, as indicated by the test response spectra on the reverse side of this sheet. The excitation frequencies of this test were 16 Hz in the horizontal direction and 8 Hz in the vertical direction.



### TEST RESPONSE SPECTRA

DATA SHEET No. 29

DATE November, 1976

REVISION No. 00

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

- TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)



☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)



TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL

☒ VERTICAL

☐ VERTICAL (180° SHIFT)



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
 HEUTTEL & ESSLER CO. MADE IN U.S.A.




FIGURE 13 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
KEITHLEY & ESSEN CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 ☒ %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFEL & ESSER CO. MADE IN U.S.A.




FIGURE 15

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: CP MACS Chasis

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Systems Engineering Laboratories  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Rack Mounted Chasis  
b. Dimensions 28" x 19" x 9-1/4"  
c. Weight 70#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 10-32)  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 29,37 F/B: 30,33  
V: 26,30,34,38  
9. a. Functional Description: Computer interface (I/O)  
for all computer communication  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-3004 Rev. 03  
1370-ICE-3004 Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Systems Engineering Laboratories, N-524280-019  
Wyle Laboratories, 42915-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
 (Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.4 g input F/B = 1.4 g input V = 1.3 g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 7  
 Other \_\_\_\_\_  
 (Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No

TRS equals or exceeds RRS at natural frequencies above 8Hz except at  
25 and 40 Hz.

6. Input g-level Test at:

S/S = 2.8

F/B = 2.6

V = 1.5

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 8, Size 10-32) ☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: N/A

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Dynamic Analysis

☐ Equivalent Static Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element ☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES VERTICAL	26, 30, 34, 38 Hz	SIDE / SIDE	29, 37 Hz	FRONT / BACK	30, 33 Hz
ELECTRICAL OPERATION	Proper operations verified; no failures				
PHYSICAL INTEGRITY	Intact; no physical effects				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

This equipment was subjected to seven (7) series of full-level sine-beat tests. The duration of each series (in each of two biaxial test directions) was 30 seconds. The frequency of each of the seven series was different. Based on the equipment natural frequencies, which were all determined to be above 25 Hz by the resonance survey, the test series involving the highest frequency sine-beats is sufficient for qualification. This test excited all equipment modes to ample acceleration levels, as indicated by the test response spectra on the reverse side of this sheet. The excitation frequencies of this test were 16 Hz in the horizontal direction and 8 Hz in the vertical direction.

# TEST RESPONSE SPECTRA

DATA SHEET No. 2f

DATE November, 1976

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 00

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)



# TEST RESPONSE SPECTRA

DATA SHEET No. 29

DATE November, 1976

REVISION No. 00

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K.E. LOGARITHMIC 3 X 3 CYCLES  
 KEUFEL & ESSER CO. MADE IN U.S.A.




FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 ☒ %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
NEUPHILL & ESSER CO. MADE IN USA




FIGURE 15

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
NEUPFEL & ESSEN CO. MADE IN U.S.A.




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: CPC Power Supply

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: None Quantity: 4  
3. Vendor: Systems Engineering Laboratories  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Rock mounted chassis  
b. Dimensions 28" x 19" x 5 1/4"  
c. Weight 60#  
6. Location: Building: Control Area Aux. Bldg  
Elevation: 30'  
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 10-32)  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 25, 33, 39 F/B: 40  
V: 26, 35, 39  
9. a. Functional Description: Provides power supply and voltage reference for CPC  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both \_\_\_\_\_  
10. Pertinent Reference Design Specifications: 00000-ICE-3004 Rev 3  
1370-ICE-3004 Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Systems Engineering Laboratories, No. 524280-019  
Wyle Laboratories, 42915-1  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only  
 3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
 5. ☐ Combination of \_\_\_\_\_  
 6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 1.4g input F/B = 1.4g input V = 1.3g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)
3. No. of Qualification Tests: OBE 0 SSE 7  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS envelops RRS at natural frequencies.

6. Input g-level Test at:

S/S = 2.8

F/B = 2.6

V = 1.5

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 8, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D

☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

V1 Test Results

NATURAL FREQUENCIES	VERTICAL	26, 35, 39 Hz	SIDE / SIDE	25, 33, 39 Hz	FRONT / BACK	None below 40 Hz
ELECTRICAL OPERATION	Performance as required - output voltage remained constant					
PHYSICAL INTEGRITY	intact - no physical effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

## VI DISCUSSION

This equipment was subjected to seven (7) series of full-level sine-beat tests. The duration of each series (in each of two biaxial test directions) was 30 seconds. The frequency of each of the seven series was different. Based on the equipment natural frequencies, which were all determined to be above 25 Hz by the resonance survey, the test series involving the highest frequency sine-beats is sufficient for qualification. This test excited all equipment modes to ample acceleration levels, as indicated by the test response spectra on the reverse side of this sheet. The excitation frequencies of this test were 16 Hz in the horizontal direction and 8 Hz in the vertical direction.



FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
KEIMPEL & ESSER CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)



# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %




FIGURE 15

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSF: CE 3. A/E: Bechtel BWR

II. Component Name: CEA Position Isolation Assembly (CPIA)

1. Scope: ☒ NSSF ☐ BOP
2. Model Number: None Quantity: 2
3. Vendor: Electro-Mechanics Inc.
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Rack mounted chassis  
 b. Dimensions 17" x 17.5" x 12.219"  
 c. Weight ≈70#
6. Location: Building: Control Area, Auxiliary Building  
 Elevation: 30'
7. Field Mounting Conditions:  
☒ Bolt (No. Back 2, 8, Size 10-32 1/4-20) Front  
☐ Weld (Length ) ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: >40 F/B: >40 V: >40
9. a. Functional Description: Transfer and isolate analog signals between protective channels.  
 b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: 00000-ICE-3009 Rev. 2  
1370-ICE-3009 Rev. 0

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, #43349-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 1.4g input F/B = 1.4g input V = 1.3g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)
3. No. of Qualification Tests: OBE 10 SSE 1  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS exceeds RRS above 2.5 hz.

6. Input g-level Test at: S/S = 13.5 F/B = 12.5 V = 13.0
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. Front 8, Back 2, Size 1/4-20 10-32)
- ☐ Weld (Length \_\_\_\_\_) ☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):
- NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis
- ☐ Dynamic Analysis ☐ Time-History
- ☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D
- ☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS
- ☐ Other: \_\_\_\_\_
- (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES	VERTICAL	No Resonance below 40 Hz	SIDE - SIDE	No Resonance below 40 Hz	FRONT - BACK	No Resonance below 40 Hz
ELECTRICAL OPERATION	Equipment operated successfully					
PHYSICAL INTEGRITY						
After the accumulative effects of several tests the lower separation plate and relay bracket loosened. The items were re-fastened and the test was then continued.						
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

## VI. DISCUSSION

During testing in the side to side and vertical axes an electrical anomaly occurred. The anomaly consisted of a 20 mv, 3 msec voltage spike located on the low output side of the three differential amplifiers being monitored. The test was then re-run three times and the anomaly did not reoccur. During further testing the seismic test table hit its mechanical stops causing the CPIA to experience a peak g level of approximately 110 g's and a ZPA of 32 g's. Once the stops were hit the same three amplifiers mentioned above were found to have intermittent voltage spikes of approximately 100 mv in amplitude on their low output side. The electrical anomaly continued to appear intermittently throughout the front to back and vertical axes. At this point the test was stopped to determine the cause of the electrical anomaly. The problem was found to be in the -15V power supply. An external +15V power supply was used to provide voltage through the same connections used by the internal +15V power supply and the entire front-to-back and vertical axis seismic test was rerun without any problems.

A new +15V power supply of the same type was later tested to the same RRS without any problems. The failure of this power supply was attributed to the hitting of the mechanical stops and accumulative effect of the large number of seismic tests required by the test procedure.

2c.



# TEST RESPONSE SPECTRA

DATA SHEET No. 21  
DATE MARCH 1977



SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

1 % CRITICAL DAMPING REVISION No. 01

<input type="checkbox"/> FRONT TO BACK	}	TEST PLANE	<input type="checkbox"/> SIDE TO SIDE
<input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL			<input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL
<input checked="" type="checkbox"/> FRONT TO BACK	}	RESPONSE DIRECTION	<input checked="" type="checkbox"/> SIDE TO SIDE (°)
<input checked="" type="checkbox"/> FRONT TO BACK (180° SHIFT)			<input checked="" type="checkbox"/> SIDE TO SIDE (180° SHIFT) (x)



<input type="checkbox"/> VERTICAL	}	TEST PLANE	<input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL
<input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL			
<input checked="" type="checkbox"/> VERTICAL	}	RESPONSE DIRECTION	<input checked="" type="checkbox"/> VERTICAL (°)
<input checked="" type="checkbox"/> VERTICAL (180° SHIFT)			<input checked="" type="checkbox"/> VERTICAL (180° SHIFT) (x)





FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K-E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

LOGARITHMIC 3 X 3 CYCLES  
NEUPH & ESSER CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
NEWELL & LUDWIG CO. MADE IN U.S.A.




FIGURE 15 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
NEUFEL & ESSEN CO. MADE IN U.S.A




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: RCP SSSS Signal Processor

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: None Quantity: 4
3. Vendor: Bently - Nevada
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Rock mounted chassis
- b. Dimensions 17.2" x 12.0" x 8.79"
- c. Weight 30#
6. Location: Building: Control Area Aux. Bldg
- Elevation: 30'
7. Field Mounting Conditions ☒ Bolt (No. 8, Size 10-32)
- ☐ Weld (Length )
- ☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: 35 F/B: 35
- V: 35
9. a. Functional Description: Process shaped pulses which are proportional to RCP speed
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown
- ☐ Both
10. Pertinent Reference Design Specifications: 00000-ICE-6003 Rev. 2  
1370-ICE-6003 Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report 54602  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.4g input F/B = 1.4g input V = 1.3g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE 0 SSE 6  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS envelops RRS at natural frequencies.

6. Input g-level Test at:

S/S = 2.5

F/B = 3.2

V = 2.2

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. Front 4, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes, ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Dynamic Analysis

☐ Equivalent Static Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D

☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



# VI Test Results

NATURAL FREQUENCIES VERTICAL	See Discussion Below	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION			
PHYSICAL INTEGRITY			
Intact; no physical effects.			
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

- (a) Mounting: Signal Processor - (4) 10-32 bolt on front and (2) 1/4-20 bolt on back  
Pulse Transmitter - (4) 10-24 bolts
- (b) Natural Frequencies: Signal Processor - No Resonance below 35 Hz.  
Transmitter - Resonance found at 30 Hz in the front-to-back and side-to-side directions.  
No resonance was found below 35 Hz in vertical.
- (c) Full Level Tests: The TRS indicated on the reverse side of this data sheet resulted from the 16 Hz tests. The other TRSs are similar except the frequency is shifted accordingly.



# TEST RESPONSE SPECTRA

DATA SHEET No. 23  
DATE MARCH 1977



SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

1 % CRITICAL DAMPING REVISION No. 01

<input type="checkbox"/> FRONT TO BACK	}	TEST PLANE	<input type="checkbox"/> SIDE TO SIDE
<input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL			<input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL
<input checked="" type="checkbox"/> FRONT TO BACK	}	RESPONSE DIRECTION	<input checked="" type="checkbox"/> SIDE TO SIDE
<input checked="" type="checkbox"/> FRONT TO BACK (180° SHIFT)			<input checked="" type="checkbox"/> SIDE TO SIDE (180° SHIFT)



<input type="checkbox"/> VERTICAL	}	TEST PLANE	<input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL
<input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL			
(→) <input checked="" type="checkbox"/> VERTICAL	}	RESPONSE DIRECTION	(→) <input checked="" type="checkbox"/> VERTICAL
(*) <input checked="" type="checkbox"/> VERTICAL (180° SHIFT)			(*) <input checked="" type="checkbox"/> VERTICAL (180° SHIFT)



## FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐DAMPING ☐ 1 %

46 7403


K&E LOGARITHMIC 3 X 3 CYCLES  
NEUFFEL & ESSER CO. MADE IN U.S.A.

FIGURE 13

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTI-FREQUENCY TEST (RUN # 19)

FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




FIGURE 14 PREDICTED COMPOSITE RESPONSE SPECTRUM FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING SS/V RANDOM MULTIFREQUENCY TEST (RUN #19)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUVEL & ESSER CO. MADE IN USA




FIGURE 15

PREDICTED COMPOSITE RESPONSE SPECTRUM FOR HORIZONTALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE HORIZONTAL CONTROL ACCELEROMETER HAD EQUALED THE HORIZONTAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTI-FREQUENCY TEST (RUN # 32)

# FULL SCALE SHOCK SPECTRUM (g Peak)

1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

DAMPING ☐ 1 %

46 7403

K&E LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSEN CO. MADE IN U.S.A.




FIGURE 16 PREDICTED COMPOSITE RESPONSE SPECTRA FOR VERTICALLY ORIENTED SPECIMEN ACCELEROMETERS IF THE TEST RESPONSE SPECTRA OF THE VERTICAL CONTROL ACCELEROMETERS HAD EQUALED THE VERTICAL REQUIRED RESPONSE SPECTRA DURING FB/V RANDOM MULTIFREQUENCY TEST (RUN #32)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_II. Component Name: In-Core Amplifier1. Scope: ☒ NSSS ☐ BOP2. Model Number: RY-010 Quantity: 43. Vendor: Electro-Mechanics, Inc.4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Panel mounted rackb. Dimensions 17" x 19" x 24"c. Weight 77#6. Location: Building: Control Area Aux Bldg  
Elevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 2, 8, Size 10-32, 1/4-20)  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \_\_\_\_\_ F/B: \_\_\_\_\_

V: \_\_\_\_\_

9. a. Functional Description: No safety related functionb. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown☐ Both Neither10. Pertinent Reference Design Specifications: 1370-1CE 5012 Rev 0

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Not yet tested  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): \_\_\_\_\_

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = \_\_\_\_\_ F/B = \_\_\_\_\_ V = \_\_\_\_\_

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: Not yet tested

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No



6. Input g-level Test at:

S/S = \_\_\_\_\_  
 F/B = \_\_\_\_\_  
 V = \_\_\_\_\_

7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: \_\_\_\_\_

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Reactor Trip Switchgear Cabinet1. Scope: ☒ NSSS ☐ BOP2. Model Number: None Quantity: 13. Vendor: Unit Electric Control4. If the component is a cabinet or panel, name and model No. of the devices included: See attached sheet5. Physical Description a. Appearance Vertical cabinetb. Dimensions 118" x 60" x 96" (L x W x H)c. Weight 8400#6. Location: Building: Radwaste Area (Auxiliary Bldg.)Elevation: 37'-0"7. Field Mounting Conditions ☒ Bolt (No. 20, Size 1/2")  
8307 Bolt☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 14.5 F/B: 14.5V: 12, 15, 20, 309. a. Functional Description: Interrupts power to CEDM latching mechanismsb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☐ Both 10. Pertinent Reference Design Specifications: 00000-ICE-3008  
Revision 00, 1370-ICE-3008, Revision 02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories Report #42835-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
[ ] \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
[ ] sine beat  
[ ] \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE 5 SSE 2  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS envelops RRS at natural frequencies/

6. Input g-level Test at:

S/S = 1.1

F/B = 1.3

V = 0.9

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 20, Size 1/2") ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: N/A

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element

☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## II. 4 Devices Included

Circuit Breakers

GE AR-25

Push Buttons

PTP43FF

## VI. 9 Test Results

NATURAL FREQUENCIES	VERTICAL	12, 15, 20, 30 Hz	SIDE / SIDE	14.5 Hz	FRONT BACK	14.5 Hz
ELECTRICAL OPERATION	The closing circuit of one breaker failed; one wire broke at its termination point; equipment performed as required - all breakers opened as required.					
PHYSICAL INTEGRITY	Intact; no physical effects except as noted above.					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS	Not available					
MAXIMUM EXTERIOR DEFLECTION	Less than 1/8 inch					
DYNAMIC LOAD TO MOUNTING	44,000 lbs. distributed among the 20 mounting bolts.					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES	Not determined					

### VI. DISCUSSION

The closing circuit of the breakers is not required to operate during a seismic event. The failure of the closing circuit is not related to the tripping function and has no effect on the trip circuit operation. The circuit breakers were successfully tripped as required.

The operation of the safety-related circuits of this equipment was successfully completed during seismic qualification testing. At the completion of this testing and prior to delivering this equipment to the nuclear station, a full functional test was performed as assurance the equipment was prepared for delivery. The full functional test evaluates all equipment features, including those not related to safety. During this test, discontinuity was found in an auxiliary circuit which feeds the plant computer. The discontinuity was traced to a wire broken at its termination, which is a crimped lug. The break occurred within the lug at the crimp, and it is believed the wire was weakened by overcrimping.

### Section IV Continued

simulate reactor trip signals and undervoltage conditions in the circuit breaker control circuits. The simulated reactor trip signals actuated the shunt trip coils and the undervoltage conditions actuated the undervoltage trip devices in the nine reactor trip circuit breakers.



# TEST RESPONSE SPECTRA

DATA SHEET No. 3  
DATE MARCH 1977



SPECTRUM FULL SCALE. ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

1 % CRITICAL DAMPING REVISION No. 01

- |  |                                  |  |
|--|----------------------------------|--|
| <input type="checkbox"/> FRONT TO BACK<br><input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL<br><input checked="" type="checkbox"/> FRONT TO BACK<br><input type="checkbox"/> FRONT TO BACK (180° SHIFT) | TEST PLANE<br>RESPONSE DIRECTION | <input type="checkbox"/> SIDE TO SIDE<br><input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL<br><input checked="" type="checkbox"/> SIDE TO SIDE<br><input type="checkbox"/> SIDE TO SIDE (180° SHIFT) |
|--|----------------------------------|--|



- |   |                                  |   |
|---|----------------------------------|---|
| <input type="checkbox"/> VERTICAL<br><input checked="" type="checkbox"/> FRONT TO BACK / VERTICAL<br><input checked="" type="checkbox"/> VERTICAL<br><input type="checkbox"/> VERTICAL (180° SHIFT) | TEST PLANE<br>RESPONSE DIRECTION | <input checked="" type="checkbox"/> SIDE TO SIDE / VERTICAL<br><input checked="" type="checkbox"/> VERTICAL<br><input type="checkbox"/> VERTICAL (180° SHIFT) |
|---|----------------------------------|---|






Reactor Trip Switchgear  
Required Response Spectrum  
SSE - Horizontal - 1% $\beta$

46 7400

KE LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




TRS: minimum of two horizontal tests (F/B & S/S)

Reactor Trip Switchgear  
Required Response Spectrum  
SSE - Vertical - 17.8

46 7400

LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



TSD minimum of two vertical tests

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSF: CE 3. A/E: Bechtel BWR

II. Component Name: ESFAS Auxiliary Relay Cabinet

1. Scope: ☒ NSSF ☐ BOP
2. Model Number: None Quantity: 1
3. Vendor: ACCO
4. If the component is a cabinet or panel, name and model No. of the devices included: See attached sheet
5. Physical Description a. Appearance 4 Bay Vertical Cabinet  
b. Dimensions 144" x 56" x 90" (L x W x H)  
c. Weight 13000#
6. Location: Building: Control Room Auxiliary Building  
Elevation: 30'-0"
7. Field Mounting Conditions ☒ Bolt (No. 12, Size 7/8)  
8307 Bolt  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 12 F/B: 9.5, 10.5, 13, 18, 27, 34, 39  
V: 18, 25, 27, 34, 39
9. a. Functional Description: Engineered Safety Features Relay Actuation  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: 1370-ICE-3002 Rev. 0  
00000-ICE-3002, Revision 04

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report 42913-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
[ ] \_\_\_\_\_  
(Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 1.0g input F/B = 1.0g input V = 0.75

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
[ ] sine beat  
[ ] \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)
3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_  
(Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS envelops RRS at natural frequencies.

## 6. Input g-level Test at:

S/S = 1.3

F/B = 1.5

V = 1.0

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 12, Size 7/8") ☐ Weld (Length )  
[ ]8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:

1. Description of Test including Results: N/A

2. Method of Analysis:

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other:

(specify)

6. Damping: Basis for the damping used:

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## I. Devices Included

NSSS 4

Current breakers  
Circuit breakers  
Connectors  
Diodes  
Diodes  
Ground detectors  
Power supply  
Power supply  
Push buttons  
Push buttons  
Relays  
Relays  
Relays  
Relays, motion  
Relays, motion

CD1-B3-DU-25-28VDC-1  
CD2-B3-DU-15-120-1  
M33102R36  
1N4004  
1N649  
Mod PR-2000  
FPS-28-26  
GD-8.0-1.5 F/6.0  
PTP42F, PTP436  
PRP32R8WK  
KHS11012-6  
20P36AF  
KHS17012-6  
MOR-7033, MOR-7034  
MOR-7032, MOR136-1

## II. Test Results

NATURAL FREQUENCIES	VERTICAL 18, 25, 27, 34, 39 Hz	SIDE SIDE 12 Hz	FRONT BACK 9, 5, 10, 5, 13, 18, 27, 34, 39 Hz
ELECTRICAL OPERATION	All components deenergized and reenergized as required. No spurious, intermittent operation or contact chatter was observed.		
PHYSICAL INTEGRITY	Intact; no physical effects.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS	Less than 2300 psi		
MAXIMUM EXTERIOR DEFLECTION	Less than 1/4 inch.		
DYNAMIC LOAD TO MOUNTING	Not calculated		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES	Not determined		

### VI. DISCUSSION

#### Equipment Operation

The ESFAS Auxiliary Relay was powered with 120 VAC, 60 HZ, single-phase power during the seismic test. All safety actuation circuits in the ESFAS Auxiliary Relay cabinet were energized during the seismic test.

Twenty-five (25) channels of electrical monitoring were recorded on an oscillograph recorder during the Seismic Test Program. These channels were used to ascertain electrical continuity, spurious operation, contact chatter, before, during and after the seismic excitation. The components that were monitored were selected at random. The monitored components were comprised of various relays, switches, and manual trip pushbuttons located in different sections of the ESFAS Cabinet. Along with the 25 electrical channels, a test bench for the ESFAS Auxiliary Relay Cabinet was wired to one contact on each subgroup relay. The test bench had a light wired to show whether each subgroup relay was either energized or de-energized. A preliminary operational test was run prior to the seismic testing. The actuation circuits were deenergized 10 seconds into the seismic test. The MSIS EFAS I and EFAS II circuits were reenergized as soon as all components were verified tripped. After about 20 seconds into the seismic test the MSIS, EFAS I and EFAS II were again de-energized. At the completion of all seismic testing the complete ESFAS cabinet was operationally tested to insure that all safety circuits operated.

# TEST RESPONSE SPECTRA

DATA SHEET No. 4

DATE MARCH 1977

SPECTRUM FULL SCALE.

ACCELERATION ☐ 10 gs ☒ 100 gs

FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

RESPONSE DIRECTION






# SCE Control Room Response Spectra

San Onofre station

SSE - vertical - 1% B




ARC: minimum of two vertical tests.

# SCE Control Room Response Spectra

San Onofre Station

SSE - Horizontal - 1% A



ARC: minimum of two horizontal tests (F/B 9 S/S)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. N555: CE 3. A/E: Bechtel BWR

II. Component Name: Process Instrument Rack

1. Scope: ☒ N555 ☐ BOP
2. Model Number: 2ES-N Quantity: 28
3. Vendor: Foxboro
4. If the component is a cabinet or panel, name and model No. of the devices included: See attached sheet
5. Physical Description a. Appearance Single bay vertical cabinet  
 b. Dimensions 88.75" x 24" x 28  
 c. Weight 575#
6. Location: Building: Control Area, Aux. Bldg.  
 Elevation: 30'
7. Field Mounting Conditions ☒ Bolt (No. 6, Size 1/2 for double cabinet)  
☐ Weld (Length )  
☐
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: 10 F/B: 18  
 V: >35
9. a. Functional Description: Provide support for process electronics modules  
 b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 001, Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report T4-1025, Rev. 1

Lab: Action Laboratory Report No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer freq. from  
1 to 35 Hz for 3 axis.  
(Specify)

4. Frequency Range: 1 to 35 Hz.

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

Not acceptable

6. Input g-level Test at:  
 S/S = 1  
 F/B = 1  
 V = 1
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 6, Size 0.50 dia.) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☒ Not Applicable
9. Test Results including modifications made: See attached sheets
10. Other tests performed (such as fragility test, including results):  
N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: N/A
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## II 4. Devices Included\*

Controller	2AC-D+A5+RM
Current to Voltage Converter	2AI-I2V
Resistance to Voltage Converter	2AI-P2V
Alarm	2AP-ALM-AS
Square Root Extractor	2AP-SQE
Summer	2AP- <del>+</del> SUM
Contact Isolator	2AO-L2C-R
Voltage to Current Converter	2AO-V2I
Power Supply	2ARPS
Power Distribution Module	2AX-DPIO-EH
Signal Distribution Module	2AX-DSI
Temperature Transmitter	442H-RP-A

\* Tested Separately

# VI Test Results


NATURAL FREQUENCIES: VERTICAL	none below 35 Hz	SIDE / SIDE	10Hz	FRONT / BACK	18Hz
ELECTRICAL OPERATION	NA				
PHYSICAL INTEGRITY	Intact; no loosening, damage or deformation.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES using sine-beat input motion maximum amplification as follows: At top of rack - 6.0 (F/B) and 6.1 (S/S); at center of rack - 4.0 (F/B) and 4.5 (S/S). No amplification in vertical direction.					

## VI. DISCUSSION

The specimen was loaded with non-operating functional electronic modules to duplicate the in-service conditions. The specimen response (input to functional modules) was monitored and is noted above in Results. The seismic qualification of the functional modules is documented on data sheets 6a, 6b, 6c, etc. in CGN-94(S); JULY, 1978.




SCE Control Room Response Spectra  
San Onofre Station  
SSE - Horizontal - 1% A



# SCE Control Room Response Spectra

San Onofre station

SSE - vertical - 1% B



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Controller, Removable Manual1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AC-D+A5+RM\* Quantity: 23. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≅1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*

\*Resonance Search Not Completed

9. a. Functional Description: Produces output signal as function of difference between inputs.b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☐ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 346 Rev 5

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Acton Laboratory Rpt. No. 1197

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other 10 cycles/beat, 10 beats full level dwell at each integer freq.  
from 1 to 35 Hz  
 (Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

Not Acceptable

6. Input g-level Test at:  
S/S = 3.5, 5, 10  
F/B = 3.5, 5, 10  
V = 3.5, 5, 10
7. Laboratory Mounting: Normal Spec. 200 equipment mounting
1. ☐ Bolt (No.           , Size           ) ☐ Weld (Length           )  
☒ Nest Assembly
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: \_\_\_\_\_ NA
2. Method of Analysis: \_\_\_\_\_
- [ ] Static Analysis [ ] Equivalent Static Analysis  
[ ] Dynamic Analysis [ ] Time-History  
[ ] Response Spectrum
3. Model Type: [ ] 3D [ ] 2D [ ] 1D  
[ ] Finite Element [ ] Beam [ ] Closed Form Solution
4. [ ] Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
[ ] Hand Calculations
5. Method of Combining Dynamic Responses: [ ] Absolute Sum [ ] SRSS  
[ ] Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION performed properly at 10.0 g's with less than 0.5% output shift		
PHYSICAL INTEGRITY Intact, No physical damage.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_II. Component Name: Current to Voltage Converter1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AI-I2V Quantity: 163. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rock Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≈1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_)  
☐ Weld (Length \_\_\_\_\_)  
☒ Nest Slot \_\_\_\_\_

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*

\*Resonance Search Not Concluded

9. a. Functional Description: Convert input current to output voltageb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown☒ Both \_\_\_\_\_10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheets 160 Rev. 1, 355 Rev. 2, 415 Rev. 1



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Aston Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 Hz  
 (Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

Not Acceptable

6. Input g-level Test at:  
 S/S = 3.5, 5, 10  
 F/B = 3.5, 5, 10  
 V = 3.5, 5, 10
7. Laboratory Mounting: Normal Spec. Equipment Mounting
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☒ Nest Assembly
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Performance as required; output deviation less than 0.5% of full range.	
PHYSICAL INTEGRITY	Intact; no physical damage.	
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. N555: CE 3. A/E: Bechtel BWR II. Component Name: Resistance to Voltage Converter1. Scope: ☒ N555 ☐ BOP2. Model Number: 2AI-P2V Quantity: 33. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rock Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≈1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*\*Resonance Search Not Concluded9. a. Functional Description: Provides output voltage proportional to input resistanceb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 356, Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Aston Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat

☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

6. Input g-level Test at:  
 S/S = 3.5, 5, 10  
 F/B = 3.5, 5, 10  
 V = 3.5, 5, 10
7. Laboratory Mounting: Normal Spec. 200 Equipment Mounting
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☒ Nest Assembly
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



# VI Test Results

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Performance as required: 0.00% deviation less than 0.5% of full range.	
PHYSICAL INTEGRITY	Intact, no physical damage.	
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. N555: CE 3. A/E: Bechtel BWR II. Component Name: Absolute Alarm1. Scope: ☒ N555 ☐ BOP2. Model Number: 2AP-ALM-AS Quantity: 83. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≅1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*\*Resonance Search Not Concluded9. a. Functional Description: Provide dual alarms with input, output and setpointb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005, Sheet 177  
Revision 2, 355 Revision 2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, PERS 75-113

Lab: Aston Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

6. Input g-level Test at:  
S/S = 3.5, 5, 10  
F/B = 3.5, 5, 10  
V = 3.5, 5, 10
7. Laboratory Mounting: Normal Spec. 200 Equipment
1. ☐ Bolt (No.           , Size           ) ☐ Weld (Length           )  
☒ Nest Assembly
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):
- NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

- [illegible]

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES	VERTICAL	SIDE / SIDE	FRONT BACK
ELECTRICAL OPERATION	Performance as required when testing at 10 g peak input amplitude. See discussion for anomalies at lower test amplitudes.		
PHYSICAL INTEGRITY	Intact, no physical effects.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

The specimen was tested at each integer frequency from 1 to 35 Hz at 3.5g, 5.0 g, and 10.0 g. During the 3.5 g test one of four alarms fired without cause (two specimens were tested). This anomaly did not occur when testing at 5g and 10g, and therefore is not considered cause for disqualification.

When testing at 5.0g, an operational amplifier failed. An investigation found a loose particle of conducting material resting on the chip within the amplifier case. The material was removed and testing was resumed successfully.

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Square Root Extractor1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AP-SQE Quantity: 83. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≈1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*\*Resonance Search Not Concluded9. a. Functional Description: Provide output proportional to square root of inputb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 358 Rev. 0, Sheet 366 Rev. 01, Sheet 364 Rev. 02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐

(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 HZ

(Specify) \_\_\_\_\_

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A



6. Input g-level Test at:  
 S/S = 3.5, 5, 10  
 F/B = 3.5, 5, 10  
 V = 3.5, 5, 10
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☒ Nest Assembly
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES, VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Performance as required; output deviation less than 0.5% of full scale</u>		
PHYSICAL INTEGRITY <u>Intact, no physical damage.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Electronic Summer1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AP & SUM Quantity: 23. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≅1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*9. a. Functional Description: Provides output proportional to sum of input signalsb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 340 Rev 01

\*Resonance Search Not Conducted.

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report TS-6089

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beats, 10 beat full level at each integer. freq. from  
1 to 35 Hz

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES: VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Output signals deviated less than 0.1% during and after testing</u>		
PHYSICAL INTEGRITY <u>Intact, no Physical damage.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

## VI. DISCUSSION



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: Contact Output Isolation

1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2A0-L2C-R Quantity: 63. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 3/4" x 8 3/4" x 13 1/2"c. Weight ≅1#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_)  
☐ Weld (Length \_\_\_\_\_)  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*

\*Resonance Search Not Concluded.

9. a. Functional Description: Interface between low level and high power loadb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both \_\_\_\_\_10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 171, Rev. 02, 350 Rev. 02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report 75-113

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐

(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 Hz

(Specify) \_\_\_\_\_

4. Frequency Range: 1 to 35 Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

- 

1. Description of Test including Results: \_\_\_\_\_ NA
2. Method of Analysis: \_\_\_\_\_  
[ ] Static Analysis [ ] Equivalent Static Analysis  
[ ] Dynamic Analysis [ ] Time-History  
[ ] Response Spectrum
3. Model Type: [ ] 3D [ ] 2D [ ] 1D  
[ ] Finite Element [ ] Beam [ ] Closed Form Solution
4. [ ] Computer Codes: \_\_\_\_\_  
Frequency Range and No. of modes considered: \_\_\_\_\_  
[ ] Hand Calculations
5. Method of Combining Dynamic Responses: [ ] Absolute Sum [ ] SRSS  
[ ] Other: \_\_\_\_\_  
(specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES: VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>The contact outputs operated properly except for the failure noted in the discussion</u>		
PHYSICAL INTEGRITY <u>Intact, no physical damage</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

## VI. DISCUSSION

Output A of the 2 AO-L2C-R No. 2 failed at 20 Hz in the side to side plane @ 10 g's. The fault was traced to two broken wires on the relay socket of K1. The broken wires occurred as a result of excessive displacement of wire bundle during testing. To correct this, a design modification has been incorporated which restrains the wire bundle in seven places, thus precluding wire damage due to bundle displacement.

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Voltage to Current Converter

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: 2A0-V2I Quantity: 2
3. Vendor: Foxboro
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Nested Module for Vertical Rack Mounting
- b. Dimensions 1 3/4" x 8 3/4" x 13 1/2"
- c. Weight ≈1#
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: \* F/B: \*  
V: \*  
\*Resonance Search Not Concluded
9. a. Functional Description: Converts 0-10 VDC Input to 4-20 MA Output
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 357 Rev. 03

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other 10 cycles/beat, 10 beats full level at each integer. freq. from  
1 to 35 HZ  
 (Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A





## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES, VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Performance as required; output deviation less than 0.5% of full range</u>		
PHYSICAL INTEGRITY <u>Intact, no physical damage.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Power Supply

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: 2ARPS Quantity: 6  
3. Vendor: Foxboro  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Module for Rack Mounting  
b. Dimensions 19" x 8-3/4" x 13-1/4"  
c. Weight 82#  
6. Location: Building: Control Area Aux. Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 29 F/B: >35  
V: 14, 17, 20, 25, 30  
9. a. Functional Description: Provide power supply to process instruments ( 15, + 25VDC)  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 162 Rev. 02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report T6-6020

Lab: Action Laboratory Report No. 12539

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 4.5g input F/B = 4.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer freq. from  
1 to 35 Hz.

(Specify)

4. Frequency Range: 1-35 Hz.

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

## 6. Response g-level Test at:

S/S = 1 to 5F/B = 1 to 5V = 1 to 57. Laboratory Mounting: Normal Spec. 200 Equipment Mounting1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

## 10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:1. Description of Test including Results: N/A

## 2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

## 6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

## 7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES: VERTICAL	14, 17, 20, 25-30 Hz	SIDE / SIDE	29 Hz	FRONT / BACK	none below 35 Hz
ELECTRICAL OPERATION	Performance as required; output deviations less than 0.1% full range except as noted in discussion.				
PHYSICAL INTEGRITY	Intact; no physical anomalies.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

Testing at frequencies above 20 Hz caused a loss of -15 VDC. The problem was traced to an unsoldered connection in series with the -15 VDC overvoltage protection circuit. Each time the connection opened, overvoltage protection was initiated and the -15 VDC output was removed. The subject relay was removed and a retesting was conducted at all frequencies from 20 to 35 Hz without failure. The unsoldered connection has been addressed by the vendor as a manufacturing quality control problem and steps have been taken to prevent the reoccurrence of unsolder connections.

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Power Distribution Module1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AX-DP10-EH Quantity: 273. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Module for Rack Mountingb. Dimensions 1 1/2" x 8 3/4" x 3"c. Weight ≈3#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*\*Resonance Search Not Conducted9. a. Functional Description: Connect external power to rest of power busb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 167 Rev. 04



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer freq. from  
1 to 35 Hz

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

6. Input g-level Test at:

S/S = 3.5, 5, 10

F/B = 3.5, 5, 10

V = 3.5, 5, 10

7. Laboratory Mounting: Normal spec 200 equipment mounting

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis  
☐ Dynamic Analysis

☐ Equivalent Static Analysis  
☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# V1 Test Results

NATURAL FREQUENCIES, VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION <u>functional properly throughout all tests</u>		
PHYSICAL INTEGRITY <u>Intact, No physical damage.</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Signal Distribution Module1. Scope: ☒ NSSS ☐ BOP2. Model Number: 2AX-DSI Quantity: 203. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 1 1/2" x 8 3/4" x 3"c. Weight ≈3#6. Location: Building: Control Area Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Nest Slot

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*

\*Resonance Search Not Conducted

9. a. Functional Description: Provide terminals for termination of signal connectionsb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 161 Rev. 04

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report PERS 75-113

Lab: Acton Laboratory Rpt. No. 11977

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1 input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 10 cycles/beat, 10 beats full level at each integer freq. from  
1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A

## 6. Input g-level Test at:

S/S = 10

F/B = 10

V = 10

7. Laboratory Mounting: Normal spec 200 equipment mounting1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

## 10. Other tests performed (such as fragility test, including results):

NAVII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:1. Description of Test including Results: NA

## 2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

## 6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

## 7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



# II. Test Results

NATURAL FREQUENCIES: VERTICAL	NA	SIDE / SIDE	NA	FRONT / BACK	NA
ELECTRICAL OPERATION	Function properly throughout all tests				
PHYSICAL INTEGRITY	Intact, no physical damage				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X

2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Temperature Transmitter

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: 442H-RP-A Quantity: 16
3. Vendor: Rosemount
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Rack Mounted Module
- b. Dimensions 3 21/32" x 3 3/8" Diam.
- c. Weight 1#
6. Location: Building: Control Area Aux. Bldg.
- Elevation: 30'
7. Field Mounting Conditions ☐ Bolt (No. , Size )
- ☐ Weld (Length )
- ☒ Nest Slot
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >35 F/B: >35
- V: >35
9. a. Functional Description: Provide output current proportional to RTD input resistance
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown
- ☒ Both
10. Pertinent Reference Design Specifications: 1370-ICE-0005
- Sheet 164 Rev. 2, 165 Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Rosemount Report 77628E

Lab: Dayton T. Brown Laboratory DTB04R76-0902

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐

(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): No RRS for mounting location. Floor RRS is attached.

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 6.1g input F/B = 6.0g input V = 0.75g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random ☐ sine beat ☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE 3 SSE 2

Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs) ☒ No RRS

6. Input g-level Test at:
- S/S = 7.0
- F/B = 6.1
- V = 5.5
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 2, Size 8-32) ☐ Weld (Length \_\_\_\_\_)
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):
- NA
- VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:
1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_
- ☐ Static Analysis ☐ Equivalent Static Analysis
- ☐ Dynamic Analysis ☐ Time-History
- ☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D
- ☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_
- Frequency Range and No. of modes considered: \_\_\_\_\_
- ☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS
- ☐ Other: \_\_\_\_\_
- (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# II. Test Results

NATURAL FREQUENCIES: VERTICAL	None below 35 Hz	SIDE / SIDE	None below 35Hz	FRONT / BACK	None below 35Hz
ELECTRICAL OPERATION	Performance as required; no deviations during testing. The only change in calibration data was an improvement of the temperature effect (ambient, not sensed) by 0.15% of span.				
PHYSICAL INTEGRITY	Intact; no physical effects other than a slight bending of the mounting screws (about 5°).				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS _____					
MAXIMUM EXTERIOR DEFLECTION _____					
DYNAMIC LOAD TO MOUNTING _____					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____					

## VI. DISCUSSION

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLB LCH

Approved By:

WUB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-719

REV.

A


DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION



PERIOD (seconds)

7-24-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

OPERATING BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LCH

Approved By:

web

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-720

REV.  
A


ACCELERATION ( $g$ 's)

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%



PERIOD (seconds)

7-24-73



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison CompanyPWR X2. NSSS: CE3. A/E: BechtelBWR II. Component Name: Vital Bus Power Supply1. Scope: ☒ NSSS ☐ BOP2. Model Number: None Quantity: 43. Vendor: Cyberex4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Vertical two-bay cabinetb. Dimensions 85" x 36" x 50" (LxWxH)c. Weight 3300#6. Location: Building: Control Area (Aux. Bldg.)Elevation: 50' - 9"7. Field Mounting Conditions ☒ Bolt (No. 6, Size 7/8" 8.325 Bolt)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 12.5F/B: 20V: 209. a. Functional Description: Provide electrical power and voltage referenceb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-3017 Rev. 2  
00000-ICE-3017 Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Labs, Report 43474

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_

(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS exceeds the RRS at natural frequencies and <3 Hz and >9 Hz.

6. Input g-level Test at:

S/S = 3.9

F/B = 3.4

V = 1.0

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 6, Size 7/8 SAE 5) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Dynamic Analysis

☐ Equivalent Static Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element ☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

VI. 9. Test Results

NATURAL FREQUENCIES: VERTICAL	2	20 Hz	SIDE / SIDE	2	12.5 Hz	FRONT / BACK	2	20 Hz
ELECTRICAL OPERATION	The Vital Bus Power Supply maintained power and continuity to the output of the Distribution Panel circuits, except as noted below.							
PHYSICAL INTEGRITY	Intact. No physical effects except as noted below.							
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)								
MAXIMUM STRUCTURAL STRESS	9000 psi							
MAXIMUM EXTERIOR DEFLECTION								
DYNAMIC LOAD TO MOUNTING								
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES								

#### VI. DISCUSSION

A piece of debris caused an electrical short circuit and subsequent shutdown of the Vital Bus Power Supply inverter during one seismic run. The debris was a washer used in mounting the unit to a shipping skid which was inadvertently left in the inverter during test preparation. After removal of the washer testing was resumed with no other anomalies.

# TEST RESPONSE SPECTRA

DATA SHEET No. 77  
DATE March 18 1978

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 gs ☒ 100 gs  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz

1 % CRITICAL DAMPING



REVISION No. \_\_\_\_\_

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)


RESPONSE DIRECTION



Vital Bus Power Supply  
 Required Response Spectrum  
 SSE - Vertical - 1% $\beta$

46 7400

LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.




TR 5: minimum of two vertical tests

Vital Bus Power Supply  
 Required Response Spectrum  
 SSE - Horizontal - 1%/g

46 7400

KE LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.



TAS: minimum of two horizontal tests (F/B & S/C)



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSF: CE 3. A/E: Bechtel BWR II. Component Name: CPC Operator's Module1. Scope: ☒ NSSF ☐ BOP2. Model Number: None Quantity: 43. Vendor: Systems Engineering Laboratory4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Module inserted on control panelb. Dimensions 12" x 10" x 8"c. Weight 20#6. Location: Building: Control Area, Auxiliary Bldg.Elevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 12 , Size 3/8")  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 24, 34 F/B: 35V: 24, 32, 349. a. Functional Description: Permits operation of CPC system from main control panelb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☐ Both 10. Pertinent Reference Design Specifications: 1370-ICE-3004, Rev. 0  
00000-ICE-3004, Revision 3

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, 43130-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0g input F/B = 3.0g input V = 3.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other Full level at natural freqs. and 10, 15, 20, 25, 30, 35Hz  
(Specify)

4. Frequency Range: 1 to 35Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No  
Not Applicable

6. Input g-level Test at:

S/S = 3

$$F/B = \underline{\quad 3 \quad}$$
$$V = 3$$

## 7. Laboratory Mounting:

1. [X] Bolt (No. 8, Size10-32) [ ] Weld (Length \_\_\_\_\_)  
[ ] \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: N/A

## 2. Method of Analysis:

## [ ] Static Analysis

## [ ] Dynamic Analysis

## [ ] Equivalent Static Analysis

[ ] Time-History

[ ] Response Spectrum

3. Model Type: [ ] 3D

[ ] 2D

[ ] 1D

☐ Finite Element    ☐ Beam

[ ] Beam

[ ] Closed Form Solution

4. [ ] Computer Codes:

Frequency Range and No. of modes considered:

[ ] Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other:

(specify)

6. Damping: Basis for the damping used:

## 7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES VERTICAL	24, 32, 34 Hz	SIDE - SIDE	24, 34 Hz	FRONT - BACK	35 Hz
ELECTRICAL OPERATION	Performance as required, no spurious or interrupted signals; key switches operated normally before and after each seismic excitation.				
PHYSICAL INTEGRITY	Intact; no loosening or deformation of any part of specimen.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY):					
MAXIMUM STRUCTURAL STRESS	NA				
MAXIMUM EXTERIOR DEFLECTION	NA				
DYNAMIC LOAD TO MOUNTING	NA				
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES	NA				

## VI. DISCUSSION

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_II. Component Name: PPS Remote Control Module1. Scope: ☒ NSSS ☐ BOP2. Model Number: None Quantity: 43. Vendor: Electro-Mechanics4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Panel Mounted Drawerb. Dimensions 13-3/4" x 12" x 15-3/4"c. Weight 50#6. Location: Building: Control Area, Auxiliary Bldg.Elevation: 30'7. Field Mounting Conditions ☒ Bolt (No. 14, Size 3/8")  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
No resonance survey conducted.

S/S: \_\_\_\_\_ F/B: \_\_\_\_\_

V: \_\_\_\_\_

9. a. Functional Description: Remote bistable status display and bypass operationb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both \_\_\_\_\_10. Pertinent Reference Design Specifications: 1370-ICE-3001, Rev. 0  
00000-ICE-3001, Revision 03

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, 43386-1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS for mounting  
location. Floor RRS  
attached.

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0g input F/B = 3.0g input V = 3.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 6  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No RRS

## 6. Input g-level Test at:

S/S = 16.0

F/B = 16.5

V = 16.0

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 20/4, Size 3/8-16) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: N/A

2. Method of Analysis:

☐ Static Analysis☐ Dynamic Analysis☐ Equivalent Static Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element☐ Beam☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES: VERTICAL _____	SIDE / SIDE _____	FRONT / BACK _____
ELECTRICAL OPERATION <u>Performance as required; See discussion item 2 below</u>		
PHYSICAL INTEGRITY <u>Intact; no physical effects</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS _____		
MAXIMUM EXTERIOR DEFLECTION _____		
DYNAMIC LOAD TO MOUNTING _____		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES _____		

## VI. DISCUSSION

1. To qualify different mounting angles and operating modes of the module, a total of 26 full level tests were performed; 24 tests were required by combinations of three mounting angles, testing in four quadrants (consistent with phase-locked biaxial test requirements), and 2 modes of electrical operation. Although only one full level test was performed for each situation, the energy imparted to the module by 26 full level tests greatly exceeds that generated by 5-1/2 level and 1 full level SSE.

2. The remote control module provides various functions. These are operating bypasses, variable setpoint resets, calibration of safety channel nuclear instruments, and annunciation.

The operating bypasses are the High Log Power Bypass and RPS/ESFAS Pressurizer Pressure Bypass. The High Log Power Bypass was tested in both operating conditions (normal and bypass). The RPS/ESFAS Pressurizer Pressure Bypass is a spring return switch and therefore was tested in the "mid" position. Contacts of both switches were continuously monitored throughout the test.

With the Remote Control Module mounted in the 45° orientation a High Log Power Bypass Switch output contact anomaly was observed while the switch was in the bypass position. This anomaly was approximately one (1) millisecond in duration with the switch remaining in the bypass position. This one (1) millisecond duration is not sufficient to remove the bypass and propagate a channel trip and therefore is acceptable.

The variable setpoint reset pushbutton contacts were continuously monitored before, during, and after seismic excitation to verify no reset occurred.

A test voltage was applied across the safety channel nuclear instrumentation calibration potentiometer via a test resistor. The resultant voltage drop across the test resistor was continuously monitored and verified proper operation of the calibration potentiometer.

# TEST RESPONSE SPECTRA

DATA SHEET No. 102

DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☒ FRONT TO BACK (180° SHIFT)

TEST PLANE

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☒ SIDE TO SIDE (180° SHIFT)

RESPONSE DIRECTION





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☒ VERTICAL (180° SHIFT)

TEST PLANE

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☒ VERTICAL (180° SHIFT)

RESPONSE DIRECTION



EQUIP

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

8023-SK-S-696

REV.

A 7/24/72

ACCELERATION (g's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 .2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

8023-SK-S-896

REV.

A 7/24/73

ACCELERATION ( $g$ 's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01

.02

.03

.04

.05

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5

PERIOD (seconds)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
 2. NSSF: CE 3. A/E: Bechtel BWR

II. Component Name: Indicator

1. Scope: ☒ NSSF ☐ BOP
2. Model Number: 1136 Quantity: 8
3. Vendor: Sigma
4. If the component is a cabinet or panel, name and model No. of the devices included: NA
5. Physical Description a. Appearance Panel Mounted Indicator  
 b. Dimensions 2 1/2" x 3 1/3" x 3/4"  
 c. Weight 5 oz
6. Location: Building: Control Area, Aux. Bldg.  
 Elevation: 30'
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Screwed on mounting plate
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S: 27, 34 F/B: >35  
 V: >35
9. a. Functional Description: Indication  
 b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 365, Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Sigma SBI-3

Lab: Acton Laboratories Rpt. No. 11879

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS for mounting.  
Floor RRS attached

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0g input F/B = 3.0g input V = 3.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE 35  
Other Full level at each integer freq. from 1 to 35 HZ  
(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No RRS or TRS

6. Input g-level Test at:

S/S = 3.5 F/B = 3.5 V = 3.5

7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 4, Size 2-56) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES: VERTICAL	None below 35 Hz	SIDE / SIDE	27, 34 Hz	FRONT / BACK	None below 35 Hz
ELECTRICAL OPERATION	Maximum change in accuracy was 1.6% of full scale.				
PHYSICAL INTEGRITY	No mechanical damage or deterioration.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 .2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-696

REV.

A 7/26/73

ACCELERATION (g's)



FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

LGH

203

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-895

REV.

A 7/24/73

ACCELERATION ( $g$ 's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

2

3

4

.5

.8

1

2

3

4

5

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison CompanyPWR X2. NSSS: CE3. A/E: Bechtel

BWR

II. Component Name: Indicator1. Scope: ☒ NSSS ☐ BOP2. Model Number: 9270 Quantity: 803. Vendor: Sigma4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Panel Mounted Indicatorb. Dimensions 2 1/2" x 7" x 8 1/2"c. Weight 4#6. Location: Building: Control Area, Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No.         , Size         )  
☐ Weld (Length         )  
☒ Screwed on mounting plate

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 27, 34 F/B: >35 V: >359. a. Functional Description: Indicationb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both10. Pertinent Reference Design Specifications: 1370-ICE-0005Sheet 151 Rev. 0, 168 Rev. 2, 179 Rev. 00, 169 Rev. 2,  
347 Rev. 1, 348 Rev. 3, 414 Rev. 01, 413 Rev. 01, 421 Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Sigma Report SBI-3

Lab: Acton Laboratories Rpt. No. 11879

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS for mounting.  
Floor RRS attached

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0g input F/B = 3.0g input V = 3.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level at each integer freq. from 1 to 35 HZ  
 (Specify)

4. Frequency Range: 1 to 35

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No RRS or TRS

6. Input g-level Test at:

S/S = 3.5 F/B = 3.5 V = 3.5

7. Laboratory Mounting: Simulated Normal Rack Mounting

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See Attached Sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis                      ☐ Equivalent Static Analysis  
☐ Dynamic Analysis                      ☐ Time-History  
☐ Response Spectrum

3. Model Type:    ☐ 3D                      ☐ 2D                      ☐ 1D  
☐ Finite Element    ☐ Beam                      ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



# I. Test Results

NATURAL FREQUENCIES: VERTICAL	None below 35 Hz	SIDE / SIDE	27 34 Hz	FRONT / BACK	None below 35 Hz
ELECTRICAL OPERATION	Maximum accuracy change of .65% of full scale				
PHYSICAL INTEGRITY	No mechanical damage or deterioration				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

Commercial steel screws were found to be bending during testing so hardened steel mounting screws were substituted and testing was completed. The hardened mounting screws are new standard mounting hardware.

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-696

REV.

A 7/24/73

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

5023-SK-S-895

REV.

A 7/24/73

ACCELERATION ( $g$ 's)



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Indicating Controller

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: 250 Quantity: 2  
3. Vendor: Foxboro Co.  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Module for Shelf Mounting  
b. Dimensions 1.89" x 8.56 x 3.6"  
c. Weight 3#  
6. Location: Building: Control Area, Aux Bldg.  
Elevation: 30'  
7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ In shelves, clamped in both sides  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S:  F/B:   
V:   
9. a. Functional Description: Indication and control of input and setpoint  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: 00000-ICE-005,  
1370-ICE-005 Rev. 1 Sheet 346 Rev. 5

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Equipment not tested yet  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS for panel; floor response attached

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0 F/B = 3.0 V = 3.0

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other \_\_\_\_\_

(Specify)

4. Frequency Range: \_\_\_\_\_

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:

S/S = \_\_\_\_\_  
 F/B = \_\_\_\_\_  
 V = \_\_\_\_\_

7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: \_\_\_\_\_

10. Other tests performed (such as fragility test, including results):  
 \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum

3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-696

REV.

4 7/28/73

ACCELERATION (g's)

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

Approved By:

WOB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-896

REV.

A 7/24/53

ACCELERATION (g's)

16

14

12

10

8

6

4

2

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

PERIOD (seconds)

.01 .02 .03 .04 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_II. Component Name: Recorder1. Scope: ☒ NSSS ☐ BOP2. Model Number: 226 Quantity: 33. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Nested Module for Rack Mountingb. Dimensions 8 1/8" x 26" x 3"c. Weight 5#6. Location: Building: Control Area, Aux. Bldg.Elevation: 30'7. Field Mounting Conditions ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_)  
☐ Weld (Length \_\_\_\_\_)  
☒ In shelves, clamped in both sides

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: \* F/B: \*V: \*

\*No Resonance Survey Conducted

9. a. Functional Description: Records value of input process  
variable on strip chartb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown☒ Both \_\_\_\_\_10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 173 Rev. 5, 328 Rev. 6, 420 Rev. 3

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report T6-6015

Lab - Acton Laboratories Rpt. No. 12447

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): No RRS for mounting  
location. Floor RRS  
attached.

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 3.0g input F/B = 3.0g input V = 3.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level at each integer freq. from 1 to 35 HZ  
 (Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS or RRS

6. Input g-level Test at:  
 S/S = 3 F/B = 3 V = 3
7. Laboratory Mounting: Standard shelf hardware (to simulate field insulation)
1. ☐ Bolt (No.       , Size       ) ☐ Weld (Length       )  
☐
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis:
- ☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes:         
 Frequency Range and No. of modes considered:         
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other:         
 (specify)
6. Damping:        Basis for the damping used:
7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES: VERTICAL	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Maximum calibration shift of 0.4% full scale, except for 2 failures whose corrections are noted in Discussion.	
PHYSICAL INTEGRITY	Intact; no physical anomalies other than those noted below as electrical anomalies	
DYNAMIC RESPONSE TO FULL-LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)		
MAXIMUM STRUCTURAL STRESS		
MAXIMUM EXTERIOR DEFLECTION		
DYNAMIC LOAD TO MOUNTING		
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES		

## VI. DISCUSSION

- 1) A wire on a printed circuit board broke at the solder joint. This break caused a pen to read incorrectly. The board was redesigned to incorporate this and other similar (loose) wires as part of the printed circuit thus eliminating loose wiring on the PC board.
- 2) The drive belt of one of the pens slipped off the idler wheel cause the pen to read incorrectly. The shoulder of the idler wheel was enlarged to prevent reoccurrence of this problem.

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF CENTRAL CONTROL AREA, AUX. BLDG.

Prepared By:

AL

Reviewed By:

FLG

LGH

QBS

Approved By:

WXB

JOB NO.

1304-803


SKETCH NO.

8023-SK-S-896

REV.

A 7/26/73

ACCELERATION (g's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 5, ELEVATION 30'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WOB

JOB NO.

1304-803


SKETCH NO.

8023-SK-S-896

REV.

A 7/26/73

ACCELERATION ( $g$ 's)



PERIOD (seconds)



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Temperature Sensor (RTD)1. Scope: ☒ NSSS ☐ BOP2. Model Number: 104A Quantity: 23. Vendor: Rosemount4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Narrow well RTDb. Dimensions 22" x 1/2", 5-1/2" Diam. headc. Weight 10#6. Location: Building: Safety Equipment BuildingElevation: -15'-6"7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Install in well

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 20, 25, 33, 44 F/B: 20, 25, 33, 44V: No resonance survey conducted in the axial direction of the RTD9. a. Functional Description: Convert temperature to electrical signalb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 337 Revision 3

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Rosemount, 273020, Revision A  
MTS Laboratory, Report #73  
 (Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 0.8g input F/B = 0.8g input V = 0.5g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ continuous sine

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level dwell at 20, 25, 33, 44 Hz  
 (Specify)

4. Frequency Range: 1 to 100 Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS

6. Input g-level Test at:

S/S = 3.6

F/B = 3.6

V = 3.0

7. Laboratory Mounting: See test results, VI below

1. ☒ Bolt (No. 4, Size 3/8-24) ☐ Weld (Length )  
☒ Sensor secured with gripper assembly at center to simulate  
in-service deep well mounting

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then  
Complete:

1. Description of Test including Results: N/A

2. Method of Analysis:

☐ Static Analysis

☐ Dynamic Analysis

☐ Equivalent Static Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element

☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other:

(specify)

6. Damping: Basis for the damping used:

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# II. Test Results

NATURAL FREQUENCIES VERTICAL	See discussion	SIDE SIDE	20, 25, 33, 44 Hz	FRONT BACK	20, 25, 33, 44 Hz
ELECTRICAL OPERATION	No change in output; no shift in calibration				
PHYSICAL INTEGRITY	Intact; no physical effects				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

1. This sensor is used in deepwell applications. To simulate this, the sensor was fixed into a rigid pipe which was attached to the shaker. The head of the sensor is massive with respect to the rest of the sensor, and is located at one end of the instrument, and was located about 12 inches from the point of attachment to the shaker. The sensor is a symmetrical beam and was tested only in the direction perpendicular to the major axis.
2. The RTD was checked at temperatures of 32°F, 212°F, 515°F, and 615°F, before and after testing. During the seismic test the resistance was monitored to detect sudden resistance changes or failures.

The RTD accuracy was found to be within the manufacturer's normal tolerances after the test. No failures or other disturbances were detected during the test.

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.60



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (-) 15'-6" OF  
SAFETY EQUIPMENT BUILDING  
(SAFETY INJECTION AREA)

Prepared By:

ADIC

Reviewed By:

And KEN

Approved By:

WJG

JOB NO.

10079-003


SKETCH NO.

S023-SK-S-937

REV.

B 1231-75

ACCELERATION (g's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.55



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
E-W HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (-) 15'-6" OF  
SAFETY EQUIPMENT BUILDING  
(SAFETY INJECTION AREA)

Prepared By:

JPIC

Reviewed By:

KH KH

Approved By:

WJG

JOB NO.

10079-003


SKETCH NO.

S023-SK-S-927

REV.

B 12/31/75

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 .2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.55



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
N-S HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (-) 15'-6" OF  
SAFETY EQUIPMENT BUILDING  
(SAFETY INJECTION AREA)

Prepared By:

*ADK*

Reviewed By:

*R. and LSH*

Approved By:

*W. G.*

JOB NO.

10079-003


SKETCH NO.

S023-SK-S-932

REV.

*B* 12-31-75

ACCELERATION ( $g$ 's)





Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Temperature Sensor (RTD)1. Scope: ☒ NSSS ☐ BOP2. Model Number: 104AFC Quantity: 223. Vendor: Rosemount4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Narrow RTDb. Dimensions 22" x 1/2" Diam., 5-1/2" Diam. Headc. Weight ≅10#6. Location: Building: Containment BuildingElevation: 80'-6"7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☐ Weld (Length )  
☒ Installed in well

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 20, 25, 33, 44 F/B: 20, 25, 33, 44V: No resonance survey conducted in the axial direction of the RTD.9. a. Functional Description: Convert temperature to electrical signalb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 163 Revision 4

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X - Model 104A

Analysis: X - Similiarity analysis

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Rosemount 27320A, 77522A

MTS Laboratory, Report No. 73

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐

(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 1.0g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ continuous sine

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other Full level dwell at 20, 25, 33, 44 Hz.

(Specify)

4. Frequency Range: 1 to 100 Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS

6. Input g-level Test at:  
 S/S = 3.6  
 F/B = 3.6  
 V = 3.0
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 4, Size 3/8-24) ☐ Weld (Length \_\_\_\_\_)  
☒ Sensor gripped at center, simulating in-service deepwell mounting.
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: N/A
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES VERTICAL	See discussion	SIDE SIDE	20, 25, 33, 44 Hz	FRONT BACK	20, 25, 33, 44 Hz
ELECTRICAL OPERATION	No change in output; no shift in calibration				
PHYSICAL INTEGRITY	Intact; no physical effects				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					


## VI. DISCUSSION

1. This sensor is used in deepwell applications. To simulate this, the sensor was fixed into a rigid pipe which was attached to the shaker. The head of the sensor is massive with respect to the rest of the sensor, and is located at one end of the instrument, and was located about 12 inches from the point of attachment to the shaker. The sensor is a symmetrical beam and was tested only in the direction perpendicular to the major axis.
2. The RTD was checked at temperatures of 32°F, 212°F, 515°F, and 615°F, before and after testing. During the seismic test the resistance was monitored to detect sudden resistance changes or failures.

The RTD accuracy was found to be within the manufacturer's normal tolerances after the test. No failures or other disturbances were detected during the test.

Required Response Spectrum  
for RTDs attached to hot  
and cold leg main coolant  
piping

SSE - 1%β - Horizontal & Vertical



K-E LOGARITHMIC 3 X 3 CYCLES  
NEUPPEL & ESSER CO. MADE IN U.S.A.

$S_d = 10 T^2 S_a$   
 $S_d$  = DISPLACEMENT RESPONSE (INCHES)  
 $T$  = PERIOD (SEC.)  
 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
 AS PERCENT OF CRITICAL




BECHTEL POWER CORPORATION  
 LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
 SAN ONOFRE NUCLEAR GENERATING STATION  
 UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
 HORIZONTAL ACCELERATION RESPONSE  
 SPECTRA FOR CONTAINMENT  
 INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By: JWW KMS	Reviewed By: LGH DB	Approved By: WAB JHE
JOB NO. 1304-803	SKETCH NO. S023-SK-S-636	REV. A

ACCELERATION ( $g$ 's)



8-23-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By:

JWW KMS

Reviewed By:

LGR QRS

Approved By:

WAB JHE

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-635

REV.

A

ACCELERATION (g's)



8-23-73



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Pressure Transmitter1. Scope: ☒ NSSS ☐ BOP2. Model Number: ELLGM Quantity: 263. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Separately Mounted Moduleb. Dimensions 11 1/3" x 6 7/8"c. Weight 20#6. Location: Building: Radwaste Area Aux. Bldg.Elevation: 24'7. Field Mounting Conditions ☒ Bolt (No. 2, Size 3/8"-24)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: See VI.9 below F/B: V: 9. a. Functional Description: Transmit outsignals proportional to input pressureb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 123 Rev. 2, 128 Rev. 4, 176 Rev. 2, 338 Rev. 0, 353 Rev. 1,  
354 Rev. 2, 418 Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro; T3-1091

Lab - Acton Laboratories Rpt. No. 10486

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.80g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other Full level at each integer freq from 1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS

## 6. Input g-level Test at:

S/S = 3.5

F/B = 3.5

V = 3.5

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 2, Size 10-32) ☐ Weld (Length )  
☐8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

## VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

2. Method of Analysis:

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other:

(specify)

6. Damping: Basis for the damping used:

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES	VERTICAL <u>See discussion</u>	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	<u>Electrical output oscillations at all frequencies. Maximum DC level Shift - 3.2%. Maximum oscillation amplitude - + 9%</u>		
PHYSICAL INTEGRITY	<u>No significant mechanical resonance; no loosening or damage</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

The transmitter was tested in same manner (sine-beat) to 10.0 qs with no effects other than larger output signal oscillations. Following testing the transmitter was hydro tested to maximum overrange pressure rating without any leakage.

Resonance, exhibited as oscillations of the electrical output, occurred at all frequencies from 1 to 35 Hz. No structural resonance of the transmitter occurred below 35 Hz.

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

 $T$  = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-5"

Prepared By:

JWW

KMS

Reviewed By:

LGH DB

Approved By:

WAB JHE

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-636

REV.

A

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION ( $g$ 's)

15

14

13

12

11

10

9

8

7

6

5

4

3

2

1

0

.01

.02

.03

.04

.06

.08

.1

2

3

.4

.6

.8

1

2

3

4

5

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

$T$  = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By:

SWW KMS

Reviewed By:

LGR QRS

Approved By:

WAB JHE

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-635

REV.

A

ACCELERATION (g's)



8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Pressure Transmitter

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: 1153GP Quantity: 6  
3. Vendor: Rosemount  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Locally mounted transmitter  
b. Dimensions 9" x 4 1/2"  
c. Weight 21#  
6. Location: Building: Containment Bldg.  
Elevation: 80-6'  
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 7/16")  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >40 F/B: >40  
V: 40  
9. a. Functional Description: Provide output signal proportional to input pressure  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 144 Rev. 3, Sheet 166 Rev. 5



III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Rosemount, 3788

Lab - Dayton T. Brown Laboratories

(Environ Engineer Rpt. No. 972B)

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ Continuous sine

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level at 10, 20, 30, 40 HZ  
 (Specify)

4. Frequency Range: 1 to 33

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS

6. Input g-level Test at:

$$S/S = 3.5$$
$$F/B = \frac{3.5}{3.5}$$
$$V = \frac{3.5}{3.5}$$

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 4 ,Size 5/16"-18) ☐ Weld (Length           )  
Vendor provided bolts  
☐

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

## 2. Method of Analysis:

## [ ] Static Analysis

## [ ] Equivalent Static Analysis

- [ ] Dynamic Analysis

[ ] Time-History

[ ] Response Spectrum

3. Model Type: [ ] 3D

[ ] 2D

[ ] 1D

[ ] Finite Element [ ] Beam

[ ] Closed Form Solution

4. [ ] Computer Codes:

Frequency Range and No. of modes considered:

[ ] Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other:

(specify)

6. Damping: Basis for the damping used:

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# VI Test Results

NATURAL FREQUENCIES: VERTICAL 40 Hz SIDE / SIDE \_\_\_\_\_ FRONT / BACK \_\_\_\_\_  
ELECTRICAL OPERATION Test units were continuously powered and pressurized at 80% full scale throughout  
seismic vibration tests, with output signals recorded. Pre- and post-test results were within limits.  
PHYSICAL INTEGRITY Three test units remained intact and performed satisfactorily after the tests.

## DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)

MAXIMUM STRUCTURAL STRESS \_\_\_\_\_  
MAXIMUM EXTERIOR DEFLECTION \_\_\_\_\_  
DYNAMIC LOAD TO MOUNTING \_\_\_\_\_  
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES \_\_\_\_\_

## VI. DISCUSSION

Only one resonance frequency was noted, at 40 Hz in the vertical direction. There was no evidence of any resonance below 10 Hz. Accuracy was within .5%, exhibiting only .1% deviation from readings taken prior to the test, with the exception of unit 106186 at a deviation of 2% from zero during the final sine/sweep dwell in the horizontal axis. This appeared to be a random failure. The unit was tested several days later with deviation less than .1%. The other units tested did not experience any similar problem.

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  - DISPLACEMENT RESPONSE (INCHES)

T - PERIOD (SEC.)

$S_a$  - ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By:

JWW KMS

Reviewed By:

LGP QRS

Approved By:

WAB JHE

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-635

REV.

A

ACCELERATION



8-23-73

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

$T$  = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-5"

Prepared By:

JWW

KMS

Reviewed By:

LGH

DB

Approved By:

WAB

gk

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-636

REV.

A


DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION ( $g$ 's)



PERIOD (seconds)

8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSF: CE 3. A/E: Bechtel BWR

II. Component Name: Differential Pressure Transmitter

1. Scope: ☒ NSSF ☐ BOP  
2. Model Number: E13DH Quantity: 2  
3. Vendor: Foxboro  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Separately Mounted Module  
b. Dimensions 14 1/2" x 6 7/8"  
c. Weight 40#  
6. Location: Building: Containment Building  
Elevation: 34'-0"  
7. Field Mounting Conditions ☒ Bolt (No. 2, Size 1")  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: See VI.9 below F/B:   
V:   
9. a. Functional Description: Transmit output signal proportional to input differential pressure  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 312, Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, T3-1091

Lab: Acton Laboratory Rpt. No. 10486

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.80g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other Full level at each integer freq from 1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS



## 6. Input g-level Test at:

S/S = 3.5

F/B = 3.5

V = 3.5

## 7. Laboratory Mounting:

1. ☒ Bolt (No. 3.5, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NAVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:1. Description of Test including Results: NA

2. Method of Analysis:

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other:

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

## II. Test Results

NATURAL FREQUENCIES: VERTICAL	See Discussion	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Electrical Output oscillations at all frequencies. Maximum DC level shift of -2.0%. Maximum oscillation amplitude of 9%. Maximum calibration shift of -2.42%.		
PHYSICAL INTEGRITY	No anomalies during 3.5g testing, no significant structural resonance. See Discussion.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

### VI. DISCUSSION

The transmitter was tested in a similar manner using 5.0g inputs, and then again with 10.0g inputs. During 10.0g testing a crack was noted in the force motor assembly. A new force motor was installed and testing with 10.0g was repeated without mechanical failure. Following testing the transmitter was hydro-tested to maximum overrange pressure rating without any leakage.

Resonance, exhibited as oscillations of the electrical output, occurred at all frequencies from 1 to 35 Hz.

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

 $S_d$  = DISPLACEMENT RESPONSE (INCHES)

 $T$  = PERIOD (SEC.)

 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By:  
JWW  
KMS

Reviewed By:  
LGH DB

Approved By:  
WAB JHE

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-636

REV.  
A

ACCELERATION ( $g$ 's)

15

14

13

12

11

10

9

8

7

6

5

4

3

2

1

0

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .06 .08 .1

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

$T$  = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION


SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By. JWW KMS	Reviewed By. LGR QRS	Approved By. WAB JME
-------------------------	-------------------------	-------------------------

JOB NO. 1304-803	SKETCH NO. S023-SK-S-635	REV. A
---------------------	-----------------------------	-----------

ACCELERATION ( $g$ 's)



8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Differential Pressure Transmitter

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: EL3DM Quantity: 14  
3. Vendor: Foxboro  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Separately Mounted Module  
b. Dimensions 11 1/8" x 6 7/8"  
c. Weight 20#  
6. Location: Building: Radwaste Area, Aux. Bldg.  
Elevation: 24"  
7. Field Mounting Conditions ☒ Bolt (No. 2, Size 1")  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: See VI.9 below F/B:   
V:   
9. a. Functional Description: Transmit output signal proportional to input differential pressure  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both   
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 344 Rev. 01, 352 Rev. 01, 417 Rev. 02

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro T3-1091

Lab - Acton Laboratories Rpt. 10486

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.0g input F/B = 1.0g input V = 0.80g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☒ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level at each integer freq from 1 to 35 HZ  
 (Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No TRS

6. Input g-level Test at:  
 S/S = 3.5 F/B = 3.5 V = 3.5
7. Laboratory Mounting: \_\_\_\_\_
1. ☒ Bolt (No. 2, Size 10-32) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached list
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES: VERTICAL	See Discussion	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	Electrical output oscillations at all test frequencies. Maximum DC level shift of + 0.4%, maximum oscillation amplitude of 5.0%. Maximum calibration shift less than 0.5% full scale.		
PHYSICAL INTEGRITY	No significant structural resonance, no loosening or damage.		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

The transmitter was tested in a similar manner using 5.0 g inputs, and then using 10.0 g inputs with no effects other than larger output signal oscillations. Following testing, the transmitter was hydro-tested to maximum overrange pressure rating without any leakage.

Resonance, exhibited as oscillations of the electrical output, occurred at all test frequencies. No significant structural resonance occurred.

$S_d = 10 T^2 S_a$   
 $S_d$  = DISPLACEMENT RESPONSE (INCHES)  
 $T$  = PERIOD (SEC.)  
 $S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL




BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By: JWW KMS	Reviewed By: LGH DB	Approved By: WAB JHE
JOB NO. 1304-803	SKETCH NO. S023-SK-S-636	REV. A

ACCELERATION ( $g$ 's)



8-23-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
INTERIOR STRUCTURE ELEVATION 80'-6"

Prepared By:

JWW KMS

Reviewed By:

LSR QRS

Approved By:

WAB JWE

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-635

REV.

2

ACCELERATION (g's)

11

10

9

8

7

6

5

4

3

2

1

0.01

0.02

0.03

0.04

0.06

0.08

0.1

2

3

4

6

8

1

2

3

4

5

PERIOD (seconds)

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: RCP SSSS Pulse Transmitter

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: None Quantity: 16
3. Vendor: Bently - Nevada
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Wall mounted module
- b. Dimensions 8.9" x 6.12" x 4.0"
- c. Weight 5#
6. Location: Building: Containment Bldg.
- Elevation: 45' + up
7. Field Mounting Conditions ☐ Bolt (No. , Size )
- ☐ Weld (Length )
- ☒ Screwed 0.31" dia. hole, 4 places
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: 30 F/B: 30
- V: >35
9. a. Functional Description: Provide shaped pulses which are proportional to RCP speed.
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown
- ☐ Both
10. Pertinent Reference Design Specifications: 00000-ICE-6003, Rev. 2
- 1370-ICE-6003, Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report 54602  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 0.95g input F/B = 0.95g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE 0 SSE 6  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using-Multi-Frequency-Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS exceeds RRS at natural frequencies and above 12 Hz.

## 6. Input g-level Test at:

S/S = 3.5F/B = 3.2V = 2.1

## 7. Laboratory Mounting: \_\_\_\_\_

1. ☒ Bolt (No. 4, Size 10-24) ☐ Weld (Length \_\_\_\_\_)  
[ ] \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:1. Description of Test including Results: N/A

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



# VI Test Results

NATURAL FREQUENCIES VERTICAL	See Discussion Below	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION			
PHYSICAL INTEGRITY			
Intact: no physical effects.			
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

## VI. DISCUSSION

- (a) Mounting: Signal Processor - (4) 10-32 bolt on front and (2) 1/4-20 bolt on back  
Pulse Transmitter - (4) 10-24 bolts
- (b) Natural Frequencies: Signal Processor - No Resonance below 35 Hz.  
Transmitter - Resonance found at 30 Hz in the front-to-back and side-to-side directions.  
No resonance was found below 35 Hz in vertical.
- (c) Full Level Tests: The TRS indicated on the reverse side of this data sheet resulted from the 16 Hz tests. The other TRSs are similar except the frequency is shifted accordingly.

# TEST RESPONSE SPECTRA

DATA SHEET No. 2  
DATE MARCH 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☒ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☒ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
(→) ☒ VERTICAL  
(\*) ☒ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL (→)  
☒ VERTICAL (180° SHIFT) (\*)



# RCPSSSS Seismic Response Spectra


SSE - Horizontal - 1% B

(probe & transmitter)

63'-6.1"  
Interior Cor'd.  
Horizontal.

46 7403

LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Minimum of Two Horizontal Tests (F/B & S/S)

RCPSSSS Seismic Response Spectra  
 SSE - Vertical - 1% $\beta$   
 (probe and transmitter)

• 63'-6"  
 Interior Cont.  
 Ver 1.

Acceleration (g) 46 7403

LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.



Minimum of Two Vertical Tests

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_II. Component Name: Proximity Probe and Connector1. Scope: ☒ NSSS ☐ BOP2. Model Number: 21955-01, 21954-01 Quantity: 163. Vendor: Bently - Nevada4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Rigidly mounted proximity probeb. Dimensions 1.25" L, .375" diam.c. Weight 2 oz.6. Location: Building: Containment Bldg.Elevation: 45' + up7. Field Mounting Conditions ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_)  
☐ Weld (Length \_\_\_\_\_)  
☒ Mounting clips to fit 1/4" holes

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: See VI 9 below F/B: \_\_\_\_\_

V: \_\_\_\_\_

9. a. Functional Description: Detect speed of RCPb. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☐ Both \_\_\_\_\_10. Pertinent Reference Design Specifications: 1370-ICE-6003, Rev. 2  
00000-ICE-6003

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report #54602  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 0.95g input F/B = 0.95g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis (Bi-Axial)
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
 Other Full level at 6, 8, 10, 12, 14, 16 Hz  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*  
\*TRS exceeds RRS above 12Hz.

## 6. Input g-level Test at:

S/S = 3.5

F/B = 3.6

V = 3.5

7. Laboratory Mounting: Simulated pump mounting1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: See attached sheet

## 10. Other tests performed (such as fragility test, including results):

N/AVII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:1. Description of Test including Results: N/A

## 2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify)

## 6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

## 7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



## II. Test Results

NATURAL FREQUENCIES	VERTICAL <u>See Discussion Below</u>	SIDE / SIDE	FRONT / BACK
ELECTRICAL OPERATION	<u>Performed as required - no degradation of output signal</u>		
PHYSICAL INTEGRITY	<u>Intact; no physical effects</u>		
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)			
MAXIMUM STRUCTURAL STRESS			
MAXIMUM EXTERIOR DEFLECTION			
DYNAMIC LOAD TO MOUNTING			
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES			

### VI. DISCUSSION

Due to its small size an accelerometer could not be placed on the probe.

TEST RESPONSE SPECTRA

DATA SHEET No. 205  
DATE March, 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
( $\rightarrow$ ) ☒ FRONT TO BACK  
( $\rightarrow$ \*) ☒ FRONT TO BACK (180° SHIFT)

TEST PLANE

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE ( $\rightarrow$ )  
☒ SIDE TO SIDE (180° SHIFT) ( $\rightarrow$ \*)

RESPONSE DIRECTION





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
( $\rightarrow$ ) ☒ VERTICAL  
( $\rightarrow$ \*) ☒ VERTICAL (180° SHIFT)

TEST PLANE


☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL ( $\rightarrow$ )  
☒ VERTICAL (180° SHIFT) ( $\rightarrow$ \*)

RESPONSE DIRECTION



RCPSSSS Seismic Response Spectra  
 SSE - Horizontal - 1% $\beta$   
 (probe & transmitter)

6.3'-6.11"  
 Interior Cont.  
 Horizontal.



Minimum of Two Horizontal Tests (F/B & S/S)


RCPSSSS Seismic Response Spectra  
 SSE - Vertical - 1% $\beta$   
 (probe and transmitter)

- 63'-6"  
 Interior Cont.  
 Vert.

Acceleration (g) 46 7403

LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.

K&E



Minimum of Two Vertical Tests

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: Nuclear Instrument Detector Assembly1. Scope: ☒ NSSS ☐ BOP2. Model Number: ELE 304-5000-1 Quantity: 43. Vendor: General Atomic/Reuter Stokes4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Cylindrical Neutron Detectorb. Dimensions 183" L, 5 3/4" Diamc. Weight 155#6. Location: Building: Containment (Bldg. Interior Structure)Elevation: 18'7. Field Mounting Conditions ☒ Bolt (No. 26, Size 1/4"- 28 x 1" long)  
☐ Weld (Length )  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: 16-33 F/B: 6, 10, 14 - 33V: 319. a. Functional Description: Neutron detectorb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown☒ Both 10. Pertinent Reference Design Specifications: 1370-ICE-3006  
00000-ICE-3006 Rev. 03

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle; 54534  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
 (Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
 S/S = 0.8g input F/B = 0.8g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]
3. No. of Qualification Tests: OBE 5 SSE 1  
 Other \_\_\_\_\_  
 (Specify)
4. Frequency Range: See TRS attached
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS exceeds RRS at natural frequencies and above 4Hz except between  
30 and 45Hz.

## 6. Input g-level Test at:

S/S = 1.0

F/B = 1.0

V = 0.8

## 7. Laboratory Mounting:

1. ☐ Bolt (No. 26, Size 1/4-28) ☐ Weld (Length )  
☐

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete:

1. Description of Test including Results: NA

2. Method of Analysis:

☐ Static Analysis☐ Dynamic Analysis☐ Equivalent Static Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D ☐ 2D ☐ 1D☐ Finite Element ☐ Beam ☐ Closed Form Solution4. ☐ Computer Codes:

Frequency Range and No. of modes considered:

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other:

(specify)

6. Damping: Basis for the damping used:

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



I. Test Results

NATURAL FREQUENCIES VERTICAL	31 Hz	SIDE SIDE	16 thru 33 Hz	FRONT BACK	6, 10, 14 thru 33 Hz
ELECTRICAL OPERATION	Proper operation verified by alpha current measurement.				
PHYSICAL INTEGRITY	Intact; No Physical Effects				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

VI. DISCUSSION

This detector assembly and a preamplifier (Data Sheet 207) were required to be interconnected to enable proper functional parameters to be recorded. Resonance frequencies noted include frequencies of mechanical resonance and frequencies of variations in electrical output.

See data sheet 207 for test response spectras and explanation of functional testing complete on both the neutron detector and preamplifier/filter assemblies.

# TEST RESPONSE SPECTRA

DATA SHEET No. 207

DATE March, 1977

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING REVISION No. 01

☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)




# Excore Seismic Response Spectra (Detector & Preamp) SSE - Horizontal - 1% $\beta$

30'

Acceleration (g) 46 7400

KE LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.




# Excise Seismic Response Spectra (Detector & Preamp) SSE - Vertical - 1% B

30'  
Interior cent.  
vert.

Acceleration(g) 46 7400

LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: Nuclear Instrument Preamplifier/Filter

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: PA5Q1 Quantity: 4  
3. Vendor: General Atomic  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Wall Mounted Module  
b. Dimensions 5" x 5" x 9"  
c. Weight 10#  
6. Location: Building: Containment Bldg. (Interior Structure)  
Elevation: 23'  
7. Field Mounting Conditions ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_)  
☐ Weld (Length \_\_\_\_\_)  
☒ Mounting Clamp  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: 16-33 F/B: 14-33  
V: 31  
9. a. Functional Description: Amplify nuclear detector signal  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both \_\_\_\_\_  
10. Pertinent Reference Design Specifications: 1370-ICE-3006  
00000-ICE-3006 Rev. 03

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Wyle Laboratories, Report 54534  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 0.8g input F/B = 0.8g input V = 0.8g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE 5 SSE 1  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: See TRS attached

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☒ No\*

\*TRS exceeds RRS from 4Hz to 30Hz.

6. Input g-level Test at:

S/S = See TRS

F/B = \_\_\_\_\_

V = \_\_\_\_\_

7. Laboratory Mounting: Mounting Clamp as intended for service

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: See attached sheet

10. Other tests performed (such as fragility test, including results):

NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: NA

2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☐ 2D

☐ 1D

☐ Finite Element ☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☐ Other: \_\_\_\_\_

(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



## II. Test Results

NATURAL FREQUENCIES	VERTICAL	31 Hz	SIDE-SIDE	16 thru 33 Hz	FRONT BACK	14 thru 33 Hz
ELECTRICAL OPERATION	Proper operation verified, outputs monitored verified proper operation within specified limits					
PHYSICAL INTEGRITY	Intact; No Physical Effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

### VI. DISCUSSION

The preamplifier/filter assembly was rigidly mounted to the same thimble that contained the detector holder assembly (data sheet 206). All electrical interconnections between the detector assembly, preamplifier/filter assembly, and Safety Drawer were intended to closely mimic the actual field mounting of these components. Prior to the actual performance of the seismic test, the "LOG CALIBRATE" Switch, located on the Safety Drawer front panel, was placed in the "Test 3" Position. This substituted test pulses from the Safety Drawer electronics into the preamplifier input. These test pulses were in turn processed by the preamplifier, and the resulting output transmitted through five hundred feet of signal cable to the Log input of the Safety Drawer. The Log output of the Safety Drawer was connected to the visicorder, such that any fluctuations in the log power output could be detected.

Proper operation of the filter portion of the preamplifier/filter assembly was verified by monitoring the linear outputs of the three detectors. The natural alpha decay present within the fission chamber provided a current of approximately 2.5 nanoamperes. All monitored outputs operated within the specified limits prior to, during, and after the seismic test.

# TEST RESPONSE SPECTRA

DATA SHEET NO. 207

DATE March, 1977

REVISION No. 01

SPECTRUM FULL SCALE: ACCELERATION ☐ 10 g ☒ 100 g  
FREQUENCY ☐ 100 Hz ☒ 1000 Hz



1 % CRITICAL DAMPING

- ☐ FRONT TO BACK  
☒ FRONT TO BACK / VERTICAL  
☒ FRONT TO BACK  
☐ FRONT TO BACK (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

- ☐ SIDE TO SIDE  
☒ SIDE TO SIDE / VERTICAL  
☒ SIDE TO SIDE  
☐ SIDE TO SIDE (180° SHIFT)





- ☐ VERTICAL  
☒ FRONT TO BACK / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)

TEST PLANE

RESPONSE DIRECTION

- ☒ SIDE TO SIDE / VERTICAL  
☒ VERTICAL  
☐ VERTICAL (180° SHIFT)




Excore Seismic Response Spectra  
 (Detector & Preamp)  
 SSE - Horizontal - 1% $\beta$

30'

Acceleration (g) 46 7400

LOGARITHMIC 3 X 3 CYCLES  
 KEUFFEL & ESSER CO. MADE IN U.S.A.




Excure Seismic Response Spectra  
(Detector & Preamp)  
SSE - Vertical - 1% $\beta$

30'  
Interior cent.  
vert.

Acceleration(g) 46 7400

KE LOGARITHMIC 3 X 3 CYCLES  
KEUFFEL & ESSER CO. MADE IN U.S.A.



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: CEDM Reed Switch Position Transmitter

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: 150" Type Quantity: 182 Per Plant
3. Vendor: Combustion Engineering, Inc.
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Slender Tube
- b. Dimensions 150" x approx. 1" dia.
- c. Weight Approx. 15 lbs.
6. Location: Building: Containment
- Elevation: 51 ft. to 63.5 ft. approx.
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/4-20)  
☐ Weld (Length )  
☒ Clamped with 3" friction collar  
secured with 2 bolts
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):
- S/S: >33 Hz F/B: >33 Hz
- V: >33 Hz
9. a. Functional Description: To transmit control element assembly position signals.
- b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both
10. Pertinent Reference Design Specifications: CE Specifications  
STD-485-311, Rev. 04 and 1370-485-311, Rev. 01

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: Multifrequency input

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Combustion Engineering TR-ESE-285  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☒ Biaxial input  
(Other, Specify)

2. Required Response Spectra (attach the graphs): Figs. 1 and 2 attached

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.1g F/B = 1.1g V = 0.8g

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☒ Multi-Frequency: ☒ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis (Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other Total of 60 OBE + DBE  
(Specify)

4. Frequency Range: See TRS

5. TRS enveloping RRS using Multi-Frequency Test ☒ Yes (plot TRS on RRS graphs)  
(over applicable range)

☐ No

6. Input g-level Test at:

S/S = >1.1 (Over applicable range)

$$F/B = \frac{\quad}{\quad} > 1.1$$
$$V = \overline{\quad} > 0.8$$

7. Laboratory Mounting: Clamped to Control Element Drive Mechanism  
Upper Pressure Housing - identical to in-plant mounting.

1. ☐ Bolt (No. 4, Size 1/4-20) ☐ Weld (Length           )

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: Equipment met all requirements, no modifications required. (See attachment)

10. Other tests performed (such as fragility test, including results):

None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results:

## 2. Method of Analysis:

## [ ] Static Analysis

[ ] Dynamic Analysis

## [ ] Equivalent Static Analysis

[ ] Time-History

[ ] Response Spectrum

3. Model Type:    ☐ 3D                      ☐ 2D                      ☐ 1D

☐ Finite Element    ☐ Beam    ☐ Closed Form Solution

4. [ ] Computer Codes:

Frequency Range and No. of modes considered:

[ ] Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

[ ] Other: \_\_\_\_\_  
(specify)

6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model:

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



## VI. Test Results

NATURAL FREQUENCIES	VERTICAL	See Discussion	SIDE SIDE	See Discussion	FRONT BACK	See Discussion
ELECTRICAL OPERATION	Proper operation verified, no failures.					
PHYSICAL INTEGRITY	Intact; no physical effects					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

### VI. DISCUSSION

- (a) Mounting: The RSPT assembly was installed inside the shroud of the 150" CEDM. The CEDM was mounted on top of a biaxial shaker table with equal, phase coherent input motion in the horizontal and vertical axes.
- (b) Full Level Seismic Test: Due to symmetry about the vertical axes of the RSPT the system was not tested in the side-to-side direction.
- (c) Electrical Operation: The electrical performance of the RSPT assembly was verified with the actuating magnet held inside the shroud at the mid-position of the CEA travel range.
- (d) Natural Frequencies: Due to the physical inaccessibility of the RSPT the natural frequencies of the RSPT could not be measured. However, the CEDM's fundamental natural frequency was found at 3.2 Hz and at about 200 Hz for the horizontal and vertical directions respectively.

2% DAMPING  
Horizontal Response Spectrum





FIGURE 2

2% DAMPING  
VERTICAL RESPONSE SPECTRUM



## ATTACHMENT


### Qualification Summary of Equipment - SAN ONOFRE RSPTs Test Response Spectra

Attached are graphs of horizontal and vertical Test Response Spectra (TRS) from the San Onofre Control Element Drive Mechanism (CEDM) Reed Switch Position Transmitter (RSPT) qualification test program. The TRSs indicate the actual seismic intensities achieved during random multi frequency bi-axial testing of the RSPT mounted inside a CEDM which was supported in a simulated SCE fashion. The spectra were developed for the simulated reactor head elevation (shaker table surface).


The vertical lines on the graphs indicate the actual achieved intensities of frequencies spaced no more than 1/6 octave apart. The solid lines indicate the Required Response Spectra (RRS). Whereas the vertical RRS is shown as specified, the horizontal RRS is shown modified below 2.25 Hertz (20% below lowest natural frequency of free standing CEDM). This modification is permissible according to Guidelines IEEE-344-1975, which only requires envelopment of the RRS over the "applicable" frequency range. The applicable range is defined as the frequency band in which support structure or specimen resonances are found. In the case of the SCE RSPT qualification test, the lowest support structure (CEDM) resonance was found at 5.6 Hertz and the reed switch assembly resonances are well above this frequency value.

Due to an asymmetric design condition of the RSPT, it was tested in two orientations. During Test Series A the RSPT was mounted inside the shroud in the rear position (facing the shaker table) and during Test Series B the RSPT was mounted in a side position.

The RSPT was found capable to withstand a minimum of 5 OBE and 1 DBE events for each test orientation without indicating any transient upset conditions or malfunctioning. Typical horizontal and vertical response spectra are attached for one DBE and two OBE events.




Horizontal  
T.R.S.




Vertical  
T.R.S.

Series B OBE Event  
Test Run No. 34





Horizontal  
T.R.S.




Vertical  
T.R.S.


Series B OBE Event  
Test Run No. 38



Series A OBE Event  
Test Run No. 39





Horizontal  
T.R.S.



Vertical  
T.R.S.



Series A OBE Event  
Test Run No. 40





Series A DBE Event

Test Run No. 54



Series B DBE Event  
Test Run No. 61

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Magetic Flow Tube

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: 2800 Quantity: 2  
3. Vendor: Foxboro  
4. If the component is a cabinet or panel, name and model No. of the devices included: NA  
5. Physical Description a. Appearance Pipe section w/windings  
b. Dimensions 11 9/16" x 10 3/4" 14 5/8"  
c. Weight 44#  
6. Location: Building: Safety Equipment Bldg.  
Elevation: 10"  
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/2 per Flange End)  
Flange connection  
☐ Weld (Length )  
☐   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >35 F/B: >35 V: >35  
9. a. Functional Description: Develop output signal proportional to fluid flow rate through tube  
b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: 1370-ICE-0005  
Sheet 342 Rev. 2

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report T5-6092

Lab - Action Laboratory Rpt. No. 12137

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_

(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.1g input F/B = 1.1g input V = 1.4g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☒ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other Full level at each integer freq from 1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

Not Acceptable

6. Input g-level Test at: (See test results attachment)  
 S/S = 3 F/B= 3 V = 3
7. Laboratory Mounting: Simulating in-service mounting
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☒ Flanged into mock-up pipes
8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☐ Static Analysis ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☐ 3D ☐ 2D ☐ 1D  
☐ Finite Element ☐ Beam ☐ Closed Form Solution
4. ☐ Computer Codes: \_\_\_\_\_  
 Frequency Range and No. of modes considered: \_\_\_\_\_  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: \_\_\_\_\_  
 (specify)
6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_
7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

# I. Test Results

NATURAL FREQUENCIES	VERTICAL	None below 35 Hz	SIDE/SIDE	None below 35 Hz	FRONT/BACK	None below 35 Hz
ELECTRICAL OPERATION	All shifts in calibration data and output signal level during testing less than 0.1% full scale.					
PHYSICAL INTEGRITY	Intact; no physical effects; no observable fluid leakage.					
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)						
MAXIMUM STRUCTURAL STRESS						
MAXIMUM EXTERIOR DEFLECTION						
DYNAMIC LOAD TO MOUNTING						
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES						

## VI. DISCUSSION

The test table acceleration (input motion to specimen) decreased to less than 3.0 g (but stayed greater than 1.0 g) at frequencies above 20 Hz due to test table non linearity.

FREQUENCY (cycles per second)  
100 50 25 10 5 2 1 .5

$S_d = 10 T^2 S_a$   
 $S_d$  = DISPLACEMENT RESPONSE (INCHES)  
 $T$  = PERIOD (SEC.)  
 $S_a$  = ACCELERATION RESPONSE (g's)  
DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3


DESIGN BASIS EARTHQUAKE  
N-S HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 30'-6" OF  
SAFETY EQUIPMENT BUILDING

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.55

Prepared By <i>J. M. C.</i>	Reviewed By <i>K. H. H.</i>	Approved By <i>J. E.</i>
JOB NO 10079-003	SKETCH NO. 5023-SK-S-835	REV <i>B. 10/79</i>

ACCELERATION (g's)

DAMPING = 0.5%  
DAMPING = 1.0%  
DAMPING = 2.0%  
DAMPING = 5.0%





FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ )

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.60



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 30'-6" OF  
SAFETY EQUIPMENT BUILDING

Prepared By:

JMC

Reviewed By:

Rmd JGH

Approved By:

WEC

JOB NO.


10079-003

SKETCH NO.

8023-SK-S-040

REV.

B'23-2



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison CompanyPWR X2. NSSS: CE3. A/E: Bechtel

BWR

II. Component Name: Magetic Flow Transmitter

1. Scope: ☒ NSSS ☐ BOP2. Model Number: E96Quantity: 23. Vendor: Foxboro4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance Enclosed Moduleb. Dimensions 10 1/4" x 12" x 4 3/4"c. Weight 20#6. Location: Building: Safety Equipment Bldg.Elevation: 11'7. Field Mounting Conditions ☒ Bolt (No. 2, Size 1/2")  
☐ Weld (Length           )  
☐           

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >35F/B: >35V: >359. a. Functional Description: Converts input siganl to output  
siganl (4-20 MA)b. Is the equipment required for ☒ Hot Standby ☐ Cold Shutdown☐ Both           10. Pertinent Reference Design Specifications: 1370-ICE-0005Sheet 343 Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Foxboro, Report T5-6092

Lab - Acton Laboratories Rpt. No. 12137

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐

(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.1g

F/B =

1.4g

V =

1.4g

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random ☒ sine beat

☐

2. ☐ Single Axis ☒ Multi-Axis [Bi-axial]

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other Full level at each integer freq. from 1 to 35 HZ

(Specify)

4. Frequency Range: 1 to 35 HZ

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)

☐ No

Not Applicable

6. Input g-level Test at: (See test results attachment)
- S/S = 3 F/B = 3 V = 3
7. Laboratory Mounting: Simultating in service mounting
1. [ ] Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) [ ] Weld (Length \_\_\_\_\_)  
[ ] \_\_\_\_\_
8. Functional operability verified: [X] Yes [ ] No [ ] Not Applicable
9. Test Results including modifications made: See attached sheet
10. Other tests performed (such as fragility test, including results):  
  
NA

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

**Complete:**

- [illegible]

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

II. Test Results

NATURAL FREQUENCIES: VERTICAL	None below 35 Hz	SIDE / SIDE	None below 35 Hz	FRONT / BACK	None below 35 Hz
ELECTRICAL OPERATION	All shifts of calibration and instrument output during testing less than 0.1% of full scale.				
PHYSICAL INTEGRITY	Intact; no physical effects.				
DYNAMIC RESPONSE TO FULL LEVEL TEST (LARGE OR SUPPORT STRUCTURES ONLY)					
MAXIMUM STRUCTURAL STRESS					
MAXIMUM EXTERIOR DEFLECTION					
DYNAMIC LOAD TO MOUNTING					
MAXIMUM TRANSMISSIBILITY TO SUPPORTED DEVICES					

## VI. DISCUSSION

The test table acceleration (input motion to specimen) decreased to less than 3g. (but stayed greater than 1.0g.) at frequencies beyond 20 Hz due to test table control difficulty.

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5

$S_d = 10 T^2 S_a$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.55



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
N-S HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 30'-6" OF  
SAFETY EQUIPMENT BUILDING

Prepared By

*JMC*

Reviewed By

*W.H. 10/11*

Approved By

*DE*

JOB NO

10079-003


SKETCH NO.

S023-SK-S-835

REV

*B-10/12*

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ )

DAMPING VALUES  
AS PERCENT OF CRITICAL

TO OBTAIN OPERATING BASIS  
EARTHQUAKE RESPONSE ACCELERATION,  
MULTIPLY BY 0.60



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONO FRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT ELEV (+) 30'-6" OF  
SAFETY EQUIPMENT BUILDING

Prepared By:

JMC

Reviewed By:

Hand LGH

Approved By:

WE

JOB NO.


10079-003

SKETCH NO.

8223-SK-S-040

REV.

B/231-E





Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Containment Purge Isolation Detector

1. Scope: ☒ NSSS ☐ BOP
2. Model Number: GA-3M-652-1-21-X-5-0 Quantity: 2
3. Vendor: Nuclear Measurements Corporation
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A
5. Physical Description a. Appearance Wall mounted detector ass'y  
 b. Dimensions 16" x 14" x 5'  
 c. Weight ≈10#
6. Location: Building: Penetration Bldg.  
 Elevation: 45'
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/4-20)  
☐ Weld (Length )  
☐ Not yet mounted
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
 S/S:  F/B:   
 V:
9. a. Functional Description: Detect high radiation level, sends analog signal to transmitter  
 b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both
10. Pertinent Reference Design Specifications: 1370-ICE-5003, Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Test report not received.  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 0.9g input F/B = 0.9g input V = 0.9g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☐ Multi-Axis (Bi-Axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other \_\_\_\_\_  
(Specify)

4. Frequency Range: \_\_\_\_\_

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:

S/S = \_\_\_\_\_  
F/B = \_\_\_\_\_  
V = \_\_\_\_\_

7. Laboratory Mounting: \_\_\_\_\_

1. [ ] Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) [ ] Weld (Length \_\_\_\_\_)  
[ ] Commercial

8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made:

10. Other tests performed (such as fragility test, including results):

N/A

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: N/A

2. Method of Analysis:

<input type="checkbox"/> Static Analysis	<input type="checkbox"/> Equivalent Static Analysis
<input type="checkbox"/> Dynamic Analysis	<input type="checkbox"/> Time-History
	<input type="checkbox"/> Response Spectrum

3. Model Type:    ☐ 3D                  ☐ 2D                  ☐ 1D  
                     ☐ Finite Element    ☐ Beam              ☐ Closed Form Solution

4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

[ ] Hand Calculations

[illegible]

6. Damping: Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: \_\_\_\_\_

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

JWW KMS

Reviewed By:

IGH QB

Approved By:

WAB JR

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-642

REV.

A

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION (g's)

13  
12  
11  
10  
9  
8  
6  
5  
4  
3  
2  
1  
0

.01 .02 .03 .04 .05 .06 .07 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 .2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

$T$  = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

Reviewed By:

Approved By:

JWW KHS

LSM 6-3

WLB 6-6

JOB NO.  
1304-803

SKETCH NO.  
S023-SK-S-641

REV.

L

ACCELERATION ( $g$ 's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .05 .06 .08 .1 .2 .3 .4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR \_\_\_\_\_

II. Component Name: Containment Purge Isolation Transmitter

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: GA-3M-652-1-21-X-5-0 Quantity: 2  
3. Vendor: Nuclear Measurements Corporation  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Wall mounted assembly  
b. Dimensions 14-1/4" x 17-1/2" x 8"  
c. Weight ≈20#  
6. Location: Building: Penetration Bldg.  
Elevation: 45'  
7. Field Mounting Conditions ☒ Bolt (No. 4, Size 1/2-20)  
☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_  
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: \_\_\_\_\_ F/B: \_\_\_\_\_  
V: \_\_\_\_\_  
9. a. Functional Description: Generate actuation signal from input analog signal  
b. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown  
☒ Both \_\_\_\_\_  
10. Pertinent Reference Design Specifications: 1370-ICE-5003, Rev. 1

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by Test report not received.

(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☐ Combination of \_\_\_\_\_

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☐ \_\_\_\_\_  
(Other, Specify)

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 0.9g input F/B = 0.9g input V = 0.9g input

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_

2. ☐ Single Axis ☐ Multi-Axis

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_

Other \_\_\_\_\_  
(Specify)

4. Frequency Range: \_\_\_\_\_

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No



A



## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61'-3"

Prepared By:

JWW KHS

Reviewed By:

ASB JCB

Approved By:

WJB JCB

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-641

REV.

1

ACCELERATION ( $g$ 's)

12  
11  
10  
9  
8  
7  
6  
5  
4  
3  
2  
1

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

.01 .02 .03 .04 .05 .06 .08 .1 2 3 4 .6 .8 1 2 3 4 5

PERIOD (seconds)

8-23-73

FREQUENCY (cycles per second)

100

50

25

10

5

2

1

.5

.2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA FOR CONTAINMENT  
EXTERIOR SHELL ELEVATION 61' 3"

Prepared By:

JWW KMS

Reviewed By:

LGH QB

Approved By:

WAB JR

JOB NO.

1304-803

SKETCH NO.

S023-SK-S-642

REV.

A

DAMPING = 0.5%

DAMPING = 1.0%

DAMPING = 2.0%

DAMPING = 5.0%

ACCELERATION ( $g$ 's)

13

12

11

10

9

8

6

5

4

3

2

1

0

.01

.02

.03

.04

.06

.08

.1

.2

.3

.4

.6

.8

1

2

3

4

5

PERIOD (seconds)

8-23-73

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: 3HV9323 2" HPSI Globe Motor Op. Valve (SI 616)1. Scope: ☒ NSSS ☐ BOP2. Model Number: TRC DWG 74R-002 Quantity: 83. Vendor: Target Rock Corp.4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance "Y" Pattern Globe Valveb. Dimensions Body = 10 1/2" long x 25 15/16" (height to top of motor)c. Weight 252 lbs6. Location: Building: AuxiliaryElevation: 33'-45'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >35Hz F/B: >35Hz.V: >35Hz.9. a. Functional Description: High Pressure Savety Injection in the Emergency Core Cooling Systemb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown☐ Both 10. Pertinent Reference Design Specifications: 1370-PE-705

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by East-West Technology Corp/Report #7905-7  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_  
5. ☒ Combination of Seismic + Pipe end loading + Design Press.  
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 3.0 F/B = 3.0 V = 3.0

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ 30 sec. continuous sine  
[Consisted of 3 tests; 1 in each direction]
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 12 @ 1, 1.5, 2, 3, 4, 6, 8, 12, 16, 24, 32, 35Hz.  
(Specify)
4. Frequency Range: 1-35Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No  
Not Applicable

## 6. Input g-level Test at:

S/S = 3.0g

F/B = 3.0g

V = 3.0g

## 7. Laboratory Mounting: In Horizontal Pipe Run:

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☒ Weld (Length \* \_\_\_\_\_)  
☐ \_\_\_\_\_

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: The natural frequency is greater than 33Hz and the valve is operable at loaded conditions

## 10. Other tests performed (such as fragility test, including results):

None

VII. If Qualification by Analysis or by the Combination of Test and Analysis, thenComplete: NA

## 1. Description of Test including Results: \_\_\_\_\_

## 2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Equivalent Static Analysis☐ Dynamic Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D ☐ 2D ☐ 1D☐ Finite Element ☐ Beam ☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_  
(specify)

## 6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

## 7. Support Considerations in the model: \_\_\_\_\_

\* Valve inlet and outlet welded to pipe sections which were attached to flanged connections.

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 6, ELEVATION 37'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

warb

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-698

REV.

A 7/24/72

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 8, ELEVATION 37'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH  
[Signature]

Approved By:

WAB  
[Signature]

JOB NO.


1304-803

SKETCH NO.

S023-SK-S-697

REV.

A7/24/73



Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X2. NSSS: CE 3. A/E: Bechtel BWR II. Component Name: 3HV 9322 8" LPSI Globe Motor Op. Valve (SI 615)1. Scope: ☒ NSSS ☐ BOP2. Model Number: TRC Dwg 74R-008 Quantity: 43. Vendor: Target Rock Corp.4. If the component is a cabinet or panel, name and model No. of the devices included: NA5. Physical Description a. Appearance "Y" Pattern Globe Valveb. Dimensions Body = 27 3/4" long x 36 5/16" (height to top of motor)c. Weight 992 lbs6. Location: Building: AuxiliaryElevation: 17' - 33'7. Field Mounting Conditions ☐ Bolt (No. , Size )  
☒ Weld (Length Continuous)  
☐ 

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: Greater than 35Hz F/B: Greater than 35HzV: Greater than 35Hz.9. a. Functional Description: Low Pressure Safety Injection  
in the Emergency Core Cooling Systemb. Is the equipment required for ☒ Hot Standby ☒ Cold Shutdown☐ Both 10. Pertinent Reference Design Specifications: 1370-PE-705

III. Is Equipment Available for Inspection in the Plant: ☐ Yes ☒ No

IV. Equipment Qualification Method: Test: X

Analysis: \_\_\_\_\_

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by East-West Technology Corp/Report #7812-7  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only  
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☒ Combination of Seismic + Pipe end loading + Design Pressure
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☐ \_\_\_\_\_  
(Other, Specify)
2. Required Response Spectra (attach the graphs): X
3. Required Acceleration in Each Direction: \_\_\_\_\_  
S/S = 3.0 F/B = 3.0 V = 3.0

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ 30 sec. continuous sine  
[Consisted of 3 tests in each direction]
2. ☒ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 12 @ 1, 1.5, 2, 3, 4, 6, 8, 12, 16, 24, 32, 35 Hz  
(Specify)
4. Frequency Range: 1-35 Hz
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No  
Not Applicable

## 6. Input g-level Test at:

S/S = 3.0gF/B = 3.0gV = 3.0g7. Laboratory Mounting: In Horizontal Pipe Run:1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☒ Weld (Length \* \_\_\_\_\_)  
☐ \_\_\_\_\_8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable9. Test Results including modifications made: The natural frequency is greater than 33Hz and the valve is operable at loaded conditions.

## 10. Other tests performed (such as fragility test, including results):

NoneVII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

## 1. Description of Test including Results: \_\_\_\_\_

## 2. Method of Analysis: \_\_\_\_\_

☐ Static Analysis☐ Dynamic Analysis☐ Equivalent Static Analysis☐ Time-History☐ Response Spectrum3. Model Type: ☐ 3D☐ 2D☐ 1D☐ Finite Element ☐ Beam☐ Closed Form Solution4. ☐ Computer Codes: \_\_\_\_\_

Frequency Range and No. of modes considered: \_\_\_\_\_

☐ Hand Calculations5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS☐ Other: \_\_\_\_\_

(specify).

## 6. Damping: \_\_\_\_\_ Basis for the damping used: \_\_\_\_\_

## 7. Support Considerations in the model: \_\_\_\_\_

\*Valve inlet and outlet welded to pipe sections which were attached to flanged connections.

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	<u>Governing Load or Response Combination</u>	<u>Seismic Stress</u>	<u>Total Stress</u>	<u>Stress Allowable</u>
----	-----------------------	-----------------	---	---------------------------	-------------------------	-----------------------------

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
----	------------------------	-----------------	---

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison CompanyPWR X2. NSSS: CE3. A/E: BechtelBWR       II. Component Name: Charging Pump1. Scope: ☒ NSSS ☐ BOP2. Model Number: DWG D14851 Quantity: 33. Vendor: Gaulin Corp.4. If the component is a cabinet or panel, name and model No. of the devices included: N/A5. Physical Description a. Appearance Low Profile, Rectangularb. Dimensions Overall, 98" L, 68" W, 37" Hc. Weight 8400 lbs.6. Location: Building: Aux. Equip.Elevation: 9 ft.7. Field Mounting Conditions ☒ Bolt (No. 14, Size 3/4)  
☐ Weld (Length       )  
☐       

8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):

S/S: >35 HzF/B: >35 HzV: >35 Hz9. a. Functional Description: To inject borated water into the reactor coolant systemb. Is the equipment required for ☐ Hot Standby ☐ Cold Shutdown[X] Both10. Pertinent Reference Design Specifications: CE Project Spec. No. 1370-PE-403, Rev. 04 and CE General Engineering Spec. No. 00000-PE-403, Rev. 04

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: \_\_\_\_\_

Combination of Test and Analysis: X

Type Test By AETC Rpt. No. 11785, 7/2/75 Act on Environmental Test Corp.  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☐ Seismic only 2. ☐ Hydrodynamic only

3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_

5. ☒ Combination of Seismic, Operating and Nozzle Loads

6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS

☒ N/A  
(Other, Specify) \_\_\_\_\_

2. Required Response Spectra (attach the graphs): X

3. Required Acceleration in Each Direction: \_\_\_\_\_

S/S = 1.5 F/B = 1.5 V = 1.0

VI. If Qualification by Test, then Complete: \_\_\_\_\_

1. ☒ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☒ 30 sec. continuous sine

2. ☐ Single Axis ☒ Multi-Axis(Bi-axial)

3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other 4 continuous sine in each horiz. and vert. at 2.5, 10, 20, 30 Hz  
(Specify)

4. Frequency Range: 2.5-33 Hz

5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No N/A



6. Input g-level Test at:

S/S = 1.5

F/B = 1.5

V = 1.5

7. Laboratory Mounting: \_\_\_\_\_

1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☒ 12 "C" Clamps

8. Functional operability verified: ☒ Yes ☐ No ☐ Not Applicable

9. Test Results including modifications made: Demonstrated successful operability during and after simultaneous horizontal and vertical seismic acceleration. Demonstrated press. boundary integrity.

10. Other tests performed (such as fragility test, including results):

Pump operating and non-operating during SSE tests. Nozzle loads applied during all tests.

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then

Complete:

1. Description of Test including Results: Type Test conducted on pump assembly almost identical to San Onofre Pump (which has a heavier baseplate, and drive motor frame one size larger than test pump).

2. Method of Analysis: \_\_\_\_\_

☒ Static Analysis

☐ Equivalent Static Analysis

☐ Dynamic Analysis

☐ Time-History

☐ Response Spectrum

3. Model Type: ☐ 3D

☒ 2D Absolute Sum Combination of Loads

☐ 1D

☐ Finite Element

☐ Beam

☐ Closed Form Solution

4. ☐ Computer Codes: N/A

Frequency Range and No. of modes considered: \_\_\_\_\_

☒ Hand Calculations

5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS

☒ Other: N/A

(specify)

6. Damping: N/A Basis for the damping used: \_\_\_\_\_

7. Support Considerations in the model: N/A

8. Critical Structural Elements: Not Tested

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response Combination	Seismic Stress	*	Stress Allowable
					Total Stress	
	Anchor Bolts	+ 9ft.	Seismic Dead- weight, and Nozzle Loads	inc. in Total	20,905 psi	25,000 psi

\*Combined Shear &amp; Tensile

B.	<u>Max. Deflection</u>	<u>Location</u>	<u>Effect Upon Functional Operability</u>
	N/A		

FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE ( $g$ 's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
HORIZONTAL ACCELERATION RESPONSE  
SPECTRA AT NODE 1, ELEVATION 8'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG LGH

Approved By:

WAB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-889

REV.

A 7/2/72

ACCELERATION ( $g$ 's)



FREQUENCY (cycles per second)

100 50 25 10 5 2 1 .5 2

$$S_d = 10 T^2 S_a$$

$S_d$  = DISPLACEMENT RESPONSE (INCHES)

T = PERIOD (SEC.)

$S_a$  = ACCELERATION RESPONSE (g's)

DAMPING VALUES  
AS PERCENT OF CRITICAL



BECHTEL POWER CORPORATION  
LOS ANGELES DIVISION

SOUTHERN CALIFORNIA EDISON COMPANY  
SAN ONOFRE NUCLEAR GENERATING STATION  
UNITS 2 & 3

DESIGN BASIS EARTHQUAKE  
VERTICAL ACCELERATION RESPONSE  
SPECTRA AT NODE 1, ELEVATION 8'-0"  
OF AUXILIARY BUILDING

Prepared By:

AL

Reviewed By:

FLG

LGH

Approved By:

WOB

JOB NO.

1304-803


SKETCH NO.

S023-SK-S-690

REV.

A 7/24/73

ACCELERATION (g's)



PERIOD (seconds)

Qualification Summary of Equipment

I. Plant Name: San Onofre Units 2&amp;3

Type:

1. Utility: Southern California Edison Company PWR X  
2. NSSS: CE 3. A/E: Bechtel BWR

II. Component Name: Shutdown Heat Exchanger

1. Scope: ☒ NSSS ☐ BOP  
2. Model Number: DWG CE-16644, 16645 Quantity: 4  
3. Vendor: EFCO  
4. If the component is a cabinet or panel, name and model No. of the devices included: N/A  
5. Physical Description a. Appearance Vertical HX, exterior painted carbon steel  
b. Dimensions 30'1" long x 56" max OD, 32 3/4" tube nozzles, 36" shell nozzles  
c. Weight Dry 42,000 lbs; Operating 61,000 lbs  
6. Location: Building: Safety Equipment Building  
Elevation: 15 ft. elev.  
7. Field Mounting Conditions ☒ Bolt (No. 16 , Size 1 1/4" Ø)  
☐ Weld (Length )  
☒ Seismic Lugs   
8. Natural Frequencies in Each Direction (Side/Side, Front/Back, Vertical):  
S/S: >33 Hz F/B: >33 Hz  
V: >33 Hz  
9. a. Functional Description: cool reactor coolant, cool ECCS sump water  
b. Is the equipment required for ☐ Hot Standby ☒ Cold Shutdown  
☐ Both   
10. Pertinent Reference Design Specifications: CE Specification No. 1370-PE-301, Revision 03

III. Is Equipment Available for Inspection in the Plant: ☒ Yes ☐ No

IV. Equipment Qualification Method: Test: \_\_\_\_\_

Analysis: X

Combination of Test and Analysis: \_\_\_\_\_

Test and/or Analysis by NUS Corp. TR-75-74 Report No. 1514 Rev. 1  
(Name of Company or Laboratory & Report No.)

V. Vibration Input:

1. Loads considered: 1. ☒ Seismic only 2. ☐ Hydrodynamic only
3. ☐ Explosive only 4. ☐ Other (Specify) \_\_\_\_\_
5. ☐ Combination of \_\_\_\_\_
6. Method of combining RRS: ☐ Absolute Sum ☐ SRSS  
☒ NA  
(Other, Specify) \_\_\_\_\_
2. Required Response Spectra (attach the graphs): NA
3. Required Acceleration in Each Direction: \_\_\_\_\_  
\_\_\_\_\_ Horiz= $DBE \pm 1.2g$  V =  $DBE \pm 1.1g$

VI. If Qualification by Test, then Complete: NA

1. ☐ Single Frequency ☐ Multi-Frequency: ☐ random  
☐ sine beat  
☐ \_\_\_\_\_
2. ☐ Single Axis ☐ Multi-Axis
3. No. of Qualification Tests: OBE \_\_\_\_\_ SSE \_\_\_\_\_  
Other \_\_\_\_\_  
(Specify)
4. Frequency Range: \_\_\_\_\_
5. TRS enveloping RRS using Multi-Frequency Test ☐ Yes (plot TRS on RRS graphs)  
☐ No

6. Input g-level Test at:
- S/S = \_\_\_\_\_  
 F/B = \_\_\_\_\_  
 V = \_\_\_\_\_
7. Laboratory Mounting: \_\_\_\_\_
1. ☐ Bolt (No. \_\_\_\_\_, Size \_\_\_\_\_) ☐ Weld (Length \_\_\_\_\_)  
☐ \_\_\_\_\_
8. Functional operability verified: ☐ Yes ☐ No ☐ Not Applicable
9. Test Results including modifications made: \_\_\_\_\_
10. Other tests performed (such as fragility test, including results): \_\_\_\_\_

VII. If Qualification by Analysis or by the Combination of Test and Analysis, then Complete:

1. Description of Test including Results: NA
2. Method of Analysis: \_\_\_\_\_  
☒ Static Analysis \* ☐ Equivalent Static Analysis  
☐ Dynamic Analysis ☐ Time-History  
☐ Response Spectrum
3. Model Type: ☒ 3D\*\* ☐ 2D ☐ 1D  
☐ Finite Element ☒ Beam ☐ Closed Form Solution  
 \*\* For Natural Frequency Determination
4. ☒ Computer Codes: CDC's Stardyne. NUS's PRECOM, COMBINE, and SANSAR  
 Frequency Range and No. of modes considered:  $f_N > 33$  Hz  
☐ Hand Calculations
5. Method of Combining Dynamic Responses: ☐ Absolute Sum ☐ SRSS  
☐ Other: NA  
 (specify)
6. Damping: NA Basis for the damping used: NA
7. Support Considerations in the model: supports - fixed, seismic lugs - slotted

\*Separate analyses were performed to determine the response in the horizontal and vertical directions. The resultant loads were combined on an absolute sum basis (2 components).

## 8. Critical Structural Elements: \_\_\_\_\_

A.	<u>Identification</u>	<u>Location</u>	Governing Load or Response	Seismic	Total	Stress
			Combination	Stress	Stress	Allowable
	Upper Seismic Lug Bolts 1 1/2" Ø SA-325	Elevation 14' 9 1/8"	Seismic + Deadweight + Nozzle loads + Pressure	***	13911 psi (shear)	15390 psi (shear)

\*\*\* Included in Total

B.	<u>Max. Deflection</u>	<u>Location</u>	Effect Upon Functional Operability
	NA		