

ENCLOSURE 3

H. B. ROBINSON STEAM ELECTRIC PLANT, UNIT NO. 2
NRC DOCKET NO. 50-261
OPERATING LICENSE DPR-23
REQUEST FOR LICENSE AMENDMENT
REACTOR TRIP SYSTEM LOGIC

TECHNICAL SPECIFICATION PAGES

9006010240 900525
PDR ADCK 05000261
P PDC

TABLE 4.1-1 (Continued)

<u>Channel Description</u>	<u>Check</u>	<u>Calibrate</u>	<u>Test</u>	<u>Remarks</u>
21. Containment Sump Level	N.A.	R	N.A.	
22. Turbine Trip Logic**	N.A.	N.A.	R	
23. Accumulator Level and Pressure	S	R	N.A.	
24. Steam Generator Pressure	S	R	M	
25. Turbine First Stage Pressure	S	R	M	
26. DELETED				
27. Logic Channel Testing	N.A.	N.A.	M(1) S/U(2)	(1) During hot shutdown and power operations. When periods of reactor cold shutdown and refueling extend this interval beyond one month, this test shall be performed prior to startup. (2) Logic channel testing for nuclear source range channels shall only be required prior to each reactor startup, if not performed within the previous seven (7) days.
28. Turbine Overspeed Protection Trip Channel (Electrical)	N.A.	R	M	
29. 4 Kv Frequency	N.A.	R	R	

** Stop valve closure or low EH fluid pressure.

TABLE 4.1-1 (Continued)

<u>Channel Description</u>	<u>Check</u>	<u>Calibrate</u>	<u>Test</u>	<u>Remarks</u>
30. Reactor Trip Breakers	N.A.	N.A.	M(1)	(1) The reactor trip breaker trip actuating device operational test shall verify the operability of the UV trip attachment and the shunt trip attachment, individually.
31. Overpressure Protection System	N.A.	R	M	