



Entergy Nuclear Northeast
Indian Point Energy Center
450 Broadway, GSB
P.O. Box 249
Buchanan, NY 10511-024
Tel 914 254 6700

Lawrence Coyle
Site Vice President

NL-15-081

June 25, 2015

U.S. Nuclear Regulatory Commission
ATTN: Document Control Desk
11545 Rockville Pike, TWFN-2F1
Rockville, MD 20852-2738

SUBJECT: Additional Information Regarding Entergy's Expedited Seismic Evaluation Process Report (CEUS Sites), Response to NRC Request for Information Pursuant to 10 CFR 50.54(f) Regarding Recommendation 2.1 of the Near-Term Task Force Review of Insights from the Fukushima Dai-ichi Accident
Indian Point Unit Number 3
Docket No. 50-286
License No. DPR-64

REFERENCES: 1. Entergy Letter (NL-14-152) to NRC regarding "Entergy's Expedited Seismic Evaluation Process Report (CEUS Sites), Response to NRC Request for Information Pursuant to 10 CFR 50.54(f) Regarding Recommendation 2.1 of the Near-Term Task Force Review of Insights from the Fukushima Dai-ichi Accident", dated December 22, 2014

Dear Sir / Madam:

On December 22, 2014, Entergy issued Reference 1 in response to the Nuclear Regulatory Commission (NRC) request for each Licensee located in the Central and Eastern United States (CEUS) to submit a Seismic Hazard Evaluation and Screening Report. The purpose of this letter is to update the Seismic Hazard Evaluation and Screening Report (enclosure) to address commitments made for Indian Point 3 (IP3) in Reference 1 as follows:

- Entergy will perform seismic walkdowns at IP3 for inaccessible items listed in Section 7.1. Status – Complete as discussed in the enclosure, Section 7.1
- Entergy will generate HCLPF calculations for IP3 inaccessible items listed in Section 7.1. Status – Complete with HCLPF screening (identified by note 3) in Appendix B of the enclosure.
- Entergy will implement any necessary IP3 modifications for inaccessible items listed in Section 7.1 based on the schedule commitment to complete this activity in NL-13-069 dated April 29, 2013 - Complete with no new modifications required per calculations in Appendix B.

AD10
NRR


dated April 29, 2013 - Complete with no new modifications required per calculations in Appendix B.

- Entergy will modify the IP3 Fire Water Storage Tanks (FWSTs) 31 and 32 and anchorages so that HCLPF > RLGM on the schedule commitment to complete this activity in NL-13-069 dated April 29, 2013 – In process and on schedule.
- Entergy will submit a letter to NRC summarizing the IP3 HCLPF results and confirming implementation of the plant modifications associated with the IP3 commitments to complete modifications for inaccessible items and modifications of the FWSTs 31 and 32 - In process with this letter closing all commitments except for FWSTs 31 and 32. A letter will be issued when they are complete in accordance with this commitment.

This letter contains no new regulatory commitments. If you have any questions regarding this report, please contact Mr. Robert Walpole, Manager, Regulatory Assurance at (914) 254-6710.

I declare under penalty of perjury that the foregoing is true and correct. Executed on June 25, 2015

Respectfully,


LC/sp

Enclosure: Expedited Seismic Evaluation Process Report for Indian Point Unit 3
– 51-9230673-002

Attachment: List of Regulatory Commitments

cc: Mr. Douglas Pickett, Senior Project Manager, NRC NRR DORL
Mr. John Boska, Senior Project Manager, NRC NRR DJLL
Mr. Daniel H. Dorman, Regional Administrator, NRC Region 1
NRC Resident Inspector
Mr. John B. Rhodes, President and CEO, NYSERDA
Ms. Bridget Frymire, New York State Dept. of Public Service

ENCLOSURE TO NL-15-081

EXPEDITED SEISMIC EVALUATION PROCESS

REPORT FOR INDIAN POINT UNIT 3

-51-9230673-002

ENTERGY NUCLEAR OPERATIONS, INC.
INDIAN POINT NUCLEAR GENERATING UNIT NO. 3
DOCKET NO. 50-286

Engineering Report No. IP-RPT-14-00038 Rev 1
Page 1 of 65



ENTERGY NUCLEAR
Engineering Report Cover Sheet

Engineering Report Title:
Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

Engineering Report Type:

New ☐ Revision ☒ Cancelled ☐ Superseded ☐
Superseded by: _____

Applicable Site(s)

IP1 ☐ IP2 ☐ IP3 ☒ JAF ☐ PNPS ☐ VY ☐ WPO ☐
ANO1 ☐ ANO2 ☐ ECH ☐ GGNS ☐ RBS ☐ WF3 ☐ PLP ☐

EC No. 58094

Report Origin: ☐ Entergy ☒ Vendor
Vendor Document No.: 51-9230673-002

Quality-Related: ☐ Yes ☒ No

Prepared by: Areva Date: 6/1/15
Responsible Engineer (Print Name/Sign)

Design Verified: N/A Date: _____
Design Verifier (if required) (Print Name/Sign)

Reviewed by: Frank Madero Date: 6/25/15
Reviewer (Print Name/Sign)

Approved by: Richard Drake Date: 6/25/15
Supervisor / Manager (Print Name/Sign)



AREVA Inc.

Engineering Information Record

Document No.: 51 - 9230673 - 002

Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit

3



20004-021 (01/30/2014)

Document No.: 51-9230673-002

Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

Safety Related? ☐ YES ☒ NODoes this document establish design or technical requirements? ☐ YES ☒ NODoes this document contain assumptions requiring verification? ☐ YES ☒ NODoes this document contain Customer Required Format? ☒ YES ☐ NO

Signature Block

Name and Title/Discipline	Signature	P/LP, R/LR, A-CRF, A	Date	Pages/Sections Prepared/Reviewed/ Approved or Comments
Bijan Mahnoori Project Engineer II	<i>Bijan Mahnoori</i>	P	5/29/15	All Revision 002, see Record of Revision for details.
Mark Stewart Principal Engineer	<i>Mark Stewart</i>	R	5-29-15	All Revision 002, see Record of Revision for details.
Kevin Connell Engineering Manager	<i>K Connell</i>	A	6/1/15	All Revision 002, see Record of Revision for details.

Note: P/LP designates Preparer (P), Lead Preparer (LP).

R/LR designates Reviewer (R), Lead Reviewer (LR)

A-CRF designates Project Manager Approver of Customer Required Format (A-CRF)

A designates Approver/RTM - Verification of Reviewer Independence

Project Manager Approval of Customer References (N/A if not applicable)

Name (printed or typed)	Title (printed or typed)	Signature	Date
Mike Terrell	Project Manager	<i>M Terrell</i>	6/3/15



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

Record of Revision

Revision No.	Pages/Sections/ Paragraphs Changed	Brief Description / Change Authorization
000	All	Initial release
001	Section 2.0 Appendix A – Section 2.0, 3.0, 3.1, 3.1.3, 4.2, 5.1, 6.0, 6.1, 6.2, 6.3.3, 6.4, 6.5, 7.1, 7.2, 8.1, 8.2, 8.3, 8.4, 9.0, Attachment A, and Attachment B	Section 2.0 <ul style="list-style-type: none"> References were added due to additional components based on new revision of supporting document. Appendix A <ul style="list-style-type: none"> Section 2.0, 3.0, 3.1, 3.1.3, 4.2, 5.1, 6.0, 6.1, 6.2, 6.3.3, 6.4, 6.5, 7.1, 7.2, 8.1, 8.2, 8.3, and 8.4 were modified to incorporate Entergy Comments [84] on Revision 0 of the document and updated with additional components based on new revision of supporting document. Attachment A - modified to incorporate Entergy Comments [84] and to update with additional components based on new revision of supporting document. Attachment B – modified to incorporate Entergy Comments [84] and to update with additional components based on new revision of supporting document.
002	Section 2.0 Appendix A – Section 5.2, 6.2, 6.3.3, 6.4, 6.6, 7.1, 7.2, 8.4, 9.0, Attachment A, and Attachment B	Section 2.0 <ul style="list-style-type: none"> Updated the revision level for References 79a and 80. Added Reference 79h. Appendix A <ul style="list-style-type: none"> Section 5.2 updated to address CR 2015-3376. Section 6.2 was updated to reflect the removal of a duplicate component. Section 6.3.3 & 6.4 were modified to include the components identified during the inaccessible components walkdown as requiring HCLPF evaluation. Section 6.6 was modified to address the conclusions of HCLPF evaluations to address CR 2015-3376. Section 7.1 was updated to remove a duplicate component. Also to include the information on the walkdowns of the inaccessible components that were performed during the 3R18 outage (March 2015). Section 7.2 was updated t results of inaccessible walkdowns Section 8.4 updated for results of inaccessible walkdowns Section 9.0 was modified to update the revision level for References 79a, and also added Reference 79h. Attachment A - Revised to reflect the removal of the duplicate component from the ESEL. Attachment B - Revised to reflect the the removal of the duplicate component and to include results of the walkdowns for the inaccessible components.



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

Table of Contents

	Page
SIGNATURE BLOCK.....	2
RECORD OF REVISION	3
1.0 DOCUMENTATION.....	5
2.0 REFERENCES.....	5
APPENDIX A : EXPEDITED SEISMIC EVALUATION PROCESS (ESEP) REPORT FOR INDIAN POINT UNIT 3.....	A-1



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

1.0 DOCUMENTATION

This document contains the Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3. This document is located in Appendix A and is presented in the customer requested format.

2.0 REFERENCES

References identified with an (*) are maintained within Indian Point Unit 3 Records System and are not retrievable from AREVA Records Management. These are acceptable references per AREVA Administrative Procedure 0402-01, Attachment 8. See page 2 for Project Manager Approval of customer references.

1. NRC (E Leeds and M Johnson) Letter to All Power Reactor Licensees et al., "Request for Information Pursuant to Title 10 of the Code of Federal Regulations 50.54(f) Regarding Recommendations 2.1, 2.3 and 9.3 of the Near-Term Task Force Review of Insights from the Fukushima Dai-Ichi Accident," March 12, 2012.
2. EPRI 3002000704, "Seismic Evaluation Guidance, Augmented Approach for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic," May 2013.
3. Entergy Letter to U.S. NRC, letter number NL-13-042 "Overall Integrated Plan in Response to March 12, 2012, Commission Order to Modify Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events (Order Number EA-12-049)," February 28, 2013, NRC ADAMS Accession No. ML13079A348.
4. Entergy Letter to U.S. NRC, letter number NL-14-031, "Indian Point Energy Center's Second Six-Month Status Report for the Implementation of Order EA-12-049 Modifying Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events," February 27, 2014, NRC ADAMS Accession No. ML14070A365.
5. Entergy Letter to U.S. NRC, letter number NL-14-110, "Indian Point Energy Center's Third Six-Month Status Report for the Implementation of Order EA-12-049 Modifying Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events," August 27, 2014, NRC ADAMS Accession No. ML14251A227.
6. *Entergy Engineering Evaluation, EC No. 45874, Revision 1, "FLEX-Beyond Design Basis External Event Phases I, II, and III Strategy Development Evaluation."
7. *Entergy Drawing 9321-F-20173, Revision 72, "Flow Diagram Main Steam."
8. *Entergy System Design Description 21.2, Revision 8, "System Description 21.2, Auxiliary Feedwater System."
9. *Entergy Drawing 9321-F-70313, Revision 17, "Auxiliary Boiler Feed Pump Room Instrument Piping Sheet No.1 Instrumentation."
10. *Entergy Drawing 9321-F-27233, Revision 40, "Flow Diagram Nitrogen to Nuclear Equipment."
11. *Entergy Plant Equipment Database for IP3.
12. *Entergy Drawing 9321-F-20193, Revision 62, "Flow Diagram Boiler Feedwater."
13. *Entergy Drawing 9321-LD-72123, Sheet 9, Revision 2, "Aux. F.W. Flow to Steam Generator #31 Loop F-1200 Diagram."
14. *Entergy Drawing 9321-LD-72123, Sheet 10 Revision 2, "Aux. F.W. Flow to Steam Generator #32 Loop F-1201 Diagram."



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

15. *Entergy Drawing 9321-LD-72123, Sheet 11, Revision 2, "Aux. F.W. Flow to Steam Generator #33 Loop F-1202 Diagram."
16. *Entergy Drawing 9321-LD-72123, Sheet 12, Revision 2, "Aux. F.W. Flow to Steam Generator #34 Loop F-1203 Diagram."
17. *Entergy Drawing 9321-F-31673, Revision 28, "Wiring Diagram 480V Switchgear Miscellaneous."
18. *Entergy Drawing 9321-F-70033, Revision 17, "Transmitter Racks Piping Arrangement – Sheet No. 2 Instrumentation for Indian Point Energy Center Unit No. 3."
19. *Entergy System Design Description 21.1, Revision 4, "System Description 21.1, Steam Generator Water Level Control."
20. *Entergy Drawing 9321-F-70253, Revision 10, "Primary Plant Instrument Piping & Supports – Sheet No. 1 Instrumentation."
21. *Entergy Drawing 9321-H-39903 Sheet 70, Revision 5, "Rack D-9 Layout."
22. *Entergy Drawing 9321-F-32273, Revision 41, "Wiring Diagram Supervisory Control Panel SC."
23. *Entergy Drawing 9321-F-70513, Revision 17, "Transmitter Racks Piping Arrangement – Sheet No. 4 Instrumentation."
24. *Entergy Drawing 9321-F-10023, Revision 22, "Plot Plan."
25. *Entergy Drawing 9321-F-20183 Sheet 1, Revision 63, "Flow Diagram Condensate & Boiler Feed Pump Suction."
26. *Entergy Drawing 9321-F-27353, Revision 42, "Flow Diagram Safety Injection System Sheet No. 1."
27. *Entergy System Design Description 10.1, Revision 10, "System Description 10.1, Safety Injection System."
28. *Entergy System Design Description 3.0, Revision 8, "System Description 3.0, Chemical and Volume Control System."
29. *Entergy System Design Description 4.2, Revision 7, "System Description 4.2, Residual Heat Removal System."
30. *Entergy System Design Description 1.4, Revision 7, "System Description 1.4, Pressurizer & Pressurizer Relief Tank."
31. *Entergy Drawing 9321-F-33853, Revision 19, "Electrical Distribution & Transmission System."
32. *Entergy Drawing 9321-F-30063 Sheet 1, Revision 81, "Single Line Diagram 480V Motor Control Center No.'s 36A, 36B & 36C."
33. *Entergy Drawing 9321-F-27363, Revision 52, Flow Diagram Chemical & Volume Control System Sheet No. 1."
34. *Entergy Drawing 9321-F-27513 Sheet 1, Revision 31, "Flow Diagram Auxiliary Coolant System In PAB & FSB Sheet No. 1."
35. *Entergy Drawing 9321-F-27503, Revision 55, "Flow Diagram Safety Injection System Sheet No. 2."



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

36. *Entergy Drawing 9321-F-27203, Revision 29, "Flow Diagram Auxiliary Coolant System Inside Containment."
37. *Entergy Drawing 9321-F-27473, Revision 43, "Flow Diagram Reactor Coolant System Sheet No. 2."
38. *Entergy Drawing 9321-F-36383, Revision 4, "Miscellaneous Wiring Details RCS-SOV-652, RCS-SOV-653, RCS-SOV-654, & RCS-SOV-655."
39. *Entergy Drawing 9321-F-30053, Revision 72, "Single Line Diagram 480V Motor Control Centers 37, 38, 39, & 311."
40. *Entergy Drawing 9321-F-30083, Revision 60, "Single Line Diagram D.C. System."
41. *Entergy Drawing IP3V-0454-0041, Revision 1, Structural Detail for Seismic Category 1 Instrument Rack."
42. *Entergy Calculation IP-CALC-07-00154, Revision 0, "Containment Atmospheric Temperature."
43. *Entergy Drawing 9321-F-33433, Revision 7, "Containment Parameters System Wiring Diagram."
44. *Entergy Drawing 9321-H-39913 Sheet 8, Revision 8, "External Connection Diagram R.P.S. Rack No. 8 (A-7)."
45. *Entergy Drawing 9321-H-36723, Revision 0, "Cover Plates on Flight Pnl. "FCF" & Supervisory Pnl. "SCF" – Fabrication Mounting Details."
46. *Entergy Drawing 9321-F-20303, Revision 30, "Flow Diagram Fuel Oil to Diesel Generators."
47. *Entergy Drawing 9321-F-39893, Revision 43, "Single Line Diagram 118VAC Instrument Buses 31, 31A, 32, 32A, 33, 33A, 34, & 34A."
48. *Entergy Document IP3-RPT-UNSPEC-02182, Indian Point Three Nuclear Power Plant Individual Plant Examination of External Events," September 1997.
49. *Entergy Drawing 9321-F-32723, Revision 28, Wiring Diagram Flight Control Pnl. FCF & FCR."
50. *Entergy Drawing 9321-LD-72453 Sheet 21A, Revision 2, "Overpressurization System Channel 1 Loop P/T-413 Diagram."
51. *Entergy Drawing 9321-LD-72453 Sheet 23A, Revision 2, "Overpressurization System Channel 4 Loop P/T-443 Diagram."
52. *Entergy Drawing 9321-LD-72453 Sheet 21, Revision 3, "Overpressurization System Channel 1 Loop P/T-413 Diagram."
53. *Entergy Drawing 9321-LD-72453 Sheet 23, Revision 3, "Overpressurization System Channel 4 Loop P/T-443 Diagram."
54. *Entergy Drawing 9321-F-27383, Revision 28, "Flow Diagram Reactor Coolant System Sheet No. 1."
55. *Entergy Drawing 9321-LL-36853, Sheet 1, Revision 3, "Schematic Block Diagram Reactor Vessel Level Instrument System Train "A"."
56. *Entergy Drawing 9321-F-33203, Sheet 1, Revision 24, "Conduit & Tray Connection Schematic Containment Building."



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

57. *Entergy Drawing 9321-F-33313, Sheet 2, Revision 6, "Conduit & Tray Connection Schematic Fan House."
58. *Entergy Drawing 9321-F-30793, Revision 50, "Conduit Layout Containment Building Piping Penetration Area – Fan House."
59. *Entergy Drawing 9321-F-72043, Revision 7, "Containment Building Reactor Vessel Level Instrumentation System Flow Diagram."
60. *Entergy Drawing 9321-F-70283, Revision 25, Containment Building Instrument Arrangement Sheet No. 2 Instrumentation."
61. *Entergy Drawing 9321-F-39933, Revision 19 "Conduit Layout TSI Room, CFM Multiplexer Room, Control Building EL. 53'-0" & Roof El. 72'-7."
62. *Entergy Drawing 9321-F-95273 Sheet 1, Revision 6, "Control Room RVLIS Rack – Train "A" Interconnection Wiring Diagram."
63. *Entergy Procedure 3-ECA-0.0, Revision 9, "Loss of All AC Power."
64. *Entergy Drawing 9321-F-32383, Revision 31, "Wiring Diagram Supervisory Control Panel SB2."
65. *Entergy System Design Description 1.1, Revision 5, "System Description 1.1, Reactor Coolant System."
66. *Entergy Drawing IP3V-0245-0001, Revision 0, "40'-0" OD x 40'-0" High Fire Protection Water Storage Tanks "FP-Tk-1" & "FP-Tk-2" Pipe Support Details."
67. *Entergy System Design Description 18.0, Revision 7, "System Description 18.0, Main and Reheat Steam."
68. EPRI 1025287, "Seismic Evaluation Guidance: Screening, Prioritization and Implementation Details (SPID) for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic. Electric Power Research Institute," February 2013.
69. Entergy Letter NL-14-043, John A. Ventosa to NRC, "Entergy Seismic Hazard and Screening Report (CEUS Sites), Response to NRC Request for Information Pursuant to 10 CFR 50.54(f) Regarding Recommendation 2.1 of the Near-Term Task Force Review of Insights from the Fukushima Dai-ichi Accident dated March 31, 2014." NRC ADAMS Accession No. ML14099A111.
70. *"Indian Point Energy Center Unit 3 Updated Final Safety Analysis Report," Revision 5, Docket No. 50-286, 2013.
71. EPRI-NP-6041-SL, "Methodology for Assessment of Nuclear Power Plant Seismic Margin," Revision 1, August 1991.
72. EPRI TR-103959, "Methodology for Developing Seismic Fragilities," July 1994.
73. NRC NUREG-1407, "Procedural and Submittal Guidance for the Individual Plant Examination of External Events (IPEEE) for Severe Accident Vulnerabilities," June 1991.
74. SQUG, "Generic Implementation Procedure (GIP) for Seismic Verification of Nuclear Plant Equipment, Seismic Qualification Utility Group," Revision 3A, December 2001.
75. NRC (E. Leeds) Letter to All Power Reactor Licensees et al., "Screening and Prioritization Results Regarding Information Pursuant to Title 10 of the Code of Federal Regulations 50.54(F)



Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

Regarding Seismic Hazard Re-Evaluations for Recommendation 2.1 of the Near-Term Task Force Review of Insights From the Fukushima Dai-Ichi Accident," May 9, 2014.

76. Nuclear Energy Institute (NEI), A. Pietrangelo, Letter to D. Skeen of the USNRC, "Seismic Core Damage Risk Estimates Using the Updated Seismic Hazards for the Operating Nuclear Plants in the Central and Eastern United States," March 12, 2014.
77. Nuclear Energy Institute (NEI), A. Pietrangelo, Letter to D. Skeen of the USNRC, "Proposed Path Forward for NTTF Recommendation 2.1: Seismic Reevaluations," April 9, 2013, NRC ADAMS Accession No. ML13101A379.
78. NRC (E Leeds) Letter to NEI (J Pollock), "Electric Power Research Institute Final Draft Report xxxxx, "Seismic Evaluation Guidance: Augmented Approach for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic," as an Acceptable Alternative to the March 12, 2012, Information Request for Seismic Reevaluations," May 7, 2013.
79. *Entergy Document EC54071, "ESEP Reports," the following AREVA documents are captured in the plant document management system:
 - a. AREVA Document 51-9212951-007, "ESEP Expedited Seismic Equipment List (ESEL) – Indian Point Unit 3."
 - b. AREVA Calculation 32-9227208-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Station Service Transformers 2, 3, 5, and 6."
 - c. AREVA Calculation 32-9227381-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Battery Bank 33 (BATT 33)."
 - d. AREVA Calculation 32-9227576-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Battery Chargers 31, 32, & 34."
 - e. AREVA Calculation 32-9230353-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Refueling Water Storage Tank, RWST-31."
 - f. AREVA Calculation 32-9230692-000, "Indian Point Unit 3 ESEP HCLPF Calculation – RCS Overpressure Racks H-1 and H-3."
 - g. AREVA Document 32-9232897-000, "Indian Point Unit 3 ESEP Calculation – Fire Water Storage Tanks FP-T-1 and FP-T-2."
 - h. AREVA Calculation 32-9238938-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Residual Heat Exchangers ACAHRS1 and ACAHRS2."

The following references are AREVA references which were used as input for Appendix A.

80. AREVA Calculation 32-9224585-003, "Indian Point Unit 3 ESEP Binning and Screening."
81. AREVA Document 51-9230419-001, "Input to Entergy ESEP Report Sections 2 and 3 for Indian Point 3."
82. AREVA Document 51-9227403-000, "Input to Entergy ESEP Report Sections 4 and 5 for Indian Point Unit 3."
83. AREVA Document 51-9230505-000, "Input to Entergy ESEP Report Sections 6, 7, and 8 for Indian Point Unit 3."
84. AREVA Document 38-9232223-000, "Indian Point Unit 3 ESEP Report Comment Resolution Form."

For Information Only



Document No.: 51-9230673-002

Expedited Seismic Evaluation Process (ESEP) Report for Indian Point Unit 3

APPENDIX A: EXPEDITED SEISMIC EVALUATION PROCESS (ESEP) REPORT FOR INDIAN POINT UNIT 3

Note: Customer requested formatting begins on the following page.

For Information Only

**EXPEDITED SEISMIC EVALUATION
PROCESS (ESEP) REPORT FOR INDIAN POINT UNIT
3 (IP3)**

Table of Contents

	Page
LIST OF TABLES.....	4
LIST OF FIGURES.....	5
1.0 PURPOSE AND OBJECTIVE.....	6
2.0 BRIEF SUMMARY OF THE FLEX SEISMIC IMPLEMENTATION STRATEGIES.....	6
3.0 EQUIPMENT SELECTION PROCESS AND ESEL.....	7
3.1 Equipment Selection Process and ESEL	8
3.1.1 ESEL Development	9
3.1.2 Power Operated Valves	9
3.1.3 Pull Boxes	10
3.1.4 Termination Cabinets.....	10
3.1.5 Critical Instrumentation Indicators.....	10
3.1.6 Phase 2 and 3 Piping Connections	10
3.2 Justification for Use of Equipment That is Not the Primary Means for FLEX Implementation	10
4.0 GROUND MOTION RESPONSE SPECTRUM (GMRS)	10
4.1 Plot of GMRS Submitted by the Licensee	10
4.2 Comparison to SSE	12
5.0 REVIEW LEVEL GROUND MOTION (RLGM)	14
5.1 Description of RLGM Selected	14
5.2 Method to Estimate In-Structure Response Spectra (ISRS).....	16
6.0 SEISMIC MARGIN EVALUATION APPROACH	16
6.1 Summary of Methodologies Used	17
6.2 HCLPF Screening Process	17
6.3 Seismic Walkdown Approach	18
6.3.1 Walkdown Approach	18
6.3.2 Application of Previous Walkdown Information	19
6.3.3 Significant Walkdown Findings	19
6.4 HCLPF Calculation Process	19
6.5 Functional Evaluations of Relays	20
6.6 Tabulated ESEL HCLPF Values (Including Key Failure Modes)	20
7.0 INACCESSIBLE ITEMS.....	21
7.1 Identification of ESEL Item Inaccessible for Walkdowns	21
7.2 Planned Walkdown / Evaluation Schedule / Close Out	21
8.0 ESEP CONCLUSIONS AND RESULTS	21
8.1 Supporting Information	21

Table of Contents
(continued)

	Page
8.2 Identification of Planned Modifications	23
8.3 Modification Implementation Schedule	23
8.4 Summary of Regulatory Commitments	23
9.0 REFERENCES	24
ATTACHMENT A – INDIAN POINT UNIT 3 ESEL	A-1
ATTACHMENT B – ESEP HCLPF VALUES AND FAILURE MODES TABULATION	B-1

List of Tables

	Page
TABLE 4-1: GMRS FOR INDIAN POINT UNIT 3	11
TABLE 4-2: SSE FOR INDIAN POINT UNIT 3	13
TABLE 5-1: RLGM FOR INDIAN POINT UNIT 3	14

List of Figures

	Page
FIGURE 4-1: GMRS FOR INDIAN POINT UNIT 3	12
FIGURE 4-2: GMRS TO SSE COMPARISON FOR INDIAN POINT UNIT 3	13
FIGURE 5-1: RLGM FOR INDIAN POINT UNIT 3	16

1.0 PURPOSE AND OBJECTIVE

Following the accident at the Fukushima Dai-ichi nuclear power plant resulting from the March 11, 2011, Great Tohoku Earthquake and subsequent tsunami, the Nuclear Regulatory Commission (NRC) established a Near-Term Task Force (NTTF) to conduct a systematic review of NRC processes and regulations and to determine if the agency should make additional improvements to its regulatory system. The NTTF developed a set of recommendations intended to clarify and strengthen the regulatory framework for protection against natural phenomena. Subsequently, the NRC issued a 50.54(f) letter on March 12, 2012 [1], requesting information to assure that these recommendations are addressed by all U.S. nuclear power plants. The 50.54(f) letter requests that licensees and holders of construction permits under 10 CFR Part 50 reevaluate the seismic hazards at their sites against present-day NRC requirements and guidance. Depending on the comparison between the reevaluated seismic hazard and the current design basis, further risk assessment may be required. Assessment approaches acceptable to the staff include a seismic probabilistic risk assessment (SPRA), or a seismic margin assessment (SMA). Based upon the assessment results, the NRC staff will determine whether additional regulatory actions are necessary.

This report describes the Expedited Seismic Evaluation Process (ESEP) undertaken for Indian Point Unit 3. The intent of the ESEP is to perform an interim action in response to the NRC's 50.54(f) letter to demonstrate seismic margin through a review of a subset of the plant equipment that can be relied upon to protect the reactor core following beyond design basis seismic events.

The ESEP is implemented using the methodologies in the NRC endorsed guidance in Electric Power Research Institute (EPRI) 3002000704, Seismic Evaluation Guidance: Augmented Approach for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic [2].

The objective of this report is to provide summary information describing the ESEP evaluations and results. The level of detail provided in the report is intended to enable the NRC to understand the inputs used, the evaluations performed, and the decisions made as a result of the interim evaluations.

2.0 BRIEF SUMMARY OF THE FLEX SEISMIC IMPLEMENTATION STRATEGIES

The Indian Point Unit 3 FLEX strategies for Reactor Core Cooling and Heat Removal, Reactor Inventory Control/Long Term Subcriticality, and Containment Function are summarized below. This summary is derived from the Indian Point Energy Center Overall Integrated Plan (OIP) in Response to the March 12, 2012, Commission Order EA-12-049 [3], and is consistent with the second and third six-month status reports [4][5] and supplemented by supporting FLEX engineering calculations [6].

Core Cooling and Heat Removal

The Phase 1 FLEX strategy at Indian Point Unit 3 for this function is to use Atmospheric Dump Valves (ADVs) and Main Steam Safety Valves (MSSVs) to remove heat, with the steam generator being fed by the turbine-driven Auxiliary Feedwater (AFW) pump. Suction for the AFW pump is from the Condensate Storage Tank (CST). Backup nitrogen cylinders are available to support cycling the ADVs.

During Phase 2 of the FLEX strategy, portable diesel-driven pumps will be staged to provide makeup to the CST or to the steam generator feedwater pump suction. The diesel-driven steam generator FLEX feed pump will be staged to provide feedwater to steam generators in the event that the turbine-driven AFW pump becomes unavailable. The Primary Water Storage Tank (PWST) or Fire Water Storage Tanks (FWSTs) will be used as makeup sources to the CST. Diesel fuel for FLEX equipment can be provided from existing onsite Emergency Diesel Generator (EDG) Fuel Oil Storage Tanks.

The key parameters to be monitored are: steam generator level, steam generator pressure, CST level, Reactor Coolant System (RCS) pressure, and RCS temperature.

RCS Inventory Control

For At Power modes

In Phase 1, plant cooldown and depressurization will occur. Inventory control is achieved via the accumulators.

During Phase 2, to avoid adverse effects on the RCS natural circulation flow, the cold-leg accumulator isolation valves are electrically closed during the cooldown to prevent nitrogen injection into the RCS. A FLEX pump will be used to provide RCS makeup with borated water supplied by the Refueling Water Storage Tank (RWST). To allow borated water injection into the RCS, the reactor head vent can be opened, if necessary, to provide a letdown path.

If the Extended Loss of AC Power (ELAP) event occurs during cold weather months when freezing of the RWST could possibly occur, a FLEX diesel generator can be used to repower the Electric Heat Trace (EHT) system.

For Shutdown modes

In Phase 1, if the refueling canal is full, RCS makeup will be supplied by gravity feed from the RWST.

During Phase 2, a FLEX pump will be used to provide RCS makeup from the RWST in the same manner as for the At Power modes.

Additional key parameters to be monitored are pressurizer level and reactor vessel level and nuclear instrumentation.

Containment Function

Containment function is not expected to be challenged during Phase 1 or Phase 2 for an ELAP event occurring when the plant is in Mode 1-4. Therefore, no FLEX strategy beyond monitoring containment pressure and temperature was developed to support containment function.

For Modes 5 and 6, containment pressure could be challenged unless a vent path is established. Methods to establish a vent path will be used and include: opening penetration UU, which is used during outages as an additional air supply, deflating the sealing ring of the equipment hatch (if installed), or another vent path identified and evaluated.

Supporting Systems

Necessary electrical components are outlined in the Indian Point Unit 3 OIP and primarily entail station batteries, Direct Current (DC) buses, distribution panels, inverters, battery chargers, and instrument buses.

3.0 EQUIPMENT SELECTION PROCESS AND ESEL

The selection of equipment for the Expedited Seismic Equipment List (ESEL) followed the guidelines of EPRI 3002000704 [2]. The ESEL for Indian Point Unit 3 is presented in Attachment A. Information presented in Attachment A is drawn from the following references [3], [4], [5], [6], [7], [8], [9], [10], [11], [12], [13], [14], [15], [16], [17], [18], [19], [20], [21], [22], [23], [24], [25], [26], [27], [28], [29], [30], [31], [32], [33], [34], [35], [36], [37], [38], [39], [40], [41], [42], [43], [44], [45], [46], [47], [48], [49], [50], [51], [52], [53], [54], [55], [56], [57], [58], [59], [60], [61], [62], [63], [64], [65], [66], and [67].

3.1 Equipment Selection Process and ESEL

The selection of equipment to be included on the ESEL was based on installed plant equipment credited in the FLEX strategies during Phase 1, 2 and 3 mitigation of a Beyond Design Basis External Event (BDBEE), as outlined in the Indian Point Unit 3 OIP in Response to the March 12, 2012, Commission Order EA-12-049 [3] and is consistent with the second and third six-month status report issued to the NRC [4][5]. The OIP provides the Indian Point Unit 3 FLEX mitigation strategy and serves as the basis for equipment selected for the ESEP.

The scope of "installed plant equipment" includes equipment relied upon for the FLEX strategies to sustain the critical functions of core cooling and containment integrity consistent with the Indian Point Unit 3 OIP. FLEX recovery actions are excluded from the ESEP scope per EPRI 3002000704 [2]. The overall list of planned FLEX modifications and the scope for consideration herein is limited to those required to support core cooling, reactor coolant inventory and subcriticality, and containment integrity functions. Portable and pre-staged FLEX equipment (not permanently installed) are excluded from the ESEL per EPRI 3002000704.

The ESEL component selection followed the EPRI guidance outlined in Section 3.2 of EPRI 3002000704.

1. The scope of components is limited to that required to accomplish the core cooling and containment safety functions identified in Table 3-2 of EPRI 3002000704. The instrumentation monitoring requirements for core cooling/containment safety functions are limited to those outlined in the EPRI 3002000704 guidance, and are a subset of those outlined in the Indian Point Unit 3 OIP.
2. The scope of components is limited to installed plant equipment, and FLEX connections necessary to implement the Indian Point Unit 3 OIP as described in Section 2 of this report.
3. The scope of components assumes the credited FLEX connection modifications are implemented, and are limited to those required to support a single FLEX success path (i.e., either "Primary" or "Back-up/Alternate").
4. The "Primary" FLEX success path is to be specified. Selection of the "Back-up/Alternate" FLEX success path must be justified.
5. Phase 3 coping strategies are included in the ESEP scope, whereas recovery strategies are excluded.
6. Structures, systems, and components excluded per the EPRI 3002000704 [2] guidance are:
 - Structures (e.g. containment, reactor building, control building, auxiliary building, etc.).
 - Piping, cabling, conduit, HVAC, and their supports.
 - Manual valves and rupture disks.
 - Power-operated valves not required to change state as part of the FLEX mitigation strategies.
 - Nuclear steam supply system components (e.g. RPV and internals, reactor coolant pumps and seals, etc.).
7. For cases in which neither train was specified as a primary or back-up strategy, then only one train component (generally 'A' train) is included in the ESEL.

3.1.1 ESEL Development

The ESEL was developed by reviewing the Indian Point OIP [3], second and third six-month status reports [4][5] to determine the major equipment involved in the FLEX strategies. Further reviews of plant drawings (e.g., Piping and Instrumentation Diagrams (P&IDs) and Electrical One Line Diagrams) were performed to identify the boundaries of the flow paths to be used in the FLEX strategies and to identify specific components in the flow paths needed to support implementation of the FLEX strategies. Boundaries were established at an electrical or mechanical isolation device (e.g., isolation amplifier, valve, etc.) in branch circuits / branch lines off the defined strategy electrical or fluid flow path. P&IDs were the primary reference documents used to identify mechanical components and instrumentation. The flow paths used for FLEX strategies were selected and specific components were identified using detailed equipment and instrument drawings, piping isometrics, electrical schematics and one-line drawings, system descriptions, design basis documents, as necessary.

Cabinets and equipment controls containing relays, contactors, switches, potentiometers, circuit breakers and other electrical and instrumentation that could be affected by high-frequency earthquake motions and that impact the operation of equipment in the ESEL are required to be on the ESEL. These cabinets and components were identified in the ESEL.

For each parameter monitored during the FLEX implementation, a single indication was selected for inclusion in the ESEL. For each parameter indication, the components along the flow path from measurement to indication were included, since any failure along the path would lead to failure of that indication. Components such as flow elements were considered as part of the piping and were not included in the ESEL.

3.1.2 Power Operated Valves

Page 3-3 of EPRI 3002000704 [2] notes that power operated valves not required to change state as part of the FLEX mitigation strategies are excluded from the ESEL. Page 3-2 also notes that “functional failure modes of electrical and mechanical portions of the installed Phase 1 equipment should be considered (e.g. AFW trips).” To address this concern, the following guidance is applied in the Indian Point Unit 3 ESEL for functional failure modes associated with power operated valves:

- Power operated valves that remain energized during the ELAP events (such as DC powered valves), were included on the ESEL.
- Power operated valves not required to change state as part of the FLEX mitigation strategies were not included on the ESEL. The seismic event also causes the ELAP event; therefore, the valves are incapable of spurious operation as they would be de-energized.
- Power operated valves not required to change state as part of the FLEX mitigation strategies during Phase 1, and are re-energized and operated during subsequent Phase 2 and 3 strategies, were not evaluated for spurious valve operation as the seismic event that caused the ELAP has passed before the valves are re-powered.

3.1.3 Pull Boxes

Pull boxes were deemed unnecessary to be added to the ESEL as these components provide completely passive locations for pulling or installing cables. No breaks or connections in the cabling were included in pull boxes. Pull boxes were considered part of conduit and cabling, which were excluded in accordance with EPRI 3002000704 [2].

3.1.4 Termination Cabinets

Termination cabinets, including cabinets necessary for FLEX Phase 2 and Phase 3 connections, provide consolidated locations for permanently connecting multiple cables. The termination cabinets and the internal connections provide a completely passive function; however, the cabinets are included in the ESEL to ensure industry knowledge on panel/anchorage failure vulnerabilities is addressed.

3.1.5 Critical Instrumentation Indicators

Critical indicators and recorders are typically physically located on panels/cabinets and are included as separate components; however, seismic evaluation of the instrument indication may be included in the panel/cabinet seismic evaluation (rule-of-the-box).

3.1.6 Phase 2 and 3 Piping Connections

Item 2 in Section 3.1 above notes that the scope of equipment in the ESEL includes "... FLEX connections necessary to implement the Indian Point Unit 3 OIP as described in Section 2." Item 3 in Section 3.1 also notes that "The scope of components assumes the credited FLEX connection modifications are implemented, and are limited to those required to support a single FLEX success path (i.e., either "Primary" or "Back-up/Alternate")."

Item 6 in Section 3.1 above goes on to explain that "Piping, cabling, conduit, HVAC, and their supports" are excluded from the ESEL scope in accordance with EPRI 3002000704 [2].

Therefore, piping and pipe supports associated with FLEX Phase 2 and Phase 3 connections are excluded from the scope of the ESEP evaluation. However, any active valves in FLEX Phase 2 and Phase 3 connection flow path are included in the ESEL.

3.2 Justification for Use of Equipment That is Not the Primary Means for FLEX Implementation

No equipment that was not part of the primary success path was selected for the Indian Point Unit 3 ESEL.

4.0 GROUND MOTION RESPONSE SPECTRUM (GMRS)

4.1 Plot of GMRS Submitted by the Licensee

In accordance with the guidance provided in Section 2.4.2 of the SPID [68] for rock sites, the Safe Shutdown Earthquake (SSE) control point elevation is defined at the top of hard-rock and is applicable at grade in the free field as well as the various foundations elevations [69]. Table 4-1 shows the GMRS acceleration for a range of spectral frequencies [69]. The GMRS at the control point is shown in Figure 4-1.

Table 4-1: GMRS for Indian Point Unit 3

Frequency (Hz)	GMRS (g)
100	4.12E-01
90	4.46E-01
80	5.04E-01
70	5.94E-01
60	7.04E-01
50	8.06E-01
45	8.42E-01
40	8.66E-01
35	8.77E-01
30	8.75E-01
25	8.58E-01
20	8.28E-01
15	7.67E-01
12.5	7.17E-01
10	6.48E-01
9	6.04E-01
8	5.55E-01
7	5.02E-01
6	4.46E-01
5	3.85E-01
4	3.14E-01
3	2.36E-01
2.5	1.94E-01
2	1.59E-01
1.5	1.17E-01
1.25	9.42E-02
1	7.04E-02
0.9	6.40E-02
0.8	5.71E-02
0.7	4.99E-02
0.6	4.25E-02
0.5	3.48E-02

Table 4-1: GMRS for Indian Point Unit 3 (continued)

Frequency (Hz)	GMRS (g)
0.4	2.78E-02
0.3	2.09E-02
0.2	1.39E-02
0.167	1.16E-02
0.125	8.69E-03
0.1	6.95E-03




Figure 4-1: GMRS for Indian Point Unit 3

4.2 Comparison to SSE

The SSE corresponds to a horizontal acceleration of 0.15g [70]. The SSE is defined in the Updated Final Safety Analysis Report [70] in terms of a Peak Ground Acceleration (PGA) and a design response spectrum. These spectra have been digitized and tabulated [69]. Table 4-2 shows the spectral acceleration values at selected frequencies for the 5% damped horizontal SSE.

Table 4-2: SSE for Indian Point Unit 3

Frequency (Hz)	Spectral Acceleration (g)
100	0.15
25	0.15
10	0.168
5	0.228
2.5	0.234
1	0.127
0.5	0.075

GMRS to SSE Comparison for Indian Point Unit 3, 5% Damping




Figure 4-2: GMRS to SSE Comparison for Indian Point Unit 3

The SSE envelops the GMRS for lower frequencies up to nearly 3 Hz. The GMRS exceeds the SSE beyond that point. As the GMRS exceeds the SSE in the 1 to 10 Hz range, the plant does not screen out of the ESEP according to Section 2.2 of EPRI 3002000704 [2]. The two special screening considerations as described in Section 2.2.1 of EPRI 3002000704, namely a) Low-frequency GMRS exceedances at Low Seismic Hazard Sites and b) Narrow Band Exceedances in the 1 to 10Hz range, provide criteria for accepting specific GMRS exceedances. However, the GMRS exceedances occur in the frequency range of interest and cannot be characterized as narrow-band exceedances. Therefore, these special screening considerations do not apply for Indian Point Unit 3 and High Confidence of a Low Probability of Failure (HCLPF) evaluations are to be performed.

5.0 REVIEW LEVEL GROUND MOTION (RLGM)

5.1 Description of RLGM Selected

The RLGM is selected based on Approach 1 in Section 4 of EPRI 3002000704 [2]. The RLGM is developed based on the SSE. The maximum GMRS/SSE ratio between 1 and 10 Hz range occurs at 10 Hz where the ratio is $0.648/0.168 = 3.86$. As the maximum ratio of the GMRS to the SSE over the 1 to 10 Hz range exceeds a value of 2, the GMRS/SSE ratio is set to the maximum scaling factor value of 2.0 for IP3 in accordance with Section 4 of EPRI 3002000704. Table 5-1 lists the horizontal ground RLGM acceleration at 5% damping at selected frequencies and the plot is shown in Figure 5-1. The RLGM is generated by plotting the digitized data on a log/linear graph paper, and connecting the points with straight lines.

Table 5-1: RLGM for Indian Point Unit 3

Frequency (Hz)	RLGM at 5% Damping (g)
100.00	0.30
33.00	0.30
15.78	0.31
13.65	0.31
12.20	0.32
10.09	0.34
8.43	0.36
7.23	0.38
6.55	0.40
5.89	0.43
5.34	0.44
4.94	0.46
4.59	0.47
4.17	0.48
3.83	0.49
3.67	0.49
3.41	0.50
3.15	0.49
2.89	0.49
2.65	0.48
2.55	0.47
2.24	0.45
2.02	0.42

Table 5-1: RLGM for Indian Point Unit 3 (continued)

Frequency (Hz)	RLGM at 5% Damping (g)
1.78	0.40
1.64	0.38
1.57	0.36
1.46	0.34
1.34	0.32
1.23	0.30
1.16	0.28
1.09	0.27
1.01	0.26
0.96	0.24
0.91	0.23
0.86	0.22
0.81	0.21
0.76	0.21
0.74	0.20
0.71	0.19
0.68	0.19
0.64	0.18
0.60	0.17
0.56	0.16
0.53	0.15
0.10	0.14




Figure 5-1: RLGM for Indian Point Unit 3

5.2 Method to Estimate In-Structure Response Spectra (ISRS)

The RLGM ISRS for Indian Point Unit 3 are generated by scaling the SSE ISRS [70]. The following steps are used to generate the RLGM ISRS.

1. Obtain the horizontal direction SSE ISRS for a particular damping value.
2. Calculate the horizontal RLGM ISRS by scaling the horizontal direction SSE ISRS by a factor of 2.0.
3. Repeat steps 1 and 2 to obtain RLGM ISRS for multiple damping values.

For each relevant floor elevation, the vertical direction RLGM ISRS is calculated as two thirds of the horizontal in-structure floor response.

6.0 SEISMIC MARGIN EVALUATION APPROACH

It is necessary to demonstrate that ESEL items have sufficient seismic capacity to meet or exceed the demand characterized by the RLGM. The seismic capacity is characterized as the PGA for which there is a HCLPF. The PGA is associated with a specific spectral shape, in this case the 5%-damped RLGM spectral shape. The HCLPF capacity must be equal to or greater than the RLGM PGA. The criteria for seismic capacity determination are given in Section 5 of EPRI 3002000704 [2].

There are two basic approaches for developing HCLPF capacities:

1. Deterministic approach using the conservative deterministic failure margin (CDFM) methodology of EPRI NP-6041-SL, A Methodology for Assessment of Nuclear Power Plant Seismic Margin (Revision 1) [71].

2. Probabilistic approach using the fragility analysis methodology of EPRI TR-103959, Methodology for Developing Seismic Fragilities [72].

6.1 Summary of Methodologies Used

Indian Point Unit 3 was classified as a 0.3g full scope plant in NUREG-1407 [73] and performed a SPRA as part of Individual Plant Examination for External Events (IPEEE) program. The SPRA is documented in [48]. Indian Point Unit 3 IPEEE program followed the NUREG-1407 methodology for seismic evaluation with plant seismic walkdowns using the EPRI NP-6041-SL [71] and Generic Implementation Procedure [74]. Walkdown efforts were coordinated for evaluations pertaining to the IPEEE and Unresolved Safety Issue (USI) A-46. Section 3.3 and Appendix B of [69] established that in accordance with the criteria established in SPID [68] Section 3.3, the IPEEE and reassessment of IHS are adequate to support screening of the updated seismic hazard for Indian Point Unit 3. Hence, the risk insights obtained from the IPEEE are used to assess risk for ESEP where applicable.

For ESEP, the evaluation consisted of screening walkdowns and HCLPF calculations. The screening walkdowns used the screening tables from Chapter 2 of EPRI NP-6041-SL. The walkdowns were conducted by engineers trained in EPRI NP-6041-SL and were documented on Screening Evaluation Work Sheets (SEWS) from EPRI NP-6041-SL. Anchorage capacity calculations used the CDFM criteria from EPRI NP-6041-SL. Seismic demand was based on EPRI 3002000704 [2] using an RLGM of 2×SSE with a PGA of 0.3g PGA as shown on Figure 5-1.

6.2 HCLPF Screening Process

For ESEP, the components are screened considering RLGM (2×SSE) with a 0.3g PGA. The screening tables in EPRI NP-6041-SL [71] are based on ground peak spectral accelerations of 0.8g and 1.2g. These both exceed the RLGM peak spectral acceleration.

The ESEL components were prescreened based on Table 2-4 of EPRI NP-6041-SL. Additional pre-screening, specifically for anchorage, considered walkdown results and documentation from NTTF 2.3 and SEWS from IPEEE and USI A-46. Equipment anchorage was screened out in cases where previous evaluations showed large available margin against SSE. The remaining components (i.e., components that do not screen out), were identified as requiring HCLPF calculations. ESEL components were walked down and based on the equipment and anchorage conditions, prescreening decisions were confirmed and a final list of required HCLPF calculations was generated. Equipment for which the screening caveats were met and for which the anchorage capacity exceeded the RLGM seismic demand are screened out from ESEP seismic capacity determination because the HCLPF capacity exceeds the RLGM.

The Indian Point Unit 3 ESEL contains 193 items. Of these, 30 are valves. In accordance with Table 2-4 of EPRI NP-6041-SL, valves may be assigned a functional capacity of 0.8g peak spectral acceleration without any review other than looking for valves with large extended operators on small diameter piping, and anchorage is not a failure mode. Therefore, valves on the ESEL are screened out from ESEP seismic capacity determination, subject to the caveat regarding large extended operators on small diameter piping.

6.3 Seismic Walkdown Approach

6.3.1 Walkdown Approach

Walkdowns were performed in accordance with the criteria provided in Section 5 of EPRI 3002000704 [2], which refers to EPRI NP-6041-SL [71] for the Seismic Margin Assessment process. Pages 2-26 through 2-30 of EPRI NP-6041-SL describe the seismic walkdown criteria, including the following key criteria.

"The SRT [Seismic Review Team] should "walk by" 100% of all components which are reasonably accessible and in non-radioactive or low radioactive environments. Seismic capability assessment of components which are inaccessible, in high-radioactive environments, or possibly within contaminated containment, will have to rely more on alternate means such as photographic inspection, more reliance on seismic reanalysis, and possibly, smaller inspection teams and more hurried inspections. A 100% "walk by" does not mean complete inspection of each component, nor does it mean requiring an electrician or other technician to de-energize and open cabinets or panels for detailed inspection of all components. This walkdown is not intended to be a QA or QC review or a review of the adequacy of the component at the SSE level.

If the SRT has a reasonable basis for assuming that the group of components are similar and are similarly anchored, then it is only necessary to inspect one component out of this group. The "similarity-basis" should be developed before the walkdown during the seismic capability preparatory work (Step 3) by reference to drawings, calculations or specifications. The one component or each type which is selected should be thoroughly inspected which probably does mean de-energizing and opening cabinets or panels for this very limited sample. Generally, a spare representative component can be found so as to enable the inspection to be performed while the plant is in operation. At least for the one component of each type which is selected, anchorage should be thoroughly inspected.

The walkdown procedure should be performed in an ad hoc manner. For each class of components the SRT should look closely at the first items and compare the field configurations with the construction drawings and/or specifications. If a one-to-one correspondence is found, then subsequent items do not have to be inspected in as great a detail. Ultimately the walkdown becomes a "walk by" of the component class as the SRT becomes confident that the construction pattern is typical. This procedure for inspection should be repeated for each component class; although, during the actual walkdown the SRT may be inspecting several classes of components in parallel. If serious exceptions to the drawings or questionable construction practices are found then the system or component class must be inspected in closer detail until the systematic deficiency is defined.

The 100% "walk by" is to look for outliers, lack of similarity, anchorage which is different from that shown on drawings or prescribed in criteria for that component, potential SI [Seismic Interaction] problems, situations that are at odds with the team members' past experience, and any other areas of serious seismic concern. If any such concerns surface, then the limited sample size of one component of each type for thorough inspection will have to be increased. The increase in sample size which should be inspected will depend upon the number of outliers and different anchorages, etc., which are observed. It is up to the SRT to ultimately select the sample size since they are the ones who are responsible for the seismic adequacy of all elements which they screen from the margin review. Appendix D gives guidance for sampling selection."

6.3.2 Application of Previous Walkdown Information

Several ESEL items were previously walked down during the Indian Point Unit 3 seismic IPEEE program, for seismic IPEEE outlier resolutions in accordance with USI A-46 evaluation program and NTTF Recommendation 2.3. Those walkdown results were reviewed and the following steps were taken to confirm that the previous walkdown conclusions remained valid.

- A walk by was performed to confirm that the equipment material condition and configuration is consistent with the walkdown conclusions and that no new significant interactions related to block walls or piping attached to tanks exist.
- If the ESEL item was screened out based on the previous walkdown, that screening evaluation was reviewed and reconfirmed for the ESEP.

6.3.3 Significant Walkdown Findings

Consistent with the guidance from EPRI NP-6041-SL [71], no significant outliers or anchorage concerns were identified during the Indian Point Unit 3 seismic walkdowns. Based on walkdown results, HCLPF capacity evaluations were recommended for the following fifteen (15) components:

- RWST-31, Refueling Water Storage Tank
- BATT CHGR 31, Battery Charger 31
- BATT CHGR 32, Battery Charger 32
- BATT CHGR 34, Battery Charger 34
- BATT 33, Battery Bank 33
- BUS2A, Bus 2A 480V
- BUS3A, Bus 3A 480V
- BUS5A, Bus 5A 480V
- BUS6A, Bus 6A 480V
- Rack H1, CCR Aux. Panel Analog Rack H1
- Rack H3, CCR Aux. Panel Analog Rack H3
- FP-T-1, 31 Fire Water Storage Tank
- FP-T-2, 32 Fire Water Storage Tank
- ACAHRS1, RHR HTEXCH # 31
- ACAHRS2, RHR HTEXCH # 32

6.4 HCLPF Calculation Process

ESEL items identified for ESEP at Indian Point Unit 3 were evaluated using the criteria in EPRI NP-6041-SL [71] and Section 5 of EPRI 3002000704 [2]. Those evaluations included the following steps:

- Performing seismic capability walkdowns for equipment not included in previous seismic walkdowns (SQUG, IPEEE, or NTTF 2.3) to evaluate the equipment installed plant conditions

- Performing screening evaluations using the screening tables in EPRI NP-6041-SL as described in Section 6.2
- Performing HCLPF calculations considering various failure modes that include both structural failure modes (e.g. anchorage, load path etc.) and functional failure modes

All HCLPF calculations were performed using the CDFM methodology. A total of Seven (7) HCLPF calculations were performed to address the fifteen (15) components.

- Calculation "Battery Chargers 31, 32, & 34" addressing three (3) components BATT CHGR 31, BATT CHGR 32 and BATT CHGR 34
- Calculation "Battery Bank 33" addressing a single component BATT 33
- Calculation "Refueling Water Storage Tank" addressing a single component RWST-31
- Calculation "Station Service Transformers 2, 3, 5, and 6" addressing transformers adjacent to our (4) components BUS2A, BUS3A, BUS5A and BUS6A
- Calculation "RCS Overpressure Racks H-1 and H-3" addressing two (2) instrument racks H1 and H3
- Calculation "Fire Water Storage Tanks FP-T-1 and FP-T-2" addressing two (2) components FP-T-1 and FP-T-2
- Calculation "Residual Heat Exchangers ACAHRS1 and ACAHRS2" addressing two (2) components ACAHRS1 and ACAHRS2

6.5 Functional Evaluations of Relays

No seal in/lockout type relays were identified on Indian Point Unit 3 ESEL. Therefore, no relay evaluations were performed.

6.6 Tabulated ESEL HCLPF Values (Including Key Failure Modes)

Tabulated ESEL HCLPF values are provided in Attachment B. The following notes apply to the information in the tables.

- For items screened out using EPRI NP-6041-SL [71] screening tables, the HCLPF capacity is provided as >RLGM and the failure mode is listed as "Screened", (unless the controlling HCLPF value is governed by anchorage).
- For items where anchorage controls the HCLPF value, the HCLPF value is listed in the table and the failure mode is noted as "anchorage." For the items where the component function controls the HCLPF value, the HCLPF value is listed in the table and the failure mode is noted as "functional."

After performing the HCLPF calculations, ESEL components were determined to have adequate capacity for the design basis loads and HCLPF greater than RLGM for all components except the following:

- FP-T-1, 31 Fire Water Storage Tank
- FP-T-2, 32 Fire Water Storage Tank

7.0 INACCESSIBLE ITEMS

7.1 Identification of ESEL Item Inaccessible for Walkdowns

Forty (41) components on the ESEL were previously identified as inaccessible and not walked down since they are located in the Primary Containment Building in a locked high radiation area. These items were walked down during 3R18 refueling outage in March 2015. During these walkdowns, two temperature elements were determined to be the same component. Thus the results for the remaining forty (40) components are now detailed in Attachment B.

Also, the two (2) Hydraulic Isolators, one (1) valve and one (1) Terminal Box listed below were not walked down due to the plant condition (inaccessible due to contamination/high radiation) at the time of the walkdowns. Subject components were evaluated based on the review of the recent photos of the components and the general area.

- LIS-1311, Hydraulic Isolator
- LIS-1312, Hydraulic Isolator
- MOV-882, RHR Pump Suction Isolation Valve
- Y29, Terminal Box

7.2 Planned Walkdown / Evaluation Schedule / Close Out

No follow up walkdowns are required.

8.0 ESEP CONCLUSIONS AND RESULTS

8.1 Supporting Information

Indian Point Unit 3 has performed the ESEP as an interim action in response to the NRC's 50.54(f) letter [1]. It was performed using the methodologies in the NRC endorsed guidance in EPRI 3002000704 [2].

The ESEP provides an important demonstration of seismic margin and expedites plant safety enhancements through evaluations and potential near-term modifications of plant equipment that can be relied upon to protect the reactor core following beyond design basis seismic events.

The ESEP is part of the overall Indian Point Unit 3 response to the NRC's 50.54(f) letter. On March 12, 2014, NEI submitted to the NRC results of a study [76] of seismic core damage risk estimates based on updated seismic hazard information as it applies to operating nuclear reactors in the Central and Eastern United States (CEUS). The study concluded that "site-specific seismic hazards show that there has not been an overall increase in seismic risk for the fleet of U.S. plants" based on the re-evaluated seismic hazards [69]. As such, the "current seismic design of operating reactors continues to provide a safety margin to withstand potential earthquakes exceeding the seismic design basis."

The NRC's May 9, 2014 NTTF 2.1 Screening and Prioritization letter [75] concluded that the "fleet wide seismic risk estimates are consistent with the approach and results used in the GI-199 safety/risk assessment." The letter also stated that "As a result, the staff has confirmed that the conclusions reached in GI-199 safety/risk assessment remain valid and that the plants can continue to operate while additional evaluations are conducted."

An assessment of the change in seismic risk for Indian Point Unit 3 was included in the fleet risk evaluation submitted in the March 12, 2014 NEI letter [76]; therefore, the conclusions in the NRC's May 9 letter also apply to Indian Point Unit 3.

In addition, the March 12, 2014 NEI letter provided an attached "Perspectives on the Seismic Capacity of Operating Plants," which (1) assessed a number of qualitative reasons why the design of Structures, Systems and Components (SSCs) inherently contain margin beyond their design level, (2) discussed industrial seismic experience databases of performance of industry facility components similar to nuclear SSCs, and (3) discussed earthquake experience at operating plants.

The fleet of currently operating nuclear power plants was designed using conservative practices, such that the plants have significant margin to withstand large ground motions safely. This has been borne out for those plants that have actually experienced significant earthquakes. The seismic design process has inherent (and intentional) conservatism which result in significant seismic margins within SSCs. These conservatisms are reflected in several key aspects of the seismic design process, including:

- Safety factors applied in design calculations
- Damping values used in dynamic analysis of SSCs
- Bounding synthetic time histories for in-structure response spectra calculations
- Broadening criteria for in-structure response spectra
- Response spectra enveloping criteria typically used in SSC analysis and testing applications
- Response spectra based frequency domain analysis rather than explicit time history based time domain analysis
- Bounding requirements in codes and standards
- Use of minimum strength requirements of structural components (concrete and steel)
- Bounding testing requirements
- Ductile behavior of the primary materials (that is, not crediting the additional capacity of materials such as steel and reinforced concrete beyond the essentially elastic range, etc.)

These design practices combine to result in margins such that the SSCs will continue to fulfill their functions at ground motions well above the SSE.

The intent of the ESEP is to perform an interim action in response to the NRC's 50.54(f) letter to demonstrate seismic margin through a review of a subset of the plant equipment that can be relied upon to protect the reactor core following beyond design basis seismic events. The RLGM used for the ESEP evaluation is a scaled version of the plant's SSE rather than the actual GMRS. To more fully characterize the risk impacts of the seismic ground motion represented by the GMRS on a plant specific basis, a more detailed seismic risk assessment (SPRA or risk-based SMA) is to be performed in accordance with EPRI 1025287 [68]. As identified in the Indian Point Unit 3 Seismic Hazard and GMRS submittal [69], Indian Point Unit 3 screens in for a risk evaluation. The complete risk evaluation will more completely characterize the probabilistic seismic ground motion input into the plant, the plant response to that probabilistic seismic ground motion input, and the resulting plant risk characterization. Indian Point Unit 3 will complete that evaluation in accordance with the schedule identified in NEI's letter dated April 9, 2013 [77] and endorsed by the NRC in their May 7, 2013 letter [78].

8.2 Identification of Planned Modifications

Insights from the ESEP identified the following items where the HCLPF is below the RLGM and plant modifications will be made in accordance with EPRI 3002000704 [2] to enhance the seismic capacity of the plant. Subject modifications are planned to provide additional seismic margin such that the HCLPF will exceed the RLGM.

- FP-T-1, 31 Fire Water Storage Tank
- FP-T-2, 32 Fire Water Storage Tank

8.3 Modification Implementation Schedule

Plant modifications described in Section 8.2 will be performed in accordance with the schedule identified in NEI letter dated April 9, 2013 [77], which states that plant modifications not requiring a planned refueling outage will be completed by December 2016 and modifications requiring a refueling outage will be completed within two planned refueling outages after December 31, 2014.

8.4 Summary of Regulatory Commitments

The following actions will be performed as a result of the ESEP.

Action #	Equipment ID	Equipment Description	Action Description	Completion Date
1	FP-T-1	31 Fire Water Storage Tank	Modify tank and anchorage such that HCLPF>RLGM	As described in Section 8.3
2	FP-T-2	32 Fire Water Storage Tank	Modify tank and anchorage such that HCLPF>RLGM	As described in Section 8.3
3	N/A	N/A	Submit a letter to NRC summarizing the HCLPF results of Items 1 and 2 confirming implementation of the plant modifications associated with items 1 and 2.	Within 60 days following completion of ESEP activities, including items 1 and 2.

9.0 REFERENCES

1. NRC (E Leeds and M Johnson) Letter to All Power Reactor Licensees et al., "Request for Information Pursuant to Title 10 of the Code of Federal Regulations 50.54(f) Regarding Recommendations 2.1, 2.3 and 9.3 of the Near-Term Task Force Review of Insights from the Fukushima Dai-Ichi Accident," March 12, 2012.
2. EPRI 3002000704, "Seismic Evaluation Guidance, Augmented Approach for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic," May 2013.
3. Entergy Letter to U.S. NRC, letter number NL-13-042 "Overall Integrated Plan in Response to March 12, 2012, Commission Order to Modify Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events (Order Number EA-12-049)," February 28, 2013, NRC ADAMS Accession No. ML13079A348.
4. Entergy Letter to U.S. NRC, letter number NL-14-031, "Indian Point Energy Center's Second Six-Month Status Report for the Implementation of Order EA-12-049 Modifying Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events," February 27, 2014, NRC ADAMS Accession No. ML14070A365.
5. Entergy Letter to U.S. NRC, letter number NL-14-110, "Indian Point Energy Center's Third Six-Month Status Report for the Implementation of Order EA-12-049 Modifying Licenses with Regard to Requirements for Mitigation Strategies for Beyond-Design-Basis External Events," August 27, 2014, NRC ADAMS Accession No. ML14251A227.
6. Entergy Engineering Evaluation, EC No. 45874, Revision 1, "FLEX-Beyond Design Basis External Event Phases I, II, and III Strategy Development Evaluation."
7. Entergy Drawing 9321-F-20173, Revision 72, "Flow Diagram Main Steam."
8. Entergy System Design Description 21.2, Revision 8, "System Description 21.2, Auxiliary Feedwater System."
9. Entergy Drawing 9321-F-70313, Revision 17, "Auxiliary Boiler Feed Pump Room Instrument Piping Sheet No.1 Instrumentation."
10. Entergy Drawing 9321-F-27233, Revision 40, "Flow Diagram Nitrogen to Nuclear Equipment."
11. Entergy Plant Equipment Database for Indian Point Unit 3.
12. Entergy Drawing 9321-F-20193, Revision 62, "Flow Diagram Boiler Feedwater."
13. Entergy Drawing 9321-LD-72123, Sheet 9, Revision 2, "Aux. F.W. Flow to Steam Generator #31 Loop F-1200 Diagram."
14. Entergy Drawing 9321-LD-72123, Sheet 10 Revision 2, "Aux. F.W. Flow to Steam Generator #32 Loop F-1201 Diagram."
15. Entergy Drawing 9321-LD-72123, Sheet 11, Revision 2, "Aux. F.W. Flow to Steam Generator #33 Loop F-1202 Diagram."
16. Entergy Drawing 9321-LD-72123, Sheet 12, Revision 2, "Aux. F.W. Flow to Steam Generator #34 Loop F-1203 Diagram."
17. Entergy Drawing 9321-F-31673, Revision 28, "Wiring Diagram 480V Switchgear Miscellaneous."

For Information Only

18. Entergy Drawing 9321-F-70033, Revision 17, "Transmitter Racks Piping Arrangement – Sheet No. 2 Instrumentation for Indian Point Energy Center Unit No. 3."
19. Entergy System Design Description 21.1, Revision 4, "System Description 21.1, Steam Generator Water Level Control."
20. Entergy Drawing 9321-F-70253, Revision 10, "Primary Plant Instrument Piping & Supports – Sheet No. 1 Instrumentation."
21. Entergy Drawing 9321-H-39903 Sheet 70, Revision 5, "Rack D-9 Layout."
22. Entergy Drawing 9321-F-32273, Revision 41, "Wiring Diagram Supervisory Control Panel SC."
23. Entergy Drawing 9321-F-70513, Revision 17, "Transmitter Racks Piping Arrangement – Sheet No. 4 Instrumentation."
24. Entergy Drawing 9321-F-10023, Revision 22, "Plot Plan."
25. Entergy Drawing 9321-F-20183 Sheet 1, Revision 63, "Flow Diagram Condensate & Boiler Feed Pump Suction."
26. Entergy Drawing 9321-F-27353, Revision 42, "Flow Diagram Safety Injection System Sheet No. 1."
27. Entergy System Design Description 10.1, Revision 10, "System Description 10.1, Safety Injection System."
28. Entergy System Design Description 3.0, Revision 8, "System Description 3.0, Chemical and Volume Control System."
29. Entergy System Design Description 4.2, Revision 7, "System Description 4.2, Residual Heat Removal System."
30. Entergy System Design Description 1.4, Revision 7, "System Description 1.4, Pressurizer & Pressurizer Relief Tank."
31. Entergy Drawing 9321-F-33853, Revision 19, "Electrical Distribution & Transmission System."
32. Entergy Drawing 9321-F-30063 Sheet 1, Revision 81, "Single Line Diagram 480V Motor Control Center No.'s 36A, 36B & 36C."
33. Entergy Drawing 9321-F-27363, Revision 52, Flow Diagram Chemical & Volume Control System Sheet No. 1."
34. Entergy Drawing 9321-F-27513 Sheet 1, Revision 31, "Flow Diagram Auxiliary Coolant System In PAB & FSB Sheet No. 1."
35. Entergy Drawing 9321-F-27503, Revision 55, "Flow Diagram Safety Injection System Sheet No. 2."
36. Entergy Drawing 9321-F-27203, Revision 29, "Flow Diagram Auxiliary Coolant System Inside Containment."
37. Entergy Drawing 9321-F-27473, Revision 43, "Flow Diagram Reactor Coolant System Sheet No. 2."

-
38. Entergy Drawing 9321-F-36383, Revision 4, "Miscellaneous Wiring Details RCS-SOV-652, RCS-SOV-653, RCS-SOV-654, & RCS-SOV-655."
 39. Entergy Drawing 9321-F-30053, Revision 72, "Single Line Diagram 480V Motor Control Centers 37, 38, 39, & 311."
 40. Entergy Drawing 9321-F-30083, Revision 60, "Single Line Diagram D.C. System."
 41. Entergy Drawing IP3V-0454-0041, Revision 1, Structural Detail for Seismic Category 1 Instrument Rack."
 42. Entergy Calculation IP-CALC-07-00154, Revision 0, "Containment Atmospheric Temperature."
 43. Entergy Drawing 9321-F-33433, Revision 7, "Containment Parameters System Wiring Diagram."
 44. Entergy Drawing 9321-H-39913 Sheet 8, Revision 8, "External Connection Diagram R.P.S. Rack No. 8 (A-7)."
 45. Entergy Drawing 9321-H-36723, Revision 0, "Cover Plates on Flight Pnl. "FCF" & Supervisory Pnl. "SCF" – Fabrication Mounting Details."
 46. Entergy Drawing 9321-F-20303, Revision 30, "Flow Diagram Fuel Oil to Diesel Generators."
 47. Entergy Drawing 9321-F-39893, Revision 43, "Single Line Diagram 118VAC Instrument Buses 31, 31A, 32, 32A, 33, 33A, 34, & 34A."
 48. Entergy Document IP3-RPT-UNSPEC-02182, Indian Point Three Nuclear Power Plant Individual Plant Examination of External Events," September 1997.
 49. Entergy Drawing 9321-F-32723, Revision 28, Wiring Diagram Flight Control Pnl. FCF & FCR."
 50. Entergy Drawing 9321-LD-72453 Sheet 21A, Revision 2, "Overpressurization System Channel 1 Loop P/T-413 Diagram."
 51. Entergy Drawing 9321-LD-72453 Sheet 23A, Revision 2, "Overpressurization System Channel 4 Loop P/T-443 Diagram."
 52. Entergy Drawing 9321-LD-72453 Sheet 21, Revision 3, "Overpressurization System Channel 1 Loop P/T-413 Diagram."
 53. Entergy Drawing 9321-LD-72453 Sheet 23, Revision 3, "Overpressurization System Channel 4 Loop P/T-443 Diagram."
 54. Entergy Drawing 9321-F-27383, Revision 28, "Flow Diagram Reactor Coolant System Sheet No. 1."
 55. Entergy Drawing 9321-LL-36853, Sheet 1, Revision 3, "Schematic Block Diagram Reactor Vessel Level Instrument System Train "A"."
 56. Entergy Drawing 9321-F-33203, Sheet 1, Revision 24, "Conduit & Tray Connection Schematic Containment Building."
 57. Entergy Drawing 9321-F-33313, Sheet 2, Revision 6, "Conduit & Tray Connection Schematic Fan House."
 58. Entergy Drawing 9321-F-30793, Revision 50, "Conduit Layout Containment Building Piping Penetration Area – Fan House."
-

59. Entergy Drawing 9321-F-72043, Revision 7, "Containment Building Reactor Vessel Level Instrumentation System Flow Diagram."
60. Entergy Drawing 9321-F-70283, Revision 25, Containment Building Instrument Arrangement Sheet No. 2 Instrumentation."
61. Entergy Drawing 9321-F-39933, Revision 19 "Conduit Layout TSI Room, CFM Multiplexer Room, Control Building EL. 53'-0" & Roof El. 72'-7."
62. Entergy Drawing 9321-F-95273 Sheet 1, Revision 6, "Control Room RVLIS Rack – Train "A" Interconnection Wiring Diagram."
63. Entergy Procedure 3-ECA-0.0, Revision 9, "Loss of All AC Power."
64. Entergy Drawing 9321-F-32383, Revision 31, "Wiring Diagram Supervisory Control Panel SB2."
65. Entergy System Design Description 1.1, Revision 5, "System Description 1.1, Reactor Coolant System."
66. Entergy Drawing IP3V-0245-0001, Revision 0, "40'-0" OD x 40'-0" High Fire Protection Water Storage Tanks "FP-Tk-1" & "FP-Tk-2" Pipe Support Details."
67. Entergy System Design Description 18.0, Revision 7, "System Description 18.0, Main and Reheat Steam."
68. EPRI 1025287, "Seismic Evaluation Guidance: Screening, Prioritization and Implementation Details (SPID) for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic. Electric Power Research Institute," February 2013.
69. Entergy Letter NL-14-043, John A. Ventosa to NRC, "Entergy Seismic Hazard and Screening Report (CEUS Sites), Response to NRC Request for Information Pursuant to 10 CFR 50.54(f) Regarding Recommendation 2.1 of the Near-Term Task Force Review of Insights from the Fukushima Dai-ichi Accident dated March 31, 2014." NRC ADAMS Accession No. ML14099A111.
70. "Indian Point Energy Center Unit 3 Updated Final Safety Analysis Report," Revision 5, Docket No. 50-286, 2013.
71. EPRI-NP-6041-SL, "Methodology for Assessment of Nuclear Power Plant Seismic Margin," Revision 1, August 1991.
72. EPRI TR-103959, "Methodology for Developing Seismic Fragilities," July 1994.
73. NRC NUREG-1407, "Procedural and Submittal Guidance for the Individual Plant Examination of External Events (IPEEE) for Severe Accident Vulnerabilities," June 1991.
74. SQUG, "Generic Implementation Procedure (GIP) for Seismic Verification of Nuclear Plant Equipment, Seismic Qualification Utility Group," Revision 3A, December 2001.
75. NRC (E. Leeds) Letter to All Power Reactor Licensees et al., "Screening and Prioritization Results Regarding Information Pursuant to Title 10 of the Code of Federal Regulations 50.54(F) Regarding Seismic Hazard Re-Evaluations for Recommendation 2.1 of the Near-Term Task Force Review of Insights From the Fukushima Dai-Ichi Accident," May 9, 2014.

76. Nuclear Energy Institute (NEI), A. Pietrangelo, Letter to D. Skeen of the USNRC, "Seismic Core Damage Risk Estimates Using the Updated Seismic Hazards for the Operating Nuclear Plants in the Central and Eastern United States," March 12, 2014.
77. Nuclear Energy Institute (NEI), A. Pietrangelo, Letter to D. Skeen of the USNRC, "Proposed Path Forward for NTTF Recommendation 2.1: Seismic Reevaluations," April 9, 2013, NRC ADAMS Accession No. ML13101A379.
78. NRC (E Leeds) Letter to NEI (J Pollock), "Electric Power Research Institute Final Draft Report xxxxx, "Seismic Evaluation Guidance: Augmented Approach for the Resolution of Fukushima Near-Term Task Force Recommendation 2.1: Seismic," as an Acceptable Alternative to the March 12, 2012, Information Request for Seismic Reevaluations," May 7, 2013.
79. Entergy Document EC54071, "ESEP Reports," the following AREVA documents are captured in the plant document management system:
 - a. AREVA Document 51-9212951-007, "ESEP Expedited Seismic Equipment List (ESEL) – Indian Point Unit 3."
 - b. AREVA Calculation 32-9227208-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Station Service Transformers 2, 3, 5, and 6."
 - c. AREVA Calculation 32-9227381-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Battery Bank 33 (BATT 33)."
 - d. AREVA Calculation 32-9227576-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Battery Chargers 31, 32, & 34."
 - e. AREVA Calculation 32-9230353-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Refueling Water Storage Tank, RWST-31."
 - f. AREVA Calculation 32-9230692-000, "Indian Point Unit 3 ESEP HCLPF Calculation – RCS Overpressure Racks H-1 and H-3."
 - g. AREVA Document 32-9232897-000, "Indian Point Unit 3 ESEP Calculation – Fire Water Storage Tanks FP-T-1 and FP-T-2."
 - h. AREVA Calculation 32-9238938-000, "Indian Point Unit 3 ESEP HCLPF Calculation – Residual Heat Exchangers ACAHRS1 and ACAHRS2."

ATTACHMENT A – INDIAN POINT UNIT 3 ESEL

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
1	MS-45-2	Steam Generator 32 Safety Relief Valve	Closed	Open	-	[7]
2	MS-45-3	Steam Generator 33 Safety Relief Valve	Closed	Open	-	[7]
3	PCV-1135	ATM Steam Relief Valve 32 Steam Generator	Closed	Cycled	-	[7]
4	PCV-1136	ATM Steam Relief Valve 33 Steam Generator	Closed	Cycled	-	[7]
5	PNL #1	ATM Steam Dump Panel #1	On	On	-	[9][67]
6	PNL #2	ATM Steam Dump Panel #2	On	On	-	[9][67]
7	32 ABFP	Turbine Driven Auxiliary Feedwater Pump No. 32	Standby	Operating	-	[7][12][8]
8	BFD-PCV-1213	Pressure Control Valve for Bearing Cooler	Closed	Open	-	[12][8]
9	HCV-1118	32 AFW Pump Turbine Governor	Closed	Open	-	[10][8]
10	MS-PCV-1139	Main Steam to AFW Turbine PCV	Closed	Open	-	[7][8]
11	MS-PCV-1310A	32 Auxiliary Boiler Feed Pump Steam Supply First Isolation	Closed	Open	Fails open on loss of instrument air or manually open per procedure	[7][63][8]
12	MS-PCV-1310B	32 Auxiliary Boiler Feed Pump Steam Supply Second Isolation	Closed	Open	Fails open on loss of instrument air or manually open per procedure	[7][63][8]
13	PNL PT2	Auxiliary Boiler Feed Pump Control Station	Off	On	-	[17][8]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
14	FT-1201	AFW to SG 32 Flow Transmitter	Off	On	-	[12][14]
15	FT-1202	AFW to SG 33 Flow Transmitter	Off	On	-	[12][15]
16	FI-1201	AFW to SG 32 Flow Indicator	On	On	-	[12][14]
17	FI-1202	AFW to SG 33 Flow Indicator	On	On	-	[12][15]
18	RACK 26	Pressure Transmitter Rack #26	On	On	-	[18][13][14][15][16]
19	RACK D-9	CCR Rack "D9" (NIS MISC Instrument)	On	On	-	[21][13][14][15][16]
20	PNL SC Supervisory Panel	Condenser & Feedwater Supervisory Panel	On	On	-	[22][13][14][15][16]
21	BFD-FCV-405B	No. 32 AFW Pump Manual Flow Control to 32 SG	Closed	Open	Per Local Equipment Procedure Manually Open Valves	[12][8]
22	BFD-FCV-405C	No. 32 AFW Pump Manual Flow Control to 33 SG	Closed	Open	Per Local Equipment Procedure Manually Open Valves	[12][8]
23	LT-427D	SG 32 Level Transmitter	On	On	-	[12][23][19][11][20]
24	LT-437D	SG 33 Level Transmitter	On	On	-	[12][23][19][11][20]
25	LI-427D	SG 32 Level Indicator	On	On	-	[19]
26	LI-437D	SG 33 Level Indicator	On	On	-	[19]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
27	RACK 21	Steam Generators Level Transmitter Rack	On	On	-	[23][20]
28	PT-429C	SG 32 Steam Pressure Transmitter	On	On	-	[7][18]
29	PT-439C	SG 33 Steam Pressure Transmitter	On	On	-	[7][18]
30	PI-1354	SG 32 Steam Pressure Indicator	On	On	Indication in AFW Pump Local Control Station	[7]
31	PI-1355	SG 33 Steam Pressure Indicator	On	On	Indication in AFW Pump Local Control Station	[7]
32	RACK 9	Instrument Rack 9	Operating	Operating	-	[18]
33	CST	Condensate Storage Tank	Available	Available	-	[24][25]
34	LI 1102-S	CST Level Indicator	Operating	Operating	-	[25]
35	LCV-1158-2	CST Low Level Control Valve	Open	Closed	-	[25]
36	LCV-1158-1	CST to Condensers Level Control Valve	Open	Closed	-	[25]
37	SI-MOV-894A	No. 31 Accumulator Isolation Valve	Open	Closed	-	[26][27]
38	SI-MOV-894B	No. 32 Accumulator Isolation Valve	Open	Closed	-	[26][27]
39	SI-MOV-894C	No. 33 Accumulator Isolation Valve	Open	Closed	-	[26][27]
40	SI-MOV-894D	No. 34 Accumulator Isolation Valve	Open	Closed	-	[26][27]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
41	36AMCC	Primary Auxiliary Building Motor Control Center 36A	On	On	-	[31][32]
42	36BMCC	Primary Auxiliary Building Motor Control Center 36B	On	On	-	[31][32]
43	CH-MOV-222	RCP Seal Water Return Isolation Valve	Open	Closed	Per Loss of All AC Power Procedure Manually Close Valves	[33][63]
44	AC-FCV-625	Thermal Barrier Isolation Valve	Open	Closed	Per Loss of All AC Power Procedure Manually Close Valves	[34][63]
45	RWST-31	Refueling Water Storage Tank	Available	Available	-	[35]
46	ACAHRS1	RHR HTEXCH # 31	Intact	Intact	Gravity feed path from RWST through heat exchanger	[36][29]
47	ACAHRS2	RHR HTEXCH # 32	Intact	Intact	Gravity feed path from RWST through heat exchanger	[36][29]
48	RCS-SOV-652	Reactor Head Vent	Closed	Open	125VDC Distribution Panel 32A	[37][38][65]
49	RCS-SOV-653	Reactor Head Vent	Closed	Open	125VDC Distribution Panel 32A	[37][38][65]
50	PNL SBF-1	Supervisory Panel SBF1	On	On	-	[38]
51	EHT Panel 34	Electric Heat Trace Panel 34	On	On	Powered by MCC 37	[39]
52	37MCC	Primary Auxiliary Building Motor Control Center 37	On	On	480VAC Bus 6A feeds to Primary Auxiliary Building 480V MCC 37 which powers Battery Charger 32	[31][39]
53	PNL K49	125 VDC Distribution Panel 32A	On	On	-	[31][40]
54	PT-1421	CTMT Pressure Transmitter	On	On	-	[35][41]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
55	PR-1421	CTMT Pressure Recorder	On	On	-	[43]
56	TE-1416-1	Fan 31 Temperature Element	On	On	-	[44][42]
57	TE-1416-2	Fan 32 Temperature Element	On	On	-	[44][42]
58	TE-1416-3	Fan 33 Temperature Element	On	On	-	[44][42]
59	TE-1416-4	Fan 34 Temperature Element	On	On	-	[44][42]
60	TE-1416-5	Fan 35 Temperature Element	On	On	-	[44][42]
61	RACK 24A	Instrument Rack	On	On	-	[41]
62	EDG-31-FO-STNK	Fuel Oil Storage Tank 31	Available	Available	-	[46][48]
63	EDG-32-FO-STNK	Fuel Oil Storage Tank 32	Available	Available	-	[46][48]
64	EDG-33-FO-STNK	Fuel Oil Storage Tank 33	Available	Available	-	[46][48]
65	31IB	118V AC Instrument Bus 31 Channel II	On	On	-	[31][47]
66	32IB	118V AC Instrument Bus 32 Channel I	On	On	-	[31][47]
67	34IB	118V AC Instrument Bus 34 Channel III	On	On	-	[31][47]
68	33IB	118V AC Instrument Bus 33 Channel IV	On	On	-	[31][47]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
69	31AIB	118V AC Instrument Bus 31A Channel II	On	On	-	[31][47]
70	32AIB	118V AC Instrument Bus 32A Channel I	On	On	-	[31][47]
71	34AIB	118V AC Instrument Bus 34A Channel III	On	On	-	[31][47]
72	33AIB	118V AC Instrument Bus 33A Channel IV	On	On	-	[31][47]
73	34 INVERTER	Static Inverter 34	On	On	-	[31][40][48]
74	33 INVERTER	Static Inverter 33	On	On	-	[31][40][48]
75	31 INVERTER	Static Inverter 31	On	On	-	[31][40][48]
76	32 INVERTER	Static Inverter 32	On	On	-	[31][40][48]
77	31DP	125VDC Distribution Panel 31	On	On	-	[31][40][48]
78	32DP	125VDC Distribution Panel 32	On	On	-	[31][40]
79	33DP	125VDC Distribution Panel 33	On	On	-	[31][40][48]
80	34DP	125VDC Distribution Panel 34	On	On	-	[31][40][48]
81	PNL K48	125 VDC Distribution Panel 31A	On	On	-	[31][40][48]
82	31PP	125VDC Power Panel 31	On	On	-	[31][40][48]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
83	32PP	125VDC Power Panel 32	On	On	-	[31][40][48]
84	33PP	125VDC Power Panel 33	On	On	-	[31][40][48]
85	34PP	125VDC Power Panel 34	On	On	-	[31][40][48]
86	BATT CHGR 31	Battery Charger 31	On	On	-	[31][40]
87	BATT CHGR 32	Battery Charger 32	On	On	-	[31][40]
88	BATT CHGR 33	Battery Charger 33	On	On	-	[31][40]
89	BATT CHGR 34	Battery Charger 34	On	On	-	[31][40]
90	BATT 31	Battery Bank 31	On	On	-	[31][40]
91	BATT 32	Battery Bank 32	On	On	-	[31][40]
92	BATT 34	Battery Bank 34	On	On	-	[31][40]
93	BATT 33	Battery Bank 33	On	On	-	[31][40]
94	BUS2A	480V(SWGR 31) Bus 2A	On	On	-	[31]
95	BUS3A	480V(SWGR 32) Bus 3A	On	On	-	[31]
96	BUS5A	480V(SWGR31) Bus 5A	On	On	-	[31]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
97	BUS6A	480V(SWGR 32) Bus 6A	On	On	-	[31]
98	36CMCC	Primary Auxiliary Building Motor Control Center 36C	On	On	-	[31]
99	39MCC	Control Building Motor Control Center 39	On	On	-	[31]
100	32MCC	Turbine-Generator Building Motor Control Center 32	On	On	-	[31]
101	NI 31B	Source Range Count Rate Meter	On	On	-	[48]
102	NI 31D	Source Range Count Rate Meter	On	On	-	[48]
103	FE1	Preamplifier For NE-31	On	On	-	[48]
104	PNL FCF	Flight Control Panel FC	On	On	-	[48][49]
105	PI-413K	Loop 31 Hot Leg Pressure Indicator	On	On	-	[50]
106	PI-443K	Loop 34 Hot Leg Pressure Indicator	On	On	-	[51]
107	PT-413	Loop 31 Hot Leg Pressure Transmitter	On	On	-	[52][54]
108	PT-443	Loop 34 Hot Leg Pressure Transmitter	On	On	-	[53][54]
109	TE-1313	Upper Tap Compensation Temperature Element	On	On	-	[59]
110	TE-1314	Upper Tap Compensation Temperature Element	On	On	-	[59]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
111	TE-1317	RVWL Conduit Compensation Temperature Element	On	On	-	[59]
112	TE-1318	RVWL Conduit Compensation	On	On	-	[59]
113	TE-1319	RVWL Lower Tap Capillary Temperature Element	On	On	-	[59]
114	TE-413A	RCS Loop 31 Hot Leg Wide Range Temperature Element	On	On	-	[60]
115	TE-423A	RCS Loop 32 Hot Leg Wide Range Temperature Element	On	On	-	[48][60]
116	CAB JR9	RVLIS Cabinet	On	On	-	[48][61][62]
117	LI-1311	RVWL Narrow Range Indicator	On	On	-	[48]
118	LI-1312	RVWL Wide Range Indicator	On	On	-	[48]
119	LT-1311	Reactor Vessel Level Transmitter Narrow Range	On	On	-	[48][59]
120	LT-1312	Reactor Vessel Level Transmitter Narrow Range	On	On	-	[48][59]
121	TI-1416	Containment Atmospheric Temperature Indicator	On	On	-	[44]
122	PM-413K	Loop 31 Hot Leg Pressure	On	On	-	[50]
123	31AIB-2 (J01)	Containment Parameters Recording Cabinet (Channel I)	On	On	-	[43]
124	PM-443K	Loop 34 Hot Leg Pressure	On	On	-	[51]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
125	PC-413	Loop 31 Hot Leg Pressure	On	On	-	[52]
126	PC-443	Loop 34 Hot Leg Pressure	On	On	-	[53]
127	PQ-413	Loop 31 Hot Leg Pressure	On	On	-	[52]
128	PQ-443	Loop 34 Hot Leg Pressure	On	On	-	[53]
129	PNL SBF-2	Supervisory Control Panel SB-2	On	On	-	[64]
130	RACK H1	CCR Auxiliary Panel Analog Rack H1	On	On	-	[52]
131	RACK H3	CCR Auxiliary Panel Analog Rack H3	On	On	-	[53]
132	Panel SFF	Supervisory Panel SF	On	On	-	[50][51]
133	RVLIS RACK TRAIN A	RVLIS Rack Train A	On	On	-	[48][59]
134	MS-45-1	Steam Generator 31 Safety Relief Valve	Closed	Open	-	[7]
135	MS-45-4	Steam Generator 34 Safety Relief Valve	Closed	Open	-	[7]
136	PCV-1134	ATM Steam Relief Valve 31 Steam Generator	Closed	Cycled	Manual Operation	[7]
137	PCV-1137	ATM Steam Relief Valve 34 Steam Generator	Closed	Cycled	Manual Operation	[7]
138	N2 TANKS	Backup Nitrogen Cylinders	Intact	Intact	-	[67][9]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
139	IA-PCV-1278	Nitrogen Pressure Regulator	Closed	Open	-	[67][9][10][11]
140	IA-PCV-1277	Nitrogen Pressure Regulator	Closed	Open	-	[67][9][10][11]
141	MS-577	32 AFW Pump Overspeed Trip & Governor Valve	Intact	Intact	Part of the TDAFWP Skid	[8][11]
142	FT-1200	AFW to SG 31 Flow Transmitter	Off	On	-	[12][13]
143	FT-1203	AFW to SG 34 Flow Transmitter	Off	On	-	[12][16]
144	FI-1200	AFW to SG 31 Flow Indicator	On	On	-	[12][13]
145	FI-1203	AFW to SG 34 Flow Indicator	On	On	-	[12][16]
146	BFD-FCV-405A	No. 32 AFW Pump Manual Flow Control to 31 SG	Closed	Open	Manually Open Valves	[12]
147	BFD-FCV-405D	No. 32 AFW Pump Manual Flow Control to 34 SG	Closed	Open	Manually Open Valves	[12]
148	LT-417D	SG 31 Level Transmitter	On	On	-	[12][23][19][11][20]
149	LT-447D	SG 34 Level Transmitter	On	On	-	[12][23][19][11][20]
150	LI-417D	SG 31 Level Indicator	On	On	-	[19]
151	LI-447D	SG 34 Level Indicator	On	On	-	[19]
152	LQ-417D	Steam Generator Level	On	On	-	[11]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
153	LQ-427D	Steam Generator Level	On	On	-	[11]
154	LQ-437D	Steam Generator Level	On	On	-	[11]
155	LQ-447D	Steam Generator Level	On	On	-	[11]
156	RACK B10	Instrument Rack	On	On	-	[11]
157	RACK B5	Instrument Rack	On	On	-	[11]
158	PI-1353	SG 31 Steam Pressure Indicator	On	On	Local Indication	[7]
159	PI-1356	SG 34 Steam Pressure Indicator	On	On	Local Indication	[7]
160	ACCUM. 31	Accumulator Tank 31	Intact	Intact	-	[26][27][11]
161	ACCUM. 32	Accumulator Tank 32	Intact	Intact	-	[26][27][11]
162	ACCUM. 33	Accumulator Tank 33	Intact	Intact	-	[26][27][11]
163	ACCUM. 34	Accumulator Tank 34	Intact	Intact	-	[26][27][11]
164	CH-LCV-459	Letdown Isolation Valve	Open	Closed	Fail Closed on Loss of instrument air	[28][11]
165	CH-HCV-133	RHR LP Bypass Valve	Open	Closed	-	[28][11]
166	MOV-882	RHR Pump Suction Isolation Valve	Closed	Open	Powered from MCC 36B	[29]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
167	LT-459	Pressurizer Level Transmitter	On	On	-	[30]
168	LI-459A	Pressurizer Level Indicator	On	On	-	[30]
169	LM-459A	Pressurizer Level	On	On	-	[11]
170	Rack A4	CCR Rack A4	On	On	-	[11]
171	Rack 19	Instrument Rack	On	On	-	[11]
172	Y39	Terminal Box	Intact	Intact	-	[55]
173	Y32	Terminal Box	Intact	Intact	-	[55]
174	Y36	Terminal Box	Intact	Intact	-	[55][56]
175	LIS-1311	Hydraulic Isolators	Intact	Intact	-	[55][11]
176	LIS-1312	Hydraulic Isolators	Intact	Intact	-	[55][11]
177	Y29	Terminal Box	Intact	Intact	-	[55][57][58]
178	PNL SN	Supervisory Panel SN (JB9)	On	On	-	[55]
179	PT-402	Pressure Transmitter	On	On	-	[55]
180	RACK 22 (C9)	Instrument Rack	On	On	-	[55][11]

For Information Only

Indian Point Unit 3 ESEP Report

ESEL Item Number	Equipment		Operating State		Notes/Comments	References
	ID	Description	Normal State	Desired State		
181	RACK 6 (A9)	Instrument Rack	On	On	-	[55][11]
182	-	TDAFWP Turbine	Standby	Operating	Part of the TDAFWP skid	[7][12][8]
183	-	TDAFWP Lube Oil Coolers	Standby	Operating	Part of the TDAFWP skid	[7][12][8]
184	TC-1416-1	Temperature Converter	On	On	-	[42]
185	TC-1416-2	Temperature Converter	On	On	-	[42]
186	TC-1416-3	Temperature Converter	On	On	-	[42]
187	TC-1416-4	Temperature Converter	On	On	-	[42]
188	TC-1416-5	Temperature Converter	On	On	-	[42]
189	Rack A-7	CCR Rack A-7	On	On	-	[42]
190	FP-T-1	31 Fire Water Storage Tank	Intact	Intact	-	[66]
191	FP-T-2	32 Fire Water Storage Tank	Intact	Intact	-	[66]
192	PW-S-TK	31 Primary Water Storage Tank	Intact	Intact	-	[11]
193	Rack B4	CCR Rack B-4	On	On	-	[11]

ATTACHMENT B – ESEP HCLPF VALUES AND FAILURE MODES TABULATION

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
1	MS-45-2	Steam Generator 32 Safety Relief Valve	>RLGM	Screened	
2	MS-45-3	Steam Generator 33 Safety Relief Valve	>RLGM	Screened	
3	PCV-1135	ATM Steam Relief Valve 32 Steam Generator	>RLGM	Screened	
4	PCV-1136	ATM Steam Relief Valve 33 Steam Generator	>RLGM	Screened	
5	PNL #1	ATM Steam Dump Panel #1	>RLGM	Screened	Note 2
6	PNL #2	ATM Steam Dump Panel #2	>RLGM	Screened	Note 2
7	32 ABFP	Turbine Driven Auxiliary Feedwater Pump No. 32	>RLGM	Screened	Note 1
8	BFD-PCV-1213	Pressure Control Valve for Bearing Cooler	>RLGM	Screened	
9	HCV-1118	32 AFW Pump Turbine Governor	>RLGM	Screened	
10	MS-PCV-1139	Main Steam to AFW Turbine PCV	>RLGM	Screened	
11	MS-PCV-1310A	32 Auxiliary Boiler Feed Pump Steam Supply First Isolation	>RLGM	Screened	
12	MS-PCV-1310B	32 Auxiliary Boiler Feed Pump Steam Supply Second Isolation	>RLGM	Screened	
13	PNL PT2	Auxiliary Boiler Feed Pump Control Station	>RLGM	Screened	Note 1
14	FT-1201	AFW to SG 32 Flow Transmitter	>RLGM	Screened	
15	FT-1202	AFW to SG 33 Flow Transmitter	>RLGM	Screened	
16	FI-1201	AFW to SG 32 Flow Indicator	>RLGM	Screened	
17	FI-1202	AFW to SG 33 Flow Indicator	>RLGM	Screened	
18	RACK 26	Pressure Transmitter Rack #26	>RLGM	Screened	Note 2
19	RACK D-9	CCR Rack "D9" (NIS MISC Instrument)	>RLGM	Screened	Note 2
20	PNL SC Supervisory Panel	Condenser & Feedwater Supervisory Panel	>RLGM	Screened	Note 2

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
21	BFD-FCV-405B	No. 32 AFW Pump Manual Flow Control to 32 SG	>RLGM	Screened	
22	BFD-FCV-405C	No. 32 AFW Pump Manual Flow Control to 33 SG	>RLGM	Screened	
23	LT-427D	SG 32 Level Transmitter	>RLGM	Screened	Note 3
24	LT-437D	SG 33 Level Transmitter	>RLGM	Screened	Note 3
25	LI-427D	SG 32 Level Indicator	>RLGM	Screened	
26	LI-437D	SG 33 Level Indicator	>RLGM	Screened	
27	RACK 21	Steam Generators Level Transmitter Rack	>RLGM	Screened	Note 3
28	PT-429C	SG 32 Steam Pressure Transmitter	>RLGM	Screened	
29	PT-439C	SG 33 Steam Pressure Transmitter	>RLGM	Screened	
30	PI-1354	SG 32 Steam Pressure Indicator	>RLGM	Screened	
31	PI-1355	SG 33 Steam Pressure Indicator	>RLGM	Screened	
32	RACK 9	Instrument Rack 9	>RLGM	Screened	Note 2
33	CST	Condensate Storage Tank	>RLGM	Screened	Note 1
34	LI 1102-S	CST Level Indicator	>RLGM	Screened	
35	LCV-1158-2	CST Low Level Control Valve	>RLGM	Screened	
36	LCV-1158-1	CST to Condensers Level Control Valve	>RLGM	Screened	
37	SI-MOV-894A	No. 31 Accumulator Isolation Valve	>RLGM	Screened	Note 3
38	SI-MOV-894B	No. 32 Accumulator Isolation Valve	>RLGM	Screened	Note 3
39	SI-MOV-894C	No. 33 Accumulator Isolation Valve	>RLGM	Screened	Note 3
40	SI-MOV-894D	No. 34 Accumulator Isolation Valve	>RLGM	Screened	Note 3
41	36AMCC	Primary Auxiliary Building Motor Control Center 36A	>RLGM	Screened	Note 1

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
42	36BMCC	Primary Auxiliary Building Motor Control Center 36B	>RLGM	Screened	Note 1
43	CH-MOV-222	RCP Seal Water Return Isolation Valve	>RLGM	Screened	
44	AC-FCV-625	Thermal Barrier Isolation Valve	>RLGM	Screened	
45	RWST-31	Refueling Water Storage Tank	0.41	Tank Sloshing	
46	ACAHRS1	RHR HTEXCH # 31	0.35	Steel Platform	Note 3
47	ACAHRS2	RHR HTEXCH # 32	0.35	Steel Platform	Note 3
48	RCS-SOV-652	Reactor Head Vent	>RLGM	Screened	Note 3
49	RCS-SOV-653	Reactor Head Vent	>RLGM	Screened	Note 3
50	PNL SBF-1	Supervisory Panel SBF1	>RLGM	Screened	Note 2
51	EHT Panel 34	Electric Heat Trace Panel 34	>RLGM	Screened	
52	37MCC	Primary Auxiliary Building Motor Control Center 37	>RLGM	Screened	Note 1
53	PNL K49	125 VDC Distribution Panel 32A	>RLGM	Screened	Note 2
54	PT-1421	CTMT Pressure Transmitter	>RLGM	Screened	
55	PR-1421	CTMT Pressure Recorder	>RLGM	Screened	
56	TE-1416-1	Fan 31 Temperature Element	>RLGM	Screened	Note 3
57	TE-1416-2	Fan 32 Temperature Element	>RLGM	Screened	Note 3
58	TE-1416-3	Fan 33 Temperature Element	>RLGM	Screened	Note 3
59	TE-1416-4	Fan 34 Temperature Element	>RLGM	Screened	Note 3
60	TE-1416-5	Fan 35 Temperature Element	>RLGM	Screened	Note 3
61	RACK 24A	Instrument Rack	>RLGM	Screened	Note 2
62	EDG-31-FO-STNK	Fuel Oil Storage Tank 31	>RLGM	Screened	Note 2

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
63	EDG-32-FO-STNK	Fuel Oil Storage Tank 32	>RLGM	Screened	Note 2
64	EDG-33-FO-STNK	Fuel Oil Storage Tank 33	>RLGM	Screened	Note 2
65	31IB	118V AC Instrument Bus 31 Channel II	>RLGM	Screened	Note 2
66	32IB	118V AC Instrument Bus 32 Channel I	>RLGM	Screened	Note 2
67	34IB	118V AC Instrument Bus 34 Channel III	>RLGM	Screened	Note 2
68	33IB	118V AC Instrument Bus 33 Channel IV	>RLGM	Screened	Note 2
69	31AIB	118V AC Instrument Bus 31A Channel II	>RLGM	Screened	Note 2
70	32AIB	118V AC Instrument Bus 32A Channel I	>RLGM	Screened	Note 2
71	34AIB	118V AC Instrument Bus 34A Channel III	>RLGM	Screened	Note 2
72	33AIB	118V AC Instrument Bus 33A Channel IV	>RLGM	Screened	Note 2
73	34 INVERTER	Static Inverter 34	>RLGM	Screened	Note 1
74	33 INVERTER	Static Inverter 33	>RLGM	Screened	Note 2
75	31 INVERTER	Static Inverter 31	>RLGM	Screened	Note 2
76	32 INVERTER	Static Inverter 32	>RLGM	Screened	Note 2
77	31DP	125VDC Distribution Panel 31	>RLGM	Screened	Note 2
78	32DP	125VDC Distribution Panel 32	>RLGM	Screened	Note 2
79	33DP	125VDC Distribution Panel 33	>RLGM	Screened	Note 2
80	34DP	125VDC Distribution Panel 34	>RLGM	Screened	Note 2
81	PNL K48	125 VDC Distribution Panel 31A	>RLGM	Screened	Note 2
82	31PP	125VDC Power Panel 31	>RLGM	Screened	Note 2
83	32PP	125VDC Power Panel 32	>RLGM	Screened	Note 2

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
84	33PP	125VDC Power Panel 33	>RLGM	Screened	Note 2
85	34PP	125VDC Power Panel 34	>RLGM	Screened	Note 2
86	BATT CHGR 31	Battery Charger 31	0.36	Anchorage	
87	BATT CHGR 32	Battery Charger 32	0.36	Anchorage	
88	BATT CHGR 33	Battery Charger 33	>RLGM	Screened	Note 1
89	BATT CHGR 34	Battery Charger 34	0.36	Anchorage	
90	BATT 31	Battery Bank 31	>RLGM	Screened	Note 1
91	BATT 32	Battery Bank 32	>RLGM	Screened	Note 1
92	BATT 34	Battery Bank 34	>RLGM	Screened	Note 2
93	BATT 33	Battery Bank 33	0.41	Anchorage	
94	BUS2A	480V(SWGR 31) Bus 2A	>RLGM	Screened	Note 2
95	BUS3A	480V(SWGR 32) Bus 3A	>RLGM	Screened	Note 2
96	BUS5A	480V(SWGR31) Bus 5A	>RLGM	Screened	Note 2
97	BUS6A	480V(SWGR 32) Bus 6A	>RLGM	Screened	Note 2
98	36CMCC	Primary Auxiliary Building Motor Control Center 36C	>RLGM	Screened	Note 2
99	39MCC	Control Building Motor Control Center 39	>RLGM	Screened	Note 2
100	32MCC	Turbine-Generator Building Motor Control Center 32	>RLGM	Screened	Note 1
101	NI 31B	Source Range Count Rate Meter	>RLGM	Screened	
102	NI 31D	Source Range Count Rate Meter	>RLGM	Screened	
103	FE1	Preamplifier For NE-31	>RLGM	Screened	Note 3

For Information Only

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
104	PNL FCF	Flight Control Panel FC	>RLGM	Screened	Note 2
105	PI-413K	Loop 31 Hot Leg Pressure Indicator	>RLGM	Screened	
106	PI-443K	Loop 34 Hot Leg Pressure Indicator	>RLGM	Screened	
107	PT-413	Loop 31 Hot Leg Pressure Transmitter	>RLGM	Screened	Note 3
108	PT-443	Loop 34 Hot Leg Pressure Transmitter	>RLGM	Screened	Note 3
109	TE-1313	Upper Tap Compensation Temperature Element	>RLGM	Screened	Note 3
110	TE-1314	Upper Tap Compensation Temperature Element	>RLGM	Screened	Note 3
111	TE-1317	RVWL Conduit Compensation Temperature Element	>RLGM	Screened	Note 3
112	TE-1318	RVWL Conduit Compensation	>RLGM	Screened	Note 3
113	TE-1319	RVWL Lower Tap Capillary Temperature Element	>RLGM	Screened	Note 3
114	TE-413A	RCS Loop 31 Hot Leg Wide Range Temperature Element	>RLGM	Screened	Note 3
115	TE-423A	RCS Loop 32 Hot Leg Wide Range Temperature Element	>RLGM	Screened	Note 3
116	CAB JR9	RVLIS Cabinet	>RLGM	Screened	Note 2
117	LI-1311	RVWL Narrow Range Indicator	>RLGM	Screened	
118	LI-1312	RVWL Wide Range Indicator	>RLGM	Screened	
119	LT-1311	Reactor Vessel Level Transmitter Narrow Range	>RLGM	Screened	
120	LT-1312	Reactor Vessel Level Transmitter Narrow Range	>RLGM	Screened	
121	TI-1416	Containment Atmospheric Temperature Indicator	>RLGM	Screened	
122	PM-413K	Loop 31 Hot Leg Pressure	>RLGM	Screened	

For Information Only

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
123	31AIB-2 (J01)	Containment Parameters Recording Cabinet (Channel I)	>RLGM	Screened	Note 2
124	PM-443K	Loop 34 Hot Leg Pressure	>RLGM	Screened	
125	PC-413	Loop 31 Hot Leg Pressure	>RLGM	Screened	
126	PC-443	Loop 34 Hot Leg Pressure	>RLGM	Screened	
127	PQ-413	Loop 31 Hot Leg Pressure	>RLGM	Screened	
128	PQ-443	Loop 34 Hot Leg Pressure	>RLGM	Screened	
129	PNL SBF-2	Supervisory Control Panel SB-2	>RLGM	Screened	Note 1
130	Rack H1	CCR Auxiliary Panel Analog Rack H1	0.47	Functional	
131	Rack H3	CCR Auxiliary Panel Analog Rack H3	0.47	Functional	
132	PANEL SFF	Supervisory Panel SF	>RLGM	Screened	Note 2
133	RVLIS RACK TRAIN A	RVLIS Rack Train A	>RLGM	Screened	Note 2
134	MS-45-1	Steam Generator 31 Safety Relief Valve	>RLGM	Screened	
135	MS-45-4	Steam Generator 34 Safety Relief Valve	>RLGM	Screened	
136	PCV-1134	ATM Steam Relief Valve 31 Steam Generator	>RLGM	Screened	
137	PCV-1137	ATM Steam Relief Valve 34 Steam Generator	>RLGM	Screened	
138	N2 TANKS	Backup Nitrogen Cylinders	>RLGM	Screened	Note 2
139	IA-PCV-1278	Nitrogen Pressure Regulator	>RLGM	Screened	
140	IA-PCV-1277	Nitrogen Pressure Regulator	>RLGM	Screened	
141	MS-577	32 AFW Pump Overspeed Trip & Governor Valve	>RLGM	Screened	
142	FT-1200	AFW to SG 31 Flow Transmitter	>RLGM	Screened	

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
143	FT-1203	AFW to SG 34 Flow Transmitter	>RLGM	Screened	
144	FI-1200	AFW to SG 31 Flow Indicator	>RLGM	Screened	
145	FI-1203	AFW to SG 34 Flow Indicator	>RLGM	Screened	
146	BFD-FCV-405A	No. 32 AFW Pump Manual Flow Control to 31 SG	>RLGM	Screened	
147	BFD-FCV-405D	No. 32 AFW Pump Manual Flow Control to 34 SG	>RLGM	Screened	
148	LT-417D	SG 31 Level Transmitter	>RLGM	Screened	Note 3
149	LT-447D	SG 34 Level Transmitter	>RLGM	Screened	Note 3
150	LI-417D	SG 31 Level Indicator	>RLGM	Screened	
151	LI-447D	SG 34 Level Indicator	>RLGM	Screened	
152	LQ-417D	Steam Generator Level	>RLGM	Screened	
153	LQ-427D	Steam Generator Level	>RLGM	Screened	
154	LQ-437D	Steam Generator Level	>RLGM	Screened	
155	LQ-447D	Steam Generator Level	>RLGM	Screened	
156	RACK B10	Instrument Rack	>RLGM	Screened	Note 1
157	RACK B5	Instrument Rack	>RLGM	Screened	Note 1
158	PI-1353	SG 31 Steam Pressure Indicator	>RLGM	Screened	
159	PI-1356	SG 34 Steam Pressure Indicator	>RLGM	Screened	
160	ACCUM. 31	Accumulator Tank 31	>RLGM	Screened	Note 3
161	ACCUM. 32	Accumulator Tank 32	>RLGM	Screened	Note 3
162	ACCUM. 33	Accumulator Tank 33	>RLGM	Screened	Note 3
163	ACCUM. 34	Accumulator Tank 34	>RLGM	Screened	Note 3

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
164	CH-LCV-459	Letdown Isolation Valve	>RLGM	Screened	Note 3
165	CH-HCV-133	RHR LP Bypass Valve	>RLGM	Screened	Note 3
166	MOV-882	RHR Pump Suction Isolation Valve	>RLGM	Screened	
167	LT-459	Pressurizer Level Transmitter	>RLGM	Screened	Note 3
168	LI-459A	Pressurizer Level Indicator	>RLGM	Screened	
169	LM-459A	Pressurizer Level	>RLGM	Screened	
170	Rack A4	CCR Rack A4	>RLGM	Screened	Note 1
171	Rack 19	Instrument Rack	>RLGM	Screened	Note 3
172	Y39	Terminal Box	>RLGM	Screened	Note 3
173	Y32	Terminal Box	>RLGM	Screened	Note 3
174	Y36	Terminal Box	>RLGM	Screened	Note 3
175	LIS-1311	Hydraulic Isolators	>RLGM	Screened	Note 2
176	LIS-1312	Hydraulic Isolators	>RLGM	Screened	Note 2
177	Y29	Terminal Box	>RLGM	Screened	Note 2
178	PNL SN	Supervisory Panel SN (JB9)	>RLGM	Screened	Note 1
179	PT-402	Pressure Transmitter	>RLGM	Screened	Note 3
180	RACK 22 (C9)	Instrument Rack	>RLGM	Screened	Note 1
181	RACK 6 (A9)	Instrument Rack	>RLGM	Screened	Note 1
182	-	TDAFWP Turbine	>RLGM	Screened	
183	-	TDAFWP Lube Oil Coolers	>RLGM	Screened	
184	TC-1416-1	Temperature Converter	>RLGM	Screened	

For Information Only

Indian Point Unit 3 ESEP Report

Item No.	Equipment ID	Equipment Description	HCLPF (g) / Screening Level	Failure Mode	Comments
185	TC-1416-2	Temperature Converter	>RLGM	Screened	
186	TC-1416-3	Temperature Converter	>RLGM	Screened	
187	TC-1416-4	Temperature Converter	>RLGM	Screened	
188	TC-1416-5	Temperature Converter	>RLGM	Screened	
189	Rack A-7	CCR Rack A-7	>RLGM	Screened	Note 1
190	FP-T-1	31 Fire Water Storage Tank	0.24	Anchorage	Modifications required.
191	FP-T-2	32 Fire Water Storage Tank	0.24	Anchorage	Modifications required.
192	PW-S-TK	31 Primary Water Storage Tank	>RLGM	Screened	Note 1
193	Rack B4	CCR Rack B-4	>RLGM	Screened	Note 1

Notes:

1. Anchorage screened out based on available margin during walkdown by SRT.
2. Anchorage screened out during walkdown validation by SRT.
3. Inaccessible components were walked down during 3R18 outage (March 2015).