

ATTACHMENT 3
REVISED PAGES

9503200102 950309
PDR ADOCK 05000269
P PDR

**ATTACHMENT 1
DUKE POWER COMPANY
OCONEE NUCLEAR STATION
UNITS 1, 2, AND 3**

**Summary of Changes to the Oconee Nuclear Station
ASME IST Valve and Pump Testing Program and
Description of Revisions for NRC SER, Dated November 23, 1994**

- 1 The ONS System Engineering Directive 4.7, ONS ASME Valve and Pump Testing Directive was re-written and re-formatted. The directive was also renamed the ONS ASME Inservice Testing Program Document to ensure consistency between the Duke Power nuclear stations (i.e. McGuire Nuclear Station and Catawba Nuclear Station do not document their pump and valve testing programs in System Engineering Directives.) The document was expanded to include program philosophy and position statements. Additionally, a document named ONS ASME Inservice Testing Program was generated to contain the contents of the attachments to ONS System Engineering Directive 4.7. This issue of the program document does not contain a copy of the retest list (list of all pumps and valves in IST and Appendix B testing programs) as was contained in the directive. These data will be included in the ONS 10CFR50 Appendix B Supplemental Testing Program and the ONS Pump and Valve Re-Test List upon completion of a comprehensive review of the Appendix B (Supplemental) Testing program.

22 a

22 a

Per recommendations in the SER, the following changes were made to the document:

- page numbers were added to the program document,
- any reference to a pump deferral or pump cold shutdown justification was deleted,
- a discussion of pump alternate acceptance criteria was added to the document,
- a discussion of Oconee's position on using non-intrusive testing techniques was added to the document,
- the statement of how category A and A/C valves are leak tested was revised,
- the index before each section of relief requests was revised to show the status of each relief request (e.g. date last revised, deleted, or date created),
- the Pump IST List was revised to reference RR-PMP-02 for only the 1A, 2A, and 3A LPI pumps.

- 2 The valve testing program was revised to document adopting the valve testing guidelines presented in ASME/ANSI OM-1987 Standard OMa-1988 Part 10 (OM-10). This revision involved re-writing the following three valve generic relief requests and four valve specific relief requests to reference the OM Code as opposed to referencing the IWV Code: GNR-VLV-03, GNR-VLV-08, GNR-VLV-10, RR-VLV-10, RR-VLV-11, RR-VLV-17, and RR-VLV-24. The revision also involved re-writing 30 cold shutdown justifications as Justification for Deferrals and 27 valve specific relief requests as Justification for Deferrals. In an effort to improve inter-station consistency, the Justification for Deferrals are numbered the same as they are at McGuire and Catawba. The following table summarizes what was re-written as a Justification for Deferral:

| Previous Cold Shutdown Justification Number | New Justification for Deferral Number | Previous Relief Request Number | New Justification for Deferral Number |
|--|---|--------------------------------------|---|
| CSD-VLV-01 | ON-SSF-01 | RR-VLV-01 | ON-HP-08 |
| CSD-VLV-02 | ON-SSF-02 | RR-VLV-02 | ON-HP-09 |
| CSD-VLV-03 | ON-HP-01 | RR-VLV-04 | ON-HP-10 |
| CSD-VLV-04 | ON-HP-02 | RR-VLV-05 | ON-HP-11 |

| Previous Cold Shutdown Justification Number | New Justification for Deferral Number | Previous Relief Request Number | New Justification for Deferral Number |
|--|---|--------------------------------------|---|
| CSD-VLV-05 | ON-HP-03 | RR-VLV-06 | ON-HP-12 |
| CSD-VLV-06 | ON-LP-01 | RR-VLV-07 | ON-HP-13 |
| CSD-VLV-07 | ON-LP-02 | RR-VLV-08 | ON-HP-14 |
| CSD-VLV-08 | ON-LP-03 | RR-VLV-09 | ON-HP-15 |
| CSD-VLV-09 | ON-RC-01 | RR-VLV-10 | ON-CF-01 |
| CSD-VLV-10 | ON-FDW-01 | RR-VLV-12 | ON-BS-01 |
| CSD-VLV-11 | ON-MS-01 | RR-VLV-13 | ON-BS-02 |
| CSD-VLV-12 | ON-CC-01 | RR-VLV-14 | ON-CS-01 |
| CSD-VLV-14 | ON-SSF-03 | RR-VLV-15 | ON-HP-16 |
| CSD-VLV-15 | ON-SSF-04 | RR-VLV-16 | ON-CC-02 |
| CSD-VLV-16 | ON-SSF-05 | RR-VLV-17 | ON-CF-02 |
| CSD-VLV-17 | ON-LPSW-01 | RR-VLV-18 | deleted |
| CSD-VLV-19 | ON-FDW-02 | RR-VLV-19 | ON-HP-17 |
| CSD-VLV-21 | ON-MS-02 | RR-VLV-21 | ON-LP-06 |
| CSD-VLV-22 | ON-LP-04 | RR-VLV-22 | ON-C-03 |
| CSD-VLV-23 | ON-FDW-03 | RR-VLV-23 | ON-AS-01 |
| CSD-VLV-24 | ON-C-01 | RR-VLV-25 | ON-CF-03 |
| CSD-VLV-25 | ON-MS-03 | RR-VLV-26 | ON-FDW-04 |
| CSD-VLV-26 | ON-MS-04 | RR-VLV-28 | ON-LPSW-03 |
| CSD-VLV-27 | ON-HP-04 | RR-VLV-29 | ON-LPSW-04 |
| CSD-VLV-28 | ON-HP-05 | RR-VLV-30 | ON-N-01 |
| CSD-VLV-29 | ON-HP-06 | RR-VLV-31 | ON-AS-02 |
| CSD-VLV-30 | ON-C-02 | RR-VLV-31 | ON-MS-05 |
| CSD-VLV-31 | ON-LP-05 | RR-VLV-32 | ON-HP-05 |
| CSD-VLV-34 | ON-LPSW-02 | new | ON-LP-07 |
| CSD-VLV-36 | deleted | new | ON-PR-01 |
| CSD-VLV-37 | ON-HP-07 | new | ON-RC-02 |

224

- 3 The revisions made to the site program to comply with the NRC SER are as follows:
- 3.1 Relief GNR-VLV-10 has been revised to clarify Duke Power's position on testing of additional relief valves in the event one fails.
 - 3.2 Relief GNR-VLV-11 has been deleted as per discussion in TER Section 2.2.
 - 3.3 Relief RR-PMP-01 has been deleted since upgraded vibration instrumentation has been installed.
 - 3.4 Relief GNR-PMP-03 has been deleted since it was redundant with RR-PMP-02.
 - 3.5 Relief RR-PMP-02 has been re-classified as an interim relief request. RR-PMP-02 has been revised to discuss when the new flow instrumentation will be installed and to discuss the accuracy of the existing "A" LPI train flow instrumentation. The relief was also revised to simply reference GNR-PMP-05 for the vibration instrumentation requirements and to remove any reference to alternate acceptance criteria.
 - 3.6 Relief GNR-PMP-04 has been deleted since relief for setting alternate acceptance criteria is not required.
 - 3.7 Relief GNR-VLV-07 has been deleted since this relief was denied.
 - 3.8 Relief RR-VLV-12 has been deleted since the relief is no longer required because the valves were replaced.

- 3.9 Relief RR-VLV-11 has been re-classified as an interim relief request. RR-VLV-11 has been revised to clarify why its subject valves cannot be disassembled.
- 3.10 Section 2 of generic relief GNR-PMP-02 has been revised to include only positive displacement pumps.
- 3.11 Relief RR-VLV-32 has been deleted since relief is not required for the method of determining acceptable seat leakage.
- 3.12 Relief GNR-PMP-05 has been reclassified as an interim relief request. GNR-PMP-05 has been revised to state that all vibration instrumentation will meet Code accuracy requirements by August 1, 1995.
- 3.13 Relief RR-PMP-03 was deleted since relief is not required for non-ASME Code Class components.
- 3.14 Relief RR-PMP-04 was deleted since relief is not required for non-ASME Code Class components.
- 3.15 Relief GNR-VLV-02 has been deleted since relief will not be required and OM-10 will be followed.
- 3.16 Relief GNR-VLV-04 has been deleted since OM-10 does not require the valve to be placed in service (declared operable) before startup like IWV-3417(b).
- 3.17 Relief GNR-VLV-05 has been deleted since OM-10 was adopted for valve testing.
- 3.18 Relief GNR-VLV-06 has been deleted since OM-10 does not require relief for testing cold shutdown frequency valves every cold shutdown.
- 3.19 Relief GNR-VLV-09 has been deleted since OM-10 was adopted for valve testing.

4 Additional changes to the site program are as follows:

- 4.1 Deferral ON-PR-01 has been written to document that Technical Specification 3.6 does not allow for the subject valves to be stroked at or above Hot Shutdown conditions.
- 4.2 Deferral ON-RC-02 has been written to document that stroking the subject valves above cold shutdown conditions will cause unnecessary reactor coolant system pressure transients.
- 4.3 Deferral ON-HP-07 has been written to document that exercising the subject valves will induce undesirable transients within the letdown coolers which can compromise the integrity of the reactor coolant system pressure boundary.
- 4.4 Relief GNR-VLV-01 has been deleted since the request was for relief from IWV-3427(b) and OM-10 has no similar requirements.
- 4.5 Valves 1DW-155 and 1DW-156 have been re-classified as passive valves. Consequently, relief RR-VLV-18 has been deleted.
- 4.6 Deferral ON-LP-07 has been written to document that Technical Specifications only allow stroking LP-17 and LP-18 at a cold shutdown frequency.

224

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| AUXILIARY STEAM | | | | | | | | | | | | | | |
| 1AS-001 | OFD-128A-1.1 | H7 | N | C | ACT | Check | SA | | | | ON-AS-02 | PS thru normal operations | Sample Disassemble | 22a |
| 1AS-039 | OFD-122A-1.4 | H6 | C | C | ACT | Check | SA | FS-Q | | | ON-AS-01 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 1AS-040 | OFD-128A-1.1 | B2 | N | B | ACT | Gate | MO | FS-Q | | | | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|---------------------------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|----------------|----------------------|-----|
| BUILDING SPRAY (REACTOR) | | | | | | | | | | | | | | |
| 1BS-001 | OFD-103A-1.1 | J8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 1BS-002 | OFD-103A-1.1 | E8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 1BS-005 | OFD-102A-1.1 | E8 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 1BS-006 | OFD-102A-1.1 | C10 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 1BS-011 | OFD-103A-1.1 | J6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 1BS-014 | OFD-103A-1.1 | J10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |
| 1BS-016 | OFD-103A-1.1 | E6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 1BS-019 | OFD-103A-1.1 | E10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| FEEDWATER | | | | | | | | | | | | | | |
| 1FDW-032 | OFD-121B-1.3 | J7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 1FDW-033 | OFD-121B-1.3 | J6 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 1FDW-035 | OFD-121B-1.3 | L7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 1FDW-039 | OFD-121D-1.1 | J10 | B | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | | 22 |
| 1FDW-041 | OFD-121B-1.3 | D7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 1FDW-042 | OFD-121B-1.3 | E6 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 1FDW-044 | OFD-121B-1.3 | F7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 1FDW-091 | OFD-121D-1.1 | I2 | N | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1FDW-103 | OFD-121B-1.5 | K8 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-104 | OFD-121B-1.5 | C8 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-105 | OFD-110A-1.1 | D2 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-106 | OFD-110A-1.1 | D6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-107 | OFD-110A-1.1 | F3 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-108 | OFD-110A-1.1 | F6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 1FDW-232 | OFD-121D-1.1 | K13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-233 | OFD-121D-1.1 | D13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-311 | OFD-121D-1.1 | J6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-312 | OFD-121D-1.1 | E6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-315 | OFD-121D-1.1 | K10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 1FDW-316 | OFD-121D-1.1 | D10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 1FDW-317 | OFD-121D-1.1 | K10 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-318 | OFD-121D-1.1 | D10 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-329 | OFD-121B-1.5 | J8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 1FDW-331 | OFD-121B-1.5 | D8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| 1FDW-334 | OFD-121B-1.5 | L6 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 1FDW-335 | OFD-121B-1.5 | C6 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 1FDW-345 | OFD-121D-1.1 | K12 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-346 | OFD-121D-1.1 | D12 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-347-SSF | OFD-121D-1.1 | D13 | C | B | ACT | Gate | MO | FS-CS | | | ON-SSF-05 | | | 22 |
| 1FDW-370 | OFD-121D-1.1 | K3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1FDW-372 | OFD-121D-1.1 | K7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1FDW-373 | OFD-121D-1.1 | K7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-378 | OFD-121D-1.1 | K3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1FDW-380 | OFD-121D-1.1 | D3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1FDW-382 | OFD-121D-1.1 | D7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1FDW-383 | OFD-121D-1.1 | D7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 1FDW-388 | OFD-121D-1.1 | D3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1FDW-432 | OFD-121D-1.1 | F10 | C | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | 22a | |
| 1FDW-442 | OFD-121D-1.1 | D11 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| 1HP-109 | OFD-101A-1.3 | G10 | B | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-11 | | | 22 |
| 1HP-112 | OFD-101A-1.3 | E6 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 1HP-113 | OFD-101A-1.3 | D10 | B | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-11 | | | 22 |
| 1HP-126 | OFD-101A-1.4 | J13 | A | C | ACT | StopCheck | SA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 1HP-127 | OFD-101A-1.4 | J13 | A | C | ACT | StopCheck | SA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 1HP-144 | OFD-101A-1.4 | G13 | B | A/C | ACT | StopCheck | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-145 | OFD-101A-1.4 | F13 | B | A/C | ACT | StopCheck | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-146 | OFD-101A-1.4 | H13 | B | A/C | ACT | StopCheck | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-147 | OFD-101A-1.4 | I12 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-152 | OFD-101A-1.4 | D14 | A | C | ACT | StopCheck | SA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 1HP-153 | OFD-101A-1.4 | E13 | A | C | ACT | StopCheck | SA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 1HP-155 | OFD-127B-1.2 | H7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 1HP-156 | OFD-127B-1.2 | I7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 1HP-188 | OFD-101A-1.4 | D11 | A | C | ACT | Check | SA | PS-CS FS-RF | | | ON-HP-14 | | | 22 |
| 1HP-189 | OFD-101A-1.2 | F6 | C | C | ACT | Check | SA | | | | ON-HP-08 | Sample Disassemble | | 22 |
| 1HP-194 | OFD-101A-1.4 | J10 | A | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-15 | | | 22 |
| 1HP-247 | OFD-101A-1.3 | K10 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 1HP-248 | OFD-101A-1.3 | L10 | B | C | ACT | StopCheck | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 1HP-249 | OFD-101A-1.3 | H9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 1HP-250 | OFD-101A-1.3 | I9 | B | C | ACT | StopCheck | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 1HP-251 | OFD-101A-1.3 | D9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 1HP-252 | OFD-101A-1.3 | E9 | B | C | ACT | StopCheck | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|---------|----------------------|-----|
| 1HP-302 | OFD-101A-1.1 | F10 | C | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 1HP-304 | OFD-101A-1.1 | G6 | C | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 1HP-363 | OFD-101A-1.2 | F7 | C | B | ACT | Globe | MA | FS-Q | | | | | | 22 |
| 1HP-364 | OFD-101A-1.2 | F7 | B | C | ACT | Check | SA | | | | ON-HP-09 | | Sample Disassemble | 22a |
| 1HP-390 | OFD-101A-1.4 | F10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-393 | OFD-101A-1.4 | I10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-398-SSF | OFD-101A-1.5 | F11 | B | B | ACT | Gate | MO | FS-CS | | | ON-SSF-03 | | | 22 |
| 1HP-399-SSF | OFD-101A-1.5 | G13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 1HP-400-SSF | OFD-101A-1.5 | H13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 1HP-401-SSF | OFD-101A-1.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 1HP-402-SSF | OFD-101A-1.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 1HP-404 | OFD-101A-1.5 | G9 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 1HP-405-SSF | OFD-101A-1.5 | H10 | B | A | PAS | Gate | MO | | LJ-RF | | | | | 22 |
| 1HP-409 | OFD-101A-1.4 | D7 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 1HP-410 | OFD-101A-1.4 | H7 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 1HP-417-SSF | OFD-101A-1.5 | H9 | B | A | ACT | Globe | MO | FS-Q | LJ-RF | | | | | 22 |
| 1HP-426-SSF | OFD-101A-1.5 | J9 | B | A | ACT | Globe | MO | FS-CS | LJ-RF | | ON-SSF-04 | | | 22 |
| 1HP-428-SSF | OFD-101A-1.5 | J13 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 1HP-454 | OFD-101A-1.4 | G10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 1HP-457 | OFD-101A-1.4 | H10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|------------------------|----------------------|-----|
| LOW PRESSURE INJECTION | | | | | | | | | | | | | | |
| 1LP-001 | OFD-102A-1.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | ON-LP-01 | | | 22 |
| 1LP-002 | OFD-102A-1.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | ON-LP-01 | | | 22 |
| 1LP-009 | OFD-102A-1.2 | I7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-010 | OFD-102A-1.2 | G7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-012 | OFD-102A-1.2 | K11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 1LP-014 | OFD-102A-1.2 | E11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 1LP-015 | OFD-102A-1.2 | L11 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-016 | OFD-102A-1.2 | O-4 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-017 | OFD-102A-1.2 | K13 | B | B | ACT | Gate | MO | FS-CS | | | ON-LP-07 | | | 22a |
| 1LP-018 | OFD-102A-1.2 | E13 | B | B | ACT | Gate | MO | FS-CS | | | ON-LP-07 | | | 22a |
| 1LP-019 | OFD-102A-1.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-020 | OFD-102A-1.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-021 | OFD-102A-1.1 | F7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-022 | OFD-102A-1.1 | D7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LP-028 | OFD-102A-1.1 | H10 | B | B | ACT | Gate | MA | FS-CS | | | ON-LP-05 | | | 22 |
| 1LP-029 | OFD-102A-1.1 | F6 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 1LP-030 | OFD-102A-1.1 | D6 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 1LP-031 | OFD-102A-1.2 | K5 | B | C | ACT | Check | SA | PS-Q FS-CS | | | ON-LP-04 | | | 22 |
| 1LP-033 | OFD-102A-1.2 | E6 | B | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LP-047 | OFD-102A-1.2 | E14 | A | A/C | ACT | Check | SA | FS-CS | LT-CS | | ON-LP-02 | Inter-System LOCA Test | | 22 |
| 1LP-048 | OFD-102A-1.2 | K14 | A | A/C | ACT | Check | SA | FS-CS | LT-FS | | ON-LP-02 | Inter-System LOCA Test | | 22 |
| 1LP-055 | OFD-101A-1.3 | K3 | B | C | ACT | Check | SA | PS-CS FS-RF | | | ON-LP-06 | | | 22 |
| 1LP-057 | OFD-101A-1.3 | C3 | B | C | ACT | Check | SA | PS-CS FS-RF | | | ON-LP-06 | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-----------------------------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| LOW PRESSURE SERVICE WATER | | | | | | | | | | | | | | |
| 1LPSW-004 | OFD-124B-1.1 | K6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LPSW-005 | OFD-124B-1.1 | H6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LPSW-006 | OFD-124B-1.4 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-LPSW-01 | | | 22 |
| 1LPSW-015 | OFD-124B-1.4 | G14 | B | A | ACT | Butterfly | MO | FS-CS | LJ-RF | | ON-LPSW-01 | | | 22 |
| 1LPSW-018 | OFD-124B-1.2 | D3 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 1LPSW-021 | OFD-124B-1.2 | D8 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 1LPSW-024 | OFD-124B-1.2 | D12 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 1LPSW-025 | OFD-124A-1.1 | D7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LPSW-028 | OFD-124A-1.1 | J7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LPSW-031 | OFD-124A-1.1 | G7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LPSW-075 | OFD-124B-1.1 | K6 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LPSW-076 | OFD-124B-1.1 | H6 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 1LPSW-137 | OFD-124A-1.3 | K11 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LPSW-138 | OFD-124A-1.3 | L11 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 1LPSW-139 | OFD-124A-1.1 | C8 | C | B | ACT | Butterfly | MO | | | | ON-LPSW-04 | | | 22 |
| 1LPSW-148 | OFD-124B-1.1 | L4 | C | C | ACT | Check | SA | FS-Q | | | ON-LPSW-03 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22 |
| 1LPSW-151 | OFD-124B-1.1 | F3 | C | C | ACT | Check | SA | FS-Q | | | ON-LPSW-03 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 1LPSW-251 | OFD-124B-1.1 | J8 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 1LPSW-252 | OFD-124B-1.1 | I8 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 1LPSW-516 | OFD-124A-1.3 | K5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 1LPSW-525 | OFD-124A-1.3 | J5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 1LPSW-565 | OFD-124B-1.2 | J8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1LPSW-566 | OFD-124B-1.2 | I8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |

**Unit 1 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|---------------------------|----------------------|-----|
| MAIN STEAM | | | | | | | | | | | | | | |
| 1MS-001 | OFD-122A-1.1 | J9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-002 | OFD-122A-1.1 | J4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-003 | OFD-122A-1.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-004 | OFD-122A-1.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-005 | OFD-122A-1.1 | J8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-006 | OFD-122A-1.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-007 | OFD-122A-1.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-008 | OFD-122A-1.1 | J6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-009 | OFD-122A-1.1 | D9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-010 | OFD-122A-1.1 | D4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-011 | OFD-122A-1.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-012 | OFD-122A-1.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-013 | OFD-122A-1.1 | D8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-014 | OFD-122A-1.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-015 | OFD-122A-1.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-016 | OFD-122A-1.1 | D6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 1MS-017 | OFD-122A-1.2 | I5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 1MS-024 | OFD-122A-1.2 | H3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1MS-025 | OFD-122A-1.2 | G3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 1MS-026 | OFD-122A-1.2 | D5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 1MS-033 | OFD-122A-1.2 | E3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 1MS-034 | OFD-122A-1.2 | F3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 1MS-035 | OFD-122A-1.3 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |
| 1MS-036 | OFD-122A-1.3 | F2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| AUXILIARY STEAM | | | | | | | | | | | | | | |
| 2AS-001 | OFD-128A-2.1 | H6 | N | C | ACT | Check | SA | | | | ON-AS-02 | PS thru normal operations | Sample Disassemble | 22a |
| 2AS-039 | OFD-122A-2.4 | H6 | C | C | ACT | Check | SA | FS-Q | | | ON-AS-01 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 2AS-040 | OFD-128A-2.1 | H3 | N | B | ACT | Gate | MO | FS-Q | | | | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGORY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|---------------------------------|-----------------|---------------|---------------|------------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|----------------|----------------------|-----|
| BUILDING SPRAY (REACTOR) | | | | | | | | | | | | | | |
| 2BS-001 | OFD-103A-2.1 | J8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 2BS-002 | OFD-103A-2.1 | E8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 2BS-005 | OFD-102A-2.1 | E8 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 2BS-006 | OFD-102A-2.1 | C10 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 2BS-011 | OFD-103A-2.1 | J6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 2BS-014 | OFD-103A-2.1 | J10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |
| 2BS-016 | OFD-103A-2.1 | E6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 2BS-019 | OFD-103A-2.1 | E10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| FEEDWATER | | | | | | | | | | | | | | |
| 2FDW-032 | OFD-121B-2.3 | J6 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 2FDW-033 | OFD-121B-2.3 | K5 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 2FDW-035 | OFD-121B-2.3 | K6 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 2FDW-039 | OFD-121D-2.1 | J10 | B | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | | 22 |
| 2FDW-041 | OFD-121B-2.3 | D5 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 2FDW-042 | OFD-121B-2.3 | E5 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 2FDW-044 | OFD-121B-2.3 | F7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 2FDW-091 | OFD-121D-2.1 | I2 | N | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2FDW-103 | OFD-121B-2.5 | J9 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-104 | OFD-121B-2.5 | C9 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-105 | OFD-110A-2.1 | F3 | B | A | ACT | Globe | MO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-106 | OFD-110A-2.1 | F6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-107 | OFD-110A-2.1 | D3 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-108 | OFD-110A-2.1 | D6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 2FDW-232 | OFD-121D-2.1 | K13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-233 | OFD-121D-2.1 | D13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-311 | OFD-121D-2.1 | J6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-312 | OFD-121D-2.1 | E7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-315 | OFD-121D-2.1 | K10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 2FDW-316 | OFD-121D-2.1 | D10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 2FDW-317 | OFD-121D-2.1 | K10 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-318 | OFD-121D-2.1 | D10 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-329 | OFD-121B-2.5 | I8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 2FDW-331 | OFD-121B-2.5 | C8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGORY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|---------------|---------------|------------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| 2FDW-334 | OFD-121B-2.5 | K7 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 2FDW-335 | OFD-121B-2.5 | C6 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 2FDW-345 | OFD-121D-2.1 | K12 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-346 | OFD-121D-2.1 | D12 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-347-SSF | OFD-121D-2.1 | D13 | C | B | ACT | Gate | MO | FS-CS | | | ON-SSF-05 | | | 22 |
| 2FDW-370 | OFD-121D-2.1 | K3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2FDW-372 | OFD-121D-2.1 | K7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2FDW-373 | OFD-121D-2.1 | K7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-378 | OFD-121D-2.1 | K3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2FDW-380 | OFD-121D-2.1 | D3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2FDW-382 | OFD-121D-2.1 | D7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2FDW-383 | OFD-121D-2.1 | D6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 2FDW-388 | OFD-121D-2.1 | D3 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2FDW-432 | OFD-121D-2.1 | E10 | C | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | 22a | |
| 2FDW-442 | OFD-121D-2.1 | D11 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|--------------|-----------|------------|--------------|---------|------------|----------|-------------------|-------------------|--------------|--------------------|-----------------------------|-------------------|-----|
| 2HP-112 | OFD-101A-2.3 | D6 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 2HP-113 | OFD-101A-2.3 | D10 | B | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-11 | | | 22 |
| 2HP-126 | OFD-101A-2.4 | J13 | A | C | ACT | Stop Check | MA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 2HP-127 | OFD-101A-2.4 | J13 | A | C | ACT | Stop Check | MA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 2HP-144 | OFD-101A-2.4 | F12 | B | A/C | ACT | Stop Check | MA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 2HP-145 | OFD-101A-2.4 | G12 | B | A/C | ACT | Stop Check | MA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 2HP-146 | OFD-101A-2.4 | H12 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 2HP-147 | OFD-101A-2.4 | I12 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 2HP-152 | OFD-101A-2.4 | D13 | A | C | ACT | Stop Check | MA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 2HP-153 | OFD-101A-2.4 | E13 | A | C | ACT | Stop Check | MA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 2HP-155 | OFD-127B-2.2 | H7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 2HP-156 | OFD-127B-2.2 | I7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 2HP-188 | OFD-101A-2.4 | D11 | A | C | ACT | Check | SA | PS-CS FS-RF | | | ON-HP-14 | | | 22 |
| 2HP-189 | OFD-101A-2.2 | F5 | C | C | ACT | Check | SA | | | | ON-HP-08 | Sample Disassemble | | 22a |
| 2HP-194 | OFD-101A-2.4 | J10 | A | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-15 | | | 22 |
| 2HP-247 | OFD-101A-2.3 | K10 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 2HP-248 | OFD-101A-2.3 | L10 | B | C | ACT | Stop Check | MA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 2HP-249 | OFD-101A-2.3 | H9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 2HP-250 | OFD-101A-2.3 | I9 | B | C | ACT | Stop Check | MA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 2HP-251 | OFD-101A-2.3 | D9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 2HP-252 | OFD-101A-2.3 | E9 | B | C | ACT | Stop Check | MA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 2HP-286 | OFD-101A-2.4 | H10 | B | A/C | ACT | Stop Check | MA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 2HP-302 | OFD-101A-2.1 | F8 | C | C | PAS | Relief | SA | RV-RV | | | | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|---------|----------------------|-----|
| 2HP-363 | OFD-101A-2.2 | F7 | C | B | ACT | Gate | MA | FS-CS | | | | | | 22 |
| 2HP-364 | OFD-101A-2.2 | F7 | B | C | ACT | Check | SA | | | | ON-HP-09 | | Sample Disassemble | 22a |
| 2HP-389 | OFD-101A-2.4 | I10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 2HP-390 | OFD-101A-2.4 | G10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 2HP-398-SSF | OFD-101A-2.5 | F11 | B | B | ACT | Gate | MO | FS-CS | | | ON-SSF-03 | | | 22 |
| 2HP-399-SSF | OFD-101A-2.5 | H13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 2HP-400-SSF | OFD-101A-2.5 | G13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 2HP-401-SSF | OFD-101A-2.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 2HP-402-SSF | OFD-101A-2.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 2HP-404 | OFD-101A-2.5 | G9 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 2HP-405-SSF | OFD-101A-2.5 | H10 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 2HP-409 | OFD-101A-2.4 | E8 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 2HP-410 | OFD-101A-2.4 | F7 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 2HP-417-SSF | OFD-101A-2.5 | I9 | B | A | ACT | Globe | MO | FS-Q | LJ-RF | | | | | 22 |
| 2HP-426-SSF | OFD-101A-2.5 | J9 | B | A | ACT | Globe | MO | FS-CS | LJ-RF | | ON-SSF-04 | | | 22 |
| 2HP-428-SSF | OFD-101A-2.5 | J13 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 2HP-454 | OFD-101A-2.4 | G10 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|------------------------|----------------------|-----|
| LOW PRESSURE INJECTION | | | | | | | | | | | | | | |
| 2LP-001 | OFD-102A-2.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | ON-LP-01 | | | 22 |
| 2LP-002 | OFD-102A-2.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | ON-LP-01 | | | 22 |
| 2LP-003 | OFD-102A-2.1 | H6 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-009 | OFD-102A-2.2 | I8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-010 | OFD-102A-2.2 | H8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-012 | OFD-102A-2.2 | K11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 2LP-014 | OFD-102A-2.2 | E11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 2LP-015 | OFD-102A-2.2 | L11 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-016 | OFD-102A-2.2 | D11 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-017 | OFD-102A-2.2 | K12 | B | B | ACT | Gate | MO | FS-CS | | | ON-LP-07 | | | 22a |
| 2LP-018 | OFD-102A-2.2 | E13 | B | B | ACT | Gate | MO | FS-CS | | | ON-LP-07 | | | 22a |
| 2LP-019 | OFD-102A-2.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-020 | OFD-102A-2.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-021 | OFD-102A-2.1 | E7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-022 | OFD-102A-2.1 | D7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LP-028 | OFD-102A-2.1 | H10 | B | B | ACT | Gate | MA | FS-CS | | | ON-LP-05 | | | 22 |
| 2LP-029 | OFD-102A-2.1 | F6 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 2LP-030 | OFD-102A-2.1 | D6 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 2LP-031 | OFD-102A-2.2 | K5 | B | C | ACT | Check | SA | PS-Q FS-CS | | | ON-LP-04 | | | 22 |
| 2LP-033 | OFD-102A-2.2 | E5 | B | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2LP-047 | OFD-102A-2.2 | E14 | A | A/C | ACT | Check | SA | FS-CS | LT-CS | | ON-LP-02 | Inter-System LOCA Test | | 22 |
| 2LP-048 | OFD-102A-2.2 | K14 | A | A/C | ACT | Check | SA | FS-CS | LT-CS | | ON-LP-02 | Inter-System LOCA Test | | 22 |
| 2LP-055 | OFD-101A-2.3 | K3 | B | C | ACT | Check | SA | PS-CS FS-RF | | | ON-LP-06 | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-----------------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| LOW PRESSURE SERVICE WATER | | | | | | | | | | | | | | |
| 2LPSW-004 | OFD-124B-2.1 | K6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LPSW-005 | OFD-124B-2.1 | H6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LPSW-006 | OFD-124B-2.4 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-LPSW-01 | | | 22 |
| 2LPSW-015 | OFD-124B-2.4 | G14 | B | A | ACT | Butterfly | MO | FS-CS | LJ-RF | | ON-LPSW-01 | | | 22 |
| 2LPSW-018 | OFD-124B-2.2 | D3 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 2LPSW-021 | OFD-124B-2.2 | D8 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 2LPSW-024 | OFD-124B-2.2 | D12 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 2LPSW-075 | OFD-124B-2.1 | K7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2LPSW-076 | OFD-124B-2.1 | H7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2LPSW-137 | OFD-124A-2.2 | K11 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LPSW-138 | OFD-124A-2.3 | L11 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 2LPSW-148 | OFD-124B-2.1 | L7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2LPSW-151 | OFD-124B-2.1 | G10 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 2LPSW-251 | OFD-124B-2.1 | J8 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 2LPSW-252 | OFD-124B-2.1 | I8 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 2LPSW-503 | OFD-124B-2.1 | G3 | C | C | ACT | Check | SA | FS-Q | | | ON-LPSW-03 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22 |
| 2LPSW-516 | OFD-124A-2.3 | K5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 2LPSW-525 | OFD-124A-2.3 | J5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 2LPSW-565 | OFD-124B-2.2 | J8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LPSW-566 | OFD-124B-2.2 | I8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2LPSW-900 | OFD-124C-2.2 | H10 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |

**Unit 2 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|---------------------------|----------------------|-----|
| MAIN STEAM | | | | | | | | | | | | | | |
| 2MS-001 | OFD-122A-2.1 | J9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-002 | OFD-122A-2.1 | J4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-003 | OFD-122A-2.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-004 | OFD-122A-2.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-005 | OFD-122A-2.1 | J8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-006 | OFD-122A-2.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-007 | OFD-122A-2.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-008 | OFD-122A-2.1 | J6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-009 | OFD-122A-2.1 | D9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-010 | OFD-122A-2.1 | D4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-011 | OFD-122A-2.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-012 | OFD-122A-2.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-013 | OFD-122A-2.1 | D8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-014 | OFD-122A-2.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-015 | OFD-122A-2.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-016 | OFD-122A-2.1 | D6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 2MS-017 | OFD-122A-2.2 | I5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 2MS-024 | OFD-122A-2.2 | H3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2MS-025 | OFD-122A-2.2 | G3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 2MS-026 | OFD-122A-2.2 | D5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 2MS-033 | OFD-122A-2.2 | E3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 2MS-034 | OFD-122A-2.2 | F3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 2MS-035 | OFD-122A-2.3 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |
| 2MS-036 | OFD-122A-2.3 | F2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| AUXILIARY STEAM | | | | | | | | | | | | | | |
| 3AS-001 | OFD-128A-3.1 | G6 | N | C | ACT | Check | SA | | | | ON-AS-02 | PS thru normal operations | Sample Disassemble | 22a |
| 3AS-039 | OFD-122A-3.4 | H6 | C | C | ACT | Check | SA | FS-Q | | | ON-AS-01 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 3AS-040 | OFD-128A-3.1 | F3 | N | B | ACT | Gate | MO | FS-Q | | | | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|----------------|----------------------|-----|
| BUIDING SPRAY (REACTOR) | | | | | | | | | | | | | | |
| 3BS-001 | OFD-103A-3.1 | J8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 3BS-002 | OFD-103A-3.1 | E8 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 3BS-005 | OFD-102A-3.1 | F8 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 3BS-006 | OFD-102A-3.1 | C9 | B | C | ACT | Check | SA | PS-Q | | 11 | | | | 22 |
| 3BS-011 | OFD-103A-3.1 | J6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 3BS-014 | OFD-103A-3.1 | J10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |
| 3BS-016 | OFD-103A-3.1 | E6 | B | C | ACT | Check | SA | PS-Q | | | ON-BS-01 | | Sample Disassemble | 22a |
| 3BS-019 | OFD-103A-3.1 | E10 | B | C | ACT | Check | SA | PS-RF | | | ON-BS-02 | PS is with air | Sample Disassemble | 22a |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| FEEDWATER | | | | | | | | | | | | | | |
| 3FDW-032 | OFD-121B-3.3 | J7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 3FDW-033 | OFD-121B-3.3 | K6 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 3FDW-035 | OFD-121B-3.3 | K7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 3FDW-039 | OFD-121D-3.1 | J10 | B | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | | 22 |
| 3FDW-041 | OFD-121B-3.3 | D7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-03 | | | 22 |
| 3FDW-042 | OFD-121B-3.3 | E6 | C | B | ACT | Gate | MO | FS-CS | | | ON-FDW-01 | | | 22 |
| 3FDW-044 | OFD-121B-3.3 | F7 | C | B | ACT | Globe | AO | FS-CS | | | ON-FDW-01 | | | 22 |
| 3FDW-091 | OFD-121D-3.1 | H3 | N | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3FDW-103 | OFD-121B-3.5 | J9 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-104 | OFD-121B-3.5 | D9 | B | A | PAS | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-105 | OFD-110A-3.1 | D2 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-106 | OFD-110A-3.1 | D6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-107 | OFD-110A-3.1 | F3 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-108 | OFD-110A-3.1 | F6 | B | A | ACT | Gate | AO | FS-Q | LJ-RF | | | | | 22 |
| 3FDW-232 | OFD-121D-3.1 | K13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-233 | OFD-121D-3.1 | D13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-311 | OFD-121D-3.1 | I6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-312 | OFD-121D-3.1 | E6 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-315 | OFD-121D-3.1 | K10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 3FDW-316 | OFD-121D-3.1 | D10 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 3FDW-317 | OFD-121D-3.1 | K10 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-318 | OFD-121D-3.1 | D10 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-329 | OFD-121B-3.5 | J8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 3FDW-331 | OFD-121B-3.5 | D8 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--------------------|----------------------|-----|
| 3FDW-334 | OFD-121B-3.5 | L6 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 3FDW-335 | OFD-121B-3.5 | C6 | B | A | PAS | Gate | MA | | LJ-RF | | | | | 22 |
| 3FDW-345 | OFD-121D-3.1 | K13 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-346 | OFD-121D-3.1 | D12 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-347-SSF | OFD-121D-3.1 | D13 | C | B | ACT | Gate | MO | FS-CS | | | ON-SSF-05 | | | 22 |
| 3FDW-370 | OFD-121D-3.1 | K4 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3FDW-372 | OFD-121D-3.1 | K7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3FDW-373 | OFD-121D-3.1 | K7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-378 | OFD-121D-3.1 | D12 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3FDW-380 | OFD-121D-3.1 | D4 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3FDW-382 | OFD-121D-3.1 | D7 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3FDW-383 | OFD-121D-3.1 | D7 | C | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |
| 3FDW-388 | OFD-121D-3.1 | D4 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3FDW-432 | OFD-121D-3.1 | E10 | C | C | ACT | Check | SA | | | | ON-FDW-04 | Sample Disassemble | 22a | |
| 3FDW-442 | OFD-121D-3.1 | D11 | B | C | ACT | Check | SA | FS-CS | | | ON-FDW-02 | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|---------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|-----------------------------|----------------------|-----|
| 3HP-109 | OFD-101A-3.3 | G10 | B | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-11 | | | 22 |
| 3HP-112 | OFD-101A-3.3 | C5 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 3HP-113 | OFD-101A-3.3 | D10 | B | C | ACT | Check | SA | PS-Q FS-RF | | | ON-HP-11 | | | 22 |
| 3HP-126 | OFD-101A-3.4 | J11 | A | C | ACT | Stop Check | SA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 3HP-127 | OFD-101A-3.4 | J11 | A | C | ACT | Stop Check | SA | PS-CS FS-RF | | | ON-HP-12 | | | 22 |
| 3HP-144 | OFD-101A-3.4 | H13 | B | A/C | ACT | Stop Check | SA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 3HP-145 | OFD-101A-3.4 | I13 | B | A/C | ACT | Stop Check | SA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 3HP-146 | OFD-101A-3.4 | G13 | B | A/C | ACT | Stop Check | SA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 3HP-147 | OFD-101A-3.4 | F13 | B | A/C | ACT | Stop Check | SA | FS-RF | LJ-RF | | ON-HP-17 | Reverse Direction Leak Test | | 22 |
| 3HP-152 | OFD-101A-3.4 | D13 | A | C | ACT | Stop Check | SA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 3HP-153 | OFD-101A-3.4 | E13 | A | C | ACT | Stop Check | SA | PS-CS FS-RF | | | ON-HP-13 | | | 22 |
| 3HP-155 | OFD-127B-3.2 | H7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 3HP-156 | OFD-127B-3.2 | I7 | B | A | PAS | Globe | MA | | LJ-RF | | | | | 22 |
| 3HP-188 | OFD-101A-3.4 | D10 | A | C | ACT | Check | SA | PS-CS FS-RF | | | ON-HP-14 | | | 22 |
| 3HP-189 | OFD-101A-3.2 | F5 | C | C | ACT | Check | SA | | | | ON-HP-08 | Sample Disassemble | | 22a |
| 3HP-194 | OFD-101A-3.4 | J8 | A | C | ACT | Check | SA | FS-Q FS-RF | | | ON-HP-15 | | | 22 |
| 3HP-247 | OFD-101A-3.3 | K9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 3HP-248 | OFD-101A-3.3 | H9 | B | C | ACT | Stop Check | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 3HP-249 | OFD-101A-3.3 | H9 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 3HP-250 | OFD-101A-3.3 | I9 | B | C | ACT | Stop Check | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |
| 3HP-251 | OFD-101A-3.3 | D8 | B | B | ACT | Globe | MA | FS-CS | | | ON-HP-06 | | | 22 |
| 3HP-252 | OFD-101A-3.3 | F8 | B | C | ACT | Stop Check | SA | | | | ON-HP-16 | Sample Disassemble | | 22a |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF. OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|--------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|---------------------|---------|----------------------|-----|
| 3HP-285 | OFD-101A-3.4 | F11 | B | A/C | ACT | Stop Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 3HP-302 | OFD-101A-3.1 | F8 | C | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 3HP-363 | OFD-101A-3.2 | F7 | C | B | ACT | Gate | MA | FS-Q | | | | | | 22 |
| 3HP-364 | OFD-101A-3.2 | F8 | B | C | ACT | Check | SA | | | | ON-HP-09 | | Sample Disassemble | 22a |
| 3HP-390 | OFD-101A-3.4 | I11 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 3HP-398-SSF | OFD-101A-3.5 | F11 | B | B | ACT | Gate | MO | FS-CS | | | ON-SSF-03 | | | 22 |
| 3HP-399-SSF | OFD-101A-3.5 | H13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 3HP-400-SSF | OFD-101A-3.5 | G13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 3HP-401-SSF | OFD-101A-3.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 3HP-402-SSF | OFD-101A-3.5 | F13 | B | C | ACT | Check | SA | FS-CS | | | ON-SSF-02 | | | 22 |
| 3HP-404 | OFD-101A-3.5 | G9 | B | C | PAS | Relief | SA | RV-RV | | | | | | 22 |
| 3HP-405-SSF | OFD-101A-3.5 | H10 | B | A | PAS | Gate | MO | | LJ-RF | | | | | 22 |
| 3HP-409 | OFD-101A-3.4 | E8 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 3HP-410 | OFD-101A-3.4 | I7 | B | B | ACT | Gate | MO | FS-CS | | | ON-HP-04 | | | 22 |
| 3HP-417-SSF | OFD-101A-3.5 | I9 | B | A | ACT | Globe | MO | FS-Q | LJ-RF | | | | | 22 |
| 3HP-426-SSF | OFD-101A-3.5 | K9 | B | A | ACT | Globe | MO | FS-CS | LJ-RF | | ON-SSF-04 | | | 22 |
| 3HP-428-SSF | OFD-101A-3.5 | J13 | B | A | ACT | Gate | MO | FS-Q | LJ-RF | | | | | 22 |
| 3HP-454 | OFD-101A-3.4 | H11 | B | A/C | ACT | Check | SA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |
| 3HP-457 | OFD-101A-3.4 | G11 | B | A/C | ACT | Stop Check | MA | FS-RF | LJ-RF | | ON-HP-17 | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COORD | ASME CLASS | VALVE CATGORY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------------------|-----------------|---------------|---------------|------------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|----------|------------------------|-----|
| LOW PRESSURE INJECTION | | | | | | | | | | | | | | |
| 3LP-001 | OFD-102A-3.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | | ON-LP-01 | | 22 |
| 3LP-002 | OFD-102A-3.1 | H2 | A | B | ACT | Gate | MO | FS-CS | | | | ON-LP-01 | | 22 |
| 3LP-003 | OFD-102A-3.1 | H6 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-009 | OFD-102A-3.2 | I7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-010 | OFD-102A-3.2 | G7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-012 | OFD-102A-3.2 | K11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 3LP-014 | OFD-102A-3.2 | E11 | B | B | ACT | Globe | MO | FS-Q | | | | | | 22 |
| 3LP-015 | OFD-102A-3.2 | K12 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-016 | OFD-102A-3.2 | E12 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-017 | OFD-102A-3.2 | K13 | B | B | ACT | Gate | MO | FS-CS | | | | ON-LP-07 | | 22a |
| 3LP-018 | OFD-102A-3.2 | E13 | B | B | ACT | Gate | MO | FS-CS | | | | ON-LP-07 | | 22a |
| 3LP-019 | OFD-102A-3.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-020 | OFD-102A-3.1 | D5 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-021 | OFD-102A-3.1 | E7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-022 | OFD-102A-3.1 | D7 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LP-028 | OFD-102A-3.1 | H10 | B | B | ACT | Gate | MA | FS-CS | | | | ON-LP-05 | | 22 |
| 3LP-029 | OFD-102A-3.1 | E7 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 3LP-030 | OFD-102A-3.1 | C6 | B | A/C | ACT | Check | SA | FS-Q | LT-RF | | | | | 22 |
| 3LP-031 | OFD-102A-3.2 | K5 | B | C | ACT | Check | SA | PS-Q FS-CS | | | | ON-LP-04 | | 22 |
| 3LP-033 | OFD-102A-3.2 | E5 | B | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LP-047 | OFD-102A-3.2 | E14 | A | A/C | ACT | Check | SA | FS-CS | LT-CS | | | ON-LP-02 | Inter-System LOCA Test | 22 |
| 3LP-048 | OFD-102A-3.2 | K14 | A | A/C | ACT | Check | SA | FS-CS | LT-CS | | | ON-LP-02 | Inter-System LOCA Test | 22 |
| 3LP-055 | OFD-101A-3.3 | K3 | B | C | ACT | Check | SA | PS-CS FS-RF | | | | ON-LP-06 | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-----------------------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|--|----------------------|-----|
| LOW PRESSURE SERVICE WATER | | | | | | | | | | | | | | |
| 3LPSW-004 | OFD-124B-3.1 | K6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LPSW-005 | OFD-124B-3.1 | H6 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LPSW-006 | OFD-124B-3.4 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-LPSW-01 | | | 22 |
| 3LPSW-015 | OFD-124B-3.4 | G14 | B | A | ACT | Butterfly | MO | FS-CS | LJ-RF | | ON-LPSW-01 | | | 22 |
| 3LPSW-018 | OFD-124B-3.2 | C3 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 3LPSW-021 | OFD-124B-3.2 | C8 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 3LPSW-024 | OFD-124B-3.2 | C12 | B | B | ACT | Butterfly | MO | FS-Q | | | | | | 22 |
| 3LPSW-045 | OFD-124A-3.1 | E10 | C | B | ACT | Butterfly | MO | FS-CS | | | ON-LPSW-02 | | | 22 |
| 3LPSW-075 | OFD-124B-3.1 | K6 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LPSW-076 | OFD-124B-3.1 | H6 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LPSW-121 | OFD-124A-3.1 | J7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LPSW-124 | OFD-124A-3.1 | G7 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LPSW-137 | OFD-124A-3.3 | K11 | C | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LPSW-138 | OFD-124A-3.3 | L11 | C | B | ACT | Globe | AO | FS-Q | | | | | | 22 |
| 3LPSW-148 | OFD-124B-3.1 | L4 | C | C | ACT | Check | SA | FS-Q | | | ON-LPSW-03 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 3LPSW-151 | OFD-124B-3.1 | F8 | C | C | ACT | Check | SA | FS-Q | | | | | | 22 |
| 3LPSW-404 | OFD-124B-3.1 | H7 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 3LPSW-405 | OFD-124B-3.1 | K7 | C | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 3LPSW-503 | OFD-124B-3.1 | F3 | C | C | ACT | Check | SA | FS-Q | | | ON-LPSW-03 | Q test in open direction SD to test in closed direction | Sample Disassemble | 22a |
| 3LPSW-516 | OFD-124A-3.3 | K5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 3LPSW-525 | OFD-124A-3.3 | J5 | N | B | ACT | Butterfly | AO | FS-Q | | | | | | 22 |
| 3LPSW-565 | OFD-124B-3.2 | I8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3LPSW-566 | OFD-124B-3.2 | I8 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |

**Unit 3 - Oconee Nuclear Station
Inservice Testing Program**

| VALVE NUMBER | FLOW DIAGRAM | FLOW COOR | ASME CLASS | VALVE CATGRY | ACT PAS | VALVE TYPE | ACT TYPE | TEST REQ'MT NO. 1 | TEST REQ'MT NO. 2 | RELIEF REQST | JUSTIF OF DEFERRAL | REMARKS | TEST ALTERNATIVES | REV |
|-------------------|-----------------|--------------|---------------|-----------------|------------|------------|-------------|-------------------------|-------------------------|-----------------|--------------------|---------------------------|----------------------|-----|
| MAIN STEAM | | | | | | | | | | | | | | |
| 3MS-001 | OFD-122A-3.1 | J9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-002 | OFD-122A-3.1 | J4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-003 | OFD-122A-3.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-004 | OFD-122A-3.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-005 | OFD-122A-3.1 | J8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-006 | OFD-122A-3.1 | J5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-007 | OFD-122A-3.1 | J7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-008 | OFD-122A-3.1 | J6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-009 | OFD-122A-3.1 | D9 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-010 | OFD-122A-3.1 | D4 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-011 | OFD-122A-3.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-012 | OFD-122A-3.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-013 | OFD-122A-3.1 | D8 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-014 | OFD-122A-3.1 | D5 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-015 | OFD-122A-3.1 | D7 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-016 | OFD-122A-3.1 | D6 | B | C | ACT | Relief | SA | RV-RV | | | | | | 22 |
| 3MS-017 | OFD-122A-3.2 | I5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 3MS-024 | OFD-122A-3.2 | H3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3MS-025 | OFD-122A-3.2 | G3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 3MS-026 | OFD-122A-3.2 | D5 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-02 | | | 22 |
| 3MS-033 | OFD-122A-3.2 | E3 | B | B | ACT | Gate | MO | FS-Q | | | | | | 22 |
| 3MS-034 | OFD-122A-3.2 | E3 | N | C | ACT | Check | SA | | | | ON-MS-05 | PS thru normal operations | Sample Disassemble | 22a |
| 3MS-035 | OFD-122A-3.3 | L2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |
| 3MS-036 | OFD-122A-3.3 | F2 | B | B | ACT | Gate | MO | FS-CS | | | ON-MS-03 | | | 22 |

4.3 VALVE JUSTIFICATION FOR DEFERRALS

229

| Justification for Deferral | Applicability | Status |
|----------------------------|---|------------------|
| ON-AS-01 | EFWPT AS Supply Checks | Written 02/13/95 |
| ON-AS-02 | Main Steam Supply Checks | Written 02/13/95 |
| ON-BS-01 | A or B RBSP Discharge Checks | Written 02/13/95 |
| ON-BS-02 | A or B RBS Containment Isol. Checks | Written 02/13/95 |
| ON-C-01 | MDEFWPs Suction from UST Block | Written 02/13/95 |
| ON-C-02 | MDEFWPs Suction from UST Check | Written 02/13/95 |
| ON-C-03 | MDEFWPs Suction from Hotwell Check | Written 02/13/95 |
| ON-CC-01 | CC Supply/Return Containment Isol. | Written 02/13/95 |
| ON-CC-02 | CC Supply Containment Isol. Check | Written 02/13/95 |
| ON-CF-01 | CFT A and B Outlet Checks | Written 02/13/95 |
| ON-CF-02 | LPI/CF Header Checks | Written 02/13/95 |
| ON-CF-03 | CFT A and B Inlet Checks | Written 02/13/95 |
| ON-CS-01 | Quench Tank Recirc. Containment Isol. Check | Written 02/13/95 |
| ON-FDW-01 | OTSG Startup Block and Control | Written 02/13/95 |
| ON-FDW-02 | TDEFWP Discharge Checks, EFW to OTSG A or B, and OTSG Emergency Header Checks | Written 02/13/95 |
| ON-FDW-03 | A or B OTSG Main Flow Control | Written 02/13/95 |
| ON-FDW-04 | Normal FDW to Emergency Checks | Written 02/13/95 |
| ON-HP-01 | Letdown Containment Isolation | Written 02/13/95 |
| ON-HP-02 | RCP Seal Return Containment Isol. | Written 02/13/95 |
| ON-HP-03 | HPI Loop A Emergency Injection Control | Written 02/13/95 |
| ON-HP-04 | HPI A or B Crossover Valves | Written 02/13/95 |
| ON-HP-05 | LDST Outlet Checks | Written 02/13/95 |
| ON-HP-06 | HPI Pump Min. Recirculation Block | Written 02/13/95 |
| ON-HP-07 | Letdown Containment Isolation | Written 02/13/95 |
| ON-HP-08 | RC Seal Return Line Check | Written 02/13/95 |
| ON-HP-09 | HPI Min. Recirc. to LPI Suction Check | Written 02/13/95 |
| ON-HP-10 | HPI Pump Emergency Suction Checks | Written 02/13/95 |
| ON-HP-11 | HPI Pump Discharge Checks | Written 02/13/95 |
| ON-HP-12 | A1 or A2 Loop Injection Stop Checks | Written 02/13/95 |
| ON-HP-13 | B1 or B2 Loop Injection Stop Checks | Written 02/13/95 |
| ON-HP-14 | HPI Loop B Emergency Injection Checks | Written 02/13/95 |
| ON-HP-15 | HPI Loop A Emergency/Normal Injection Checks | Written 02/13/95 |
| ON-HP-16 | HPI Pump Min. Recirculation Stop Checks | Written 02/13/95 |
| ON-HP-17 | RCP Seal Supply Containment Isol. Checks | Written 02/13/95 |
| ON-LP-01 | Decay Heat Drop Line Isolation | Written 02/13/95 |
| ON-LP-02 | A or B LPI Header Containment Isol. Checks | Written 02/13/95 |
| ON-LP-03 | Post-LOCA Boron Dilution Valves | Written 02/13/95 |
| ON-LP-04 | A LPI Pump Discharge | Written 02/13/95 |
| ON-LP-05 | BWST Outlet Isolation | Written 02/13/95 |
| ON-LP-06 | LPI Supply to HPI Isolation | Written 02/13/95 |
| ON-LP-07 | A or B LPI Header Isolation | Written 03/01/95 |
| ON-LPSW-01 | RCP Cooler Supply and Discharge Block | Written 02/13/95 |
| ON-LPSW-02 | U3 MTOT Cooler Supply Block | Written 02/13/95 |
| ON-LPSW-03 | Normal/Emergency Supply Checks to HPIP Motor | Written 02/13/95 |
| ON-LPSW-04 | U1 & 2 LPSW Seismic Isolation | Written 02/13/95 |
| ON-MS-01 | Turbine Stop | Written 02/13/95 |

229

| Justification for Deferral | Applicability | Status |
|----------------------------|--|------------------|
| ON-MS-02 | Main Steam Turbine Bypass | Written 02/13/95 |
| ON-MS-03 | MS Supply to FDWPTs Block | Written 02/13/95 |
| ON-MS-04 | MS Supply to SSRH Block | Written 02/13/95 |
| ON-MS-05 | MS Supply to AS Checks | Written 02/13/95 |
| ON-N-01 | CFT A and B Inlet Containment Isol. Checks | Written 02/13/95 |
| ON-PR-01 | RB Purge Containment Isolation | Written 02/13/95 |
| ON-RC-01 | RCS/Reactor Vessel Vent Block | Written 02/13/95 |
| ON-RC-02 | Pressurizer Spray Control | Written 02/13/95 |
| ON-SSF-01 | SSF ASW Supply to A OTSG | Written 02/13/95 |
| ON-SSF-02 | SSF RC Makeup Supply to RCP Seals | Written 02/13/95 |
| ON-SSF-03 | SSF RC Makeup to RCP Seals Block | Written 02/13/95 |
| ON-SSF-04 | Letdown to Spent Fuel Vent | Written 02/13/95 |
| ON-SSF-05 | SSF AFW Supply to B OTSG Control | Written 02/13/95 |

Justification for Deferrals written 02/13/95 were generated as a result of adopting the guidelines presented in OM-10. A cross-reference of 'old' Relief Requests and Cold Shutdown Justifications is contained in Attachment 1 (Summary of Program Changes) of the 02/21/95 Duke letter to the NRC (Response to 11/23/94 NRC SER).

Justification for Deferral

Item Number: ON-LP-07

Valve: 1LP-17, 2LP-17, and 3LP-17
1LP-18, 2LP-18, and 3LP-18

Flow Diagram: OFD-102A-1.2/K-13, OFD-102A-2.2/K-13, and OFD-102A-3.2/K-13
OFD-102A-1.2/E-13, OFD-102A-2.2/E-13, and OFD-102A-3.2/E-13

Code Category: B

ISI Class/Duke Class: B/B

Function: Open (ES actuated) to provide low pressure injection to the reactor vessel.

Test Requirement: Verify proper valve movement once per three months as required by OMa-1988 Part 10, 4.2.1.1.

Basis for Deferral: Technical Specification 4.5.1.2.1 only allows these valves to be stroked at a cold shutdown frequency.

Test Alternative & Frequency: The valves are stroked open and closed at a cold shutdown frequency.

- 4.3.6 As per NUREG-1482 and recommendations stated in ONS SER, the licensee recognizes the NRC's acceptance of nonintrusive techniques (N.I.T.) for testing check valves. The licensee in fact has purchased N.I.T. equipment and is investigating incorporation into the testing program. However, this N.I.T. equipment has only recently been introduced to the industry and was not supplied from the vendor under the elements of the Q.A. program as with other equipment utilized for testing safety related components. This presents the burden on the licensee to validate the technology (i.e. software qualifications, calculation validity, engineering correlation, etc.). Therefore, it is the licensee's position that (N.I.T.) is a voluntary option and will be evaluated on a specific application basis if full stroke exercising or sample disassembly cannot be performed.

4.4 Relief Valve Testing

Relief valves tested under the jurisdiction of this program will be tested per code requirements of OM-1, 1987, unless it has been determined to be impractical. This section of the program document is to provide the site's positions with regards to interpretations, guidance, and testing alternatives for relief valves. Relief valves shall be considered for inclusion in the program if they provide overpressure protection for portions of systems that perform a specific function in shutting down a reactor or in mitigating the consequences of an accident.

- 4.4.1 Relief valves that are not credited for assisting in mitigating the consequences of an accident and are only installed for over-pressure protection are considered passive.

22 a

4.5 Leak Rate Testing

All category A valves will be tested per OM-10, section 4.2.2.2, except those valves which function in the course of plant operation in a manner that demonstrates adequate seat leak-tightness need not be leakage tested. In such cases (i.e., Containment Purge Isolation Valves) proper administrative controls will be implemented and the valves leak tested during refueling outages.

- 4.5.1 Category A containment isolation valves shall be tested per 10CFR50, Appendix J and shall be included in the program per GL 89-04, Position 10. Where a valve is identified as a containment isolation valve in the Technical Specification or SAR and if it is determined to be an "active" valve with respect to this function, it will be exercised to the closed position when there is an associated requirement for leak testing.

4.6 Testing from Remote Location

Section 4.1 of OM-10 requires valves with remote position indication to be tested at least once every 2 years to verify that the valve operation is accurately indicated. Valves that have remote operating switches and/or power supplies (e.g. SSF valves) shall also be tested and verified for proper indication from the remote location. Other valve operating parameters, such as timing will not be performed from the remote location during this testing.

4.7 Post Maintenance/Modification Testing (Retest)

Discussion to be completed once NSD 408 -- Testing is published.

4.8 Fail-Safe Testing of Valves

All Fail-Safe valves shall be tested in accordance with OM-10, section 4.2.1.6. Control valves are typically excluded from testing in the IST program. However, if a control valve must change position to support a safety-related function and it has a fail-safe position, then it must be included in the program and tested to verify the ability to perform that function with power removed (or simulated power removal).