

# PRIORITY 1

ACCELERATED RIDS PROCESSING

## REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 9506200218      DOC. DATE: 95/06/12      NOTARIZED: NO      DOCKET #  
 FACIL: 50-269 Oconee Nuclear Station, Unit 1, Duke Power Co.      05000269  
       50-270 Oconee Nuclear Station, Unit 2, Duke Power Co.      05000270  
       50-287 Oconee Nuclear Station, Unit 3, Duke Power Co.      05000287

AUTH. NAME      AUTHOR AFFILIATION  
 HAMPTON, J.W.      Duke Power Co.  
 RECIP. NAME      RECIPIENT AFFILIATION  
                   Document Control Branch (Document Control Desk)

SUBJECT: Forwards third ten yr ISI interval Request for Relief 93-08 supplemental info, including B&W ltr dtd 950608 providing description of rev to B&W TR BAW-2228, "Fracture Mechanics Assessment of Postulated Outer Surfaces, Semi-Elliptical...."

DISTRIBUTION CODE: A047D      COPIES RECEIVED: LTR 1 ENCL 1 SIZE: 11  
 TITLE: OR Submittal: Inservice/Testing/Relief from ASME Code - GL-89-04

NOTES:

| RECIPIENT<br>ID CODE/NAME | COPIES<br>LTTR ENCL | RECIPIENT<br>ID CODE/NAME | COPIES<br>LTTR ENCL |
|---------------------------|---------------------|---------------------------|---------------------|
| PD2-2 LA                  | 1    1              | PD2-2 PD                  | 1    1              |
| WIENS, L                  | 1    1              |                           |                     |
| INTERNAL: ACRS            | 6    6              | AEOD/SPD/RAB              | 1    1              |
| <u>FILE CENTER 01</u>     | 1    1              | NRR/DE/EMCB               | 1    1              |
| NRR/DE/EMEB               | 1    1              | NUDOCS-ABSTRACT           | 1    1              |
| OGC/HDS2                  | 1    0              | RES/DSIR/EIB              | 1    1              |
| EXTERNAL: LITCO ANDERSON  | 1    1              | LITCO RANSOME, C          | 1    1              |
| NOAC                      | 1    1              | NRC PDR                   | 1    1              |

NOTE TO ALL "RIDS" RECIPIENTS:

PLEASE HELP US TO REDUCE WASTE! CONTACT THE DOCUMENT CONTROL DESK, ROOM P1-37 (EXT. 504-2083) TO ELIMINATE YOUR NAME FROM DISTRIBUTION LISTS FOR DOCUMENTS YOU DON'T NEED!

TOTAL NUMBER OF COPIES REQUIRED: LTTR    20    ENCL    19

*may*

Duke Power Company  
Oconee Nuclear Site  
P.O. Box 1439  
Seneca, SC 29679

J. W. HAMPTON  
Vice President  
(803)885-3499 Office  
(803)885-3564 Fax



**DUKE POWER**

June 12, 1995

U.S. Nuclear Regulatory Commission  
Attention Document Control Desk  
Washington, DC 20555

Subject: Duke Power Company  
Oconee Nuclear Station, Unit 3  
Docket Nos. 50-269, -270, -287  
Third Ten Year Inservice Inspection Interval  
Request for Relief No. 93-08  
Supplemental Information

On September 13, 1984, Duke Power submitted a Relief from Code requirement concerning the Reactor Vessel Core Flood, Inlet, and Outlet nozzle to pipe welds. This request was needed due to the unusual difficulty, without a compensating increase in quality or safety, in performing the required surface examination. This difficulty is a result of the radiation dose levels and time required to perform a surface examination of these welds. This request was to allow the use of an ultrasonic examination of the welds from the inside diameter in lieu of the required surface examination on the outside weld surface.

Throughout the Second ISI Interval, resolution to this item was pursued by Duke/BWOG through dialogue with the NRC. As Duke approached the end of the second interval, it was recognized that this issue would not be resolved before the last outages of each Oconee Unit. Therefore, Relief Request 93-08, dated December 21, 1993, was submitted to delay performance of the code-required examination on each of the units to the first outages of the Third ISI Interval based on results of the alternate examinations. In an SER dated March 31, 1994, the NRC approved the delay requested in Relief Request 93-08.

In August 1994, in followup to a final NRC request for additional information regarding the acceptability of the proposed alternate testing, B&W Topical Report BAW-2228 was submitted to the NRC for review. The NRC reviewed and approved this topical report in an SER dated December 2, 1994. In this SER, the NRC states that

"Each licensee that references this topical report as the basis for the request for relief from the external surface examination of RV nozzle-to-piping welds must confirm plant specific applicability by demonstrating that (1) the input stresses shown in Table 1 for its

9506200218 950612  
PDR ADDOCK 05000269  
Q PDR


ADK

plant is a result of using the bounding transient analysis and (2) the material in its inlet, outlet, and core flood nozzles is (the same as those stated in the B&W topical report)."

Duke verified that the assumptions and stress values used in the B&W Topical Report BAW-2228 are consistent with current Oconee parameters. This verification required a review of Oconee's original stress reports along with a search for any changes or modifications to the plant which would conflict with the original stress reports. Although this review has required a revision to BAW-2228, the analyses conducted to support this revision conclude that Oconee Units remain within the assumptions and limitations described in the original report reviewed by the NRC. A description of this revision is provided in the attached B&W letter dated 6/8/95. Duke considers this item satisfactorily completed with no further actions required.

If there are any questions or further information is needed you may contact D. A. Nix at (803) 885-3634.

Very truly yours,

A handwritten signature in cursive script, appearing to read "J. W. Hampton".

J. W. Hampton  
Site Vice President

Attachment

U. S. Nuclear Regulatory Commission  
Page 3

xc (w/attch):        Mr. L. A. Wiens  
                         Office of Nuclear Reactor Regulation  
                         U. S. Nuclear Regulatory Commission  
                         Washington, DC 20555

xc (w/o attch):        Mr. S. D. Ebnetter  
                         Regional Administrator, Region II  
                         U. S. Nuclear Regulatory Commission

                         Mr. P. E. Harmon  
                         Senior NRC Resident Inspector  
                         Oconee Nuclear Station

                         Mr. Virgil R. Autry  
                         Bureau of Radiological Health  
                         SC Dept. of Health & Environmental Control  
                         2600 Bull St.  
                         Columbia, SC 29201



**B&W NUCLEAR TECHNOLOGIES**

3315 Old Forest Road  
P.O. Box 10935  
Lynchburg, VA 24506-0935  
Telephone: 804-832-3000  
Telecopy: 804-832-3663

June 9, 1995  
ESC-95-441

Mr. David Nix  
Duke Power Company  
Oconee Nuclear Station  
P.O. Box 1439  
Seneca, SC 29679

Subject: Revision to BWNT Report BAW-2228A

- References:
- 1) BWNT Report BAW-2228A, Entitled "Fracture Mechanics Assessment of Postulated Outer Surface, Semi-Elliptical Circumferential RV Nozzle-To-Pipe Weld Flaws," Rev. 0 dated February 1995
  - 2) NRC Letter B. W. Sheron (NRC) to D. A. Gulling (FPC) dated December 2, 1994

Dear Mr. Nix:

The purpose of this letter is to provide technical justification in support of Duke Power Company's (DPCo) review of the Reference 1 report. The NRC's acceptance of the report is documented in the Reference 2 Safety Evaluation Report (SER). However, as part of the NRC's SER, the NRC requested that DPCo confirm the applicability of the Reference 1 conclusions to the Oconee Unit 1, 2, and 3 plants. Specifically the NRC stated:

"Each licensee that references this topical report as the basis for the request for relief from the external examination of RV nozzle-to-piping welds must confirm plant specific applicability by demonstrating that (1) the input stresses shown in Table 1 is applicable to the plant and the materials are the same as those used in BAW-2228A."

During the review of Oconee specific applications DPCo and BWNT discovered that there is a need for a revision to BAW-2228A since:

- Stress values are slightly different since the original stresses were obtained from the component stress reports and consequently only nozzle cross-sections were considered. Additional stresses based on the thinner piping cross-sections (piping side of the weld) should be included in the evaluation.

- The calculation of the attached piping stresses and thermal transient stresses should be refined for the emergency/faulted condition.
- A more appropriate, but still conservative, fracture mechanics solution methodology was determined to be applicable to the analysis.

BWNT has completed the calculations to support the revision to the Reference 1 report. To aid with the Oconee review, BWNT is providing copies of the new stress tables which replace Tables 1 through 4 in BAW-2228A, Rev. 0. In addition, a transient description is also included. A re-analysis of these new stresses resulted in new allowable flaw sizes as shown below:

Maximum Allowable Flaw Depth as Function of Wall Thickness


| <u>Core Flood Nozzle</u>   | <u>BAW- 2228A</u> | <u>BAW-2228 Rev. 1</u> |
|----------------------------|-------------------|------------------------|
| i) Nozzle-to-safe end weld | 37.0%             | > 60%                  |
| ii) Safe end-to-pipe weld  | 58.7%             | 60%                    |
| <br><u>Inlet Nozzle</u>    |                   |                        |
| i) Nozzle-to-pipe weld     | 56.5%             | 57%                    |
| <br><u>Outlet Nozzle</u>   |                   |                        |
| i) Nozzle-to-pipe weld     | 25.9%             | 25.5%                  |

As can be seen from the allowable flaw size table above, the changes in stresses resulted in only a minor change to the previously reported allowable flaw size values. Therefore, it is BWNT's technical position that the conclusions reached in BAW-2228A are still valid and applicable to Oconee Units 1, 2 and 3. The alternate examination performed on the RV nozzle-to-pipe welds in the Unit 3 refueling outage 14 (12/93) is adequate for the full inspection interval.

BWNT is currently revising the Reference 1 report to include the stress values and flaw sizes discussed in this letter.

If you have any questions regarding this letter or the attached stress tables, please call me at (804)832-3290.

Sincerely,



A. W. Robinson  
Project Manager  
Owners Group Projects

AWR/mcl

Attachment

c: NDE Committee

|                 |                             |
|-----------------|-----------------------------|
| E. E. Addison   | - Entergy Operations, Inc.  |
| R. G. Sheffield | - Duke Power Company        |
| D. A. Gulling   | - Florida Power Corporation |
| G. J. Navratil  | - GPU Nuclear Corporation   |
| M. D. Shepherd  | - Toledo Edison Company     |
| W. F. Brady     | - Duke Power Company        |

Revised BAW-2228 Stresses

Table 1a. Stresses at Core Flood Nozzle, Safe End-to-Pipe Weld (piping side)

| Plant     | Fatigue Group | Cycles until next 10 yr. ISI | Normal / Upset         |                       | Normal / Upset         |                       | Emergency / Faulted    |                       |
|-----------|---------------|------------------------------|------------------------|-----------------------|------------------------|-----------------------|------------------------|-----------------------|
|           |               |                              | Maximum Membrane (ksi) | Maximum Bending (ksi) | Minimum Membrane (ksi) | Minimum Bending (ksi) | Maximum Membrane (ksi) | Maximum Bending (ksi) |
| OC- 1,2,3 | 1a            | 90                           | 13.9                   | 6.8                   | 0.0                    | 0.0                   | 4.8                    | -85.5                 |
|           | 1b            | 90                           | 10.0                   | 6.3                   | 9.1                    | 1.9                   |                        |                       |
|           | 1c            | 90                           | 9.1                    | 5.3                   | 9.1                    | 3.4                   |                        |                       |
|           | 2             | 4500                         | 13.9                   | 6.8                   | 13.3                   | 6.5                   | 23.2                   | 7.3                   |
| ANO-1     | 1a            | 60                           | 26.1                   | 8.0                   | 0.0                    | 0.0                   | 16.5                   | -84.4                 |
|           | 1b            | 60                           | 22.2                   | 7.5                   | 21.3                   | 3.1                   |                        |                       |
|           | 1c            | 60                           | 21.3                   | 6.5                   | 21.2                   | 4.6                   |                        |                       |
|           | 2             | 12000                        | 26.1                   | 8.0                   | 25.5                   | 7.7                   | 35.1                   | 8.5                   |
| DB-1      | 1a            | 60                           | 13.5                   | 6.7                   | 0.0                    | -0.8                  | 4.1                    | -85.8                 |
|           | 1b            | 60                           | 10.7                   | 6.5                   | 10.0                   | -0.8                  |                        |                       |
|           | 1c            | 60                           | 9.5                    | 5.3                   | 9.5                    | 3.5                   |                        |                       |
|           | 2             | 12000                        | 13.5                   | 6.7                   | 13.5                   | 6.0                   | 22.8                   | 6.9                   |
| CR-3      | 1a            | 60                           | 13.8                   | 6.9                   | 0.0                    | 0.0                   | 4.8                    | -85.5                 |
|           | 1b            | 60                           | 13.8                   | 3.9                   | 9.8                    | 2.1                   |                        |                       |
|           | 1c            | 60                           | 13.8                   | 5.1                   | 9.3                    | 3.9                   |                        |                       |
|           | 2             | 12000                        | 13.8                   | 6.9                   | 13.2                   | 3.9                   | 23.0                   | 4.7                   |
| TMI-1     | 1a            | 60                           | 21.7                   | 7.6                   | 0.0                    | 0.0                   | 16.1                   | -84.5                 |
|           | 1b            | 60                           | 21.7                   | 4.6                   | 17.7                   | 2.8                   |                        |                       |
|           | 1c            | 60                           | 21.7                   | 5.8                   | 17.2                   | 4.6                   |                        |                       |
|           | 2             | 12000                        | 21.7                   | 7.6                   | 21.1                   | 4.6                   | 32.5                   | 5.6                   |

Table 1b. Stresses at Core Flood Nozzle, Safe End-to-Pipe Weld (nozzle side) for Limiting Plant

| Plant | Fatigue Group | Cycles until next 10 yr. ISI | Normal / Upset         |                       | Normal / Upset         |                       | Emergency / Faulted    |                       |
|-------|---------------|------------------------------|------------------------|-----------------------|------------------------|-----------------------|------------------------|-----------------------|
|       |               |                              | Maximum Membrane (ksi) | Maximum Bending (ksi) | Minimum Membrane (ksi) | Minimum Bending (ksi) | Maximum Membrane (ksi) | Maximum Bending (ksi) |
| ANO-1 | 1a            | 60                           | 23.3                   | 6.9                   | 0.0                    | 0.0                   | 14.7                   | -84.4                 |
|       | 1b            | 60                           | 19.8                   | 6.5                   | 19.0                   | 2.8                   |                        |                       |
|       | 1c            | 60                           | 19.0                   | 5.7                   | 18.9                   | 4.1                   |                        |                       |
|       | 2             | 12000                        | 23.3                   | 6.9                   | 22.7                   | 6.6                   | 31.2                   | 7.4                   |



Revised BAW-2228 Stresses

Table 2. Stresses at Core Flood Nozzle, Nozzle-to-Safe End Weld

| Plant     | Fatigue | Cycles<br>until next<br>10 yr. ISI | Normal / Upset               |                             | Normal / Upset               |                             | Emergency / Faulted          |                             |
|-----------|---------|------------------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|
|           | Group   |                                    | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) | Minimum<br>Membrane<br>(ksi) | Minimum<br>Bending<br>(ksi) | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) |
| OC- 1,2,3 | 1a      | 90                                 | 10.6                         | 5.1                         | 0.0                          | -13.8                       | 3.3                          | -74.1                       |
|           | 1b      | 90                                 | 7.1                          | -0.4                        | 6.3                          | -13.8                       |                              |                             |
|           | 1c      | 90                                 | 6.3                          | -2.1                        | 6.2                          | -7.7                        |                              |                             |
|           | 2       | 4500                               | 10.6                         | 5.1                         | 10.0                         | 0.2                         | 16.9                         | 9.1                         |
| ANO-1     | 1a      | 60                                 | 18.9                         | 6.0                         | 0.0                          | -13.0                       | 11.2                         | -73.2                       |
|           | 1b      | 60                                 | 15.3                         | 0.4                         | 14.5                         | -13.0                       |                              |                             |
|           | 1c      | 60                                 | 14.5                         | -1.3                        | 14.5                         | -6.8                        |                              |                             |
|           | 2       | 12000                              | 18.9                         | 6.0                         | 18.3                         | 1.1                         | 25.0                         | 9.8                         |
| DB-1      | 1a      | 60                                 | 10.3                         | 5.1                         | 0.0                          | -14.5                       | 2.9                          | -74.3                       |
|           | 1b      | 60                                 | 7.8                          | 0.3                         | 7.3                          | -14.5                       |                              |                             |
|           | 1c      | 60                                 | 6.8                          | -2.5                        | 6.8                          | -8.2                        |                              |                             |
|           | 2       | 12000                              | 10.3                         | 5.1                         | 10.3                         | 0.8                         | 16.6                         | 8.9                         |
| CR-3      | 1a      | 60                                 | 10.4                         | 4.6                         | 0.0                          | -11.4                       | 3.3                          | -74.1                       |
|           | 1b      | 60                                 | 10.4                         | 4.1                         | 6.9                          | -11.4                       |                              |                             |
|           | 1c      | 60                                 | 10.4                         | 4.1                         | 5.9                          | -5.4                        |                              |                             |
|           | 2       | 12000                              | 10.4                         | 4.6                         | 9.9                          | 4.1                         | 16.7                         | 9.1                         |
| TMI-1     | 1a      | 60                                 | 15.8                         | 5.2                         | 0.0                          | -10.8                       | 11.0                         | -73.3                       |
|           | 1b      | 60                                 | 15.8                         | 4.7                         | 12.3                         | -10.8                       |                              |                             |
|           | 1c      | 60                                 | 15.8                         | 4.7                         | 11.3                         | -4.8                        |                              |                             |
|           | 2       | 12000                              | 15.8                         | 5.2                         | 15.3                         | 4.7                         | 23.2                         | 9.8                         |

## Revised BAW-2228 Stresses

**Table 3a. Stresses at RV Outlet Nozzle, Nozzle-to-Pipe Weld (piping side)**

| Plant     | Fatigue | Cycles                   | Normal / Upset               |                             | Normal / Upset               |                             | Emergency / Faulted          |                             |
|-----------|---------|--------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|
|           | Group   | until next<br>10 yr. ISI | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) | Minimum<br>Membrane<br>(ksi) | Minimum<br>Bending<br>(ksi) | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) |
| OC- 1,2,3 | 3       | 90                       | 9.7                          | 0.0                         | 0.0                          | -12.1                       |                              |                             |
|           | 4       | 4500                     | 9.7                          | -9.6                        | 9.7                          | -12.1                       |                              |                             |
|           | 1       | 2463                     | 9.7                          | -12.1                       | 9.7                          | -12.1                       |                              |                             |
|           | 2       | 120                      | 9.7                          | -4.1                        | 9.1                          | -12.1                       | 14.1                         | 0.1                         |
| ANO-1     | 1       | 60                       | 10.7                         | 3.1                         | 0.0                          | -15.1                       |                              |                             |
|           | 2       | 12360                    | 10.7                         | 2.6                         | 10.6                         | -2.8                        |                              |                             |
|           | 4       | 2232                     | 11.5                         | 2.6                         | 10.7                         | -1.5                        | 14.9                         | 2.9                         |
| DB-1      | 1       | 60                       | 33.0                         | 4.6                         | 0.0                          | -12.8                       |                              |                             |
|           | 2       | 12360                    | 33.0                         | 3.7                         | 25.9                         | -1.0                        |                              |                             |
|           | 4       | 2232                     | 26.8                         | 3.7                         | 25.9                         | -0.3                        | 34.3                         | 4.3                         |
| CR-3      | 1       | 60                       | 10.1                         | 2.9                         | 0.0                          | -14.4                       |                              |                             |
|           | 2       | 12360                    | 10.1                         | 2.5                         | 10.0                         | -2.7                        |                              |                             |
|           | 4       | 2232                     | 10.9                         | 2.5                         | 10.1                         | -1.5                        | 15.4                         | 2.9                         |
| TMI-1     | 1       | 60                       | 12.6                         | 0.2                         | 0.0                          | -11.9                       |                              |                             |
|           | 2       | 12000                    | 12.6                         | -9.4                        | 12.6                         | -11.9                       |                              |                             |
|           | 3       | 4538                     | 12.6                         | -3.9                        | 12.1                         | -11.9                       | 17.1                         | 0.1                         |

Table 3b. Stresses at RV Outlet Nozzle, Nozzle-to-Pipe Weld (nozzle side) for Limiting Plant

| Plant | Fatigue<br>Group | Cycles<br>until next<br>10 yr. ISI | Normal / Upset               |                             | Normal / Upset               |                             | Emergency / Faulted          |                             |
|-------|------------------|------------------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|
|       |                  |                                    | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) | Minimum<br>Membrane<br>(ksi) | Minimum<br>Bending<br>(ksi) | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) |
| DB-1  | 1                | 60                                 | 29.4                         | 4.1                         | 0.0                          | -10.1                       | 30.5                         | 3.8                         |
|       | 2                | 12360                              | 29.4                         | 3.7                         | 29.3                         | -0.5                        |                              |                             |
|       | 4                | 2232                               | 30.1                         | 3.7                         | 29.4                         | 0.5                         |                              |                             |
|       |                  |                                    |                              |                             |                              |                             |                              |                             |

Revised BAW-2228 Stresses

Table 4a. Stresses at RV Inlet Nozzle, Nozzle-to-Pipe Weld (piping side) for DB-1

| Plant | Fatigue<br>Group | Cycles<br>until next<br>10 yr. ISI | Normal / Upset               |                             | Normal / Upset               |                             | Emergency / Faulted          |                             |
|-------|------------------|------------------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|
|       |                  |                                    | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) | Minimum<br>Membrane<br>(ksi) | Minimum<br>Bending<br>(ksi) | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) |
| DB-1  | 1                | 60                                 | 16.7                         | 6.4                         | 0.0                          | -1.5                        |                              |                             |
|       | 2                | 12360                              | 16.6                         | 5.0                         | 16.2                         | 2.6                         |                              |                             |
|       | 5                | 2212                               | 17.1                         | 5.0                         | 16.2                         | 3.8                         | 40.6                         | 5.3                         |

Table 4b. Stresses at RV Inlet Nozzle, Nozzle-to-Pipe Weld (nozzle side) for DB-1

| Plant | Fatigue<br>Group | Cycles<br>until next<br>10 yr. ISI | Normal / Upset               |                             | Normal / Upset               |                             | Emergency / Faulted          |                             |
|-------|------------------|------------------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|
|       |                  |                                    | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) | Minimum<br>Membrane<br>(ksi) | Minimum<br>Bending<br>(ksi) | Maximum<br>Membrane<br>(ksi) | Maximum<br>Bending<br>(ksi) |
| DB-1  | 1                | 60                                 | 14.9                         | 5.3                         | 0.0                          | -1.1                        |                              |                             |
|       | 2                | 12360                              | 14.8                         | 4.2                         | 14.8                         | 2.2                         |                              |                             |
|       | 5                | 2212                               | 15.6                         | 4.2                         | 14.8                         | 3.2                         | 36.1                         | 4.7                         |

## **Transient Description for Core Flood Nozzle**

### Fatigue Group   Normal/Upset Condition Transient

- 1a      Overall heatup/cooldown transient
- 1b      Core flood line valve test (during cooldown)
- 1c      Decay heat initiation (during cooldown)
- 2        Power loading and unloading

### Emergency/Faulted Condition Transient

- Top pair      Core flood injection transient during LOCA
- Bottom pair   SRSS of (SSE + LOCA) + steady state thermal

## **Transient Description for the RV Inlet/Outlet Nozzles**

### Fatigue Group   Normal/Upset Condition Transient

- 1-5      Grouping of transients as selected for fatigue analysis in the component stress report

### Emergency/Faulted Condition Transient

SRSS of (SSE + LOCA) + steady state thermal