

DUKE POWER COMPANY
OCONEE 2 CYCLE 16
CORE OPERATING LIMITS REPORT
REVISION 6

QA CONDITION 1

REFERENCE OSC-6215

Prepared by: L. Dewain McClinton

Date: October 3, 1996

Checked by: J. L. Elv

Date: 03 OCT 96

Approved by: R. R. St. Clair

Date: 08 OCT 96

9610170133 961003
PDR ADOCK 05000270
P PDR

Oconee Nuclear Station
Unit 2 Cycle 16
Core Operating Limits Report
Insertion Sheet for Revision 6

Remove these Revision 5 pages

1-3, 18

Insert these Revision 6 pages

1-3, 18

Oconee Nuclear Station
Unit 2 Cycle 16
Core Operating Limits Report
Revision Log

Revision	Effective Date	Pages Revised	Pages Added	Pages Deleted	Total Effective Pages
6	October 1996	1-3, 18	-	-	38
5	March 4, 1996	1-34	35-38	-	38

Oconee 2 Cycle 15 Revisions Below					
4	January 5, 1996	1-5, 16	-	-	34
3	September 22, 1995	1-3, 12	-	-	34
2	March 9, 1995	1-3, 13, 20, 23-26	-	-	34
1	January 30, 1995	1-3, 13, 20, 23-26	-	-	34
0	September 30, 1994	-	1-34	-	34

OCONEE 2 CYCLE 16 IMBALANCE SETPOINTS

3 PUMP OPERATION BOC TO EOC

PERCENT OF FULL POWER	R P S	TRIP	FULL INCORE ALARM		OUTCORE ALARM	
80.6	-14.40	14.40				
80	-15.04	15.04				
79	-16.10	16.10				
78	-17.16	17.16				
77	-18.23	18.23	-17.00	17.00	-17.00	17.00
76	-19.29	19.29	-18.06	18.06	-18.06	18.06
75	-20.35	20.35	-19.12	19.12	-19.12	19.12
74	-21.41	21.41	-20.18	20.18	-20.18	20.18
73	-22.48	22.48	-21.23	21.23	-21.23	21.23
72	-23.54	23.54	-22.29	22.29	-22.29	22.29
71	-24.60	24.60	-23.35	23.35	-23.35	23.35
70	-25.67	25.67	-24.41	24.41	-24.41	24.41
69	-26.73	26.73	-25.47	25.47	-25.47	25.47
68.69	-27.06	27.06	-25.80	25.80	-25.80	25.80
68	-27.79	27.79	-26.53	26.53	-26.53	25.80
67	-28.85	28.85	-27.58	27.58	-27.58	25.80
66	-29.92	29.92	-28.64	28.64	-28.64	25.80
65	-30.98	30.98	-29.70	29.70	-29.70	25.80
64	-32.04	32.04	-30.76	30.76	-30.76	25.80
63.3	-32.79	32.79	-31.50	31.50	-31.50	25.80
63.1	-33.00	33.00	-31.50	31.50	-31.50	25.80
63	-33.00	33.00	-31.50	31.50	-31.50	25.80
62	-33.00	33.00	-31.50	31.50	-31.50	25.80
61	-33.00	33.00	-31.50	31.50	-31.50	25.80
60	-33.00	33.00	-31.50	31.50	-31.50	25.80
0	-33.00	33.00	-31.50	31.50	-31.50	25.80
PERCENT OF FULL POWER	R P S	TRIP	FULL INCORE ALARM		OUTCORE ALARM	