

CHAPTER 3

DESIGN OF STRUCTURES, COMPONENTS, EQUIPMENT AND SYSTEMS

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
3.1	CONFORMANCE WITH NUCLEAR REGULATORY COMMISSION GENERAL DESIGN CRITERIA.....	3.1-1
3.1.2	PROTECTION BY MULTIPLE FISSION PRODUCT BARRIERS .	3.1-1
3.2	CLASSIFICATION OF STRUCTURES, COMPONENTS, AND SYSTEMS	3.2-1
3.2.1	SEISMIC CLASSIFICATION	3.2-1
3.2.2	AP1000 CLASSIFICATION SYSTEM	3.2-1
3.3	WIND AND TORNADO LOADINGS.....	3.3-1
3.3.1.1	Design Wind Velocity.....	3.3-1
3.3.2.1	Applicable Design Parameters	3.3-1
3.3.2.3	Effect of Failure of Structures or Components Not Designed for Tornado Loads	3.3-1
3.3.3	COMBINED LICENSE INFORMATION.....	3.3-1
3.4	WATER LEVEL (FLOOD) DESIGN.....	3.4-1
3.4.1.3	Permanent Dewatering System	3.4-1
3.4.3	COMBINED LICENSE INFORMATION.....	3.4-1
3.5	MISSILE PROTECTION.....	3.5-1
3.5.1.3	Turbine Missiles.....	3.5-1
3.5.1.5	Missiles Generated by Events Near the Site	3.5-1
3.5.1.6	Aircraft Hazards	3.5-2
3.5.4	COMBINED LICENSE INFORMATION.....	3.5-4
3.6	PROTECTION AGAINST THE DYNAMIC EFFECTS ASSOCIATED WITH THE POSTULATED RUPTURE OF PIPING.....	3.6-1
3.6.4.1	Pipe Break Hazard Analysis	3.6-1
3.6.4.4	Primary System Inspection Program for Leak-before-Break Piping	3.6-2

TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Title</u>	<u>Page</u>
3.7	SEISMIC DESIGN	3.7-1
3.7.1.1.1	Design Foundation Response Spectra	3.7-1
3.7.2.1.2	Time-History Analysis and Complex Frequency Response Analysis	3.7-3
3.7.2.8.4	Seismic Modeling and Analysis of Seismic Category II Building Structures.....	3.7-4
3.7.2.12	Methods for Seismic Analysis of Dams	3.7-7
3.7.2.15	Site-Specific Analyses of Nuclear Island Seismic Category I Structures	3.7-7
3.7.4.1	Comparison with Regulatory Guide 1.12	3.7-11
3.7.4.2.1	Triaxial Acceleration Sensors	3.7-11
3.7.4.4	Comparison of Measured and Predicted Responses	3.7-11
3.7.4.5	Tests and Inspections.....	3.7-12
3.7.5	COMBINED LICENSE INFORMATION.....	3.7-12
3.7.5.1	Seismic Analysis of Dams	3.7-12
3.7.5.2	Post-Earthquake Procedures.....	3.7-12
3.7.5.3	Seismic Interaction Review.....	3.7-12
3.7.5.4	Reconciliation of Seismic Analyses of Nuclear Island Structures.....	3.7-13
3.7.5.5	Free Field Acceleration Sensor	3.7-13
3.7.6	REFERENCES	3.7-13
3.8	DESIGN OF CATEGORY I STRUCTURES	3.8-1
3.8.3.7	In-Service Testing and Inspection Requirements	3.8-1
3.8.4.4.4	Below Grade Exterior Walls.....	3.8-1
3.8.4.7	Testing and In-Service Inspection Requirements	3.8-3
3.8.5.1	Description of the Foundations	3.8-3
3.8.5.5.1	Nuclear Island Maximum Bearing Pressures.....	3.8-3
3.8.5.7	In-Service Testing and Inspection Requirements	3.8-4
3.8.6.5	Structures Inspection Program	3.8-4
3.8.6.6	Construction Procedures Program	3.8-4
3.8.7	REFERENCES	3.8-4
3.9	MECHANICAL SYSTEMS AND COMPONENTS	3.9-1
3.9.3	ASME CODE CLASSES 1, 2, AND 3 COMPONENTS, COMPONENT SUPPORTS, AND CORE SUPPORT STRUCTURES	3.9-1
3.9.3.1.2	Loads for Class 1 Components, Core Support, and Component Supports.....	3.9-2
3.9.3.4.4	Inspection, Testing, Repair, and/or Replacement of Snubbers	3.9-3

TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Title</u>	<u>Page</u>
3.9.6	INSERVICE TESTING OF PUMPS AND VALVES	3.9-7
3.9.6.2.2	Valve Testing	3.9-8
3.9.6.2.3	Valve Disassembly and Inspection	3.9-13
3.9.6.2.4	Valve Preservice Tests	3.9-14
3.9.6.2.5	Valve Replacement, Repair, and Maintenance	3.9-14
3.9.6.3	Relief Requests	3.9-14
3.9.8	COMBINED LICENSE INFORMATION.....	3.9-16
3.9.8.2	Design Specifications and Reports.....	3.9-16
3.9.8.3	Snubber Operability Testing	3.9-16
3.9.8.4	Valve Inservice Testing.....	3.9-17
3.9.8.5	Surge Line Thermal Monitoring	3.9-17
3.9.8.7	As-Designed Piping Analysis.....	3.9-17
3.9.9	REFERENCES	3.9-17
3.10	SEISMIC AND DYNAMIC QUALIFICATION OF SEISMIC CATEGORY I MECHANICAL AND ELECTRICAL EQUIPMENT.....	3.10-1
3.11	ENVIRONMENTAL QUALIFICATION OF MECHANICAL AND ELECTRICAL EQUIPMENT	3.11-1
3.11.5	COMBINED LICENSE INFORMATION ITEM FOR EQUIPMENT QUALIFICATION FILE	3.11-1
APP. 3A	HVAC DUCTS AND DUCT SUPPORTS	3A-1
APP. 3B	LEAK-BEFORE-BREAK EVALUATION OF THE AP1000 PIPING	3B-1
APP. 3C	REACTOR COOLANT LOOP ANALYSIS METHODS	3C-1
APP. 3D	METHODOLOGY FOR QUALIFYING AP1000 SAFETY-RELATED ELECTRICAL AND MECHANICAL EQUIPMENT	3D-1
APP. 3E	HIGH-ENERGY PIPING IN THE NUCLEAR ISLAND	3E-1
APP. 3F	CABLE TRAYS AND CABLE TRAY SUPPORTS	3F-1
APP. 3G	NUCLEAR ISLAND SEISMIC ANALYSES	3G-1
APP. 3H	AUXILIARY AND SHIELD BUILDING CRITICAL SECTIONS	3H-1

TABLE OF CONTENTS (Continued)

<u>Section</u>	<u>Title</u>	<u>Page</u>
APP. 3I	EVALUATION FOR HIGH FREQUENCY SEISMIC INPUT	3I-1
3I.1	INTRODUCTION	3.I-1
3I.2	HIGH FREQUENCY SEISMIC INPUT.....	3.I-1
3I.3	NI MODELS USED TO DEVELOP HIGH FREQUENCY RESPONSE.....	3.I-1
3I.6	EVALUATION	3.I-2
3I.6.1	Building Structures.....	3.I-2
3I.6.2	Primary Coolant Loop	3.I-2
3I.6.3	Piping Systems	3.I-2
3I.6.4	Electrical and Electro-Mechanical Equipment	3.I-3
3I.7	REFERENCES	3.I-4

LIST OF TABLES

<u>Number</u>	<u>Title</u>
3.2-201	AP1000 Classification of Mechanical and Fluid Systems, Components, and Equipment
3.7-201	Summary of Characteristics of Artificial Time Histories Representing NI FIRS
3.7-202	Seismic Category I Equipment Outside Containment by Room Number
3.8-201	Fraction of AP1000 Generic Lateral Soil Resistance Mobilized
3.9-201	Safety Related Snubbers
3.9-202	List of ASME Class 1, 2, and 3 Active Valves
3.9-203	Valve Inservice Test Requirements
3.9-204	System Level Operability Test Requirements
3.11-201	Environmentally Qualified Electrical and Mechanical Equipment
3.11-202	Environmentally Qualified Electrical and Mechanical Equipment
3I-201	List of Potential High Frequency Sensitive AP1000 Safety-Related Electrical and Electro-Mechanical Equipment
3I-202	List of AP1000 Safety-Related Electrical and Mechanical Equipment Not High Frequency Sensitive

LIST OF FIGURES

<u>Number</u>	<u>Title</u>
3.7-201	Design Ground Motion Response Spectra - NI FIRS Horizontal
3.7-202	Design Ground Motion Response Spectra - NI FIRS Vertical
3.7-203	Deleted
3.7-203a	Time History Representing NI FIRS (N)
3.7-203b	Time History Representing NI FIRS (W)
3.7-203c	Time History Representing NI FIRS (V)
3.7-204a	Deleted
3.7-204b	Deleted
3.7-204c	Deleted
3.7-205a	Deleted
3.7-205b	Deleted
3.7-205c	Deleted
3.7-206a	Deleted
3.7-206b	Deleted
3.7-206c	Deleted
3.7-207a	Deleted
3.7-207b	Deleted
3.7-207c	Deleted
3.7-208a	Deleted
3.7-208b	Deleted
3.7-208c	Deleted

LIST OF FIGURES (Continued)

<u>Number</u>	<u>Title</u>
3.7-209a	Comparison of 3D FRS and AP1000 Envelopes (X-Direction, Nodes 1761 and 2078)
3.7-209b	Comparison of 3D FRS and AP1000 Envelopes (X-Direction, Nodes 2199 and 2675)
3.7-209c	Comparison of 3D FRS and AP1000 Envelopes (X-Direction, Nodes 2788 and 3329)
3.7-210a	Comparison of 3D FRS and AP1000 Envelopes (Y-Direction, Nodes 1761 and 2078)
3.7-210b	Comparison of 3D FRS and AP1000 Envelopes (Y-Direction, Nodes 2199 and 2675)
3.7-210c	Comparison of 3D FRS and AP1000 Envelopes (Y-Direction, Nodes 2788 and 3329)
3.7-211a	Comparison of 3D FRS and AP1000 Envelopes (Z-Direction, Nodes 1761 and 2078)
3.7-211b	Comparison of 3D FRS and AP1000 Envelopes (Z-Direction, Nodes 2199 and 2675)
3.7-211c	Comparison of 3D FRS and AP1000 Envelopes (Z-Direction, Nodes 2788 and 3329)
3.7-212	In-Structure Response Spectra with High Frequency Exceedances
3.7-213a	Units 1 and 2 Annex Building Foundation Response Spectrum Envelope in East-West Direction, GW Backfill - All Nodes
3.7-213b	Units 1 and 2 Annex Building Foundation Response Spectrum Envelope in Vertical Direction, GW Backfill - All Nodes
3.7-214a	Units 1 and 2 Turbine Building 1st Bay Foundation Response Spectrum Envelope in North-South Direction, GW Backfill - All Nodes
3.7-214b	Units 1 and 2 Turbine Building 1st Bay Foundation Response Spectrum Envelope in Vertical Direction, GW Backfill - All Nodes

LIST OF FIGURES (Continued)

<u>Number</u>	<u>Title</u>
3.8-201a	Maximum E-W Lateral Pressures – Loading Combinations 1, 2, 3 and 7
3.8-201b	Maximum E-W Lateral Pressures – Loading Combinations 4, 5, 6, 8 and 9
3.8-202a	Maximum N-S Lateral Pressures – Loading Combinations 1, 2, 3 and 7
3.8-202b	Maximum N-S Lateral Pressures – Loading Combinations 4, 5, 6, 8 and 9
3.8-203	E-W Lateral Pressures – Loading Combination 7 AP1000 and WLS Site-Specific Lateral Pressure for Mobilized Earth Pressures
3.8-204	N-S Lateral Pressures – Loading Combination 7 AP1000 and WLS Site-Specific Lateral Pressure for Mobilized Earth Pressures
3.8-205	Containment Vessel General Outline
3D-201	Typical Abnormal Environmental Test Profile: Main Control Room
3I.1-201	Design Ground Motion Response Spectra - NI FIRS Horizontal
3I.1-202	Design Ground Motion Response Spectra - NI FIRS Vertical

CHAPTER 3**DESIGN OF STRUCTURES, COMPONENTS, EQUIPMENT AND SYSTEMS****3.1 CONFORMANCE WITH NUCLEAR REGULATORY COMMISSION
GENERAL DESIGN CRITERIA**

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.1.2 PROTECTION BY MULTIPLE FISSION PRODUCT BARRIERS

Revise the first sentence of the third paragraph of AP1000 Compliance section of Criterion 19 - Control Room of DCD Subsection 3.1.2 to read as follows:

- WLS DEP 6.4-1 If ac power is unavailable for more than 10 minutes or if "High-2" particulate, low pressurizer pressure is detected, or "High-2" iodine radioactivity is detected in the main control room supply air duct, which would lead to exceeding General Design Criteria 19 operator dose limits, the protection and safety monitoring system automatically isolates the main control room and operator habitability requirements are then met by the main control room emergency habitability system (VES).

3.2 CLASSIFICATION OF STRUCTURES, COMPONENTS, AND SYSTEMS

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.2.1 SEISMIC CLASSIFICATION

Add the following information to the end of DCD Subsection 3.2.1:

STD SUP 3.2-1 There are no safety-related structures, systems, or components outside the scope of the DCD. The nonsafety-related structures, systems and components outside the scope of the DCD are classified as non-seismic (NS).

3.2.2 AP1000 CLASSIFICATION SYSTEM

Add the following information to the end of DCD Subsection 3.2.2:

STD SUP 3.2-1 There are no safety-related structures, systems, or components outside the scope of the DCD.

WLS DEP 3.2-1

TABLE 3.2-201
AP1000 CLASSIFICATION OF MECHANICAL AND FLUID SYSTEMS,
COMPONENTS, AND EQUIPMENT

Tag Number	Description	AP1000 Class	Seismic Category	Principal Construction Code	Comments
Passive Core Cooling System (Continued)					
PXS-MY-Y81	Downspout Screen 1A	C	I	Manufacturer Std.	
PXS-MY-Y82	Downspout Screen 1B	C	I	Manufacturer Std.	
PXS-MY-Y83	Downspout Screen 1C	C	I	Manufacturer Std.	
PXS-MY-Y84	Downspout Screen 1D	C	I	Manufacturer Std.	
PXS-MY-Y85	Downspout Screen 2A	C	I	Manufacturer Std.	
PXS-MY-Y86	Downspout Screen 2B	C	I	Manufacturer Std.	
PXS-MY-Y87	Downspout Screen 2C	C	I	Manufacturer Std.	
PXS-MY-Y88	Downspout Screen 2D	C	I	Manufacturer Std.	

3.3 WIND AND TORNADO LOADINGS

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.3.1.1 Design Wind Velocity

Add the following information to the end of DCD Subsection 3.3.1.1:

WLS COL 3.3-1 The wind velocity characteristics for Lee Nuclear Station Units 1 and 2, are given in **Subsection 2.3.1.2.8**. These values are bounded by the design wind velocity values given in **DCD Subsection 3.3.1.1** for the AP1000 plant.

3.3.2.1 Applicable Design Parameters

Add the following information to the end of DCD Subsection 3.3.2.1:

WLS COL 3.3-1 The tornado characteristics for Lee Nuclear Station Units 1 and 2 are given in **Subsection 2.3.1.2.2**. These values are bounded by the tornado design parameters given in **DCD Subsection 3.3.2.1** for the AP1000 plant.

3.3.2.3 Effect of Failure of Structures or Components Not Designed for Tornado Loads

Add the following information to the end of DCD Subsection 3.3.2.3:

STD COL 3.3-1 Consideration of the effects of wind and tornado due to failures in an adjacent AP1000 plant are bounded by the evaluation of the buildings and structures in a single unit.

3.3.3 COMBINED LICENSE INFORMATION

Add the following information to the end of DCD Subsection 3.3.3:

WLS COL 3.3-1 The Lee Nuclear Station site satisfies the site interface criteria for wind and tornado (see **Subsections 3.3.1.1**, **3.3.2.1**, and **3.3.2.3**) and does not have a wind or tornado-initiated failure of structures and components within the applicant's

scope that compromises the safety of AP1000 safety-related structures and components (see also [Subsection 3.5.4](#)).

3.4 WATER LEVEL (FLOOD) DESIGN

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.4.1.3 Permanent Dewatering System

Add the following information to the end of DCD Subsection 3.4.1.3:

WLS COL 3.4-1 No permanent dewatering system is required because site groundwater levels are two feet or more below site grade level as described in **Subsection 2.4.12.5**.

3.4.3 COMBINED LICENSE INFORMATION

Replace the first paragraph of DCD Subsection 3.4.3 with the following information:

WLS COL 3.4-1 The site-specific water levels given in **Section 2.4** satisfy the interface requirements identified in **DCD Section 2.4**.

3.5 MISSILE PROTECTION

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.5.1.3 Turbine Missiles

Add the following information to the end of DCD Subsection 3.5.1.3:

- STD SUP 3.5-1 The potential for a turbine missile from another AP1000 plant in close proximity has been considered. As noted in **DCD Subsection 10.2.2**, the probability of generation of a turbine missile (or P1 as identified in SRP 3.5.1.3) is less than 1×10^{-5} per year. This missile generation probability (P1) combined with an unfavorable orientation P2xP3 conservative product value of 10^{-2} (from SRP 3.5.1.3) results in a probability of unacceptable damage from turbine missiles (or P4 value) of less than 10^{-7} per year per plant which meets the SRP 3.5.1.3 acceptance criterion and the guidance of Regulatory Guide 1.115. Thus, neither the orientation of the side-by-side AP1000 turbines nor the separation distance is pertinent to meeting the turbine missile generation acceptance criterion. In addition, the shield building and auxiliary building walls, roofs, and floors provide further conservative, inherent protection of the safety-related SSCs from a turbine missile.
-

- STD SUP 3.5-2 The turbine system maintenance and inspection program is discussed in **Subsection 10.2.3.6**.
-

3.5.1.5 Missiles Generated by Events Near the Site

Add the following information to the end of DCD Subsection 3.5.1.5:

- WLS COL 3.5-1 The gate house, administrative building, security control building, warehouse and shops, water service building, diesel-driven fire pump / enclosure, and miscellaneous structures are common structures that are at a nuclear power plant. They are of similar design and construction to those that are typical at nuclear power plants. Therefore, any missiles resulting from a tornado-initiated failure are not more energetic than the tornado missiles postulated for design of the AP1000.

The missiles generated by events near the site are discussed and evaluated in **Subsection 2.2.3**. The effects of external events on the safety-related components of the plant are insignificant. The pressure effect of potential explosions in the

vicinity of the plant site are estimated to result in less than 1 psi overpressure on plant structures. Therefore, these potential explosions do not represent design basis events per Regulatory Guide 1.91.

3.5.1.6 Aircraft Hazards

Add the following information to the end of DCD Subsection 3.5.1.6:

WLS COL 3.5-1 The approach and methodology outlined in NUREG-0800 Standard Review Plan (SRP) 3.5.1.6, "Aircraft Hazards," have been used in the calculation of the probability of an aircraft crash into the effective plant areas of the safety related structures on the site. In accordance with SRP 3.5.1.6, if the plant-to-airport distance (D) is between five and ten statute miles, and the projected annual number of operations is less than $500D^2$, or the plant-to-airport distance is greater than ten statute miles, and the projected annual number of operations is less than $1000D^2$, the aircraft hazard probability does not need to be calculated because it is considered to be less than an order of magnitude of 10^{-7} per year. If the plant is at least two statute miles beyond the nearest edge of a Federal airway, holding pattern, or approach pattern, the order of magnitude is considered 10^{-7} per year according to SRP 3.5.1.6, and the aircraft hazard probability does not need to be calculated. The aircraft handling facilities and air routes are described in [Subsection 2.2.2.7](#). The aircraft hazard probability developed from the total probability of an aircraft crash into the effective areas of the plant does not constitute a design basis event. The probability of aircraft accidents resulting in radiological consequences greater than the 10 CFR Part 100 exposure guidelines is based on the following:

- Charlotte/Douglas International Airport (CLT) is located about 34.4 miles from Lee Nuclear Station. The average number of operations is approximately 502,152 operations per year, which is less than the acceptable projected annual number of operations of 1,183,360. Based on forecast for terminal area by Federal Aviation Administration (FAA), the number of CLT operations for year 2025 is 767,691 operations per year. Assuming annual compound growth rate of two percent after year 2025, the acceptable projected annual number of operations of 1,183,360 will be reached at year 2046. This increases the number of annual operations over 236 percent from year 2007. Significant expansion of the existing airport facility or construction of a new airport will be required to accommodate this large an increase of air traffic. Thus, the aircraft hazard from this airport to the site is acceptable based on the maximum aircraft activity expected without significant changes to the airport facility.
- One federal airway passes within four miles of the plant site. Low altitude Airway V54 runs between Spartanburg Downtown Memorial Airport, South Carolina (SPA) located 26.1 miles from Lee Nuclear Station and CLT

located 34.4 miles from Lee Nuclear Station. The average annual number of flights using Airway V54 is approximately 15 to 25 percent of the total airport operation. The FAA forecast number of SPA operation for year 2025 is approximately 73,000 operations per year. Based on annual compound growth rate of one percent from year 2025 to year 2060 for SPA, the projected annual number of operations at year 2060 is approximately 103,412. The average annual number of flights for Airway V54 is assumed to be 25 percent of the total airport operation. Therefore, the annual number of flights for Airway V54 is assumed to be 25,853.

- No airports having more than 500D² movements per year are located within 10 miles of the site and no airports having more than 1000D² movements per year are located beyond 10 miles of the site.
- There are no military training routes within 10 miles of the site.

There is one private-use heliport, one private-use ultra-light aircraft airport, and one private-use single-engine airport within a twenty mile range from the site. Because these privately-owned heliport and airports are used for small aircraft, which are low weight, low airspeeds, and low penetration capability, these helicopters and light aircraft are not considered a significant hazard to the nuclear plant.

The analysis conservatively shows that the total probability of aircraft accidents that hit safety-related structures is less than 1.8×10^{-7} per year. This result meets the NRC staff objective of an order of magnitude of 10^{-7} per year, as stated in SRP 3.5.1.6 for meeting the requirements of 10 CFR Part 100 exposure guidelines. In addition, if the expected rate of exposure is an order of magnitude of 10^{-6} per year, and it can be shown with rigorous analysis, using realistic assumptions and reasonable arguments that the estimated probability could be lower, then, in accordance with SRP 2.2.3, it is acceptable.

The following conservatisms used in the analysis are summarized below:

- The only safety-related structures of the AP1000 design are the containment and the auxiliary building. The effective area of these structures is determined using a conservative model for each structure; these areas are added together. The containment was modeled as a rectangle with length and width equal to the diameter of the containment. This assumption will result in diagonal length of the containment greater than the actual diameter of the containment. The area and the diagonal length of the auxiliary building assume that the building is rectangular and does not take credit that some of the area is containment. Credit is not taken for the overlap in these structures.
- The above total aircraft hazard probability at the site is obtained from aircraft crashing from the low altitude federal Airway V54 into the site. This

low altitude route is primarily flown by small, light general aviation aircraft. Light general aviation aircraft are not considered a significant hazard to nuclear power stations because of their low airspeeds, short distance landing capability, high maneuverability and low penetration capability. In addition, the nuclear plant site is not an attractive emergency landing area. Plant protective features against tornado missiles, the inherent strength of the safety-related systems and structures such as containment and auxiliary building, as well as the diversity and redundancy of plant systems reduce the potential hazards to the facility from light aircraft operations to acceptably low levels.

- The heading of the crashing aircraft with respect to the facility is assumed to be the worst case perpendicular to the diagonal of the bounding rectangle regardless of direction of actual flights.
- Credit is not taken for nearby cooling towers, building structures, transmission lines, natural terrain features, etc. that would reduce the effective area of the safety related structures and prevent many disabled aircraft from reaching the critical structures.

As a result of the above conservatisms in the analysis, the aircraft crash hazard probability calculated for Lee Nuclear Station can qualitatively shown to be much lower than the calculated value. Therefore, the aircraft hazards at Lee Nuclear Station pose no undue risk to the health and safety of the public.

3.5.4 COMBINED LICENSE INFORMATION

WLS COL 3.5-1 This COL Item is addressed in **Subsections 3.5.1.5 and 3.5.1.6.**

3.6 PROTECTION AGAINST THE DYNAMIC EFFECTS ASSOCIATED WITH THE POSTULATED RUPTURE OF PIPING

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.6.4.1 Pipe Break Hazard Analysis

Replace the last paragraph in DCD Subsection 3.6.4.1 with the following information:

STD COL 3.6-1 The as-designed pipe rupture hazards evaluation is made available for NRC review. The completed as-designed pipe rupture hazards evaluation will be in accordance with the criteria outlined in **DCD Subsections 3.6.1.3.2** and **3.6.2.5**. Systems, structures, and components identified to be essential targets protected by associated mitigation features (reference is **DCD Table 3.6-3**) will be confirmed as part of the evaluation, and updated information will be provided as appropriate.

A pipe rupture hazards analysis is part of the piping design. The evaluation will be performed for high and moderate energy piping to confirm the protection of systems, structures, and components which are required to be functional during and following a design basis event. The locations of the postulated ruptures and essential targets will be established and required pipe whip restraints and jet shield designs will be included. The report will address environmental and flooding effects of cracks in high and moderate energy piping. The as-designed pipe rupture hazards evaluation is prepared on a generic basis to address COL applications referencing the AP1000 design.

The pipe whip restraint and jet shield design includes the properties and characteristics of procured components connected to the piping, components, and walls at identified break and target locations. The design will be completed prior to installation of the piping and connected components.

The as-built reconciliation of the pipe rupture hazards evaluation whip restraint and jet shield design in accordance with the criteria outlined in **DCD Subsections 3.6.1.3.2** and **3.6.2.5** will be completed prior to fuel load (in accordance with **DCD Tier 1 Table 3.3-6**, Item 8).

This COL item is also addressed in **Subsection 14.3.3**.

3.6.4.4 Primary System Inspection Program for Leak-before-Break Piping

Replace the first paragraph of DCD Subsection 3.6.4.4 with the following information:

STD COL 3.6-4 Alloy 690 is not used in leak-before-break piping. No additional or augmented inspections are required beyond the inservice inspection program for leak-before-break piping. An as-built verification of the leak-before-break piping is required to verify that no change was introduced that would invalidate the conclusion reached in this subsection.

3.7 SEISMIC DESIGN

This section of the referenced DCD is incorporated by reference with the following departures and/or supplements.

Add Subsection 3.7.1.1.1 as follows:

3.7.1.1.1 Design Foundation Response Spectra

WLS SUP 3.7-3 Design foundation response spectra for Lee Nuclear Station Unit 1 and Unit 2 nuclear islands are presented in this subsection. The foundation conditions at Lee Nuclear Station are unique in that the Unit 1 nuclear island foundation is supported on new and previously placed concrete materials placed directly over continuous rock. In contrast, the Unit 2 nuclear island foundation is configured more conventionally with the nuclear island founded directly over continuous rock, except for the eastern edge of the Unit 2 nuclear island, which will require approximately 20 ft. of fill concrete to build up the support zone to the base of the nuclear island. The Lee Nuclear Station site provides uniform hard-rock support for the nuclear island; foundation conditions and uniformity are described in Subsection 2.5.4.7.4 (Figure 2.5.4-241). Measured shear wave velocities for continuous rock underlying the Units 1 and 2 nuclear islands range from between 9000 to 10,000 fps, as described in Subsection 2.5.4.7. The stability of subsurface materials including foundation conditions are described in Subsection 2.5.4.

Based on these foundation conditions, individual foundation response spectra are provided for the certified design portion of the plant at Units 1 and 2. The site-specific dynamic velocity profiles developed for the Lee Nuclear Station are described in Subsection 2.5.4.7.5. As described in Subsection 2.5.2.7.4, the site ground motion response spectra (GMRS) defines the input motion (FIRS) at Unit 2, while the FIRS associated with dynamic profile A1 defines the Unit 1 FIRS.

For Unit 1, the Foundation Input Response Spectrum (FIRS) defines the site response foundation input motion for the nuclear island foundation placed on concrete over continuous rock. Unit 1 FIRS, associated with Unit 1 FIRS A1 dynamic velocity profile (Figure 2.5.4-252a), represents the nuclear island centerline foundation input motion and is based on the GMRS developed at the top of a hypothetical outcrop (e.g. continuous rock) fixed at 530 feet North American Vertical Datum (NAVD) transferred up through previously placed and new concrete materials to the basemat foundation level at 553.5 feet (NAVD).

For Unit 2, the GMRS defines the site response foundation input motion developed at the top of a hypothetical outcrop of competent material (e.g. continuous rock) fixed at the basemat foundation level at 553.5 feet (NAVD). The GMRS (Unit 2 FIRS) is associated with dynamic velocity Profile C (Figure 2.5.4-250).

Detailed discussions of the methods used to calculate the horizontal and vertical GMRS and FIRS are described in [Subsections 2.5.2.6](#), Ground Motion Response Spectra (GMRS), and [2.5.2.7](#), Development of FIRS for Units 1 and 2.

WLS DEP 2.0-1 Both the GMRS and the Unit 1 FIRS exceed the AP1000 CSDRS at higher frequencies. As a conservative simplification, the site-specific foundation input motion for both Units 1 and 2 is represented as the horizontal and vertical envelope of the GMRS (Unit 2) and Unit 1 FIRS. These envelope spectra, considered to be applicable to both units, are illustrated in [Figures 3.7-201](#) and [3.7-202](#), and are referred to as the nuclear island FIRS (NI FIRS). As shown on [Figure 3.7-201](#), the horizontal NI FIRS exceeds the horizontal AP1000 CSDRS at frequencies above approximately 14 hertz. PGA at 100 hertz of the NI FIRS is 0.352 g. As shown on [Figure 3.7-202](#), the vertical NI FIRS exceeds the vertical AP1000 CSDRS at frequencies above approximately 16 hertz.

As shown on [Figure 3.7-201](#), the horizontal NI FIRS is above the horizontal AP1000 HRHF spectrum for all frequencies above about 3 hertz. As shown on [Figure 3.7-202](#), the vertical NI FIRS is above the vertical AP1000 HRHF for frequencies between about 3 to 55 hertz and 80 to 100 hertz.

WLS SUP 3.7-3 As described in AP1000 [DCD Appendix 3I](#), generic hard rock spectrum high frequency exceedances are within the seismic design margin of the AP1000 and will not adversely affect the structures, systems, or components of the plant.

The Lee Nuclear Station site provides uniform hard-rock support for the nuclear island, but the site characteristic NI FIRS exceed the horizontal and vertical AP1000 HRHF. As described in AP1000 [DCD Section 2.5.2.1](#), Paragraph 4b, if the site-specific spectra are not enveloped by the AP1000 HRHF envelope response spectra or the AP1000 CSDRS, the COL applicant may perform site-specific studies to demonstrate high frequency is not damaging. Therefore, a site-specific analysis of the AP1000 has been performed, similar to the analysis described in AP1000 [DCD Appendix 3I](#), to demonstrate that these high frequency spectra exceedances are within the seismic design margin of the AP1000 certified design and will not adversely affect the structures, systems, or components of the plant ([Reference 206](#)). [Subsection 3.7.2.15](#) describes confirmatory site-specific analyses of the nuclear island that demonstrate compliance with the AP1000 DCD.

3.7.2.1.2 Time-History Analysis and Complex Frequency Response Analysis

Add the following information to the end of DCD Subsection 3.7.2.1.2:

WLS SUP 3.7-6 For cases when site-specific analyses of the nuclear island structures may be required, artificial time histories (two horizontal and one vertical) were developed to be compatible with the Lee Nuclear Station foundation input motions, and to satisfy the requirements of Standard Review Plan (SRP) 3.7.1. As a conservative simplification, the foundation input motion for both units was represented as the envelope of the GMRS (Unit 2 FIRS) and the Unit 1 FIRS, referred to as the Lee Nuclear Station NI FIRS (Figures 3.7-201 and 3.7-202). The methodology used in the development of these time histories is summarized in the following four steps:

1. Select a real 3-component ground-motion record to use as a starting point. All components should be broad-banded and should have reasonable durations consistent with the magnitude and distance of the earthquake. The ILA031 record from the 1999 Chi-Chi earthquake in Taiwan (magnitude (**M**) 7.6, closest distance (R_{closest}) = 94.7 km) is selected. This record is part of the NRC time history library (Reference 207) and belongs to the WUS ROCK, **M**>7, D=50-100 km bin.
2. Modify the time history for each component using spectral-matching software until it is compatible with the target response spectrum.
3. Use visual examination of the results to confirm that the resulting time histories are realistic and independent calculations to confirm that they meet the requirements of SRP 3.7.1 as well as the requirements defined in Item 4 below. A scaling factor may be used in this step to make minor adjustments.
4. Calculate the cross-correlation coefficients between the three components of acceleration and check that they do not exceed the criterion of $|\text{cross-correlation}| < 0.16$.

Additionally, the following criteria are also applied:

- a. Time step interval shall be no more than 0.005 seconds.
- b. Total duration of the motion shall be no less than 30 seconds.
- c. The strong motion duration (5%-75% Arias intensity) shall be consistent with the magnitude and distance of interest.
- d. The time histories of the three components shall be statistically independent. The cross-correlation shall not exceed 0.16.

Attributes of the resulting time histories representing the NI FIRS are shown in Table 3.7-201. Figures 3.7-203a through 203c illustrate the three component time histories.

3.7.2.8.4 Seismic Modeling and Analysis of Seismic Category II Building Structures

Add the following information to the end of DCD Subsection 3.7.2.8.4:

WLS SUP 3.7-4 FSAR Subsection 2.5.4.5.2 describes how areas in the foundation support zones of Seismic Category II buildings (the Annex Building and Turbine Building first bay) will be excavated to expose concrete or rock, and fill concrete will be used to build up to the base level of the nuclear island. If rock within the foundation support zone of these Seismic Category II structures is higher than the base of the nuclear island, the rock will be removed to the elevation of the base of the nuclear island. In areas where the pre-existing concrete and/or rock within the foundation support zone of these Seismic Category II structures are at a lower elevation than the base of the nuclear island, fill concrete will be used to build up to the base level of the nuclear island. This configuration is illustrated in FSAR Figures 2.5.4-245 and 2.5.4-260 through 2.5.4-265. These measures ensure that the Lee Nuclear Station site provides uniform support for the Seismic Category II structures in a configuration identical to that considered in the AP1000 DCD designs.

From the candidate granular fill materials described in FSAR Subsection 2.5.4, Duke Energy has determined that Macadam Base Course material provides properties appropriate for precluding interaction of Seismic Category II buildings with the nuclear island. Duke Energy has selected the static and dynamic properties described in FSAR Subsection 2.5.4 as well-graded gravel (GW) to represent that Macadam Base Course material.

The properties of the granular fill material that will be placed above continuous rock, presented in FSAR Table 2.5.4-211 and FSAR Tables 2.5.4-224A through 2.5.4-224F, are consistent with those used by Westinghouse in developing design criteria for adjacent Seismic Category II structures and include having a shear wave velocity greater than 500 fps.

The Lee site-specific bearing capacity for the granular fill material supporting the Seismic Category II structures (shown in FSAR Table 2.5.4-228) is greater than the generic AP1000 bearing demand for these structures.

As described in FSAR Subsection 2.5.4.5.1, the source for the granular fill material (Macadam Base Course) supporting the Seismic Category II buildings has not yet been identified. Once a source for the granular fill material has been selected, the static and dynamic properties of the material supporting Seismic

Category II buildings will be verified as compatible with Lee Nuclear Station site response analyses.

The information above demonstrates that the Lee site provides uniform support for the Seismic Category II buildings; site-specific fill material is consistent with that considered in establishing generic AP1000 design criteria for these buildings; the configuration of the granular fill supporting the Seismic Category II buildings is consistent with that described in the AP1000 DCD; and the bearing capacity of the supporting granular fill is greater than the bearing demand. Therefore, the Lee Nuclear Station site complies explicitly with the requirements of **DCD**

WLS DEP 2.0-1 **Subsection 3.7.2.8.4** for a hard rock site, with the exception that the NI FIRS is not bounded by the AP1000 HRHF spectra.

WLS SUP 3.7-4 As permitted by **DCD Subsection 3.7.2.8.4**, site-specific analyses of the Lee Nuclear Station Seismic Category II adjacent buildings were performed. Site-specific performance-based surface response spectra (PBSRS) at plant grade were developed for each Seismic Category II building, using the same analytical methods used in calculating the Unit 1 FIRS. Hazard-consistent, strain-compatible properties were also developed for the granular fill material supporting the Seismic Category II adjacent buildings. These site-specific characteristics are used as inputs to the site-specific soil-structure interaction analyses described in **Reference 205**, which are performed using analyses consistent with those supporting the AP1000 DCD.

The analyses presented in **Reference 205** confirm that the calculated site-specific relative displacements of the Seismic Category II adjacent buildings are much less than the building separation provided, so there is no contact between the nuclear island and the Seismic Category II adjacent buildings. The maximum relative displacements at the foundation level are approximately 0.10" and 0.20" for the Annex Building and Turbine Building, respectively, compared to 2" separation provided at the foundation level. The maximum relative displacement between the top of the adjacent structure and the nuclear island is approximately 0.27" and 0.58" for the Annex Building and Turbine Building, respectively, compared to 4" separation provided. The maximum site-specific bearing demand (approximately 24.5 ksf for the Annex Building and 5.3 ksf for the Turbine Building) is significantly less than the site-specific allowable bearing pressure shown in **FSAR Table 2.5.4-228** (approximately 33.55 ksf for the Annex Building and 45.03 ksf for the Turbine Building), demonstrating that the granular fill material selected is adequate for supporting those structures.

FSAR Subsection 19.55 discusses confirming the seismic design margin for potential events up to a Review Level Earthquake (RLE) of 1.67 times the SSE. By scaling the differential displacements above for the RLE, the estimated maximum relative displacements at the foundation level are approximately 0.17" and 0.34" for the Annex Building and Turbine Building, respectively, compared to 2" separation provided at the foundation level. For the RLE, the maximum relative displacement between the top of the adjacent structures and the nuclear island is approximately 0.45" and 0.97" for the Annex Building and Turbine Building, respectively, compared to 4" separation provided. These comparisons demonstrate the building separation design margin available is adequate for the

RLE. Similarly, since the allowable bearing pressures shown in **FSAR Table 2.5.4-228** already include a factor of safety of three against bearing failure, the granular fill material supporting the Seismic Category II buildings also clearly satisfies the bearing capacity design margin requirements for the RLE.

As required by AP1000 **DCD Subsection 3.7.2.8.4**, the Lee site-specific Seismic Category II foundation seismic response spectra are compared to the corresponding AP1000 annex building and turbine building first bay generic design envelope response spectra. This comparison is shown in **Figures 3.7-213a** and **3.7-213b** for the annex building and **Figures 3.7-214a** and **3.7-214b** for the first bay of the turbine building. These foundation response spectra are computed in 2-D analyses, and have been adjusted for 3-D effects, as required by the AP1000 DCD.

Figure 3.7-213a demonstrates that the site-specific annex building horizontal foundation response spectrum falls beneath the generic design envelope that is used in designing the AP1000 standard annex building. **Figure 3.7-214a** illustrates the comparable horizontal foundation response spectrum for the turbine building first bay, which is generally less than the generic design envelope, but exhibits a minor exceedance between 3 Hz and 5 Hz for one soil case. These horizontal foundation response spectra are of primary importance in assessing the potential interactions of Seismic Category II adjacent buildings with the nuclear island. The comparison provides high confidence that the lateral force resisting system for the AP1000 standard Seismic Category II adjacent structures is also adequate for the Lee site-specific seismic requirements.

Figure 3.7-213b and **Figure 3.7-214b** compare the site-specific vertical foundation response spectra to the comparable generic design envelope for the AP1000 standard annex building and turbine building first bay, respectively. For both the annex building and the turbine building first bay, vertical spectra exceedances are noted between about 6 Hz and 25 Hz. These exceedances are likely associated with vertical resonance of the granular fill column in this frequency range. These vertical foundation response spectra are of less importance in assessing potential interactions with the nuclear island, but are important for design of individual building elements such as floor slabs and roofs within the Seismic Category II adjacent structures.

As required by **DCD Subsection 3.7.2.8**, Seismic Category II adjacent structures must be designed to prevent their collapse when subjected to their design earthquake. Therefore, the detailed design of the building elements making up the AP1000 standard Seismic Category II adjacent structures will be reviewed to confirm that they satisfy the acceptance criteria specified in AP1000 **DCD Subsection 3.7.2** when subjected to the forces resulting from the site-specific foundation response spectra. Should any building element not meet those criteria, appropriate design changes will be implemented to increase its capacity. In this manner, Duke Energy will confirm that the Seismic Category II adjacent buildings are designed not only for the site-specific seismic requirements, but also for the AP1000 Seismic Category II adjacent buildings generic design envelope. The review will also include considerations of adjacent structure sliding and overturning in response to the site-specific seismic requirements. This review will

be conducted when the source of the actual granular fill material supporting the Seismic Category II adjacent buildings is selected, as part of verifying the compatibility of that material with the facility seismic design. This approach to the non-safety related Seismic Category II adjacent buildings is similar to that used for an item of equipment for which detailed fabrication design has not been completed, but for which all safety-related performance requirements have been identified. The review and any required design changes will be completed prior to start of construction of the Seismic Category II adjacent buildings at Lee Nuclear Station.

3.7.2.12 Methods for Seismic Analysis of Dams

Add the following information to the end of DCD Subsection 3.7.2.12:

- WLS COL 3.7-1 The evaluation of existing and new dams whose failure could affect the site interface flood level specified in **DCD Subsection 2.4.1.2** is included in **Subsection 2.4.4**.
-

3.7.2.15 Site-Specific Analyses of Nuclear Island Seismic Category I Structures

Add the following information to the end of DCD Subsection 3.7.2:

- WLS DEP 2.0-1 As described in **FSAR Subsection 3.7.1.1.1**, the Lee Nuclear Station site provides uniform hard-rock support but the updated site characteristic GMRS and Unit 1
WLS SUP 3.7-5 FIRS are not bounded by the HRHF spectra. To address the exceedances of the design basis AP1000 CSDRS and alternate AP1000 HRHF spectra described above, confirmatory site-specific analyses of the nuclear island Seismic Category I structures were performed using an envelope of the updated GMRS (Unit 2 FIRS) and Unit 1 FIRS, referred to as NI FIRS, to confirm that site-specific seismic demands will not adversely affect the structures, systems, or components of the Lee Nuclear Station (**Reference 206**). This site-specific evaluation uses the same methodology described in AP1000 **DCD Appendix 3I** to evaluate and qualify the AP1000 HRHF spectra.
-

- WLS SUP 3.7-5 These site-specific analyses described in **Reference 206** include three-dimensional incoherent SSI analysis based on the NI FIRS. The nuclear island analytical model used in these analyses is an updated version of the NI20 model referred to as NI20u. The updated NI20u model includes detailed design changes identified since AP1000 DCD Revision 19. The model also includes refinements to

provide a better match to the more detailed NI10 model used in the AP1000 DCD analyses, while continuing to be a conservative representation of the NI10 model. All AP1000 DCD descriptions of the NI20 model remain applicable to the NI20u model, and the changes incorporated do not impact or require an update to the licensing basis as defined in the AP1000 DCD Revision 19.

A screening criteria is used to identify a representative sample of AP1000 structures, systems, and components (SSCs) to be evaluated to demonstrate acceptability of the AP1000 certified design for the Lee Nuclear Station NI FIRS (Reference 206). To better understand the significance of the evaluations required, the in-structure response spectra for the AP1000 CSDRS, HRHF spectra and NI FIRS were compared at the six key locations identified in AP1000 DCD Table 3G.4-1 as listed below.

- Containment internal structures (CISs) at elevation of reactor vessel support – Node 1761
- Auxiliary building northeast corner at elevation 116'-6" – Node 2078
- Containment operating floor – Node 2199
- Shield building at fuel building roof – Node 2675
- Steel containment vessel (SCV) at polar crane support – Node 2788
- Shield building roof – Node 3329

The resulting site-specific in-structure FRS are shown in Figures 3.7-209a through 3.7-211c for these six (6) key locations. These figures compare the in-structure spectra resulting from the envelope of the AP1000 CSDRS cases (bold black curve) to that resulting from the AP1000 HRHF analyses (solid red curve) to that resulting from the site-specific NI FIRS (dashed blue curve). Note that these spectra are at the same locations, though the node numbers in the site-specific NI20u model are different than in the NI20 model used for AP1000 DCD Revision 19. Note that the AP1000 HRHF broad curve (envelope) is based on SASSI 3D analyses and includes seismic motion incoherency effects. The 3D analyses compare the Lee Nuclear Station 3D FRS results with incoherency to the AP1000 HRHF envelope, also including incoherency.

WLS DEP 2.0-1 At these six key locations, minor exceedances of the comparable AP1000 DCD in-structure spectra resulting from the AP1000 CSDRS or HRHF spectra were noted. More detailed evaluations are therefore presented in Reference 206 to justify those exceedances and to demonstrate that they are acceptable.

In-structure floor response spectra were investigated in additional locations, consistent with the evaluations supporting Appendix 3I of the DCD. These locations are shown below.

- Auxiliary and Shield Building at Grade
- Auxiliary and Shield Building at Main Control Room Floor
- Auxiliary and Shield Building at Elevation 135'
- Auxiliary and Shield Building at Elevations 160', 180' and 230'
- Auxiliary and Shield Building at Elevations 267', 289' and 327'
- Containment Internal Structures at Grade Elevation 99'
- Containment Internal Structures at Elevation 135'
- Containment Internal Structures at Elevations 153' East, 153' West, and 160'
- Hot Legs and Pressurizer Bottom

In-structure response spectra at these locations were investigated and all exceedances of the CSDRS or HRHF spectra were identified. Three instances of largest exceedances were noted, and these three instances were investigated as bounding conditions.

The first instance is above 60 Hz in the vertical direction for the Auxiliary and Shield Building at Main Control Room Floor. The second instance is above 60 Hz in the vertical direction for the Containment Internal Structures at Elevation 153'. **Figure 3.7-212** shows the in-structure vertical spectra for these two locations. The only equipment potentially affected by such high frequency exceedance is tested to levels higher than those imposed by these in-structure spectra.

Reference 206 describes a review of current AP1000 equipment qualification test methods and requirements, and a comparison of those requirements to the Lee site-specific requirements. Some of the site-specific in-structure spectra exhibit minor exceedances of the comparable standard AP1000 qualification required response spectra (RRS) envelopes. Nevertheless, in all cases the actual test response spectra (TRS) used in completed testing exceed the site-specific demands by a significant margin. Therefore, those qualification tests are also concluded to be applicable for the Lee site-specific requirements, and that there is high confidence that future tests will also be applicable to Lee site-specific requirements. Duke Energy will ensure that all seismic qualification testing for safety-related equipment required per **DCD Appendix 3I** appropriately envelopes the Lee site-specific requirements, in addition to the CSDRS and HRHF RRS.

The third instance of in-structure response spectrum exceedance was at lower horizontal frequencies at the reactor coolant loop hot legs and pressurizer bottom. This exceedance was justified by detailed comparative analyses of two representative piping systems (the Automatic Depressurization System and the Pressurizer Surge Line) attached at these locations.

As described in [DCD Appendix 3I](#), ASME Class 1, Class 2, and Class 3 piping is designed for both CSDRS and HRHF spectra. As described in [Reference 206](#), forty piping packages and the associated floor response spectra were reviewed for susceptibility to high frequency input motion. Three piping packages were selected for detailed review as the most susceptible to the effects of high frequency inputs, and to any differences between the site-specific spectra and CSDRS or HRHF spectra. Two of those packages, a portion of the Automatic Depressurization System and the Pressurizer Surge Line, attach to the reactor coolant loop hot legs and to the pressurizer bottom, where in-structure spectra exceedances of the Lee site-specific spectra compared to CSDRS or HRHF spectra were noted. The third package, a portion of the Spent Fuel System in the Auxiliary Building, was selected based on its potential susceptibility to high-frequency input motion.

The stress analysis results for these three piping systems ([Reference 206](#)) indicate that the piping stresses resulting from the site-specific spectra are less than those resulting from HRHF spectra except for the Pressurizer Surge Line, where the site-specific stresses are slightly higher. Nevertheless, the stresses resulting from the CSDRS were demonstrated to control the design over both the site-specific spectra and HRHF spectra, except for one point where the site-specific stresses are slightly higher than those due to CSDRS. At this single point, the site-specific stresses are less than those associated with the HRHF. Therefore, the standard design practices for AP1000 piping systems have considered cases enveloping the Lee site-specific requirements. Based on the selection of these piping packages, these results are representative of all safety class piping for the plant. In conclusion, stresses resulting from site-specific high frequency input are bounded by AP1000 design basis analysis results, and the effect of site-specific high frequency input on piping is non-damaging.

Evaluations of representative portions of the building structures (three locations in the Auxiliary Building, eight locations in the Shield Building and three areas in the CIS) confirmed that the seismic loads associated with the design basis AP1000 CSDRS envelope those from the Lee site-specific spectra in all cases ([Reference 206](#)).

The reactor vessel and internals were selected for evaluation as representative of major equipment. The analyses described in [Reference 206](#) demonstrate that the AP1000 CSDRS results in higher loads and stresses than those from the Lee site-specific spectra. Likewise, the design of the primary component supports and the reactor coolant loop primary equipment nozzles were found to be controlled by the CSDRS rather than the Lee site-specific spectra.

As described above, a site-specific analysis of the AP1000 using the Lee site-specific criteria has been performed, comparing the resulting in-structure spectra at six key locations to the spectra resulting from the design basis AP1000 CSDRS envelope. Exceedances of those in-structure standard plant spectra have been evaluated and justified ([Reference 206](#)) by detailed site-specific analyses of representative portions of building structures, primary equipment and piping

systems, and by a review of standard AP1000 seismic qualification testing practices.

3.7.4.1 Comparison with Regulatory Guide 1.12

Add the following information to the end of DCD Subsection 3.7.4.1:

- STD SUP 3.7-1 Administrative procedures define the maintenance and repair of the seismic instrumentation to keep the maximum number of instruments in-service during plant operation and shutdown in accordance with Regulatory Guide 1.12.
-

3.7.4.2.1 Triaxial Acceleration Sensors

Add the following information to the end of DCD Subsection 3.7.4.2.1:

- STD COL 3.7-5 A free-field sensor will be located and installed to record the ground surface motion representative of the site. It will be located such that the effects associated with surface features, buildings, and components on the recorded ground motion will be insignificant. The trigger value is initially set at 0.01g.
-

3.7.4.4 Comparison of Measured and Predicted Responses

Add the following information to the end of DCD Subsection 3.7.4.4:

- STD COL 3.7-2 Post-earthquake operating procedures utilize the guidance of EPRI Reports NP-5930, TR-100082, and NP-6695, as modified and endorsed by the NRC in Regulatory Guides 1.166 and 1.167. A response spectrum check up to 10Hz will be based on the foundation instrument. The cumulative absolute velocity will be calculated based on the recorded motions at the free field instrument. If the operating basis earthquake ground motion is exceeded or significant plant damage occurs, the plant must be shutdown in an orderly manner.

In addition, the procedures address measurement of the post-seismic event gaps between the new fuel rack and walls of the new fuel storage pit, between the individual spent fuel racks, and from the spent fuel racks to the spent fuel pool

walls, and provide for appropriate corrective actions to be taken if needed (such as repositioning the racks or analysis of the as-found condition).

3.7.4.5 Tests and Inspections

Add the following information to the end of DCD Subsection 3.7.4.5:

- STD SUP 3.7-2 Installation and acceptance testing of the triaxial acceleration sensors described in **DCD Subsection 3.7.4.2.1** is completed prior to initial startup. Installation and acceptance testing of the time-history analyzer described in **DCD Subsection 3.7.4.2.2** is completed prior to initial startup.
-

3.7.5 COMBINED LICENSE INFORMATION

3.7.5.1 Seismic Analysis of Dams

- WLS COL 3.7-1 This COL Item is addressed in **Subsection 3.7.2.12**.
-

3.7.5.2 Post-Earthquake Procedures

- STD COL 3.7-2 This COL Item is addressed in **Subsection 3.7.4.4**.
-

3.7.5.3 Seismic Interaction Review

Replace DCD Subsection 3.7.5.3 with the following information:

- STD COL 3.7-3 The seismic interaction review will be updated for as-built information. This review is performed in parallel with the seismic margin evaluation. The review is based on as-procured data, as well as the as-constructed condition. The as-built seismic interaction review is completed prior to fuel load.
-

3.7.5.4 Reconciliation of Seismic Analyses of Nuclear Island Structures

Replace DCD Subsection 3.7.5.4 with the following information:

- STD COL 3.7-4 The seismic analyses described in **DCD Subsection 3.7.2** will be reconciled for detailed design changes, such as those due to as-procured or as-built changes in component mass, center of gravity, and support configuration based on as-procured equipment information. Deviations are acceptable based on an evaluation consistent with the methods and procedure of **DCD Section 3.7** provided the amplitude of the seismic floor response spectra, including the effect due to these deviations, does not exceed the design basis floor response spectra by more than 10 percent. This reconciliation will be completed prior to fuel load.
-

3.7.5.5 Free Field Acceleration Sensor

- STD COL 3.7-5 This COL Item is addressed in **Subsection 3.7.4.2.1**.
-

3.7.6 REFERENCES

- 201. Removed
- 202. Removed
- 203. Removed
- 204. Removed
- 205. Westinghouse Electric Company Report WLG-1000-S2R-804, Revision 3, William S. Lee Site Specific Adjacent Buildings Seismic Evaluation Report, February 2014.
- 206. Westinghouse Electric Company, LLC, "Effect of William S. Lee Site Specific Seismic Requirements on AP1000 SSCs," WLG-GW-GLR-815, Revision 0, January 17, 2014.
- 207. McGuire, R.K., Silva, W.J., and Constantino, C.J. (2001). Technical basis for revision of regulatory guidance on design ground motions: hazard- and risk-consistent ground motion spectra guidelines, U.S. Nuclear Regulatory Commission Report, NUREG/CR-6728, October, 2001.

WLS SUP 3.7-6

TABLE 3.7-201
SUMMARY OF CHARACTERISTICS OF ARTIFICIAL TIME
HISTORIES REPRESENTING NI FIRS

Parameter	Horizontal 1	Horizontal 2	Vertical
Duration (5-75%; sec)	13.6	14.4	11.3
PGA (g)	0.36	0.36	0.33
PGV (cm/sec)	11	15	8.7
PGD (cm)	7.4	7.7	5.5
PGD/PGA (cm/g)	21	21	17
PGV/PGA (cm/sec/g)	30	42	27
PGA*PGD/PGV ²	22	12	23
Correlation with Horizontal 1	--	0.044	0.15
Correlation with Horizontal 2	--	--	0.077

Note: Individual time histories are denoted as follows:

Horizontal 1 = ILA031-N
Horizontal 2 = ILA031-W
Vertical = ILA031-V

TABLE 3.7-202 (Sheet 1 of 2)
SEISMIC CATEGORY I EQUIPMENT OUTSIDE CONTAINMENT
BY ROOM NUMBER

Room No.	Room Name	Equipment Description
12101	Division A battery room	Batteries
12102	Division C battery room 1	Batteries
12103	Spare battery room	Spare batteries
12104	Division B battery room 1	Batteries
12105	Division D battery room	Batteries
12113	Spare battery charger room	
12162	RNS pump room A	RNS pressure boundary
12163	RNS pump room B	RNS pressure boundary
12201	Division A dc equipment room	dc equipment
12202	Division C battery room 2	Batteries
12203	Division C dc equipment room	dc equipment
12204	Division B battery room 2	Batteries
12205	Division D dc equipment room	dc equipment
12207	Division B dc equipment room	dc equipment
12211	Corridor	Divisional cables
12212	Division B RCP trip switchgear room	RCP trip switchgear
12244	Lower annulus valve area	CVS/WLS containment isolation valves
12251	Demineralizer/filter access area	CVS/DWS isolation valves
12254	SFS penetration room	SFS containment isolation valve
12256	Containment isolation valve room	RNS containment isolation valves
12259	Pipe chase	RNS piping
12262	Piping/Valve room	RNS pressure boundary, SFS piping
12265	Waste monitor tank room C	SFS piping
12269	Pipe chase	RNS pressure boundary
WLS DEP 6.4-2 12300	Corridor	Divisional cable, MCR load shed panel
12301	Division A I&C room	Divisional I&C
12302	Division C I&C room	Divisional I&C
12303	Remote shutdown room	Divisional cabling

TABLE 3.7-202 (Sheet 2 of 2)
SEISMIC CATEGORY I EQUIPMENT OUTSIDE CONTAINMENT
BY ROOM NUMBER

Room No.	Room Name	Equipment Description	
12304	Division B I&C/penetration room	Divisional I&C/electrical penetrations	
12305	Division D I&C/penetration room	Divisional I&C/electrical penetrations	
12306	Valve/piping penetration room	CCS/CVS/DWS/FPS/SGS containment isolation valves	
12311	Corridor	Divisional cabling	
12312	Division C RCP trip switchgear room	RCP trip switchgear	
12313	Division C I&C/penetration room	Divisional I&C/electrical penetrations	
12321	Non-1E equipment/penetration room	Divisional cabling	
12341	Middle annulus	Class 1E electrical penetrations Various mechanical piping penetrations	
12351	Maintenance floor staging area	Divisional cabling (ceiling)	
12352	Personnel hatch	Personnel airlock (interlocks)	
12354	Middle annulus access room	PSS/SFS containment isolation valves	
12362	RNS HX room	RNS pressure boundary	
12365	Waste monitor tank room B	SFS piping	
12400	Control room vestibule	Control room access	
12401	Main control room	Dedicated safety panel VBS HVAC dampers VES isolation valves Lighting circuits Mounting for lighting fixtures	
12404	Lower MSIV compartment B	SGS containment isolation valves, instrumentation and controls	
12405	Lower VBS B and D equipment room	VWS/PXS/CAS containment isolation valves	
12406	Lower MSIV compartment A	SGS containment isolation valves, instrumentation and controls	
WLS DEP 6.4-2	12412 Electrical penetration room Division A	Divisional electrical penetrations, MCR load shed panel	

3.8 DESIGN OF CATEGORY I STRUCTURES

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.8.3.7 In-Service Testing and Inspection Requirements

Replace the existing DCD statement with the following:

STD COL 3.8-5 The inspection program for structures is identified in **Section 17.6**. This inspection program is consistent with the requirements of 10 CFR 50.65 and the guidance in Regulatory Guide 1.160.

WLS SUP 3.8-1 3.8.4.4.4 Below Grade Exterior Walls

Add the following to DCD Subsection 3.8.4.4.4, at the end of the discussion under the sub-heading Load Combinations:

In **Reference 201**, Westinghouse has evaluated the Lee Nuclear Station site-specific lateral earth pressures by comparing the site-specific pressures on the nuclear island below-grade walls for Load Combinations (LC) 1 through 9 in **DCD Table 3.8.4-2** to the corresponding pressures that were used in the AP1000 standard design. **Reference 201** notes that the site-specific lateral pressures on the nuclear island exterior walls below grade are bounded by the AP1000 design pressures for load combinations 1, 2, 3, 4, 5, 6, 8 and 9 in both the east-west (E-W) and north-south (N-S) directions. **Reference 201** also notes that the site-specific lateral pressure in Load Combination 7 (LC7) for the GW backfill material slightly exceeds the AP1000 LC7 lateral pressure. **Figures 3.8-201a, 3.8-201b, 3.8-202a and 3.8-202b** compare the site-specific pressures on the below-grade walls to those used in the AP1000 standard design.

LC7 includes the summation of the full passive lateral earth pressure, the static and dynamic lateral surcharges, and the water pressure. The difference in LC7 for the Lee Nuclear Station site compared to the AP1000 generic site is mainly attributed to the site-specific ground water level, which in its shallowest/closest to ground surface condition, is at 8.0 feet below ground surface (bgs) as compared to the AP 1000 ground water level of 2 feet bgs. This difference results in six additional feet of non-buoyant (heavier) soil than considered in the AP1000 standard evaluations, resulting in a corresponding higher passive earth pressure component in the LC7 equation.

Passive pressure, which resists the lateral movement of the nuclear island, is not relied upon for resistance to sliding during a seismic event. Further, development of the full passive pressure requires more displacement than the nuclear islands will experience during a seismic event. As described in **DCD Subsection 3.8.5.5.5**, the maximum lateral displacement at the base of the nuclear island when

subjected to the CSDRS is expected to be 0.12 inches neglecting buoyancy of the nuclear island, and 0.19 inches considering buoyancy effects. Since overall site-specific analyses of the nuclear island demonstrate that the effects of the CSDRS bound those of the Lee Nuclear Station NI FIRS, the Lee site-specific lateral displacements will be even less. Small lateral displacements such as these are not capable of developing the full passive earth pressure. Therefore, the site-specific nuclear island below-grade wall pressures resulting from the NI FIRS will be less than those used in the standard AP1000 design for this load combination.

As confirmation, analytical estimates of the fraction of the full Lee Nuclear Station site-specific passive earth pressure that might be mobilized in the GW backfill have been calculated. These values are calculated for a given displacement of the nuclear island, conservatively assumed to be 0.2 inches. The estimates are made using the methodology in [References 202 and 203](#), and investigate a range of site-specific groundwater levels from high (8 ft bgs) to low (18 ft bgs), and a wide range of soil modulus values, including those from results in [Reference 204](#).

[Table 3.8-201](#) (Column 6) summarizes the mobilized fraction (“Mob”) of the full Lee Nuclear Station passive lateral earth pressure for the assumed 0.2” displacement for the range of water table depths at the Lee Nuclear Station site, and for the range of soil modulus and Poisson’s ratio values used. This fraction ranges from about 0.09 to about 0.60 in the E-W direction, and from about 0.12 to about 0.65 in the N-S direction. [Table 3.8-201](#) (Column 7) presents the mobilized Lee Nuclear Station passive lateral earth pressure as a fraction of the full passive earth pressure considered in the AP1000 standard design. This fraction ranges from about 0.22 to about 0.77 in the east-west direction and from about 0.25 to about 0.83 in the north-south direction. The wide range of soil modulus values used in the analyses to conservatively bound a range of possible values accounts for the range of ratios shown. These ratio values are conservative since the actual displacements at the Lee Nuclear Station site will be less than the range for the generic AP1000 site and thus less than the assumed displacement of 0.2 inches used to calculate the ratios in [Table 3.8-201](#).

The mobilized soil pressures, combined with the static and (site-specific) dynamic lateral surcharges and the site-specific water pressures, are plotted in [Figures 3.8-203 and 3.8-204](#). These figures also illustrate the standard AP1000 design pressures for LC7 (from [Reference 201](#)). [Figures 3.8-203 and 3.8-204](#) convincingly illustrate that WLS passive pressure in LC7 will not be fully developed, and that the AP1000 standard pressures for LC7 conservatively bound the pressures that will actually occur at the Lee Nuclear Station site.

WLS DEP 3.8-1 [DCD Subsection 3.8.4.4.4](#) states that below-grade walls are designed for the full passive earth pressure. Since the site-specific pressures on below-grade walls for LC7 exceed those used in the AP1000 standard design when full passive earth pressures are assumed, this statement is not correct for the Lee Nuclear Station site. This is identified as a departure from the AP1000 DCD. The departure is of no significance since the pressures on below-grade walls used in the AP1000

standard design bound those that will actually occur at the Lee Nuclear Station site.

3.8.4.7 Testing and In-Service Inspection Requirements

Replace the existing DCD final statement of the subsection with the following:

- STD COL 3.8-5 The inspection program for structures is identified in **Section 17.6**. This inspection program is consistent with the requirements of 10 CFR 50.65 and the guidance in Regulatory Guide 1.160.
-

3.8.5.1 Description of the Foundations

Add the following information after paragraph one of DCD Subsection 3.8.5.1:

- STD SUP 3.8-1 The depth of overburden and depth of embedment are given in **Subsection 2.5.4**.
-

Add the following information to the end of DCD Subsection 3.8.5.1 as a new paragraph:

- WLS COL 2.5-17 The Lee Nuclear Station site-specific waterproofing approach has not yet been selected. However, the waterproof membrane or waterproofing system for the Seismic Category I structures below grade will be selected from one of the acceptable approaches described in **DCD Subsection 3.4.1.1.1.1**. Duke Energy will notify NRC within 60 days of selecting the waterproofing system to be used, including the qualification methods planned to demonstrate the required performance characteristics. Duke Energy will also notify NRC not less than 90 days prior to site-specific qualification testing to demonstrate that the selected waterproofing system complies with DCD requirements. Both selection and testing milestones will be added to the detailed construction schedule to ensure tracking and closure of ITAAC 14.3.3.1.

3.8.5.5.1 Nuclear Island Maximum Bearing Pressures

Add the following information to the end of DCD Subsection 3.8.5.5.1:

As part of the site-specific analyses of the nuclear island described in **FSAR Subsection 3.7.2.15**, the foundation loadings (forces and moments) resulting from the CSDRS were confirmed to be greater than the foundation loadings that result from the Lee Nuclear Station NI FIRS. The site-specific maximum bearing

pressure was determined to be approximately 23,030 lb/ft². This is significantly less than the AP1000 DCD site acceptance characteristic of 35,000 lb/ft², which resulted from evaluating hard rock support conditions and applied loadings associated with the CSDRS. The site-specific analyses also confirmed that no foundation liftoff is expected when the nuclear islands are subjected to the NI FIRS.

3.8.5.7 In-Service Testing and Inspection Requirements

Replace the existing DCD first statement with the following:

- STD COL 3.8-5 The inspection program for structures is identified in **Section 17.6**. This inspection program is consistent with the requirements of 10 CFR 50.65 and the guidance in Regulatory Guide 1.160.

3.8.6.5 Structures Inspection Program

- STD COL 3.8-5 This item is addressed in **Subsections 3.8.3.7, 3.8.4.7, 3.8.5.7, and 17.6**.

3.8.6.6 Construction Procedures Program

Add the following to the end of DCD Subsection 3.8.6.6:

- STD COL 3.8-6 Construction and inspection procedures for concrete filled steel plate modules address activities before and after concrete placement, use of construction mock-ups, and inspection of modules before and after concrete placement as discussed in **DCD Subsection 3.8.4.8**. The procedures will be made available to NRC inspectors prior to use.

WLS SUP 3.8-1 3.8.7 REFERENCES

201. Westinghouse Electric Company LLC, "William S. Lee Site-Specific Assessment of Lateral Earth Pressure Loads Due to 2012/2013 CEUS Ground Motion Seismic Input," WLG-1000-S2R-806, Rev. 2, November, 2013.

- 202. Cole, R.T. and Rollins, K.M, 2006. "Passive Earth Pressure Mobilization during Cyclic Loading", Journal of Geotechnical and Environmental Engineering. Vol. 132, No. 9, pp 1154-1164.
- 203. Duncan, J. M., and Mokwa, R. M., 2001. "Passive Earth Pressures: Theories and Tests." Journal of Geotechnical and Environmental Engineering, Vol. 127, No. 3, pp 248–257.
- 204. Westinghouse Electric Company LLC, 2014. "William S. Lee Site Specific Adjacent Buildings Seismic Evaluation Report", Westinghouse Report WLG-1000-S2R-804, Rev. 3, February 2014.

WLS SUP 3.8-1

TABLE 3.8-201 (Sheet 1 of 2)
FRACTION OF AP1000 GENERIC LATERAL SOIL RESISTANCE MOBILIZED

Column 1	Column 2	Column 3	Column 4	Column 5	Column 6	Column 7	Column 8
Direction of NI Displacement	Water Table Depth, ft	Soil Modulus Case [1],[2]	Modulus Ei, ksf	Poisson's Ratio	Fraction of Soil Passive Pressure Mobilized at $\Delta_{calc}=0.2$ inch To Ultimate WLS Passive Pressure "Mob"	To Standard AP1000 Passive Pressure	WLS Site-Specific Lateral Pressure with Mobilized Soil Pressure Bounded by AP1000 Design for LC7?
E-W	8	Triax	1311	0.5	0.103	0.217	Yes
		Strain-Compatible Median- σ	3082	0.43	0.207	0.320	Yes
		Strain-Compatible Median	7289	0.45	0.384	0.494	Yes
		Strain-Compatible Median+ σ	17401	0.47	0.600	0.707	Yes
	18	Triax	1379	0.5	0.092	0.224	Yes
		Strain-Compatible Median- σ	3082	0.43	0.180	0.327	Yes
		Strain-Compatible Median	7289	0.45	0.343	0.519	Yes
		Strain-Compatible Median+ σ	17401	0.47	0.557	0.771	Yes

WLS SUP 3.8-1

TABLE 3.8-201 (Sheet 2 of 2)
FRACTION OF AP1000 GENERIC LATERAL SOIL RESISTANCE MOBILIZED

Column 1	Column 2	Column 3	Column 4	Column 5	Column 6	Column 7	Column 8
Direction of NI Displacement	Water Table Depth, ft	Soil Modulus Case [1],[2]	Modulus E_i , ksf	Poisson's Ratio	Fraction of Soil Passive Pressure Mobilized at $\Delta_{calc}=0.2$ inch To Ultimate WLS Passive Pressure "Mob"	To Standard AP1000 Passive Pressure	WLS Site-Specific Lateral Pressure with Mobilized Soil Pressure Bounded by AP1000 Design for LC7?
N-S	8	Triax	1426	0.5	0.132	0.246	Yes
		Strain-Compatible Median- σ	3082	0.43	0.243	0.355	Yes
		Strain-Compatible Median	7289	0.45	0.433	0.542	Yes
		Strain-Compatible Median+ σ	17401	0.47	0.647	0.753	Yes
	18	Triax	1487	0.5	0.117	0.254	Yes
		Strain-Compatible Median- σ	3082	0.43	0.212	0.365	Yes
		Strain-Compatible Median	7289	0.45	0.390	0.574	Yes
		Strain-Compatible Median+ σ	17401	0.47	0.606	0.829	Yes

Notes:

[1] Triax is modulus determined from CD triaxial test data by Duncan and Mokwa (2001), and adjusted for confining pressure.

[2] Strain-compatible modulus from WEC (2014), Report WLG-1000-S2R-804, Rev. 3, average of 4 profiles.

3.9 MECHANICAL SYSTEMS AND COMPONENTS

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.9.3 ASME CODE CLASSES 1, 2, AND 3 COMPONENTS, COMPONENT SUPPORTS, AND CORE SUPPORT STRUCTURES

Add the following at the end of DCD Subsection 3.9.3:

When performing an as-built reconciliation of piping analysis packages, Duke Energy and Westinghouse will also use **Reference 205** to justify existing analysis instead of having to create a new analysis to incorporate slightly different dimensional changes in the models. Parameters like location of supports, centerline lengths to fittings, angular deviations of the pipe centerline, and valve concentrated weights, all have some tolerance that, if met, maintain the applicability of the design basis analysis without a formal reanalysis.

Reference 205 has a basic assumption that the seismic analysis used to qualify the piping package used uniform envelope response spectra. The NRC has accepted this approach to as-built reconciliation and **Reference 205** is cited in the AP1000 DCD, Revision 19 (**DCD Subsection 3.6.3.2**).

The analyses described in **Reference 206** demonstrate that the Lee site-specific spectra and HRHF spectra are similar. Detailed stress analysis of selected piping systems indicates that the site-specific pipe stresses are enveloped by the CSDRS pipe stresses. Therefore, as described in **FSAR Subsection 3.7.2.15**, standard design practices for AP1000 piping systems have considered cases enveloping the Lee site-specific requirements. In some cases the as-built reconciliation review using **Reference 205** may indicate that a detailed as-built re-analysis of certain piping systems is needed. For those cases, as-built piping systems will be qualified using the DCD CSDRS/HRHF seismic spectra, since all piping systems were analyzed and designed for both CSDRS and HRHF. In addition, for these cases when as-built re-analyses are needed, the as-built piping system will also be qualified using the Lee site-specific spectra to confirm that configuration changes during construction have not affected the piping system qualification for site-specific demands.

3.9.3.1.2 Loads for Class 1 Components, Core Support, and Component Supports

STD COL 3.9-5 Add the following after the last paragraph under DCD subheading Request 3) and prior to DCD subheading Other Applications.

PRESSURIZER SURGE LINE MONITORING

General

The pressurizer surge line is monitored at the first AP1000 plant to record temperature distributions and thermal displacements of the surge line piping, as well as pertinent plant parameters. This monitoring occurs during the hot functional testing and first fuel cycle. The resulting monitoring data is evaluated to verify that the pressurizer surge line is within the bounds of the analytical temperature distributions and displacements.

Subsequent AP1000 plants (after the first AP1000 plant) confirm that the heatup and cooldown procedures are consistent with the pertinent attributes of the first AP1000 plant surge line monitoring. In addition, changes to the heatup and cooldown procedures consider the potential impact on stress and fatigue analyses consistent with the concerns of NRC Bulletin 88-11.

The pressurizer surge line monitoring activities include the following methodology and requirements:

Monitoring Method

The pressurizer surge line pipe wall is instrumented with outside mounted temperature and displacement sensors. The data from this instrumentation is supplemented by plant computer data from related process and control parameters.

Locations to be Monitored

In addition to the existing permanent plant temperature instrumentation, temperature and displacement monitoring will be included at critical locations on the surge line. The additional locations utilized for monitoring during the hot functional testing and the first fuel cycle (see [Subsection 14.2.9.2.22](#)) are selected based on the capability to provide effective monitoring.

Data Evaluation

Data evaluation is performed at the completion of the monitoring period (one fuel cycle). The evaluation includes a comparison of the data evaluation results with the thermal profiles and transient loadings defined for the pressurizer surge line, accounting for expected pipe outside wall temperatures. Interim evaluations of the data are performed during the hot functional testing period, up to the start of

normal power operation, and again once three months worth of normal operating data has been collected, to identify any unexpected conditions in the pressurizer surge line.

3.9.3.4.4 Inspection, Testing, Repair, and/or Replacement of Snubbers

Add the following text after the last paragraph of DCD Subsection 3.9.3.4.4:

STD COL 3.9-3 a. Snubber Design and Testing

1. A list of snubbers on systems which experience sufficient thermal movement to measure cold to hot position is included in **Table 3.9-201**.
2. The snubbers are tested to verify they can perform as required during the seismic events, and under anticipated operational transient loads or other mechanical loads associated with the design requirements for the plant. Production and qualification test programs for both hydraulic and mechanical snubbers are carried out by the snubber vendors in accordance with the snubber installation instruction manual required to be furnished by the snubber supplier. Acceptance criteria for compliance with ASME Section III Subsection NF, and other applicable codes, standards and requirements, are as follows:
 - Snubber production and qualification test programs are carried out by strict adherence to the manufacturer's snubber installation and instruction manual. This manual is prepared by the snubber manufacturer and subjected to review for compliance with the applicable provisions of the ASME Pressure Vessel and Piping Code of record. The test program is periodically audited during implementation for compliance.
 - Snubbers are inspected and tested for compliance with the design drawings and functional requirements of the procurement specifications.
 - Snubbers are inspected and qualification tested. No sampling methods are used in the qualification tests.
 - Snubbers are load rated by testing in accordance with the snubber manufacturer's testing program and in compliance with the applicable sections of ASME QME-1-2007, Subsection QDR and the ASME Code for Operation and

Maintenance of Nuclear Power Plants (OM Code), Subsection ISTD.

- Design compliance of the snubbers per ASME Section III Paragraph NF-3128, and Subparagraphs NF-3411.3 and NF-3412.4.
 - The snubbers are tested for various abnormal environmental conditions. Upon completion of the abnormal environmental transient test, the snubber is tested dynamically at a frequency within a specified frequency range. The snubber must operate normally during the dynamic test. The functional parameters cited in Subparagraph NF-3412.4 are included in the snubber qualification and testing program. Other parameters in accordance with applicable ASME QME-1-2007 and the ASME OM Code will be incorporated.
 - The codes and standards used for snubber qualification and production testing are as follows:
 - ASME B&PV Code Section III (Code of Record date) and Subsection NF.
 - ASME QME-1-2007, Subsection QDR and ASME OM Code, Subsection ISTD.
 - Large bore hydraulic snubbers are full Service Level D load tested, including verifying bleed rates, control valve closure within the specified velocity ranges and drag forces/ breakaway forces are acceptable in accordance with ASME, QME-1-2007 and ASME OM Codes.
3. Safety-related snubbers are identified in **Table 3.9-201**, including the snubber identification and the associated system or component, e.g., line number. The snubbers on the list are hydraulic and constructed to ASME Section III, Subsection NF. The snubbers are used for shock loading only. None of the snubbers are dual purpose or vibration arrestor type snubbers.

b. Snubber Installation Requirements

Installation instructions contain instructions for storage, handling, erection, and adjustments (if necessary) of snubbers. Each snubber has an installation location drawing that contains the installation location of the snubber on the pipe and structure, the hot and cold settings, and additional information needed to install the particular snubber.

STD COL 3.9-3 The description of the snubber preservice and inservice testing programs in this section is based on the ASME OM Code 2001 Edition through 2003 Addenda. The initial inservice testing program incorporates the latest edition and addenda of the ASME OM Code approved in 10 CFR 50.55a(f) on the date 12 months before initial fuel load. Limitations and modifications set forth in 10 CFR 50.55a are incorporated.

c. Snubber Preservice Examination and Testing

The preservice examination plan for applicable snubbers is prepared in accordance with the requirements of the ASME Code for Operation and Maintenance of Nuclear Power Plants (OM Code), Subsection ISTD, and the additional requirements of this Section. This examination is made after snubber installation but not more than 6 months prior to initial system preoperational testing. The preservice examination verifies the following:

1. There are no visible signs of damage or impaired operational readiness as a result of storage, handling, or installation.
2. The snubber load rating, location, orientation, position setting, and configuration (attachments, extensions, etc.) are according to design drawings and specifications.
3. Snubbers are not seized, frozen or jammed.
4. Adequate swing clearance is provided to allow snubber movements.
5. If applicable, fluid is to the recommended level and is not to be leaking from the snubber system.
6. Structural connections such as pins, fasteners and other connecting hardware such as lock nuts, tabs, wire, cotter pins are installed correctly.

If the period between the initial preservice examination and initial system preoperational tests exceeds 6 months, reexamination of Items 1, 4, and 5 is performed. Snubbers, which are installed incorrectly or otherwise fail to meet the above requirements, are repaired or replaced and re-examined in accordance with the above criteria.

A preservice thermal movement examination is also performed, during initial system heatup and cooldown. For systems whose design operating temperature exceeds 250°F (121°C), snubber thermal movement is verified.

Additionally, preservice operational readiness testing is performed on snubbers. The operational readiness test is performed to verify the parameters of ISTD-5120. Snubbers that fail the preservice operational

readiness test are evaluated to determine the cause of failure, and are retested following completion of corrective action(s).

Snubbers that are installed incorrectly or otherwise fail preservice testing requirements are re-installed correctly, adjusted, modified, repaired or replaced, as required. Preservice examination and testing is re-performed on installation-corrected, adjusted, modified, repaired or replaced snubbers as required.

d. Snubber Inservice Examination and Testing

Inservice examination and testing of safety-related snubbers is conducted in accordance with the requirements of the ASME OM Code, Subsection ISTD. Inservice examination is initially performed not less than two months after attaining 5% reactor power operation and is completed within 12 calendar months after attaining 5% reactor power. Subsequent examinations are performed at intervals defined by ISTD-4252 and Table ISTD-4252-1. Examination intervals, subsequent to the third interval, are adjusted based on the number of unacceptable snubbers identified in the current interval.

An inservice visual examination is performed on the snubbers to identify physical damage, leakage, corrosion, degradation, indication of binding, misalignment or deformation and potential defects generic to a particular design. Snubbers that do not meet visual examination requirements are evaluated to determine the root cause of the unacceptability, and appropriate corrective actions (e.g., snubber is adjusted, repaired, modified or replaced) are taken. Snubbers evaluated as unacceptable during visual examination may be accepted for continued service by successful completion of an operational readiness test.

Snubbers are tested inservice to determine operational readiness during each fuel cycle, beginning no sooner than 60 days before the start of the refueling outage. Snubber operational readiness tests are conducted with the snubber in the as-found condition, to the extent practicable, either in place or on a test bench, to verify the test parameters of ISTD-5210. When an in-place test or bench test cannot be performed, snubber subcomponents that control the parameters to be verified are examined and tested. Preservice examinations are performed on snubbers after reinstallation when bench testing is used (ISTD-5224), or on snubbers where individual subcomponents are reinstalled after examination (ISTD-5225).

Defined test plan groups (DTPG) are established and the snubbers of each DTPG are tested each fuel cycle according to an established sampling plan. Sample plan size and composition is determined as required for the selected sample plan, with additional sampling as may be required for that sample plan based on test failures and failure modes identified. Snubbers that do not meet test requirements are evaluated to determine root cause of the failure, and are assigned to failure mode

groups (FMG) based on the evaluation, unless the failure is considered unexplained or isolated. The number of unexplained snubber failures, not assigned to a FMG, determines the additional testing sample. Isolated failures do not require additional testing. For unacceptable snubbers, additional testing is conducted for the DTPG or FMG until the appropriate sample plan completion criteria are satisfied.

Unacceptable snubbers are adjusted, repaired, modified or replaced. Replacement snubbers meet the requirements of ISTD-1600. Post-maintenance examination and testing, and examination and testing of repaired snubbers, is done to verify as acceptable the test parameters that may have been affected by the repair or maintenance activity.

Service life for snubbers is established, monitored and adjusted as required by ISTD-6000 and the guidance of ASME OM Code Nonmandatory Appendix F.

3.9.6 INSERVICE TESTING OF PUMPS AND VALVES

Revise the third sentence of the third paragraph of DCD Subsection 3.9.6, and add information between the third and fourth sentences as follows:

- STD COL 3.9-4 The edition and addenda to be used for the inservice testing program are administratively controlled; the description of the inservice testing program in this section is based on the ASME OM Code 2001 Edition through 2003 Addenda. The initial inservice testing program incorporates the latest edition and addenda of the ASME OM Code approved in 10 CFR 50.55a(f) on the date 12 months before initial fuel load. Limitations and modifications set forth in 10 CFR 50.55a are incorporated.

Revise the fifth sentence of the sixth paragraph of DCD Subsection 3.9.6 as follows:

- STD COL 3.9-4 Alternate means of performing these tests and inspections that provide equivalent demonstration may be developed in the inservice test program ~~as described in subsection 3.9.8.~~

Revise the first two sentences of the final paragraph of DCD Subsection 3.9.6 to read as follows:

- STD COL 3.9-4 A preservice test program, which identifies the required functional testing, is to be submitted to the NRC prior to performing the tests and following the start of

construction. The inservice test program, which identifies requirements for functional testing, is to be submitted to the NRC prior to the anticipated date of commercial operation as described above.

Add the following text after the last paragraph of DCD Subsection 3.9.6:

Table 13.4-201 provides milestones for preservice and inservice test program implementation.

3.9.6.2.2 Valve Testing

Add the following prior the initial paragraph of DCD Subsection 3.9.6.2.2:

STD COL 3.9-4 Valve testing uses reference values determined from the results of preservice testing (PST) or inservice testing (IST). These tests that establish reference and IST values are performed under conditions as near as practicable to those expected during the IST. Reference values are established only when a valve is known to be operating acceptably.

Pre-conditioning of valves or their associated actuators or controls prior to IST testing undermines the purpose of IST testing and is not allowed. Pre-conditioning includes manipulation, pre-testing, maintenance, lubrication, cleaning, exercising, stroking, operating, or disturbing the valve to be tested in any way, except as may occur in an unscheduled, unplanned, and unanticipated manner during normal operation.

Add the following sentence to the end of the fourth paragraph under the heading "Manual/Power-Operated Valve Tests":

STD COL 3.9-4 Stroke time is measured and compared to the reference value, except for valves classified as fast-acting (e.g., solenoid-operated valves with stroke time less than 2 seconds), for which a stroke time limit of 2 seconds is assigned.

Add the following paragraph after the fifth paragraph under the heading "Manual/Power-Operated Valve Tests":

STD COL 3.9-4 During valve exercise tests, the necessary valve obturator movement is verified while observing an appropriate direct indicator, such as indicating lights that signal the required changes of obturator position, or by observing other evidence or

positive means, such as changes in system pressure, flow, level, or temperature that reflects change of obturator position.

- STD COL 3.9-4 Insert new second sentence of the paragraph containing the subheading "Power-Operated Valve Operability Tests" in DCD Subsection 3.9.6.2.2 (immediately following the first sentence of the DCD paragraph) to read:

The POVs include the motor-operated valves.

Add the following sentence as the last sentence of the paragraph containing the subheading "Power-Operated Valve Operability Tests" in DCD Subsection 3.9.6.2.2:

Table 13.4-201 provides milestones for the MOV program implementation.

Insert the following as the last sentence in the paragraph under the bulleted item titled "Risk Ranking" in DCD Subsection 3.9.6.2.2:

- STD COL 3.9-4 Guidance for this process is outlined in the JOG MOV PV Study, MPR-2524-A.
-

Insert the following text after the last paragraph under the sub-heading of "Power-Operated Valve Operability Tests" and before the sub-heading "Check Valve Tests" in DCD Subsection 3.9.6.2.2:

- STD COL 3.9-4 **Active MOV Test Frequency Determination** - The ability of a valve to meet its design basis functional requirements (i.e. required capability) is verified during valve qualification testing as required by procurement specifications. Valve qualification testing measures valve actuator actual output capability. The actuator output capability is compared to the valve's required capability defined in procurement specifications, establishing functional margin; that is, that increment by which the MOV's actual output capability exceeds the capability required to operate the MOV under design basis conditions. **DCD Subsection 5.4.8** discusses valve functional design and qualification requirements. The initial inservice test frequency is determined as required by ASME OM Code Case OMN-1, Revision 1 (**Reference 202**). The design basis capability testing of MOVs utilizes guidance from Generic Letter 96-05 and the JOG MOV Periodic Verification PV Program. Valve functional margin is evaluated following subsequent periodic testing to address potential time-related performance degradation, accounting for applicable uncertainties in the analysis. If the evaluation shows that the functional margin will be reduced to less than established acceptance criteria within the established test interval, the test interval is decreased to less than the time for the functional margin to decrease below acceptance criteria. If there is not sufficient data to

determine test frequency as described above, the test frequency is limited to not exceed two (2) refueling cycles or three (3) years, whichever is longer, until sufficient data exist to extend the test frequency. Appropriate justification is provided for any increased test interval, and the maximum test interval shall not exceed 10 years. This is to ensure that each MOV in the IST program will have adequate margin (including consideration for aging-related degradation, degraded voltage, control switch repeatability, and load-sensitive MOV behavior) to remain operable until the next scheduled test, regardless of its risk categorization or safety significance. Uncertainties associated with performance of these periodic verification tests and use of the test results (including those associated with measurement equipment and potential degradation mechanisms) are addressed appropriately. Uncertainties may be considered in the specification of acceptable valve setup parameters or in the interpretation of the test results (or a combination of both). Uncertainties affecting both valve function and structural limits are addressed.

Maximum torque and/or thrust (as applicable) achieved by the MOV (allowing sufficient margin for diagnostic equipment inaccuracies and control switch repeatability) are established so as not to exceed the allowable structural and undervoltage motor capability limits for the individual parts of the MOV.

Solenoid-operated valves (SOVs) are tested to confirm the valve moves to its energized position and is maintained in that position, and to confirm that the valve moves to the appropriate failure mode position when de-energized.

Other Power-Operated Valve Operability Tests - Power-Operated valves other than active MOVs are exercised quarterly in accordance with ASME OM ISTC, unless justification is provided in the inservice testing program for testing these valves at other than Code mandated frequencies.

Although the design basis capability of power-operated valves is verified as part of the design and qualification process, power-operated valves that perform an active safety function are tested again after installation in the plant, as required, to ensure valve setup is acceptable to perform their required functions, consistent with valve qualification. These tests, which are typically performed under static (no flow or pressure) conditions, also document the "baseline" performance of the valves to support maintenance and trending programs. During the testing, critical parameters needed to ensure proper valve setup are measured. Depending on the valve and actuator type, these parameters may include seat load, running torque or thrust, valve travel, actuator spring rate, bench set and regulator supply pressure. Uncertainties associated with performance of these tests and use of the test results (including those associated with measurement equipment and potential degradation mechanisms) are addressed appropriately. Uncertainties may be considered in the specification of acceptable valve setup parameters or in the interpretation of the test results (or a combination of both). Uncertainties affecting both valve function and structural limits are addressed.

Additional testing is performed as part of the air-operated valve (AOV) program, which includes the key elements for an AOV Program as identified in the JOG AOV program document, Joint Owners Group Air Operated Valve Program

Document, Revision 1, December 13, 2000 ([References 203](#) and [204](#)). The AOV program incorporates the attributes for a successful power-operated valve long-term periodic verification program, as discussed in Regulatory Issue Summary 2000-03, Resolution of Generic Safety Issue 158: Performance of Safety-Related Power-Operated Valves Under Design Basis Conditions, by incorporating lessons learned from previous nuclear power plant operations and research programs as they apply to the periodic testing of air- and other power-operated valves included in the IST program. For example, key lessons learned addressed in the AOV program include:

- Valves are categorized according to their safety significance and risk ranking.
- Setpoints for AOVs are defined based on current vendor information or valve qualification diagnostic testing, such that the valve is capable of performing its design-basis function(s).
- Periodic static testing is performed, at a minimum on high risk (high safety significance) valves, to identify potential degradation, unless those valves are periodically cycled during normal plant operation, under conditions that meet or exceed the worst case operating conditions within the licensing basis of the plant for the valve, which would provide adequate periodic demonstration of AOV capability. If required based on valve qualification or operating experience, periodic dynamic testing is performed to re-verify the capability of the valve to perform its required functions.
- Sufficient diagnostics are used to collect relevant data (e.g., valve stem thrust and torque, fluid pressure and temperature, stroke time, operating and/or control air pressure, etc.) to verify the valve meets the functional requirements of the qualification specification.
- Test frequency is specified, and is evaluated each refueling outage based on data trends as a result of testing. Frequency for periodic testing is in accordance with [References 203](#) and [204](#), with a minimum of 5 years (or 3 refueling cycles) of data collected and evaluated before extending test intervals.
- Post-maintenance procedures include appropriate instructions and criteria to ensure baseline testing is re-performed as necessary when maintenance on the valve, repair or replacement, have the potential to affect valve functional performance.
- Guidance is included to address lessons learned from other valve programs specific to the AOV program.

- Documentation from AOV testing, including maintenance records and records from the corrective action program are retained and periodically evaluated as a part of the AOV program.

Insert the following two paragraphs as the final paragraphs under the sub-heading of "Power-Operated Valve Operability Tests" in DCD Subsection 3.9.6.2.2:

- STD COL 3.9-4 The attributes of the AOV testing program described above, to the extent that they apply to and can be implemented on other safety-related power-operated valves, such as electro-hydraulic valves, are applied to those other power-operated valves.

Successful completion of the preservice and IST of MOVs, in addition to MOV testing as required by 10 CFR 50.55a, demonstrates that the following criteria are met for each valve tested: (i) valve fully opens and/or closes as required by its safety function; (ii) adequate margin exists and includes consideration of diagnostic equipment inaccuracies, degraded voltage, control switch repeatability, load-sensitive MOV behavior, and margin for degradation; and (iii) maximum torque and/or thrust (as applicable) achieved by the MOV (allowing sufficient margin for diagnostic equipment inaccuracies and control switch repeatability) does not exceed the allowable structural and undervoltage motor capability limits for the individual parts of the MOV.

Add the following new paragraph under the heading "Check Valve Tests" in DCD Subsection 3.9.6.2.2:

- STD COL 3.9-4 Preoperational testing is performed during the initial test program (refer to **DCD Section 14.2**) to verify that valves are installed in a configuration that allows correct operation, testing, and maintenance. Preoperational testing verifies that piping design features accommodate check valve testing requirements. Tests also verify disk movement to and from the seat and determine, without disassembly, that the valve disk positions correctly, fully opens or fully closes as expected, and remains stable in the open position under the full spectrum of system design-basis fluid flow conditions.

Add the following new last paragraphs under the subheading "Check Valve Exercise Tests" in DCD Subsection 3.9.6.2.2:

- STD COL 3.9-4 Acceptance criteria for this testing consider the specific system design and valve application. For example, a valve's safety function may require obturator movement in both open and closed directions. A mechanical exerciser may be used to operate a check valve for testing. Where a mechanical exerciser is used, acceptance criteria are provided for the force or torque required to move the

check valve's obturator. Exercise tests also detect missing, sticking, or binding obturators.

When operating conditions, valve design, valve location, or other considerations prevent direct observation or measurements by use of conventional methods to determine adequate check valve function, diagnostic equipment and nonintrusive techniques are used to monitor internal conditions. Nonintrusive tests used are dependent on system and valve configuration, valve design and materials, and include methods such as ultrasonic (acoustic), magnetic, radiography, and use of accelerometers to measure system and valve operating parameters (e.g., fluid flow, disk position, disk movement, disk impact, and the presence or absence of cavitation and back-tapping). Nonintrusive techniques also detect valve degradation. Diagnostic equipment and techniques used for valve operability determinations are verified as effective and accurate under the PST program.

Testing is performed, to the extent practicable, under normal operation, cold shutdown, or refueling conditions applicable to each check valve. Testing includes effects created by sudden starting and stopping of pumps, if applicable, or other conditions, such as flow reversal. When maintenance that could affect valve performance is performed on a valve in the IST program, post-maintenance testing is conducted prior to returning the valve to service.

STD COL 3.9-4 Add the following new paragraph under the heading "Other Valve Inservice Tests" following the Explosively Actuated Valves paragraph in DCD Subsection 3.9.6.2.2:

Industry and regulatory guidance is considered in development of the IST program for squib valves. In addition, the IST program for squib valves incorporates lessons learned from the design and qualification process for these valves such that surveillance activities provide reasonable assurance of the operational readiness of squib valves to perform their safety functions.

3.9.6.2.3 Valve Disassembly and Inspection

Add the following paragraph as the new second paragraph of DCD Subsection 3.9.6.2.3:

STD COL 3.9-4 During the disassembly process, the full-stroke motion of the obturator is verified. Nondestructive examination is performed on the hinge pin to assess wear, and seat contact surfaces are examined to verify adequate contact. Full-stroke motion of the obturator is re-verified immediately prior to completing reassembly. At least one valve from each group is disassembled and examined at each refueling outage, and all the valves in each group are disassembled and examined at least once every eight years. Before being returned to service, valves disassembled for examination or valves that received maintenance that could affect their

performance are exercised with a full- or part-stroke. Details and bases of the sampling program are documented and recorded in the test plan.

Add Subsections 3.9.6.2.4 and 3.9.6.2.5 following the last paragraph of DCD Subsection 3.9.6.2.3:

3.9.6.2.4 Valve Preservice Tests

- STD COL 3.9-4 Each valve subject to inservice testing is also tested during the preservice test period. Preservice tests are conducted under conditions as near as practicable to those expected during subsequent inservice testing. Valves (or the control system) that have undergone maintenance that could affect performance, and valves that have been repaired or replaced, are re-tested to verify performance parameters that could have been affected are within acceptable limits. Safety and relief valves and nonreclosing pressure relief devices are preservice tested in accordance with the requirements of the ASME OM Code, Mandatory Appendix I.

Preservice tests for valves are performed in accordance with ASME OM, ISTC-3100.

3.9.6.2.5 Valve Replacement, Repair, and Maintenance

- STD COL 3.9-4 Testing in accordance with ASME OM, ISTC-3310 is performed after a valve is replaced, repaired, or undergoes maintenance. When a valve or its control system has been replaced, repaired, or has undergone maintenance that could affect valve performance, a new reference value is determined, or the previous value is reconfirmed by an inservice test. This test is performed before the valve is returned to service, or immediately if the valve is not removed from service. Deviations between the previous and new reference values are identified and analyzed. Verification that the new values represent acceptable operation is documented.
-

3.9.6.3 Relief Requests

Insert the following text after the first paragraph in DCD Subsection 3.9.6.3:

- STD COL 3.9-4 The IST Program described herein utilizes Code Case OMN-1, Revision 1, "Alternative Rules for the Preservice and Inservice Testing of Certain Electric Motor-Operated Valve Assemblies in Light Water Reactor Power Plants" ([Reference 202](#)). Code Case OMN-1 establishes alternate rules and requirements for preservice and inservice testing to assess the operational readiness of certain

motor operated valves, in lieu of the requirements set forth in ASME OM Code Subsection ISTC.

STD COL 3.9-4 OMN-1, Alternative Rules for the Preservice and Inservice Testing of Certain MOVs

Code Case OMN-1, Revision 1, "Alternative Rules for the Preservice and Inservice Testing of Certain Electric Motor Operated Valve Assemblies in Light Water Reactor Power Plants," establishes alternate rules and requirements for preservice and inservice testing to assess the operational readiness of certain motor-operated valves in lieu of the requirements set forth in OM Code Subsection ISTC. However, Regulatory Guide 1.192, "Operation and Maintenance Code Case Acceptability, ASME OM Code," June 2003, has not yet endorsed OMN-1, Revision 1.

Code Case OMN-1, Revision 0, has been determined by the NRC to provide an acceptable level of quality and safety when implemented in conjunction with the conditions imposed in Regulatory Guide 1.192. NUREG-1482, Revision 1, "Guidelines for Inservice Testing at Nuclear Power Plants," recommends the implementation of OMN-1 by all licensees. Revision 1 to OMN-1 represents an improvement over Revision 0, as published in the ASME OM-2004 Code. OMN-1 Revision 1 incorporates the guidance on risk-informed testing of MOVs from OMN-11, "Risk-Informed Testing of Motor-Operated Valves," and provides additional guidance on design basis verification testing and functional margin, which eliminates the need for the figures on functional margin and test intervals in Code Case OMN-1.

The IST Program implements Code Case OMN-1, Revision 1, in lieu of the stroke-time provisions specified in ISTC-5120 for MOVs, consistent with the guidelines provided in NUREG-1482, Revision 1, Section 4.2.5.

Regulatory Guide 1.192 states that licensees may use Code Case OMN-1, Revision 0, in lieu of the provisions for stroke-time testing in Subsection ISTC of the 1995 Edition up to and including the 2000 Addenda of the ASME OM Code when applied in conjunction with the provisions for leakage rate testing in ISTC-3600 (1998 Edition with the 1999 and 2000 Addenda). Licensees who choose to apply OMN-1 are required to apply all of its provisions. The IST program incorporates the following provisions from Regulatory Guide 1.192:

- (1) The adequacy of the diagnostic test interval for each motor-operated valve (MOV) is evaluated and adjusted as necessary, but not later than 5 years or three refueling outages (whichever is longer) from initial implementation of OMN-1.
- (2) The potential increase in core damage frequency and risk associated with extending high risk MOV test intervals beyond quarterly is determined to be small and consistent with the intent of the Commission's Safety Goal Policy Statement.

- (3) Risk insights are applied using MOV risk ranking methodologies accepted by the NRC on a plant-specific or industry-wide basis, consistent with the conditions in the applicable safety evaluations.
- (4) Consistent with the provisions specified for Code Case OMN-11 the potential increase in CDF and risk associated with extending high risk MOV test intervals beyond quarterly is determined to be small and consistent with the intent of the Commission's Safety Goal Policy Statement.

Compliance with the above items is addressed in [Subsection 3.9.6.2.2](#). Code Case OMN-1, Revision 1, is considered acceptable for use with OM Code-2001 Edition with 2003 Addenda. Finally, consistent with Regulatory Guide 1.192, the benefits of performing any particular test are balanced against the potential adverse effects placed on the valves or systems caused by this testing.

3.9.8 COMBINED LICENSE INFORMATION

3.9.8.2 Design Specifications and Reports

Add the following text after the second paragraph in DCD Subsection 3.9.8.2.

STD COL 3.9-2 Design specifications and design reports for ASME Section III piping are made available for NRC review. Reconciliation of the as-built piping (verification of the thermal cycling and stratification loading considered in the stress analysis discussed in [DCD Subsection 3.9.3.1.2](#)) is completed by the COL holder after the construction of the piping systems and prior to fuel load (in accordance with DCD Tier 1 Section 2 ITAAC line items for the applicable systems).

3.9.8.3 Snubber Operability Testing

STD COL 3.9-3 This COL Item is addressed in [Subsection 3.9.3.4.4](#).

3.9.8.4 Valve Inservice Testing

STD COL 3.9-4 This COL Item is addressed in Subsections 3.9.6, 3.9.6.2.2, 3.9.6.2.3, 3.9.6.2.4, 3.9.6.2.5, and 3.9.6.3.

3.9.8.5 Surge Line Thermal Monitoring

STD COL 3.9-5 This COL item is addressed in Subsection 3.9.3.1.2 and Subsection 14.2.9.2.22.

3.9.8.7 As-Designed Piping Analysis

Add the following text at the end of DCD Subsection 3.9.8.7.

STD COL 3.9-7 The as-designed piping analysis is provided for the piping lines chosen to demonstrate all aspects of the piping design. A design report referencing the as-designed piping calculation packages, including ASME Section III piping analysis, support evaluations and piping component fatigue analysis for Class I piping using the methods and criteria outlined in DCD Table 3.9-19 is made available for NRC review.

This COL item is also addressed in Subsection 14.3.3.

3.9.9 REFERENCES

201. Not used.
202. ASME Code Case OMN-1, Revision 1, "Alternative Rules for the Preservice and Inservice Testing of Certain Electric Motor-Operated Valve Assemblies in Light Water Reactor Power Plants."
203. Joint Owners Group Air Operated Valve Program Document, Revision 1, December 13, 2000.
204. USNRC, Eugene V. Imbro, letter to Mr. David J. Modeen, Nuclear Energy Institute, Comments On Joint Owners' Group Air Operated Valve Program Document, dated October 8, 1999.

- 205. Electric Power Research Institute, "Guidelines for Piping System Reconciliation (NCIG-05, Revision 1), Document ID NP-5639, May 1988.
- 206. Westinghouse Electric Company, LLC, "Effect of William S. Lee Site Specific Seismic Requirements on AP1000 SSCs," WLG-GW-GLR-815, Revision 0, January 17, 2014.

STD COL 3.9-3

TABLE 3.9-201
SAFETY RELATED SNUBBERS

System	Snubber (Hanger) No.	Line #	System	Snubber (Hanger) No.	Line #
CVS	APP-CVS-PH-11Y0164	L001	RNS	APP-RNS-PH-12Y2060	L006
PXS	APP-PXS-PH-11Y0020	L021A	SGS	APP-SGS-PH-11Y0001	L003B
RCS	APP-RCS-PH-11Y0039	L215	SGS	APP-SGS-PH-11Y0002	L003B
RCS	APP-RCS-PH-11Y0067	L005B	SGS	APP-SGS-PH-11Y0004	L003B
RCS	APP-RCS-PH-11Y0080	L112	SGS	APP-SGS-PH-11Y0057	L003A
RCS	APP-RCS-PH-11Y0081	L215	SGS	APP-SGS-PH-11Y0058	L004B
RCS	APP-RCS-PH-11Y0082	L112	SGS	APP-SGS-PH-11Y0063	L003A
RCS	APP-RCS-PH-11Y0090	L118A	SGS	APP-SGS-PH-11Y0065	L005B
RCS	APP-RCS-PH-11Y0099	L022B	SGS	APP-SGS-PH-12Y0136	L015C
RCS	APP-RCS-PH-11Y0103	L003	SGS	APP-SGS-PH-12Y0137	L015C
RCS	APP-RCS-PH-11Y0105	L003	SGS	APP-SGS-PH-11Y0470	L006B
RCS	APP-RCS-PH-11Y0112	L032A	SGS	APP-SGS-PH-11Y2002	L006A
RCS	APP-RCS-PH-11Y0429	L225B	SGS	APP-SGS-PH-11Y2021	L006A
RCS	APP-RCS-PH-11Y0528	L005A	SGS	APP-SGS-PH-11Y3101	L006B
RCS	APP-RCS-PH-11Y0539	L225C	SGS	APP-SGS-PH-11Y3102	L006B
RCS	APP-RCS-PH-11Y0550	L011B	SGS	APP-SGS-PH-11Y3121	L006B
RCS	APP-RCS-PH-11Y0551	L011A	SGS	APP-SGS-PH-11Y0463	L006A
RCS	APP-RCS-PH-11Y0553	L153B	SGS	APP-SGS-PH-11Y0464	L006A
RCS	APP-RCS-PH-11Y0555	L153A	SGS	SG 1 Snubber A (1A)	(1)
RCS	APP-RCS-PH-11Y2005	L022A	SGS	SG 1 Snubber B (1B)	(1)
RCS	APP-RCS-PH-11Y2101	L032B	SGS	SG 2 Snubber A (2A)	(1)
RCS	APP-RCS-PH-11Y2117	L225A	SGS	SG 2 Snubber B (2B)	(1)

(1) These snubbers are on the upper lateral support assembly of the steam generators.

TABLE 3.9-202
LIST OF ASME CLASS 1, 2, AND 3 ACTIVE VALVES

Valve No.	Description	Function ^(a)
Steam Generator System (Cont.)		
SGS-PL-V040A	Main Steam Line Isolation	2,3,4
SGS-PL-V040B	Main Steam Line Isolation	2,3,4
SGS-PL-V057A	Main Feedwater Isolation	2,3,4
SGS-PL-V057B	Main Feedwater Isolation	2,3,4
SGS-PL-V067A	Startup Feedwater Isolation	2,3,4
SGS-PL-V067B	Startup Feedwater Isolation	2,3,4
SGS-PL-V074A	Steam Generator Blowdown Isolation	2,3,4
SGS-PL-V074B	Steam Generator Blowdown Isolation	2,3,4
SGS-PL-V075A	Steam Generator Series Blowdown Isolation	3,4
SGS-PL-V075B	Steam Generator Series Blowdown Isolation	3,4
SGS-PL-V086A	Steam Line Condensate Drain Control	3,4
SGS-PL-V086B	Steam Line Condensate Drain Control	3,4
SGS-PL-V233A	Power Operated Relief Valve	3,4
SGS-PL-V233B	Power Operated Relief Valve	3,4
SGS-PL-V240A	Main Steam Isolation Valve Bypass Isolation	2,3,4
SGS-PL-V240B	Main Steam Isolation Valve Bypass Isolation	2,3,4
SGS-PL-V250A	Main Feedwater Control	3,4
SGS-PL-V250B	Main Feedwater Control	3,4
SGS-PL-V255A	Startup Feedwater Control	3,4
SGS-PL-V255B	Startup Feedwater Control	3,4
Nuclear Island Nonradioactive Ventilation System		
VBS-PL-V186	MCR Supply Air Isolation Valve	3
VBS-PL-V187	MCR Supply Air Isolation Valve	3
VBS-PL-V188	MCR Return Air Isolation Valve	3
VBS-PL-V189	MCR Return Air Isolation Valve	3
VBS-PL-V190	MCR Exhaust Air Isolation Valve	3
VBS-PL-V191	MCR Exhaust Air Isolation Valve	3
Main Control Room Habitability System		
VES-PL-V001	Air Delivery Alternate Isolation Valve	3
VES-PL-V002A	Pressure Regulating Valve A	3
VES-PL-V002B	Pressure Regulating Valve B	3
VES-PL-V005A	Air Delivery Isolation Valve A	3
VES-PL-V005B	Air Delivery Isolation Valve B	3
VES-PL-V018	Temporary Instrument Isolation Valve A	3
VES-PL-V019	Temporary Instrument Isolation Valve B	3
VES-PL-V022A	Pressure Relief Isolation Valve A	3
VES-PL-V022B	Pressure Relief Isolation Valve B	3
VES-PL-V040A	Air Tank Safety Relief Valve A	3
VES-PL-V040B	Air Tank Safety Relief Valve B	3

WLS DEP 6.4-2

WLS DEP 6.4-2

TABLE 3.9-203
VALVE INSERVICE TEST REQUIREMENTS

Valve Tag Number	Description ⁽¹⁾	Valve / Actuator Type	Safety-Related Missions	Safety Functions ⁽²⁾	ASME Class / IST Category	Inservice Testing Type and Frequency	IST Notes
VES-PL-V001	Air Delivery Isolation Valve	Manual	Maintain Close Transfer Open Maintain Open	Active	Class 3 Category B	Exercise Full Stroke/2 Years	37
VES-PL-V002A	Pressure Regulating Valve A	Press. Req.	Throttle Flow	Active	Class 3 Augmented	Exercise Stroke/Quarterly Operability Test	31, 38
VES-PL-V002B	Pressure Regulating Valve B	Press. Req.	Throttle Flow	Active	Class 3 Augmented	Exercise Stroke/Quarterly Operability Test	31, 38
VES-PL-V005A	Air Delivery Isolation Valve A	Remote SO GLOBE	Maintain Open Transfer Open	Active-to-Failed	Class 3 Category B	Remote Position Indication, Exercise/2 Years Exercise Full Stroke/Quarterly Failsafe Test/Quarterly Operability Test	31
VES-PL-V005B	Air Delivery Isolation Valve B	Remote SO GLOBE	Maintain Open Transfer Open	Active-to-Failed	Class 3 Category B	Remote Position Indication, Exercise/2 Years Exercise Full Stroke/Quarterly Failsafe Test/Quarterly Operability Test	31
WLS DEP 6.4.2 VES-PL-V018	Temporary Instrument Isolation Valve A	Manual	Maintain Close Transfer Open Maintain Open	Active	Class 3 Category B	Exercise Full Stroke/2 Years	
WLS DEP 6.4.2 VES-PL-V019	Temporary Instrument Isolation Valve B	Manual	Maintain Close Transfer Open Maintain Open	Active	Class 3 Category B	Exercise Full Stroke/2 Years	
VES-PL-V022A	Pressure Relief Isolation Valve A	Remote AO Butterfly	Maintain Open Transfer Open	Active-to-Failed	Class 3 Category B	Remote Position Indication, Exercise/2 Years Exercise Full Stroke/Quarterly Failsafe Test/Quarterly Operability Test	31
VES-PL-V022B	Pressure Relief Isolation Valve B	Remote AO Butterfly	Maintain Open Transfer Open	Active-to-Failed	Class 3 Category B	Remote Position Indication, Exercise/2 Years Exercise Full Stroke/Quarterly Failsafe Test/Quarterly Operability Test	31
VES-PL-V040A	Air Tank Safety Relief Valve A	Relief	Maintain Close Transfer Open	Active	Class 3 Category BC	Class 2/3 Relief Valve Tests/10 Years and 20% in 4 Years	
VES-PL-V040B	Air Tank Safety Relief Valve B	Relief	Maintain Close Transfer Open	Active	Class 3 Category BC	Class 2/3 Relief Valve Tests/10 Years and 20% in 4 Years	
VES-PL-V041A	Air Tank Safety Relief Valve A	Relief	Maintain Close Transfer Open	Active	Class 3 Category BC	Class 2/3 Relief Valve Tests/10 Years and 20% in 4 Years	
VES-PL-V041B	Air Tank Safety Relief Valve B	Relief	Maintain Close Transfer Open	Active	Class 3 Category BC	Class 2/3 Relief Valve Tests/10 Years and 20% in 4 Years	
VES-PL-V044	Main Air Flowpath Isolation Valve	Manual	Maintain Open Transfer Close	Active	Class 3 Category B	Exercise Full Stroke/2 Years	37

TABLE 3.9-204 (Sheet 1 of 2)
SYSTEM LEVEL OPERABILITY TEST REQUIREMENTS

System/Feature	Test Purpose	Test Method	Tech Spec ^a
PCS			
PCCWST drain lines	Flow capability and water coverage	Note 1	SR 3.6.6.6
PXS			
Accumulator injection lines	Flow capability	Note 2	SR 3.5.1.6
CMT injection lines	Flow capability	Note 3	SR 3.5.2.7
PRHR HX	Heat transfer capability	Note 4	SR 3.5.4.6
IRWST injection lines	Flow capability	Note 5	SR 3.5.6.10
Containment recirculation lines	Flow capability	Note 6	SR 3.5.6.10
VES			
MCR isolation/makeup	MCR pressurization capability	Note 7	SR 3.7.6.9

WLS DEP 6.4-2

Alpha Note:

- a. Refer to the Technical Specification surveillance identified in this column for the test frequency.

Notes:

1. The flow capability of each PCS water drain line is demonstrated by conducting a test where water is drained from the PCS water storage tank onto the containment shell by opening two of the three parallel isolation valves. During this flow test the water coverage is also demonstrated. The test is terminated when the flow measurement is obtained and the water coverage is observed. The minimum allowable flowrate is 469.1 gpm with the passive containment cooling water storage tank level 27.3 feet above the lowest standpipe. The test may be run with a higher water level and the test results adjusted for the increased level. Water coverage is demonstrated by visual inspection that there is unobstructed flow from the lower weirs. In addition, at least four air baffle panels will be removed at the containment vessel spring line, approximately 90 degrees apart, to permit visual inspection of the water coverage and the vessel coating. The water coverage observed at these locations will be compared against the coverage measured at the same locations during pre-operational testing (see item 7.(b)(i) of ITAAC Table 2.2.2-6).
2. The flow capability of each accumulator is demonstrated by conducting a test during cold shutdown conditions. The initial conditions of the test include reduced accumulator pressure. Flow from the accumulator to the RCS is initiated by opening the accumulator isolation valve. Sufficient flow is provided to fully open the check valves. The test is terminated when the flow measurement is obtained. The allowable calculated flow resistance between each accumulator and the reactor vessel is $\geq 1.47 \times 10^{-5} \text{ ft/gpm}^2$ and $\leq 1.83 \times 10^{-5} \text{ ft/gpm}^2$.
3. The flow capability of each CMT is demonstrated by conducting a test during cold shutdown conditions. The initial conditions of the test include the RCS loops drained to a level below the top of the RCS hot leg. Flow from the CMT to the RCS is initiated by opening one CMT isolation valve. The test is terminated when the flow measurement is obtained. The allowable calculated flow resistance between each CMT and the reactor vessel is $\geq 1.83 \times 10^{-5} \text{ ft/gpm}^2$ and $\leq 2.25 \times 10^{-5} \text{ ft/gpm}^2$.

TABLE 3.9-204 (Sheet 2 of 2)
SYSTEM LEVEL OPERABILITY TEST REQUIREMENTS

4. The heat transfer capability of the passive residual heat exchanger is demonstrated by conducting a test during cold shutdown conditions. The test is conducted with the RCPs in operation and the RCS at a reduced temperature. Flow through the heat exchanger is initiated by opening one outlet isolation valve. The test is terminated when the flow and temperature measurements are obtained. The allowable calculated heat transfer is $\geq 1.04\text{E}8$ Btu/hr with an inlet temperature of 250°F and an IRWST temperature of 120°F and the design basis number of tubes plugged.
5. The flow capability of each IRWST injection line is demonstrated by conducting flow tests and inspections. A flow test is conducted to demonstrate the flow capability of the injection line from the IRWST through the IRWST injection check valves. Water flow from the IRWST through the IRWST injection check valve demonstrates the flow capability of this portion of the line. Sufficient flow is provided to fully open the check valves. The test is terminated when the flow measurement is obtained. The allowable calculated flow resistance from the IRWST to each injection line check is: Line A: $\geq 5.53 \times 10^{-6}$ ft/gpm² and $\leq 9.20 \times 10^{-6}$ ft/gpm² and Line B: $\geq 6.21 \times 10^{-6}$ ft/gpm² and $\leq 1.03 \times 10^{-5}$ ft/gpm².

The flow capability of the portion of the line from the IRWST check valves to the DVI line is demonstrated by conducting an inspection of the inside of the line. The inspection shows that the lines are not obstructed. It is not necessary to operate the IRWST injection squib valves for this inspection.

6. The flow capability of each containment recirculation line is demonstrated by conducting an inspection. The line from the containment to the containment recirculation squib valve is inspected from the containment side. The line from the squib valve to the IRWST injection line is inspected from the IRWST side. The inspection shows that the lines are not obstructed. It is not necessary to operate the containment recirculation squib valves for this inspection.
7. The MCR pressurization capability is demonstrated by conducting a test. The test is conducted with the normal HVAC lines connected to the MCR isolated using the dampers in VBS designated for this purpose in [Subsection 9.4.1](#). Pressurization of the MCR is initiated by opening one of the emergency MCR habitability air supply lines. The test is performed on a staggered test basis and, therefore, the air supply lines are alternated for subsequent tests. The test is a limited duration test and is terminated when the MCR pressurization is measured. The minimum allowable MCR pressurization is 1/8 inch gauge pressure relative to the surrounding areas, with 65 ± 5 scfm air flow supplied by the emergency MCR habitability air supply line.

Control room envelope inleakage is evaluated by tracer gas testing performed as part of initial plant preoperational testing, as discussed in [Subsection 6.4.5.1](#), and periodically thereafter, as discussed in [Subsection 6.4.5.4](#). Where possible, inleakage testing is performed in conjunction with the VES system level operational testing since the VES must be in operation to perform the inleakage testing.

3.10 SEISMIC AND DYNAMIC QUALIFICATION OF SEISMIC CATEGORY I MECHANICAL AND ELECTRICAL EQUIPMENT

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

3.11 ENVIRONMENTAL QUALIFICATION OF MECHANICAL AND ELECTRICAL EQUIPMENT

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

3.11.5 COMBINED LICENSE INFORMATION ITEM FOR EQUIPMENT QUALIFICATION FILE

Add the following information to the end of DCD Subsection 3.11.5:

STD COL 3.11-1 The COL holder is responsible for the maintenance of the equipment qualification file upon receipt from the reactor vendor. The documentation necessary to support the continued qualification of the equipment installed in the plant that is within the environmental qualification (EQ) program scope is available in accordance with 10 CFR Part 50 Appendix A, General Design Criterion 1.

EQ files developed by the reactor vendor are maintained as applicable for equipment and certain post-accident monitoring devices that are subject to a harsh environment. The contents of the qualification files are discussed in **DCD Section 3D.7**. The files are maintained for the operational life of the plant.

For equipment not located in a harsh environment, design specifications received from the reactor vendor are retained. Any plant modifications that impact the equipment use the original specifications for modification or procurement. This process is governed by applicable plant design control or configuration control procedures.

Central to the EQ program is the EQ master equipment list (EQMEL). This EQMEL identifies the electrical and mechanical equipment or components that must be environmentally qualified for use in a harsh environment. The EQMEL consists of equipment that is essential to emergency reactor shutdown, containment isolation, reactor core cooling, or containment and reactor heat removal, or that is otherwise essential in preventing significant release of radioactive material to the environment. This list is developed from the equipment list provided in AP1000 **DCD Table 3.11-1**. The EQMEL and a summary of equipment qualification results are maintained as part of the equipment qualification file for the operational life of the plant.

Administrative programs are in place to control revision to the EQ files and the EQMEL. When adding or modifying components in the EQ Program, EQ files are generated or revised to support qualification. The EQMEL is revised to reflect these new components. To delete a component from the EQ Program, a deletion justification is prepared that demonstrates why the component can be deleted. This justification consists of an analysis of the component, an associated circuit review if appropriate, and a safety evaluation. The justification is released and/or referenced on an appropriate change document. For changes to the EQMEL, supporting documentation is completed and approved prior to issuing the

changes. This documentation includes safety reviews and new or revised EQ files. Plant modifications and design basis changes are subject to change process reviews, e.g. reviews in accordance with 10 CFR 50.59 or Section VIII of Appendix D to 10 CFR Part 52, in accordance with appropriate plant procedures. These reviews address EQ issues associated with the activity. Any changes to the EQMEL that are not the result of a modification or design basis change are subject to a separate review that is accomplished and documented in accordance with plant procedures.

Engineering change documents or maintenance documents generated to document work performed on an EQ component, which may not have an impact on the EQ file, are reviewed against the current revision of the EQ files for potential impact. Changes to EQ documentation may be due to, but not limited to, plant modifications, calculations, corrective maintenance, or other EQ concerns.

Table 13.4-201 provides milestones for EQ implementation.

TABLE 3.11-201 (Sheet 14 of 51)
 ENVIRONMENTALLY QUALIFIED ELECTRICAL AND
 MECHANICAL EQUIPMENT

Description	AP1000 Tag No.	Envir. Zone (Note 2)	Function (Note 1)	Operating Time Required (Note 5)	Qualification Program (Note 6)
SG1 Wide Range Level	SGS-JE-LT011	1	ESF PAMS	5 min 2 wks	E *
SG1 Wide Range Level	SGS-JE-LT012	1	ESF PAMS	5 min 2 wks	E *
SG1 Wide Range Level	SGS-JE-LT015	1	ESF PAMS	5 min 2 wks	E * E *
SG1 Wide Range Level	SGS-JE-LT016	1	ESF PAMS	5 min 2 wks	E * E *
SG2 Wide Range Level	SGS-JE-LT013	1	ESF PAMS	5 min 2 wks	E *
SG2 Wide Range Level	SGS-JE-LT014	1	ESF PAMS	5 min 2 wks	E *
SG2 Wide Range Level	SGS-JE-LT017	1	ESF PAMS	5 min 2 wks	E *
SG2 Wide Range Level	SGS-JE-LT018	1	ESF PAMS	5 min 2 wks	E *
WLS DEP 3.11-1 Spent Fuel Pool Level	SFS-JE-LT019A	6	PAMS	2 wks	E **
WLS DEP 3.11-1 Spent Fuel Pool Level	SFS-JE-LT019B	7	PAMS	2 wks	E **
WLS DEP 3.11-1 Spent Fuel Pool Level	SFS-JE-LT019C	6	PAMS	2 wks	E **
Air Storage Tank Pressure - A	VES-JE-PT001A	7	PAMS	2 wks	E+
Air Storage Tank Pressure - B	VES-JE-PT001B	7	PAMS	2 wks	E+
Containment Pressure Normal Range	PCS-JE-PT005	7	ESF PAMS	5 min 4 mos	E *
Containment Pressure Normal Range	PCS-JE-PT006	7	ESF PAMS	5 min 4 mos	E *
Containment Pressure Normal Range	PCS-JE-PT007	7	ESF PAMS	5 min 4 mos	E *
Containment Pressure Normal Range	PCS-JE-PT008	7	ESF PAMS	5 min 4 mos	E *
Containment Pressure Extended Range	PCS-JE-PT012	7	PAMS	4 mos	E *
Containment Pressure Extended Range	PCS-JE-PT013	7	PAMS	4 mos	E *
Containment Pressure Extended Range	PCS-JE-PT014	7	PAMS	4 mos	E *

TABLE 3.11-202 (Sheet 1 of 3)
ENVIRONMENTALLY QUALIFIED ELECTRICAL AND
MECHANICAL EQUIPMENT

Description	AP1000 Tag No.	Envir. Zone (Note 2)	Function (Note 1)	Operating Time Required (Note 5)	Qualification Program (Note 6)
Power Range Neutron Flux High Voltage Distribution Box C	PMS-JW-007C	2	RT	5 min	E
Power Range Neutron Flux High Voltage Distribution Box D	PMS-JW-007D	2	RT	5 min	E
MAIN CONTROL ROOM					
Operator Workstation A	N/A	3	RT ESF PAMS	5 min 24 hr 2 wks	E
Operator Workstation B	N/A	3	RT ESF PAMS	5 min 24 hr 2 wks	E
Supervisor Workstation	N/A	3	RT ESF PAMS	5 min 24 hr 2 wks	E
Switch Station (Including Switches)	N/A	3	RT ESF	5 min 24 hr	E
QDPS MCR Display Unit	PMS-JY-001B	3	PAMS	2 wks	E
QDPS MCR Display Unit	PMS-JY-001C	3	PAMS	2 wks	E
WLS DEP 6.4-2 MCR Load Shed Panel 1	VES-EP-01	2	ESF PAMS	24 hr 2 wks	E S
WLS DEP 6.4-2 MCR Load Shed Panel 2	VES-EP-02	2	ESF PAMS	24 hr 2 wks	E
PENETRATIONS					
Penetrations (Mechanical)	See Table 6.2.3-1				M *
Penetrations (Electrical)	See Figure 3.8.2-4				E *
ACTIVE VALVES					
Containment Isolation – Air Out Solenoid Valve Limit Switch	CAS-PL-V014	2	ESF	5 min	M S
	CAS-PL-V014-S	2	ESF	5 min	E
	CAS-PL-V014-L	2	PAMS	2 wks	E
Containment Isolation – Air In	CAS-PL-V015	1	ESF	5 min	M *
Containment Isolation – Inlet Limit Switch Motor Operator	CCS-PL-V200	2	ESF	5 min	M S
	CCS-PL-V200-L	2	PAMS	2 wks	E
	CCS-PL-V200-M	2	ESF	5 min	E
Service Air Supply Inside Containment Isolation	CAS-PL-V205	1	PB	1 yr	M *
Containment Isolation – Inlet	CCS-PL-V201	1	ESF	5 min	M *
Containment Isolation – Outlet Limit Switch Motor Operator	CCS-PL-V207	1	ESF	5 min	M *
	CCS-PL-V207-L	1	PAMS	1 yr	E *
	CCS-PL-V207-M	1	ESF	5 min	E *

TABLE 3.11-202 (Sheet 2 of 3)
ENVIRONMENTALLY QUALIFIED ELECTRICAL AND
MECHANICAL EQUIPMENT

	Description	AP1000 Tag No.	Envir. Zone (Note 2)	Function (Note 1)	Operating Time Required (Note 5)	Qualification Program (Note 6)
	MCR Isolation Valve	VBS-PL-V191	3	ESF	24 hr	M
	Limit Switch	VBS-PL-V191-L	3	PAMS	2 wks	E
	Motor Operator	VBS-PL-V191-M	3	ESF	24 hr	E
	Air Delivery Isolation Valve	VES-PL-V001	3	ESF	2 wks	M
	Pressure Regulator Valve A	VES-PL-V002A	7	ESF	2 wks	M
	Pressure Regulator Valve B	VES-PL-V002B	7	ESF	2 wks	M
	Actuation Valve A	VES-PL-V005A	3	ESF	2 wks	M
	Limit Switch	VES-PL-V005A-L	3	PAMS	2 wks	E
	Solenoid Operator	VES-PL-V005A-S	3	ESF	2 wks	E
	Actuation Valve B	VES-PL-V005B	3	ESF	2 wks	M
	Limit Switch	VES-PL-V005B-L	3	PAMS	2 wks	E
	Solenoid Operator	VES-PL-V005B-S	3	ESF	2 wks	E
WLS DEP 6.4-2	Temporary Instrument Isolation Valve A	VES-PL-V018	7	ESF	2 wks	M
WLS DEP 6.4-2	Temporary Instrument Isolation Valve B	VES-PL-V019	7	ESF	2 wks	M
	Relief Isolation Valve A	VES-PL-V022A	3	ESF	2 wks	M
	Limit Switch	VES-PL-V022A-L	3	PAMS	2 wks	E
	Solenoid Valve	VES-PL-V022A-S	3	ESF	2 wks	E
	Relief Isolation Valve B	VES-PL-V022B	3	ESF	2 wks	M
	Limit Switch	VES-PL-V022B-L	3	PAMS	2 wks	E
	Solenoid Valve	VES-PL-V022B-S	3	ESF	2 wks	E
	Air Tank Relief A	VES-PL-V040A	7	ESF	2 wks	M
	Air Tank Relief B	VES-PL-V040B	7	ESF	2 wks	M
	Air Tank Relief C	VES-PL-V040C	7	ESF	2 wks	M
	Air Tank Relief D	VES-PL-V040D	7	ESF	2 wks	M
	Main Air Flow Path Isolation Valve	VES-PL-V044	3	ESF	2 wks	M
	Eductor Flow Path Isolation Valve	VES-PL-V045	3	ESF	2 wks	M
	Eductor Bypass Isolation Valve	VES-PL-V046	3	ESF	2 wks	M
	Containment Purge Inlet	VFS-PL-V003	7	ESF	5 min	M S
	Isolation Limit Switch	VFS-PL-V003-L	7	PAMS	2 wks	E
	Solenoid Valve	VFS-PL-V003-S1	7	ESF	5 min	E
	Containment Purge Inlet	VFS-PL-V004	1	ESF	5 min	M *
	Isolation Limit Switch	VFS-PL-V004-L	1	PAMS	1 yr	E *
	Solenoid Valve	VFS-PL-V004-S1	1	ESF	5 min	E *
	Containment Purge Discharge	VFS-PL-V009	1	ESF	5 min	M *
	Isolation Limit Switch	VFS-PL-V009-L	1	PAMS	1 yr	E *
	Solenoid Valve	VFS-PL-V009-S1	1	ESF	5 min	E *
	Containment Purge Discharge	VFS-PL-V010	6	ESF	5 min	M S **
	Isolation Limit Switch	VFS-PL-V010-L	6	PAMS	2 wks	E **
	Solenoid Valve	VFS-PL-V010-S1	6	ESF	5 min	E **

TABLE 3.11-202 (Sheet 3 of 3)
 ENVIRONMENTALLY QUALIFIED ELECTRICAL AND
 MECHANICAL EQUIPMENT

Description	AP1000 Tag No.	Envir. Zone (Note 2)	Function (Note 1)	Operating Time Required (Note 5)	Qualification Program (Note 6)
Steam Line Condensate Drain Level Isolation Valve	SGS-PL-V096B	5	PB	1 yr	M *
Steam Line Condensate Drain Level Isolation Valve	SGS-PL-V097A	5	PB	1 yr	M *
Steam Line Condensate Drain Level Isolation Valve	SGS-PL-V097B	5	PB	1 yr	M *
Startup Feedwater Check Valve	SGS-PL-V256A	5	PB	1 yr	M *
Startup Feedwater Check Valve	SGS-PL-V256B	5	PB	1 yr	M *
Air Delivery Line Pressure Instrument Isolation Valve A	VES-PL-V006A	7	PB	1 yr	M
Air Delivery Line Pressure Instrument Isolation Valve B	VES-PL-V006B	7	PB	1 yr	M
Air Delivery Line Maintenance Isolation Valve A	VES-PL-V010A	7	PB	1 yr	M
Air Delivery Line Maintenance Isolation Valve B	VES-PL-V010B	7	PB	1 yr	M
Air Delivery Line Maintenance Isolation Valve A	VES-PL-V011A	7	PB	1 yr	M
Air Delivery Line Maintenance Isolation Valve B	VES-PL-V011B	7	PB	1 yr	M
Temporary Instrument Isolation Valve A	VES-PL-V016	7	PB	1 yr	M
Deleted					
Deleted					
Temporary Instrument Isolation Valve B	VES-PL-V020	7	PB	1 yr	M
Air Bank 1 Isolation Valve A	VES-PL-V024A	7	PB	1 yr	M
Air Bank 2 Isolation Valve B	VES-PL-V024B	7	PB	1 yr	M
Air Bank 3 Isolation Valve C	VES-PL-V024C	7	PB	1 yr	M
Air Bank 4 Isolation Valve D	VES-PL-V024D	7	PB	1 yr	M
Air Bank 1 Isolation Valve A	VES-PL-V025A	7	PB	1 yr	M
Air Bank 2 Isolation Valve B	VES-PL-V025B	7	PB	1 yr	M
Air Bank 3 Isolation Valve C	VES-PL-V025C	7	PB	1 yr	M
Air Bank 4 Isolation Valve D	VES-PL-V025D	7	PB	1 yr	M
Air Bank 1 Fill/Vent Isolation Valve A	VES-PL-V026A	7	PB	1 yr	M

WLS DEP 6.4-2

WLS DEP 6.4-2

APPENDIX 3A
HVAC DUCTS AND DUCT SUPPORTS

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3B

LEAK-BEFORE-BREAK EVALUATION OF THE AP1000 PIPING

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3C
REACTOR COOLANT LOOP ANALYSIS METHODS

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3D
METHODOLOGY FOR QUALIFYING AP1000 SAFETY-RELATED ELECTRICAL
AND MECHANICAL EQUIPMENT

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

Figure 3D-201 replaces DCD Figure 3D.5-1, Sheet 1 of 3, Typical Abnormal Environmental Test Profiles: Main Control Room.

APPENDIX 3E
HIGH-ENERGY PIPING IN THE NUCLEAR ISLAND

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3F
CABLE TRAYS AND CABLE TRAY SUPPORTS

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3G
NUCLEAR ISLAND SEISMIC ANALYSES

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3H
AUXILIARY AND SHIELD BUILDING CRITICAL SECTIONS

This **section** of the referenced DCD is incorporated by reference with no departures or supplements.

APPENDIX 3I EVALUATION FOR HIGH FREQUENCY SEISMIC INPUT

This **section** of the referenced DCD is incorporated by reference with the following departures and/or supplements.

WLS DEP 2.0-1 3I.1 INTRODUCTION

Add the following information to the end of DCD Subsection 3I.1

The nuclear island foundation input response spectra (NI FIRS) for Lee Nuclear Station, the envelope of the GMRS (Unit 2 FIRS) and the Unit 1 FIRS (**Subsection 3.7.1.1.1**), are slightly above the AP1000 HRHF spectra, but the spectra are very similar. **Figures 3I.1-201** and **3I.1 202** compare the NI FIRS to the AP1000 CSDRS and the AP1000 HRHF spectra for the horizontal and vertical directions for 5% damping. The NI FIRS exceeds the AP1000 CSDRS for frequencies above approximately 14 Hz and the AP1000 HRHF spectra above approximately 3 Hz.

Because the NI FIRS are not enveloped by the AP1000 HRHF spectra, a site-specific analysis is performed to evaluate and justify exceedances. Technical report WLG-GW-GLR-815 (**Reference 201**) provides a summary of those evaluations and results. This report presents in-structure response spectra throughout the Nuclear Island resulting from the site-specific input. These in-structure response spectra were investigated and all exceedances of the CSDRS or HRHF spectra were identified. Three instances of largest exceedances were noted, and these three instances were investigated as bounding conditions and justified by further evaluations.

WLS DEP 2.0-1 3I.2 HIGH FREQUENCY SEISMIC INPUT

Add the following information to the end of DCD Subsection 3I.2

Figures 3I.1-201 and **3I.1-202** present a comparison of the horizontal and vertical (respectively) Lee Nuclear Station NI FIRS to the AP1000 CSDRS and the AP1000 HRHF. The NI FIRS are calculated at foundation level (39.5' below grade), at the upper most competent material and treated as an outcrop for calculation purposes.

For each direction, the NI FIRS exceeds the CSDRS in higher frequencies (greater than 14 Hz horizontal and 16 Hz vertical) and the AP1000 HRHF spectra at frequencies greater than 3 Hz in both the horizontal and vertical directions.

WLS DEP 2.0-1 3I.3 NI MODELS USED TO DEVELOP HIGH FREQUENCY RESPONSE

Add the following information to the end of DCD Subsection 3I.3

The NI20u nuclear island model (**Reference 201**) is analyzed in ACS SASSI using the Lee Nuclear Station NI FIRS time histories (**Subsection 3.7.2.1.2**) applied at foundation level to obtain the motion at the base.

The NI20u model used in the Lee Nuclear Station site-specific analysis was updated to incorporate design changes from detailed design finalization of the AP1000 standard plant (no impact from design changes to licensing basis as defined in AP1000 DCD Rev 19) and to improve the match between the NI20u model and the more realistic NI10 model used to design and qualify the AP1000 standard plant for the CSDRS.

Evaluation of incoherent NI FIRS has been performed. In-structure response spectra for the AP1000 CSDRS, incoherent HRHF spectra and the incoherent NI FIRS were compared at a number of locations/elevations in the Nuclear Island. Several minor exceedances were noted that are addressed as part of the sampling evaluation outlined in [DCD Subsection 3I.6](#).

WLS DEP 2.0-1 3I.6 EVALUATION

Add the following information to the end of DCD Subsection 3I.6

As described in Lee Nuclear Station site-specific Technical Report WLG-GW-GLR-815 ([Reference 201](#)), all exceedances of the in-structure response spectra resulting from the Lee Nuclear Station NI FIRS input were identified. Three instances of largest in-structure response spectra exceedances were investigated as bounding conditions and justified by further evaluation. Therefore, the sample of structures, systems and components selected for evaluation remains unchanged.

WLS DEP 2.0-1 3I.6.1 Building Structures

Add the following information to the end of DCD Subsection 3I.6.1

Load comparisons for the building structures evaluated show that the seismic loads resulting from the CSDRS input motion are greater than the seismic loads generated from the NI FIRS ([Reference 201](#)).

WLS DEP 2.0-1 3I.6.2 Primary Coolant Loop

Add the following information to the end of DCD Subsection 3I.6.2

Load comparisons for the primary component supports and nozzles evaluated show that the seismic loads resulting from the CSDRS input motion are greater than the seismic loads generated from the NI FIRS ([Reference 201](#)).

WLS DEP 2.0-1 3I.6.3 Piping Systems

Add the following information to the end of DCD Subsection 3I.6.3

ASME Class 1, 2, and 3 piping packages were reviewed along with local input seismic response spectra for susceptibility to excitation from high frequency seismic input motion. Since the in-structure floor response spectra (FRS) generated from the Lee Nuclear Station NI FIRS are enveloped completely by

either by the FRS generated from the CSDRS or HRHF spectra in most locations, all of the piping analyses do not need to be redone for the NI FIRS.

Three piping packages, ADS 4th Stage East Compartment and Passive RHR Supply, Pressurizer Surge Line, and SFS from Auxiliary Building Area 4 SCV to Auxiliary Building Area 6 SFS Pumps (SFS Aux. Building 4 to 6) were chosen for evaluation ([Reference 201](#)). These packages are representative of all safety class piping in Lee Nuclear Station because they are the most susceptible to excitation from high frequency seismic input motion.

The stress results of the sample piping analysis packages show that the AP1000 HRHF stresses were greater than the NI FIRS stresses for all nodes in the ADS 4th Stage and SFS Aux. Building 4 to 6 piping packages and only slightly less in the Pressurizer Surge Line piping package. Stress comparison results show that AP1000 CSDRS stresses are greater than the NI FIRS stresses at all nodes in all three piping packages except for one node in the SFS Aux. Building 4 to 6 piping package where there was a slight NI FIRS exceedance. At this one point, the stresses resulting from the NI FIRS were less than those from the HRHF spectra. Therefore, the design practices for standard plant AP1000 piping systems have considered cases that envelope the Lee site-specific requirements.

The stresses due to the Lee Nuclear Station NI FIRS input are bounded by design basis analysis results. The same applies to all of the analyzed piping supports. As a result, the effect of the NI FIRS input on safety class piping is found to be non-damaging ([Reference 201](#)).

WLS DEP 2.0-1 3I.6.4 Electrical and Electro-Mechanical Equipment

Add the following information to the end of DCD Subsection 3I.6.4

To demonstrate acceptability, the test response spectra (TRS) for high frequency sensitive equipment procured for Lee Nuclear Station will have to bound the required response spectra (RRS) of the AP1000 CSDRS, AP1000 HRHF spectra, and the NI FIRS generated in-structure response spectra. As shown in the Lee Nuclear Station site-specific Technical Report WLG-GW-GLR-815 ([Reference 201](#)), very little if any of the AP1000 equipment will need to be re-qualified for the Lee Nuclear Station high frequency seismic motion considering margins in the TRS currently being used to qualify AP1000 high frequency sensitive equipment. However, per the licensing commitment in [Subsection 3.7.2.15](#), Duke Energy will ensure that all seismic qualification testing for safety-related equipment required per this Appendix appropriately envelopes the Lee Nuclear Station site-specific seismic requirements, in addition to the CSDRS and HRHF RRS.

WLS DEP 2.0-1 3I.7 REFERENCES

Add the following information to the end of DCD Subsection 3I.7

201. Westinghouse Electric Company, LLC, "Effect of William S. Lee Site Specific Seismic Requirements on AP1000 SSCs," WLG-GW-GLR-815, Revision 0, January 17, 2014.

TABLE 3I-201
LIST OF POTENTIAL HIGH FREQUENCY SENSITIVE AP1000 SAFETY-
RELATED ELECTRICAL AND ELECTRO-MECHANICAL EQUIPMENT

	Description	AP1000 Tag Number
	Intermediate Range Neutron Flux Preamplifier Panel D	PMS-JW-006D
	Power Range Neutron Flux High Voltage Distribution Box A	PMS-JW-007A
	Power Range Neutron Flux High Voltage Distribution Box B	PMS-JW-007B
	Power Range Neutron Flux High Voltage Distribution Box C	PMS-JW-007C
	Power Range Neutron Flux High Voltage Distribution Box D	PMS-JW-007D
	Main Control Room	
	Operator Workstation A	N/A
	Operator Workstation B	N/A
	Supervisor Workstation	N/A
	Switch Station (Including Switches)	N/A
	QDPS MCR Display Unit	PMS-JY-001B
	QDPS MCR Display Unit	PMS-JY-001C
WLS DEP 6.4-2	MCR Load Shed Panel 1	VES-EP-01
WLS DEP 6.4-2	MCR Load Shed Panel 2	VES-EP-02
	Active Valves	
	Containment Isolation – Air Out Solenoid Valve Limit Switch	CAS-PL-V014-S CAS-PL-V014-L
	Containment Isolation – Inlet Limit Switch Motor Operator	CCS-PL-V200-L CCS-PL-V200-M
	Containment Isolation – Outlet Limit Switch Motor Operator	CCS-PL-V207-L CCS-PL-V207-M
	Containment Isolation – Outlet Limit Switch Motor Operator	CCS-PL-V208-L CCS-PL-V208-M

TABLE 3I-202 (Sheet 1 of 2)
LIST OF AP1000 SAFETY-RELATED ELECTRICAL AND MECHANICAL
EQUIPMENT NOT HIGH FREQUENCY SENSITIVE

Description	AP1000 Tag Number	Comment
SG Blowdown Isolation	SGS-PL-V074B	2
SG Series Blowdown Isolation	SGS-PL-V075A	2
SG Series Blowdown Isolation	SGS-PL-V075B	2
Steam Line Condensate Drain Isolation	SGS-PL-V086A	2
Steam Line Condensate Drain Isolation	SGS-PL-V086B	2
Power-Operated Relief Valve	SGS-PL-V233A	2
Power-Operated Relief Valve	SGS-PL-V233B	2
MSIV Bypass Isolation Valve	SGS-PL-V240A	2
MSIV Bypass Isolation Valve	SGS-PL-V240B	2
Main Feedwater Control Valve	SGS-PL-V250A	2
Main Feedwater Control Valve	SGS-PL-V250B	2
Startup Feedwater Control Valve	SGS-PL-V255A	2
Startup Feedwater Control Valve	SGS-PL-V255B	2
MCR Isolation Valve	VBS-PL-V186	2
MCR Isolation Valve	VBS-PL-V187	2
MCR Isolation Valve	VBS-PL-V188	2
MCR Isolation Valve	VBS-PL-V189	2
MCR Isolation Valve	VBS-PL-V190	2
MCR Isolation Valve	VBS-PL-V191	2
Air Delivery Isolation Valve	VES-PL-V001	2
Pressure Regulator Valve A	VES-PL-V002A	2
Pressure Regulator Valve B	VES-PL-V002B	2
Actuation Valve A	VES-PL-V005A	2
Actuation Valve B	VES-PL-V005B	2
WLS DEP 6.4-2 Temporary Instrument Isolation Valve A	VES-PL-V018	2
WLS DEP 6.4-2 Temporary Instrument Isolation Valve B	VES-PL-V019	2
Relief Isolation Valve A	VES-PL-V022A	2
Relief Isolation Valve B	VES-PL-V022B	2

TABLE 3I-202 (Sheet 2 of 2)
LIST OF AP1000 SAFETY-RELATED ELECTRICAL AND MECHANICAL
EQUIPMENT NOT HIGH FREQUENCY SENSITIVE

	Description	AP1000 Tag Number	Comment
	Startup Feedwater Check Valve	SGS-PL-V256B	2
	Air Delivery Line Pressure Instrument Isolation Valve A	VES-PL-V006A	2
	Air Delivery Line Pressure Instrument Isolation Valve B	VES-PL-V006B	2
	Temporary Instrument Isolation Valve A	VES-PL-V016	2
WLS DEP 6.4-2	Deleted		
WLS DEP 6.4-2	Deleted		
	Temporary Instrument Isolation Valve B	VES-PL-V020	2
	Air Tank Isolation Valve A	VES-PL-V024A	2
	Air Tank Isolation Valve B	VES-PL-V024B	2
	Air Tank Isolation Valve A	VES-PL-V025A	2
	Air Tank Isolation Valve B	VES-PL-V025B	2
	Refill Line Isolation Valve	VES-PL-V038	2
	DP Instrument Line Isolation Valve A	VES-PL-V043A	2
	DP Instrument Line Isolation Valve B	VES-PL-V043B	2
	Containment Isolation Test Connection	VFS-PL-V008	2
	Containment Isolation Test Connection	VFS-PL-V012	2
	Containment Isolation Test Connection	VFS-PL-V015	2
	Main Equipment Hatch Test Connection	VUS-PL-V015	2
	Maintenance Equipment Hatch Test Connection	VUS-PL-V016	2
	Personnel Hatch Test Connection	VUS-PL-V017	2
	Personnel Hatch Test Connection	VUS-PL-V018	2
	Personnel Hatch Test Connection	VUS-PL-V019	2
	Personnel Hatch Test Connection	VUS-PL-V020	2
	Personnel Hatch Test Connection	VUS-PL-V021	2
	Personnel Hatch Test Connection	VUS-PL-V022	2
	Fuel Transfer Tube Test Connection	VUS-PL-V023	2