

L-CE-8081

SEISMIC QUALIFICATION TEST REPORT

Test Report STR6764

Ex-Core Safety Channel
Neutron Flux Signal Processing Electronics

.. CE Specification No. 13172-ICE-3006, Rev. 01

P/N 39500

S/N E39131

Prepared By:

George C. Boyer

Date: 6-9-82

Reviewed By:

7th Jan. 1901.

Date: 6/7/82

Approved By:

CID Kipling (Eng.)

Date: 6-9-82

Approved By:

JO. Karland (QA)

Date: 6/9/8.

Revision	Date
Rev. A Extensively Revised 10/26/82	ECO #15166 10/25/82
3303110268 830309 PDR ADDCK 05000389 PDR	



1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.

TABLE OF CONTENTS

<u>Section No.</u>	<u>Title</u>	<u>Page No.</u>
1.0	<u>SCOPE</u>	1
2.0	<u>APPLICABLE REFERENCES</u>	2
3.0	<u>SUMMARY AND CONCLUSIONS</u>	3
Appendix A	American Environments Company, Inc., Ex-Core Safety Channel Seis- mic Qualification Test Report STR- 52781-2	
Appendix B	Electro-Mechanics, Inc. Seismic Test Data	

1.0 SCOPE

This document describes the seismic qualification test efforts relative to the Ex-Core Safety Channel Neutron Flux Signal Processing Electronics Assembly, Florida Power and Light, St. Lucie Unit #2, as set forth in Combustion Engineering Project Specification No. 13172-ICE-3006, Rev. 01 and related documents as set forth in Section 2.0 of this report.

2.0 APPLICABLE REFERENCES

- 2.1 Combustion Engineering, Inc. Specification 13172-ICE-3006, Rev. 01
- 2.2 Electro-Mechanics, Inc. Seismic Qualification Test Procedure TP 6764-13, Rev. E
- 2.3 Electro-Mechanics, Inc. Functional Test Procedure TP 6764-2
- 2.4 Machinery's Handbook, 20th Edition, Industrial Press, Inc., 1978

3.0 SUMMARY AND CONCLUSIONS

3.1 GENERAL

- 3.1.1 Prior to start of testing, the Ex-Core Safety Channel Assembly with the specified aged components installed, was cycled in accordance with paragraph 5.2.3.1 of CE Specification 13172-ICE-3006, Rev. 01, as relates to component cycling and environmental testing.

3.2 SEISMIC QUALIFICATION TESTING

- 3.2.1 The complete method of testing is delineated in the American Environments Seismic qualification Test Report STR 52781-2, Appendix A, of this document.

- 3.2.2 Electrical test data as indicated in American Environments Test Report STR-52781-2 and Electro-Mechanics Test Procedure TP 6764-13 is presented in Appendix B of this report and includes the following:

- a) Pretest data following environmental testing per Electro-Mechanics Test Procedures TP 6764-2 and TP 6764-13.
- b) Seismic Electrical Test Data per Electro-Mechanics Test Procedure TP 6764-13.
- c) Post test data per Electro-Mechanics Test Procedure TP 6764-2.

NOTE: Original Strip Chart recordings are submitted separately with this report.



3.2.3 The visual inspection of the unit revealed no evidence of physical damage to the unit as a result of this test as noted in American Environments Test Report STR-52781-2, paragraph 4.8.

3.2.4 A review of the electrical test data both during and following the subjection of the unit to the stipulated seismic events did not reveal any evidence of the occurrence of malfunctions as a result of this testing.

3.2.5 A total of two (2) strain gages were used located at positions of maximum strain (see Appendix B, Table I for specific locations). Calculations (Appendix B, Calculation I) are provided to indicate the apparent stress the unit experienced during each SSE. The apparent stress was considerably less than the typical yield stress for steel, 30×10^3 PSI (refer to Reference 2.4, Table I on page 452).

3.2.6 No deflection beyond 1/2" occurred at any monitored point during the test, thus meeting acceptance criteria as specified in EM TP 6764-13.


3.3 CONCLUSIONS

3.3.1 It is the conclusion of this activity that the Ex-Core Safety Neutron Flux Signal Processing Electronics Assembly is in complete compliance with all of the seismic requirements set forth in Combustion Engineering Specification No. 13172-ICE-3006, Rev. 01, Sections 4.1.5.2, 5.2.3.3 and related documents referenced therein.



Appendix A





AMERICAN ENVIRONMENTS COMPANY INC., 166D CABOT STREET, WEST BABYLON, N.Y. 11704 (516) 752-0989

SEISMIC QUALIFICATION TEST REPORT

ON

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

FOR

ELECTRO-MECHANICS INCORPORATED

NEW BRITAIN, CONNECTICUT

NUMBER	BY	DATE
STR-52781-2	AMERICAN ENVIRONMENTS COMPANY	04/07/82
REVISION "A"	AMERICAN ENVIRONMENTS COMPANY	09/07/82

PREPARED BY:

Paul Bauer

QUALITY ASSURANCE
BY:

David Netman

APPROVAL
CERTIFICATION
BY:

Shirley Holman

CUSTOMER REVIEW
BY:

George A. Polyzos

CUSTOMER APPROVAL
BY:

AD Mukherji

STR-52781-2





REVISION RECORD

DATE	REVISION NUMBER	PAGE NUMBER	PARAGRAPH NUMBER	CHANGES OR ADDITIONS	APPROVED BY
04/07/82	N/C	-	-	-	<i>Eth</i>
09/07/82	A	21	-	Changed SSE #6 4.5 micro-in. to 2.25 micro-in. Changed SSE #24 10.2 micro-in. to 5.1 micro-in.	<i>ETH</i>



DATE: 7 April 1982

PURPOSE OF TEST:

To determine the effects of Seismic Qualification Testing on the physical and operational characteristics of the submitted test specimen.

MANUFACTURER:

Electro-Mechanics Inc.
150 John Downey Drive
New Britain, Conn. 06051

MANUFACTURER TYPE AND
SERIAL NUMBER:

Ex-core Safety Channel Neutron Flux
Signal Processing Electronics.

DRAWINGS SPECIFICATIONS
OR EXHIBITS:

- A) Electro-Mechanics Test Procedure
No. TP/TR-6764-13, Rev. C.
- B) IEEE-STD-344 1975.
- C) American Environments Test Plan
No. STP-48681-2, Rev.0.

QUANTITY OF ITEMS TESTED:

One (1) assembly.

DISPOSITION OF TEST
SPECIMEN:

Returned to client.

TEST COMPLETED ON:

26 March 1982

ARCHITECT / ENGINEER:
NUCLEAR UNIT(S):

N/A
N/A

TEST CONDUCTED BY:

AMERICAN ENVIRONMENTS COMPANY, INC.
Division of: East-West Technology
119 Cabot Street
West Babylon, N.Y. 11704

ABSTRACT:

It is the function of American Environments Company, Inc., as an impartial testing agency in performing this test, to subject the test specimen to seismic vibrations of magnitude and direction as specified in the RRS Curves, Figure 1 and orientations as shown in Figure 2, herein.

1.0 DESCRIPTION OF TEST APPARATUS

- 1.1 Function Generator, Model No. 202A, Serial No. 11638, manufactured by Hewlett Packard. Calibration Due: 10 May 1982.
- 1.2 DC Servo Controller, Model No. 82B300, Serial No. 193, manufactured by Moog, Inc. Calibration not required.
- 1.3 Actuator, Model No. DN-65, Serial No. 70552, manufactured by Miller Fluid Power Company. Calibration not required.
- 1.4 Servo Valve, Model No. 72-103, Serial No. 68, manufactured by Moog, Inc. Calibration not required.
- 1.5 Hydraulic Power Pack, Model No. 240/3000-5606, Serial No. 03, manufactured by East West Technology Corp. Calibration not required.
- 1.6 Displacement Transducer, Model No. 7312-V4-A0, Serial No. 036, manufactured by Pickering and Company. Calibrated immediately prior to test.
- 1.7 Signal Amplifier (1), Model No. 914, Serial No. 145, manufactured by Technology for Energy Corporation. Calibration Due: 16 August 1982.
- 1.8 Signal Charge Amplifiers (8), Model No. 500LF, Serial Nos. 01167 through 01174, manufactured by Technology for Energy Corporation. Calibration Due: 16 August 1982.
- 1.9 DC Servo Controller, Model No. 710, Serial No. 001, manufactured by CGS System, Inc. Calibration not required.
- 1.10 Accelerometers (8), Model No. 320, Serial Nos. 675 through 678 and 680 through 683, manufactured by Columbia Research Laboratories. Calibration Due: 16 August 1982.

TABLE OF CONTENTS

PAGE 2

<u>PARAGRAPH</u>	<u>PAGE</u>
ADMINISTRATIVE DATA .	3
1.0 TEST APPARATUS	4
2.0 DESCRIPTION OF TEST SPECIMEN	5
3.0 METHOD OF TEST	5
3.1 TEST SEQUENCE	6
3.2 TEST SETUP	6
3.3 FUNCTIONAL TESTS	6
3.4 SEISMIC QUALIFICATION TEST METHOD	7
4.0 TEST RESULTS	9
5.0 SUMMARY OF STRUCTURAL CONDITON	13
6.0 RECOMMENDATIONS	13
7.0 CONCLUSIONS	13
APPENDIX A - FIGURES	14
APPENDIX B-STRAIN GAUGE RECORDINGS & STRESS CALCULATIONS	17
APPENDIX C - ZPA TEST DATA & DEFLECTION CALCULATIONS	22
APPENDIX D - TRANSMISSIBILITY DATA PLOTS	27
APPENDIX E - TEST RESPONSE SPECTRA	41
APPENDIX F - EQUIPMENT RESPONSE SPECTRA	67
APPENDIX G - PHOTOGRAPHS	141

STR-52781-2

1.0 DESCRIPTION OF TEST APPARATUS CONTINUED

- 1.11 Oscilloscope, Model No. 453, Serial No. 028412, manufactured by Tektronix. Calibration Due: 6 April 1982.
- 1.12 Digital Plotter, Model No. 7225A/17603A, Serial No. 1823A00171, manufactured by Hewlett Packard. Calibrated immediately prior to use.
- 1.13 X-Y Recorder, Model 7035B, Serial No. 2007818582, manufactured by Hewlett Packard. Calibration Due: 9 April 1982.
- 1.14 FM Tape Recorder (1), Model No. 5600C, Serial No. 081117, manufactured by The Honeywell Corporation. Calibration Due: 19 November 1982.
- 1.15 Spectrum Analyzer, Model No. 505N2, Serial No. 505-10, manufactured by M-Rad Corporation. Calibration Due: 15 September 1982.
- 1.16 Spectrum Synthesizer, Model No. N284, Serial No. 197-22, manufactured by M-Rad Corporation. Calibration Due: 10 June 1982.
- 1.17 Spectrum Analyzer, Model No. 3582A, Serial No. 1809A03066, manufactured by Hewlett-Packard. Calibration Due: 9 April 1982.
- 1.18 Strain Gage Conditioners (2), Model No. 3502-08A/08-0049, Serial Nos. 10229 (2010) and 10230 (2011), manufactured by Jay Controls Company. Calibration Due: 16 August 1982.

2.0 DESCRIPTION OF TEST SPECIMEN

Ex-core Safety Channel Neutron Flux Signal Processing Electronics, Assembly P/N 39500, Serial No. E39131.

3.0 METHOD OF TEST

The following test procedure was employed during the progress of the Qualification Test program.





3.1 TEST SEQUENCE

The test sequence, as state below, was followed during the execution of the qualification program:

- 3.1.1 Pre-test Inspection and Electrical Tests.
- 3.1.2 Resonant Frequency Search Test (Phase I).
- 3.1.3 Seismic Random Test (Phase II).
- 3.1.4 Post Seismic Inspection and Electrical Tests.

3.2 TEST SET-UP

The test specimen was secured to a test fixture which was securely mounted to the seismic vibration table. The test fixture was rigid when subjected to the seismic simulation. The front panel mounting screws were provided by Electro-Mechanics (eight (8) flathead screws, #10-32 and two (2) side slide mounts). The test cable connections to the unit were typical of in-service connections and were unsupported for a span of approximately one (1) foot. The set up was in accordance with Electro-Mechanics drawing No. 0000-39526.

3.3 ELECTRICAL INSPECTION AND OPERATIONAL TESTS

Prior to and following the Seismic Qualification test the specimen was subjected to visual and electrical tests in order to determine it's ability to operate in a normal manner.

The specific operational test method was in accordance with Electro-Mechanics procedures as follows:

3.3.1 Pre-test Inspection

The pre-test inspection consisted of visually examining the specimen for evidence of physical or other damage that may have been caused by shipment to the test site or in mounting the specimen. Points of particular interest were:

- Overall appearance and condition of test specimen
- Circuit boards and components
- Cables
- Connectors

3.3 ELECTRICAL INSPECTION AND OPERATIONAL TESTS (CON'T)

3.3.2 Electrical Tests - Seismic

All Electrical tests were performed by Electro-Mechanics personnel, in accordance with the requirements of Test Procedure No. TP 6764-13, Rev. C prior to, during, and at the conclusion of the Seismic Test Program. All test data was retained by Electro-Mechanics personnel.

3.3.3 Post-test Inspection

The post-test inspection consisted of visually examining the specimen for evidence of physical or other damage that may have been caused by the stresses of the seismic qualification test. Points of particular interest were:

- Structural areas that may have experienced high stress
- Circuit boards and components
- Cables
- Connectors

3.4 SEISMIC QUALIFICATION TESTS

3.4.1 Phase I - Resonant Frequency Search

A resonant frequency search was performed in the frequency range of 1.0 to 35 Hz at an input excitation level of approximately 0.2 g peak. The input acceleration was controlled at all times by means of a piezoelectric accelerometer and displacement potentiometer. Six (6) response accelerometers were used to monitor specimen response and to determine specimen resonant frequencies, if any. Additionally, two (2) strain gages were secured to the test specimen. The accelerometer and strain gage locations are noted in the test results portion of the test report.

The frequency range from 1.0 to 35 Hz was searched by sweeping the input frequency at a rate of approximately one half octave per minute and remaining at each discrete frequency for a period of approximately fifteen (15) seconds in order to record specimen response data.



3.4 SEISMIC QUALIFICATION TESTS (CON'T)

3.4.1 Phase I - Resonant Frequency Search (Con't)

Phase I testing was performed in each of three (3) mutually perpendicular axes. The resonant frequency survey was performed in all four (4) test directions.

The specimen was energized for all resonant search testing. Performance was not monitored.

3.4.2 Phase II - Seismic Random Test (Multi-Frequency)

Upon completion of Phase I testing in the first biaxial pair (minor horizontal and vertical axes), the test specimen was subjected to seismic (random) event tests. The input motion was phase coherent, random multi-frequency in waveform and equalized in 1/3 octave segments from 1.0 to 100 Hz. The input acceleration response levels were sufficient to envelope the Required Response Spectrum shown in Figure 1 of Appendix A, contained herein.

Analysis was performed in 1/6 octave segments, in the frequency range of 1.0 to 200 Hz, utilizing 1% of critical damping for the OBE and SSE Seismic loadings. The input accelerations were applied simultaneously, in-phase and at an angle of 45 degrees from the horizontal axis. Each seismic event was repeated with the inputs simultaneous but 180 degrees out-of-phase (ie., specimen and fixture were rotated 180 degrees about the vertical axis on the vibration table). The duration of each seismic event was a minimum of thirty (30) seconds, uninterrupted. The apparent ZPA level was monitored and recorded during each seismic event. There were a total of six (6) seismic events for each of the in-phase and out-of-phase conditions (ie., twelve (12) events for each biaxial pair) as follows:

FIVE TIMES IN-PHASE & FIVE TIMES OUT-OF-PHASE

Operating Basis Earthquake (OBE) - Equipment energized.

ONE TIME IN-PHASE AND ONE TIME OUT-OF-PHASE

Safe Shutdown Earthquake (SSE) - Equipment energized.

3.4.2 Phase II - Seismic Random Test (Multi-Frequency) (Con't)

At the conclusion of testing for the first biaxial pair the specimen was rotated 90 degrees on the seismic table, about the vertical, resulting in the second mutually perpendicular horizontal axis. Phase I testing was then repeated, in it's entirety, for the second horizontal (major) and vertical axes combination. Phase II testing was then repeated (in it's entirety) for the second biaxial pair (major horizontal and vertical axes). There were a total of six (6) seismic events for each of the in-phase and out-of-phase conditions (ie., twelve (12) events for each biaxial pair) as follows:

FIVE TIMES IN-PHASE & FIVE TIMES OUT-OF-PHASE

Operating Basis Earthquake (OBE) - Equipment energized.

ONE TIME IN-PHASE AND ONE TIME OUT-OF-PHASE

Safe Shutdown Earthquake (SSE) - Equipment energized.

Functional testing was performed during each Seismic Event by Electro-Mechanics personnel and all data retained by them.

4.0 TEST RESULTS:

The following information was observed and recorded before, during and after exposure to the stresses of the Seismic Qualification Test.

4.1 PRE-TEST INSPECTION

The following information was observed and recorded during the Pre-Test Inspection and Electrical Tests.

Visual Inspection - There was no evidence of physical damage to the test specimen as a result of shipment to the test site or subsequent to it's installation on the test table.

Electrical Test - Electrical performance data was obtained and retained by Electro-Mechanics personnel.



4.2 PHASE I RESONANCE SEARCH TEST

BIAXIAL PAIR NO. 1 (FRONT TO BACK):

Channel Number	Motion Axis Monitored	Observed Resonant Freq. (Hz)	Ratio g out/ g in	Comments
3	Vertical			No Significant Resonances Observed
4	Horizontal	25	2.5	Specimen Mounted Resonance
5	Vertical	36.5	2.2	Slight Card Cage Resonance
6	Horizontal	25	3.3	Specimen Mounted Resonance
7	Vertical	15.5	2.8	Specimen Mounted Resonance
8	Vertical			No Significant Resonances Observed

See Appendix for Transmissibility Data Plots.

4.3 PHASE I RESONANCE SEARCH TEST

BIAXIAL PAIR NO. 2 (SIDE TO SIDE):

Channel Number	Motion Axis Monitored	Observed Resonant Freq. (Hz)	Ratio g out/ g in	Comments
3	Vertical	20-35	3.4	Broadband Resonance
4	Horizontal	26	6.8	Specimen Mounted Resonance
5	Vertical	35.5	6.1	Card Cage Resonance
6	Horizontal	26.5	7.2	Specimen Mounted Resonance
7	Vertical	20.5	3.3	Specimen Mounted Resonance
8	Vertical	20.5	3.7	Specimen Mounted Resonance

See Appendix for Transmissibility Data Plots.



4.4 SEISMIC RANDOM EVENT TESTS - PHASE II

BIAXIAL PAIR NO. 1
IN-PHASE

RUN NO.	EVENT	DURATION
1	OBE	30 SEC.
2	OBE	30 SEC.
3	OBE	30 SEC.
4	OBE	30 SEC.
5	OBE	30 SEC.
6	SSE	30 SEC.

There was no evidence of physical damage observed as a result of the stresses of these events. All electrical performance data was obtained and retained by Electro-Mechanics personnel. See Appendix E for Test Response Spectra and Appendix F for Equipment Response Spectra. Note: Typical OBE response data is presented in these appendices and response data not shown was verified to be consistent with those presented.

4.5 SEISMIC RANDOM EVENT TESTS - PHASE II

BIAXIAL PAIR NO. 1
OUT-OF-PHASE

RUN NO.	EVENT	DURATION
7	OBE	30 SEC.
8	OBE	30 SEC.
9	OBE	30 SEC.
10	OBE	30 SEC.
11	OBE	30 SEC.
12	SSE	30 SEC.

There was no evidence of physical damage observed as a result of the stresses of these events. All electrical performance data was obtained and retained by Electro-Mechanics personnel. See Appendix E for Test Response Spectra and Appendix F for Equipment Response Spectra. Note: Typical OBE response data is presented in these appendices and response data not shown was verified to be consistent with those presented.



4.6 SEISMIC RANDOM EVENT TESTS - PHASE II

BIAXIAL PAIR NO. 2
IN-PHASE

RUN NO.	EVENT	DURATION
13	OBE	30 SEC.
14	OBE	30 SEC.
15	OBE	30 SEC.
16	OBE	30 SEC.
17	OBE	30 SEC.
18	SSE	30 SEC.

There was no evidence of physical damage observed as a result of the stresses of these events. All electrical performance data was obtained and retained by Electro-Mechanics personnel. See Appendix E for Test Response Spectra and Appendix F for Equipment Response Spectra. Note: Typical OBE response data is presented in these appendices and response data not shown was verified to be consistent with those presented.

4.7 SEISMIC RANDOM EVENT TESTS - PHASE II

BIAXIAL PAIR NO. 2
OUT-OF-PHASE

RUN NO.	EVENT	DURATION
19	OBE	30 SEC.
20	OBE	30 SEC.
21	OBE	30 SEC.
22	OBE	30 SEC.
23	OBE	30 SEC.
24	SSE	30 SEC.

There was no evidence of physical damage observed as a result of the stresses of these events. All electrical performance data was obtained and retained by Electro-Mechanics personnel. See Appendix E for Test Response Spectra and Appendix F for Equipment Response Spectra. Note: Typical OBE response data is presented in these appendices and response data not shown was verified to be consistent with those presented.



4.8 POST-TEST INSPECTION

The following information was observed and recorded during the Post-Test Inspection.

Visual Inspection - There was no evidence of physical damage observed as a result of the stresses of this Qualification test program.

Electrical Tests - All electrical performance data was obtained and retained by Electro-Mechanics personnel.

5.0 SUMMARY OF STRUCTURAL CONDITION

There was no evidence of physical damage observed as a result of the stresses of this test program.

6.0 RECOMMENDATIONS

None, data merely submitted.

7.0 CONCLUSIONS

It is the function of AMERICAN ENVIRONMENTS COMPANY, INC., to report the test data as observed. Final evaluation of the test results shall be accomplished by Electro-Mechanics Incorporated.





FIGURES

PAGE 14

APPENDIX A

FIGURES

FOR

ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




FIGURE 1 - HORIZONTAL & VERTICAL REQUIRED RESPONSE SPECTRA (OBE&SSE)
1.0 % OF CRITICAL DAMPING




FIGURES



PAGE 16

FIGURE 2


BIAXIAL PAIR TWO




IN-PHASE





OUT-OF-PHASE




BIAXIAL PAIR ONE




IN-PHASE



OUT-OF-PHASE







APPENDIX B

STRAIN GAUGE RECORDINGS & STRESS CALCULATIONS

FOR

ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2




TABLE I
STRAIN GAUGE MOUNTING LOCATIONS


Gauge Number	Motion Axis Monitored	Location
1	Vertical	Inside - Middle Right Side of Drawer
2	Horizontal (F/B)	




STRAIN GAUGE RECORDINGS

PAGE 19

BIAXIAL PAIR NO. 1 IN-PHASE



BIAXIAL PAIR NO. 1 OUT-OF-PHASE





STRAIN GAUGE RECORDINGS
BIAXIAL PAIR NO. 2 IN-PHASE

PAGE 20

CH #1

25mm/sec

ELECTRO MECHANICS
EX CORE SAFETY CHANNEL

3/25/82

SSE #18 B.P.2 IN-PHASE

100 μ "/IN BOTH CHANNEL

CH #2

BIAXIAL PAIR NO. 2 OUT-OF-PHASE

CH #1

5 μ "/IN

25mm/sec

ELECTRO MECHANICS
EX CORE SAFETY CHANNEL

3/25/82

SSE #24 B.P.2 OUT-OF-PHASE

100 μ "/IN

CH #2

CALCULATION I

The maximum observed strain for the Biaxial Pair No. 1 (In-Phase) Test (SSE #6) was 2.25 micro-inches/inch, peak.

The maximum observed strain for the Biaxial Pair No. 1 (Out-of-Phase) test (SSE #12) was 10 micro-inches/inch, peak.

The maximum observed strain for the Biaxial Pair No. 2 (In-Phase) Test (SSE #18) was 18 micro-inches/inch, peak.

The maximum observed strain for the Biaxial Pair No. 2 (Out-of-Phase) test (SSE #24) was 5.1 micro-inches/inch, peak.

$$\Delta L/L = e ; S = E \cdot e$$

Where: ΔL = Change in length of gauge

L = Length of gauge

e = Apparent strain

E = Young's modulus (30×10^6 steel)

S = Apparent stress (psi)

For SSE #6, Biaxial Pair No. 1 - In-Phase:

$$\Delta L/L (\text{peak}) = 2.25 \times 10^{-6} \text{ inches/inch}$$

$$S = 30 \times 10^6 \times 2.25 \times 10^{-6}$$

$$S = 67.5 \text{ psi}$$

For SSE #12, Biaxial Pair No. 1 - Out-of-Phase:

$$\Delta L/L (\text{peak}) = 10.0 \times 10^{-6} \text{ inches/inch}$$

$$S = 30 \times 10^6 \times 10.0 \times 10^{-6}$$

$$S = 300 \text{ psi}$$

For SSE #18, Biaxial Pair No. 2 - In-Phase:

$$\Delta L/L (\text{peak}) = 18.0 \times 10^{-6} \text{ inches/inch}$$

$$S = 30 \times 10^6 \times 18.0 \times 10^{-6}$$

$$S = 540 \text{ psi}$$

For SSE #24, Biaxial Pair No. 2 - Out-of-Phase:

$$\Delta L/L (\text{peak}) = 5.1 \times 10^{-6} \text{ inches/inch}$$

$$S = 30 \times 10^6 \times 5.1 \times 10^{-6}$$

$$S = 153 \text{ psi}$$





APPENDIX C

ZPA TEST DATA & DEFLECTION CALCULATIONS

FOR

ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2





TABLE I
ACCELEROMETER MOUNTING LOCATIONS

Accelerometer Number	Motion Axis Monitored	Location
1	Horizontal	Control - on Seismic Table
2	Vertical	Control - on Seismic Table
3	Vertical	Adjacent to the Power Supply
4	Horizontal	Center of Card Cage
5	Vertical	
6	Horizontal	Upper Front Left Corner of the Specimen
7	Vertical	
8	Vertical	Upper Rear Left Corner of the Specimen

ZPA TEST DATA

PAGE 24

RECORDED ZPA VALUES
BIAXIAL PAIR NO. 1 IN-PHASE
RUN - SSE NUMBER 6

Accelerometer Number	Value (g)
1	2.57 - Horizontal Control
2	2.23 - Vertical Control
3	2.84
4	2.68
5	2.47
6	2.75
7	2.27
8	2.32

RECORDED ZPA VALUES
BIAXIAL PAIR NO. 1 OUT-OF-PHASE
RUN - SSE NUMBER 12

Accelerometer Number	Value (g)
1	2.62 - Horizontal Control
2	2.47 - Vertical Control
3	2.85
4	2.73
5	2.52
6	2.72
7	2.51
8	2.63

STR-52781-2



RECORDED ZPA VALUES
BIAXIAL PAIR NO. 2 IN-PHASE
RUN - SSE NUMBER 18

Accelerometer Number	Value (g)
1	2.51 - Horizontal Control
2	2.44 - Vertical Control
3	2.78
4	2.65
5	2.47
6	2.63
7	2.53
8	2.76

RECORDED ZPA VALUES
BIAXIAL PAIR NO. 2 OUT-OF-PHASE
RUN - SSE NUMBER 24

Accelerometer Number	Value (g)
1	2.59 - Horizontal Control
2	2.45 - Vertical Control
3	2.83
4	2.72
5	2.52
6	2.71
7	2.65
8	2.51

CALCULATION II

The maximum deflection of the specimen exterior relative to the mounting base was calculated as follows:

$$d = g / 0.1022 f^2$$

Where:

d = Single amplitude deflection
f = lowest resonance frequency of specimen structure
g = highest measured acceleration (ZPA value of response spectra) from accelerometers selected to represent maximum deflection of cabinet exterior (doors not applicable).

For SSE Number 6:

Biaxial Pair No. 1 In-Phase

$$d = 2.84 / 0.1022 * (15.5)^2 = 0.116 \text{ inches}$$

For SSE Number 12:

Biaxial Pair No. 1 Out-of-Phase

$$d = 2.85 / 0.1022 * (15.5)^2 = 0.116 \text{ inches}$$

For SSE Number 18:

Biaxial Pair No. 2 In-Phase

$$d = 2.78 / 0.1022 * (20)^2 = 0.068 \text{ inches}$$

For SSE Number 24:

Biaxial Pair No. 2 Out-of-Phase

$$d = 2.83 / 0.1022 * (20)^2 = 0.069 \text{ inches}$$

APPENDIX D

TRANSMISSIBILITY DATA PLOTS

FOR

ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2





TABLE I
ACCELEROMETER MOUNTING LOCATIONS


Accelerometer Number	Motion Axis Monitored	Location
1	Horizontal	Control - on Seismic Table
2	Vertical	Control - on Seismic Table
3	Vertical	Adjacent to the Power Supply
4	Horizontal	Center of Card Cage
5	Vertical	
6	Horizontal	Upper Front Left Corner of the Specimen
7	Vertical	
8	Vertical	Upper Rear Left Corner of the Specimen



TRANSFERENCE FUNCTIONS
BIAXIAL PAIR NO. 1 (FRONT TO BACK)
CHANNEL NO. 3




TRANSFER FUNCTIONS :
 BIAxIAL PAIR NO. 3 (FRONT TO BACK)
 CHANNEL NO. 4




STR-52781-2

PAGE 30

TRANSFER FUNCTIONS
BIAXIAL PAIR NO. 5 (FRONT TO BACK)
CHANNEL NO. 5




TRANSFER FUNCTIONS
BIAXIAL PAIR NO. 6 (FRONT TO BACK)
CHANNEL NO. 6






TRANSF. FUNCTIONS
BIAXIAL PAIR NO. (FRONT TO BACK)
CHANNEL NO. 7






TRANSFER FUNCTIONS
BIAXIAL PAIR NO. 2 (SIDE TO SIDE)
CHANNEL NO. 3






TRANSFER FUNCTIONS
BIAXIAL PAIR NO. C (SIDE TO SIDE)
CHANNEL NO. 4




TRANSFORM FUNCTIONS
BIAXIAL PAIR NO. 5 (SIDE TO SIDE)
CHANNEL NO. 5






TRANSFORMATIONS
BIAxIAL PAIR NO. 2 (SIDE TO SIDE)
CHANNEL NO. 6






TRANSFER FUNCTIONS
BIAXIAL PAIR NO. 2 (SIDE TO SIDE)
CHANNEL NO. 7



TRANSFORMATIONS
BIAXIAL PAIR NO. 2 (SIDE TO SIDE)
CHANNEL NO. 8



APPENDIX E

TEST RESPONSE SPECTRA

FOR

ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

NOTE: Typical OBE Response Data is presented in this Appendix.
The OBE Response Data not shown was verified to be consistent
with the response data presented.




TABLE I


ACCELEROMETER MOUNTING LOCATIONS

Accelerometer Number	Motion Axis Monitored	Location
1	Horizontal	Control - on Seismic Table
2	Vertical	Control - on Seismic Table
3	Vertical	Adjacent to the Power Supply
4	Horizontal	Center of Card Cage
5	Vertical	
6	Horizontal	Upper Front Left Corner of the Specimen
7	Vertical	
8	Vertical	Upper Rear Left Corner of the Specimen

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 24 TRS - VERTICAL (BIAXIAL PAIR NO. 2 OUT-OF-PHASE) SSE
CHANNEL NUMBER.. 2 1.0 X OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 44

+ RUN NUMBER.. 24 TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 OUT-OF-PHASE) SSE
CHAN' NUMBER.. 1 1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200
FREQUENCY (Hz)

TRS

RRS

+ RUN NUMBER.. 23 TRS - VERTICAL (BIAxIAL PAIR NO. 2 OUT-OF-PHASE) OBE
CHANNEL NUMBER.. 2 1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 45

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2


PAGE 46

+ RUN NUMBER.. 23 TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 OUT-OF-PHASE) OBE
 CHAN# NUMBER.. 1 1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 19 TRS - VERTICAL (BIAXIAL PAIR NO. 2 OUT-OF-PHASE) OBE
CHANNEL NUMBER.. 2 1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 47

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 19 TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 OUT-OF-PHASE) OBE
 CHAN. NUMBER.. 1 1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

TRS

RRS

RUN NUMBER.. 18

CHANNEL NUMBER.. 2

TRS - VERTICAL (BIAXIAL PAIR NO. 2 IN-PHASE) SSE

1.0 % OF CRITICAL DAMPING

STR-52781-2


PAGE 49



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




STR-52781-2

PAGE 50


+ RUN NUMBER.. 18
CHANL NUMBER.. 1

TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 IN-PHASE) SSE
1.0 % OF CRITICAL DAMPING

RESPONSE
ACCELERATION
G

+ RUN NUMBER.. 17
CHANNEL NUMBER.. 2

TRS - VERTICAL (BIAXIAL PAIR NO. 2 IN-PHASE) OBE
1.0 % OF CRITICAL DAMPING


RESPONSE
ACCELERATION
G

+ RUN NUMBER.. 17 TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 IN-PHASE) OBE
CHANNEL NUMBER.. 1 1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 53

+ RUN NUMBER.. 13
CHANNEL NUMBER.. 2


TRS - VERTICAL (BIAXIAL PAIR NO. 2 IN-PHASE) OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 13 TRS - HORIZONTAL (BIAXIAL PAIR NO. 2 IN-PHASE) OBE
 CHANL NUMBER.. 1 1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 54



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

TRS

RRS

+ RUN NUMBER.. 12 TRS - VERTICAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) SSE
CHANNEL NUMBER.. 2 1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 55

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 56

+ RUN NUMBER.. 12 TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) SSE
 CHAN1 NUMBER.. 1 1.0 % OF CRITICAL DAMPING




R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1



STR-52781-2

PAGE 57

+ RUN NUMBER.. 11 TRS - VERTICAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) OBE
CHANNEL NUMBER.. 2 1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200
FREQUENCY (Hz)

TRS

RBS

RUN NUMBER.. 11 TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) OBE
CHANNEL NUMBER.. 1 1.0 % OF CRITICAL DAMPING

STR-52781-2


PAGE 58



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 7 TRS - VERTICAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) OBE
CHANNEL NUMBER.. 2 1.0 % OF CRITICAL DAMPING


R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10


1



STR-52781-2

PAGE 60

+ RUN NUMBER.. 7 TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 OUT-OF-PHASE) OBE
 CHANN. NUMBER.. 1 1.00 % OF CRITICAL DAMPING

RESPONSE
ACCELERATION
G

+ RUN NUMBER.. 6
CHANNEL NUMBER.. 2

TRS - VERTICAL (BIAXIAL PAIR NO. 1 IN-PHASE) SSE
1.0 % OF CRITICAL DAMPING

STR-52781-2


PAGE 61



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 6
CHAN# NUMBER.. 1

TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 IN-PHASE) SSE
1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 62



STR-52781-2

PAGE 63


+ RUN NUMBER.. 5
CHANNEL NUMBER.. 2

TRS - VERTICAL (BIAXIAL PAIR NO. 1 IN-PHASE) OBE
1.00 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 5
CHANNEL NUMBER.. 1

TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 IN-PHASE) OBE
1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 64


R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1



+ RUN NUMBER.. 1
CHANNEL NUMBER.. 2

TRS - VERTICAL (BIAXIAL PAIR NO. 1 IN-PHASE) OBE
1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 65



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

+ RUN NUMBER.. 1
CIANT NUMBER.. 1


TRS - HORIZONTAL (BIAXIAL PAIR NO. 1 IN-PHASE) OBE
1.0 % OF CRITICAL DAMPING

TRS

RRS

STR-52781-2

PAGE 66



APPENDIX F
EQUIPMENT RESPONSE SPECTRA
FOR
ELECTRO-MECHANICS INC.

EX-CORE-SAFETY CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2





TABLE I
ACCELEROMETER MOUNTING LOCATIONS

Accelerometer Number	Motion Axis Monitored	Location
1	Horizontal	Control - on Seismic Table
2	Vertical	Control - on Seismic Table
3	Vertical	Adjacent to the Power Supply
4	Horizontal	Center of Card Cage
5	Vertical	
6	Horizontal	Upper Front Left Corner of the Specimen
7	Vertical	
8	Vertical	Upper Rear Left Corner of the Specimen

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 1
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

ERS

+ RUN NUMBER.. 1
CHANNEL NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

STR-52781-2


PAGE 70



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 1
CHANNEL NUMBER.. 5


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

RUN NUMBER.. 1
CHANNEL NUMBER.. 6


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 1
CHANNEL NUMBER.. 7


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

FREQUENCY (Hz)


+ RUN NUMBER.. 1
CHAN/ NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 75

+ RUN NUMBER.. 5
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING


R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1



ERS

+ RUN NUMBER.. 5
CHANN NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

RESPONSE
ACCELERATION
G

ERS

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

+ RUN NUMBER.. 5
CHANNEL NUMBER.. 5EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 77

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 5
CHANN. NUMBER.. 6

EQUIPMENT RESPONSE SPECTRUM - OBE.
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)


+ RUN NUMBER.. 5
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

ERS

STR-52781-2

PAGE 79






R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 80

+ RUN NUMBER.. 5
CHANN NUMBER.. 8


EQUIPMENT RESPONSE SPECTRUM - OBE.
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 8
CHANNEL NUMBER.. 3


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 82

+ RUN NUMBER.. 8
CHANN NUMBER.. 4


EQUIPMENT RESPONSE SPECTRUM - SSE.
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 83

RUN NUMBER.. 8
CHANNEL NUMBER.. 5

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

RUN NUMBER.. 8
CHANNEL NUMBER.. 8

ERS

STR-52781-2


PAGE 84



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 85

RUN NUMBER.. 8
CHANNEL NUMBER.. 7


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 86

+ RUN NUMBER.. 8
CHANNEL NUMBER.. 8


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 87

+ RUN NUMBER.. 7
CHANNEL NUMBER.. 3


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 88

RUN NUMBER.. 7
CHANN NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

100

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE

1.0 % OF CRITICAL DAMPING

RUN NUMBER.. 7

CHANNEL NUMBER.. 5

ERS


STR-52781-2

PAGE 89

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 90

RUN NUMBER.. 7
CHANNEL NUMBER.. 6


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 X OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 91

RUN NUMBER.. 7
CHANNEL NUMBER.. 7


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 92


RUN NUMBER.. 7
CHANN NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 93


RUN NUMBER.. 11
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - OBE.
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 94

+ RUN NUMBER.. 11
CHANL NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

100

10

1

1.0

2.0

4.0

8.0

16

32

63

125

200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE.


1.0 % OF CRITICAL DAMPING


+ RUN NUMBER.. 11
CHANNEL NUMBER.. 5

STR-52781-2

PAGE 95

ERS





+ RUN NUMBER.. 11
CHANN NUMBER.. 8


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



RUN NUMBER.. 11
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 97

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 98

+ RUN NUMBER.. 11
CHANNEL NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - SSE
1.00 % OF CRITICAL DAMPING

RUN NUMBER.. 12
CHANNEL NUMBER.. 3

ERS


STR-52781-2

PAGE 99

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 100


+ RUN NUMBER.. 12
CHANNEL NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 101


+ RUN NUMBER.. 12
CHANNEL NUMBER.. 5

EQUIPMENT RESPONSE SPECTRUM - SSE
1.00 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 12
CHANN. NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

STR-52781-2

PAGE 103

+ RUN NUMBER.. 12
CHANNEL NUMBER.. 7


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 12
CHANL NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 13
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE

1.0 % OF CRITICAL DAMPING

+ RUN NUMBER.. 13
CHANNEL NUMBER.. 4

ERS


STR-52781-2

PAGE 106

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER..*13
CHANNEL NUMBER.. 5

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

ERS

+ RUN NUMBER.. 13
CHANN NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 108

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 109

RUN NUMBER.. 13
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

ERS

+ RUN NUMBER.. 13
CHANNEL NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 110

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

ERS

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

+ RUN NUMBER.. 17
CHANNEL NUMBER.. 3

STR-52781-2

PAGE 111





R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

RUN NUMBER.. 17
CHANNEL NUMBER.. 4

ERS

RESPONSE
ACCELERATION
G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200
FREQUENCY (Hz)

ERS

+ RUN NUMBER.. 17
CHANNEL NUMBER.. 5EQUIPMENT RESPONSE SPECTRUM - OBE.
1.0 % OF CRITICAL DAMPING

STR-52781-2

PAGE 113

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200
FREQUENCY (Hz)

ERS

+ RUN NUMBER.. 17
CHANN: NUMBER.. 6

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

STR-52781-2


PAGE 114



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

STR-52781-2

PAGE 115

+ RUN NUMBER.. 17
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)


+ RUN NUMBER.. 17
CHANN NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

ERS

STR-52781-2


PAGE 116



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

FREQUENCY (Hz)

RUN NUMBER.. 18

CHANNEL NUMBER.. 3


EQUIPMENT RESPONSE SPECTRUM - SSE

1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 18
CHANN NUMBER.. 4

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 X OF ()TICAL DAMPING

Step	Measurement/Observation	Acceptable Range	Actual
4.4.12.2 (cont.)	Test Set Position 8		
	Input Voltage -0.924 VDC	6.000±0.300 VDC	<u>6.002</u>
	Input Voltage -1.078 VDC	7.000±0.300 VDC	<u>7.001</u>
	Input Voltage -1.232 VDC	8.000±0.300 VDC	<u>8.002</u>
	Input Voltage -1.386 VDC	9.000±0.300 VDC	<u>9.004</u>
	Input Voltage -1.540 VDC	10.000±0.300 VDC	<u>10.001</u>
			Pass Fail
4.5.1.2	Log Indicator	Lit	<u>✓</u>
	Test Set "Log" N.O. Indicator	Lit	<u>✓</u>
			Actual
10 4.5.1.2.1	Test Set Position 1	3.700±0.100 VDC	<u>3.650</u>
	Log Power Meter	10 ⁻⁴ %	<u>10⁻⁴%</u>
4.5.1.3	Test Set Position 1	0.100±0.050 greater than step 4.5.1.2.1	<u>3.711</u>
4.5.1.3-1	Log Indicator	Not Lit	<u>✓</u>
			Pass Fail
4.5.2.1	Log Trouble Indicator	Lit	<u>✓</u>
	Power Supply	Approx. 650V	<u>✓</u>
4.5.2.1.1	Test Set "WRT" N.C. Indicator	Lit	<u>✓</u>
	Test Set "LT+WRT" Indicator	Not Lit	<u>✓</u>
4.5.2.2	Log Trouble	Not Lit	<u>✓</u>
4.5.2.3	Remove Board J18	Log Trouble Lit	<u>✓</u>

Step	Measurement/Observation	Acceptable Range	Pass.	Fail
4.5.2.3.1	Replace Board J18	Log Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.2.3.2	Remove Board J20	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J20:	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J21	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J21	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J22	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J22	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J27	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J27	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J28	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J28	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J31	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J31	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.2.4	Log Calibrate	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.2.4.1	Log Calibrate	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.2.4.2	Log Trip Test	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Log Trip Test	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Rate Trip Test	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Rate Trip Test	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.1	Linear Trouble Indicator	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Power Supply	Approx. 650V	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Step	Measurement/Observation	Acceptable Range	Pass	Fail
4.5.3.1.1	Test Set "LT" N.C. Indicators	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Test Set "LT+WRT" N.C. Indicators	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.2	Linear Trouble Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.3	Remove Board J26	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.3.1	Replace Board J26	Linear Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.3.2	Remove Board J24	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J24	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J26	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J26	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J27	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J27	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Remove Board J29	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Replace Board J29	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.4	Linear Calibrate	Linear Trouble Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.4.1	Linear Calibrate	Linear Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.3.4.2	Linear Trip Test Upper	Linear Trouble Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Linear Trip Test Upper	Linear Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Linear Trip Test Lower	Linear Trouble Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Linear Trip Test Lower	Linear Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>



Step	Measurement/Observation	Acceptable Range	Pass	Fail
4.5.3.4.2 (cont.)	Linear Trip Test Low Power	Linear Trouble Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Linear Trip Test Low Power	Linear Trouble Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.4.2	ZPMB Indicator	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Output Low Power Position	2.5±0.100 VDC	Actual <u>2.534</u>	
			Pass	Fail
4.5.4.2.1	Test Set Low Power N.O. Indicators	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			Actual	
4.5.4.2.2	Output Low Power Position	0.100±0.050 greater than step 4.5.4.2	<u>2.671</u>	
			Pass	Fail
4.5.4.2.3	ZPMB Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			Actual	
4.5.5.1	Output Cal Avg Position	0.750±0.100 VDC	<u>0.743</u>	
			Pass	Fail
4.5.5.1.1	Test Set Linear N.C. Indicators	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			Actual	
	Linear Power Meter	15±2%	<u>15%</u>	
4.5.5.2	Output Cal Avg Position	0.100±0.050 less than step 4.5.5.1	<u>0.621</u>	

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

+ RUN NUMBER.. 18
CHANNEL NUMBER.. 5

ERS

STR-52781-2


PAGE 119



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS


+ RUN NUMBER.. 18
CHANN NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 18
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 18
CHANN · NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF (TICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

RUN NUMBER.. 19
CHANNEL NUMBER.. 3

ERS


STR-52781-2

PAGE 123



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

STR-52781-2

PAGE 125


+ RUN NUMBER.. 19
CHANNEL NUMBER.. 5

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 19
CHANN. NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

100

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - OBE


1.0 % OF CRITICAL DAMPING

ERS

STR-52781-2

PAGE 127


+ RUN NUMBER.. 19
CHANNEL NUMBER.. 7



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 18
CHANNEL NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 23
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - OBE.
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

+ RUN NUMBER.. 23
CHANN NUMBER.. 4

ERS

STR-52781-2


PAGE 130



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G




+ RUN NUMBER.. 23
CHANNEL NUMBER.. 5

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 132


+ RUN NUMBER.. 23
CHANN NUMBER.. 6

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 133

+ RUN NUMBER.. 23

CHANNEL NUMBER.. 7


EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 23
CHANNEL NUMBER.. 8

EQUIPMENT RESPONSE SPECTRUM - OBE
1.0 % OF CRITICAL DAMPING


STR-52781-2

PAGE 134

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



STR-52781-2

PAGE 135


RUN NUMBER.. 24
CHANNEL NUMBER.. 3

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

+ RUN NUMBER.. 24
CHANN NUMBER.. 4


EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G



ERS

STR-52781-2

PAGE 137


+ RUN NUMBER., 24
CHANNEL NUMBER., 5

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E


A
C
C
E
L
E
R
A
T
I
O
N

G



+ RUN NUMBER.. 24
CHANN. NUMBER.. 6

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING



+ RUN NUMBER.. 24
CHANNEL NUMBER.. 7

EQUIPMENT RESPONSE SPECTRUM - SSE
1.0 % OF CRITICAL DAMPING

R
E
S
P
O
N
S
E

A
C
C
E
L
E
R
A
T
I
O
N

G

10

1

1.0 2.0 4.0 8.0 16 32 63 125 200

FREQUENCY (Hz)

EQUIPMENT RESPONSE SPECTRUM - SSE

1.0 % OF CRITICAL DAMPING

ERS

STR-52781-2

PAGE 140

+ RUN NUMBER.. 24
: CHANNI NUMBER.. 8

APPENDIX G

PHOTOGRAPHS

FOR

ELECTRO-MECHANICS INC.

EX-CORE-~~SAFETY~~ CHANNEL NEUTRON FLUX SIGNAL
PROCESSING ELECTRONICS

STR-52781-2



ELECTRO-MECHANICS, INC.
New Britain, Connecticut
REJECTION OR REMARKS SHEET

Description EX-CORE SAFETY CHANNEL
Part No. 39500
Tested Per TP. 6764-2 F

Job No. 6764
WO or PDR No. 13036
Serial No. E 39131


Ref. TR Sht.	REJECTIONS OR REMARKS	Entered	Retest		
		By/Date	Acc	Rej	By/Date
	<p>REV F CHANGES WERE MADE IN THE FIELD DURING THE SEISMIC TEST ON 3.25.82 THESE CHANGES WERE THEN DOCUMENTED ON 4/15/82</p> <p>THIS UNIT MEETS OR EXCEEDS THE CHANGES OF REV F</p>	<p>BN 6.9.82</p>	✓		








TEST SET UP
BIAXIAL PAIR NO. 1
IN-PHASE

TEST SET UP
BIAXIAL PAIR NO. 1
OUT-OF-PHASE





TEST SET UP
BIAXIAL PAIR NO. 2
IN-PHASE



TEST SET UP
BIAXIAL PAIR NO. 2
OUT-OF-PHASE






TABLE I


ACCELEROMETER MOUNTING LOCATIONS

Accelerometer Number	Motion Axis Monitored	Location
1	Horizontal	Control - on Seismic Table
2	Vertical	Control - on Seismic Table
3	Vertical	Adjacent to the Power Supply
4	Horizontal	Center of Card Cage
5	Vertical	
6	Horizontal	Upper Front Left Corner of the Specimen
7	Vertical	
8	Vertical	Upper Rear Left Corner of the Specimen

STRAIN GAUGE MOUNTING LOCATIONS

Gauge Number	Motion Axis Monitored	Location
1	Vertical	Inside - Middle Right Side of Drawer
2	Horizontal (F/B)	


AE



CONTROL
ACCELEROMETERS
CHANNELS 1 & 2




RESPONSE
ACCELEROMETER
CHANNEL 3



RESPONSE
ACCELEROMETERS
CHANNELS 4 & 5


RESPONSE
ACCELEROMETERS
CHANNELS 6 & 7



AE


PHOTOGRAPHS

PAGE 147



RESPONSE
ACCELEROMETER
CHANNEL 8

STRAIN GAUGE
LOCATIONS
CHANNELS 1 & 2





Appendix B

DRIG IN
ETR 6764

AFTER ENVIRONMENTAL BEFORE SEISMIC

ELECTRO-MECHANICS, INC.
New Britain, Connecticut

Functional Test

Test Record TR 6764-2

Ex-Core Safety Channel
Neutron Flux Signal Processing
Description Electronics Channel Part No. 39500
Serial No. E 39131 Job No. 6764
Tested Per TP 6764-2 Rev. GF W.O. or ~~FOR~~ No. 13036
Tested by: Jack Lerner Date 3-18-82 Acc ☒ Rej. ☐
Test Record Review by: H. A. Polozie Date 3-27-82 Acc ☒ Rej. ☐
QA Test Review by: Ray Mahr Date 6-9-82 Acc ☒ Rej. ☐

Test Equipment Used: DATA PRECISION TEP 2393N 10-31-82
KE 2VM TEP 2313N 8-8-82
WAVETEK S/G TEP 2327N 12-14-82
DIGITEC C/V TEP 2280N 6-30-82
BELKMAN 3020 TEP 2304N 4-21-82
TEST SET TE 352N DO CAL RE
TEKTRONICS TEP 2409N 4-15-82

Revision Status of Sheets

Page	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	1A
Rev.	G	F	E	D	C	C	G	G	E	C	G	G															G

	Engineer		QA		ECO #	
	Date	Initial	Date	Initial	Date	ECO #
Original Issue	4-16-81	P. J. K.	4/11/81	P. J. K.	—	—
Rev. A	4-28-81	P. J. K.	4-29-81	P. J. K.	4-28-81	13119
Rev. B	6-5-81	P. J. K.	6/5/81	P. J. K.	5/29/81	13192
Rev. C	8-24-81	P. J. K.	8-26-81	P. J. K.	8/24/81	13606
Rev. D	10-23-81	P. J. K.	10-26-81	P. J. K.	10/23/81	13871

Rev. G
TR 6764-2
Page 1 cont. on 1A

Revisions Continued

	Engineer		OA		ECO #	
	Date	Initial	Date	Initial	Date	ECO #
Rev. E	2-16-82	WAP	2-17-82	ECW	2-15-82	14246
Rev. F	3-8-82	WAP	3/8/82	WAP	3-1-82	14298
Rev. G	4-14-82	WAP	4/15/82	WAP	4-14-82	14448
Rev. H						
Rev. J						

TEST RECORD

Step	Measurement/Observation	Acceptable Range	Actual
4.1.2.1	Output Select +15 Position	+15V±0.250 VDC	<u>14.974</u>
4.1.3.1	Output Select -15 Position	-15V±0.250 VDC	<u>-15.012</u>
4.1.4.1	Output Select +5 Position	+5V±0.250 VDC	<u>5.023</u>
4.1.5.1	Output Select Preamp +15 Position	+15V±0.250 VDC	<u>15.040</u>
4.1.6.1	Output Select Preamp -15 Position	-15V±0.250 VDC	<u>-14.990</u>
4.1.7.1	High Voltage Meter HV Log	800±20 VDC	<u>800</u>
4.1.8.1	High Voltage Meter HV Lin	800±20 VDC	<u>800</u>
4.2.1.1	Log Power Meter	Approx. $10^{-8}\%$	<u>$1 \times 10^{-8}\%$</u>
4.2.2.1	Test Set Position 1	-0.301±0.300 VDC	<u>-0.259</u>
4.2.3.1	Log Power Meter LCR-1	Between 1.3×10^{-5} and 3.3×10^{-5}	<u>2.5×10^{-5}</u>
4.2.3.2	Test Set Position 1	+3.020±0.300 VDC	<u>3.016</u>
4.2.4.1	Log Power Meter LCR-2	Between 5.9×10^{-3} and 1.9×10^{-2}	<u>1×10^{-2}</u>
4.2.4.2	Test Set Position 1	5.719±0.300 VDC	<u>5.678</u>
4.2.5.1	Log Power Meter LCR-3	Between 2.6×10^{-2} and 6.6×10^{-2}	<u>6×10^{-2}</u>
4.2.5.2	Test Set Position 1	6.321±0.300 VDC	<u>6.428</u>
4.2.6.1	Log Power Meter MSV-4	Between 2.6×10^{-2} and 6.6×10^{-2}	<u>6×10^{-2}</u>
4.2.6.2	Test Set Position 1	6.321±0.300 VDC	<u>6.454</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.2.7.1	Log Power Meter MSV-5	Between 0.26 and 0.66	<u>0.50</u>
4.2.7.2	Test Set Position 1	7.321±0.300 VDC	<u>7.273</u>
4.2.8.1	Log Power Meter MSV-6	Between 2.6 and 6.6	<u>4.0</u>
4.2.8.2	Test Set Position 1	8.321±0.300 VDC	<u>8.269</u>
4.2.10.1	Log Monitor	1.00±0.10µsec	<u>1.00µs</u>
4.2.11.1	Scaler	0.50±0.50µsec	<u>0.50µs</u>
4.2.12.1	Test Set Position 2	5.719±0.300 VDC	<u>5.681</u>
4.2.13.1	Test Set Position 3	5.719±0.300 VDC	<u>5.695</u>
4.2.14.1	Output Log Position	5.719±0.300 VDC	<u>5.694</u>
4.2.15.1	Test Set Position 1		
	Log Power Meter 2x10 ⁻⁸	0.000±0.300 VDC	<u>-0.037</u>
	Log Power Meter 2x10 ⁻⁷	1.000±0.300 VDC	<u>0.902</u>
	Log Power Meter 2x10 ⁻⁶	2.000±0.300 VDC	<u>1.918</u>
	Log Power Meter 2x10 ⁻⁵	3.000±0.300 VDC	<u>2.922</u>
	Log Power Meter 2x10 ⁻⁴	4.000±0.300 VDC	<u>3.934</u>
	Log Power Meter 2x10 ⁻³	5.000±0.300 VDC	<u>4.914</u>
	Log Power Meter 2x10 ⁻²	6.000±0.300 VDC	<u>5.912</u>
	Log Power Meter 2x10 ⁻¹	7.000±0.300 VDC	<u>7.011</u>
	Log Power Meter 2	8.000±0.300 VDC	<u>8.028</u>
	Log Power Meter 20	9.000±0.300 VDC	<u>8.976</u>
	Log Power Meter 200	10.000±0.300 VDC	<u>10.029</u>

	Measurement/Observation	Acceptable Range	Actual
4.3.2.1	Rate Meter	0 ± 0.2 DPM	<u>0.0</u>
4.3.2.2	Test Set Position 5	1.250 ± 0.050 VDC	<u>1.252</u>
4.3.3.1	Rate Meter	0 ± 0.2 DPM	<u>0.0</u>
4.3.3.2	Test Set Position 5	1.250 ± 0.050 VDC	<u>1.245</u>
4.3.4.1	Rate Meter	7 ± 0.2 DPM	<u>7.0</u>
4.3.4.2	Test Set Position 5	10.000 ± 0.050 VDC	<u>10.029</u>
4.3.5.1	Test Set Position 5		
	Rate Meter 1	2.500 ± 0.250 VDC	<u>2.508</u>
	Rate Meter 2	3.750 ± 0.250 VDC	<u>3.738</u>
	Rate Meter 3	5.000 ± 0.250 VDC	<u>5.026</u>
	Rate Meter 4	6.250 ± 0.250 VDC	<u>6.263</u>
	Rate Meter 5	7.500 ± 0.250 VDC	<u>7.559</u>
	Rate Meter 6	8.750 ± 0.250 VDC	<u>8.755</u>
	Rate Meter 7	10.000 ± 0.250 VDC	<u>10.015</u>
4.3.6.1	Test Set Position 4	1.250 ± 0.250 VDC	<u>1.262</u>
4.3.7.2	Output Rate Position	1.250 ± 0.250 VDC	<u>1.270</u>
4.4.1.3	Linear Power Meter	Approx. 0%	<u>0%</u>
4.4.2.1	Output Cal Avg Position	0.000 ± 0.300 VDC	<u>0.012</u>
4.4.3.1	Linear Power Meter	$200 \pm 2\%$	<u>200%</u>
4.4.3.2	Output Cal Avg Position	10.000 ± 0.300 VDC	<u>10.029</u>
4.4.4.1	Linear Power Meter	$2 \pm 2\%$	<u>2%</u>

p	Measurement/Observation	Acceptable Range	Actual
4.4.4.2	Output Cal Avg Position	0.100 ± 0.300 VDC	<u>0.109</u>
4.4.4.3	Output Low Power Position	5.000 ± 0.300 VDC	<u>5.031</u>
4.4.5.1	Linear Power Meter	Approx. 0%	<u>0%</u>
4.4.5.2	Output Cal Avg Position	0.000 ± 0.300 VDC	<u>0.010</u>
4.4.6.3	Test Set Position 11	10.000 ± 0.300 VDC	<u>10.040</u>
4.4.6.4	Linear Power Meter	$200 \pm 2\%$	<u>200%</u>
4.4.6.5	Test Set Position 8	10.000 ± 0.300 VDC	<u>10.064</u>
4.4.7.3	Test Set Position 10	10.000 ± 0.300 VDC	<u>10.047</u>
4.4.7.4	Linear Power Meter	$200 \pm 2\%$	<u>200%</u>
4.4.7.5	Test Set Position 8	10.000 ± 0.300 VDC	<u>10.070</u>
4.4.7.6	Test Set Position 8	5.000 ± 0.300 VDC	<u>5.033</u>
4.4.8.4	Test Set Position 12	-1.000 ± 0.300 VDC	<u>-1.013</u>
4.4.8.5	Test Set Position 6	-1.000 ± 0.300 VDC	<u>-1.014</u>
4.4.9.4	Output Cal Avg Position	5.000 ± 0.300 VDC	<u>5.017</u>
4.4.9.6	Test Set Position 7	5.000 ± 0.300 VDC	<u>5.018</u>
4.4.9.7	Test Set Positon 8	5.000 ± 0.300 VDC	<u>5.019</u>
	Test Set Positon 9	5.000 ± 0.300 VDC	<u>5.021</u>
	Test Set Positon 10	5.000 ± 0.300 VDC	<u>5.017</u>
	Test Set Positon 11	5.000 ± 0.300 VDC	<u>5.011</u>
4.4.10.3.1	Output Cal Avg Position	0.100 ± 0.300 VDC	<u>0.099</u>
4.4.10.3.2	Linear Power Meter	$2 \pm 2\%$	<u>2%</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.4.10.3.3	Output Low Power Position	5.0±0.300 VDC	<u>4.851</u>
4.4.10.4	Output Cal Avg Position		
	Linear Power Meter 20%	1.000±0.300 VDC	<u>1.018</u>
	Linear Power Meter 40%	2.000±0.300 VDC	<u>2.006</u>
	Linear Power Meter 60%	3.000±0.300 VDC	<u>3.017</u>
	Linear Power Meter 80%	4.000±0.300 VDC	<u>4.019</u>
	Linear Power Meter 100%	5.000±0.300 VDC	<u>5.003</u>
	Linear Power Meter 120%	6.000±0.300 VDC	<u>6.019</u>
	Linear Power Meter 140%	7.000±0.300 VDC	<u>7.011</u>
	Linear Power Meter 160%	8.000±0.300 VDC	<u>8.013</u>
	Linear Power Meter 180%	9.000±0.300 VDC	<u>9.020</u>
	Linear Power Meter 200%	10.000±0.300 VDC	<u>10.031</u>
4.4.11.2	Test Set Position 10		
	Input Current -0.154ma	1.000±0.300 VDC	<u>0.979</u>
	Input Current -0.308ma	2.000±0.300 VDC	<u>1.981</u>
	Input Current -0.462ma	3.000±0.300 VDC	<u>2.978</u>
	Input Current -0.616ma	4.000±0.300 VDC	<u>3.979</u>
	Input Current -0.770ma	5.000±0.300 VDC	<u>4.982</u>
	Input Current -0.924ma	6.000±0.300 VDC	<u>5.978</u>
	Input Current -1.078ma	7.000±0.300 VDC	<u>6.977</u>
	Input Current -1.232ma	8.000±0.300 VDC	<u>7.979</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.4.11.2 (cont.)	Test Set Position 10		
	Input Current -1.386ma	9.000±0.300 VDC	<u>8.981</u>
	Input Current -1.540ma	10.000±0.300 VDC	<u>9.979</u>
4.4.11.5	Test Set Position 11		
	Input Current -0.154ma	1.000±0.300 VDC	<u>0.976</u>
	Input Current -0.308ma	2.000±0.300 VDC	<u>1.978</u>
	Input Current -0.462ma	3.000±0.300 VDC	<u>2.975</u>
	Input Current -0.616ma	4.000±0.300 VDC	<u>3.976</u>
	Input Current -0.770ma	5.000±0.300 VDC	<u>4.978</u>
	Input Current -0.924ma	6.000±0.300 VDC	<u>5.975</u>
	Input Current -1.078ma	7.000±0.300 VDC	<u>6.974</u>
	Input Current -1.232ma	8.000±0.300 VDC	<u>7.976</u>
	Input Current -1.386ma	9.000±0.300 VDC	<u>8.978</u>
	Input Current -1.540ma	10.000±0.300 VDC	<u>9.975</u>
4.4.12.2	Test Set Position 8		
	Input Voltage -0.154 VDC	1.000±0.300 VDC	<u>1.000</u>
	Input Voltage -0.308 VDC	2.000±0.300 VDC	<u>2.000</u>
	Input Voltage -0.462 VDC	3.000±0.300 VDC	<u>2.995</u>
	Input Voltage -0.616 VDC	4.000±0.300 VDC	<u>3.995</u>
	Input Voltage -0.770 VDC	5.000±0.300 VDC	<u>4.995</u>

Step	Measurement/Observation	Acceptable Range	Actual	Pass	Fail
4.4.12.2 (cont.)	Test Set Position 8				
	Input Voltage -0.924 VDC	6.000±0.300 VDC	<u>5.990</u>		
	Input Voltage -1.078 VDC	7.000±0.300 VDC	<u>6.987</u>		
	Input Voltage -1.232 VDC	8.000±0.300 VDC	<u>7.988</u>		
	Input Voltage -1.386 VDC	9.000±0.300 VDC	<u>8.989</u>		
	Input Voltage -1.540 VDC	10.000±0.300 VDC	<u>9.985</u>		
				Pass	Fail
4.5.1.2	Log Indicator	Lit	<u>/</u>		
	Test Set "Log" -				
	N.O. Indicator	Lit	<u>/</u>		
			Actual		
4.5.1.2.1	Test Set Position 1	3.700±0.100 VDC	<u>3.755</u>		
	Log Power Meter	10 ⁻⁴ %	<u>10⁻⁴ %</u>		
4.5.1.3	Test Set Position 1	0.100±0.050 greater than step 4.5.1.2.1	<u>3.877</u>		
4.5.1.3.1	Log Indicator	Not Lit	<u>/</u>		
				Pass	Fail
4.5.2.1	Log Trouble Indicator	Lit	<u>/</u>		
	Power Supply	Approx. 650V	<u>/</u>		
4.5.2.1.1	Test Set "WRT" N.C. Indicator	Lit	<u>/</u>		
	Test Set "LT+WRT" Indicator	Not Lit	<u>/</u>		
4.5.2.2	Log Trouble	Not Lit	<u>/</u>		
4.5.2.3	Remove Board J18	Log Trouble Lit	<u>/</u>		

Step	Measurement/Observation	Acceptable Range	Pass.	Fail
4.5.2.3.1	Replace Board J18	Log Trouble Not Lit	✓	—
4.5.2.3.2	Remove Board J20	Lit	✓	—
	Replace Board J20	Not Lit	✓	—
	Remove Board J21	Lit	✓	—
	Replace Board J21	Not Lit	✓	—
	Remove Board J22	Lit	✓	—
	Replace Board J22	Not Lit	✓	—
	Remove Board J27	Lit	✓	—
	Replace Board J27	Not Lit	✓	—
	Remove Board J28	Lit	✓	—
	Replace Board J28	Not Lit	✓	—
	Remove Board J31	Lit	✓	—
	Replace Board J31	Not Lit	✓	—
4.5.2.4	Log Calibrate	Lit	✓	—
4.5.2.4.1	Log Calibrate	Not Lit	✓	—
4.5.2.4.2	Log Trip Test	Lit	✓	—
	Log Trip Test	Not Lit	✓	—
	Rate Trip Test	Lit	✓	—
	Rate Trip Test	Not Lit	✓	—
4.5.3.1	Linear Trouble Indicator	Lit	✓	—
	Power Supply	Approx. 650V	✓	—

Step	Measurement/Observation	Acceptable Range	Pass	Fail
4.5.3.1.1	Test Set "LT" N.C. Indicators	Lit	✓	—
	Test Set "LT+WRT" N.C. Indicators	Lit	✓	—
4.5.3.2	Linear Trouble Indicator.	Not Lit	✓	—
4.5.3.3	Remove Board J26	Lit	✓	—
4.5.3.3.1	Replace Board J26	Linear Trouble Not Lit	✓	—
4.5.3.3.2	Remove Board J24	Lit	✓	—
	Replace Board J24	Not Lit	✓	—
	Remove Board J26	Lit	✓	—
	Replace Board J26	Not Lit	✓	—
	Remove Board J27	Lit	✓	—
	Replace Board J27	Not Lit	✓	—
	Remove Board J29	Lit	✓	—
	Replace Board J29	Not Lit	✓	—
4.5.3.4	Linear Calibrate	Linear Trouble Lit	✓	—
4.5.3.4.1	Linear Calibrate	Linear Trouble Not Lit	✓	—
4.5.3.4.2	Linear Trip Test Upper	Linear Trouble Lit	✓	—
	Linear Trip Test Upper	Linear Trouble Not Lit	✓	—
	Linear Trip Test Lower	Linear Trouble Lit	✓	—
	Linear Trip Test Lower	Linear Trouble Not Lit	✓	—

Step	Measurement/Observation	Acceptable Range	Pass	Fail
4.5.3.4.2 (cont.)	Linear Trip Test Low Power	Linear Trouble Lit	/	
	Linear Trip Test Low Power	Linear Trouble Not Lit	/	
4.5.4.2.	ZPMB Indicator	Lit	/	
			Actual	
	Output Low Power Position	2.5 ± 0.100 VDC	<u>2.518</u>	
			Pass	Fail
4.5.4.2.1	Test Set Low Power N.O. Indicators	Lit	/	
			Actual	
4.5.4.2.2	Output Low Power Position	0.100 ± 0.050 greater than step 4.5.4.2.	<u>2.651</u>	
			Pass	Fail
4.5.4.2.3	ZPMB Indicator	Not Lit	/	
			Actual	
4.5.5.1.	Output Cal Avg. Position	0.750 ± 0.100 VDC	<u>0.753</u>	
			Pass	Fail
4.5.5.1.1	Test Set Linear N.C. Indicators	Lit	/	
			Actual	
	Linear Power Meter	$15 \pm 2\%$	<u>16%</u>	
4.5.5.2	Output Cal Avg Position	0.100 ± 0.050 less than step 4.5.5.1	<u>0.637</u>	

Measurement/Observation

Acceptable Range ~~Pass~~ ~~Fail~~

4.5.5.3	Linear 1 Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.6.1	Linear 2 Indicator	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Test Set Linear 2 N.O. Indicator	Lit:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			Actual	
4.5.6.1.1	Output Cal Avg Position	3.000±0.100 VDC	<u>3.004</u>	
	Linear Power Meter	60±2%	<u>60%</u>	
4.5.6.2	Output Cal Avg Position	0.100±0.050 VDC greater than step 4.5.6.1.1	<u>3.114</u>	
			Pass	Fail
4.5.6.2.1	Linear 2 Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Rev. G

TR 6754-2

Page 12 cont. on 13

ELECTRO-MECHANICS, INC.

New Britain, Connecticut

REJECTION OR REMARKS SHEET

Description EX-CORE SAFETY CHANNELJob No. 6764Part No. 39500WO or PDR No. 13036Tested Per TP 6764-2 FSerial No. E89131

Ref. TR Sht.	REJECTIONS OR REMARKS	Entered	Retest		
		By/Date	Acc	Rej	By/Date
	REV F CHANGES WERE MADE IN THE FIELD DURING THE SIESMIL TEST ON 3.25.82 THESE CHANGES WERE WERE THEN DOCUMENTED ON ON 4/15/82 THIS UNIT MEETS OR EXCEEDS THE CHANGES OF REV F	BN 6.9.82	✓		



ELECTRO-MECHANICS, INC.
New Britain, Connecticut

Test Record TR 6764-13

Ex-Core Safety Channel
Seismic Qualification

Description _____ Part No. 39500
Serial No. E 39131 Job No. 6764
Tested Per TP 6764-13 Rev. E W.O. or PDR No. 13036
Tested by: Jack Jensen Date 3-26-82 Acc ☒ Rej. ☐
Test Record Review by: W.A. Polyzio Date 3-27-82 Acc ☒ Rej. ☐
QA Test Review by: Ray Magner Date 6-9-82 Acc ☒ Rej. ☐

Test Equipment Used: LISTED ON PAGE 3.

Revision Status of Sheets

Page	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
Rev.	B	B	-																								

	Engineer		OA		ECO #	
	Date	Initial	Date	Initial	Date	ECO #
Original Issue	4-7-81	P.L.R.	4/24/81	ADW	—	—
Rev. A	2-9-82	W.A.P.	2/22/82	W.A.P.	2-9-82	14273
Rev. B	3-26-82	W.A.P.	3-26-82	W.A.P.	3-26-82	14391
Rev. C						
Rev. D						



TEST RECORD

Pre-Seismic Test

Section

6 Visual Inspection Done 3.26.82 BN ^{6/9/82} Passed ☒ Failed ☐
 7 Electrical Function Test Done 3.19.82 Passed ☒ Failed ☐

Seismic Test

INPUT	PARAMETER	SPEC. VALUES	ERRORS				
			Pretest	Test #1	Test #2	Test #3	Test #4
J1	Relays	$\pm 25\text{VDC}$	19.151	19.151	19.151	19.151	19.151
J2	Sum	$5.00 \pm 0.200\text{VDC}$	5.025	5.025	5.025	5.025	5.025
J3	Linear Deviation	$0.00 \pm 0.200\text{VDC}$	0.006	0.006	0.006	0.006	0.006
J4	Rate	$1.25 \pm 0.350\text{VDC}$	1.238	1.238	1.238	1.238	1.238
J5	Log	$10.00 \pm 0.300\text{VDC}$	10.066	10.066	10.066	10.066	10.066
J6	Linear	$5.00 \pm 0.200\text{VDC}$	5.034	5.034	5.034	5.034	5.034
J7	LCR	$5.40 \pm 0.300\text{VDC}$	5.665	5.665	5.665	5.665	5.665

Inputs: Log (J5) $50\text{KHz} \pm 1\text{KHz}$ at 0.663 ± 0.010 VRMS
 Lin (J8, J9) $-0.770\text{mA} \pm 0.010\text{mA}$ DC

NOTE: Data for Test 1, Test 2 and Test 3 from recordings. Recordings must be integral part of these test records.



Post-Seismic Test

Section

8.1 Visual Inspection Done 3-26-82 Passed ☒ Failed ☐
 8.2 Electrical Function Test Done 3-26-82 Passed ☒ Failed ☐

TEST EQUIPMENT	TYPE	SERIAL #	CALIB. DATE
Current Sources	DIGITEC	TEP 2280 N	6-30-82
Current Sources	DATA PRECISION BECKMAN	TEP 2343 N TEP 2304 N	10-31-82 4-29-82
Signal Generator	WAVETEK	TEP 2327 N	12-14-82
Visicorder	HONEYWELL	TEP 2478 N	1-5-83
DVM	FLUKE 3810	TEP 2313 N	8-8-82

AFTER SEISMIC

ELECTRO-MECHANICS, INC.
New Britain, Connecticut

Functional Test

Test Record TR 6764-2

Description Ex-Core Safety Channel
Neutron Flux Signal Processing
Electronics Channel Part No. 39500

Serial No. E 39131 Job No. 6764

Tested Per TP 6764-2 Rev. GFB^N W.O. or PDR No. 13036
6/9/82

Tested by: Jack Kerner Date 3/27/82 ORL 6/9/82 Acc ☒ Rej. ☐

Test Record Review by: W.D. Plozie Date 3.27.82 Acc ☒ Rej. ☐

QA Test Review by: Ray Majors Date 6-9-82 Acc ☒ Rej. ☐

Test Equipment Used:
OKE 3VM TEP 2313N 8-8-82
TEKTRONICS TEP 2409N 4-15-82
DIGITEC 4/ TEP 2280N 6-30-82
TEST SET TE 352N NO CAL REQD.

DATA PRECISION 1/8 TEP 2393N 10-31-82
BECKMAN 3020 TEP 2304N 4-29-82
WAVETEK 5/4 TEP 2327N 12-14-82

Revision Status of Sheets

Page	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	1A
Rev.	G	F	E	D	C	C	G	G	R	C	G	G															G

	Engineer		OA		ECO #	
	Date	Initial	Date	Initial	Date	ECO #
Original Issue	4-16-81	P.L.K.	4/21/81	QAS	—	—
Rev. A	4-28-81	P.L.K.	4-29-81	ECW	4-28-81	13119
Rev. B	6-5-81	P.L.K.	6/9/81	QAS	5/29/81	13192
Rev. C	8-24-81	P.L.K.	8-26-81	ECW	8/24/81	13606
Rev. D	10-23-81	P.L.K.	10-26-81	ECW	10/23/81	13871

Rev. G
TR 6764-2
Page 1 cont. on 1A

Revisions Continued

	Engineer		OA		ECO #	
	Date	Initial	Date	Initial	Date	ECO #
Rev. E	2-16-82	EAP	2-17-82	ECW	2-15-82	14246
Rev. F	3-8-82	EAP	3/8/82	EAP	3-1-82	14298
Rev. G	4-14-82	EAP	4/15/82	EAP	4-14-82	14448
Rev. H						
Rev. J						

TEST RECORD

Step	Measurement/Observation	Acceptable Range	Actual
4.1.2.1	Output Select +15 Position	+15V±0.250 VDC	<u>15.016</u>
4.1.3.1	Output Select -15 Position	-15V±0.250 VDC	<u>-15.049</u>
4.1.4.1	Output Select +5 Position	+5V±0.250 VDC	<u>5.021</u>
4.1.5.1	Output Select Preamp +15 Position	+15V±0.250 VDC	<u>15.038</u>
4.1.6.1	Output Select Preamp -15 Position	-15V±0.250 VDC	<u>-14.984</u>
4.1.7.1	High Voltage Meter HV Log	800±20 VDC	<u>800</u>
4.1.8.1	High Voltage Meter HV Lin	800±20 VDC	<u>800</u>
4.2.1.1	Log Power Meter	Approx. $10^{-8}\%$	<u>$1 \times 10^{-8}\%$</u>
4.2.2.1	Test Set Position 1	-0.301±0.300 VDC	<u>-0.259</u>
4.2.3.1	Log Power Meter LCR-1	Between 1.3×10^{-5} and 3.3×10^{-5}	<u>2×10^{-5}</u>
4.2.3.2	Test Set Position 1	+3.020±0.300 VDC	<u>3.038</u>
4.2.4.1	Log Power Meter LCR-2	Between 5.9×10^{-3} and 1.9×10^{-2}	<u>1×10^{-2}</u>
4.2.4.2	Test Set Position 1	5.719±0.300 VDC	<u>5.684</u>
4.2.5.1	Log Power Meter LCR-3	Between 2.6×10^{-2} and 6.6×10^{-2}	<u>6×10^{-2}</u>
4.2.5.2	Test Set Position 1	6.321±0.300 VDC	<u>6.436</u>
4.2.6.1	Log Power Meter MSV-4	Between 2.6×10^{-2} and 6.6×10^{-2}	<u>6×10^{-2}</u>
4.2.6.2	Test Set Position 1	6.321±0.300 VDC	<u>6.461</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.2.7.1	Log Power Meter MSV-5	Between 0.26 and 0.66	<u>0.50</u>
4.2.7.2	Test Set Position 1	7.321±0.300 VDC	<u>7.288</u>
4.2.8.1	Log Power Meter MSV-6	Between 2.6 and 6.6	<u>4.0</u>
4.2.8.2	Test Set Position 1	8.321±0.300 VDC	<u>8.297</u>
4.2.10.1	Log Monitor	1.00±0.10µsec	<u>1.00µs</u>
4.2.11.1	Scaler	0.50±0.50µsec	<u>0.50µs</u>
4.2.12.1	Test Set Position 2	5.719±0.300 VDC	<u>5.685</u>
4.2.13.1	Test Set Position 3	5.719±0.300 VDC	<u>5.697</u>
4.2.14.1	Output Log Position	5.719±0.300 VDC	<u>5.688</u>
4.2.15.1	Test Set Position 1		
	Log Power Meter 2x10 ⁻⁸	0.000±0.300 VDC	<u>-0.009</u>
	Log Power Meter 2x10 ⁻⁷	1.000±0.300 VDC	<u>1.004</u>
	Log Power Meter 2x10 ⁻⁶	2.000±0.300 VDC	<u>1.954</u>
	Log Power Meter 2x10 ⁻⁵	3.000±0.300 VDC	<u>2.938</u>
	Log Power Meter 2x10 ⁻⁴	4.000±0.300 VDC	<u>3.954</u>
	Log Power Meter 2x10 ⁻³	5.000±0.300 VDC	<u>4.940</u>
	Log Power Meter 2x10 ⁻²	6.000±0.300 VDC	<u>5.931</u>
	Log Power Meter 2x10 ⁻¹	7.000±0.300 VDC	<u>6.987</u>
	Log Power Meter 2	8.000±0.300 VDC	<u>7.991</u>
	Log Power Meter 20	9.000±0.300 VDC	<u>9.003</u>
	Log Power Meter 200	10.000±0.300 VDC	<u>10.032</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.3.2.1	Rate Meter	0 ± 0.2 DPM	<u>0 DPM</u>
4.3.2.2	Test Set Position 5	1.250 ± 0.050 VDC	<u>1.265</u>
4.3.3.1	Rate Meter	0 ± 0.2 DPM	<u>0 DPM</u>
4.3.3.2	Test Set Position 5	1.250 ± 0.050 VDC	<u>1.263</u>
4.3.4.1	Rate Meter	7 ± 0.2 DPM	<u>7 DPM</u>
4.3.4.2	Test Set Position 5	10.000 ± 0.050 VDC	<u>10.041</u>
4.3.5.1	Test Set Position 5		
	Rate Meter 1	2.500 ± 0.250 VDC	<u>2.357</u>
	Rate Meter 2	3.750 ± 0.250 VDC	<u>3.690</u>
	Rate Meter 3	5.000 ± 0.250 VDC	<u>4.925</u>
	Rate Meter 4	6.250 ± 0.250 VDC	<u>6.222</u>
	Rate Meter 5	7.500 ± 0.250 VDC	<u>7.479</u>
	Rate Meter 6	8.750 ± 0.250 VDC	<u>8.741</u>
	Rate Meter 7	10.000 ± 0.250 VDC	<u>10.010</u>
4.3.6.1	Test Set Position 4	1.250 ± 0.250 VDC	<u>1.273</u>
4.3.7.2	Output Rate Position	1.250 ± 0.250 VDC	<u>1.276</u>
4.4.1.3	Linear Power Meter	Approx. 0%	<u>0%</u>
4.4.2.1	Output Cal Avg Position	0.000 ± 0.300 VDC	<u>0.014</u>
4.4.3.1	Linear Power Meter	$200 \pm 2\%$	<u>200%</u>
4.4.3.2	Output Cal Avg Position	10.000 ± 0.300 VDC	<u>10.045</u>
4.4.4.1	Linear Power Meter	$2 \pm 2\%$	<u>2%</u>



Dep	Measurement/Observation	Acceptable Range	Actual
4.4.4.2	Output Cal Avg Position	0.100±0.300 VDC	<u>0.111</u>
4.4.4.3	Output Low Power Position	5.000±0.300 VDC	<u>5.043</u>
4.4.5.1	Linear Power Meter	Approx. 0%	<u>0%</u>
4.4.5.2	Output Cal Avg Position	0.000±0.300 VDC	<u>0.012</u>
4.4.6.3	Test Set Position 11	10.000±0.300 VDC	<u>10.005</u>
4.4.6.4	Linear Power Meter	200±2%	<u>200%</u>
4.4.6.5	Test Set Position 8	10.000±0.300 VDC	<u>10.036</u>
4.4.7.3	Test Set Position 10	10.000±0.300 VDC	<u>10.005</u>
4.4.7.4	Linear Power Meter	200±2%	<u>200%</u>
4.4.7.5	Test Set Position 8	10.000±0.300 VDC	<u>10.038</u>
4.4.7.6	Test Set Position 8	5.000±0.300 VDC	<u>5.022</u>
4.4.8.4	Test Set Position 12	-1.000±0.300 VDC	<u>-0.994</u>
4.4.8.5	Test Set Position 6	-1.000±0.300 VDC	<u>-0.982</u>
4.4.9.4	Output Cal Avg Position	5.000±0.300 VDC	<u>5.014</u>
4.4.9.6	Test Set Position 7	5.000±0.300 VDC	<u>5.006</u>
4.4.9.7	Test Set Position 8	5.000±0.300 VDC	<u>5.004</u>
	Test Set Position 9	5.000±0.300 VDC	<u>5.003</u>
	Test Set Position 10	5.000±0.300 VDC	<u>4.984</u>
	Test Set Position 11	5.000±0.300 VDC	<u>4.995</u>
4.4.10.3.1	Output Cal Avg Position	0.100±0.300 VDC	<u>0.098</u>
4.4.10.3.2	Linear Power Meter	2±2%	<u>2%</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.4.10.3.3	Output Low Power Position	5.0±0.300 VDC	<u>4.957</u>
4.4.10.4	Output Cal Avg Position		
	Linear Power Meter 20%	1.000±0.300 VDC	<u>1.000</u>
	Linear Power Meter 40%	2.000±0.300 VDC	<u>2.002</u>
	Linear Power Meter 60%	3.000±0.300 VDC	<u>3.008</u>
	Linear Power Meter 80%	4.000±0.300 VDC	<u>4.001</u>
	Linear Power Meter 100%	5.000±0.300 VDC	<u>5.015</u>
	Linear Power Meter 120%	6.000±0.300 VDC	<u>6.012</u>
	Linear Power Meter 140%	7.000±0.300 VDC	<u>7.022</u>
	Linear Power Meter 160%	8.000±0.300 VDC	<u>8.013</u>
	Linear Power Meter 180%	9.000±0.300 VDC	<u>9.020</u>
	Linear Power Meter 200%	10.000±0.300 VDC	<u>10.031</u>
4.4.11.2	Test Set Position 10		
	Input Current -0.154ma	1.000±0.300 VDC	<u>0.981</u>
	Input Current -0.308ma	2.000±0.300 VDC	<u>1.983</u>
	Input Current -0.462ma	3.000±0.300 VDC	<u>2.979</u>
	Input Current -0.616ma	4.000±0.300 VDC	<u>3.957</u>
	Input Current -0.770ma	5.000±0.300 VDC	<u>4.983</u>
	Input Current -0.924ma	6.000±0.300 VDC	<u>5.979</u>
	Input Current -1.078ma	7.000±0.300 VDC	<u>6.978</u>
	Input Current -1.232ma	8.000±0.300 VDC	<u>7.979</u>

Step	Measurement/Observation	Acceptable Range	Actual
4.4.11.2 (cont.)	Test Set Position 10		
	Input Current -1.386ma	9.000±0.300 VDC	<u>8.981</u>
	Input Current -1.540ma	10.000±0.300 VDC	<u>9.977</u>
4.4.11.5	Test Set Position 11		
	Input Current -0.154ma	1.000±0.300 VDC	<u>0.981</u>
	Input Current -0.308ma	2.000±0.300 VDC	<u>1.984</u>
	Input Current -0.462ma	3.000±0.300 VDC	<u>2.981</u>
	Input Current -0.616ma	4.000±0.300 VDC	<u>3.982</u>
	Input Current -0.770ma	5.000±0.300 VDC	<u>4.985</u>
	Input Current -0.924ma	6.000±0.300 VDC	<u>5.982</u>
	Input Current -1.078ma	7.000±0.300 VDC	<u>6.980</u>
	Input Current -1.232ma	8.000±0.300 VDC	<u>7.983</u>
	Input Current -1.386ma	9.000±0.300 VDC	<u>8.985</u>
	Input Current -1.540ma	10.000±0.300 VDC	<u>9.981</u>
4.4.12.2	Test Set Position 8		
	Input Voltage -0.154 VDC	1.000±0.300 VDC	<u>1.006</u>
	Input Voltage -0.308 VDC	2.000±0.300 VDC	<u>2.008</u>
	Input Voltage -0.462 VDC	3.000±0.300 VDC	<u>3.004</u>
	Input Voltage -0.616 VDC	4.000±0.300 VDC	<u>4.004</u>
	Input Voltage -0.770 VDC	5.000±0.300 VDC	<u>5.006</u>

Step	Measurement/Observation	Acceptable Range	Pass	Fail
4.5.5.3	Linear 1 Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4.5.6.1	Linear 2 Indicator	Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	Test Set Linear 2 N.O. Indicator	Lit:	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			Actual	
4.5.6.1.1	Output Cal Avg Position	3.000±0.100 VDC	<u>3.001.</u>	
	Linear Power Meter	60±2%	<u>60%</u>	
4.5.6.2	Output Cal Avg Position	0.100±0.050 VDC greater than step 4.5.6.1.1	<u>3.113</u>	
			Pass	Fail
4.5.6.2.1	Linear 2 Indicator	Not Lit	<input checked="" type="checkbox"/>	<input type="checkbox"/>