

REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 8108030329 DOC. DATE: 81/07/27 NOTARIZED: NO DOCKET #
 FACIL: 50-397 WPPSS Nuclear Project, Unit 2, Washington Public Powe 05000397
 AUTH. NAME: AUTHOR AFFILIATION
 BOUCHEY, G.D. Washington Public Power Supply System
 RECIP. NAME: RECIPIENT AFFILIATION
 SCHWENCER, A. Licensing Branch 2

SUBJECT: Forwards addl info re safety relief valve methodology, in response to NRC 810528 request. Info will be incorporated into FSAR within 4 months.

DISTRIBUTION CODE: B001S COPIES RECEIVED: LTR 1 ENCL 1 SIZE: 17
 TITLE: PSAR/FSAR AMDTS and Related Correspondence

NOTES: PM: 2 copies of all material. 1 cy: BWR-LRG. PM(L, RIB)

05000397

ACTION:	RECIPIENT ID CODE/NAME	COPIES		RECIPIENT ID CODE/NAME	COPIES	
		LTTR	ENCL		LTTR	ENCL
ACTION:	A/D LICENSNG	1	0	LIC BR #2 BC	1	0
	LIC BR #2 LA	1	0	AULUCK, R. 04	1	1
INTERNAL:	ACCID EVAL BR26	1	1	AUX SYS BR 27	1	1
	CHEM ENG BR 11	1	1	CONT SYS BR 09	1	1
	CORE PERF BR 10	1	1	EFF TR SYS BR12	1	1
	EMRG PRP DEV 35	1	1	EMRG PRP LIC 36	3	3
	EQUIP QUAL BR13	3	3	FEMA-REP DIV 39	1	1
	GEOSCIENCES 28	2	2	HUM FACT ENG 40	1	1
	HYD/GEO BR 30	2	2	I&C SYS BR 16	1	1
	I&EI 06	3	3	LIC GUID BR 33	1	1
	LIC QUAL BR 32	1	1	MATL ENG BR 17	1	1
	MECH ENG BR 18	1	1	MPA	1	0
	NRC PDR 02	1	1	OELD	1	0
	OP LIC BR 34	1	1	POWER SYS BR 19	1	1
	PROC/TST REV 20	1	1	QA BR 21	1	1
	RAD ASSESS BR22	1	1	REAC SYS BR 23	1	1
	<u>REG. FILE</u> 01	1	1	SIT ANAL BR 24	1	1
	STRUCT ENG BR25	1	1			
	EXTERNAL:	ACRS 41	16	16	LPDR 03	1
NSIC 05		1	1	NTIS	1	1

AUG 5 1981

TOTAL NUMBER OF COPIES REQUIRED: LTTR

65
62 ENCL 60
57

3F

1. The first part of the document is a letter from the President of the United States to the Congress, dated January 1, 1861. It is a very important document, as it sets out the policy of the new administration. The President states that he is committed to the principles of liberty and justice for all, and that he will work to maintain the Union and the Constitution.

2. The second part of the document is a report from the Secretary of the Treasury, dated January 1, 1861. It provides a detailed account of the financial state of the country at the beginning of the year. The report shows that the government is in a sound financial position, with a surplus of funds. It also discusses the various measures that have been taken to improve the economy and to reduce the national debt.

3. The third part of the document is a report from the Secretary of the Interior, dated January 1, 1861. It provides a detailed account of the various activities of the Department of the Interior during the year. The report covers a wide range of topics, including the management of the public lands, the protection of the wildlife, and the promotion of agriculture and industry. It also discusses the various measures that have been taken to improve the education and the health of the people.

Washington Public Power Supply System

P.O. Box 968 3000 George Washington Way Richland, Washington 99352 (509) 372-5000

Docket No. 50-397


Director, Nuclear Reactor Regulation
U.S. Nuclear Regulatory Commission
Washington D.C. 20555

July 27, 1981
G02-81-196
NS-L-02-CDT-81-14

Attention: Mr. A. Schwencer, Chief
Licensing Branch No. 2
Division of Licensing

Gentlemen:

Subject: SUPPLY SYSTEM NUCLEAR PROJECT NO. 2
RESPONSES TO ROUND TWO QUESTIONS
SRV METHODOLOGY



Reference: Letter, R. L. Tedesco (NRC) to R. L. Ferguson, "Request
for Additional Information - SRV Methodology", May 28, 1981.

Enclosed are sixty (60) copies of the responses to the SRV Methodology questions which were transmitted to us by the reference letter. These responses are to be incorporated formally into the FSAR in an amendment within four months.

Very truly yours,

G. D. BOUCHEY
Director, Nuclear Safety

GDB:CDT:ct

Enclosure

cc: WS Chin, BPA
V. Stello, NRC
AD Toth, NRC, Resident Inspector
J. Plunkett, NUS Corporation
WNP-2 Files
R. Auluck, NRC
OK Earle, B&R

8108030329 810727
PDR ADOCK 05000397
A PDR

Boo!
5/11

WNP-2

Q. 022.107

Provide detailed calculations of the wall pressure amplitude multiplier to account for the difference between WNP-2 design conditions and Caorso test conditions.

Response:

Provided below are detailed calculations of the pressure amplitude multiplier developed to convert from Caorso test conditions to WNP-2 design conditions. Table 6.1 of the SRV report defines key plant parameters for single valve actuations important in defining pressure amplitudes for both Caorso and WNP-2 facilities. Test conditions chosen for Caorso were conditions which were typical of subsequent actuations of a single valve.

WALL PRESSURE AMPLITUDE MULTIPLIER
(DFFR Methodology)

I. WNP-2 pressure prediction: (single valve, subsequent actuation).

$$VA = 2.423 \text{ m}^3$$

$$AQ = 6.93 \text{ m}^2$$

$$AW = 419 \text{ m}^2$$

$$WCL = 5.3 \text{ m}$$

$$TW = 200^\circ\text{F}$$

$$VOT = 20 \text{ ms}$$

$$MN = 412 \text{ metric tons/hr.}$$

Ref: (See Table 6.1, SRV Report)

$$VAAQ = \frac{VA}{AQ} = \frac{2.423}{6.93} = 0.3496$$

$$MNAQ = \frac{(MN)^{0.7}}{AQ} = \frac{412^{(0.7)}}{6.93} = 9.766$$

$$AWAQ = \frac{AW}{AQ(NN)} \quad \text{Where } NN = \text{number of quenchers}$$

$$= \frac{419}{(6.93)(1.0)} = 60.46$$

Since $VAAQ > 0.255$, $VAAQ$ is redefined as 0.255

Since $MNAQ > 6.89$,

$$COF = 0.01$$

$$MNQJ = MNAQ = 9.766$$

$MNAQ$ is redefined as 6.89

$$MNQ1 = MNAQ = 6.89$$

$$MNQ2 = (MNAQ)^2 = 47.47$$

Since $AWAQ > 20$,

$$AWAQ = 20$$

$$C = \frac{5(F-32)}{9} = \frac{5(200-32)}{9} = 93.33$$

$$LNTW = \ln c = 4.535$$

$$WCL2 = (WCL)^2 = (5.3)^2 = 28.09$$

$$AWQ2 = (AWAQ)^2 = 400.0$$

$$A1 = (VAAQ - 0.1706) (2.58) = (0.255 - 0.1706) (2.58) = 0.2178$$

$$A2 = 0.$$

$$A3 = (MNQ2 - 52.7) (0.0089) = (47.47 - 52.7) (0.0089) = -0.04655$$

$$A4 = (MNQJ - 6.89) * COF = (9.766 - 6.89) (0.01) = 0.02876$$

$$A5 = (LNTW - 3.83) (0.1377) = (4.536 - 3.83) (0.1377) = 0.09722$$

$$A6 = (WCL - 4.0) (0.206) = (5.3 - 4.0) (0.206) = 0.2678$$

$$A7 = (WCL2 - 16.0) (0.0176) = (28.09 - 16.0) (0.0176) = 0.2128$$

$$A8 = (VOT - 532.0) (0.000148) = (20 - 532.0) (0.000148) = -0.07578$$

$$A9 = 0.$$

$$A10 = 0.$$

$$PRD 1 = A1 + A2 - A3 + A4 + A5 + A6 - A7 - A8 - A9 + A10 + 0.253$$

$$PRD 1 = 0.7741 = AA$$

For subsequent actuations,

$$CMSA = 1.744$$

$$VVPM = 0.012$$

$$PROR = 0.229$$

$$CONF = 2.065$$

$$VVP1 = 0.006$$

$$\begin{aligned} AB &= (CMSA)^2 (VVP1) + \left[(VVPM) + \frac{(PROR)^2 (CMSA)^2}{(NN)} \right] (AA)^2 \\ &= (1.744)^2 (0.006) + \left[(0.012) + \frac{(0.229)^2 (1.744)^2}{(1)} \right] (0.7741)^2 \\ &= 0.1210 \end{aligned}$$

AB is redefined as $\sqrt{AB} * (CONF)$

$$= \sqrt{0.1210} (2.065) = 0.7183$$

$$\begin{aligned} \text{MPPDV} &= (\text{CMSA}) (\text{AA}) + (\text{AB}) \\ &= (1.744) (0.7741) + (0.7183) \\ &= 2.068 \text{ bar} \end{aligned}$$

The predicted peak positive pressure amplitude for single valve, subsequent actuation is

$$2.068 \frac{(14.7)}{(1.014)} = \underline{29.98 \text{ psid}}$$

II. Caorso Pressure Prediction:
(Single valve, subsequent actuations)

$$VA = 1.781 \text{ m}^3$$

$$AQ = 6.93 \text{ m}^2$$

$$AW = 370 \text{ m}^2$$

$$WCL = 5.09 \text{ m}$$

$$TW = 90^\circ\text{F}$$

$$VOT = 45 \text{ ms}$$

$$MN = 390 \text{ metric tons/hr.}$$

} Found typical for single
valve, subsequent actuation
tests at Caorso.

Ref: (Table 6.1, SRV Report)

$$VAAQ = \frac{VA}{AQ} = \frac{1.781}{6.93} = 0.2570$$

$$MNAQ = \frac{MN}{AQ}^{(0.7)} = \frac{(390)^{0.7}}{6.93} = 9.397$$

$$AWAQ = \frac{AW}{AQ^{(NN)}} \quad \text{Where NN = Number of quenchers}$$

$$= \frac{370}{(6.93)(1.0)} = 53.39$$

Since $VAAQ > 0.255$, $VAAQ$ is redefined as 0.255

Since $MNAQ > 6.89$,

$$COF = 0.01$$

$$MNQJ = MNAQ = 9.397$$

$MNAQ$ is redefined as 6.89

$$MNQ1 = MNAQ = 6.89$$

$$MNQ2 = (MNAQ)^2 = 47.47$$

Since $AWAQ > 20$,

$$AWAQ = 20$$

$$C = \frac{5}{9} (F-32) = \frac{5}{9} (90-32) = 32.22$$

$$LNTW = \ln c = 3.473$$

$$WCL2 = (WCL)^2 = (5.09)^2 = 25.91$$

$$AWQ2 = (AWAQ)^2 = 400.0$$

$$A1 = (VAAQ - 0.1706)(2.5) = 0.2178$$

$$A2 = 0.$$

$$A3 = (MNQ2-52.7)(0.0089) = -0.04655$$

$$A4 = (MNQJ-6.89)(COF) = 0.02507$$

$$A5 = (LNTW-3.83)(0.1377) = -0.04916$$

$$A6 = (WCL-4.0)(0.206) = 0.2245$$

$$A7 = (WCL2-16.0)(0.0176) = 0.1744$$

$$A8 = (VOT-532.0)(0.000148) = -0.07208$$

$$A9 = 0.$$

$$A10 = 0.$$

$$PRD1 = A1 + A2 - A3 + A4 + A5 + A6 - A7 - A8 - A9 + A10 \\ + 0.253$$

$$PRD1 = AA = 0.6154$$

For subsequent actuations,

$$CMSA = 1.744$$

$$VVPM = 0.012$$

$$PROR = 0.229$$

$$CONF = 2.065$$

$$VVP1 = 0.006$$

$$AB = (CMSA)^2(VVP1) + \left| (VVPM) + \frac{(PROR)^2(CMSA)^2}{(NN)} \right| (AA)^2$$

$$AB = 0.08320$$

$$AB \text{ is redefined as } \sqrt{AB} * CONF$$

$$AB = 0.5956$$

$$MPPDV = (CMSA)(AA) + (AB) \\ = 1.669 \text{ bar}$$

The predicted peak positive pressure amplitude for single valve, subsequent actuation at Caorso is:

$$1.669 \frac{(14.7)}{(1.014)} = \underline{24.20 \text{ psid}}$$

PRESSURE AMPLITUDE MULTIPLIER

Conversion from Caorso test conditions to WNP-2
design conditions

$$C_r = \frac{29.98}{24.20} \approx 1.2$$

REFERENCES:

1. Letter, D. L. Renberger to B. J. Youngblood, "Submittal of SRV Report", dated August 8, 1980, G02-80-172, transmitting report titled "SRV Loads - Improved Definition and Application Methodology for Mark II Containments".

WNP-2

Q. 022.109

Provide the quencher submergence and SRV line volumes for all WNP-2 discharge lines.

Detailed quencher design and vacuum breaker characteristics are important in the determination of SRV air clearing load. Due to the difference in detailed quencher design and vacuum breaker characteristics between Caorso and WNP-2, we require further justification of the applicability of Caorso data to WNP-2 or require in-plant test.

Response:

Table 022.109-1 provides the quencher submergence and SRV line volumes for all 18 SRV discharge lines at WNP-2. The comparison between the quenchers at Caorso and WNP-2 is discussed in the response to Question 022.053 and the vacuum breaker comparison is addressed in Question 022.054. In both comparisons there appear to be no significant differences that would substantially affect the SRV air clearing load. For the details of the responses refer to the above referenced questions. Based on these comparisons, an in-plant SRV test at WNP-2 does not appear to be required.

TABLE Q22.102-1

QUENCHER SUBMERGENCE AND SRV DISCHARGE LINE AIR VOLUMES

Valve No.	Length (ft.)		Total (ft.) (1)	Submergence (ft.) (2)	Air Volume (ft. ³) (3)
	10"Ø	12"Ø			
1A	104.5	31.96	136.48	17.3	65.1
2A	106.81	34.96	141.77	17.3	68.3
3A	109.20	42.97	152.17	17.3	75.2
4A*	127.98	29.95	157.93	17.3	75.4
1B	91.53	30.00	121.53	17.3	57.2
2B	108.11	35.67	143.77	17.3	69.5
3B	131.04	34.96	166.01	17.3	80.4
4B*	118.54	51.19	169.74	17.3	85.6
5B*	109.28	38.67	147.96	17.3	72.2
1C	101.92	30.00	131.92	17.3	62.4
2C	129.31	34.05	163.36	17.3	78.9
3C	141.79	30.67	172.46	17.3	82.8
4C*	136.72	29.96	166.67	17.3	79.7
5C*	126.47	49.04	175.53	17.3	88.1
1D	84.36	43.17	127.53	17.3	62.9
2D	118.57	45.27	163.84	17.3	81.5
3D*	110.44	34.95	145.39	17.3	70.1
4D*	106.38	44.17	150.55	17.3	74.6

*ADS Valves

- NOTES: 1. SRV line to the top of quencher.
2. High water level (El. 466.40 ft.) to the ϕ of a quencher arm.
(Top of quencher to the ϕ of arm = 3.75 ft.)
3. 10" and 12" - Sch. 80.

WNP-2

Q. 022.110

Our evaluation of the Caorso data reveals that higher wall pressure amplitudes are observed for consecutive SRV actuation tests for lines with two 10" vacuum breakers than those with only one vacuum breaker. Since the WNP-2 design utilizes two 10" vacuum breakers on each SRV line, it is our position that pressure amplitude multipliers which will account for this difference should be provided.

Response:

Please refer to the response to Question 022.057.

WNP-2

Q. 022.111

Our evaluation of the Caorso data indicates that higher pressure amplitudes are observed for multiple SRV actuation tests than single SRV first actuation tests. Since WNP-2 specifications are based on single SRV actuation test results, it is our position that a pressure amplitude multiplier for the all-valve case based on the DFFR correlation (assuming WNP-2 surface area) should be used.

Response:

Please refer to the response to Question 022.055.

WNP-2

Q. 022.112

The vertical wall pressure distribution in the WNP-2 specification does not bound Caorso test results. Since the accuracy of sensors used to obtain test data is questionable, it is our position that the staff generic acceptance criteria set forth in NUREG-0487, Supplement 2, Item II.B.4.d should be used.

Response:

As indicated in the response to Question 022.059 and illustrated in Figure 022.059-1, the vertical wall pressure distribution in the WNP-2 specification does bound Caorso test results. Furthermore, the vertical wall pressure distribution in the WNP-2 specification was also verified by TOKAI 2 test results, as shown in Figure 3.8b of the Reference 1 report. Plant assessments are being performed using the vertical wall pressure distribution defined in the SRV report. A major effort would be involved in adopting an alternative vertical wall pressure distribution which does not appear to be warranted based on existing test data.

REFERENCES:

1. Burns and Roe, Inc., "SRV Loads - Improved Definition and Application Methodology to Mark II Containments - Technical Report", dated July 29, 1980 (proprietary), submitted to NRC by WPPSS to NRC letter G02-80-172, "Submittal of SRV Report", August 8, 1980.

WNP-2

Q. 022.113

The method used in the calculation of the circumferential pressure distribution in the WNP-2 asymmetric case may not be conservative because of an over-prediction of pressure on the opposite side of the pool of the discharging quencher(s).

It is our recommendation that zero dynamic pressure be specified for the 180° circumference on the opposite side of operating quenchers to assure a maximum overturning moment.

Response:

Please refer to the response to Question 022.061.

WNP-2

Q. 022.114

The use of the DFFR correlation in the calculation of pressure multipliers to account for differences in parameter values between the WNP-2 design condition and Caorso test conditions is not necessarily conservative.

Over-prediction of pressure amplitude corresponding to the Caorso test conditions by the DFFR correlation may lead to under-prediction of the pressure multiplier. Furthermore, despite the overall conservatism in the DFFR correlation, trends with respect to individual parameters may not be conservative, e.g., trend with respect to SRV steam flow.

It is, therefore, our position that trends obtainable from Caorso test results, if more conservative than the DFFR correlation should be used in the pressure multiplier calculations or incorporation of the Caorso data in the DFFR model should be provided for our review.

Response:

Please refer to the response to Question 022.058.