

## SPECIAL TEST EXCEPTIONS

### 3/4.10.5 OXYGEN CONCENTRATION

#### LIMITING CONDITION FOR OPERATION

3.10.5 The provisions of Specification 3.5.6.4 may be suspended during the performance of the Startup Test Program until either the required 100% of RATED THERMAL POWER trip tests have been completed or the reactor has operated for 120 Effective Full Power Days.

APPLICABILITY: OPERATIONAL CONDITION 1.

#### ACTION

With the requirements of the above specification not satisfied, be in at least STARTUP within 6 hours.

#### SURVEILLANCE REQUIREMENTS

4.10.5 The Effective Full Power Days of operation shall be verified to be less than 120, by calculation, at least once per 7 days during the Startup Test Program.

PROPOSED CHANGE

Attachment

8405160258 840511  
PDR ADOCK 05000397  
P PDR

3/4 10-5

1000 1000 1000 1000