

## CONTAINMENT SYSTEMS

### SURVEILLANCE REQUIREMENTS (Continued)

- d. Type B and C tests shall be conducted with gas at  $P_a$ , 34.7 psig,\* at intervals no greater than 24 months except for tests involving:
1. Air locks,
  2. Main steam line isolation valves,
  3. Valves pressurized with fluid from a seal system,
  4. ECCS and RCIC containment isolation valves in hydrostatically tested lines which penetrate the primary containment, and
  5. Purge supply and exhaust isolation valves with resilient seals.
- e. Air locks shall be tested and demonstrated OPERABLE per Surveillance Requirement 4.6.1.3.
- f. Main steam line isolation valves shall be leak tested at least once per 18 months.
- g. Leakage from isolation valves that are sealed with fluid from a seal system may be excluded, subject to the provisions of Appendix J, Section III.C.3, when determining the combined leakage rate provided the seal system and valves are pressurized to at least  $1.10 P_a$ , 38.2 psig, and the seal system capacity is adequate to maintain system pressure for at least 30 days.
- h. ECCS and RCIC containment isolation valves in hydrostatically tested lines which penetrate the primary containment shall be leak tested at least once per 18 months.
- i. Purge supply and exhaust isolation valves with resilient material seals shall be tested and demonstrated OPERABLE per Surveillance Requirements 4.6.1.8.2 and 4.6.1.8.3.
- j. The provisions of Specification 4.0.2 are not applicable to 24-month or  $40 \pm 10$  month surveillance intervals.

\*Unless a hydrostatic test is required per Table 3.6.3-1.

\*\* The 24 month type B test of the drywell head "O" rings is deferred until the first refueling outage.

11/19

11/19/00 11:19 AM 11/19/00 11:19 AM 11/19/00 11:19 AM 11/19/00 11:19 AM