



8803150313 880307  
PDR ADOCK 05000397  
P PDR

## ADVANCED NUCLEAR FUELS CORPORATION


ANF-88-02  
Issue Date: 1/15/88

### WNP-2 CYCLE 4 RELOAD ANALYSIS

Prepared By:

   
J. E. Krajicek/M. J. Hibbard  
BWR Safety Analysis  
Licensing and Safety Engineering  
Fuel Engineering and Technical Services

Prepared By:

  
J. C. Rawlings  
ENSA

**NUCLEAR REGULATORY COMMISSION REPORT DISCLAIMER**

**IMPORTANT NOTICE REGARDING CONTENTS AND USE OF THIS  
DOCUMENT**

**PLEASE READ CAREFULLY**

This technical report was derived through research and development programs sponsored by Advanced Nuclear Fuels Corporation. It is being submitted by Advanced Nuclear Fuels Corporation to the U.S. Nuclear Regulatory Commission as part of a technical contribution to facilitate safety analyses by licensees of the U.S. Nuclear Regulatory Commission which utilize Advanced Nuclear Fuels Corporation-fabricated reload fuel or other technical services provided by Advanced Nuclear Fuels Corporation for light water power reactors and it is true and correct to the best of Advanced Nuclear Fuels Corporation's knowledge, information, and belief. The information contained herein may be used by the U.S. Nuclear Regulatory Commission in its review of this report, and under the terms of the respective agreements, by licensees or applicants before the U.S. Nuclear Regulatory Commission which are customers of Advanced Nuclear Fuels Corporation in their demonstration of compliance with the U.S. Nuclear Regulatory Commission's regulations.

Advanced Nuclear Fuels Corporation's warranties and representations concerning the subject matter of this document are those set forth in the agreement between Advanced Nuclear Fuels Corporation and the customer to which this document is issued. Accordingly, except as otherwise expressly provided in such agreement, neither Advanced Nuclear Fuels Corporation nor any person acting on its behalf:

- A. Makes any warranty, or representation, express or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this document, or that the use of any information, apparatus, method, or process disclosed in this document will not infringe privately owned rights, or
- B. Assumes any liabilities with respect to the use of, or for damages resulting from the use of, any information, apparatus, method, or process disclosed in this document.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION.....	1
2.0 FUEL MECHANICAL DESIGN ANALYSIS.....	2
3.0 THERMAL HYDRAULIC DESIGN ANALYSIS.....	3
3.1 Design Criteria.....	3
3.1.3 Fuel Centerline Temperature.....	3
3.2 Hydraulic Characterization.....	3
3.2.5 Bypass Flow.....	3
3.3 MCPR Fuel Cladding Integrity Safety Limit.....	3
3.3.1 Coolant Thermodynamic Condition.....	3
3.3.2 Design Basis Radial Power Distribution.....	3
3.3.3 Design Basis Local Power Distribution.....	4
4.0 NUCLEAR DESIGN ANALYSIS.....	5
4.1 Fuel Bundle Nuclear Design Analysis.....	5
4.2 Core Nuclear Design Analysis.....	5
4.2.1 Core Configuration.....	5
4.2.2 Core Reactivity Characteristics.....	5
4.2.4 Core Hydrodynamic Stability.....	6
5.0 ANTICIPATED OPERATIONAL OCCURRENCES.....	7
5.1 Analysis Of Plant Transients At Increased Core Flow Conditions..	7
5.2 Analyses For Reduced Flow Operation.....	8
5.4 ASME Overpressurization Analysis.....	8
5.5 Control Rod Withdrawal Error.....	9
5.6 Fuel Loading Error.....	9
5.7 Determination Of Thermal Margins.....	9
6.0 POSTULATED ACCIDENTS.....	12
6.1 Loss-Of-Coolant Accident.....	12
6.1.1 Break Location Spectrum.....	12
6.1.2 Break Size Spectrum.....	12
6.1.3 MAPLHGR Analyses.....	12
6.2 Control Rod Drop Accident.....	12

TABLE OF CONTENTS  
(Continued)

<u>Section</u>	<u>Page</u>
7.0 TECHNICAL SPECIFICATIONS.....	13
7.1 Limiting Safety System Settings.....	13
7.1.1 MCPR Fuel Cladding Integrity Safety Limit.....	13
7.1.2 Steam Dome Pressure Safety Limit.....	13
7.2 Limiting Conditions For Operation.....	13
7.2.1 Average Planar Linear Heat Generation Rate Limits For ANF 8x8 Fuel.....	13
7.2.2 Minimum Critical Power Ratio.....	13
7.2.3 Surveillance Requirements.....	14
7.2.3.1 Scram Insertion Time Surveillance .....	14
7.2.3.2 Stability Surveillance.....	15
7.2.3.3 Technical Specification LHGR Surveillance.....	15
9.0 ADDITIONAL REFERENCES.....	27
APPENDIX A.....	A-1

LIST OF TABLES

<u>Table</u>	<u>Page</u>
4.1 Neutronic Design Values.....	16

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
3.1 Radial Power Histogram For 1/4 Core Safety Limit Model.....	18
3.2 WNP-2 Cycle 4 Safety Limit Local Peaking Factors (ANF XN-3 Fuel)..	19
3.3 WNP-2 Cycle 4 Safety Limit Local Peaking Factors (ANF XN-1, -2 Fuel).....	20
4.1 WNP-2 Cycle 4 Enriched Zone Enrichment Distribution.....	21
4.2 WNP-2 Cycle 4 Reference Loading Pattern By Fuel Type (One Quarter Of Symmetrical Core Loading).....	22
5.1 WNP-2 Cycle 4 Control Rod Withdrawal Analysis Initial Control Rod Pattern.....	23
5.2 Reduced Flow MCPWR Operating Limit For Normal Feedwater Temperature.....	24
5.3 Reduced Flow MCPWR Operating Limit For FFTR Operation.....	25
7.1 Linear Heat Generation Rate (LHGR) Limit Versus Average Planar Exposure, ANF 8x8 Fuel.....	26



## 1.0 INTRODUCTION

This report summarizes the results of the analyses performed by Advanced Nuclear Fuels Corporation (ANF) in support of the Cycle 4 reload for the Supply System Nuclear Project Number 2 (WNP-2). WNP-2 is scheduled to commence Cycle 4 operation in June 1988. This report is intended to be used in conjunction with Exxon Nuclear Company (ENC) topical report XN-NF-80-19(A), Volume 4, Rev. 1, "Application of the ENC Methodology to BWR Reloads," which describes the analyses performed in support of this reload, identifies the methodology used for those analyses, and provides a generic reference list. Section numbers in this report are the same as corresponding section numbers in XN-NF-80-19(A), Volume 4, Rev. 1. Appendix A of this report addresses single loop operation.

Final feedwater temperature reduction (FFTR) analysis with thermal coastdown was performed for WNP-2. This FFTR analysis is applicable after the all rods out condition is reached with normal feedwater temperature. That is, additional MCPR limit changes are applicable when Cycle 4 reactor operation is being extended with thermal coastdown and FFTR.

The WNP-2 Cycle 4 core will comprise a total of 764 fuel assemblies, including 152 ANF 8x8 unirradiated assemblies, 148 once irradiated ANF 8x8 assemblies, 128 twice irradiated ANF 8x8 assemblies, and 336 thrice irradiated P8x8R assemblies fabricated by General Electric (GE). The reference core configuration is described in Section 4.2.

The design and safety analyses reported in this document were based on the design and operational assumptions in effect for WNP-2 during the previous operating cycle which encompass core flow up to 106% of the design basis value.

## 2.0 FUEL MECHANICAL DESIGN ANALYSIS

Applicable Fuel Design Report:

Reference 9.8

The expected power history for the fuel to be irradiated during Cycle 4 of WNP-2 is bounded by the assumed power history in the fuel mechanical design analyses.



### 3.0 THERMAL HYDRAULIC DESIGN ANALYSIS

#### 3.1 Design Criteria

##### 3.1.3 Fuel Centerline Temperature

The LHGR curve in Figure 3.4 of Reference 9.8 shows that the ANF 8x8 fuel centerline temperature is protected for 120% over power. The LHGR curve in Reference 9.8 is greater than 120% above the LHGR limit curve in Reference 9.1. Therefore, fuel centerline melt is protected for all ANF 8x8 exposures within the bounds of the referenced LHGR curves.

#### 3.2 Hydraulic Characterization

##### 3.2.5 Bypass Flow

Calculated Bypass Flow Fraction	11.6%
---------------------------------	-------

### 3.3 MCPR Fuel Cladding Integrity Safety Limit

#### 3.3.1 Coolant Thermodynamic Condition

Core Power	3817 MWt
Core Inlet Enthalpy	526.4 Btu/lbm
Steam Dome Pressure	1030 psia
Feedwater Temperature	420°F

#### 3.3.2 Design Basis Radial Power Distribution

See Figure 3.1

### 3.3.3 Design Basis Local Power Distribution

See Figures 3.2 and 3.3.

#### 4.0 NUCLEAR DESIGN ANALYSIS

##### 4.1 Fuel Bundle Nuclear Design Analysis

Assembly Average Enrichment	2.64 w/o U-235
Radial Enrichment Distribution	Figure 4.1
Axial Enrichment Distribution	Uniform 2.81 w/o U-235 with 6-inch top and bottom natural uranium blankets
Burnable Poisons	Figure 4.1
Non-Fueled Rods	Figure 4.1
Neutronic Design Parameters	Table 4.1
Note: The reload includes 24 ANF 8x8 assemblies of the 2.72 w/o U-235 design loaded in Cycle 3 and described in the Cycle 3 Reload Analysis Report XN-NF-87-25.	

##### 4.2 Core Nuclear Design Analysis

###### 4.2.1 Core Configuration Figure 4.2

Core Exposure at EOC3 (MWd/MTU)	15,300
Core Exposure at BOC4 (MWd/MTU)	11,200
Core Exposure at EOC4 (MWd/MTU)	16,900

###### 4.2.2 Core Reactivity Characteristics

BOC Cold k-eff, All Rods Out	1.1194
BOC Cold k-eff, Strongest Rod Out	0.9894
Reactivity Defect (R-Value)	0.0
Standby Liquid Control System (SBLC)	0.9654
660 ppm Boron, Cold k-eff	

#### 4.2.4 Core Hydrodynamic Stability

<u>%Power/%Flow State Points</u>	<u>Decay Ratio (COTRAN)</u>
65/45*	0.55
46/27.6**	0.88
42/23.8***	0.82

---

\*45 percent flow - APRM Rod Block intercept point.

\*\*Two pump minimum flow - 46 percent power.

\*\*\*Natural circulation flow - APRM Rod Block intercept point.

## 5.0 ANTICIPATED OPERATIONAL OCCURRENCES

Applicable Transient Analysis Report

Reference 9.3

### 5.1 Analysis Of Plant Transients At Increased Core Flow Conditions

Reference 9.3  
and 9.11

Limiting Transient(s):    Load Rejection Without Bypass (LRWB)  
                              Feedwater Controller Failure (FWCF)  
                              Loss of Feedwater Heating (LOFH)

Transient analyses for WNP-2 Cycle 2 anticipated operational events showed that delta CPR values at design basis conditions are bounded by delta CPR values at design basis power (104%) and increased core flow conditions (106%). Thus Cycle 4 analyses results at increased core flow conditions are conservatively applicable to rated flow conditions.

Cycle 4 specific analyses of transient events were performed with the recirculation pump (RPT) in service and out of service, with normal scram speed (NSS) and technical specification scram speed (TSSS), and at exposures of end-of-cycle and at end-of-cycle -2000 MWd/MTU (3754 MWd/MTU) as shown in following table. On a generic basis, analyses were performed for thermal coastdown with FFTR to extend cycle operation.

The loss of feedwater heating event was analyzed on a plant specific bounding value basis and the delta CPR results are bounding values for WNP-2.

<u>Transient*</u>	<u>% Power/ % Flow</u>	<u>Maximum Heat Flux %</u>	<u>Maximum Power %</u>	<u>Maximum Pressure psig</u>	<u>Delta CPR</u>	
					<u>GE Fuel</u>	<u>ANF Fuel</u>
LRNB, NSS RPT Operable	104/106	119	373	1170	0.25	0.24
LRNB, NSS RPT Inoperable	104/106	125	505	1181	0.32	0.29
LRNB, TSSS RPT Operable	104/106	125	442	1175	0.32	0.30
LRNB, TSSS RPT Inoperable	104/106	131	574	1189	0.38	0.35
LRNB, TSSS RPT Inoperable end-of-cycle minus 20QO MWd/MTU	104/106	110	284	1168	0.05	0.05
FWCF, NSS RPT Operable	47/106	50	187	1010	0.12	0.11
FWCF, NSS RPT Inoperable	47/106	52	129	1020	0.15	0.14
FWCF, TSSS RPT Operable	47/106	51	110	1013	0.14	0.12
LOFH	N/A	N/A	N/A	N/A	0.09	0.09

## 5.2 Analyses For Reduced Flow Operation

Reference 9.3  
and 9.11

Limiting Transient: Recirculation Flow Increase

## 5.4 ASME Overpressurization Analysis

Reference 9.3  
and 9.11

Limiting Event

MSIV Closure

\*Normal scram speed (NSS) is based on measured plant scram insertion data, see Section 7.2.3.1.

Worst Single Failure

MSIV Position  
Scram Trip

Maximum Pressure

1315 psig

Maximum Steam Dome Pressure

1286 psig

## 5.5 Control Rod Withdrawal Error

Initial Control Rod Pattern for CRWE Analysis

Figure 5.1

<u>Rod Block Monitor Setting</u>	<u>Distance Withdrawn (ft)</u>	<u>ANF Fuel Delta-CPR</u>	<u>GE Fuel Delta-CPR</u>
106%*	5.0	0.17	0.21
107%	5.5	0.18	0.22
108%	6.0	0.20	0.23

## 5.6 Fuel Loading Error

	<u>With Loading Error</u>	<u>Correctly Loaded Core</u>
Maximum LHGR, kW/ft	16.2	13.4
Minimum MCPR	1.25	1.41

## 5.7 Determination Of Thermal Margins

Summary of Thermal Margin Requirements

All system transient results at the more limiting increased flow conditions (106%). LRWB results for the more limiting power (design basis condition - 104%) for this transient.

---

\*Rod Block Monitor Setting (RBM) of 106% for Cycle 4.

<u>Event</u>	<u>Equipment Operational Status</u>	<u>Delta CPR</u>		<u>MCPR Limit</u>		<u>Model</u>	
		<u>GE Fuel</u>	<u>ANF Fuel</u>	<u>GE Fuel</u>	<u>ANF Fuel</u>		
LRNB	RPT Operable, NSS	0.25	0.24	1.31	1.30	COTRANSA/XCOBRA-T	
LRNB	RPT Inoperable, NSS	0.32	0.29	1.38	1.35	"	"
LRNB	RPT Operable, TSSS	0.32	0.30	1.38	1.36	"	"
LRNB	RPT Inoperable, TSSS	0.38	0.35	1.44	1.41	"	"
LRNB	RPT Inoperable, TSSS, EOC -2000 MWd/MTU	0.05	0.05	1.11	1.11	"	"
FWCF	RPT Operable, NSS	0.12	0.11	1.18	1.17	"	"
FWCF	RPT Inoperable, NSS	0.15	0.14	1.21	1.20	"	"
FWCF	RPT Operable, TSSS	0.14	0.12	1.20	1.18	"	"
LOFH	N/A	0.09	0.09	1.15	1.15	XTGBWR	

Note: For cycle extension with reduced feedwater temperature, add 0.02 to delta CPR/MCPR LRNB and subtract 0.01 delta CPR/MCPR from FWCF transient results in the above table.

MCPR Operating Limits At Rated Condition For Cycle Exposures Less Than EOC -2000 MWd/MTU (100 To 106% Flow)

<u>Fuel Type</u>	<u>MCPR Limit (106% RBS)</u>
ANF	1.23
GE	1.27



MCPR Operating Limits At Rated Condition From EOC -2000 MWd/MTU To EOC (100 To 106% Flow) With Normal Feedwater Temperature

<u>Fuel Type</u>	<u>MCPR Limit</u>
ANF	1.30
GE	1.31

MCPR Operating Limits At Rated Condition Beyond All Rods Out With Reduced Feedwater Temperature (100 To 106% Flow And Thermal Coastdown) Point (EOC4)

<u>Fuel Type</u>	<u>MCPR Limit</u>
ANF	1.32
GE	1.33

MCPR Limits at Off-Rated Conditions

Figure 5.2  
and 5.3

Reduced Flow MCPR Limit

Reference 9.3  
and 9.11



6.0 POSTULATED ACCIDENTS6.1 Loss-Of-Coolant Accident6.1.1 Break Location Spectrum

Reference 9.4

6.1.2 Break Size Spectrum

Reference 9.4

6.1.3 MAPLHGR Analyses (ANF Fuel)

Reference 9.5

Limiting Break: Split Break in the Recirculation Suction Piping  
 With an Area Equal to Sixty Percent of the  
 Double-Ended Cross-Sectional Pipe Area

Bundle Average  
 Exposure  
 (MWd/MTM)

MAPLHGR  
 (kW/ft)

Peak Clad  
 Temperature, °F

Peak Local  
 MWR, %

0	13.0	1765	0.49
5,000	13.0	1766	0.48
10,000	13.0	1765	0.47
15,000	13.0	1772	0.47
20,000	13.0	1788	0.54
25,000	11.3	1699	0.34
30,000	9.4	1521	0.17
35,000	7.9	1397	0.10

6.2 Control Rod Drop Accident

Reference 9.7

Dropped Control Rod Worth, mK	8.9
Doppler Coefficient dk/kdT, 1/°F	$9.5 \times 10^{-6}$
Effective Delayed Neutron Fraction	0.0050
Four-Bundle Local Peaking Factor	1.26
Maximum Deposited Fuel Rod Enthalpy (cal/gm)	149



## 7.0 TECHNICAL SPECIFICATIONS

### 7.1 Limiting Safety System Settings

#### 7.1.1 MCPR Fuel Cladding Integrity Safety Limit

MCPR Safety Limit 1.06

#### 7.1.2 Steam Dome Pressure Safety Limit

Pressure Safety Limit 1346 psig

### 7.2 Limiting Conditions For Operation

#### 7.2.1 Average Planar Linear Heat Generation Rate Limits For ANF 8x8 Fuel

<u>Bundle Average Exposure (MWd/MTU)</u>	<u>MAPLHGR (kW/ft)</u>
0	13.0
5,000	13.0
10,000	13.0
15,000	13.0
20,000	13.0
25,000	11.3
30,000	9.4
35,000	7.9

These MAPLHGR limits are not impacted by the small enrichment change associated with ANF fuel loaded for Cycle 4. For single loop operation these limits also apply to ANF Fuel consistent with the flow dependent MCPR curve (1.35 at 50 percent of rated flow)

#### 7.2.2 Minimum Critical Power Ratio

Rated Condition MCPR Operating Limit Up To EOC -2000 MWd/MTU Exposure (100 To 106% Flow)

<u>Fuel Type</u>	<u>Limit (106% RBS)</u>
ANF	1.23
GE	1.27

Rated Conditions MCPR Operating Limits From EOC -2000 MWd/MTU To EOC (100% To 106% Flow)

<u>Fuel Type</u>	<u>Limit</u>
ANF	1.30
GE	1.31

Thermal Coastdown and FFTR Rated Condition MCPR Operating Limit Beyond All Rods Out Point With Reduced Feedwater Temperature (100% to 106% Flow)

<u>Fuel Type</u>	<u>Limit</u>
ANF	1.32
GE	1.33

Reduced Flow MCPR Limit (all cycle exposures)

Figures 5.2  
and 5.3

### 7.2.3 Surveillance Requirements

#### 7.2.3.1 Scram Insertion Time Surveillance

The ANF reload safety analyses were performed using the control rod insertion times shown below which are based on plant data. In the event that plant surveillance shows these scram insertion times may be exceeded, the plant thermal margin limits are to default to the values which correspond to the technical specification (TSSS) control rod scram times (see Section 5.7).

<u>Position Inserted From Fully Withdrawn</u>	<u>Average Rod Time In Seconds As Defined In Footnote*</u>
Notch 45	0.404
Notch 39	0.660
Notch 25	1.504
Notch 5	2.624

#### 7.2.3.2 Stability Surveillance

Core hydrodynamic stability analyses require slight modification to the Technical Specifications which preclude operation in specified power/flow regions. The results of these analyses support operation below a line defined by the following power/flow points: 42% Power/23.8% Flow, 46% Power/27.6% Flow and 65% Power/45% Flow (see Section 4.2.4).

Surveillance requirements remain unchanged for Cycle 4, e.g., surveillance is required when operating in a power flow region above the 80% rod line and less than 45% core flow.

#### 7.2.3.3 Technical Specification LHGR Surveillance

The Technical Specification linear heat generation rate (LHGR) limit versus average planar exposure for ANF 8x8 reload fuel is shown in Figure 7.1. This figure was developed from information contained in Reference 9.1, and the region of permissible operation is shown.

---

\*Slowest measured average control rod insertion time to specified notches for each group of four control rods arranged in a 2x2 array.

TABLE 4.1 NEUTRONIC DESIGN VALUES

Fuel Pellet

Fuel Material	UO <sub>2</sub> Sintered Pellets
Density, g/cc	10.36
% of T.D.	94.5
Diameter, inch	
Enriched Fuel	0.4055
Natural Fuel	0.4045

Fuel Rod

Fuel Length, inch	150
Cladding Material	Zircaloy-2
Clad, I.D., inch	0.414
Clad, O.D., inch	0.484

Fuel Assembly

Number of Fuel Rods	62
Number of Inert Water Rods	2
Fuel Rod Enrichments	Figure 4.1
Fuel Rod Pitch, inch	0.641
Fuel Assembly Loading, kgU	176.0




TABLE 4.1 NEUTRONIC DESIGN VALUES  
(Continued)Core Data

Number of Fuel Assemblies	764
Rated Thermal Power, MW	3323
Rated Core Flow, Mlbm/hr	108.5
Core Inlet Subcooling, Btu/lbm	19.0
Reactor Pressure, psia	1008.0
Channel Thickness, inch	0.100
Fuel Assembly Pitch, inch	6.00
Water Gap Thickness (symmetric), inch	0.522

Control Rod Data

Absorber Material	B <sub>4</sub> C
Total Blade Span, inch	9.75
Total Blade Support Span, inch	1.58
Blade Thickness, inch	0.260
Blade Face-To-Face Internal Dimension, inch	0.200
Absorber Rods Per Blade	76
Absorber Rod Outside Diameter, inch	0.188
Absorber Rod Inside Diameter, inch	0.138
Absorber Density, % of Theoretical	70.0



18

ANF-88-02

Figure 3.1 Radial Power Histogram For 1/4 Core Safety Limit Model

LL 0.93	L 0.95	ML 1.02	M 1.06	M 1.06	ML 1.02	L 0.95	LL 0.92
L 0.95	ML 0.97	H 1.08	ML 0.87	H 1.04	H 1.07	M 1.04	L 0.95
ML 1.02	H 1.08	H 1.01	H 1.00	H 0.98	H 1.00	ML 0.90	ML 1.02
M 1.06	ML 0.87	H 1.00	W 0.00	M 0.90	H 0.97	H 1.03	M 1.06
M 1.06	H 1.04	H 0.98	M 0.90	W 0.00	H 0.99	M 0.93	M 1.05
ML 1.02	H 1.07	H 1.00	H 0.97	H 0.99	H 1.00	H 1.06	M 1.08
L 0.95	M 1.04	ML 0.90	H 1.03	M 0.93	H 1.06	ML 0.96	ML 1.07
LL 0.92	L 0.95	ML 1.02	M 1.06	M 1.05	M 1.08	ML 1.07	L 1.03

Figure 3.2 WNP-2 Cycle 4 Safety Limit Local Peaking Factors  
(ANF XN-3 Fuel)

LL 0.95	L 0.96	ML 1.00	M 1.03	M 1.03	ML 1.00	L 0.96	LL 0.95
L 0.96	ML 0.98	H 1.05	ML 0.92	H 1.03	H 1.05	M 1.02	L 0.96
ML 1.00	H 1.05	H 1.02	H 1.01	H 1.00	H 1.01	ML 0.94	ML 1.00
M 1.03	ML 0.92	H 1.01	W 0.00	M 0.93	H 1.00	H 1.03	M 1.03
M 1.03	H 1.03	H 1.00	M 0.93	W 0.00	H 1.00	M 0.97	M 1.03
ML 1.00	H 1.05	H 1.01	H 1.00	H 1.00	H 1.02	H 1.05	M 1.04
L 0.96	M 1.02	ML 0.94	H 1.03	M 0.97	H 1.05	ML 0.97	ML 1.03
LL 0.95	L 0.96	ML 1.00	M 1.03	M 1.03	M 1.04	ML 1.03	L 1.00

Figure 3.3 WNP-2 Cycle 4 Safety Limit Local Peaking Factors  
(ANF XN-1, -2 Fuel)

*****																
*****																
*****	:	LL	:	L	:	ML	:	M	:	M	:	ML	:	L	:	LL
*****	:		:		:		:		:		:		:		:	
*****	:	L	:	ML	:	H	:	ML*	:	H	:	H	:	M	:	L
*****	:		:		:		:		:		:		:		:	
*****	:	ML	:	H	:	H	:	H	:	H	:	H	:	ML*	:	ML
*****	:		:		:		:		:		:		:		:	
*****	:	M	:	ML*	:	H	:	W	:	M	:	H	:	H	:	M
*****	:		:		:		:		:		:		:		:	
*****	:	M	:	H	:	H	:	M	:	W	:	H	:	M	:	M
*****	:		:		:		:		:		:		:		:	
*****	:	ML	:	H	:	H	:	H	:	H	:	H	:	H	:	M
*****	:		:		:		:		:		:		:		:	
*****	:	L	:	M	:	ML*	:	H	:	M	:	H	:	ML*	:	ML
*****	:		:		:		:		:		:		:		:	
*****	:	LL	:	L	:	ML	:	M	:	M	:	M	:	ML	:	L
*****	:		:		:		:		:		:		:		:	

LL RODS ( 3) --- 1.50 W/O U235  
 L RODS ( 7) --- 1.94 W/O U235  
 ML RODS ( 9) --- 2.50 W/O U235  
 M RODS (16) --- 2.86 W/O U235  
 H RODS (22) --- 3.43 W/O U235  
 ML\* RODS ( 5) --- 2.50 W/O U235 + 2.00 W/O GD203  
 W RODS ( 2) --- INERT WATER ROD

Figure 4.1 WNP-2 Cycle 4 Enriched Zone Enrichment Distribution

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	C	B	D	B	C	B	D	B	C	B	D	B	C	D	A
2	B	E	B	F	B	F	B	F	B	F	C	E	B	F	A
3	D	B	D	B	D	C	D	B	D	B	D	C	D	C	B
4	B	F	B	C	B	F	B	F	B	F	B	E	B	F	A
5	C	B	D	B	F	B	D	B	D	C	D	C	D	C	B
6	B	F	C	F	B	C	B	F	B	F	B	F	B	F	A
7	D	B	D	B	D	B	F	B	D	C	C	C	D	B	B
8	B	F	B	F	B	F	B	D	B	F	B	F	B	A	
9	C	B	D	B	D	B	D	B	E	C	D	D	A		
10	B	F	B	F	C	F	C	F	C	D	B	A	B		
11	D	C	D	B	D	B	C	B	D	B	C				
12	B	E	C	E	C	F	C	F	D	A					
13	C	B	D	B	D	B	D	B	A	B					
14	D	F	C	F	C	F	B	A							
15	A	A	B	A	B	A	B								

<u>Fuel Type</u>	<u>Number of Assemblies</u>	<u>Description</u>
A	56	GE 8x8 Type II 1.76 w/o U-235 (Cycle 1)
B	280	GE 8x8 Type III 2.19 w/o U-235 (Cycle 1)
C	128	ANF 8x8 2.72 w/o U-235 (Cycle 2)
D	148	ANF 8x8 2.72 w/o U-235 (Cycle 3)
E	24	ANF 8x8 2.72 w/o U-235 (Cycle 4)
F	128	ANF 8x8 2.64 w/o U-235 (Cycle 4)

Figure 4.2 WNP-2 Cycle 4 Reference Loading Pattern by Fuel Type  
(One Quarter of Symmetrical Core Loading)

	2	6	10	14	18	22	26	30	34	38	42	46	50	54	58	
59					--	--	--	--	--	--	--					59
55				--	--	00	--	36	--	00	--	--				55
51			--	--	--	--	--	--	--	--	--	--	--			51
47		--	--	24	--	18	--	00	--	18	--	24	--	--		47
43	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	43
39	--	00	--	18	--	00	--	24	--	00	--	18	--	00	--	39
35	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	35
31	--	36	--	00	--	24	--	12	--	24	--	00	--	36	--	31
27	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	27
23	--	00	--	18	--	00	--	24	--	00*	--	18	--	00	--	23
19	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	19
15		--	--	24	--	18	--	00	--	18	--	24	--	--		15
11			--	--	--	--	--	--	--	--	--	--	--			11
7				--	--	00	--	36	--	00	--	--				7
3					--	--	--	--	--	--	--					3
	2	6	10	14	18	22	26	30	34	38	42	46	50	54	58	

\* Control Rod Being Withdrawn  
 Rod Position in Notches Withdrawn  
 Full in = 00  
 Full Out = --

Figure 5.1 WNP-2 Cycle 4 Control Rod Withdrawal Analysis  
 Initial Control Rod Pattern




Figure 5.2 Reduced Flow MCPR Operating Limit For Normal Feedwater Temperature






Figure 5.3 Reduced Flow MCPR Operating Limit For FFTR Operation




Figure 7.1 Linear Heat Generation Rate (LHGR) Limit Versus Average Planar Exposure, ANF 8x8 Fuel

## 9.0 ADDITIONAL REFERENCES

- 9.1 S. F. Gaines, "Generic Mechanical Design for Exxon Nuclear Jet Pump BWR Reload Fuel," XN-NF-81-21(A), Revision 1, Exxon Nuclear Company, Inc., Richland, WA 99352, January 1982.
- 9.2 R. H. Kelley, "Exxon Nuclear Plant Transient Methodology for Boiling Water Reactors," XN-NF-79-71(P), Revision 2, Exxon Nuclear Company, Inc., Richland, WA 99352, November 1981.
- 9.3 J. E. Krajicek, "WNP-2 Cycle 4 Plant Transient Analysis," ANF-88-01, Advanced Nuclear Fuels Corporation, Richland, WA 99352, January 1988.
- 9.4 J. E. Krajicek, "LOCA Break Spectrum for a BWR 5," XN-NF-85-138(P), Exxon Nuclear Company, Inc., Richland, WA 99352, December 1985.
- 9.5 D. J. Braun, "WNP-2 LOCA-ECCS Analysis, MAPLHGR Results," XN-NF-85-139, Exxon Nuclear Company, Inc., Richland, WA 99352, December 1984.
- 9.6 M. H. Smith, "Generic Mechanical Design for Exxon Nuclear Jet Pump BWR Reload Fuel," XN-NF-81-21(P), Revision 1, Supplement 1, Exxon Nuclear Company, Inc., Richland, WA 99352, March 1985.
- 9.7 "Exxon Nuclear Methodology for Boiling Water Reactors-Neutronics Methods for Design and Analysis," XN-NF-80-19(A), Volume 1 and Supplements, Exxon Nuclear Company, Inc., Richland, WA 99352, May 1980.
- 9.8 "Generic Mechanical Design for Exxon Nuclear Jet Pump BWR Reload Fuel," XN-NF-85-67(A), Revision 1, Exxon Nuclear Company, Inc., Richland, WA 99352, September 1986.
- 9.9 "Exxon Nuclear Methodology for Boiling Water Reactors Neutronics Methods for Design Analysis," XN-NF-80-19(A), Volume 1, Supplements 1 and 2, Exxon Nuclear Company, Inc., Richland, WA 99352, March 1983.
- 9.10 J. B. Edgar, Letter to WPPSS, Supplemental Licensing Analysis Results, ENWP-86-0067, Exxon Nuclear Company, Inc., Richland, WA 99352, April 15, 1986.
- 9.11 J. E. Krajicek, "WNP-2 Plant Transient Analysis With Final Feedwater Temperature Reduction," XN-NF-87-92, Advanced Nuclear Fuels Corporation, Richland, WA 99352, June 1987.

## APPENDIX A

Single Loop Operation  
(SLO)

ANF recently performed analyses for WNP-2 which demonstrate the safety of plant operation with a single recirculation loop out of service for an extended period of time. These analyses were performed for the most limiting transient events, the pump seizure accident and the loss-of-coolant-accident (LOCA) for the maximum extended power state during WNP-2 single loop operation (SLO). The results of the SLO analyses are summarized below:

- o The two loop MCPR operating limits (rated conditions) bound the transient requirements for SLO. The single loop transient analyses need not be performed on a cycle by cycle basis and the two loop MCPR operating limits applicable for a cycle are appropriate for single loop conditions for that cycle.
- o The postulated pump seizure accident, evaluated for SLO conditions, is calculated to have a less severe radiological release than the LOCA. The radiological consequences of this postulated accident are bounded by the radiological evaluation performed by General Electric (GE) for the LOCA and are well within the 10 CFR 100 limits.
- o The single loop ECCS analysis supports the use of the WNP-2 two loop MAPLHGR limits for ANF fuel when the reactor is operating in the SLO mode consistent with the flow dependent MCPR curve (1.35 at 50 percent of rated flow). Single loop operation of WNP-2 with the two loop ANF fuel MAPLHGR limits assures that the emergency core cooling systems for the WNP-2 plant will meet the U.S. NRC acceptance criteria of 10 CFR 50.46 for loss-of-coolant accident breaks up to and including the double-ended severance of a reactor coolant pipe.

The transient and pump seizure accident analyses are described in ANF-87-119

and the LOCA analyses are described in ANF-87-118.

With a single recirculation loop in operation, the GE analyses supported continued operation with an increase of 0.01 in the MCPR safety limit. ANF performed a single loop MCPR safety limit calculation and found that less than one tenth of one percent of the rods to be in boiling transition which supports a MCPR safety limit of 1.07. Because of the similarity between the ANF and GE fuel types making up the core, and because of the similarity in the magnitude of the uncertainties which determine the MCPR safety limit, this small increase in the safety limit value can be used for operation with ANF fuel and single loop analyses. For Cycle 4 operation with both recirculation loops in operation, the MCPR safety limit is 1.06, which is the same value as was used for the previous cycles. For Cycle 4 operation with a single recirculation-loop-in-service, the MCPR safety limit is 1.07, which is at the same value used for the previous cycles.

WNP-2 CYCLE 4 RELOAD ANALYSIS

Distribution:

O. C. Brown  
R. E. Collingham  
R. A. Copeland  
L. J. Federico  
M. J. Hibbard  
J. G. Ingham  
S. E. Jensen  
T. H. Keheley  
J. E. Krajicek  
J. L. Maryott  
J. N. Morgan  
J. C. Rawlings (ENSA)  
A. Reparaz  
G. L. Ritter  
J. R. Tandy  
H. E. Williamson

J. B. Edgar/WPPSS (50)  
Document Control (5)



.9003080150

**SUPPLY SYSTEM/NRC - REGION V MANAGEMENT MEETING**  
**JANUARY 18, 1990**  
**WALNUT CREEK, CA**

**AGENDA**

<b>I.</b>	<b>INTRODUCTION</b>	<b>D. W. MAZUR</b>	<b>5 MIN</b>
<b>II.</b>	<b>SALP STATUS</b>		
	<b>* OVERVIEW OF OPERATIONS ACTIVITIES</b>	<b>C. M. POWERS</b>	<b>5 MIN</b>
	<b>* MAINTENANCE</b>	<b>R. L. WEBRING</b>	<b>60 MIN</b>
	<b>* OPERATIONS</b>	<b>C. M. POWERS</b>	<b>30 MIN</b>
	<b>* ENGINEERING TECHNICAL SUPPORT</b>	<b>J. P. BURN</b>	<b>30 MIN</b>
	<b>* SAFETY ASSESSMENT/ QUALITY VERIFICATION</b>	<b>G. D. BOUCHEY</b>	<b>30 MIN</b>
<b>III.</b>	<b>FASTENER ISSUES</b>	<b>C. M. POWERS</b>	<b>15 MIN</b>
<b>IV.</b>	<b>SUMMARY</b>	<b>A. L. OXSEN</b>	<b>10 MIN</b>



## **OPERATIONS**

- \* MAINTENANCE ENHANCEMENT PROGRAM**
- \* TECH SPEC IMPROVEMENT PROGRAM**
- \* TECHNICAL SUPPORT**
- \* RADIOLOGICAL WORK PRACTICES/EFFLUENT MONITORING ISSUE**
- \* ADHERENCE TO PROCEDURES**
- \* EQUIPMENT OPERABILITY DETERMINATIONS**

## **WNP-2 MAINTENANCE INITIATIVES**

### **\* DRIVEN BY:**

- NRC CONCERNS (SALP/SSOMI REPORTS)**
  - o PROCEDURAL INADEQUACIES AND WEAKNESS RESULTING IN OVER-RELIANCE ON "SKILL OF THE CRAFT"**
  - o WORK CONTROL PROCESS INADEQUACIES - DETAIL, CONTENT, RIGOR AND COMPLIANCE**
  - o PLANT MATERIEL CONDITION INCLUDING WORK BACKLOG/DEFERRAL OF LONG-TERM CORRECTIVE MAINTENANCE**

## **WNP-2 MAINTENANCE INITIATIVES**

- **SUPPLY SYSTEM MANAGEMENT PERSPECTIVE  
(FEEDBACK FROM INTERNAL AUDITS AND  
CONTRACTED AUDITORS) INCLUDING:**
  - o **SUPPLY SYSTEM QA MAINTENANCE  
ASSESSMENT**
  - o **INPO EVALUATION REPORT**
  - o **SUPPLY SYSTEM CONTRACTED AUDITS  
(IMPELL AND HARE)**
  - o **MAINTENANCE SELF-ASSESSMENT**
  - o **INCREASED EXPECTATIONS FOR  
MAINTENANCE BASED ON INDUSTRY  
TRENDS**
- **PERFORMANCE DURING AND FOLLOWING THE  
SPRING, 1989 OUTAGE**
  - o **SHUTDOWN COOLING ISOLATIONS**
  - o **REACTOR SCRAM RESULTING FROM  
PERSONNEL ERROR - 8/17/89**
  - o **OTHER PERSONNEL/PROCEDURE  
RELATED ERRORS**

## **WNP-2 MAINTENANCE INITIATIVES**

### **\* CONCLUSIONS:**

- GENERAL CONSENSUS OF EVALUATION FINDINGS**
- NEED FOR IMPROVEMENT IN THOSE AREAS IDENTIFIED BY SALP/SSOMI**
- ADDITIONAL ISSUES FOR IMPROVEMENT INCLUDE:**
  - o EXCESSIVE CONTROL ROOM DEFICIENCIES**
  - o PREVENTIVE MAINTENANCE PROGRAM**
  - o TRENDING OF EQUIPMENT FAILURES**
  - o MAINTENANCE TRAINING**
  - o CRAFT TASK ASSIGNMENT AND COORDINATION OF WORK ACTIVITIES**

- \* FUNDING HAS BEEN ALLOCATED FOR THIS FISCAL YEAR AND IS PLANNED FOR FUTURE BUDGET CYCLES**



## PROCEDURE UPGRADE PLAN

### \* GOALS/OBJECTIVES

- IMPROVE EXISTING PROCEDURES:
  - CONTENT/LEVEL OF DETAIL
  - TECHNICAL ACCURACY
  - SETPOINTS/TOLERANCES
  - TOOLING/TEST EQUIPMENT REQUIREMENTS
  - WORKING CONDITIONS AND LIMITATIONS
- IDENTIFY AND DEVELOP NEW PROCEDURES
- INCORPORATE LESSONS LEARNED
- INCORPORATE IN A COMMON FORMAT --  
OTHER DEPARTMENTS AND INPO GUIDELINES
- IMPROVE "HUMAN FACTORS" ELEMENT
- INSTITUTE A VALIDATION AND  
VERIFICATION REVIEW - ALL  
PROCEDURES

## PROCEDURE UPGRADE PLAN

### \* STAFFING STATUS

- FULL STAFFING:  
1 SUPERVISOR AND 7 + WRITERS
- CURRENTLY:  
1 SUPERVISOR AND 4 WRITERS
- COMPRISED OF MAINTENANCE/  
CONTRACT ENGINEERS AND  
TECHNICIANS
- FULL STAFFING BY 3/1/90 ALONG  
WITH COMPLETION OF FACILITY
- STAFF ASSIGNMENTS WILL BE FULL  
TIME INCLUDING OUTAGES

## **PROCEDURE UPGRADE PLAN**

### **\* SCHEDULE**

- UPGRADES COMPLETE 1ST QUARTER 1992**
- PRIORITY ASSIGNED TO PREVIOUSLY IDENTIFIED CRITICAL AREAS (RCA/LEs/NOV)**
- PROCEDURES CRITICAL TO PLANNED PLANT EVOLUTIONS GIVEN PRIORITY (EG. EXCESS FLOW CHECK VALVE TESTING)**
- SURVEILLANCES UPGRADED IN CONJUNCTION WITH THE TECH SPEC IMPROVEMENT PROGRAM**



## **PROCEDURE UPGRADE PLAN**

### **\* TO DATE**

- A REVERIFICATION HAS BEEN CONDUCTED TO ENSURE EACH TECH SPEC SURVEILLANCE REQUIREMENT HAS BEEN MET - NO DISCREPANCIES WERE IDENTIFIED**
- DETAILED REVIEWS OF SELECTED SURVEILLANCE PROCEDURES BY THE SUPPLY SYSTEM SSFI TEAM HAVE DETERMINED THAT TECH SPEC REQUIREMENTS ARE ADEQUATELY ADDRESSED AND DOCUMENTED.**

**PROCEDURE WRITER'S GUIDE/HUMAN FACTORS PLAN FOR WNP-2**

**\* SHORT TERM - UTILIZE THE MAINTENANCE PROCEDURE  
WRITER'S GUIDE WHICH INCORPORATES  
INPO GUIDELINES**

- PROVIDE EACH WRITER WITH HUMAN FACTORS  
PRINCIPLE'S TRAINING**
- PROVIDE EACH WRITER WITH TRAINING ON THE  
EXISTING WRITER'S GUIDE**

**PROCEDURE WRITER'S GUIDE/HUMAN FACTORS PLAN FOR WNP-2**

**\* LONG TERM - DEVELOP AND IMPLEMENT THE WNP-2  
WRITER'S GUIDE**

- **APPLICABLE TO MAINTENANCE AND OPERATIONS  
WITH SOME DEPARTMENT-SPECIFIC GUIDELINES**
- **COMPLETE AND AVAILABLE FOR USE BY 4/1/90**
- **UTILIZE LESSONS LEARNED FROM INDUSTRY EOP  
AUDITS AND UPGRADE PROCESS**
- **ESTABLISH METHODOLOGY FOR PERFORMING  
VERIFICATION AND VALIDATION OF PLANT  
PROCEDURES**
- **WILL HELP TO ENSURE:**
  - TECHNICAL ACCURACY**
  - INCORPORATION OF HUMAN FACTORS PRINCIPLES**
  - PROCEDURE USEABILITY**
  - OPERATIONAL CORRECTNESS**

## **PROCEDURE COMPLIANCE**

### **\* I & C SURVEILLANCE EFFORT, R-4 TO PRESENT**

- CRITICAL SURVEILLANCES INITIALLY LIMITED TO SPECIFIC CRAFT**
- FULL TIME SUPERVISION OF CRITICAL SURVEILLANCES**
- IN-DEPTH REVIEW OF SURVEILLANCE PRACTICES**
- INTERVIEWS OF CRAFT, SUPERVISION, ENGINEERS**
- DEVELOPED A DETAILED SURVEILLANCE WORK PRACTICE DOCUMENT**
- TRAINING CONDUCTED BY THE I & C SUPERVISOR WITH EACH TECHNICIAN**
- ELIMINATED REQUIREMENT FOR FULL-TIME SUPERVISION OF SURVEILLANCE ACTIVITIES**

## **PROCEDURE COMPLIANCE**

### **\* IMPROVED PROCEDURES**

- TECHNICIAN FEEDBACK ON PROCEDURAL INADEQUACIES HAS INCREASED DRAMATICALLY**
- TECHNICIANS UNWILLING TO "MAKE" A PROCEDURE WORK - REQUIRING DEVIATIONS OR REVISIONS TO REMOVE ERRORS**
- PROCEDURE IMPROVEMENTS INCLUDE HUMAN FACTOR ELEMENTS**



## **PROCEDURE COMPLIANCE**

### **\* DISCIPLINE FOR COMPLIANCE PROBLEMS**

- DISCIPLINE INCLUDING TIME OFF WITHOUT PAY, PERSONNEL LETTERS ON FILE AND LIMITATIONS ON WORK ASSIGNMENTS HAVE BEEN ENACTED**
- DRIVEN HOME THE MESSAGE OF PROCEDURAL COMPLIANCE**

## **PREVENTIVE MAINTENANCE PROGRAM UPGRADE**

### **\* PHASE I REVIEW**

#### **- GOALS AND OBJECTIVES**

- o COORDINATE PM ACTIVITIES WITH ONGOING CORRECTIVE MAINTENANCE**
- o MINIMIZE INEFFICIENCIES IN THE EXISTING PM PROGRAM**
- o ELIMINATE MULTIPLE VISITS TO COMPONENTS**
- o ELIMINATE TIME DEPENDENT ACTIVITIES THROUGH CONDITION MONITORING**
- o SUPPORT THE PHASE II EFFORT IN IMPLEMENTATION**
- o DEVELOP SUPPLY SYSTEM READINESS TO CONTINUE RCM APPLICATION AT CONTRACT END**
- o PROVIDE ENGINEERING SUPPORT OF THE PHASE II EFFORT VIA PERFORMING THE PRA ANALYSES OF PLANT SYSTEMS**
- o ESTABLISH A SUPPLY SYSTEM REVIEW TEAM**



## **PREVENTIVE MAINTENANCE PROGRAM UPGRADE**

### **\* PHASE I REVIEW**

#### **- STAFFING**

- o FULL STAFFING LEVEL:  
1 SUPERVISOR AND 4 REVIEWERS**
- o CURRENT STAFFING:  
1 SUPERVISOR AND 3 REVIEWERS**
- o COMPRISED OF MAINTENANCE/CONTRACT  
ENGINEERS AND SELECTED CRAFT  
PERSONNEL**
- o FULL STAFFING BY 3/1/90**
- o STAFF ASSIGNMENTS WILL BE FULL TIME**
- o EFFORT WILL CONTINUE FOR A MINIMUM  
OF 2 YEARS**



## **PREVENTIVE MAINTENANCE PROGRAM UPGRADE**

### **\* PHASE II REVIEW**

#### **- GOALS AND OBJECTIVES**

- o IMPROVE THE EFFICIENCY AND EFFECTIVENESS OF APPLIED MAINTENANCE EFFORTS**
- o REDUCE PROGRAM SCOPE THROUGH DIRECTED EFFORTS AT CRITICAL COMPONENTS WHERE PERFORMANCE CAN BE INFLUENCED BY PM OR WHERE FAILURE MEASURABLY IMPACTS PLANT SAFETY OR AVAILABILITY**

# **PREVENTIVE MAINTENANCE PROGRAM UPGRADE**

## **\* PHASE II REVIEW**

### **- RELIABILITY CENTERED MAINTENANCE APPROACH**

- o EVALUATION OF ALL WNP-2 SYSTEMS**
- o APPLY RCM TO SELECTED SYSTEMS**
- o UTILIZE SYSTEM PRA ANALYSES,  
EQUIPMENT HISTORY, INDUSTRY  
HISTORY, PLANT ENVIRONMENTAL  
AND SERVICE CONDITIONS, SAFETY  
SIGNIFICANCE AND VENDOR  
RECOMMENDATIONS TO DEVELOP  
COMPONENT RECOMMENDATIONS**
- o DEVELOP REVISED PROGRAM FOR  
PLANNED MAINTENANCE, CONDITION  
MONITORING, COMPONENT  
REPLACEMENT, AND IDENTIFY  
RECOMMENDED DESIGN CHANGES**
- o DEVELOP PROCEDURES TO SUPPORT  
RECOMMENDED ACTIVITIES**
- o DEVELOP A LIVING RCM PROGRAM TO  
BE CONDUCTED BY THE SUPPLY SYSTEM**

## **PREVENTIVE MAINTENANCE PROGRAM UPGRADE**

### **\* PHASE II REVIEW**

#### **- SCHEDULE**

- o PRE-SELECTION OF 5 POTENTIAL CONTRACTORS FROM A FIELD OF 17 COMPLETED**
- o REQUEST FOR PROPOSALS TO BE ISSUED 1/19/90**
- o NEGOTIATIONS AND RECOMMENDATIONS FOR AWARD IN MARCH, 1990**
- o CONTRACT AWARD SCHEDULED FOR APRIL**
- o MOBILIZATION ON SITE AS EARLY AS MAY**
- o RCM REVIEW PERIOD APPROXIMATELY 2 YEARS**

## PREVENTIVE MAINTENANCE PROGRAM UPGRADE

### \* PHASE II REVIEW

#### - STAFFING

- o 7 MEMBER SELECTION PANEL APPOINTED  
TO GUIDE PROCUREMENT
- o PHASE I STAFF IN PLACE TO SUPPORT  
CONTRACT EFFORTS
- o SUPPLY SYSTEM ENGINEERING CURRENTLY  
WORKING ON WNP-2 PRA ANALYSES
- o CONTRACTOR STAFFING TO INCLUDE A  
MINIMUM OF 15 PEOPLE



## **WORK PROCESS IMPROVEMENTS**

### **\* APPROACH**

- ASSIGNMENT OF A MAINTENANCE SUPERVISOR, FULL TIME FOR 3+ MONTHS**
- REVIEW OF THE PROCESS FOR 5 OTHER UTILITIES**
- REVIEW CONCERNS OF NRC/INPO/INTERNAL AUDITS**
- CONSIDERED KNOWN INEFFICIENCIES COMMON TO WNP-2 USERS**





## **WORK PROCESS IMPROVEMENTS**

### **\* GOALS**

- REDUCE DEPENDENCY ON "SKILL OF THE CRAFT"**
- IMPROVE PACKAGE CLARITY - AVOID MISUNDERSTANDINGS**
- ADDRESS HUMAN FACTORS PRINCIPLES IN PACKAGING**
- ACHIEVE INCREASED CRAFT ACCOUNTABILITY**
- DEVELOP COMMONALITY OF CONTENT AND FORMAT**
- IMPROVE WORK DOCUMENTATION AND FEEDBACK FROM CRAFT PERSONNEL**
- INCREASE EFFICIENCY IN WORK IMPLEMENTATION THROUGH MORE ACCURATE DETAILED INSTRUCTIONS TO THE CRAFT**

## **WORK PROCESS IMPROVEMENTS**

### **\* WORK PACKAGING AND TRAINING**

- DEVELOP STANDARDS FOR PACKAGES (EG. TOOLING, PARTS, SETPOINTS, TOLERANCES, SETTINGS)**
- REQUIRE PARTS STAGING AND DOCUMENT INCORPORATION INTO EACH PACKAGE.**
- UTILIZE A COMMON FORMAT TO ASSIST IN THE REVIEW AND IMPLEMENTATION OF THE PACKAGE**
- DEVELOP AND IMPLEMENT A TRAINING PROGRAM PRIOR TO IMPLEMENTATION**

## **WORK PROCESS IMPROVEMENTS**

### **\* TRANSITION TO COMPUTER DEVELOPED PACKAGES**

- ONE SHOP CURRENTLY CONVERTING TO PC DEVELOPED PACKAGES**
- NEW PROCESS BEING DEVELOPED TO COMPLEMENT PC DEVELOPED PACKAGES**
- REMAINING MAINTENANCE SHOPS WILL CONVERT TO PC DEVELOPED PACKAGES WITHIN THE YEAR**

## **WORK PROCESS IMPROVEMENTS**

### **\* SCHEDULE**

- PROCEDURE DRAFT BY THE END OF JANUARY 1990**
- PROCEDURE POC APPROVAL BY MID FEBRUARY 1990**
- TRAINING COMPLETE AND IMPLEMENT BY MARCH 1990**



## **WORK CONTROL PROGRAM**

### **\* GOALS**

- IMPLEMENT A "DEMAND SCHEDULE" SUPPORTING GOALS, NEEDS AND PRIORITIES OF THE PLANT**
- IMPLEMENT AN EFFECTIVE "WORK COORDINATION FUNCTION" TO SUPPORT DEMAND SCHEDULE**





## **WORK CONTROL PROGRAM**

- \* IMPROVE THE "READY TO WORK" PROCESS**
  - INCREASE COMMITMENT AND ACCOUNTABILITY FOR WORK PACKAGE PREPARATION**
  - INCREASE EMPHASIS WITHIN SUPPORT ORGANIZATIONS FOR ACHIEVING "READY TO WORK" STATUS**

## **WORK CONTROL PROGRAM**

### **\* COORDINATION IMPROVEMENT**

- IMPROVE METERING OF WORK TO THE CONTROL ROOM -  
DECREASE CHALLENGES TO PLANT**
- DEVELOP MANAGEMENT FEEDBACK**
- INCREASE ACCOUNTABILITY ACROSS DISCIPLINES**
- INCREASE COORDINATION BETWEEN MAINTENANCE AND  
SUPPORT ORGANIZATIONS**
- HELP ELIMINATE BARRIERS WHICH SLOW OR STOP  
PLANNED WORK**

## **WORK CONTROL PROGRAM**

### **\* ORGANIZATION STRUCTURE AND STAFFING**

- CHARTERED IN DECEMBER, 1989**
- IMPLEMENT IN FEBRUARY, 1990**
- NEW GROUP WITH A FULL TIME SUPERVISOR IN THE PLANNING & SCHEDULING DEPARTMENT**
- TOTAL OF 9 MEMBERS, AT LEAST 6 IN A FULL TIME STATUS**
- INITIALLY HEADED BY THE ASSISTANT OPERATIONS MANAGER**
- STAFFED BY HAND-PICKED INDIVIDUALS FROM EACH DEPARTMENT, INCLUDING THOSE WHO CURRENTLY HOLD SUPERVISORY POSITIONS**

## **WORK CONTROL PROGRAM**

### **\* REQUESTED INPO ASSISTANCE**

- SS REQUESTED AN INPO ASSIST VISIT DIRECTED AT WORK CONTROL**
- TEAM WILL BE ON-SITE THE FIRST OF FEBRUARY**
- GOAL TO OBTAIN CRITICAL AND TIMELY COUNSELING DURING THE START-UP PHASE OF THIS EFFORT**

**DEFERRAL OF LONG TERM CORRECTIVE MAINTENANCE/  
PLANT MATERIEL CONDITION/BACKLOG REDUCTION**

**\* CORRECTION OF LONG STANDING ISSUES**

- MSIV GALLING REPAIRS COMPLETE  
IN SPRING 1990 OUTAGE**
- SRV VACUUM BREAKER LEAKAGE  
REPAIRED, CONTAINMENT  
UNIDENTIFIED LEAKAGE BELOW  
.5 GPM**
- SRV REBUILD PROGRAM ONGOING  
WITH COMPLETION PLANNED IN  
1991**
- REPLACEMENT OF THE RILEY LEAK  
DETECTION MODULES IN 1989**
- REPLACEMENT OF ALL MAIN  
TURBINE LOW PRESSURE ROTORS  
IN 1991**



**DEFERRAL OF LONG TERM CORRECTIVE MAINTENANCE/  
PLANT MATERIEL CONDITION/BACKLOG REDUCTION**

**\* ATTENTION TO GENERIC CONCERNS**

- INITIATING A LIVE-LOAD VALVE  
PACKING PROGRAM IN  
CONTAINMENT IN 1990**
- MOV UPGRADE PROGRAM ONGOING  
FOR ALL PLANT MOVs**
- MOV DESIGN BASIS TESTING  
PROGRAM UNDERWAY -  
GENERIC LETTER 89-10**
- CRD HCU VALVE REFURBISHMENT  
EFFORT BEGINNING IN 1990**





**DEFERRAL OF LONG TERM CORRECTIVE MAINTENANCE/  
PLANT MATERIEL CONDITION/BACKLOG REDUCTION**

**\* ONGOING ISSUES**

- SEMI-ANNUAL PLANT CLEANUP  
EFFORT ESTABLISHED**
- BACKLOG REDUCTION PROGRAM  
INSTITUTED FOR MWRs/PMs**
- INCREASED VISIBILITY OF  
LONG STANDING PROBLEMS  
THROUGH THE PLANT WEEKLY  
REPORT**
- ONGOING PAINTING PROGRAM**

## **WNP-2 EQUIPMENT TRENDING PROGRAMS**

### **\* PERFORMANCE MONITORING**

- **ON-GOING PROGRAM SHARED BETWEEN  
PLANT TECHNICAL/PLANT MAINTENANCE**
- **BASED ON VIBRATION MONITORING,  
OIL ANALYSIS, TRENDING  
OPERATIONAL PARAMETERS,  
THERMOGRAPHY, MOVATS**
- **PROVIDES HISTORY FOR TECH  
SPEC/ASME COMPONENT TRENDS**
- **PROVIDES A HISTORY OF  
SELECTED PLANT COMPONENT  
OPERATIONAL PARAMETERS AT  
GIVEN FREQUENCIES**
- **HELPS IDENTIFY PROBLEMS  
BEFORE THE FAILURE STAGE  
IS REACHED**

## WNP-2 EQUIPMENT TRENDING PROGRAMS

### \* EQUIPMENT FAILURE TRENDING

- NEWLY INSTITUTED IN MAINTENANCE
- PERFORMED ON A 6 MONTH FREQUENCY -  
REVIEW OF PLANT FAILURE HISTORY
- REQUIRES DETAILED REVIEW OF  
COMPONENTS WHICH EXCEED 20  
FAILURES IN PLANT LIFE, 3 IN  
THE PAST 12 MONTHS OR SHOW AN  
INCREASING TREND
- RECOMMENDATIONS FOR INCREASED  
CONDITION MONITORING, REVISED  
WORK PRACTICES, EQUIPMENT  
CHANGEOUT RESULT FROM THE  
REVIEW
- PROVIDES A HARD COPY REPORT  
FOR EQUIPMENT HISTORY ON  
RESULTS OF THE EVOLUTION

## **WNP-2 EQUIPMENT TRENDING PROGRAMS**

### **\* FUTURE IMPROVEMENTS**

- RCM RECOMMENDATIONS FOR CONDITION MONITORING WILL ESTABLISH THE BASIS OF THE PERFORMANCE MONITORING PROGRAM**
- IMPROVEMENTS IN WORK PROCESS (MWR) PROGRAM WILL RESULT IN MORE DETAILED AND ACCURATE FAILURE DATA**

## MAINTENANCE/TRAINING INITIATIVES

### \* GOALS AND OBJECTIVES

- RE-EVALUATION IN PROCESS TO  
ESTABLISH PERFORMANCE  
BASED OBJECTIVES AND  
MEASURES OF MAINTENANCE  
ACTIVITIES
- RESTRUCTURING OF THE  
EXISTING TRAINING PROGRAM  
WILL FALL OUT OF THIS  
RE-EVALUATION

## **MAINTENANCE/TRAINING INITIATIVES**

### **\* JOB AND TASK ANALYSIS (JTA)**

- SUPPLY SYSTEM CONTRACTED (AUGUST, 1989) JOB AND TASKS ANALYSIS OF THE 3 MAINTENANCE DISCIPLINES**
- PRODUCTS WILL INCLUDE: TRAINING OBJECTIVES, JOB PERFORMANCE MEASURES, AND INSTRUCTIONAL SEQUENCING**
- RESULT WILL BE TO DEVELOP THE BASIS FOR FUTURE TRAINING PROGRAMS BASED ON ACTUAL TASKS REQUIRED**
- SCHEDULED TO COMPLETE IN JUNE, 1990**




## **MAINTENANCE/TRAINING INITIATIVES**

### **\* ON THE JOB TRAINING (OJT)**

- TASK IS TO: 1) EVALUATE TRAINING PERFORMANCE  
2) ASSIST IN OJT 3) SERVE AS PLANT POINT  
OF CONTACT WITH TRAINING**
- THREE FULL TIME TRAINERS HIRED AND ASSIGNED**
- REMOVES THIS BURDEN FROM THE MAINTENANCE SUPERVISOR**





## **MAINTENANCE/TRAINING INITIATIVES**

### **\* QUALITY ASSESSMENT TEAM (QAT)**

- CHARTERED BY THE SUPPLY SYSTEM QUALITY COUNCIL**
- TASKED WITH IDENTIFYING ISSUES CRITICAL TO THE SUCCESSFUL IMPLEMENTATION OF THE MANY CHANGES UNDERWAY IN MAINTENANCE/TRAINING**
- CHAIRED BY THE MANAGER OF MAINTENANCE TRAINING**
- 8 MEMBERS FROM VARIOUS LEVELS WITHIN MAINTENANCE AND TRAINING**

## **MAINTENANCE/TRAINING INITIATIVES**

### **\* MAINTENANCE ASSIGNMENT OF PERSONNEL**

- GOAL TO CLARIFY THE BASIS OF CRAFT WORK ASSIGNMENT**
- CONVERTING TO COMPUTER BASED SYSTEM FOR IDENTIFYIN CRAFT TRAINING**
- ESTABLISH FORMAL DOCUMENTATION OF CRAFT QUALIFICAT BASIS**
- ASSURE PERSONNEL QUALIFICATIONS BY DEMONSTRATED PERFORMANCE**
- INCORPORATE THIS REVISED PROCESS INTO THE WORK PLANNING EFFORT**
- FULLY IMPLEMENT BY 3/1/90**

## **MAINTENANCE MANAGEMENT/SUPERVISORY REALIGNMENT**

### **\* GOAL**

- IMPROVE WORK CONTROL, PACKAGE PREPARATION  
AND TASK ACCOUNTABILITY IN EACH DISCIPLINE  
SHOP**



## **MAINTENANCE MANAGEMENT/SUPERVISORY REALIGNMENT**

### **\* ACTION TAKEN**

- SHOP RESTRUCTURING - ADDITION OF WORK CONTROL AND ENGINEERING SUPERVISORS**
- ASSIGNMENT OF HAND-PICKED, EXEMPT CRAFT SUPERVISORS IN EACH SHOP**
- ASSIGNMENT OF PARTS/MATERIALS HANDLERS AND SHOP PLANNERS IN EACH SHOP**
- PROVIDES THE ORGANIZATIONAL STRUCTURE NECESSARY IN TAKING THE NEXT STEPS IN MAINTENANCE IMPROVEMENT**

## **CONTROL ROOM DEFICIENCY REDUCTION PROGRAM**

### **\* GOAL**

- REDUCE THE NUMBER OF DEFICIENCIES TO  
50 BY 1/1/90**
- REDUCE THE NUMBER OF DEFICIENCIES TO  
25 AT THE END OF THE SPRING 1990  
OUTAGE**

## CONTROL ROOM DEFICIENCY REDUCTION PROGRAM

### \* ACTIONS TAKEN

- MANAGEMENT "WHITE PAPER" DEVELOPED OUTLINING PROGRAM ELEMENTS
  - o ASSIGNMENT OF A NEW PRIORITY WORK CLASS BETWEEN 1 AND 2
  - o REQUIRE WORK INSTRUCTION COMPLETION WITHIN 3 DAYS OF PROBLEM IDENTIFICATION
  - o SCHEDULE TO WORK JOBS WITHIN 3 DAYS OF ACHIEVING RTW STATUS
  - o EXPEDITE PARTS PROCUREMENT
  - o UTILIZE SHOP OVERTIME AS NECESSARY
  - o INCREASE DESIGN CHANGE PRIORITY WITHIN ENGINEERING





## CONTROL ROOM DEFICIENCY REDUCTION PROGRAM

### \* RESULTS TO DATE/PLANS

- NUMBER OF DEFICIENCIES LOWERED TO 74 FROM 94 IN OCTOBER
- 53 TASKS ARE CURRENTLY OUTAGE-RELATED
- ENGINEERING WILL COMPLETE THE DESIGN FOR OVER 20 PACKAGES PRIOR TO R-5
- THE POST R-5 GOAL IS STILL ACHIEVABLE




## **TECHNICAL SPECIFICATION IMPROVEMENT PROGRAM**

- \* COMPLETE REWRITE OF LCOs; EXPANSION OF BASES**
- \* PROCEDURE TO REQUIREMENT CROSS-CHECK**
- \* SSFI REVIEW OF APPLICABLE PROCEDURES**
- \* MODE CHANGE SURVEILLANCE REVIEW**
- \* VALIDATION AND VERIFICATION ON REVISED PROCEDURES**



## **TECHNICAL SUPPORT**

- \* . ADDED RESOURCES FOR BACKLOG REDUCTION EFFORTS  
AND SYSTEM ENGINEERING SUPPORT**
- \* COMPLIANCE SUPPORT FOR REPORTABILITY DETERMINATIONS  
FOR OPERATIONS**
- \* TECHNICAL STAFF TRAINING COURSES ON:**
  - 10 CFR 50.59**
  - ROOT CAUSE ASSESSMENTS**
  - PROJECT MANAGEMENT**
  - PMRs**
  - MWR WORK PACKAGE PREPARATION**
  - PMT**
- \* IMPROVED LONG RANGE PLANNING**
- \* DEVELOPED A JOINT TECH STAFF/  
GENERATION ENGINEERING SYSTEM  
WALKDOWN PROCESS**



## **IMPROVEMENTS IN RADIOLOGICAL WORK PRACTICES**

- \* IMPROVED ROR IDENTIFICATION, ROOT CAUSE ASSESSMENTS & TRENDING OF RESULTS**
- \* ESTABLISHED HP SPONSOR PROGRAM**
- \* HP SUPERVISION ASSISTS IN RAD. REFRESHER TRAINING COURSES**
- \* DEVELOPING MORE MOCK-UP TRAINING FOR CRAFTS**
- \* CONDUCTING STRENGTHENED ALARA PRE-JOB BRIEFINGS**
- \* IMPROVED RAD. WORK PRACTICES EMPHASIZED BY CRAFT SUPERVISION, FIELD WALKDOWNS**
- \* HP SPONSORED NUMEROUS DOSE REDUCTION INITIATIVES**
  - CRD ROOM MODS**
  - SYSTEM FLUSHES**
  - MODIFIED SHUTDOWN SEQUENCES**
- \* PERFORMANCE INDICATORS PROVIDE POSITIVE FEEDBACK**






## **ADHERENCE TO PROCEDURES**

- \* TQA AND QAT - TRAINING ON QUALITY IMPROVEMENTS**
- \* PER PROCESS**
  - HPES**
  - PEER**
  - ROOT CAUSE**
- \* DISCIPLINE**
- \* SURVEILLANCE WORK DOCUMENT/TRAINING**



# ENGINEERING IMPROVEMENT PROGRAM




LEGEND:  SCHEDULE  PERCENT ACHIEVED TODAY

902004A



# ENGINEERING IMPROVEMENT PROGRAM EFFECTIVENESS



ENGINEERING IMPROVEMENT PROGRAM EFFECTIVENESS  
QUALITY CIRCLE RESULTS

<u>DESCRIPTION</u>	<u>TECHNICAL MERIT</u>	<u>CONSTRUCT- ABILITY</u>	<u>MOD TEST &amp; OPERABILITY</u>	<u>WALKDOWN EFFECTIVENESS</u>
BDC 86-0617 IN-1 INVERTER	5.0	5.0	4+	4.0
BDC 86-0273 FW HTR DUAL LEVEL CONTROL	5.0	4.0	4.8	4.0
BDC 84-0542-1 RRC PUMP SEAL FLOW INSTRUMENTATION	NOT EVALUATED	2.5	3.0	5.0

LEGEND

1.0 - UNSATISFACTORY


2.5 - AVERAGE

5.0 - EXCELLENT





# DESIGN REQUIREMENTS PROGRAM



LEGEND:

[White Box] SCHEDULED [Hatched Box] COMPLETED

902004.B

## ELECTRICAL WIRING DIAGRAMS

\* EWD'S COMPLETE

- MOV'S 463

- SYSTEM LEVEL 240

TOTAL 703

\* EWD'S PLANNED NEXT 6 MOS 330


\* EWD'S PLANNED FY - 1991 330



## **CONFIGURATION MANAGEMENT IMPROVEMENT PROGRAM (CMIP)**

### **\* PURPOSE**

- ESTABLISH THE REQUIREMENTS FOR CONFIGURATION MANAGEMENT, I.E., THOSE REQUIREMENTS WHICH WOULD ENSURE PLANT HARDWARE COMPLIES WITH AND IS ACCURAT REFLECTED IN PLANT DOCUMENTS**
- DEVELOP AND IMPLEMENT A PLAN TO**
  - o REVIEW CURRENT ORGANIZATIONAL WORK PROCESSES TO THE ESTABLISHED REQUIREMENTS**
  - o PROVIDE RECOMMENDATIONS FOR IMPROVEMENTS**



LEGEND:  SCHEDULE  PERCENT ACHIEVED

902004



## SETPOINT PROGRAM

<u>TASK</u>	<u>PLAN</u>	<u>STATUS</u>
1.0 IDENTIFY HARSH ENVIRONMENT EQUIPMENT	10/31/89	COMPLETE
2.0 PERFORM SAFE SHUTDOWN ANALYSIS	12/31/89	COMPLETE
3.A REVISE METHODOLOGY USING ISA RP67.04	12/31/89	COMPLETE
3.B TABULATE TESTED SETPOINT ACCURACY FROM EQ DATA	12/31/89	COMPLETE
3.C RECALCULATE SETPOINTS	3/31/90	BEHIND SCHEDULE
4.0 RESOLVE SETPOINT OPERATIONAL PROBLEMS	6/30/90	NOT STARTED
5.0 REVISE PROCEDURES/RECALIBRATE EQUIPMENT	8/1/90	NOT STARTED





## **SAFETY ASSESSMENT/QUALITY VERIFICATION**

### **\* SALP ISSUES**

- "AGGRESSIVENESS" OF OVERSIGHT GROUPS/RESPONSIVENESS  
IN RESOLVING PROBLEMS**
- ORGANIZATION/STAFFING QUALIFICATIONS**
- ROOT CAUSE PROGRAM EFFECTIVENESS**
- QUALITY OF LICENSING SUBMITTALS**

## **SAFETY ASSESSMENT/QUALITY VERIFICATION**

### **\* OVERALL PROGRAM STATUS/DIRECTION**

- QUALITY IMPROVEMENT**
- NUCLEAR SAFETY PROGRAMS**
- PROCUREMENT QA**
- QA/QC**



## **EFFECTIVENESS ASSESSMENT**

- \* PLANS APPROVED BY QUALITY COUNCIL (DIRECTOR)**
- \* STATUS REVIEWED MONTHLY BY QUALITY COUNCIL**
- \* RESULTS REPORTED TO QUALITY COUNCIL**
- \* EXPERT CONSULTANTS IN SOME CASES**

## EFFECTIVENESS ASSESSMENT

<u>CATEGORY</u>	<u>STATUS/SCHEDULE</u>
1) CHEMISTRY	DRAFT COMPLETE Q COUNCIL BRIEFING 2/90
2) EMERGENCY PREPAREDNESS	2/90
3) ENGINEERING/TECH SUPPORT	FOUR PHASE PLAN (8/90)
4) INDUSTRIAL SAFETY	MULTIPHASE PLAN (12/90)
5) MAINTENANCE/SURVEILLANCE	TWO PHASE PLAN (4/90 AND 1/91)
6) OPERATING EXPERIENCE REVIEWS	THREE PHASES (2 COMPLETE) LAST PHASE SCHEDULED (4/90)
7) OPERATIONS	SCHEDULED (2/90)
8) ORG AND ADMIN.	MULTIPHASE PLAN (6/90)
9) OUTAGE MANAGEMENT	SCHEDULED (9/90)
10) RADIOLOGICAL PROTECTION	COMPLETED (11/89)
11) SAFETY ASSURANCE/QUALITY	PLAN UNDER DEVELOPMENT
12) SECURITY	SCHEDULED 2/90
13) TRAINING AND QUALIFICATION	PLAN UNDER DEVELOPMENT

## 1989 ASSESSMENT STATISTICS

* NUCLEAR SAFETY	NUMBER
- INDUSTRY OPERATING EXPERIENCE REVIEWS:	490
- NUCLEAR SAFETY/ENGINEERING ASSESSMENTS:	28
- MAJOR TEAM INSPECTIONS (SSFI, SSOMI):	2
* QUALITY ASSURANCE	
- CORPORATE QA AUDITS:	15
- WNP-2 QUALITY SURVEILLANCES:	96
- OFF-SITE VENDOR AUDITS/REVIEWS:	71
* QUALITY CONTROL INSPECTIONS	
- MWRs REVIEWED:	5,994
- MWRs ASSIGNED INSPECTION "HOLD POINTS":	1,294
- OTHER INSPECTIONS:	161
- RECEIVING INSPECTIONS (LINE ITEMS):	8,405
* TOTAL NUMBER OF QUALITY FINDINGS	
- QFRs ISSUED:	289*
* INCLUDES 33 FINDINGS ASSOCIATED WITH SSFI ISSUED AS PERS	

## ORGANIZATION/STAFF QUALIFICATION

1) ORGANIZATION IMPROVEMENTS COMPLETE

2) STAFF INCREASED IN FY 90

3) RECRUITING SUCCESS	INTERNAL	8
	EXTERNAL	<u>14</u>
	TOTAL	22

4) OPERATIONAL EXPERIENCE (NRC LICENSES & CERTIFICATES)

\* 19 INDIVIDUALS

* SROs	WNP-2	6
	COMMERCIAL BWRs	11
	OTHER	<u>5</u>

* ROs	<u>12</u>
-------	-----------

TOTAL	34
-------	----

5) EDUCATIONAL QUALIFICATIONS

* ADVANCED DEGREES	7 INDIVIDUALS (10 DEGREES)
* ENGR OR SCIENCE	33 INDIVIDUALS (43 DEGREES)
* CERTIFIED PEs	17 INDIVIDUALS

6) USE OF OUTSIDE EXPERTS

- \* CONSULTANTS
- \* UTILITY TRADES
- \* INTERNAL ASSIGNMENTS





## **ROOT CAUSE ASSESSMENT PROGRAM STATUS**

### **\* IMPROVED PROBLEM REPORTING AND RCA**

- MORE PROBLEMS REPORTED (976 IN 1989 vs 728 IN 1988)**
- MANAGEMENT REVIEW OF ALL PERs (MRC)**
- MORE FORMAL RCA (192 IN 1989 vs 29 IN 1988)**

### **\* INCIDENT INVESTIGATION PROCESS IMPLEMENTED**

- ACTIVATED BY MANAGEMENT**
- BROADER VIEW THAN NORMAL RCA**

### **\* TRAINING OF ADDITIONAL RCA STAFF**

- RCA PROCESS TRAINING - 140 ENGINEERS**
- IN-HOUSE RCA TRAINING - 17 ENGINEERS**
- MORT TRAINING FOR RCA STAFF**

### **\* INCREASED EMPHASIS ON IMPLEMENTATION**

### **\* REPORT QUALITY/PRECURSOR ASSESSMENT**

### **\* INDEPENDENT EFFECTIVENESS ASSESSMENT**

**ROOT CAUSE ASSESSMENT  
PROGRAM STATUS  
(CON'T)**

**\* EXAMPLES OF SIGNIFICANT EVENTS ANALYZED (1989)**

- INSULATOR FAULT (SCRAM 89-01)
- ROD DRIFT EVENT
- SHUTDOWN COOLING EVENTS IN R-4
- TURBINE BLADE CRACKS
- SCRAM DURING DEH TESTING (SCRAM 89-02)
- RFW PUMP TRIP (SCRAM 89-03)
- RFW THRUST BEARING FAILURE
- I & C SURVEILLANCE SCRAM (89-04)
- EXTRACTION STEAM LINE EXPANSION JOINT FAILURE
- LIMITORQUE BOLT TORQUING ISSUE
- RESINS IN HVAC SYSTEM
- COOLING TOWER STRUCTURAL AND MECHANICAL  
(CONCRETE SPALLING)

## **QUALITY OF LICENSING SUBMITTALS**

- \* QUARTERLY MEETINGS WITH NRR TO SPECIFICALLY ADDRESS THIS ISSUE**
- \* NO KNOWN PROBLEMS SINCE ISSUANCE OF THE LATEST SALP**

## **SAFETY ASSESSMENT/QUALITY VERIFICATION PROGRAM STATUS AND INITIATIVES**



### **\* QUALITY IMPROVEMENT**

- MANAGEMENT TRAINING (QMS)**
- EMPLOYEE TRAINING ("THE QUALITY ADVANTAGE")**
- TEAMS - PROBLEM SOLVING**
- MANAGEMENT EMPHASIS - QUALITY COUNCIL**

## NUCLEAR SAFETY ASSESSMENT

- \* INDUSTRY EXPERIENCE REVIEW
- \* 50.59 REVIEW IMPROVEMENTS
  - PROCEDURES
  - TRAINING
- \* SSFI - AC DISTRIBUTION SYSTEM
- \* TECHNICAL ASSESSMENTS
- \* RELIABILITY/RISK DIRECTED OVERSIGHT

# OER PERFORMANCE





## **QUALITY VERIFICATION**

- \* PROCUREMENT QA**

- RECEIVING INSPECTION**
- VENDOR AUDITS**
- SPECIFICATION/DOCUMENT REVIEWS**

- \* TRENDING AND REPORTING**

- \* QA/QC EFFECTIVENESS**



## **SAFETY ASSESSMENT/QUALITY VERIFICATION PROGRAM STATUS AND INITIATIVES**

### **\* SUMMARY**

- ADDRESSING SALP ISSUES**
- "AGGRESSIVE" STATE-OF-ART  
SAFETY/QUALITY PROGRAMS**
- EXCELLENT STAFF (DEDICATED/  
QUALIFIED)**
- CONTINUOUS IMPROVEMENT**
  - o OPERATING EXPERIENCE (RCA)**
  - o NUCLEAR SAFETY ASSESSMENT**
  - o QA/QC**
  - o LICENSING PROGRAMS**

## **SAFETY RELATED VALVE FASTENERS**

- \* NOV RECEIVED 1/15/90**
- \* SUPPLY SYSTEM CONCURS WITH VALIDITY OF THE VIOLATIONS**
- \* INDUSTRY EXPERIENCE ALERTED SUPPLY SYSTEM TO POTENTIAL PROBLEMS WITH VIBRATION LOOSENING BOLTS**
- \* SS DEVISED PREVENTIVE MAINTENANCE ACTIVITY WHICH WAS LATER PROVEN INADEQUATE**

## **SAFETY RELATED VALVE FASTENERS**

- \* ACTIVITY LACKED DELINEATION OF VIBRATION-SENSITIVE VALVES, POSITIVE CLAMPING FORCE VERIFICATION TECHNIQUE AND MANAGEMENT FEEDBACK ON EFFECTIVENESS**
- \* ABSENT FEEDBACK, MANAGEMENT INACCURATELY BELIEVED PROBLEM WAS PRECLUDED**
- \* GIVEN NEW PER PROCESS AND FORMAL ROOT CAUSE ASSESSMENTS. APPROPRIATE PM ACTIONS IN PLACE:  
TORQUE VERIFICATION MONTHLY  
ENGINEERED CAPTURE MECHANISM FOR SUSPECT VALVES  
FAILURE REPORTING**

## **SAFETY RELATED VALVE FASTENERS**

- \* EXPERIENCE INDICATES TORQUE SELECTION IS INADEQUATE**
- \* SPECIFIC ACTIONS TO RE-TORQUE RHR-V-24A/B INADEQUATE**
- \* Q/A SURVEILLANCE ON BOLT TORQUING CONCLUDED:**
  - TRAINING NEEDED FOR WORK PACKAGE PREPARERS,  
QC OVERVIEWERS AND CRAFT IMPLEMENTERS**
  - TORQUE SELECTION NEEDS CLARIFICATION AND REVIEW**
  - GENERIC TORQUE SELECTION GUIDANCE (PPM10.2.10)  
NEEDS CLARIFICATION/RESTRICTIONS**
- \* CORRECTIVE ACTIONS ON THESE ISSUES UNDER DEVELOPMENT**