

CONTROLLED COPY

INSTRUMENTATION

SURVEILLANCE REQUIREMENTS

4.3.2.1 Each isolation actuation instrumentation channel shall be demonstrated OPERABLE by the performance of the CHANNEL CHECK, CHANNEL FUNCTIONAL TEST and CHANNEL CALIBRATION operations for the OPERATIONAL CONDITIONS and at the frequencies shown in Table 4.3.2.1-1.

4.3.2.2 LOGIC SYSTEM FUNCTIONAL TESTS and simulated automatic operation of all channels shall be performed at least once per 18 months.

4.3.2.3 The ISOLATION SYSTEM RESPONSE TIME of each isolation trip function shown in Table 3.3.2-3 shall be demonstrated to be within its limit at least once per 18 months.* Each test shall include at least one channel per trip system such that all channels are tested at least once every N times 18 months, where N is the total number of redundant channels in a specific isolation trip system.

* Response time testing of the Isolation Actuation Instrumentation Response Times for Isolation Groups 3 and 4, as specified in Technical Specification Table 3.3.2-1, is not a requirement for OPERABILITY until entry into a COLD SHUTDOWN condition no later than startup from the Spring 1994 Refueling Outage.

9310070198 931003
PDR ADOCK 05000397
P PDR

ATTACHMENT 1

