

CATEGORY 1

REGULATOR INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 9710150015 DOC. DATE: 97/10/02 NOTARIZED: NO DOCKET #
 FACIL: 50-397 WPPSS Nuclear Project, Unit 2, Washington Public Powe 05000397
 AUTH. NAME AUTHOR AFFILIATION
 BEMIS, P. R. Washington Public Power Supply System
 RECIP. NAME RECIPIENT AFFILIATION
 Document Control Branch (Document Control Desk)

SUBJECT: Provides update of process re revs to WNP-2 inservice testing program plan for pumps & valves that result from change in classification. Process will incorporate guidelines provided in NUREG-1482, Section 7.2, "Design Basis Reviews."

DISTRIBUTION CODE: A047D COPIES RECEIVED: LTR 1 ENCL 1 SIZE: 2
 TITLE: DR Submittal: Inservice/Testing/Relief from ASME Code - GL-89-04

NOTES:

	RECIPIENT ID CODE/NAME	COPIES LTTR ENCL	RECIPIENT ID CODE/NAME	COPIES LTTR ENCL
	PD4-2 LA	1 1	PD4-2 PD	1 1
	COLBURN, T	1 1		
INTERNAL:	ACRS	1 1	AEOD/SPD/RAB	1 1
	FILE CENTER O	1 1	NRR/DE/EMEB	1 1
	RODUCS-ABSTRACT	1 1	OGC/HDS3	1 0
	RES/DET/EIB	1 1	RES/DET/EMMEB	1 1
EXTERNAL:	LITCO ANDERSON	1 1	NOAC	1 1
	NRC PDR	1 1		

NOTE TO ALL "RIDS" RECIPIENTS:

PLEASE HELP US TO REDUCE WASTE. TO HAVE YOUR NAME OR ORGANIZATION REMOVED FROM DISTRIBUTION LISTS OR REDUCE THE NUMBER OF COPIES RECEIVED BY YOU OR YOUR ORGANIZATION, CONTACT THE DOCUMENT CONTROL DESK (DCD) ON EXTENSION 415-2083

TOTAL NUMBER OF COPIES REQUIRED: LTTR 14 ENCL 13

C
A
T
E
G
O
R
Y

1

D
O
C
U
M
E
N
T

WASHINGTON PUBLIC POWER SUPPLY SYSTEM

P.O. Box 968 • Richland, Washington 99352-0968

October 2, 1997
GO2-97-185

Docket No. 50-397

U.S. Nuclear Regulatory Commission
Attn: Document Control Desk
Washington, DC 20555

Gentlemen:

Subject: **WNP-2, OPERATING LICENSE NPF-21,
INSERVICE TESTING PROGRAM PLAN FOR PUMPS AND VALVES,
PLAN SCOPE UPDATE**

- References:
- 1) Letter, dated September 12, 1996, KE Brockman (NRC) to JV Parrish (SS), "NRC Inspection Report 50-397/96-11 and Notice of Violation"
 - 2) NUREG-1482, "Guidelines for Inservice Testing at Nuclear Power Plants, April 1995"

The Supply System has returned the quality and seismic classification of the RCIC System to the classifications that were described in the FSAR when the plant was initially licensed. These classifications, Quality Class I and Seismic Category I, are consistent with the classifications established for a safety system. The action to return the classifications to their original status was taken as a result of NRC Inspection 96-11 .

The purpose of this letter is to provide the Staff with an overview of the process that the Supply System will follow in making any necessary revisions to the WNP-2 Inservice Testing Program Plan for Pumps and Valves that result from the change in classification. The process will incorporate the guidelines provided in NUREG-1482 Section 7.2, Design Basis Reviews (Reference 2). It is anticipated that some components not currently in the Plan will be added and the testing requirements for others may require revision to include consideration of changes in their safety function.

9710150015 971002
PDR ADDCK 05000397
PDR



A047 1/1

**INSERVICE TESTING PROGRAM FOR PUMPS AND VALVES
PROGRAM SCOPE UPDATE**

In accordance with NUREG 1482, Section 7.2, the following description of the review process is provided.

- (1) The process for performing the programmatic review:

The initial task includes performing a design basis review for each of the RCIC System components. The design basis review determines the component status in relationship to ASME Section XI (OMa-1988, Addenda to the OM-1987 Edition, Part 6 and Part 10) as required by 10 CFR 50.55a(f) and the current scope of the WNP-2 Inservice Testing Program Plan (IST) for the second ten-year interval.

- (2) The actions to be taken when a component or test not previously in the IST Program is identified:

Changes to the IST Program Plan and implementing procedures will be completed by 12/31/97. If Code testing requirements cannot be met due to design or system limitations (e.g., lack of process instrumentation), partial or alternative testing will be implemented while Code relief is being requested.


In addition, affected components will be evaluated with respect to WNP-2 Technical Specification SR 3.0.3 and action taken, if required, in accordance with the applicable Limiting Condition for Operation.

- (3) The schedule for performing the testing once the need has been identified:

Testing of the components will commence in accordance with the changes to the IST Program Plan and implementing procedures which will comply with the Code testing frequency requirements.

Should you have any questions or desire additional information regarding this matter, please call me or Mr. PJ Inserra at (509) 377-4147.

Respectfully,



PR Bemis
Vice President, Nuclear Operations
Mail Drop PE23

cc: EW Merschoff - NRC RIV
DL Williams - BPA/399
PD Robinson - Winston & Strawn

NRC Sr. Resident Inspector - 927N
KE Perkins, Jr. NRC RIV, WCFO
TG Colburn - NRR

