

# Dry Cask Storage Inspection and Delivery System Development

**NRC RegCon**

**Jeremy Renshaw**  
Program Manager, EPRI


**Jamie Beard, Steve Glovsky**  
Robotic Technologies of Tennessee

Tuesday, October 31, 2017



# Introduction


- Dry Cask Storage System (DCSS) are intended for temporary storage of spent fuel
- Permanent repositories not yet available
- DCSS are now being used for longer than anticipated (or licensed) for storage of spent fuel
  - Some have been in use for >20 years
  - Currently, >2500 casks/canisters in operation
- Concern for long term operations, especially at coastal sites
  - Inspection of DCSS canisters is one of the key issues for continued licensing and operation





# Project Overview – Significant Industry Collaboration

**Goal: Develop Capability to Detect a Part-Wall Crack with ASME-accepted methods**



# Mockup Development

- EPRI worked with flaw manufacturers to build flaw mockups for industry use
  - **8 QA flaw mockups**
  - 3 non-QA mockups
  - Flaws of interest primarily in the weld and heat-affected zone
  - All are complete & available for open technique development
- 4 additional mockups were provided to EPRI by Sandia National Labs
  - One full diameter, 2' long section
    - PNNL funded flaw implantation
  - Two welded mockups
  - One base metal sample





# DCSSs Present Challenges for NDE

## Temperature

- Originally estimated to be up to  $\sim 180^{\circ}\text{C}$
- Measured temperatures have ranged from  $21\text{-}118^{\circ}\text{C}$  ( $70\text{-}245^{\circ}\text{F}$ )



## Radiation Dose

- Original estimate was  $\sim 1\text{-}10$  kR/hr
- Max measured to date is  $\sim 0.1$  kR/hr

## Challenging Access

- Confined entry and exit pathways
- Narrow annulus between canister and overpack with obstructions

**Desire is to have qualified NDE techniques, such as visual, eddy current, and ultrasound**




# Qualitative Overview of NDE Technologies

NDE Technique	Temperature Resistant	Radiation Resistant	Small Form Factor	Sensitive to ODSCC	Compatibility for DCSS Inspection	Time to Delivery
Visual (VT)						Now
Eddy Current Testing (ECT)						Now, if needed
Ultrasonic Testing (UT)						
EMAT/Guided Waves (GW)						
Acoustic Emission (AE)						
X-ray (RT)						
Penetrant Testing (PT)						N/A
Thermography						
Muon Imaging						

Now		Not Applicable
< 1 year		Good Performance / Yes
< 3 years		Fair Performance / Maybe
4+ years or N/A		Poor Performance / Not Well Suited

**Desire is to have qualified NDE techniques, such as UT or EC**





# NDE Techniques Under Development

## EPRI Projects

- Eddy Current Array (ECA)
  - Using ECA in a new way to help differentiate flaws of interest
  - Excellent results obtained
- Guided Waves
  - Ability to find defects in inaccessible areas (under rails, supports, etc.)
- Acoustic Emission
  - Potential to monitor from outside of the cask

*Supplement above inspections using visual imaging (cameras only)*



## Vendor Development Needs

- Gaps correlate to vendor strengths
  - Visual Techniques (VT-1 & VT-3)
  - Ultrasonics for length and depth sizing
- EPRI ESCP NDE Subcommittee Report contains input from 22 organizations performing NDE R&D (30020010617)






Image Courtesy of Intelligent Optical Systems – used with permission

# Eddy Current Inspection – Cracks/Pitting

○ = Simulated Cracks



↓ = Pitting ~1.0-2.5 mm pits










# Guided Wave Inspection

- Evaluating guided waves for DCSS inspection
- Technique has significant potential, especially for difficult-to-access or occluded areas
- Demonstration identified some areas for improvement
- Results are contained in EPRI Report 3002008234



# NDE Delivery Development

- Started robotic development in late 2014
- Moved from design to prototyping and deployment with
  - 2 field trials in 2015
  - 2 field trials in 2016 (one on a GTCC canister)
  - 1+ field trials in 2017
  - Fuel-loaded canister inspection in 2018






# Field Trial #1

- First robotic and NDE demonstration was completed successfully with a cask vendor
  - Field study of first operational robotic prototype carrying an NDE payload (eddy current array)
  - Field study of acoustic emission

## Key Lessons Learned

1. Corner transitions needed improvement
2. Vacuum suction needed to be stronger





# Field Trial #2

- Second robotic and NDE demonstration was completed successfully at a nuclear plant site (Palo Verde) using two cask/canister mockups
  - 28 demonstration visitors from 15 organizations (not including Palo Verde)
  - Demonstration of a second generation robotic prototype carrying NDE payloads
    - Onboard camera
    - Eddy current array
    - EMAT-generated guided waves
  - Demonstration of acoustic emission

## Key Lessons Learned

1. System was able to enter an actual cask system!
2. Potential FME issues identified





## Field Trial #3 – McGuire NPP

- Robotic field trial completed alongside Penn State University
  - Preparation for Maine Yankee field inspection

### Key Lessons Learned

1. Potential issues with cables on standoffs – specific cask design
2. FME Issue – lost wheel (retrieved without issue)
3. Identified a weakness in the robot design
4. RTT made immediate (overnight) design changes to eliminate the issues and developed the next generation design



# Field Trial #4 – Maine Yankee

- First robotic and NDE inspection completed on a live canister

## Key Lessons Learned

1. Robotic system was able to take visual, thermal, and radiation data
2. Inspection completed without issue
3. Several samples taken & sent to Sandia National Labs for analysis
4. Identified several best practices for performing inspections





## Field Trial #5 – Hatch NPP

- First robotic and NDE demonstration was completed successfully on a Holtec System
  - Added a thermocouple for temperature readings
  - Demonstrated the second generation cleaning pad

### Key Lessons Learned

1. Miniaturized robot operated well in the Holtec system – no issues
2. First demonstration of a thermocouple measurement











## Field Trial Summary

- To date, 5 field trials have been completed
  1. AREVA's Aiken Facility
  2. APS – Palo Verde
  3. Duke Energy – McGuire
  4. 3 Yankees – Maine Yankee (loaded GTCC canister)
  5. Southern Company – Hatch
- Improvements have been made based on lessons learned from each field trial
- Field deployment on a canister loaded with fuel is scheduled for 2017-8, 1-2 years ahead of schedule

**EPRI welcomes participation**  
**Technology transfer to  
the industry is the goal**






# “Hot Off the Presses” – Horizontal Cask Developments





# Summary

- EPRI is working towards solutions to the DCSS inspection issue via:
  - Collaboration – Working with many organizations and communicating via the ESCP NDE Subcommittee
  - Mockup Fabrication – 8 QA plus 8 non-QA Mockups fabricated and open for industry use for technique development
  - NDE Development
    - Eddy current, EMAT, and Acoustic Emission work are ongoing
    - UT and VT work progressing with vendor-led collaboration
  - Robotic Delivery – Five field trials complete, additional development and demonstrations to follow
- Results contained in EPRI Reports 3002008234 & 3002010617
  - Upcoming report: 3002010621 (latest developments)





# Together...Shaping the Future of Electricity