



Arizona Nuclear Power Project

DOCUMENT NUMBER

13-MC-HJ-255


TITLE/DESCRIPTION

CONTROL ROOM HEAT LOAD  
CALCULATION

QUALITY CLASS Q

8811230004

△						
△						
△						
△						
△						
△	8811230009 881109 PIR ADOCK 05000528 P PDC					
△						
△	ISSUED FOR USE	V.K. Chandra 9/21/88	PEM Maynard 9/28/88	BLR Riley 9/28/88	N/A	N/A
REV	REVISION DESCRIPTION	ORIGINATOR DATE	CHECKER DATE	RS DATE	QA DATE	NEM/PEM DATE




# ENGINEERING SKETCH PAD

BY V.K.Chang	DATE 9/21/88	SUBJECT CONTROL ROOM HEAT LOAD CALC.	SHEET NO 1 of 10
CHECKED BY PE. Maynard	DATE 9/28/88		JCS NO. 13-MC-HJ-255

## TABLE OF CONTENTS

	PAGE
1.0 PURPOSE	2
2.0 SUMMARY	3
3.0 INPUT DATA AND ASSUMPTIONS	4
4.0 CALCULATION AND RESULTS	6
5.0 REFERENCES	9
6.0 ATTACHMENT 1	10



# ENGINEERING SKETCH PAD

BY V.K. Chowdh	DATE 9/21/88	SUBJECT CONTROL ROOM HEAT LOAD CALCULATION	SHEET NO. 2 of 10
CHECKED BY P.E. Maynard	DATE 9/28/88		JOB NO. 13-MC-HJ-255

## 1.0 PURPOSE

THE PURPOSE OF THIS CALCULATION IS TO ESTIMATE THE HEAT LOAD FOR THE CONTROL ROOM. THE HEAT LOAD DATA FOR CONTROL ROOM IS REQUIRED FOR A SEPARATE EVALUATION COMPRISING OF NON-OPERATION OF ESSENTIAL CHILLERS.



# ENGINEERING SKETCH PAD

BY: V.K. Lawlor	DATE: 9/21/88	SUBJECT: CONTROL ROOM HEAT LOAD CALC	SHEET NO.: 3 of 10
CHECKED BY: P.E. J. Jeynand	DATE: 9/28/88		JOB NO.:

## 2. SUMMARY OF RESULTS :

(a) FAN HEAT LOAD, ONE FAN = 185700 BTU/HR

(b) CHILLER HEAT EXCHANGE = 866600 BTU/HR

(c) HEAT LOSS FROM CONTROL  
Room = 103800 BTU/HR

(d) HEAT LOAD (OSA-MAKE-UP) = 129750 BTU/HR

(e) CONTROL ROOM HEAT LOAD = 654950 BTU/HR





# ENGINEERING SKETCH PAD

BY V.K. Chumb	DATE 9/21/88	SUBJECT CONTROL ROOM HEAT LOAD CALCULATION	SHEET NO 4 of 10
CHECKED BY P.E. Maynard	DATE 9/29/88		JOB NO 13-MC-HJ-255

## INPUT DATA & BASIS

DATA FROM THE TEST CONDUCTED BY ENGINEERING EVALUATION DEPARTMENT ON 7/21/88:

MAIN SUPPLY HEADER = 27500 SCFM

OUT-SIDE AIR MAKE-UP = 769 SCFM  
(OSA)

PROCESS TEMP: (SEE FLOW DIAGRAM ON PAGE No. 6)

@

Loc. #	LOCATION	D.B. TEMP	R. HUMIDITY
④	UPSTREAM FAN	77.1 °F	63 %
⑤	DOWNSTREAM FAN	84.1 °F	50 %
③	SUPPLY HEADER	68.6 °F	65 %
⑦	RETURN HEADER	77.0 °F	55 %
⑥	OSA HEADER	90.5 °F	46.9 %

## ASSUMPTIONS:

- (1) THE LOSS OF AIR FROM CONTROL ROOM IS NOT MEASURED. THE LOSS OCCURS BY WAY OF OPENING DOORS ETC. THE CONTROL ROOM IS MAINTAINED AT SLIGHT POSITIVE PRESSURE, AND IN THE STEADY STATE SCENARIO OF EQUILIBRIUM, CONDITIONS UNDER WHICH TEST WAS CONDUCTED, THE RATE OF OUT-SIDE AIR MAKE-UP HAS TO BE EQUAL TO THE RATE OF LOSS OF AIR FROM CONTROL ROOM (FIRST LAW OF THERMODYNAMICS)
- (2) NEGLECTING HEAT LOSS FROM DUCTING BETWEEN FAN AND ESSENTIAL CHILLER UNIT WILL RESULT IN MORE CONSERVATIVE HEAT LOAD. THIS IMPLIES THE ENTHALPY OF AIR AT EXIT OF FAN IS EQUAL TO THE ENTHALPY AT ENTRANCE TO THE CHILLER UNIT.



# ENGINEERING SKETCH PAD

BY: V.K. Chawla	DATE: 9/21/88	SUBJECT: CONTROL ROOM HEAT LOAD CALCULATION	SHEET NO. 5 of 10
CHECKED BY: P.E. Maynard	DATE: 9/28/88		JOB NO.


(3) BY FIRST LAW OF THERMODYNAMICS,  
 AT THE EQUILIBRIUM CONDITIONS OF STEADY STATE,  
 THE HEAT INPUT = HEAT OUTPUT FOR THE  
 CONTROL ROOM



# ENGINEERING SKETCH PAD

BY: V.K. Chawla	DATE: 9/21/88	SUBJECT: CONTROL ROOM HEAT LOAD CALCULATION	SHEET NO: 6 of 10
CHECKED BY: P.E. W. Hayward	DATE: 9/28/88		JOB NO.: 13-MC-HJ-255

## CALCULATIONS AND RESULTS:



### RATES:

LET  $Q_S$  = AIR SUPPLY TO CONTROL ROOM, SCFM

$Q_R$  = AIR RETURN FROM CONTROL ROOM, SCFM

$Q_{OSA}$  = OUTSIDE AIR MAKE-UP, SCFM

$Q_{EX}$  = AIR LOST FROM CONTROL ROOM, SCFM =  $Q_{OSA}$

$\dot{m}_s$  = MASS FLOW RATE, SUPPLY AIR TO CONTROL ROOM, LBS/HR

$\dot{m}_O$  = MASS FLOW RATE, OUTSIDE MAKE-UP AIR, LBS/HR

$q_{CR}$  = CONTROL ROOM HEAT LOAD, BTU/HR

$q_{EX}$  = HEAT LOAD OF AIR LOST FROM CONTROL ROOM, BTU/HR

$q_{FAN}$  = HEAT LOAD FOR ONE FAN, BTU/HR

$q_{EC}$  = HEAT EXCHANGED IN THE ESSENTIAL CHILLER, BTU/HR

$q_O$  = HEAT INPUT FROM THE MAKE-UP OUTSIDE AIR, BTU/HR



# ENGINEERING SKETCH PAD

BY <b>V.K. Clark</b>	DATE <b>9/21/88</b>	SUBJECT <b>CONTROL ROOM HEAT LOAD CALCULATION</b>	SHEET NO. <b>7 of 10</b>
CHECKED BY <b>P.E. Maynard</b>	DATE <b>9/28/88</b>	JOB NO. <b>13-MC-HJ-255</b>	

THE DENSITY OF AIR (REF 2, PAGE 13) = 0.075 lbs/ft<sup>3</sup>

CONVERTING VOLUMETRIC FLOW TO MASS FLOW:

$$\dot{M}_S = 27500 \text{ (ft}^3/\text{min)} \times 60 \text{ (min/hr)} \times 0.075 \frac{\text{LB}}{\text{ft}^3}$$

$$\approx 123800 \text{ LBS/HR}$$

$$\text{AND } \dot{M}_D = Q_0 \times 0.075 = 769 \times 60 \times 0.075$$

$$= 3460 \text{ LBS/HR}$$

FROM PSYCHROMETRIC CHART (REF 3, PAGE 6.14) THE ENTHALPY VALUES OF AIR AT VARIOUS LOCATIONS ALONG THE FLOW PATH:

(REFER TO SKETCH ON PAGE 6 TO FIND LOCATIONS LOCATIONS ARE INDICATED BY CIRCLED NUMBERS)

USED DATA ON PAGE NO 4:

$$h_1 = 34 \text{ BTU/LB} = h_5 \text{ at Location } \textcircled{1}$$

$$h_2 = 27 \text{ BTU/LB} \quad " \quad " \quad \textcircled{2}$$

$$h_3 = 30 \text{ BTU/LB} \quad " \quad " \quad \textcircled{3}$$

$$h_4 = 32.5 \text{ BTU/LB} \quad " \quad " \quad \textcircled{4}$$

$$h_5 = 34 \text{ BTU/LB} = h_1 \quad " \quad " \quad \textcircled{5}$$

$$h_6 = 37.5 \text{ BTU/LB} \quad " \quad " \quad \textcircled{6}$$

BY FORMULA (REF 1, PAGE 303),

HEAT INPUT FROM FAN

$$q_{\text{FAN}} = \dot{M}_S \times (h_5 - h_4) = 123800 \times (34 - 32.5)$$

$$= 185700 \text{ BTU/HR}$$

HEAT REMOVED BY EC

$$q_{\text{EC}} = \dot{M}_S \times (h_1 - h_2) = 123800 \times (34 - 27)$$

$$= 866600 \text{ BTU/HR}$$

HEAT LOST FROM THE CONTROL ROOM

$$q_{\text{EX}} = 3460 \times h_3 = 3460 \times 30$$

$$= 103800 \text{ BTU/HR}$$





# ENGINEERING SKETCH PAD

BY <i>V.K. Chandra</i>	DATE <i>9/21/88</i>	SUBJECT CONTROL Room HEAT LOAD CALCULATION	SHEET NO. <i>8 of 10</i>
CHECKED BY <i>P.E. Maynard</i>	DATE <i>9/24/88</i>		JOB NO. <i>13-MC-HJ-255</i>

HEAT INPUT BY MAKE-UP AIR (OUT-SIDE AIR, OSA)

$$\begin{aligned}
 \dot{Q}_O &= 3460 \times 26 = 3460 \times 37.5 \\
 &= \underline{\underline{129750 \text{ BTU/HR}}}
 \end{aligned}$$

AS THE TEST WAS CONDUCTED UNDER A STEADY STATE CONDITION, THE OVERALL ENERGY BALANCE, BY FIRST LAW OF THERMODYNAMICS, GIVES:

HEAT INPUT = HEAT OUTPUT

$$\dot{Q}_{CR} + \dot{Q}_O + \dot{Q}_{FAN} = \dot{Q}_{EX} + \dot{Q}_{EC}$$

$$\begin{aligned}
 \text{OR } \dot{Q}_{CR} &= (\dot{Q}_{EX} + \dot{Q}_{EC}) - (\dot{Q}_{FAN} + \dot{Q}_O) \\
 &= (103800 + 86660.0) - (185700 + 129750) \\
 &= \underline{\underline{65495.0 \text{ BTU/HR}}}
 \end{aligned}$$



# ENGINEERING SKETCH PAD

BY V.K. Chae	DATE 9/21/88	SUBJECT CONTROL ROOM HEAT LOAD CALCULATION	SHEET NO 9 of 10
CHECKED BY P.E. Maynard	DATE 9/28/88		JOB NO

## REFERENCES:

(1) UNIT OPERATIONS OF CHEMICAL ENGINEERING BY McCABE AND SMITH, 2nd EDITION, Mc Graw Hill

(2) FAN ENGINEERING, ROBERT JORGENSEN, BUFFALO FORGE, SEVENTH EDITION

(3) ASHRAE HANDBOOK 1985 FUNDAMENTALS  
INCH- POUND EDITION

(5) CONTROL ROOM HEAT LOAD TEST, CONDUCTED BY  
ENGINEERING EVALUATION DEPT. ON 7/21/88, (WILL  
BE ASSIGNED A DOCUMENT NUMBER ON A  
LATER DATE) ATTACHMENT 1.



## ATTACHMENT 1

PAGE 1 OF 5

## CONTROL ROOM HEAT LOAD TEST

ESTABLISH EQUILIBRIUM TEMPERATURE OF  
~75°F IN CONSOLE AREA USING  
CONTROL ROOM ESSENTIAL AFU

TRAVERSE MAIN SUPPLY HEADER  
TO DETERMINE FLOWRATE

TRAVERSE OUTSIDE AIR DUCT TO  
DETERMINE FLOWRATE

MEASURE DIFFERENTIAL PRESSURE;  
ACROSS THE WATER SIDE OF AFU  
COOLING COIL. RECORD INLET AND  
OUTLET WATER TEMPERATURE

MEASURE / RECORD AIR TEMPERATURE  
AND HUMIDITY IN

I. UPSTREAM OF CIRC FAN \*

II. DOWNSTREAM OF CIRC FAN \*

III. SUPPLY HEADER \*

IV. RETURN HEADER \*

V. OSA HEADER \*



MEASURE/RECORD CONTROL ROOM AIR  
TEMPERATURE IN

i. ZONE 1 145'

ii. ZONE 1 152'

iii. ZONE 2 145'

iv. ZONE 2 152'

v. ZONE 3 145'

vi. ZONE 3 155'

vii. ZONE 4 145'

viii. ZONE 4 155'

ix. ZONE 5 145'

x. ZONE 5 155'

\*

RETURN TO NORMAL VENTILATION

REMOVE TEST MATE AND RESTORE  
SYSTEM

\* SPECIAL TEST INSTALLED MATE





## CONTROL ROOM HEAT RATE TEST

SUBCOOL CONTROL ROOM TO BY OPERATION:  
CONTROL ROOM <sup>OR NORMAL AHU</sup> ESSENTIAL AFU (WITH  
TIC @ 62°F) FOR 48 HOURS

ENGAGE TEMPERATURE DATA RECORDERS  
IN THE FOLLOWING AREAS

ZONE 1 145'

ZONE 1 152'

ZONE 2 145'

ZONE 2 152'

ZONE 3 145'

ZONE 3 155'

ZONE 4 145'

ZONE 4 155'

ZONE 5 145'

ZONE 5 155'

RETURN AIR HEADER (REDUNDANT TRAIN)

→ ALIGN HT IN CRGAS MODE

START REDUNDANT CONTROL ROOM ESSENTIAL  
AFU WITH EC CIRC PUMP

AND CHILLER IN STAND-BY, IMMEDIATELY

STOP THE ORIGINAL CONTROL ROOM ESSENTIAL  
AFU, RECORD TIME.



MAINTAIN TEMPERATURE RECORDERS

AND ALLOW CONTROL ROOM TO HEAT

UP UNTIL THE FIRST ZONE TEMPERATURE

LIMIT IS REACHED

ZONE LIMITS

ZONE 1 84°

ZONE 2 84°

ZONE 3 84°

ZONE 4 90°

ZONE 5 90°

RESTORE NORMAL COOLING

REMOVE TEST EQUIPMENT



MAN SUPPLY HEADER

Q = 26750 SCFM  
27500

OSA 76.1

Q = 713 SCFM

WATERSIDE

INLET TEMP 43 °F TI 26

OUTLET TEMP 75 °F TI 125

UPPER COIL DP 6 "WC

LOWER COIL DP 6 "WC

ACTUATOR  
FULL OPEN

PROCESS TEMP

110-75  
35

- ① UPSTRM FAN 77.1 °F 63 % RH FROM CHART
- ② DNSTRM FAN 84.1 °F 50 % RH
- ③ SUPPLY HEADER 68.6 °F 65 % RH
- ④ RETURN HEADER 77.0 °F 55 % RH
- ⑤ OSA HEADER 90.5 °F 46.9 % RH

TI 117 64 °F

