

ATTACHMENT NO. 2 TO AEP:NRC:0433
REVISED TECHNICAL SPECIFICATIONS PAGES
DONALD C. COOK NUCLEAR PLANT
UNIT NO. 1

8305160126 830510
PDR ADOCK 05000315
P PDR

3/4.0 APPLICABILITY

SURVEILLANCE REQUIREMENTS

4.0.1 Surveillance Requirements shall be applicable during the OPERATIONAL MODES or other conditions specified for individual Limiting Conditions for Operation unless otherwise stated in an individual Surveillance Requirement.

4.0.2 Each Surveillance Requirement shall be performed within the specified time interval with:

- a. A maximum allowable extension not to exceed 25% of the surveillance interval, and
- b. A total maximum combined time for any 3 consecutive surveillance intervals not to exceed 3.25 times the specified surveillance interval.

4.0.3 Performance of a Surveillance Requirement within the specified time interval shall constitute compliance with OPERABILITY requirements for a Limiting Condition for Operation and associated ACTION statements unless otherwise required by the specification. Surveillance requirements do not have to be performed on inoperable equipment.

4.0.4 Entry into an OPERATIONAL MODE or other specified applicability condition shall not be made unless the Surveillance Requirement(s) associated with the Limiting Condition for Operation have been performed within the stated surveillance interval or as otherwise specified.

4.0.5 Surveillance Requirements for inservice inspection and testing of ASME Code Class 1, 2, and 3 components shall be applicable as follows:

- a. Inservice inspection of ASME Code Class 1, 2, and 3 components and inservice testing of ASME Code Class 1, 2 and 3 pumps and valves shall be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code and applicable Addenda as required by 10 CFR 50, Section 50.55a(g), except where specific written relief has been granted by the Commission pursuant to 10 CFR 50, Section 50.55a(g)(6)(i).

REACTIVITY CONTROL SYSTEMS

CHARGING PUMP - SHUTDOWN

LIMITING CONDITION FOR OPERATION

3.1.2.3 One charging pump in the boron injection flow path required by Specification 3.1.2.1 shall be OPERABLE and capable of being powered from an OPERABLE emergency bus.

APPLICABILITY: MODES 5 and 6.

ACTION:

- a. With no charging pump OPERABLE, suspend all operations involving CORE ALTERATIONS or positive reactivity changes.
- b. With more than one charging pump OPERABLE or with a safety injection pump(s) OPERABLE when the temperature of any RCS cold leg is less than or equal to 188°F unless the reactor vessel head is removed, remove the additional charging pump(s) and the safety injection pump(s) motor circuit breakers from the electrical power circuit within one hour.
- c. The provisions of Specification 3.0.3 are not applicable.

SURVEILLANCE REQUIREMENTS

4.1.2.3.1 The above required charging pump shall be demonstrated OPERABLE by verifying, that on recirculation flow, the pump develops a discharge pressure of ≥ 2390 psig when tested pursuant to Specification 4.0.5.

4.1.2.3.2 All charging pumps and safety injection pumps, excluding the above required OPERABLE charging pump, shall be demonstrated inoperable by verifying that the motor circuit breakers have been removed from their electrical power supply circuits at least once per 12 hours, except when:

- a. The reactor vessel head is removed, or
- b. The temperature of all RCS cold legs is greater than 188°F

REACTIVITY CONTROL SYSTEMS

CHARGING PUMPS - OPERATING

LIMITING CONDITION FOR OPERATION

3.1.2.4 At least two charging pumps shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With only one charging pump OPERABLE, restore at least two charging pumps to OPERABLE status within 72 hours or be in HOT STANDBY within the next 6 hours; restore at least two charging pumps to OPERABLE status within the next 48 hours or be in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.1.2.4 At least two charging pumps shall be demonstrated OPERABLE by verifying, that on recirculation flow, each pump develops a discharge pressure of ≥ 2405 psig when tested pursuant to Specification 4.0.5.

REACTIVITY CONTROL SYSTEMS

BORIC ACID TRANSFER PUMPS - SHUTDOWN

LIMITING CONDITION FOR OPERATION

3.1.2.5 At least one boric acid transfer pump shall be OPERABLE and capable of being powered from an OPERABLE emergency bus if only the flow path through the boric acid transfer pump of Specification 3.1.2.1a is OPERABLE.

APPLICABILITY: MODES 5 and 6.

ACTION:

With no boric acid transfer pump OPERABLE as required to complete the flow path of Specification 3.1.2.1a, suspend all operations involving CORE ALTERATIONS or positive reactivity changes until at least one boric acid transfer pump is restored to OPERABLE status.

SURVEILLANCE REQUIREMENTS

4.1.2.5 No additional Surveillance Requirements other than those required by Specification 4.0.5.

REACTIVITY CONTROL SYSTEMS

BORIC ACID TRANSFER PUMPS - OPERATING

LIMITING CONDITION FOR OPERATION

3.1.2.6 At least one boric acid transfer pump in the boron injection flow path required by Specification 3.1.2.2a shall be OPERABLE and capable of being powered from an OPERABLE emergency bus if the flow path through the boric acid pump in Specification 3.1.2.2a is OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With no boric acid transfer pump OPERABLE, restore at least one boric acid transfer pump to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours and borated to a SHUTDOWN MARGIN equivalent to 1% $\Delta k/k$ at 200°F; restore at least one boric acid transfer pump to OPERABLE status within the next 7 days or be in COLD SHUTDOWN within the next 30 hours.

SURVEILLANCE REQUIREMENTS

4.1.2.6 No additional Surveillance Requirements other than those required by Specification 4.0.5.

REACTOR COOLANT SYSTEM

STEAM GENERATORS

LIMITING CONDITION FOR OPERATION

3.4.5 Each steam generator shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With one or more steam generators inoperable, restore the inoperable generator(s) to OPERABLE status prior to increasing T_{avg} above 200°F.

SURVEILLANCE REQUIREMENTS

4.4.5.0 Each steam generator shall be demonstrated OPERABLE by performance of the following augmented inservice inspection program and the requirement of Specification 4.0.5.

4.4.5.1 Steam Generator Sample Selection and Inspection - Each steam generator shall be determined OPERABLE during shutdown by selecting and inspecting at least the minimum number of steam generators specified in Table 4.4-1.

4.4.5.2 Steam Generator Tube Sample Selection and Inspection - The steam generator tube minimum sample size, inspection result classification, and the corresponding action required shall be as specified in Table 4.4-2. The inservice inspection of steam generator tubes shall be performed at the frequencies specified in Specification 4.4.5.3 and the inspected tubes shall be verified acceptable per the acceptance criteria of Specification 4.4.5.4. The tubes selected for each inservice inspection shall include at least 3% of the total number of tubes in all steam generators; the tubes selected for these inspections shall be selected on a random basis except:

- a. Where experience in similar plants with similar water chemistry indicates critical areas to be inspected, then at least 50% of the tubes inspected shall be from these critical areas.
- b. The first sample of tubes selected for each inservice inspection (subsequent to the preservice inspection) of each steam generator shall include:

REACTOR COOLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

1. All nonplugged tubes that previously had detectable wall penetrations ($\geq 20\%$).
 2. Tubes in those areas where experience has indicated potential problems.
 3. A tube inspection (pursuant to Specification 4.4.5.4.a.8) shall be performed on each selected tube. If any selected tube does not permit the passage of the eddy current probe for a tube inspection, this shall be recorded and an adjacent tube shall be selected and subjected to a tube inspection.
- c. The tubes selected as the second and third samples (if required by Table 4.4-2) during each inservice inspection may be subjected to a partial tube inspection provided:
1. The tubes selected for these samples include the tubes from those areas of the tube sheet array where tubes with imperfections were previously found.
 2. The inspections include those portions of the tubes where imperfections were previously found.

The results of each sample inspection shall be classified into one of the following three categories.

Category

Inspection Results

- | | |
|-----|--|
| C-1 | Less than 5% of the total tubes inspected are degraded tubes and none of the inspected tubes are defective. |
| C-2 | One or more tubes, but not more than 1% of the total tubes inspected are defective, or between 5% and 10% of the total tubes inspected are degraded tubes. |
| C-3 | More than 10% of the total tubes inspected are degraded tubes or more than 1% of the inspected tubes are defective. |

Note: In all inspections, previously degraded tubes must exhibit significant ($\geq 10\%$) further wall penetrations to be included in the above percentage calculations.

REACTOR COOLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

4.4.5.3 Inspection Frequencies - The above required inservice inspections of steam generator tubes shall be performed at the following frequencies:

- a. The first inservice inspection shall be performed after 6 Effective Full Power Months but within 24 calendar months of initial criticality. Subsequent inservice inspections shall be performed at intervals of not less than 12 nor more than 24 calendar months after the previous inspection. If two consecutive inspections following service under AVT conditions, not including the preservice inspection, result in all inspection results falling into the C-1 category or if two consecutive inspections demonstrate that previously observed degradation has not continued and no additional degradation has occurred, the inspection interval may be extended to a maximum of once per 40 months.
- b. If the results of the inservice inspection of a steam generator conducted in accordance with Table 4.4-2 at 40 month intervals fall in Category C-3, the inspection frequency shall be increased to at least once per 20 months. The increase in inspection frequency shall apply until the subsequent inspections satisfy the criteria of Specification 4.4.5.3.a; the interval may then be extended to a maximum of once per 40 months.
- c. Additional, unscheduled inservice inspections shall be performed on each steam generator in accordance with the first sample inspection specified in Table 4.4-2 during the shutdown subsequent to any of the following conditions:
 1. Primary-to-secondary tubes leaks (not including leaks originating from tube-to-tube sheet welds) in excess of the limits of Specification 3.4.6.2.
 2. A seismic occurrence greater than the Operating Basis Earthquake.
 3. A loss-of-coolant accident requiring actuation of the engineered safeguards.
 4. A main steam line or feedwater line break.

REACTOR COOLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

4.4.5.4 Acceptance Criteria

a. As used in this Specification:

1. Imperfection means an exception to the dimensions, finish or contour of a tube from that required by fabrication drawings or specifications. Eddy-current testing indications below 20% of the nominal tube wall thickness, if detectable, may be considered as imperfections.
2. Degradation means a service-induced cracking, wastage, wear or general corrosion occurring on either inside or outside of a tube.
3. Degraded Tube means a tube containing imperfections $\geq 20\%$ of the nominal wall thickness caused by degradation.
4. % Degradation means the percentage of the tube wall thickness affected or removed by degradation.
5. Defect means an imperfection of such severity that it exceeds the plugging limit. A tube containing a defect is defective.
6. Plugging Limit means the imperfection depth at or beyond which the tube shall be removed from service because it may become unserviceable prior to the next inspection and is equal to 40% of the nominal tube wall thickness.
7. Unserviceable describes the condition of a tube if it leaks or contains a defect large enough to affect its structural integrity in the event of an Operating Basis Earthquake, a loss-of-coolant accident, or a steam line or feedwater line break as specified in 4.4.5.3.c, above.
8. Tube Inspection means an inspection of the steam generator tube from the point of entry (hot leg side) completely around the U-bend to the top support of the cold leg.

REACTOR COOLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

- b. The steam generator shall be determined OPERABLE after completing the corresponding actions (plug all tubes exceeding the plugging limit and all tubes containing through-wall cracks) required by Table 4.4-2.

4.4.5.5 Reports

- a. Following each inservice inspection of steam generator tubes, the number of tubes plugged in each steam generator shall be reported to the Commission within 15 days.
- b. The complete results of the steam generator tube inservice inspection shall be included in the Annual Operating Report for the period in which this inspection was completed. This report shall include:
 - 1. Number and extent of tubes inspected.
 - 2. Location and percent of wall-thickness penetration for each indication of an imperfection.
 - 3. Identification of tubes plugged.
- c. Results of steam generator tube inspections which fall into Category C-3 and require prompt notification of the Commission shall be reported pursuant to Specification 5.9.1 prior to resumption of plant operation. The written followup of this report shall provide a description of investigations conducted to determine cause of the tube degradation and corrective measures taken to prevent recurrence.

TABLE 4.4-1

MINIMUM NUMBER OF STEAM GENERATORS TO BE
INSPECTED DURING INSERVICE INSPECTION

Preservice Inspection	Yes
No. of Steam Generators per Unit	Four
First Inservice Inspection	Two
Second & Subsequent Inservice Inspections	One ²

Table Notation:

1. The inservice inspection may be limited to one steam generator on a rotating schedule encompassing 3 N % of the tubes (where N is the number of steam generators in the plant) if the results of the first or previous inspections indicate that all steam generators are performing in a like manner. Note that under some circumstances, the operating conditions in one or more steam generators may be found to be more severe than those in other steam generators. Under such circumstances the sample sequence shall be modified to inspect the most severe conditions.
2. Each of the other two steam generators not inspected during the first inservice inspection shall be inspected during the second and third inspections. The fourth and subsequent inspections shall follow the instructions described in 1 above.

REACTOR COOLANT SYSTEM

3/4.4.10. STRUCTURAL INTEGRITY

ASME CODE CLASS 1, 2 and 3 COMPONENTS

LIMITING CONDITION FOR OPERATION

3.4.10.1 The structural integrity of ASME Code Class 1, 2 and 3 components shall be maintained in accordance with Specification 4.4.10.1.

APPLICABILITY: ALL MODES

ACTION:

- a. With the structural integrity of any ASME Code Class 1 component(s) not conforming to the above requirements, restore the structural integrity of the affected component(s) to within its limit or isolate the affected component(s) prior to increasing the Reactor Coolant System temperature more than 50°F above the minimum temperature required by NDT considerations.
- b. With the structural integrity of any ASME Code Class 2 component(s) not conforming to the above requirements, restore the structural integrity of the affected component(s) to within its limit or isolate the affected component(s) prior to increasing the Reactor Coolant System temperature above 200°F.
- c. With the structural integrity of any ASME Code Class 3 component(s) not conforming to the above requirements, restore the structural integrity of the affected component(s) to within its limit or isolate the affected component(s) from service.
- d. The provisions of Specification 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

4.4.10.1 In addition to the requirements of Specification 4.0.5, each reactor coolant pump flywheel shall be inspected per the recommendations of Regulatory Position C.4.b of Regulatory Guide 1.14, Revision 1, August 1975.

REACTOR COOLANT SYSTEM

RELIEF VALVES - OPERATING

LIMITING CONDITION FOR OPERATION

3.4.11 Three power operated relief valves (PORVs) and their associated block valves shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTION:

- a. With one or more PORV(s) inoperable, within 1 hour either restore the PORV(s) to OPERABLE status or close the associated block valve(s) and remove power from the block valve(s); otherwise, be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.
- b. With one or more block valve(s) inoperable, within 1 hour either (1) restore the block valve(s) to OPERABLE status, or (2) close the block valve(s) and remove power from the block valve(s), or (3) close the associated PORV(s) and remove power from the associated solenoid valve(s); otherwise, be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.*
- c. The provisions of Specification 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

4.4.11.1 Each of the three PORVs shall be demonstrated OPERABLE:

- a. At least once per 31 days by performance of a CHANNEL FUNCTIONAL TEST, excluding valve operation, and
- b. At least once per 18 months by performance of a CHANNEL CALIBRATION.

*When ACTION 3.4.11.b.(3) is applied, no report pursuant to Specification 6.9.1.9 is required for the PORV.

REACTOR COOLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

4.4.11.2 Each of the three block valves shall be demonstrated OPERABLE at least once per 92 days by operating the valve through one complete cycle of full travel. The block valve(s) do not have to be tested nor is a report required pursuant to Specification 6.9.1.9 when ACTION 3.4.11.a is applied.

4.4.11.3 The emergency power supply for the PORVs and block valves shall be demonstrated OPERABLE at least once per 18 months by operating the valves through a complete cycle of full travel while the emergency buses are energized by the onsite diesel generators and onsite plant batteries. This testing can be performed in conjunction with the requirements of Specifications 4.8.1.1.2.b and 4.8.2.3.2.c.

EMERGENCY CORE COOLING SYSTEMS

SURVEILLANCE REQUIREMENTS

4.5.2 Each ECCS subsystem shall be demonstrated OPERABLE:

- a. At least once per 12 hours by verifying that the following valves are in the indicated positions with power to the valve operators removed:

<u>Valve Number</u>	<u>Valve Function</u>	<u>Valve Position</u>
a. IMO-390	a. RWST to RHR	a. Open
b. IMO-315	b. Low head SI to Hot Leg	b. Closed
c. IMO-325	c. Low head SI to Hot Leg	c. Closed
d. IMO-262*	d. Mini flow line	d. Open
e. IMO-263*	e. Mini flow line	e. Open
f. IMO-261*	f. SI Suction	f. Open
g. ICM-305*	g. Sump line	g. Closed
h. ICM-306*	h. Sump line	h. Closed

- b. At least once per 31 days by verifying that each valve (manual, power operated or automatic) in the flow path that is not locked, sealed, or otherwise secured in position, is in its correct position.

- c. By a visual inspection which verifies that no loose debris (rags, trash, clothing, etc.) is present in the containment which could be transported to the containment sump and cause restriction of the pump suctions during LOCA conditions. This visual inspection shall be performed:

1. For all accessible areas of the containment prior to establishing CONTAINMENT INTEGRITY, and
2. Of the areas affected within containment at the completion of each containment entry when CONTAINMENT INTEGRITY is established.

*These valves must change position during the switchover from injection to recirculation flow following LOCA.

EMERGENCY CORE COOLING SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- d. At least once per 18 months by:
 - 1. Verifying automatic isolation and interlock action of the RHR system from the Reactor Coolant System when the Reactor Coolant System pressure is above 600 psig.
 - 2. A visual inspection of the containment sump and verifying that the subsystem suction inlets are not restricted by debris and that the sump components (trash racks, screens, etc.) show no evidence of structural distress or corrosion.
- e. At least once per 18 months, during shutdown, by:
 - 1. Verifying that each automatic valve in the flow path actuates to its correct position on a Safety Injection test signal.
 - 2. Verifying that each of the following pumps start automatically upon receipt of a safety injection test signal:
 - a) Centrifugal charging pump
 - b) Safety injection pump
 - c) Residual heat removal pump
- f. By verifying that each of the following pumps develops the indicated discharge pressure on recirculation flow when tested pursuant to Specification 4.0.5:
 - 1. Centrifugal charging pump \geq 2405 psig
 - 2. Safety Injection pump \geq 1445 psig
 - 3. Residual heat removal pump \geq 195 psig
- g. By verifying the correct position of each mechanical stop for the the following Emergency Core Cooling System throttle valves:
 - 1. Within 4 hours following completion of each valve stroking operation or maintenance on the valve when the ECCS sub-systems are required to be OPERABLE.

EMERGENCY CORE COOLING SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

2. At least once per 18 months.

<u>Boron Injection Throttle Valves</u>	<u>Safety Injection Throttle Valves</u>
Valve Number	Valve Number
1. -SI-141 L1	1. -SI-121 N
2. -SI-141 L2	2. -SI-121 S
3. -SI-141 L3	
4. -SI-141 L4	

- h. By performing a flow balance test during shutdown following completion of modifications to the ECCS subsystem that alter the subsystem flow characteristics and verifying the following flow rates:

<u>Boron Injection System Single Pump*</u>	<u>Safety Injection System Single Pump**</u>
Loop 1 Boron Injection Flow 117.5 gpm	Loop 1 and 4 Cold Leg Flow \geq 300 gpm
Loop 2 Boron Injection Flow 117.5 gpm	Loop 2 and 3 Cold Leg Flow \geq 300 gpm
Loop ³ Boron Injection Flow 117.5 gpm	**Total SIS (single pump) flow, including miniflow, shall not exceed 650 gpm.
Loop 4 Boron Injection Flow 117.5 gpm	

*The flow rate in each Boron Injection (BI) line should be adjusted to provide 117.5 gpm (nominal) flow into each loop. Under these conditions there is zero mini-flow and 80 gpm simulated RCP seal injection line flow. The actual flow in each BI line may deviate from the nominal so long as the difference between the highest and lowest flow is 10 gpm or less and the total flow to the four branch lines does not exceed 470 gpm. Minimum flow (total flow) required is 345.8 gpm to the three most conservative (lowest flow) branch lines.

CONTAINMENT SYSTEMS

3/4.6.2 DEPRESSURIZATION AND COOLING SYSTEMS

CONTAINMENT SPRAY SYSTEM

LIMITING CONDITION FOR OPERATION

3.6.2.1 Two independent containment spray systems shall be OPERABLE with each spray system capable of taking suction from the RWST and transferring suction to the containment sump.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With one containment spray system inoperable, restore the inoperable spray system to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours; restore the inoperable spray system to OPERABLE status within the next 48 hours or be in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.6.2.1 Each containment spray system shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) in the flow path that is not locked sealed, or otherwise secured in position, is in its correct position.
- b. By verifying, that on recirculation flow, each pump develops a discharge pressure of ≥ 255 psig at a flow of ≥ 700 gpm, when tested pursuant to Specification 4.0.5.
- c. At least once per 18 months during shutdown, by:
 1. Verifying that each automatic valve in the flow path actuates to its correct position on a Containment Pressure--High-High test signal.
 2. Verifying that each spray pump starts automatically on a Containment Pressure--High-High test signal.
- d. At least once per 5 years by performing an air or smoke flow test through each spray header and verifying each spray nozzle is unobstructed.

This page intentionally left blank.

PLANT SYSTEMS

AUXILIARY FEEDWATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.1.2 At least three independent steam generator auxiliary feedwater pumps and associated flow paths shall be OPERABLE with:

- a. Two feedwater pumps, each capable of being powered from separate emergency busses, and
- b. One feedwater pump capable of being powered from an OPERABLE steam supply system.

APPLICABILITY: MODES 1, 2 and 3.

ACTION:

With one auxiliary feedwater pump inoperable, restore at least three auxiliary feedwater pumps (two capable of being powered from separate emergency busses and one capable of being powered by an OPERABLE steam supply steam) to OPERABLE status within 72 hours or be in HOT SHUTDOWN within the next 12 hours.

SURVEILLANCE REQUIREMENTS

4.7.1.2 The auxiliary feedwater system shall be demonstrated OPERABLE:

- a. By verifying that each motor driven pump develops a discharge pressure ≥ 1375 psig on recirculation flow when tested pursuant to specification 4.0.5.
- b. By verifying that the steam turbine driven pump develops a discharge pressure of ≥ 1285 psig at a flow of ≥ 700 gpm when the secondary steam supply pressure is greater than 310 psig. when tested pursuant to specification 4.0.5. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
- c. At least once per 31 days by verifying that each nonautomatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS

- d. At least once per 31 days by verifying that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER.
- e. At least once per 18 months during shutdown by:
 - 1. Verifying that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
 - 2. Verifying that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.

PLANT SYSTEMS

3/4.7.3 COMPONENT COOLING WATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.3.1 At least two independent component cooling water loops shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With only one component cooling water loop OPERABLE, restore at least two loops to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.3.1 At least two component cooling water loops shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) servicing safety related equipment that is not locked, sealed, or otherwise secured in position, is in its correct position.
- b. At least once per 18 months during shutdown, by verifying that each automatic valve servicing safety related equipment actuates to its correct position on a Safety Injection test signal.

This page intentionally left blank.

PLANT SYSTEMS

3/4.7.4 ESSENTIAL SERVICE WATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.4.1 At least two independent essential service water loops shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With only one service water loop OPERABLE, restore at least two loops to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.4.1 At least two essential service water loops shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) servicing safety related equipment that is not locked, sealed, or otherwise secured in position, is in its correct position.
- b. At least once per 18 months during shutdown, by verifying that each automatic valve servicing safety related equipment actuates to its correct position on a Safety Injection test signal.

This page intentionally left blank

APPLICABILITY

BASES

4.0.5 This specification ensures that inservice inspection of ASME Code Class 1, 2 and 3 components and inservice testing of ASME Code Class 1, 2 and 3 pumps and valves will be performed in accordance with a periodically updated version of Section XI of the ASME Boiler and Pressure Vessel Code and Addenda as required by 10 CFR 50.55a. Relief from any of the above requirements has been provided in writing by the Commission and is not a part of these technical specifications.

This specification includes a clarification of the frequencies for performing the inservice inspection and testing activities required by Section XI of the ASME Boiler and Pressure Vessel Code and applicable Addenda. This clarification is provided to ensure consistency in surveillance intervals throughout these technical specifications and to remove any ambiguities relative to the frequencies for performing and the required inservice inspection and testing activities.

Under the terms of this specification, the more restrictive requirements of the Technical Specifications take precedence over the ASME Boiler and Pressure Vessel Code and applicable Addenda. For example, the requirements of Specification 4.0.4 to perform surveillance activities prior to entry into an OPERATIONAL MODE or other specified applicability condition takes precedence over the ASME Boiler and Pressure Vessel Code provision which allows pumps to be tested up to one week after return to normal operation. And for example, the Technical Specification definition of OPERABLE does not grant a grace period before a device that is not capable of performing its specified function is declared inoperable and takes precedence over the ASME Boiler and Pressure Vessel Code provision which allows a valve to be incapable of performing its specified function for up to 24 hours before being declared inoperable.

REACTOR COOLANT SYSTEM

BASES

3/4.4.10 STRUCTURAL INTEGRITY

The inspection and testing programs for ASME Code Class 1, 2 and 3 components ensure that the structural integrity of these components will be maintained at an acceptable level throughout the life of the plant. To the extent applicable, the inspection program for these components is in compliance with Section XI of the ASME Boiler and Pressure Vessel Code.

3/4.4.11 RELIEF VALVES

The power operated relief valves (PORVs) operate to relieve RCS pressure below the setting of the pressurizer code safety valves. These relief valves have remotely operated block valves to provide a positive shutoff capability should the relief valve become inoperable. The electrical power for both the relief valves and the block valves is supplied from an emergency power source to ensure the ability to seal this possible RCS leakage path.

ATTACHMENT NO. 3 TO AEP:NRC:0433
REVISED TECHNICAL SPECIFICATIONS PAGES
DONALD C. COOK NUCLEAR PLANT
UNIT NO. 2

REACTIVITY CONTROL SYSTEMS

CHARGING PUMP - SHUTDOWN

LIMITING CONDITION FOR OPERATION

3.1.2.3 One charging pump in the boron injection flow path required by Specification 3.1.2.1 shall be OPERABLE and capable of being powered from an OPERABLE emergency bus.

APPLICABILITY: MODES 5 and 6.

ACTION:

- a. With no charging pump OPERABLE, suspend all operations involving CORE ALTERATIONS or positive reactivity changes.
- b. With more than one charging pump OPERABLE or with a safety injection pump(s) OPERABLE when the temperature of any RCS cold leg is less than or equal to 152°F, unless the reactor vessel head is removed, remove the additional charging pump(s) and the safety injection pump(s) motor circuit breakers from the electrical power circuit within one hour.
- c. The provisions of Specification 3.0.3 are not applicable.

SURVEILLANCE REQUIREMENTS

4.1.2.3.1 The above required charging pump shall be demonstrated OPERABLE by verifying, that on recirculation flow, the pump develops a discharge pressure of ≥ 2390 psig when tested pursuant to Specification 4.0.5.

4.1.2.3.2 All charging pumps and safety injection pumps, excluding the above required OPERABLE charging pump, shall be demonstrated inoperable by verifying that the motor circuit breakers have been removed from their electrical power supply circuits at least once per 12 hours, except when:

- a. The reactor vessel head is removed, or
- b. The temperature of all RCS cold legs is greater than 152°F.

PLANT SYSTEMS

AUXILIARY FEEDWATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.1.2 At least three independent steam generator auxiliary feedwater pumps and associated flow paths shall be OPERABLE with:

- a. Two feedwater pumps, each capable of being powered from separate emergency busses, and
- b. One feedwater pump capable of being powered from an OPERABLE steam supply system.

APPLICABILITY: MODES 1, 2 and 3.

ACTION:

With one auxiliary feedwater pump inoperable, restore at least three auxiliary feedwater pumps (two capable of being powered from separate emergency busses and one capable of being powered by an OPERABLE steam supply steam) to OPERABLE status within 72 hours or be in HOT SHUTDOWN within the next 12 hours.

SURVEILLANCE REQUIREMENTS

4.7.1.2 The auxiliary feedwater system shall be demonstrated OPERABLE:

- a. By verifying that each motor driven pump develops a discharge pressure ≥ 1375 psig on recirculation flow when tested pursuant to specification 4.0.5.
- b. By verifying that the steam turbine driven pump develops a discharge pressure of ≥ 1285 psig at a flow of ≥ 700 gpm when the secondary steam supply pressure is greater than 310 psig. when tested pursuant to specification 4.0.5. The provisions of Specification 4.0.4 are not applicable for entry into MODE 3.
- c. At least once per 31 days by verifying that each nonautomatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS

- d. At least once per 31 days by verifying that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER.
- e. At least once per 18 months during shutdown by:
 - 1. Verifying that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
 - 2. Verifying that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.