

Attachment 2 to AEP:NRC:0916AE

Proposed Revised Technical Specification Pages
for D. C. Cook Unit 2

8711030476 871028
PDR ADOCK 05000316
P PDR

3/4.0 APPLICABILITY

SURVEILLANCE REQUIREMENTS

- b. Surveillance intervals specified in Section XI of the ASME Boiler and Pressure Vessel Code and applicable Addenda for the inservice inspection and testing activities required by the ASME Boiler and Pressure Vessel Code and applicable Addenda shall be applicable as follows in these Technical Specifications:

ASME Boiler and Pressure Vessel
Code and applicable Addenda
terminology for inservice
inspection and testing criteria

Required frequencies for
performing inservice in-
spection and testing
activities

Weekly
Monthly
Quarterly or every 3 months
Semiannually or every 6 months
Yearly or annually

At least once per 7 days
At least once per 31 days
At least once per 92 days
At least once per 184 days
At least once per 366 days

- c. The provisions of Specification 4.0.2 are applicable to the above required frequencies for performing inservice inspection and testing activities.
- d. Performance of the above inservice inspection and testing activities shall be in addition to other specified Surveillance Requirements.
- e. Nothing in the ASME Boiler and Pressure Vessel Code shall be construed to supersede the requirements of any Technical Specification.
- 4.0.6 By specific reference to this section, those surveillances which must be performed on or before March 31, 1986, and are designated as 18-month surveillances (or required as outage-related surveillances under the provisions of Specification 4.0.5) may be delayed until the end of the refueling outage scheduled to begin on or before February 28, 1986. For these specific surveillances under this section, the specified time intervals required by Specification 4.0.2 will be determined with the new initiation date established by the surveillance date during the Unit 2 1986 refueling outage.
- 4.0.7 By specific reference to this section, those surveillances which must be performed on or before July 1, 1988 and are designated as 18-month surveillances (or required as outage-related surveillances under the provisions of Specification 4.0.5) may be delayed until the end of the cycle 6-7 refueling outage (currently scheduled to begin during the latter part of the second quarter of 1988). For these specific surveillances under this section, the specified time intervals required by Specification 4.0.2 will be determined with the new initiation date established by the surveillance date during the Unit 2 1988 refueling outage.

3/4.3 INSTRUMENTATION

3/4.3.1 REACTOR TRIP SYSTEM INSTRUMENTATION

LIMITING CONDITION FOR OPERATION

3.3.1.1 As a minimum, the reactor trip system instrumentation channels and interlocks of Table 3.3-1 shall be OPERABLE with RESPONSE TIMES as shown in Table 3.3-2.

APPLICABILITY: As shown in Table 3.3-1.

ACTION:

As shown in Table 3.3-1.

SURVEILLANCE REQUIREMENTS

4.3.1.1.1. Each reactor trip system instrumentation channel shall be demonstrated OPERABLE by the performance of the CHANNEL CHECK, CHANNEL CALIBRATION and CHANNEL FUNCTIONAL TEST operations for the MODES and at the frequencies shown in Table 4.3-1.*

4.3.1.1.2 The logic for the interlocks shall be demonstrated OPERABLE prior to each reactor startup unless performed during the preceding 92 days. The total interlock function shall be demonstrated OPERABLE at least once per 18 months during CHANNEL CALIBRATION testing of each channel affected by interlock operation.*

4.3.1.1.3 The REACTOR TRIP SYSTEM RESPONSE TIME of each reactor trip function shall be demonstrated to be within its limit at least once per 18 months. Each test shall include at least one logic train such that both logic trains are tested at least once per 36 months and one channel per function such that all channels are tested at least once every N times 18 months where N is the total number of redundant channels in a specific reactor trip function as shown in the "Total No. of Channels" column of Table 3.3-1.*, **

* The provisions of Specification 4.0.6 are applicable.

** The provisions of Specification 4.0.7 are applicable.

INSTRUMENTATION

3/4.3.2 ENGINEERED SAFETY FEATURE ACTUATION SYSTEM INSTRUMENTATION

LIMITING CONDITION FOR OPERATION

3.3.2.1 The Engineered Safety Feature Actuation System (ESFAS) instrumentation channels and interlocks shown in Table 3.3-3 shall be OPERABLE with their trip setpoints set consistent with the values shown in the Trip Setpoint column of Table 3.3-4 and with RESPONSE TIMES as shown in Table 3.3-5.

APPLICABILITY: As shown in Table 3.3-3.

ACTION:

- a. With an ESFAS instrumentation channel trip setpoint less conservative than the value shown in the Allowable Values column of Table 3.3-4, declare the channel inoperable and apply the applicable ACTION requirement of Table 3.3-3 until the channel is restored to OPERABLE status with the trip setpoint adjusted consistent with the Trip Setpoint value.
- b. With an ESFAS instrumentation channel inoperable, take the ACTION shown in Table 3.3-3.

SURVEILLANCE REQUIREMENTS

4.3.2.1.1 Each ESFAS instrumentation channel shall be demonstrated OPERABLE the performance of the CHANNEL CHECK, CHANNEL CALIBRATION and CHANNEL FUNCTIONAL TEST operations for the MCCES and at the frequencies shown in Table 4.3-2.*

4.3.2.1.2 The logic for the interlocks shall be demonstrated OPERABLE during the automatic actuation logic test. The total interlock function shall be demonstrated OPERABLE at least once per 18 months during CHANNEL CALIBRATION testing of each channel affected by interlock operation.*

4.3.2.1.3 The ENGINEERED SAFETY FEATURES RESPONSE TIME of each ESFAS function shall be demonstrated to be within the limit at least once per 18 months. Each test shall include at least one logic train such that both logic trains are tested at least once per 36 months and one channel per function such that all channels are tested at least once per N times 18 months where N is the total number of redundant channels in a specific ESFAS function as shown in the "Total No. of Channels" Column of Table 3.3-3.* **

* The provisions of Specification 4.0.6 are applicable.

** The provisions of Specification 4.0.7 are applicable.

TABLE 4.3-2 (Continued)
ENGINEERED SAFETY FEATURE ACTUATION SYSTEM INSTRUMENTATION
SURVEILLANCE REQUIREMENTS

<u>FUNCTIONAL UNIT</u>	<u>CHANNEL CHECK</u>	<u>CHANNEL CALIBRATION</u>	<u>CHANNEL FUNCTIONAL TEST</u>	<u>MODES IN WHICH SURVEILLANCE REQUIRED</u>
4. STEAM LINE ISOLATION				
a. Manual	N.A.	N.A.	M(1)	1, 2, 3
b. Automatic Actuation Logic	N.A.	N.A.	M(2)	1, 2, 3
c. Containment Pressure-- High-High	S	R	M(3)	1, 2, 3
d. Steam Flow in Two Steam Lines-- High Coincident with T _{avg} --Low-Low	S	R	M	1, 2, 3
e. Steam Line Pressure-Low	S	R	M	1, 2, 3
5. TURBINE TRIP AND FEEDWATER ISOLATION				
a. Steam Generator Water Level--High-High	S	R	M	1, 2, 3 and
6. MOTOR DRIVEN AUXILIARY FEEDWATER PUMPS				
a. Steam Generator Water Level -- Low-Low	S	R	M	1, 2, 3
b. 4 kv Bus Loss of Voltage	S	R	M	1, 2, 3
c. Safety Injection	N.A.	N.A.	M(2)	1, 2, 3
d. Loss of Main Feed Pumps	N.A.	N.A.	R ⁺	1, 2

+ The provisions of Specification 4.0.7 are applicable.

REACTOR COOLANT SYSTEM

LIMITING CONDITION FOR OPERATION (Continued)

2. With two or more block valves inoperable,

within 1 hour either (1) restore a total of at least two block valves to OPERABLE status, or (2) close the block valves and remove power from the block valves, or (3) close the associated PORVs and remove power from their associated solenoid valves; and apply the portions of ACTION a.2 or a.3 above for inoperable PORVs, relating to OPERATIONAL MODE, as appropriate.

- c. With PORVs and block valves not in the same line inoperable,*

within 1 hour either (1) restore the valves to OPERABLE status or (2) close and de-energize the other valve in each line. Apply the portions of ACTION a.2 or a.3 above, relating to OPERATIONAL MODE, as appropriate for two or three lines unavailable.

- d. The provisions of Specification 3.0.4 are not applicable.

SURVEILLANCE REQUIREMENTS

- 4.4.11.1 Each of the three PORVs shall be demonstrated OPERABLE:

- a. At least once per 31 days by performance of a CHANNEL FUNCTIONAL TEST, excluding valve operation, and
- b. At least once per 18 months by performance of a CHANNEL CALIBRATION.

- 4.4.11.2 Each of the three block valves shall be demonstrated OPERABLE at least once per 92 days by operating the valve through one complete cycle of full travel. The block valve(s) do not have to be tested when ACTION 3.4.11.a or 3.4.11.c is applied.

- 4.4.11.3 The emergency power supply for the PORVs and block valves shall be demonstrated OPERABLE at least once per 18 months by operating the valves through a complete cycle of full travel while the emergency buses are energized by the onsite diesel generators and onsite plant batteries. This testing can be performed in conjunction with the requirements of Specifications 4.8.1.1.2.c and 4.8.2.3.2.d. **

* PORVs isolated to limit RCS leakage through their seats and the block valves shut to isolate this leakage are not considered inoperable.

** The provisions of Specification 4.0.7 are applicable.

TABLE 4.3-10

POST-ACCIDENT MONITORING INSTRUMENTATION SURVEILLANCE REQUIREMENTS

<u>INSTRUMENT</u>	<u>CHANNEL</u>	<u>CHANNEL</u>
	<u>CHECK</u>	<u>CALIBRATION</u>
1. Containment Pressure	M	R
2. Reactor Coolant Outlet Temperature - T _{HOT} (Wide Range)	M	R
3. Reactor Coolant Inlet Temperature - T _{COLD} (Wide Range)	M	R
4. Reactor Coolant Pressure - Wide Range	M	R
5. Pressurizer Water Level	M	R
6. Steam Line Pressure	M	R
7. Steam Generator Water Level - Narrow Range	M	R
8. RWST Water Level	M	R
9. Boric Acid Tank Solution Level	M	R
10. Auxiliary Feedwater Flow Rate	M	R
11. Reactor Coolant System Subcooling Margin Monitor	M	R
12. PORV Position Indicator - Limit Switches	M	R
13. PORV Block Valve Position Indicator - Limit Switches	M	R
14. Safety Valve Position Indicator - Acoustic Monitor	M	R
15. Incore Thermocouples (Core Exit Thermocouples) (4)	M	R(1)
16. Reactor Coolant Inventory Tracking System (Reactor Vessel Level Indication)	M(2)	R(3) +

(1) Partial range channel calibration for sensor to be performed below P-12 in MODE 3.

(2) With one train of Reactor Vessel Level Indication inoperable, Subcooling Margin Indication and Core Exit Thermocouples may be used to perform a CHANNEL CHECK to verify the remaining Reactor Vessel Indication train OPERABLE.

(3) Completion of channel calibration for sensors to be performed below P-12 in MODE 3.

(4) The core exit thermocouples will not be installed until the 1988 refueling outage; therefore, surveillances will not be required until that time. See license amendment dated April 10, 1987.

+ The provisions of Specification 4.0.7 are applicable.

EMERGENCY CORE COOLING SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- b. At least once per 31 days and within 6 hours after each solution volume increase of $\geq 1\%$ of tank volume by verifying the boron concentration of the accumulator solution.
- c. At least once per 31 days when the RCS pressure is above 2000 psig by verifying that power to the isolation valve operator is disconnected by removal of the breaker from the circuit...
- d. At least once per 18 months by verifying that each accumulator isolation valve opens automatically upon receipt of a safety injection test signal.*

* The provisions of Specification 4.0.7 are applicable.

EMERGENCY CORE COOLING SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- d. At least once per 18 months by:
 - 1. Verifying automatic isolation and interlock action of the RHR system from the Reactor Coolant System when the Reactor Coolant System pressure is above 600 psig.
 - 2. A visual inspection of the containment sump and verifying that the subsystem suction inlets are not restricted by debris and that the sump components (trash racks, screens, etc.) show no evidence of structural distress or corrosion.
- e. At least once per 18 months, during shutdown, by: *
 - 1. Verifying that each automatic valve in the flow path actuates to its correct position on a Safety Injection test signal.
 - 2. Verifying that each of the following pumps start automatically upon receipt of a safety injection test signal:
 - a) Centrifugal charging pump
 - b) Safety injection pump
 - c) Residual heat removal pump
- f. By verifying that each of the following pumps develops the indicated discharge pressure on recirculation flow when tested pursuant to Specification 4.0.5:
 - 1. Centrifugal charging pump \geq 2405 psig
 - 2. Safety Injection pump \geq 1445 psig
 - 3. Residual heat removal pump \geq 195 psig
- g. By verifying the correct position of each mechanical stop for the the following Emergency Core Cooling System throttle valves:
 - 1. Within 4 hours following completion of each valve stroking operation or maintenance on the valve when the ECCS sub-systems are required to be OPERABLE.

* The provisions of Specification 4.0.7 are applicable.

CONTAINMENT SYSTEMS

3/4.6.2 DEPRESSURIZATION AND COOLING SYSTEMS

CONTAINMENT SPRAY SYSTEM

LIMITING CONDITION FOR OPERATION

3.6.2.1 Two independent containment spray systems shall be OPERABLE with each spray system capable of taking suction from the RWST and transferring suction to the containment sump.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With one containment spray system inoperable, restore the inoperable spray system to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours; restore the inoperable spray system to OPERABLE status within the next 48 hours or be in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.6.2.1 Each containment spray system shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) in the flow path that is not locked sealed, or otherwise secured in position, is in its correct position.
- b. By verifying, that on recirculation flow, each pump develops a discharge pressure of ≥ 255 psig at a flow of ≥ 700 gpm, when tested pursuant to Specification 4.0.5.
- c. At least once per 18 months during shutdown, by: *
 1. Verifying that each automatic valve in the flow path actuates to its correct position on a Containment Pressure--High-High test signal.
 2. Verifying that each spray pump starts automatically on a Containment Pressure--High-High test signal.
- d. At least once per 5 years by performing an air or smoke flow test through each spray header and verifying each spray nozzle is unobstructed.

* The provisions of Specification 4.0.7 are applicable.

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- c. At least once per 18 months during shutdown, by verifying that each automatic valve in the flow path actuates to its correct position on a Containment Pressure--High-High test signal.*
- d. At least once per 5 years by verifying a water flow rate of at least 20 gpm (≥ 20 gpm) but not to exceed 50 gpm (≤ 50 gpm) from the spray additive tank test line to each containment spray system with the spray pump operating on recirculation with a pump discharge pressure ≥ 255 psig.

* The provisions of Specification 4.0.7 are applicable.

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

4.6.3.1.2 Each isolation valve specified in Table 3.6-1 shall be demonstrated OPERABLE during the COLD SHUTDOWN or REFUELING MODE at least once per 18 months by: *

- a. Verifying that on a Phase A containment isolation test signal, each Phase A isolation valve actuates to its isolation position.
- b. Verifying that on a Phase B containment isolation test signal, each Phase B isolation valve actuates to its isolation position.
- c. Verifying that on a Containment Purge and Exhaust isolation test signal, each Purge and Exhaust valve actuates to its isolation position.

4.6.3.1.3 The isolation time of each power operated or automatic valve of Table 3.6-1 shall be determined to be within its limit when tested pursuant to Specification 4.0.5.

* The provisions of Specification 4.0.7 are applicable.

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

3. Verifying that each non-automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in its correct position.
 4. Verifying that each automatic valve in the flow path is in the fully open position whenever the auxiliary feedwater system is placed in automatic control or when above 10% RATED THERMAL POWER. This requirement is not applicable for those portions of the Auxiliary Feedwater System being used intermittently to maintain steam generator level.
- b. At least once per 18 months during shutdown by: *
1. Verifying that each automatic valve in the flow path actuates to its correct position upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.
 2. Verifying that each auxiliary feedwater pump starts as designed automatically upon receipt of the appropriate engineered safety features actuation test signal required by Specification 3/4.3.2.

* The provisions of Specification 4.0.7 are applicable.



PLANT SYSTEMS

3/4.7.3 COMPONENT COOLING WATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.3.1 At least two independent component cooling water loops shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With only one component cooling water loop OPERABLE, restore at least two loops to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.3.1 At least two component cooling water loops shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) servicing safety related equipment that is not locked, sealed, or otherwise secured in position, is in its correct position.
- b. At least once per 18 months during shutdown, by verifying that each automatic valve servicing safety related equipment actuates to its correct position on a Safety Injection test signal*.

* The provisions of Specification 4.0.7 are applicable.

PLANT SYSTEMS

3/4.7.4 ESSENTIAL SERVICE WATER SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.4.1 At least two independent essential service water loops shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3 and 4.

ACTION:

With only one service water loop OPERABLE, restore at least two loops to OPERABLE status within 72 hours or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.4.1 At least two essential service water loops shall be demonstrated OPERABLE:

- a. At least once per 31 days by verifying that each valve (manual, power operated or automatic) servicing safety related equipment that is not locked, sealed, or otherwise secured in position, is in its correct position.
- b. At least once per 18 months during shutdown, by verifying that each automatic valve servicing safety related equipment actuates to its correct position on a Safety Injection test signal.*

* The provisions of Specification 4.0.7 are applicable.

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

e. At least once per 18 months by:

1. Verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is < 6 inches Water Gauge while operating the ventilation system at a flow rate of 6000 cfm $\pm 10\%$.
2. Verifying that on a Safety Injection Signal from either Unit 1 or Unit 2, or on a containment phase A isolation signal, the system automatically diverts its inlet flow through the HEPA filters and charcoal adsorber bank and that either fan can then be manually started in the recirculation mode.*
3. Verifying that the system maintains the control room at a positive pressure of $> 1/16$ inch W. G. relative to the outside atmosphere at a system flow rate of 6000 cfm $\pm 10\%$.

f. After each complete or partial replacement of a HEPA filter bank by verifying that the HEPA filter banks remove $> 99\%$ of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the ventilation system at a flow rate of 6000 cfm $\pm 10\%$.

g. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove $> 99\%$ of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the ventilation system at a flow rate of 6000 cfm $\pm 10\%$.

* The provisions of Specification 4.0.7 are applicable.

PLANT SYSTEM

SURVEILLANCE REQUIREMENTS (Continued)

3. Verifying that the standby fan starts automatically on a Containment Pressure--High-High Signal and diverts its exhaust flow through the HEPA filters and charcoal adsorber banks on a Containment Pressure--High-High Signal.*
- e. After each complete or partial replacement of HEPA filter bank by verifying that the HEPA filter banks remove $\geq 99\%$ of the DOP when they are tested in-place in accordance with ANSI NS10-1975 while operating the ventilation system at a flow rate of 25,000 cfm $\pm 10\%$.
- f. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove $\geq 99\%$ of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI NS10-1975 while operating the ventilation system at a flow rate of 25,000 cfm $\pm 10\%$.

* The provisions of Specification 4.0.7 are applicable.

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

3. Verifying the fuel transfer pump can be started and transfers fuel from the storage system to the day tank.
 4. Verifying the diesel starts from ambient condition and accelerates to at least 514 rpm in ≤ 10 seconds.
 5. Verifying the generator is loaded to ≥ 1750 kw, and operates for ≥ 60 minutes and verifying that the generator output breaker to the emergency bus is OPERABLE.
 6. Verifying the diesel generator is aligned to provide standby power to the associated emergency busses.
- b. At least once per 92 days by verifying that a sample of diesel fuel from the fuel storage tank obtained in accordance with ASTM-D270-65 is within the acceptable limits specified in Table 1 of ASTM-D975-74 when checked for viscosity, water and sediment.
- c. At least once per 18 months during shutdown by:*
1. Subjecting the diesel to an inspection in accordance with procedures prepared in conjunction with its manufacturer's recommendations for this class of standby service.
 2. Verifying that the automatic sequence timing relays are OPERABLE with each load sequence time within $\pm 5\%$ of its required value and that each load is sequenced on within the design allowable time limit.
 3. Verifying the generator capability to reject a load of > 600 kw while maintaining voltage at 4160 ± 420 volts and frequency at 60 ± 1.2 Hz.
 4. Verifying the generator capability to reject a load of 3500 kw without exceeding 75% of the difference between nominal speed and the overspeed trip setpoint.
 5. Simulating a loss of offsite power by itself, and:
 - a) Verifying de-energization of the emergency busses and load shedding from the emergency busses.

* The provisions of Specification 4.0.7 are applicable.

ELECTRICAL POWER SYSTEMS

SHUTDOWN

LIMITING CONDITION FOR OPERATION

3.8.1.2 As a minimum, the following A.C. electrical power sources shall be OPERABLE:

- a. One circuit between the offsite transmission network and the onsite Class 1E distribution system, and
- b. One diesel generator with:
 1. A day fuel tank containing a minimum volume of 70 gallons of fuel,
 2. A fuel storage system containing a minimum volume of 42,000 gallons of fuel, and
 3. A fuel transfer pump.

APPLICABILITY: MODES 5 and 6.

ACTION:

With less than the above minimum required A.C. electrical power sources OPERABLE, suspend all operations involving CORE ALTERATIONS or positive reactivity changes.

SURVEILLANCE REQUIREMENTS

4.8.1.2 The above required A.C. electrical power sources shall be demonstrated OPERABLE by the performance of each of the Surveillance Requirements of 4.8.1.1.1 and 4.8.1.1.2 except for Requirement 4.8.1.1.2.a.5.*, **

* The provisions of Specification 4.0.6 are applicable.

** The provisions of Specification 4.0.7 are applicable.

REFUELING OPERATIONS

CONTAINMENT BUILDING PENETRATIONS

LIMITING CONDITION FOR OPERATION

3.9.4 The containment building penetrations shall be in the following status:

- a. The equipment door closed and held in place by a minimum of four bolts,
- b. A minimum of one door in each airlock is closed, and
- c. Each penetration providing direct access from the containment atmosphere to the outside atmosphere shall be either:
 1. Closed by an isolation valve, blind flange, or manual valve, or
 2. Be capable of being closed by an OPERABLE automatic Containment Purge and Exhaust isolation valve.

APPLICABILITY: During CORE ALTERATIONS or movement of irradiated fuel within the containment.

ACTION:

With the requirements of the above specification not satisfied, immediately suspend all operations involving CORE ALTERATIONS or movement of irradiated fuel in the containment building. The provisions of Specification 3.0.3 are not applicable.

SURVEILLANCE REQUIREMENTS

4.9.4 Each of the above required containment building penetrations shall be determined to be either in its closed/isolated condition or capable of being closed by an OPERABLE automatic Containment Purge and Exhaust isolation valve within 100 hours prior to the start of and at least once per 7 days during CORE ALTERATIONS or movement of irradiated fuel in the containment building by:

- a. Verifying the penetrations are in their closed/isolated condition, or
- b. Testing the Containment Purge and Exhaust isolation valves per the applicable portions of Specification 4.6.3.1.2.*

* The provisions of Specification 4.0.7 are applicable.

