

REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR: 7910220255 DOC. DATE: 79/10/16 NOTARIZED: NO DOCKET #
 FACIL: 50-250 Turkey Point Plant, Unit 3, Florida Power and Light C 05000250
 AUTH. NAME AUTHOR AFFILIATION
 UHRIG, R.E. Florida Power & Light Co.
 RECIP. NAME RECIPIENT AFFILIATION
 DENTON, H.R. Office of Nuclear Reactor Regulation

SUBJECT: Forwards revised Page 2 of integrated leak rate test rept.

DISTRIBUTION CODE: A017S COPIES RECEIVED: LTR 3 ENCL 3 SIZE: 2
 TITLE: Containment Leak Rate Testing - Appendix J

NOTES: -----

	RECIPIENT		COPIES			RECIPIENT		COPIES	
	ID	CODE/NAME	LTTR	ENCL		ID	CODE/NAME	LTTR	ENCL
ACTION:	05	BC ORB #1	7	7		LA	ORB #1	1	0
INTERNAL:	01	REG FILE	1	1		02	NRC PDR	1	1
	12	I&E	2	2		14	TA/EDO	1	1
	16	ENGR BR	1	1		17	REAC SFTY BR	1	1
	18	PLANT SYS BR	1	1		19	EEB	1	1
	20	EFLT TRT SYS	1	1		21	OELD	1	1
	22	CONTMNT SYS	1	1		23	HUANG, Y.S.	1	1
EXTERNAL:	03	LPDR	1	1		04	NSIC	1	1
	24	ACRS	16	16					

OCT 23 1979

ccp

MAZ





October 16, 1979
L-79-289

Mr. Harold R. Denton, Director
Office of Nuclear Reactor Regulation
U. S. Nuclear Regulatory Commission
Washington, D. C. 20555

Dear Mr. Denton:

Re: Turkey Point Unit 3
Docket No. 50-250
Integrated Leak Rate Test Report

The subject report was forwarded to you on June 20, 1979 (L-79-171). Since then, we have revised page 2 of the report to bring Section III.B (Technical Data) into agreement with the Final Safety Analysis Report. Twelve copies of the revised page are attached for use by your office.

Very truly yours,

Robert E. Uhrig
Vice President
Advanced Systems & Technology

REU/MAS/cph

cc: Mr. James P. O'Reilly, Region II
Robert Lowenstein, Esquire

A017
5/3

7910220 255

III. TEST DATA SUMMARY

A. Plant Information

Owner	Florida Power and Light Company
Plant	Turkey Point Plant, Unit 3
Location	Homestead, Florida
Containment Type	Prestressed, post-tensioned concrete
NSSS Supplier, Type	Westinghouse, PWR
Date Test Completed	March 20, 1979

B. Technical Data

- | | |
|--|-------------------|
| 1. Containment Net Free Air Volume | 1,550,000 cu. ft. |
| 2. Design Pressure | 59 psig |
| 3. Design Temperature | 283°F |
| 4. Calculated Peak Accident Pressure, Pa | 50 psig |
| 5. Containment ILRT Average Temperature Limits | 80 - 90°F |
| 6. Calculated Peak Accident Temperature | 276°F |

C. Test Results - Type A Test

- | 1. Test Method | Absolute | | | | | | | | |
|--|--|---------------------|--|---|-------------------------------------|------------------------|------------------|------------------------|------------------|
| 2. Data Analysis Techniques | Mass Point (per ANSI N274)
and Total-Time (per BN-TOP-1) | | | | | | | | |
| 3. Test Pressure | 25 psig | | | | | | | | |
| 4. Maximum Allowable Leakage Rate, L_t | 0.1029%/day | | | | | | | | |
| 5. 75% of L_t | 0.0772%/day | | | | | | | | |
| 6. Integrated Leakage Rate Test Results | <table><thead><tr><th colspan="2">Leakage Rate, %/day</th></tr><tr><th>From Regres-
sion Line
(L_{tm})</th><th>At Upper 95%
Confidence
Limit</th></tr></thead><tbody><tr><td>a. Mass point analysis</td><td>0.031 0.033</td></tr><tr><td>b. Total-Time analysis</td><td>0.034 0.060</td></tr></tbody></table> | Leakage Rate, %/day | | From Regres-
sion Line
(L_{tm}) | At Upper 95%
Confidence
Limit | a. Mass point analysis | 0.031 0.033 | b. Total-Time analysis | 0.034 0.060 |
| Leakage Rate, %/day | | | | | | | | | |
| From Regres-
sion Line
(L_{tm}) | At Upper 95%
Confidence
Limit | | | | | | | | |
| a. Mass point analysis | 0.031 0.033 | | | | | | | | |
| b. Total-Time analysis | 0.034 0.060 | | | | | | | | |
| 7. Verification Test Imposed Leakage Rate, L_o , %/day | 0.103 | | | | | | | | |

