

ATTACHMENT 3

PROPOSED TECHNICAL SPECIFICATIONS

Marked-up Technical Specifications Pages,

6-20

9501270177 950117
PDR ADDCK 05000250
P PDR

ADMINISTRATIVE CONTROLS

PEAKING FACTOR LIMIT REPORT (Continued)

Factor Limit Report, the Peaking Factor Limit Report shall be provided to the NRC Document Control desk with copies to the Regional Administrator and the Resident Inspector within 30 days of their implementation, unless otherwise approved by the Commission.

The analytical methods used to generate the Peaking Factor limits shall be those previously reviewed and approved by the NRC. If changes to these methods are deemed necessary they will be evaluated in accordance with 10 CFR 50.59 and submitted to the NRC for review and approval prior to their use if the change is determined to involve an unreviewed safety question or if such a change would require amendment of previously submitted documentation.

CORE OPERATING LIMITS REPORT

6.9.1.7 Core operating limits shall be established and documented in the CORE OPERATING LIMITS REPORT (COLR) before each reload cycle or any remaining part of a reload cycle for the following:

1. Axial Flux Difference for Specification 3.2.1.
2. Control Rod Insertion Limits for Specification 3.1.3.6.
3. Heat Flux Hot Channel Factor - $F_Q(Z)$ for Specification 3/4.2.2.

The analytical methods used to determine the AFD limits shall be those previously reviewed and approved by the NRC in:

1. WCAP-10216-P-A, "RELAXATION OF CONSTANT AXIAL OFFSET CONTROL F_Q SURVEILLANCE TECHNICAL SPECIFICATION," June 1983.
2. WCAP-8385, "POWER DISTRIBUTION CONTROL AND LOAD FOLLOWING PROCEDURES - TOPICAL REPORT," September 1974.

The analytical methods used to determine the K(Z) curve shall be those previously reviewed and approved by the NRC in:

1. WCAP-9220-P-A, Rev. 1, "Westinghouse ECCS Evaluation Model-1981 Version," February 1982.
2. WCAP-9561-P-A, ADD. 3, Rev. 1, "BART A-1: A Computer Code for the Best Estimate Analysis of Reflood Transients - Special Report: Thimble Modeling W ECCS Evaluation Model."

The analytical methods used to determine the Rod Bank Insertion Limits shall be those previously reviewed and approved by the NRC in:

1. WCAP-9272-P-A, "Westinghouse Reload Safety Evaluation Methodology," July 1985.

INSERT (A) - here

The AFD, K(Z), and Rod Bank Insertion Limits shall be determined such that all applicable limits of the safety analyses are met. The CORE OPERATING LIMITS REPORT, including any mid-cycle revisions or supplements thereto, shall be provided upon issuance, for each reload cycle, to the NRC Document Control Desk with copies to the Regional Administrator and the Resident Inspector, unless otherwise approved by the Commission.

1426K (A) - 1000

L-95-006

INSERT (A)

The ability to calculate the COLR nuclear design parameters are demonstrated in:

1. Florida Power & Light Company Topical Report NF-TR-95-01, "Nuclear Physics Methodology for Reload Design of Turkey Point & St. Lucie Nuclear Plants".

Topical Report NF-TR-95-01 was approved by the NRC for use by Florida Power & Light Company in:

1. Safety Evaluation by the Office of Nuclear Reactor Regulations Related to Amendment No. xxx to Facility Operating License DPR-31 and Amendment No. xxx to Facility Operating License No. DPR-41, Florida Power & Light Company Turkey Point Units Nos. 3 and 4, Docket Nos. 50-250 and 50-251.

ATTACHMENT 4

FPL TOPICAL REPORT NF-TR-95-01:

NUCLEAR PHYSICS METHODOLOGY FOR RELOAD DESIGN
OF TURKEY POINT & ST. LUCIE NUCLEAR PLANTS