



RECEIVED
FEB 21 1983

DOCUMENT CONTROL CENTER



PERFORMANCE

GROSS GENERATION
KW.

905693.

TURBINE HEAT-RATE
BTU/KW-HR

10218.2

LEGEND

Q---FLOW-LBS/HR
F---TEMPERATURE-F
P---PRESSURE-LBS/SQ. IN ABS.
H---ENTHALPY OF STEAM-BTU/LB
FTD--TERMINAL DIFFERENCE (F)
ELEV-EXPANSION LINE END POINT
UEEP-USED ENERGY END POINT
D.C.-DRAIN COOLER APPROACH (F)
S.C.-SUBCOOLING (F)

--- STEAM
--- WATER
--- EXTRACTION STEAM
--- TWO PHASE FLOW
--- MAIN PATH

SHEET NO	THROTTLE FLOW LBS/HR	THROTTLE PRESSURE PSIA	BACK PRESSURE IN. HG ABS	CYCLE LOSSES LBS/HR	BLOW DOWN LBS/HR
22.	10819703.	851	2.00	18859.	15000.
23.	10819700.	851	2.20	18859.	15000.
24.	10819697.	851	2.40	18859.	15000.
25.	10819695.	851	2.60	18859.	15000.
26.	10819695.	851	2.80	18859.	15000.
27.	10819692.	851	3.00	18859.	15000.
28.	10819688.	851	3.20	18859.	15000.
29.	10819685.	851	3.40	18859.	15000.

THIS DOCUMENT IS THE PROPERTY OF EBASCO SERVICES INCORPORATED. ITS USE IS EXPRESSLY RESTRICTED BY THE TERMS OF THE CONTRACT, DATED AS OF AUGUST 10, 1986 BETWEEN EBASCO SERVICES INCORPORATED AND FLORIDA POWER & LIGHT COMPANY.

FLORIDA POWER & LIGHT COMPANY
ST. LUCIE PLANT
1976 - 890,000 KW INSTALLATION UNIT NO.1
HEAT BALANCE
2710 MWT VARIABLE BACK PRESSURE
2.60 INCHES HG ABSOLUTE

EBASCO SERVICES INCORPORATED NEW YORK.

SCALE-NONE APPROVED DATE 9-8-82

DIV. APPROVED 8770-C-057

CH. APPROVED SH 25

DRAWING ORIGINALLY APPROVED
AS BCS-125-81.302 SH 4 OF 8
NO. DATE REVISION BY CH. APPROVED