



PERFORMANCE

GROSS GENERATION
KW

869378.

TURBINE HEAT-RATE
BTU/KW-HR

10326.9

LEGEND

Q---FLOW-LBS/HR
F---TEMPERATURE- F
P---PRESSURE-LBS/SQ. IN. ABS.
H---ENTHALPY OF STEAM-BTU/LB
FTD---TERMINAL DIFFERENCE (F)
ELEV-EXPANSION LINE END POINT
UEEP-USED ENERGY END POINT
D.C.-DRAIN COOLER APPROACH (F)
S.C.-SUBCOOLING (F)

--- STEAM
--- WATER
--- EXTRACTION STEAM
--- TWO PHASE FLOW
--- MAIN PATH

SHEET NO	THROTTLE FLOW LBS/HR	THROTTLE PRESSURE PSIA	BACK PRESSURE IN. HG. ABS	CYCLE LOSSES LBS/HR	BLOW DOWN LBS/HR
14.	10722336.	652	2.00	18697.	15000.
15.	10722333.	652	2.20	18697.	15000.
16.	10722331.	652	2.40	18697.	15000.
17.	10722328.	652	2.60	18697.	15000.
18.	10722326.	652	2.80	18697.	15000.
19.	10722323.	652	3.00	18697.	15000.
20.	10722321.	652	3.20	18697.	15000.
21.	10722319.	652	3.40	18697.	15000.

THIS DOCUMENT IS THE PROPERTY OF EBASCO SERVICES INCORPORATED. ITS USE IS EXPRESSLY RESTRICTED BY THE TERMS OF THE CONTRACT, DATED AS OF AUGUST 10, 1968 BETWEEN EBASCO SERVICES INCORPORATED AND FLORIDA POWER & LIGHT COMPANY.

FLORIDA POWER & LIGHT COMPANY
ST. LUCIE PLANT
1976 - 880,000 KW INSTALLATION UNIT NO. 1
HEAT BALANCE
2590 MWT VARIABLE BACK PRESSURE
3.20 INCHES HG ABSOLUTE

EBASCO SERVICES INCORPORATED NEW YORK

SCALE-NONE	APPROVED	DATE 9-6-82
DIV. _____	_____ N. P. ...	8770-C-057
DR. _____	_____ H. ...	SH 20
CH. _____	_____ H. ...	

NO.	DATE	REVISION	BY	CH.	APPROVED
1					

DRAWING ORIGINALLY APPROVED
AS BCS-125-61.303 SH 7 OF 8