

RESPONSE TO NOVEMBER 18, 1977, LETTER
FROM EDSON G. CASE TO GODWIN WILLIAMS, JR.
"ELECTRICAL CONNECTOR ASSEMBLIES"

This response provides the environmental qualification information for the electrical connectors used in the Browns Ferry Nuclear Plant, as requested by the November 18, 1977, letter from Edson G. Case to Godwin Williams, Jr., which references IE Bulletins 77-05 and 77-05A, dated November 8 and November 15, 1977, respectively. Also, this response includes TVA's justification for continued operation of the facilities without creating undue risk to the health and safety of the public. This response is divided into the following:

- Part I - Identification of Systems, Components, and Associated Electrical Connectors Required to Function to Mitigate Design Basis Events.
- Part II - Environmental Qualification of Electrical Connectors
- Part III - Justification for Continued Operation

Part I

Identification of Systems, Components, and Associated Electrical Connectors Required to Function to Mitigate Design Basis Events.

Table 1 lists the safety systems and components required to function to mitigate a postulated design basis event or accident outside containment. Those systems containing electrical connectors are so designated in this table. These systems or portions of systems and components have been categorized as being either inside primary containment or outside primary containment. Table 2 lists those electrical connectors for each Browns Ferry unit that are inside the primary containment and are a part of a safety system as listed in Table 1. Table 2 identifies the electrical penetration through the primary containment that each electrical connector is located on, the type of connector, the number of wires to the connector, the system whose circuits pass through the connector, the system component associated with the circuits, and the function of the circuits. Table 3 lists those electrical connectors for all three Browns Ferry units that are outside the primary containment and are a part of a safety system circuit. Only those safety systems which are required to function to mitigate a postulated design basis event or accident outside containment where the event itself could adversely affect the ability of the system to perform its safety function have been considered and listed in Tables 2 and 3.

For units 1 and 2, only one type of connector is used inside the primary containment in the identified safety circuits. This connector was supplied by Physical Sciences Corporation and is an integral part of the penetration. It has 48 pins, has gold-plated surfaces on both the pins and the female receptacles, utilizes a Neoprene 'O' ring as a sealing surface where the plug shell and receptacle shell interface, and has the insulated conductors potted in the shell. Both the plug shell and the receptacle shell are metallic.



For unit 3, two types of connectors are used inside the primary containment in identified safety circuits. These were supplied by Bendix and are similar to each other in design:

Part No. 10-214636-78S or P, 14 contacts (2Nos.16, 12Nos.8);

and Part No. 10-214628-51S or P, 12 contacts (Nos.12).

The types of connectors used outside of the primary containment in identified safety circuits are of various types as shown in Table 3.

TABLE 1

SYSTEMS AND COMPONENTS REQUIRED TO FUNCTION TO
MITIGATE DESIGN BASIS EVENTS

I. INSIDE PRIMARY CONTAINMENT (* Denotes Systems with Connectors)

- *Inboard Main Steam Isolation Valve Circuits
- *Automatic Depressurization Relief Valve Circuits
- *Inboard Containment Isolation Valve Circuits (See note 1)
- *Oxygen and Hydrogen Monitoring Systems
- *Suppression Pool to Drywell Vacuum Breakers
- *Recirculation System Suction and Discharge Valves (See Note 1)
- *Residual Heat Removal System Head Spray Flow Control Valves (See Note 1)
- *High Pressure Coolant Injection System Steam Supply Valve (See Note 1)
- *Reactor Core Isolation Cooling System Steam Supply Valve (See Note 1)

II. OUTSIDE PRIMARY CONTAINMENT

A. Inside Secondary Containment (* Denotes Systems with Connectors)

- *Main Steam Isolation Valve Circuits (See Note 2)
- *Automatic Depressurization Relief Valve Circuits (See Note 2)
- *Containment Isolation Valve Circuits (See Note 2)
- *Oxygen and Hydrogen Monitoring Systems (See Note 2)
- 4 KV and 480 V Boards (See Note 3)
- Diesel Generators and Process Auxiliaries (See Note 3)
- 4 KV and 480 V System Circuits
- 250 VDC System Circuits
- Control Bay Ventilation System Circuits (See Note 4)
- Corner Room (Elev 519) Level Switch Circuits (See Note 5)
- *Radiation Monitoring Systems
- *- Main Steam Vault
- *- RHR SW Effluent
- *- RBCCW
- *- RSW Effluent

10 2 01

TABLE 1 (CONT.)

Diesel-Generator Shutdown Board Room Ventilation System Circuits
(See Note 4)

*RCIC Circuits (See Note 6)

Circuits for Other Essential Systems (See Note 7)

*- Automatic Depressurization System

*- Primary Containment Isolation

- Containment Inerting

- Reactor Building Isolation

- Reactor Building Vacuum Relief

- Standby Gas Treatment

- RHR

- RHRSW

- RHR Room Coolers

- EECW

- CS

- CS Room Coolers

- HPCI

- Reactor Protection System (Excluding Neutron Monitoring System, Control Rod Drive and Position Indicating Systems)

- Reactor Building Closed Cooling Water

- Fuel Pool Cooling

*- Reactor Water Cleanup (Isolation Function Only)

- Torus Water Level and Temperature

B. Control Bay

The control bay environment is controlled by the control bay ventilation system. The environment for equipment within the control bay is no more severe during design basis events than that to which it is exposed during normal unit operations.

C. Unit 1, 2, and 3 Diesel-Generator Shutdown Board Rooms

The diesel-generator shutdown board room environments are controlled by the board room ventilation systems. The environment for equipment within these board rooms is no more severe during design basis events than that to which they are exposed during normal unit operation.

TABLE 1 (CONT.)

Notes:

1. Connections at motor operated valves were excluded since these connections were qualified in conjunction with qualification of the valves and associated motor operators.
2. Circuits for any safety-related components outside containment were investigated. In addition, circuits outside containment serving safety-related components which are located inside containment were investigated.
3. Failure of these components that are required for onsite power distribution was analyzed previously. See "Concluding Report on the Effects of Postulated Pipe Failure Outside of Containment for Unit 1 of the Browns Ferry Nuclear Plant" DED-TM-PF1 (October 15, 1973) and "Concluding Report on the Effects of Postulated Pipe Failure Outside of Containment for the Browns Ferry Nuclear Plant Units 2 and 3" DED-TM-PF2 (March 1, 1974).
4. These circuits were investigated for any extensions outside of the control bay or shutdown board rooms into the boundaries of secondary containment.
5. These rooms contain vital HPCI, RCIC, CS, and RHR equipment. The level switch circuits investigated are those which warn of flooding internal to these rooms.
6. In terms of function and objective, the RCIC system is not actually a safety system. However, with regard to engineering analyses, fabrication, and erection processes, and quality assurance control and documentation, this system received the same attention as the safety-related systems. For this reason, RCIC was evaluated using the same criteria as for the safety-related systems.
7. The investigation includes any wall sockets or wall power outlets associated with these circuits.

TABLE 2

UNIT 1 - PENETRATION CONNECTORS INSIDE PRIMARY CONTAINMENT
 MANUFACTURER - PHYSICAL SCIENCES, 48 PIN, NO. 12
 PLUG NO. 6448-2
 RECEPTACLE NO. 6445-2

Penetration No.	Connector No.*	System	Component	Function	No. of Wires
EB	G2-2G	Recirculation Discharge	FCV-68-79	Logic	7
		Recirculation Suction	FCV-68-77	Logic	7
		Recirculation Discharge	FCV-68-79	Logic	2
	G3-3G	Relief Valve	PSV-1-30	Power	2
		Recirculation Discharge	FCV-68-79	Logic	2
		HPCI Steam Supply	FCV-73-2	Logic	7
	G4-4G	RHR Head Spray	FCV-74-78	Logic	7
		Recirculation Sampling	FCV-43-13	Power & Logic	5
		MS Drain	FCV-1-55	Logic	7
		RWCU Letdown	FCV-69-1	Logic	7
	G5-5G	Relief Valve	PSV-1-5	Sol Valve Power	2
	G7-7G	Main Steam Isolation	FCV-1-14	Logic	2
		Main Steam Isolation	FCV-1-37	Logic	2
	G8-8G	Main Steam Isolation	FCV-1-14	Power & Logic	9
		Main Steam Isolation	FCV-1-26	Power & Logic	9
		Main Steam Isolation	FCV-1-37	Power & Logic	9
		Main Steam Isolation	FCV-1-51	Power & Logic	9
		RHR Letdown Supply	FCV-74-48	Power & Logic	11
	G9-9G	RWCU Letdown	ZS-69-1	Logic	4
EC	G4-4G	Relief Valve	PSV-1-19	Power	2
		Relief Valve	PSV-1-31	Power	2
	G9-9G	Main Steam Isolation	FCV-1-14	Logic	2
		Main Steam Isolation	FCV-1-26	Logic	2
		Relief Valve	PSV-1-22	Power	2
		Relief Valve	PSV-1-34	Power	2
ED	J3-3J	H ₂ E	HE 76-39	Instrumentation	4
		O ₂ E	OE 76-43	Instrumentation	4
EE	G4-4G	RHR Letdown Supply	FCV-74-48	Logic	4
		RCIC Steam Supply	FCV-71-2	Logic	7
	G6-6G	Drywell Equipment Sump	FCV-77-14B	Power & Logic	9
	G7-7G	Main Steam Isolation	FCV-1-26	Logic	2
		Main Steam Isolation	FCV-1-51	Logic	2

TABLE 2 (CONT.)

UNIT 1 - CONNECTORS INSIDE CONTAINMENT

<u>Penetration No.</u>	<u>Connector No.*</u>	<u>System</u>	<u>Component</u>	<u>Function</u>	<u>No. of Wires</u>
	G8-8G	Main Steam Isolation	FCV-1-37	Logic	2
		Main Steam Isolation	FCV-1-51	Logic	2
	G9-9G	Recirculation Suction	FCV-68-1	Logic	7
		Recirculation Discharge	FCV-68-3	Logic	11

*The penetrations have connectors on both ends, only the inboard connectors are listed since they experience the worst environment.

TABLE 2 (CONT.)

UNIT 2 - PENETRATION CONNECTORS INSIDE PRIMARY CONTAINMENT
 MANUFACTURER - PHYSICAL SCIENCES, 48 PIN, NO. 12
 PLUG NO. 6448-2
 RECEPTACLE NO. 6445-2

<u>Penetration No.</u>	<u>Connector No.*</u>	<u>System</u>	<u>Component</u>	<u>Function</u>	<u>No. of Wires</u>
EB	G2-2G	Recirculation Discharge	FCV-68-79	Logic	7
		Recirculation Suction	FCV-68-77	Logic	7
		Recirculation Discharge	FCV-68-79	Logic	2
	G3-3G	Relief Valve	PSV-1-30	Power	2
		HPCI Steam Supply	FCV-73-2	Logic	7
	G4-4G	RHR Head Spray	FCV-74-78	Logic	7
		Recirculation Sampling	FCV-43-13	Power & Logic	5
		Main Steam Drain	FCV-1-55	Logic	7
		RWCU Letdown	FCV-69-1	Logic	7
	G6-6G	Relief Valve	PSV-1-5	Power	2
	G7-7G	Main Steam Isolation	FCV-1-14	Logic	2
		Main Steam Isolation	FCV-1-37	Logic	2
	G8-8G	Main Steam Isolation	FCV-1-14	Logic	9
		Main Steam Isolation	FCV-1-26	Logic	9
		Main Steam Isolation	FCV-1-37	Logic	9
		Main Steam Isolation	FCV-1-51	Logic	9
		RHR Letdown Supply	FCV-74-48	Logic	11
	G9-9G	RWCU Letdown	ZS-69-1	Logic	4
EC	G4-4G	Relief Valve	PSV-1-19	Power	2
		Relief Valve	PSV-1-31	Power	2
	G9-9G	Main Steam Isolation	FCV-1-14	Logic	2
		Main Steam Isolation	FCV-1-26	Logic	2
		Relief Valve	PSV-1-22	Power	2
ED	J3-3J	H ₂ E	H ₂ E-76-39	Instrumentation	4
		O ₂ E	O ₂ E-76-43	Instrumentation	4
EE	G4-4G	RHR Letdown Supply	FCV-74-48	Logic	4
		RCIC Steam Supply	FCV-71-2	Logic	7
	G5-5G	Recirculation Discharge	FCV-68-3	Logic	2
	G6-6G	Drywell Equipment Sump	FCV-77-14B	Power & Logic	9

TABLE 2 (CONT.)

UNIT 2 - PENETRATION CONNECTORS INSIDE PRIMARY CONTAINMENT

<u>Penetration No.</u>	<u>Connector No.*</u>	<u>System</u>	<u>Component</u>	<u>Function</u>	<u>No. of Wires</u>
	G7-7G	Main Steam Isolation	FCV-1-26	Logic	2
		Main Steam Isolation	FCV-1-51	Logic	2
	G8-8G	Main Steam Isolation	FCV-1-37	Logic	2
		Main Steam Isolation	FCV-1-51	Logic	2
	G9-9G	Recirculation Suction	FCV-68-1	Logic	7
		Recirculation Discharge	FCV-68-3	Logic	9

*The penetrations have connectors on both ends, only the inboard connectors are listed since they experience the worst environment.

TABLE 2 (CONT.)

UNIT 3 - CONNECTORS INSIDE PRIMARY CONTAINMENT
MANUFACTURER - BENDIX

Penetration No.	Connector ^{1,2}		System	Component	Function	No. of Wires
	No.	Type				
EA	J1	1	HPCI Steam Supply	FCV-73-2	Power	3
	J6	1	Recirculation Discharge	FCV-68-79	Logic	5
	J7	1	Recirculation Discharge	FCV-68-79	Power	3
			Recirculation Suction	FCV-68-77	Power	3
			Main Steam Drain	FCV-1-55	Power	3
	J8	1	RWCU Letdown	FCV-69-1	Power	3
	J9	1	RHR Head Spray	FCV-74-78	Power	3
			RHR Letdown Supply	FCV-74-48	Power	3
EB	J1	2	Relief Valve	PSV-1-18	Power	2
	J2	2	Relief Valve	PSV-1-41	Power	2
	J3	2	Relief Valve	PSV-1-5	Power	2
	J7	2	Recirculation Discharge	FCV-68-79	Logic	7
	J8	2	Recirculation Discharge	FCV-68-79	Logic	2
			Suction	FCV-68-77		7
	J11	2	RWCU Letdown	FCV-69-1	Logic	7
			RWCU Letdown	ZS-69-1	Logic	4
	J12	2	HPCI Steam Supply	FCV-73-2	Logic	7
	J17	2	RHR Head Spray	FCV-74-78	Logic	7
			Recirculation Sampling	FCV-43-13	Power & Logic	5
	J19	2	RHR Letdown Supply	FCV-74-48	Logic	11
	J20	2	Main Steam Isolation	FCV-1-14	Power & Logic	9
	J21	2	Main Steam Isolation	FCV-1-26	Power & Logic	9
	J22	2	Main Steam Isolation	FCV-1-37	Power & Logic	9
	J23	2	Main Steam Isolation	FCV-1-51	Power & Logic	9
	J29	2	Main Steam Drain	FCV-1-55	Logic	7
	25	2	Main Steam Isolation	FCV-1-14	Logic	2
			Main Steam Isolation	FCV-1-37	Logic	2

UNIT 3 - CONNECTORS INSIDE PRIMARY CONTAINMENT

<u>Penetration No.</u>	<u>Connector No.</u>	<u>Type</u>	<u>System</u>	<u>Component</u>	<u>Function</u>	<u>No. of Wires</u>
EC	J16	2	Relief Valve	PSV-1-19	Power	2
	J18	2	Relief Valve	PSV-1-22	Power	2
			Relief Valve	PSV-1-34	Power	2
	25	2	Main Steam Isolation	FCV-1-14	Logic	2
			Main Steam Isolation	FCV-1-26	Logic	2
ED	J13	2	H ₂ E	H ₂ E-76-39	Instrumentation	4
			O ₂ E	O ₂ E-76-43	Instrumentation	3
	16	2	Main Steam Isolation	FCV-1-26	Logic	2
			Main Steam Isolation	FCV-1-51	Logic	2
EE	J1	2	Recirculation Discharge	FCV-68-1	Logic	7
	J2	2	Recirculation Discharge	FCV-68-3	Logic	9
	J9	2	RHR Letdown Supply	FCV-74-48	Logic	4
	J10	2	RCIC Steam Supply	FCV-71-2	Logic	7
	J11	2	Recirculation Discharge	FCV-68-3	Power & Logic	2
	J12	2	Drywell Equipment Sump	FCV-77-14B	Power & Logic	9
	25	2	Main Steam Isolation	FCV-1-37	Logic	2
			Main Steam Isolation	FCV-1-51	Logic	2
EF	J4	1	Recirculation Discharge	FCV-68-1	Power	3
			Recirculation Discharge	FCV-68-3	Power	3
	J6	1	RCIC Steam Supply	FCV-71-2	Power	3
	J7	1	Recirculation Discharge	FCV-68-3	Logic	5

1. NOTE: Type 1 - Bendix Part No. 10-214636-78S or P, 14 Contacts (2Nos.16, 12Nos.8)
 Type 2 - Bendix Part No. 10-214628-51S or P, 12 Contacts (Nos.12)

2. NOTE: The penetrations have connectors on both ends that are not part of the pressure boundary, only the inboard connectors are listed since they experience the worst environment.

TABLE 3

CONNECTORS OUTSIDE OF CONTAINMENT

System	Function	Unit	No. of Devices/ Unit	Manufacturer	Type	Temperature °F	
						Design	Environment
Main Steam Line Rad Mon	Instrumentation	1,2,3	4	Amphenol	B2-816	350	300
Reactor Water Cleanup and Primary Containment	Isolation	1,2,3	2	Amphenol	MS3106-A-20-4P MS3102-A-20-4S	257	170
Main Steam Line Leak Detectors & Pri Containment	Isolation	1,2,3	16 16	Amphenol Amphenol	MS3102-A-20-4F MS3102-A-20-4S	257*	550
RHR Heat Exch Disch Rad Mon	Instrumentation	1,2,3	6 2 2	Amphenol Amphenol Amphenol	UG1213/U UG932/U UG260/U	185 350 185	150 150 150
Raw Water Effluent Rad Mon	Instrumentation	1,2,3	3 1 1	Amphenol Amphenol Amphenol	UG1213/U UG260/U UG932/U	185 185 350	150 150 150
Reac Bldg Closed Cool Water Effluent	Instrumentation	1,2,3	3 1 1	Amphenol Amphenol Amphenol	UG1213/U UG932/U UG260/U	185 350 185	115 115 115
HPCI Steam Leak Detectors	Instrumentation	1,2,3	16 16	Amphenol Amphenol	3106A-20-4P 3102A-20-4S	257	550
RCIC Leak Detectors	Instrumentation	1,2,3	16 16	Amphenol Amphenol	3106A-20-4P 3102A-20-4S	257*	550
RCIC Backup Control Center	Test	1,2,3	1	Amphenol	69-OB-18-15	257*	115
Fuel Pool Cooling	Instrumentation	1,2,3	1	Amphenol	Rept 69-OR16-105-C100 Plug 69-6R-16-10P	257	115

*See Part II, Section C

Part II

Environmental Qualification of Electrical Connectors

A. Original Testing

The original qualification tests (i.e., pressure, temperature) conducted on the Browns Ferry penetrations and associated connectors were described during a meeting with NRC representatives on November 16, 1977. These tests did not include qualification for the electrical connectors for the environment resulting from a postulated design basis event or accident outside containment.

B. Steam Environment Test

Based on the discussions held during the November 16, 1977, meeting and on the November 18, 1977, letter, TVA decided to conduct a preliminary environmental test on selected samples of the electrical connector types used in containment in identified safety systems to determine if they could continue to function in a steam environment of a design basis event. These samples were taken from the plant stock of spares and were not thermally or radiation preaged. Attachment 1 describes the test procedures used, the connector samples tested, the test facility, the environmental conditions used in the test, the electrical loadings used, and the test results. The actual test conditions exceeded those that would be expected in the case of an actual design basis event for Browns Ferry Nuclear Plant. The electrical connectors satisfactorily passed the steam environment test.

The purpose of this test was to provide a rapid assessment of the performance in a steam environment of the electrical connectors within primary containment.

1950

1951

1952

1953

1954

1955

1956

1957

1958

C. Evaluation of Connectors Outside Primary Containment

The critical electrical connectors outside containment are those that are associated with the main steam, HPCI, and RCIC leak detectors. The postulated accident environment temperature can exceed the design temperature of these connectors. These are identified in Table 3 with an asterisk (*). These circuits are provided to detect and initiate isolation signals in the event of a pipe break. Since the signal to initiate isolation is set at 200° F and is well below the design temperature of 257° F for the electrical connectors, these connectors will have performed their safety function before any potential environmental degradation. These sensors and associated electrical connectors are not required to function following the initiation of the isolation signal.

D. Evaluation of Radiation Effects

The Physical Science and Bendix connectors were specified to withstand a nuclear radiation of 10^8 R. In actuality, the threshold for damage of organic materials generally is greater than 10^8 R, with embrittlement beginning above approximately five times this value. The integrated dose to affected connectors would not be expected to exceed 10^8 R during the time interval in which they are needed following an LOCA, and the exposure from operation to the present time is extremely small by comparison. Therefore, radiation damage to these connectors is not a concern related to operation during the next few months. (See Item E).

E. Tests to Determine Qualified Life (Future Additional Tests)

TVA intends to establish the qualified life of all electrical connectors both inside and outside primary containment used in safety-related

circuits at Browns Ferry using the requirements of IEEE Standard 323-1974, "IEEE Standard for Qualifying Class 1E Equipment for Nuclear Power Generating Stations." Type testing will be used to establish qualified life with the effects of thermal and radiation aging included. It is anticipated that this portion of the program will be completed within 90 days.

Attachment 1

Date November 22, 1977 Unit 0 BFSTER No. 22

System N/A Originator J. E. Gibbs

Title: TEST PROCEDURE FOR BROWNS FERRY CONNECTORS Cognizant Section Outage

Reason for Test or Experiment:

To test Bendix Corporation type and Physical Science type connectors used in electrical penetrations at Browns Ferry Nuclear Plant.

Safety Related <input type="checkbox"/>	Non-Safety-Related <input checked="" type="checkbox"/>
<ul style="list-style-type: none">Transmitted to NGB: Date _____Required safety review and safety analyses (10 CFR 50.59) have been completed for<ul style="list-style-type: none">A. Unreviewed safety questionB. Technical specification limits<ul style="list-style-type: none">DED signoff _____ Date _____OPP signoff _____ Date _____PORC Review: _____ Approved: _____ Date _____ Plant Superintendent _____Authorization to Perform: _____ Plant Superintendent _____ Date _____	<ul style="list-style-type: none">PORC Review: _____ November 22, 1977 Date _____Approved: <u>J. S. Demaree</u> Plant SuperintendentAuthorization to Perform: <u>J. S. Demaree</u> Plant Superintendent November 22, 1977 Date _____Plant Superintendent <u>J. S. Demaree</u> General Revision Date <u>11/25/77</u>

BFSTER Complete J. S. Demaree
Plant Superintendent

Date 11/27/77
Date

OFFICIAL COPY

1

2

3

4

Attachment 2
(Sheet 1 of 2)

Unreviewed Safety Question Determination

Originator J. E. GibbsSTER No. 22References: NONE*Test or Experiment Summary

To test electrical connectors to verify response to LOCA conditions
and main steam line break.

Unreviewed Safety Question

Is the probability of occurrence or the consequences of an accident or
malfunction of equipment important to safety previously evaluated in the
Final Safety Analysis Report increased?

Yes ☐No ☒Justification

This is a test that is performed in a test laboratory.

OFFICIAL COPY

*Revision APV

Attachment 2
(Sheet 2 of 2)

Unreviewed Safety Question Determination

Unreviewed safety question (Continued)

Is the possibility for an accident or malfunction of a different type than any evaluated previously in the Final Safety Analysis Report created?

Yes

☐

No

☒Justification

This is a test conducted at a laboratory for purposes of collecting data.

Is the margin of safety as defined in the basis for any technical specification reduced?

Yes

☐

No

☒Justification

This test is not performed at Browns Ferry Nuclear Plant.

OFFICIAL COPY

*Unreviewed safety question involved (PORC).

Yes

☐

No

☒

TEST PROCEDURE FOR BROWNS FERRY CONNECTORS

1. Scope

To test connectors used in electrical penetrations for units 1 and 2 at Browns Ferry and to test typical connectors used for unit 3 at Browns Ferry for ability to withstand the steam temperature pressure profile resulting from a LOCA or a pipe break.

2. Material to be tested shall be:

- 1 - 48-pin connector Physical Science type contained in electrical penetration type used for Browns Ferry units 1 and 2
- 1 - 12-pin connector Bendix Corporation type 10-214-628-515 used on pigtails out of Browns Ferry unit 3 penetration

3. Test Setup

Provide an environmental test chamber with dimensions capable of containing the test specimens (see figure 1). The chamber shall be provided with a pressure gauge and temperature sensors for measuring the temperature inside the test chamber.

- 3.1 Connect the pins of the connectors with wires so as to form a series parallel circuit which will give a voltage gradient within the connector as well as simulate a load (see figure 2)

The circuit shall be loaded to approximately 5 amperes and a voltmeter and ammeter shall be connected to the load.

4. Test Procedure

- 4.1 Verify the initial status of the penetration connector and the separate connector for voltage integrity. Megger pin to all other pins and shell combined. Check for current continuity through the connector.
- 4.2 Energize the connectors from a 250 V dc source. Bring the environmental chamber to the initial condition of 150 F.
- 4.3 Admit steam into the environmental chamber at flow condition so as to achieve a stabilized temperature of 322°F. Hold this condition for 5 minutes. Record all voltmeter, ammeter, pressure and temperature readings at each major change in profile and each hour.

OFFICIAL COPY


TEST PROCEDURE FOR BROWNS FERRY CONNECTORS

- 4.4 Reduce pressure at 0.7 lb/minute to reach 36 psig and 282F in 60 minutes. Then drop the pressure immediately to 15 psig (approximately 250F). Thereafter reduce the pressure at 1.0 lb/hour until atmospheric pressure is reached at 16 hours into the test (212F).
- 4.5 Thereafter drop the temperature at $7\frac{1}{2}^{\circ}\text{F/hr}$ at atmospheric pressure until 150°F is reached after 24 hours into the test. The profile curve is figure 3.

5. Criteria

- 5.1 The connector shall carry the required load at not more than 10% reduction in voltage after the full duration of the test.

OFFICIAL COPY



Page 3
BF STER 22
11/25/77


Test item #2 { Physical Science 6445-1 Receptacle
Physical Science 644B-1 Plug

Test item #1 { Bendix 10-21402B-51 Receptacle
Bendix 10-21462B-51 Plug


FIGURE 1
ENVIRONMENTAL
TEST CHAMBER

OFFICIAL COPY

BROWNS FERRY NUCLEAR NA
CONNECTOR TEST



TEST ITEM # 2




TEST ITEM # 1

FIGURE 2

OFFICIAL COPY

2AM15

BROWN'S FERRY NUCLEAR P
CONNECTOR TEST



OFFICIAL COPY

Fig No 3

THIS PAGE DELETED

OFFICIAL COPY

DATA COVER SHEET

1 BENDIX

This data package includes test data sheets.

Instrument Calibrated

Verified By

Date

Acceptance Criteria Met

Yes

Yes

No

Data Takers/Organization

J. Edward Gibbs DPP (Outage)

David Dugton, DED

Dennis McCloud, DPRP

Mike Montsinger, DPP (QA)

Tom Kulaga, DPP (Outage)

Mike McInerney, DPP (QA?)

Joe Bradley, DED

Dates Test Performed

11/26/77 - 11/27/77

Reviewed by Cognizant Engineer

Reviewed by Results Section Supervisor

Reviewed by Quality Assurance Supervisor

J. Edward Gibbs

Wm C. Thompson 11/27/77

John T. Harman 11/27/77

OFFICIAL COPY

STER 22

TEST DATA/BROWNS FERRY CONNECTORS

#1 Pin Connector

BENDIX Model Number

STEP	ITEM	RESULTS	BY/DATE
4.1.a	Verify proper hook up for connector (test item #2, figure 2, for 48-pin connector; test item #1, figure 2, for 12-pin connector)	✓ OK	QDD 11/24/77 Verified
4.1.b	Megger: pin to all pins and shell combined	7 45 X 10 ⁹ Ohms	
	pin to shell	14 X 10 ⁹ Ohms	
4.1.c	Verify current continuity	✓ OK	
4.2.a	Energize connector from nominal 250 VDC source (verify)	✓ OK	J52 11/24/77 Verified
4.2.b	Load voltage	247.0 Volts	J52 11/26/77
4.2.c	Set load for connector so as to give load current of 5.0 ± 0.5 amps (initial values)	4.95 Amps	NI 7/29/77 11/26/77 QC
4.2.d	Initial test chamber pressure and temperature	0 psig 150 °F.	J52 11/26/77 Verified
4.3.a	Admit steam, bringing temperature to 322 ± 5° F. Also note start time of the test (t ₀).	78 psig 322 °F. 10:45:14 Start time	7/29/77 11/26/77 Verified
4.3.b	Stabilize temperature and pressure at 322 ± 5° F.	10:50:09 time	7/29/77 11/26/77 Verified
4.3.c	When stabilized, record load current and voltage.	4.96 amps Load: 248 volts Input: 251 volts	7/29/77 11/26/77 QC

OFFICIAL COPY

Connector #1, Bendix

STEP	ITEM	RESULTS	BY/DATE
4.3	(Continued)		
4.3.d	Maintain in stabilized condition for 5 minutes; record load current and voltage at end.	<div>Load <u>4.97</u> Amps</div> <div>Input <u>24.7</u> Volts</div> <div>Input <u>250</u> Volts</div>	<div>92</div> <div><u>MGM 11/26/77</u></div> <div>QC</div>

OFFICIAL COPY

Connector #1, Bendix

STEP	ITEM	RESULTS	BY/DATE
4.4			
4.4.a	Reduce pressure at 0.7 psig/ minute to 282°F at 36 psig in one hour; record initial load current and voltage.	10:55:04 time 4.98 amps load 247.2 volts input 250 volts	MGM 11/24/77 verified
	Repeat at three 5 minute intervals	11:02:35 time 4.91 amps load 248.8 volts input 251 volts	MGM 11/24/77 verified
		11:07:35 time 4.94 amps load 248.7 volts input 250 volts	MGM 11/24/77 verified
		11:12:35 time 4.93 amps load 248.3 volts input 250 volts	MGM 11/24/77 verified
4.4.b	Drop pressure immediately to 150 psig. Record load current and voltage. should be 250°F, 15 psig 952 11/27/77	12:01 time 4.98 amps load 248.5 volts input 251 volts	MGM 11/24/77 verified
4.4.c	At hourly intervals; reduce the pressure by 1.0 ± 0.5 psig Record time of pressure reduction, new pressure (psig), load current and voltage. Repeat for 15 hours until 212°F at atmospheric pressure is obtained.		

OFFICIAL COPY

Connector #1, Bendix11/25/77
BF STER 22
11/25/77

STEP	ITEM	RESULTS	BY/DATE
4.4.c	(Continued)	26:13:01:13 T	JSS 11/28
		14 P	
		4.88 A	
	Load	248.56 V	
	Input	250 V	
		14:02:19 T	JSS 11/26
		13 P	
		4.89 A	
	Load	249.57 V	
	Input	250 V	
		15:03:19 T	JSS 11/26
		12 P	
		9.86 A	
	Load	248.23 V	
	Input	250 V	
		16:05:24 T	JSS 11/26
		10.8 P	
		4.86 A	
	Load	248.14 V	
	Input	250 V	
		17:05:24 T	dem 11/26
		10.0 P	
		4.85 A	
	Load	247.8 V	
	Input	249 V	
		18:05:24 T	dem 11/26
		9 P	
		4.87 A	
	Load	248.66 V	
	Input	250 V	

OFFICIAL COPY

Connector

#1, Bendix

BF STER 22
11/25/77

STEP	ITEM	RESULTS
4.4.c (Continued)		19:05:24 T
		8 P
		4.85 A
	Load	247.8 V
	Input	248 V
		20:05:24 T
		7 P
		4.84 A
	Load	246.8 V
	Input	249 V
		21:05:24 T
		TAK 11/26/77 6 4.73 P
		4.93 A
	Load	248.4 V
	Input	250 V
		22:05:24 T
		5 P
		4.87 A
	Load	248.5 V
	Input	250 V
		23:05:24 T
		4 P
		4.86 A
	Load	248.4 V
	Input	250 V
		00:05:24 T
		3 P
		4.86 A
	Load	248.0 V
	Input	250 V

B. DATE

dem 1

11/26

TAK 11/26

TAK 11/26

TAK 11/26

TAK 11/26

TAK 11/26

OFFICIAL COPY

Connector #1, Bendix

STEP	ITEM	RESULTS	BY/DATE
4.4.c	(Continued)	01:05:24 T	TAK 11/27
		2 P	
		4.87 A	
	Load	248.8 V	
	Input	250 V	
		2:05:24 T	TAK 11/2
		1 P	
		4.86 A	
	Load	248.0 V	
	Input	250 V	
		3:05:24 T	TAK 11/2
		0 P	
		4.87 A	
	Load	248.7 V	
	Input	250 V	
		_____ T	
		_____ P	
		_____ A	
	Load	_____ V	
	Input	_____ V	

Not Required
JSS 11/24/77

4.5 At hourly intervals, reduce temperature by $7\frac{1}{2}^{\circ}\text{F/hr}$. Record time of temperature reduction, new temperature, load current and voltage. Repeat until 150°F is reached after 24 hours into the test.

OFFICIAL COPY

Connector

#1, Bendix

DE SIER 22
11/25/77

STEP

ITEM

RESULTS

BY/DATE

4.5 (Continued)

4:05:24 T

TAK 11/2

209°F temp

4.87 A

Load 248.6 V

Input 250 V

5:05:24 T

TAK 11/2

196°F temp

4.86 A

Load 248.0 V

Input 250 V

06:05:24 T

J.S. 11/2

188°F temp

4.865 A

Load 248.4 V

Input 249.0 V

07:05:24 T

J.S. 11/2

182°F temp

4.87 A

Load 248.9 V

Input 250.0 V

08:05:24 T

J.S. 11/2

174°F temp

4.85 A

Load 247.8 V

Input 250.0 V

09:05:24 T

J.S. 11/2

166.5°F temp

4.85 A

Load 247.5 V

Input 244.0 V

OFFICIAL COPY

Connector #1, Bendix

STEP	ITEM	RESULTS	BY/DATE
4.5	(Continued)	27:10:05:24 T	<u>MGM 11/27/77</u>
		<u>16.0</u> temp	
		<u>4.86</u> A	
	Load	<u>248.47</u> V	
	Input	<u>250.0</u> V	
		37:11:04:57 T	<u>down 1</u> <u>11/27/77</u>
		<u>159</u> temp	
		<u>4.85</u> A	
	Load	<u>247.8</u> V	
	Input	<u>249</u> V	

Test Data Verification:

M.J. McLaughlin 11/27/77 J. Edward Doherty 11/27/77
QC Inspector/Date Test Engineer/Date

OFFICIAL COPY

DATA COVER SHEET

#2 GULTON

This data package includes test data sheets.

Instrument Calibrated

J. Edward Gibbs 11/25/77
Verified By Date

Acceptance Criteria Met

Yes
Yes

No
No

Data Takers/Organization

Joe Bradley, DED
David Dayton, DED
Dennis McCloud, DPRP
J. Edward Gibbs, DPP (Outage)
Mike Montsinger, DPP (QA)
Tom Kulaga, DPP (Outage)
Mike McInerney, DPP (QA)

Dates Test Performed

11/26/77 - 11/27/77

Reviewed by Cognizant Engineer

J. Edward Gibbs 11/27/77

Reviewed by Results Section Supervisor

Wm C. Thompson 11/27/77

Reviewed by Quality Assurance Supervisor

John L. Harner

OFFICIAL COPY

STER 22

TEST DATA/BROWNS FERRY CONNECTORS

#2 Pin Connector

GULTON Model Number

STEP	ITEM	RESULTS	BY/DATE
4.1.a	Verify proper hook up for connector (test item #2, figure 2, for 48-pin connector; test item #1, figure 2, for 12-pin connector)	<u>✓</u> OK	<u>000</u> 11/24/77 Verified
4.1.b	Megger: pin to all pins and shell combined	<u>≥ 1.3X10⁹</u> Ohms	<i>Eliminated pin "9" as it showed discoloration around base of pin. Eliminated pin "8" to restore test circuit. (inboard plug)</i>
	pin to shell	<u>320X10⁶</u> Ohms	
4.1.c	Verify current continuity	<u>✓</u> OK	
4.2.a	Energize connector from nominal 250 VDC source (verify)	<u>✓</u> OK	<u>052</u> 11/24/77 Verified
4.2.b	Load voltage	<u>242</u> Volts	<u>052</u> 11/24/77
4.2.c	Set load for connector so as to give load current of 5.0 ± 0.5 amps (initial values)	<u>4.83</u> Amps	<u>052</u> 11/24/77 QC
4.2.d	Initial test chamber pressure and temperature	<u>0</u> psig <u>150</u> °F.	<u>052</u> 11/24/77 Verified
4.3.a	Admit steam, bringing temperature to $322 \pm 5^\circ$ F. Also note start time of the test (t_0).	<u>28</u> psig <u>322</u> °F. <u>10:45:14</u> Start time	<u>052</u> 11/24/77 Verified
4.3.b	Stabilize temperature and pressure at $322 \pm 5^\circ$ F.	<u>10:50:01</u> time	<u>052</u> 11/24/77 Verified
4.3.c	When stabilized, record load current and voltage.	<u>4.83</u> amps Load <u>242</u> volts Input <u>251</u> volts	<u>052</u> 11/24/77 QC

OFFICIAL COPY

Connector #2, GULTON

STEP	ITEM	RESULTS	BY/DATE
4.3	(Continued)		
4.3.d	Maintain in stabilized condition for 5 minutes; record load current and voltage at end.	<u>4.82</u> Amps Load <u>242</u> Volts Input <u>250</u> Volts	<u>Mgmm 11/26</u> QC

OFFICIAL COPY

Connector #2, GOWEN

STEP	ITEM	RESULTS	BY/DATE
4.4			
4.4.a	Reduce pressure at 0.7 psig/ minute to 282°F at 36 psig in one hour; record initial load current and voltage.	10:55:04 time. 4.82 amps load 243.8 volts input 250 volts	<u>M. G. M</u> 11/26 verified
	Repeat at three 5 minute intervals	11:02:35 time 4.81 amps load 243.1 volts input 251 volts	<u>M. G. M</u> 11/26 verified
		11:07:35 time 4.80 amps load 243.2 volts input 250 volts	<u>M. G. M</u> 11/26 verified
		11:12:35 time 4.79 amps load 242.6 volts input 250 volts	<u>M. G. M</u> 11/26 verified
4.4.b	Drop pressure immediately to 150 psig. Record load current and voltage.	12:01:00 time 4.82 amps load 243 volts input 251 volts	<u>M. G. M</u> 11/26 verified
	should be 250°F 15 psig		
4.4.c	At hourly intervals, reduce the pressure by 1.0 ± 0.5 psig Record time of pressure reduction, new pressure (psig), load current and voltage. Repeat for 15 hours until 212°F at atmospheric pressure is obtained.		

OFFICIAL COPY

Connector #2, GULFON

BF STER 22 /
11/25/77

STEP	ITEM	RESULTS	BS/DATE
4.4.c (Continued)		26:13:01:13 T	<u>0.52</u> 11/26
		14 P	
		4.79 A	
	Load	242.4 V	
	Input	250 V	
		14:02:19 T	<u>0.58</u> 11/26
		13 P	
		4.80 A	
	Load	243.34 V	
	Input	250 V	
		15:02:19 T	<u>0.58</u> 11/26
		12 P	
		4.77 A	
	Load	241.86 V	
	Input	250 V	
		16:05:24 T	<u>0.13</u> 11/26
		10.8 P	
		4.77 A	
	Load	241.79 V	
	Input	250 V	
		17:05:24 T	<u>dem</u> 11/26
		10.0 P	
		4.77 A	
	Load	241.5 V	11/26/77
	Input	249 V	
		18:05:24 T	<u>dem</u> 11/26
		9 P	
		4.78 A	
	Load	242.3 V	
	Input	250 V	

OFFICIAL COPY

Connector

712, GULTON

11/25/77

STEP	ITEM	RESULTS	BY/DATE
4.4.c (Continued)		19:05:24 T	denis 11/26
		8 P	
		4.76 A	
	Load	241.4 V	
	Input	248 V	
		20:05:24 T	TAK 11/26
		7 P	
		4.74 A	
	Load	240.6 V	
	Input	249 V	
		21:05:24 T	TAK 11/26
		6 P	
		4.78 A	
	Load	242.0 V	
	Input	250 V	
		22:05:24 T	TAK 11/26
		5 P	
		4.78 A	
	Load	242.0 V	
	Input	250 V	
		23:05:24 T	TAK 11/26
		4 P	
		4.78 A	
	Load	241.9 V	
	Input	250 V	
		00:05:24 T	TAK 11/26
		3 P	
		4.77 A	
	Load	241.25 V	
	Input	250 V	

OFFICIAL COPY

Connector #2, Gulton

STEP	ITEM	RESULTS	BY/DATE
4.4.c	(Continued)	<u>1:05:24</u> T	<u>TAK 11/27</u>
		<u>2</u> P	
		<u>4.78</u> A	
	Load	<u>242.4</u> V	
	Input	<u>250.</u> V	
		<u>2:05:24</u> T	<u>TAK 11/27</u>
		<u>1</u> P	
		<u>4.77</u> A	
	Load	<u>241.7</u> V	
	Input	<u>250</u> V	
		<u>3:05:24</u> T	<u>TAK 11/27</u>
		<u>0</u> P	
		<u>4.78</u> A	
	Load	<u>242.4</u> V	
	Input	<u>250</u> V	
		<u>1</u> T	
		<u>1</u> P	
		<u>1</u> A	
	Load	<u>1</u> V	
	Input	<u>1</u> V	

Not Required
JSS 11/24/77

4.5

At hourly intervals, reduce temperature by $7\frac{1}{2}^{\circ}\text{F/hr}$. Record time of temperature reduction, new temperature, load current and voltage. Repeat until 150°F is reached after 24 hours into the test.

OFFICIAL COPY

BY/DATE

TA King

4.76 A

4.77 A

188°F temp

4.78 A

Input 249.0 V

07:05:24 T

18.2 °F temp

4. 7 8. A

Load 242.7 v

Input 250 V

08:05:24- T

174.0 F temp

4.77 A

Load 241.6 V

Input : 250.0 V

09:05:24 T

1.66.5 °F temp

4:77 A

Load 246.4 v

Input 249.0 V

OFFICIAL COPY

Connector #2, GULTON

STEP	ITEM	RESULTS	BY/DATE
4.5	(Continued)	27:10:05:24 T	<u>Mg. M</u> 11/27/77
		<u>160</u> temp	
		<u>4.78</u> A	
	Load	<u>242.30</u> V	
	Input	<u>250.</u> V	
		27:11:04:57 T	<u>Dean</u> 11/27/77
		<u>159</u> temp	
		<u>4.78</u> A	
	Load	<u>241.62</u> V	
	Input	<u>249</u> V	

Test Data Verification:

MD McInerney 11/27/77
QC Inspector/Date

J. Edward Dobb 11/27/77
Test Engineer/Date

OFFICIAL COPY

Part III

Justification for Continued Operation

TVA considers the tests and evaluations described in Part II sufficient to permit the continued operation of the facility without creating undue risk to the health and safety of the public for the period it will take to fully environmentally qualify the connectors. This position is based upon the low probability of the events that produce adverse environments, the supplemental testing that demonstrated that the connectors within containment can continue to function in a postulated steam environment, the short time required for critical connectors outside containment to function before exceeding their design temperature, and the connector resistance to a radiation environment.

