

Frederick W. Schneider  
ice President  
roduction

Public Service Electric and Gas Company 80 Park Place Newark, N.J. 07101 201/622-7000


October 28, 1977

Mr. Boyce H. Grier, Director  
U.S. Nuclear Regulatory Commission  
Office of Inspection and Enforcement  
Region 1  
631 Park Avenue  
King of Prussia, Pennsylvania 19406

Dear Mr. Grier:

NRC IE BULLETIN NO. 77-03  
"ON-LINE TESTING OF THE WESTINGHOUSE (W) SOLID  
STATE PROTECTION SYSTEM (SSPS)"  
NO. 1 AND 2 UNITS  
SALEM NUCLEAR GENERATING STATION

In response to your letter of September 12, 1977 transmitting NRC IE Bulletin No. 77-03, we have investigated this matter with respect to applicability to Salem No. 1 and 2 Units. The following summarizes the results of our investigation.

1. The testing provisions for the Salem SSPS did not include testing of the reset timing circuitry.
  2. To assure periodic testing of the safety injection reset timing circuit, Performance Department Procedure Number PD-18.1.001, "SSPS Periodic Test", has been revised to incorporate the scheme specified by the Westinghouse Technical Bulletin NSD-TB-77-11.
  3. The above action applies to Salem No. 1 and 2 Units.
- 


Mr. B.H. Grier

- 2 -

10-28-77

If you require additional information, we will be pleased to discuss it with you.

Very truly yours,

A handwritten signature in cursive script, appearing to read "E. Schneider". The signature is written in dark ink and is positioned below the typed phrase "Very truly yours,".