

TABLE 4.1-1 (Continued)

	<u>CHANNEL DESCRIPTION</u>	<u>CHECK</u>	<u>TEST</u>	<u>CALIBRATE</u>	<u>REMARKS</u>
38.	Steam Generator Water Level	W	NA	R	
39.	Turbine Overspeed Trip	NA	R*	NA	
40.	Sodium Thiosulfate Tank Level Indicator	NA	NA	R	
41.	Sodium Hydroxide Tank Level Indicator	NA	NA	R	
42.	Diesel Generator Protective Relaying	NA	NA	R	
43.	1 KV ES Bus Undervoltage Relays (Diesel Start)	NA	M(1)	R	(1) Relay operation will be checked by local test pushbuttons.
44.	Reactor Coolant Pressure DH Valve Interlock Bistable	S(1)	M	R	(1) When reactor coolant system is pressurized above 300 psig of Taves is greater than 200°F.

S - Each Shift

T/W - Twice per week

R - Each Refueling Period

D - Daily

B/M - Every 2 months

NA - Not Applicable

W - Weekly

Q - Quarterly

B/W - Every two weeks

M - Monthly

P - Prior to each startup
if not done previous week

*Test to be performed prior to exceeding 20% power during Cycle 5 start up only.

4.5 EMERGENCY LOADING SEQUENCE AND POWER TRANSFER, EMERGENCY CORE COOLING SYSTEM AND REACTOR BUILDING COOLING SYSTEM PERIODIC TESTING

4.5.1 EMERGENCY LOADING SEQUENCE

Applicability

Applies to periodic testing requirements for safety actuation systems.

Objective

To verify that the Emergency loading sequence and automatic power transfer is operable.

Specifications

4.5.1.1* Sequence and Power Transfer Test

- a. During each refueling interval, a test shall be conducted to demonstrate that the emergency loading sequence and power transfer is operable.
- b. The test will be considered satisfactory if the following pumps and fans have been successfully started and the following valves have completed their travel on preferred power and transferred to the emergency power as evidenced by the control board component operating lights, and either the station computer or pressure/flow indication.
 - M. U. Pump
 - D. H. Pump and D. H. Injection Valves and D. H. Supply Valves
 - R. B. Cooling Pump
 - R. B. Ventilators
 - D. H. Closed Cycle Cooling Pump
 - N. S. Closed Cycle Cooling Pump
 - D. H. River Cooling Pump
 - N. S. River Cooling Pump
 - D. H. and N. S. Pump Area Cooling Fan
 - Screen House Area Cooling Fan
 - Spray Pump. (Initiated in coincidence with a 2 out of 3 R. B. 30 psi Pressure Test Signal.)

*This test shall be performed prior to Cycle 5 criticality.

4.5.1.2 Sequence Test

- a. At intervals not to exceed 3 months, a test shall be conducted to demonstrate that the emergency loading sequence is operable, this test shall be performed on either preferred power or emergency power.
- b. The test will be considered satisfactory if the pumps and fans listed in 4.5.1.1b have been successfully started and the valves listed in 4.5.1.1b have completed their travel as evidenced by the control board component operating lights, and either the station computer or pressure/flow indication.

Bases

The Emergency loading sequence and automatic power transfer controls the operation of the pumps associated with the emergency core cooling system and Reactor Building cooling system.

4.5.2 EMERGENCY CORE COOLING SYSTEM

Applicability

Applies to periodic testing requirement for emergency core cooling systems.

Objective

To verify that the emergency core cooling systems are operable.

Specification

4.5.2.1 High Pressure Injection

- a. During each refueling interval and following maintenance or modification that affects system flow characteristics, system pumps and system high point vents shall be vented, and a system test shall be conducted to demonstrate that the system is operable.*

The M. U. Pump and its required supporting auxiliaries will be started manually by the operator and a test signal will be applied to the high pressure injection valves MU-V-16A, B, C, D to demonstrate activation of the high pressure injection system for emergency core cooling operation.

- b. The test will be considered satisfactory if the valves have completed their travel and the M. U. Pumps are running as evidenced by the control board component operating lights. Minimum acceptable injection flow must be greater than or equal to 500 gpm per HPI pump when pump discharge pressure is 600 psig or greater (the pressure between the pump and flow limiting device) and when the RC pressure is equal to or less than 600 psig.
- c. Testing which requires HPI flow thru MU-V16A, B, C, D shall be conducted only under either of the following conditions:
 - 1) T avg. shall be greater than 320°F.
 - 2) Head of the Reactor Vessel shall be removed.

*The High Pressure Injection Test shall be performed prior to Cycle 5 criticality.

4.5.2.2 Low Pressure Injection

- a. During each refueling period and following maintenance or modification that affects system flow characteristics, system pumps and high point vents shall be vented, and a system test shall be conducted to demonstrate that the system is operable. The auxiliaries required for low pressure injection are all included in the emergency loading sequence specified in 4.5.1.**
- b. The test will be considered satisfactory if the decay heat pumps listed in 4.5.1.1b have been successfully started and the decay heat injection valves and the decay heat supply valves have completed their travel as evidenced by the control board component operating lights. Flow shall be verified to be equal or greater than the flow assumed in the Safety Analysis for the single corresponding RCS pressure used in the test.

b. Reactor Building Cooling and Isolation System

1. During each refueling period, a system test shall be conducted to demonstrate proper operation of the system.* A test signal will actuate the R.B. emergency cooling system valves to demonstrate operability of the coolers.
2. The test will be considered satisfactory if the valves have completed their expected travel as evidenced by the control board component operating lights, and either the station computer or local verification.

*The system test shall be conducted prior to heatup following Cycle 4 refueling.

4.5.3.2 Component Tests

- a. At intervals not to exceed three months, the components required for reactor building cooling and isolation will be tested.
- b. The test will be considered satisfactory if the valves have completed their expected travel as evidenced by the control board component operating lights, and either the station computer or local verification.

Bases

The reactor building cooling and isolation systems and reactor building spray system are designed to remove the heat in the containment atmosphere to prevent the building pressure from exceeding the design pressure.

The delivery capability of one reactor building spray pump at a time can be tested by opening the valve in the line from the borated water storage tank, opening the corresponding valve in the test line, and starting the corresponding pump.

With the pumps shut down and the borated water storage tank outlet closed, the reactor building spray injection valves can each be opened and closed by the operator action. With the reactor building spray inlet valves closed, low pressure air can be blown through the test connections of the reactor building spray nozzles to demonstrate that the flow paths are open.

The equipment, piping, valves and instrumentation of the reactor building cooling system are arranged so that they can be visually inspected. The cooling units and associated piping are located outside the secondary concrete shield. Personnel can enter the reactor building during power operations to inspect and maintain this equipment.

The reactor building fans are normally operating periodically, constituting the test that these fans are operable.

Reference

- (1) FSAR, Section 6

4.12 AIR TREATMENT SYSTEMS

4.12.1 EMERGENCY CONTROL ROOM AIR TREATMENT SYSTEM

Applicability

Applies to the emergency control room a treatment system and associated components.

Objective

To verify that this system and associated components will be able to perform its design functions.

Specification

- 4.12.1.1 At least every refueling interval or once every 18 months, whichever comes first, the pressure drop across the combined HEPA filters and charcoal adsorber banks of AH-F3A and 33 shall be demonstrated to be less than 6 inches of water at system design flow rate ($\pm 10\%$).
- 4.12.1.2 a.* The tests and sample analysis required by Specification 3.15.1.2 shall be performed initially and at least once per year for standby service or after every 720 hours of system operation and following significant painting, steam, fire or chemical release in any ventilation zone communicating with the system that could contaminate the HEPA filters or charcoal adsorbers.
- b.* DOP testing shall be performed after each complete or partial replacement of the HEPA filter bank or after any structural maintenance on the system housing which could affect the HEPA filter bank bypass leakage.
- c.* Halogenated hydrocarbon testing shall be performed after each complete or partial replacement of the charcoal adsorber bank or after any structural maintenance on the system housing which could affect the charcoal adsorber bank bypass leakage.
- d. Each AH-E18A and B (AH-F3A and B) fan/filter circuit shall be operating at least 10 hours every month.
- 4.12.1.3 At least once per refueling interval or once every 18 months, whichever comes first, automatic initiation of the Control Building isolation and recirculation Dampers AH-D28, 37, 39, and 36 shall be demonstrated as operable.
- 4.12.1.4 An air distribution test shall be performed on the HEPA filter bank initially, and after any maintenance or testing that could affect the air distribution within the system. The air distribution across the HEPA filter bank shall be uniform within $\pm 20\%$. The test shall be performed at 40,000 cfm ($\pm 10\%$) flow rate.

*Surveillance to be performed prior to Cycle 5 criticality in lieu of once per refueling interval or once per 18 months.

4.12.2 REACTOR BUILDING PURGE AIR TREATMENT SYSTEM

Applicability

Applies to the reactor building purge air treatment system and associated components.

Objective

To verify that this system and associated components will be able to perform its design functions.

Specification

- 4.12.2.1 At least once per refueling interval or once per 18 months, whichever comes first it shall be demonstrated that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches of water at system design flow rate ($\pm 10\%$).
- 4.12.2.2 a.* The tests and sample analysis required by Specification 3.15.2.2, shall be performed initially, once per refueling interval or 18 months, whichever comes first, or after each 720 hours of operation or following significant painting, steam, fire, or chemical release in any ventilation zone communicating with the system that could contaminate the HEPA filters or charcoal adsorbers.
- b.* DOP testing shall be performed after each complete or partial replacement of a HEPA filter bank or after any structural maintenance on the system housing which could affect HEPA frame bypass leakage.
- c.* Halogenated hydrocarbon testing shall be performed after each complete or partial replacement of a charcoal adsorber bank or after any structural maintenance on the system housing which could affect the charcoal adsorber bank bypass leakage.
- d.* The DOP and halogenated hydrocarbon testing shall be performed at the maximum available flow considering physical restrictions, i.e., purge valve position, and gaseous radioactive release criteria.
- e. The Reactor Building purge exhaust fans AH-E7A and B shall be operated at least 10 hours every month, either during actual purging or using makeup air.
- 4.12.2.3 An air distribution test shall be performed on the HEPA filter bank initially and after any maintenance or testing that could affect the air distribution within the system. The air distribution across the HEPA filter bank shall be uniform within $\pm 20\%$. The test shall be performed at 25,000 cfm ($\pm 10\%$) flow rate.

*Surveillance to be performed prior to Cycle 5 criticality in lieu of once per refueling interval or once per 18 months.

Bases

Pressure drop across the combined HEPA filters and charcoal adsorbers of less than 6 inches of water at the system design flow rate will indicate that the filters and adsorbers are not clogged by excessive amounts of foreign matter. Pressure drop should be determined at least once every refueling interval to show system performance capability.