

EXHIBIT B

License Amendment Request Dated September 2, 1977

This exhibit consists of the following pages revised to incorporate the proposed Technical Specification changes:

Page 141

9102080432 770902
PDR ADOCK 05000263
P PDR

3.0 LIMITING CONDITIONS FOR OPERATION

4.0 SURVEILLANCE REQUIREMENTS

- (3) ence, prior to and after repair shall be added to the final integrated leak rate result.
- (4) Closure of the containment isolation valves for the purpose of the test shall be accomplished by the means provided for normal operation of the valves.
- (5) Test duration shall be at least eight hours and shall include at least 20 sets of data taken at approximately equal time intervals. In addition, the test shall have a duration sufficiently long to accumulate and analyze enough data to verify that the measured leakage rate, at the 95% confidence level, is less than the acceptance criterion contained in Specification 4.7.A.2(b)(2).
- (6) Each test shall be immediately followed by a verification test using a known superimposed leak in accordance with Appendix C to ANSI N45.4 -1972. The verification test shall have a duration sufficiently long to accumulate and analyze enough data to verify that at the 95% confidence level the measured composite leakage lies within $0.25L_a$ of the sum of the superimposed leak rate and the measured overall containment leak rate.

(b) Acceptance Criteria for IPCLT

- (1) The maximum allowable leak rate L_t shall not exceed 1.2 weight percent of the contained air per 24 hours at the test pressure of 41 psig (P_t).

50-263

FILE NUMBER

NRC-DISTRIBUTION FOR PART 50 DOCKET MATERIAL

TO: Mr. Victor Stello

FROM: NSP
Minneapolis, Minnesota 55401
L. O. Mayer

DATE OF DOCUMENT

09/02/77

DATE RECEIVED

09/08/77

☒ LETTER
☒ ORIGINAL
☐ COPY

☐ NOTORIZED
☒ UNCLASSIFIED

PROP

INPUT FORM

NUMBER OF COPIES RECEIVED

3 SIGNED

DESCRIPTION

DO NOT REMOVE

2p

ENCLOSURE Consists of License No. DPR-22 Appl
for Amend: tech specs proposed change concerning
revising current tech specs to permit contain-
ment integrated leak rate tests to be terminated
in less than 24 hours...Notorized 09/02/77...

7p

ACKNOWLEDGED

PLANT NAME: MONTICELLO
jcm 09/09/77

SAFETY

FOR ACTION/INFORMATION

BRANCH CHIEF: (7)

DAVIS

INTERNAL DISTRIBUTION

REG FILE

NRC PDR

I & E (2)

OELD

HANAUER

CHECK

STELLO

EISENHUT

SHAO

BAER

BUTLER

GRIMES

J. COLLINS

EXTERNAL DISTRIBUTION

LPDR: MINNEAPOLIS MN.

TIC

NSIC

16 CYS ACRS SENT CATEGORY B

CONTROL NUMBER

772520147