

1901 Chouteau Avenue
Post Office Box 149
St. Louis, Missouri 63166
314 554-2860



April 25, 1994

Donald F. Schnell
Senior Vice President
Nuclear

U.S. Nuclear Regulatory Commission
ATTN.: Document Control Desk
Mail Station P1-137
Washington, D.C. 20555

ULNRC-2992

Gentlemen:

DOCKET NUMBER 50-483
CALLAWAY PLANT
ASME CODE CASE N-416-1

The American Society of Mechanical Engineers has submitted Code Case N-416-1 to the Nuclear Regulatory Commission for review and approval. Code Case N-416-1 is entitled "Alternative Pressure Test Requirement for Welded Repairs or Installation of Replacement Items by Welding." Approval is hereby requested for use of the provisions of Code Case N-416-1 for ASME Class 1 and Class 2 systems. Approval for use on ASME Class 3 systems is specifically excluded from this request, and will be submitted for consideration on a separate letter (ULNRC-2993). The reason for separate submittal of ASME Class 3 systems is to facilitate timely approval for use of N-416-1 in ASME Class 1 and 2 systems.

Approval is requested by September, 1994, to permit utilization during Callaway's next refueling outage (currently scheduled for Spring, 1995). The need for timely approval is a result of Callaway's implementation of Code Case N-416-0. N-416-0 permits deferral of hydrostatic testing for specific ASME Class 2 repairs and replacements until the end of the 10-year ISI interval. Additionally, the NRC has approved Code Case N-498, which permits elimination of 10-year ISI hydrostatic testing for ASME Class 1 and 2 systems. Callaway has adopted Code Case N-498 which, with the exception of the tests deferred under N-416-0, eliminates the need for 10-year ISI hydrostatic tests. Approval of Code Case

030014

9405040074 940425
PDR ADOCK 05000483
P PDR

Ac47
1/0

U.S. Nuclear Regulatory Commission
ULNRC-2992
Page 2
April 25, 1994

N-416-1 is needed in order to eliminate the requirement for hydrostatic testing of the components deferred in accordance with Code Case N-416-0. Cost savings resulting from elimination of these deferred hydrostatic tests are conservatively estimated at approximately \$19,000.00. Cost savings resulting from elimination of all Class 1, 2, and 3 repair/replacement hydrostatic tests are estimated at approximately \$225,000.00. Significant reductions in radiation exposure will also result.

Very truly yours,

A handwritten signature in dark ink, appearing to read "Donald F. Schnell", written in a cursive style.

Donald F. Schnell

CDN/kea

cc: T. A. Baxter, Esq.
Shaw, Pittman, Potts & Trowbridge
2300 N. Street, N.W.
Washington, D.C. 20037

M. H. Fletcher
CFA, Inc.
18225-A Flower Hill Way
Gaithersburg, MD 20879-5334

L. Robert Greger
Chief, Reactor Project Branch 1
U.S. Nuclear Regulatory Commission
Region III
801 Warrenville Road
Lisle, IL 60532-4351

Bruce Bartlett
Callaway Resident Office
U.S. Regulatory Commission
RR#1
Steedman, MO 65077

L. R. Wharton (2)
Office of Nuclear Reactor Regulation
U.S. Nuclear Regulatory Commission
1 White Flint, North, Mail Stop 13E21
11555 Rockville Pike
Rockville, MD 20852

Manager, Electric Department
Missouri Public Service Commission
P.O. Box 360
Jefferson City, MO 65102