



**Consumers
Power
Company**

James W Cook
*Vice President - Projects, Engineering
and Construction*

General Offices: 1945 West Parnall Road, Jackson, MI 49201 • (517) 788-0453

81-03 #13

April 23, 1982

Mr J G Keppler, Regional Administrator
US Nuclear Regulatory Commission
Region III
799 Roosevelt Road
Glen Ellyn, IL 60137

Mr H R Denton (25)
Office of Nuclear Reactor Regulation
US Nuclear Regulatory Commission
Washington, DC 20555



MIDLAND PROJECT -
DOCKET NOS 50-329 AND 50-330
BORATED WATER STORAGE TANK FOUNDATION OL DESIGN CALCULATIONS
FILE: 0485.16, 0.4.9.49 SERIAL: 16172

References: J W Cook letters to J G Keppler:

- (1) Serial 11201, dated February 20, 1981
- (2) Serial 11528, dated April 3, 1981
- (3) Serial 12015, dated June 12, 1981
- (4) Serial 12799, dated June 26, 1981
- (5) Serial 13352, dated July 21, 1981
- (6) Serial 13653, dated August 28, 1981
- (7) Serial 14591, dated October 26, 1981
- (8) Serial 14339, dated November 13, 1981
- (9) Serial 14902, dated November 24, 1981
- (10) Serial 14645, dated December 11, 1981
- (11) Serial 14664, dated January 18, 1982
- (12) Serial 16127, dated March 15, 1982

This letter, as were the referenced letters, is an interim 50.55(e) report concerning the existence of cracks in the borated water storage tank foundation.

Attachment 1 provides a report of the analyses and corrective actions that have been or will be taken as a result of the deficiency identified with these cracks.

Another report, either interim or final, will be sent on or before July 2, 1982.

APR 29 1982

8205110089 820423
PDR ADOCK 05000329
S PDR

James W. Cook
IE27
5/11
IE19

Bechtel Associates Professional Corporation

067174

067259

SUBJECT: MCAR 48 (issued 1/29/81)

The Existence of Cracks in the Borated Water
Storage Tank Foundation - Units 1 and 2

FINAL REPORT

DATE: April 20, 1982

PROJECT: Consumers Power Company
Midland Plant Units 1 and 2
Bechtel Job 7220

Introduction

This report addresses the existence of cracks in the borated water storage tank (BWST) foundations as described in MCAR 48 and three subsequent interim reports. This report is a final statement on the investigative analyses and all corrective actions that have been or will be taken as a result of the deficiency identified with these cracks.

Description of Deficiency

The 52-foot diameter, stainless steel BWSTs are 32 feet high and rest on a reinforced concrete ring wall and compacted, granular backfill material contained within the ring wall. On one side is an integral valve pit that houses connections and valves for the two 18-inch diameter pipelines that service each tank. Figure BWST-1 from the Atomic Safety and Licensing Board (ASLB) Hearing Testimony of Alan J. Boos and Dr. Robert Hanson regarding remedial measures for the BWST is attached for reference.

During the load test on the Unit 1 tank (conducted in compliance with the response to 10 CFR 50.54(f), Question 4), a discrepancy was noted between measurements of settlements recorded at the jobsite and the computed displacements derived from the structural analysis used at that time. As a result, the analysis was modified to include a finite-element model of the soil subgrade. A number of analyses were completed using various values for the modulus of elasticity (E) of the soil. The results of the analyses predicted that moments at several locations in the foundation structure exceed allowable moments. The foundation at these locations was examined to verify whether visible signs of high strain in the reinforcement existed. Cracks were found in the structure at those locations indicated by the analysis as having greater than allowable moments. The largest crack measured 0.063 inch. Subsequently, the Unit 2 tank foundation was also examined; similar cracks were found, and the largest crack measured 0.035 inch. The smaller bearing area of the Unit 2 valve pit partially explains why the cracks in the Unit 2 tank foundation are smaller than the cracks in the Unit 1 tank foundation.

2

Serial 16172

81-03 #13

Attachment 1: MCAR 48, Final Report, "The Existence of Cracks in the
Borated Water Storage Tank Foundation - Units 1 and 2,
dated April 20, 1982

CC: RJCook, Midland Resident Inspector
Document Control Desk, NRC Washington, DC
Atomic Safety & Licensing Appeal Board
CBechhoefer, ASLB
MMCherry, Esq
FPCowan, ASLB
RSDecker, ASLB
DSHood, USNRC (2)
RHernan, USNRC
JHarbour, ASLB
JDKane, USNRC
Wotto, US Army Corps of Engineers
WHMarshall
FRinaldi, USNRC
HSingh, US Army Corps of Engineers
MSinclair
BStamiris
SJPoulos, Geotech Eng, Inc

Bechtel Associates Professional Corporation

067174

067259

MCAR 48
Final Report
April 20, 1982
Page 2

Safety Implications

As shown in Figure BWST-1, the tanks' outside shell is attached to the ring wall foundation by equally spaced anchor bolts that transfer induced forces from the anchor chair. Field observations indicated gaps between the anchor bolt nut and anchor chair in several locations around the periphery of the tank. In other locations, the anchor chairs were deflected, indicating high tensile stress in the bolts. This anchor bolt behavior results from the distortion of the foundation ring which is caused by differential settlement; this agrees with the conclusions of the modified structural analysis. The tension induced in the bolts is similar to the tension induced by a preload phenomenon and does not affect the ability of the bolts to resist design loads. Although the ring wall is cracked, it is capable of providing the necessary anchorage for the anchor bolts to resist tension due to externally applied forces.

The concrete ring wall confines the foundation material which is loaded by the tank; this confinement causes hoop tension in the ring wall. Cracks equal in size to those observed in the ring wall expose the reinforcing steel to the groundwater and atmosphere. If the reinforcing steel carrying the hoop tension were to corrode significantly, the ability of the ring wall to resist the hoop tension would be reduced. Reduction of overall strength of the ring wall, combined with increased displacements (both vertically and laterally) of the ring wall, may occur, causing stress concentrations in the tank near anchor chairs.

Based on the foregoing discussion, it is concluded that the cracking of the ring beam does not create a present safety problem for the tank. However, it could not be conclusively shown that the safety of future plant operations would not have been affected if the deficiency had gone uncorrected. Therefore, the condition was treated as reportable under the provisions of 10 CFR 50.55(e).

Probable Cause

Review of field observations and analytical investigations leads to an understanding of the probable cause. When the tank was loaded, the bearing pressure on the tank area was increased to approximately 2 ksf greater than the valve pit area; however, this 2 ksf differential was not accounted for in the calculation for ring beam reinforcing. As a result, the valve pit restrained the tank foundation from settling uniformly, causing bending at the ring wall/valve pit junction.

Bechtel Associates Professional Corporation

067174

067259

MCAR 48

Final Report

April 20, 1982

Page 3

Corrective Action

To ensure that the BWSTs function properly in the future under all design conditions, the following actions are being implemented.

1. A portion of the valve pit and its surrounding area has been surcharged. Figure BWST-2 from the ASLB Hearing Testimony of A.J. Boos and Dr. R. Hanson details the surcharge program which was begun October 27, 1981, and completed March 19, 1982.

The surcharge operation has consolidated the fill beneath the valve pit, thereby reducing the amount of expected residual differential settlement of the foundation structure over the 40-year life of the plant. In addition, by reducing the differential settlement, the surcharging has reduced the ring wall distortion. However, the proposed remedial plan for the ring wall described below will not take credit for this reduced distortion, and, therefore, is conservative.

2. A reinforcing ring beam will be constructed around the existing ring wall. The new ring beam is sized to resist all imposed loading from the tank, including additional future bending induced by the predicted residual differential settlement between the ring wall and the valve pit. Shear connectors transfer the shear force from the existing ring wall to the new ring beam. One end of the shear connectors will be installed in the existing ring wall by drilling and grouting. The other end will be cast in the new ring beam. All cracks in the existing ring wall that exceed 10 mils will be repaired by pressure grouting. The main reinforcing bars in the new ring beam that terminate at the valve pit are anchored in the roof or base slab of the valve pit by grouting them into drilled holes.

Construction of the new ring beam is scheduled to take place between May 10, 1982, and July 23, 1982.

3. After ring beam construction is complete, the Unit 1 tank (BWST 1T-60) will be releveled. The Unit 2 tank (BWST 2T-60) need not be releveled because the ring wall foundation is not severely distorted.

A detailed procedure has been developed to define a plan of action to relevel BWST 1T-60. This procedure is supported by an analysis which demonstrates that the tank will not be overstressed during this operation. Strain gaging of the tank will be used as a backup to this analysis. A brief summary of the procedure is provided below.

Bechtel Associates Professional Corporation

067174

067259

MCAR 48
Final Report
April 20, 1982
Page 4

- a. Drain and vent the tank
- b. Mount strain gages
- c. Attach 12 to 16 electromechanical jacks to the anchor bolt chairs
- d. Lift the vessel approximately 3 feet. (All jacks will be controlled from a central control panel and will lift at the same rate and time.)
- e. Support tank with cribbing
- f. Install Celotex cofferdam around the inner diameter of the ring wall to contain grout placed in Step k below
- g. Add and contour oil-impregnated sand
- h. Clean the top surface of the ring wall
- i. Place stainless steel shims on the original concrete ring wall. Level to a common datum plane approximately 1-1/2 inches above the ring wall. Set shims to the following standard:
 - 1) 1/8 inch within any 30 feet of circumference
 - 2) 1/4 inch over total circumference
- j. Remove cribbing and lower the tank
- k. Add nonshrink grout under the tank bottom to the Celotex cofferdam and allow grout to set
- l. Remove strain gages
- m. Tighten anchor bolt nuts

This releveing of BWST 1T-60 is scheduled to begin July 19, 1982, and be completed September 17, 1982. At that time, the piping will be reconnected to the tanks, the tanks will be refilled, and by December 17, 1982, the BWSTs will be in conformance with the requirements of the final safety analysis report (FSAR).

Bechtel Associates Professional Corporation

067174

067259

MCAR 48
Final Report
April 20, 1982
Page 5

4. After the new ring beam is constructed, two observation pits will be provided for each BWST foundation at the high stress locations. The new ring beams will be monitored monthly for possible cracks under the service condition for 6 months after filling the tanks. At the end of the monitoring period, a report evaluating cracks will be submitted to the NRC. However, if during the monitoring period any cracks are noted to be 30 mils or larger, an engineering evaluation will be conducted to determine whether the tank should be drained.

BWST foundation settlement will also be monitored as part of the foundation survey. Foundations are surveyed at 60-day intervals during construction and at 90-day intervals for the first year of plant operation. Subsequent survey frequency will be established after evaluating the data taken during the first year of plant operation. As a minimum, the tank foundation would be monitored annually for the next 5 years of operation and at 5-year intervals thereafter.

The critical areas of each foundation at the transition zone between the ring wall and the valve pit will be monitored using a strain gage system. This system will be monitored at the same frequency as the foundation survey using established acceptance criteria.

The construction period survey requirements are currently a part of project construction specifications (7220-C-76). The construction period strain gage monitoring requirements will be incorporated into the project construction drawings of the new ring beam (7220-C-1153 and C-1154) by May 21, 1982. The long-term survey and strain gage monitoring requirements will be incorporated in the FSAR technical specifications by January 1, 1983.

Submitted by:

DM Griffith *ST/HE*

Approved by:

on loan for L.H. Curtis
L.H. Curtis
Project Engineering Manager

Concurrence by:


E.H. Smith
E.H. Smith
Engineering Manager

Concurrence by:

M.A. Dietrich
for M.A. Dietrich
Project Quality Assurance Engineer

067174

067259



CONSUMERS POWER COMPANY
MIDLAND PLANT UNITS 1 & 2

BORATED WATER STORAGE TANK

FIGURE BWST-1

067174

* Granular fill shall be placed to a height such that its weight is equivalent to the weight of the concrete blocks in the corresponding area.




TABLE 1 SETTLEMENT MONITORING					
DATA BASE NO.	LOCATION (IT 40)	ELEVATION (ft)	DATA BASE NO.	LOCATION (IT 40)	ELEVATION (ft)
01	0	535.0'	016	0	535.0'
02	30'	535.0'	017	30'	535.0'
03	60'	535.0'	018	60'	535.0'
04	90'	535.0'	019	90'	535.0'
05	120'	535.0'	020	120'	535.0'
06	150'	535.0'	021	150'	535.0'
07	180'	535.0'	022	180'	535.0'
08	210'	535.0'	023	210'	535.0'
09	240'	535.0'	024	240'	535.0'
10	270'	535.0'	025	270'	535.0'
11	300'	535.0'	026	300'	535.0'
12	330'	535.0'	027	330'	535.0'
13	VALVE PIT	535.0'	028	VALVE PIT	535.0'
14	VALVE PIT	535.0'	029	VALVE PIT	535.0'
15	VALVE PIT	535.0'	030	VALVE PIT	535.0'
041	VALVE PIT	537.4'	040	DOCK WALL	537.4'
041	DOCK WALL	537.4'	041	DOCK WALL	537.4'
042	DOCK WALL	537.4'	042	DOCK WALL	537.4'
043	DOCK WALL	537.4'	043	DOCK WALL	537.4'
044	DOCK WALL	537.4'	044	DOCK WALL	537.4'
045	DOCK WALL	535.0'	045	DOCK WALL	535.0'
046	DOCK WALL	535.0'	046	DOCK WALL	535.0'
047	DOCK WALL	535.0'	047	DOCK WALL	535.0'
048	DOCK WALL	535.0'	048	DOCK WALL	535.0'
049	DOCK WALL	535.0'	049	DOCK WALL	535.0'
050	DOCK WALL	535.0'	050	DOCK WALL	535.0'
051	DOCK WALL	535.0'	051	DOCK WALL	535.0'
052	DOCK WALL	535.0'	052	DOCK WALL	535.0'
053	DOCK WALL	535.0'	053	DOCK WALL	535.0'
054	DOCK WALL	535.0'	054	DOCK WALL	535.0'
055	DOCK WALL	535.0'	055	DOCK WALL	535.0'
056	DOCK WALL	535.0'	056	DOCK WALL	535.0'
057	DOCK WALL	535.0'	057	DOCK WALL	535.0'
058	DOCK WALL	535.0'	058	DOCK WALL	535.0'
059	DOCK WALL	535.0'	059	DOCK WALL	535.0'
060	DOCK WALL	535.0'	060	DOCK WALL	535.0'
061	DOCK WALL	535.0'	061	DOCK WALL	535.0'
062	DOCK WALL	535.0'	062	DOCK WALL	535.0'
063	DOCK WALL	535.0'	063	DOCK WALL	535.0'
064	DOCK WALL	535.0'	064	DOCK WALL	535.0'
065	DOCK WALL	535.0'	065	DOCK WALL	535.0'
066	DOCK WALL	535.0'	066	DOCK WALL	535.0'
067	DOCK WALL	535.0'	067	DOCK WALL	535.0'
068	DOCK WALL	535.0'	068	DOCK WALL	535.0'
069	DOCK WALL	535.0'	069	DOCK WALL	535.0'
070	DOCK WALL	535.0'	070	DOCK WALL	535.0'
071	DOCK WALL	535.0'	071	DOCK WALL	535.0'
072	DOCK WALL	535.0'	072	DOCK WALL	535.0'
073	DOCK WALL	535.0'	073	DOCK WALL	535.0'
074	DOCK WALL	535.0'	074	DOCK WALL	535.0'
075	DOCK WALL	535.0'	075	DOCK WALL	535.0'
076	DOCK WALL	535.0'	076	DOCK WALL	535.0'
077	DOCK WALL	535.0'	077	DOCK WALL	535.0'
078	DOCK WALL	535.0'	078	DOCK WALL	535.0'
079	DOCK WALL	535.0'	079	DOCK WALL	535.0'
080	DOCK WALL	535.0'	080	DOCK WALL	535.0'
081	DOCK WALL	535.0'	081	DOCK WALL	535.0'
082	DOCK WALL	535.0'	082	DOCK WALL	535.0'
083	DOCK WALL	535.0'	083	DOCK WALL	535.0'
084	DOCK WALL	535.0'	084	DOCK WALL	535.0'
085	DOCK WALL	535.0'	085	DOCK WALL	535.0'
086	DOCK WALL	535.0'	086	DOCK WALL	535.0'
087	DOCK WALL	535.0'	087	DOCK WALL	535.0'
088	DOCK WALL	535.0'	088	DOCK WALL	535.0'
089	DOCK WALL	535.0'	089	DOCK WALL	535.0'
090	DOCK WALL	535.0'	090	DOCK WALL	535.0'
091	DOCK WALL	535.0'	091	DOCK WALL	535.0'
092	DOCK WALL	535.0'	092	DOCK WALL	535.0'
093	DOCK WALL	535.0'	093	DOCK WALL	535.0'
094	DOCK WALL	535.0'	094	DOCK WALL	535.0'
095	DOCK WALL	535.0'	095	DOCK WALL	535.0'
096	DOCK WALL	535.0'	096	DOCK WALL	535.0'
097	DOCK WALL	535.0'	097	DOCK WALL	535.0'
098	DOCK WALL	535.0'	098	DOCK WALL	535.0'
099	DOCK WALL	535.0'	099	DOCK WALL	535.0'
100	DOCK WALL	535.0'	100	DOCK WALL	535.0'
101	DOCK WALL	535.0'	101	DOCK WALL	535.0'
102	DOCK WALL	535.0'	102	DOCK WALL	535.0'
103	DOCK WALL	535.0'	103	DOCK WALL	535.0'
104	DOCK WALL	535.0'	104	DOCK WALL	535.0'
105	DOCK WALL	535.0'	105	DOCK WALL	535.0'
106	DOCK WALL	535.0'	106	DOCK WALL	535.0'
107	DOCK WALL	535.0'	107	DOCK WALL	535.0'
108	DOCK WALL	535.0'	108	DOCK WALL	535.0'
109	DOCK WALL	535.0'	109	DOCK WALL	535.0'
110	DOCK WALL	535.0'	110	DOCK WALL	535.0'
111	DOCK WALL	535.0'	111	DOCK WALL	535.0'
112	DOCK WALL	535.0'	112	DOCK WALL	535.0'
113	DOCK WALL	535.0'	113	DOCK WALL	535.0'
114	DOCK WALL	535.0'	114	DOCK WALL	535.0'
115	DOCK WALL	535.0'	115	DOCK WALL	535.0'
116	DOCK WALL	535.0'	116	DOCK WALL	535.0'
117	DOCK WALL	535.0'	117	DOCK WALL	535.0'
118	DOCK WALL	535.0'	118	DOCK WALL	535.0'
119	DOCK WALL	535.0'	119	DOCK WALL	535.0'
120	DOCK WALL	535.0'	120	DOCK WALL	535.0'
121	DOCK WALL	535.0'	121	DOCK WALL	535.0'
122	DOCK WALL	535.0'	122	DOCK WALL	535.0'
123	DOCK WALL	535.0'	123	DOCK WALL	535.0'
124	DOCK WALL	535.0'	124	DOCK WALL	535.0'
125	DOCK WALL	535.0'	125	DOCK WALL	535.0'
126	DOCK WALL	535.0'	126	DOCK WALL	535.0'
127	DOCK WALL	535.0'	127	DOCK WALL	535.0'
128	DOCK WALL	535.0'	128	DOCK WALL	535.0'
129	DOCK WALL	535.0'	129	DOCK WALL	535.0'
130	DOCK WALL	535.0'	130	DOCK WALL	535.0'
131	DOCK WALL	535.0'	131	DOCK WALL	535.0'
132	DOCK WALL	535.0'	132	DOCK WALL	535.0'
133	DOCK WALL	535.0'	133	DOCK WALL	535.0'
134	DOCK WALL	535.0'	134	DOCK WALL	535.0'
135	DOCK WALL	535.0'	135	DOCK WALL	535.0'
136	DOCK WALL	535.0'	136	DOCK WALL	535.0'
137	DOCK WALL	535.0'	137	DOCK WALL	535.0'
138	DOCK WALL	535.0'	138	DOCK WALL	535.0'
139	DOCK WALL	535.0'	139	DOCK WALL	535.0'
140	DOCK WALL	535.0'	140	DOCK WALL	535.0'
141	DOCK WALL	535.0'	141	DOCK WALL	535.0'
142	DOCK WALL	535.0'	142	DOCK WALL	535.0'
143	DOCK WALL	535.0'	143	DOCK WALL	535.0'
144	DOCK WALL	535.0'	144	DOCK WALL	535.0'
145	DOCK WALL	535.0'	145	DOCK WALL	535.0'
146	DOCK WALL	535.0'	146	DOCK WALL	535.0'
147	DOCK WALL	535.0'	147	DOCK WALL	535.0'
148	DOCK WALL	535.0'	148	DOCK WALL	535.0'
149	DOCK WALL	535.0'	149	DOCK WALL	535.0'
150	DOCK WALL	535.0'	150	DOCK WALL	535.0'
151	DOCK WALL	535.0'	151	DOCK WALL	535.0'
152	DOCK WALL	535.0'	152	DOCK WALL	535.0'
153	DOCK WALL	535.0'	153	DOCK WALL	535.0'
154	DOCK WALL	535.0'	154	DOCK WALL	535.0'
155	DOCK WALL	535.0'	155	DOCK WALL	535.0'
156	DOCK WALL	535.0'	156	DOCK WALL	535.0'
157	DOCK WALL	535.0'	157	DOCK WALL	535.0'
158	DOCK WALL	535.0'	158	DOCK WALL	535.0'
159	DOCK WALL	535.0'	159	DOCK WALL	535.0'
160	DOCK WALL	535.0'	160	DOCK WALL	535.0'
161	DOCK WALL	535.0'	161	DOCK WALL	535.0'
162	DOCK WALL	535.0'	162	DOCK WALL	535.0'
163	DOCK WALL	535.0'	163	DOCK WALL	535.0'
164	DOCK WALL	535.0'	164	DOCK WALL	535.0'
165	DOCK WALL	535.0'	165	DOCK WALL	535.0'
166	DOCK WALL	535.0'	166	DOCK WALL	535.0'
167	DOCK WALL	535.0'	167	DOCK WALL	535.0'
168	DOCK WALL	535.0'	168	DOCK WALL	535.0'
169	DOCK WALL	535.0'	169	DOCK WALL	535.0'
170	DOCK WALL	535.0'	170	DOCK WALL	535.0'
171	DOCK WALL	535.0'	171	DOCK WALL	535.0'
172	DOCK WALL	535.0'	172	DOCK WALL	535.0'
173	DOCK WALL	535.0'	173	DOCK WALL	535.0'
174	DOCK WALL	535.0'	174	DOCK WALL	535.0'
175	DOCK WALL	535.0'	175	DOCK WALL	535.0'
176	DOCK WALL	535.0'	176	DOCK WALL	535.0'
177	DOCK WALL	535.0'	177	DOCK WALL	535.0'
178	DOCK WALL	535.0'	178	DOCK WALL	535.0'
179	DOCK WALL	535.0'	179	DOCK WALL	535.0'
180	DOCK WALL	535.0'	180	DOCK WALL	535.0'
181	DOCK WALL	535.0'	181	DOCK WALL	535.0'
182	DOCK WALL	535.0'	182	DOCK WALL	535.0'
183	DOCK WALL	535.0'	183	DOCK WALL	535.0'
184	DOCK WALL	535.0'	184	DOCK WALL	535.0'
185	DOCK WALL	535.0'	185	DOCK WALL	535.0'
186	DOCK WALL	535.0'	186	DOCK WALL	535.0'
187	DOCK WALL	535.0'	187	DOCK WALL	535.0'
188	DOCK WALL	535.0'	188	DOCK WALL	535.0'
189	DOCK WALL	535.0'	189	DOCK WALL	535.0'
190	DOCK WALL	535.0'	190	DOCK WALL	535.0'
191	DOCK WALL	535.0'	191	DOCK WALL	535.0'
192	DOCK WALL	535.0'	192	DOCK WALL	535.0'
193	DOCK WALL	535.0'	193	DOCK WALL	535.0'
194	DOCK WALL	535.0'	194	DOCK WALL	535.0'
195	DOCK WALL	535.0'	195	DOCK WALL	535.0'
196	DOCK WALL	535.0'	196	DOCK WALL	535.0'
197	DOCK WALL	535.0'	197	DOCK WALL	535.0'
198	DOCK WALL	535.0'	198	DOCK WALL	535.0'
199	DOCK WALL	535.0'	199	DOCK WALL	535.0'
200	DOCK WALL	535.0'	200	DOCK WALL	535.0'
201	DOCK WALL	535.0'	201	DOCK WALL	535.0'
202	DOCK WALL	535.0'	202	DOCK WALL	535.0'
203	DOCK WALL	535.0'	203	DOCK WALL	535.0'
204	DOCK WALL	535.0'	204	DOCK WALL	535.0'
205	DOCK WALL	535.0'	205	DOCK WALL	535.0'
206	DOCK WALL	535.0'	206	DOCK WALL	535.0'
207	DOCK WALL	535.0'	207	DOCK WALL	535.0'
208	DOCK WALL	535.0'	208	DOCK WALL	535.0'
209	DOCK WALL	535.0'	209	DOCK WALL	535.0'
210	DOCK WALL	535.0'	210	DOCK WALL	535.0'
211	DOCK WALL	535.0'	211	DOCK WALL	535.0'
212	DOCK WALL	535.0'	212	DOCK WALL	535.0'
213	DOCK WALL	535.0'	213	DOCK WALL	535.0'
214	DOCK WALL	535.0'	214	DOCK WALL	535.0'
215	DOCK WALL	535.0'	215	DOCK WALL	535.0'
216	DOCK WALL	535.0'	216	DOCK WALL	535.0'
217	DOCK WALL	535.0'	217	DOCK WALL	535.0'
218	DOCK WALL	535.0'	218	DOCK WALL	535.0'
219	DOCK WALL	535.0'	219	DOCK WALL	535.0'
220	DOCK WALL	535.0'	220	DOCK WALL	535.0'
221	DOCK WALL	535.0'	221	DOCK WALL	535.0'
222	DOCK WALL	535.0'	222	DOCK WALL	535.0'
223	DOCK WALL	535.0'	223	DOCK WALL	535.0'
224	DOCK WALL	535.0'	224	DOCK WALL	535.0'
225	DOCK WALL	535.0'	225	DOCK WALL	535.0'
226	DOCK WALL	535.0'	226	DOCK WALL	535.0'
227	DOCK WALL	535.0'	227	DOCK WALL	535.0'
228	DOCK WALL	535.0'	228	DOCK WALL	535.0'
229	DOCK WALL	535.0'	229	DOCK WALL	535.0'
230	DOCK WALL	535.0'	230	DOCK WALL	535.0'
231	DOCK WALL	535.0'	231	DOCK WALL	535.0'
232	DOCK WALL	535.0'	232	DOCK WALL	535.0'
233	DOCK WALL	535.0'	233	DOCK WALL	535.0'
234	DOCK WALL	535.0'	234	DOCK WALL	535.0'
235	DOCK WALL	535.0'	235	DOCK WALL	535.0'
236	DOCK WALL	535.0'	236	DOCK WALL	535.0'
237	DOCK WALL	535.0'	237	DOCK WALL	535.0'
238	DOCK WALL	535.0'	238	DOCK WALL	535.0'
239	DOCK WALL	535.0'	239	DOCK WALL	535.0'
240	DOCK WALL	535.0'	240	DOCK WALL	535.0'
241	DOCK WALL	535.0'	241	DOCK WALL	535.0'
242	DOCK WALL	535.0'	242	DOCK WALL	535.0'
243	DOCK WALL	535.0'	243	DOCK WALL	535.0'
244	DOCK WALL	535.0'	244	DOCK WALL	53