



# MISSISSIPPI POWER & LIGHT COMPANY

Helping Build Mississippi

P. O. BOX 1640, JACKSON, MISSISSIPPI 39205

April 19, 1982

NUCLEAR PRODUCTION DEPARTMENT

U.S. Nuclear Regulatory Commission  
Office of Nuclear Reactor Regulation  
Washington, D.C. 20555

Attention: Mr. Harold R. Denton, Director

Dear Mr. Denton:



SUBJECT: Grand Gulf Nuclear Station  
Units 1 and 2  
Docket Nos. 50-416 and 50-417  
File 0260/L-814.2  
SQRT - Additional Information  
Supporting Justification for  
Interim Operation  
Reference: AECM-82/128, dated  
April 5, 1982  
AECM-82/173

Mississippi Power & Light Company's (MP&L) letter of April 5, 1982, (AECM-82/128) provided MP&L's justification for interim operation for equipment not qualified to the SQRT criteria.

On April 13, 1982, the NRC Equipment Qualification Branch notified MP&L of their concerns in regard to MP&L's SQRT justification for interim operation. The Equipment Qualification Branch requested MP&L to provide additional information to support the justification of interim operation.

The purpose of this letter is to provide the additional information which has been requested by the Equipment Qualification Branch.

The following additional information is provided:

A. To Equipment Qualification Branch on April 20, 1982

1. Main Steam Isolation Valve
2. RHR Heat Exchanger
3. CRD Solenoid Valve C11-F009
4. Conductivity Cell
5. Air Operated Butterfly Valve (M-257.0/258.0)
6. Safety Relief Valve (M-141.1)

B. To Equipment Qualification Branch on April 21, 1982

1. HPCS Valve Actuator
2. HPCS Diesel Generator
3. Switches
4. Pressure Indicator

*Bool  
SIP Limited  
Dist  
Add: T.Y. Chang EQB*


8204220386 820419  
PDR ADOCK 05000416  
A PDR

...nber Middle South Utilities System

- C. Attachment No. 1  
Main Steam Isolation Valve
- D. Attachment No. 2  
RHR Heat Exchanger
- E. Attachment No. 3  
CRD Solenoid Valve (C11-F009)
- F. Attachment No. 4  
Conductivity Cell (E12-N025A, B)
- G. Attachment No. 5  
Air Operated Butterfly Valves (M-257.0/258.0)
- H. Attachment No. 6  
Safety Relief Valve (M-141.0)
- I. Attachment No. 7  
Refurbishment Schedule for HPCS Injection Valve (E22-F004)

If you have any questions or require further information, please contact this office.

Yours truly,



L. F. Dale  
Manager of Nuclear Services

RAB/SHH/JDR:lm

- Attachments:
1. Main Steam Isolation Valve
  2. RHR Heat Exchanger
  3. CRD Solenoid Valve (C11-F009)
  4. Conductivity Cell (E12-N025A, B)
  5. Air Operated Butterfly Valves (M-257.0/258.0)
  6. Safety Relief Valve (M-141.1)
  7. Refurbishment Schedule for HPCS Injection Valve (E22-F004)

cc: (See Next Page)



MISSISSIPPI POWER & LIGHT COMPANY

AECM-82/173

Page 3

cc: Mr. N. L. Stampley (w/o)  
Mr. G. B. Taylor (w/o)  
Mr. R. B. McGehee (w/o)  
Mr. T. B. Conner (w/o)

Mr. Richard C. DeYoung, Director (w/o)  
Office of Inspection & Enforcement  
U.S. Nuclear Regulatory Commission  
Washington, D.C. 20555

Mr. J. P. O'Reilly, Regional Administrator (w/a)  
Office of Inspection & Enforcement  
U.S. Nuclear Regulatory Commission  
Region II  
101 Marietta St., N.W., Suite 3100  
Atlanta, Georgia 30303

ATTACHMENT NO. 1

Main Steam Isolation Valve  
B21-F022/F028

GRAND GULF  
MAIN STEAM ISOLATION VALVES

MPL# B21-F022

MPL# B21-F028

ADDITIONAL INFORMATION SUPPORTING  
JUSTIFICATION FOR INTERIM OPERATION

PREPARED BY:

K. Kumar  
K. KUMAR 4/17/82

U. N. Sinha  
U. N. SINHA

APPROVED BY:

H. Ehsan 4/17/82  
H. EHSAN

E. O. Swain  
E. O. SWAIN

GENERAL ELECTRIC  
175 CURTNER AVENUE  
SAN JOSE, CALIFORNIA 95125

APRIL 17, 1982

## TABLE OF CONTENTS

	<u>Page No.</u>
1. Abstract	1
2. General Information	2
3. Dynamic Information	7
4. Tests and Analyses Supporting Operability of Grand Gulf Main Steam Isolation Valves	8
5. Conclusions and Justifications	9
6. Figure 1 - Response Spectrum	10
7. Appendix I - Physical Comparison of Grand Gulf and the Tested Upper Structure	11
8. Appendix II - Valve Assembly Drawings	12

## ABSTRACT

The following tests and analyses have been performed on the Grand Gulf Main Steam Isolation Valves Upper Structure, or similar Upper Structures:

- Grand Gulf 28" Main Steam Isolation Valve Upper Structure has been compared with a dynamically tested 26" main steam isolation valve Upper Structure and it has been concluded that Grand Gulf Upper Structure is similar to the tested Upper Structure.
- Required Response Spectra have been developed for Grand Gulf at the base of valve cover. These response spectra have been compared with the test response spectra for the tested similar valve upper structure. The TRS envelope the RRS with margin.
- Static Bend tests have been performed on the Grand Gulf Main Steam Isolation Valve which assure valve operability under expected loads.
- A special valve closure analysis demonstrates adequacy of structure during opening/closing of the valve.

It is therefore, concluded that the Grand Gulf Main Steam Isolation Valve Upper Structure is dynamically adequate to meet the expected loadings. Thus, use of this equipment during startup and operation of the Grand Gulf Station is justified until such time as the requalification is complete.

## GENERAL INFORMATION

### Main Steam Isolation Valves

#### General Description

The Main Steam Isolation Valve is of a quick closing design for high pressure steam service. It is a Wye pattern type valve complete with actuator and accessory equipment. The valve is actuated with an air cylinder operator (air-to-open, air-and/or spring-to-close). The valves are usually installed in a horizontal main steam line with two valves in series per main steam line, inboard valve located within the drywell and the outboard valve located outside the containment. The valve is designed for steam service. The 28" size has a capacity of 4,120,000# per hour with 06.6 psig maximum calculated pressure drop across the fully open valve. The base material is carbon steel, with a type 17-4PH stainless steel stem and a stellite guide bushing located in the cover. The body seating surface and guide ribs, the disc seating surfaces and the guide surface near the main seat and the cover back-seating surface are all faced with stellite. The body-to-bonnet joint is a bolted type construction with a totally enclosed spiral wound stainless steel, asbestos filled gasket. The bonnet joint is prepared for seal welding, but seal welding would be performed by others at the installation site if required. The stem seal stuffing box is equipped with two sets of packing. A lantern ring is located between the two sets of packing with a leakoff connection to the lantern ring in the form of a socket welded pipe nipple. The body is equipped with provision for a 2" schedule 160 drain nipple located in the inlet end of the valve body. The valve is equipped with position switches to indicate open, closed and 94 percent open positions.

#### Operational Requirements

NOTE: All part nos. referred to are from dwg. 13561-01-H, Sheet 1 unless otherwise noted.

The valve is to be capable of opening with a 200 psi differential pressure tending to hold the valve closed, utilizing a minimum of 90 psig min. air pressure in the cylinder actuator. To accomplish this requirement and keep the cylinder size within reasonable limits a cylinder balancing arrangement in the form of a cup whose upper end extends into the valve body bonnet bore is employed. The poppet is equipped with an internal pilot valve seat, and the end of the valve stem acts as the pilot valve poppet. When the valve stem lifts, the pressure in the balancing cylinder area decays, and thereby reduces the differential pressure acting over the main poppet area, thus reducing the operator force required to open the valve.

The valve is required to have an adjustable closing speed of three to ten seconds. This requirement is accomplished by a tandem air and hydraulic cylinder (part no. 37) and 1" flow control valve (part no. 6 sheet 4 of dwg. 13561-01-H) installed in the external manifold mounted on the hydraulic section of the tandem cylinder (part no. 37).

When closing the main steam isolation valve, the oil in the underside of the piston in the hydraulic cylinder must be displaced through the external manifold to the top side of the piston. The rate at which this oil displacement takes place is controlled by the adjustment of the 1" flow control valve (part no. 6 sheet 4 of dwg. 13561-01-H) which in turn controls the rate of valve closure.



### Operational Requirements (Continued)

The closing speed control is provided with a minimum flow position to prevent full closure of the flow through the hydraulic cylinder's external piping.

The range of closing speed adjustment (3 to 10 seconds) is accomplished with not less than two full revolutions of the adjustment spindle of the 1" flow control valve (part no. 6 sheet 4 of dwg. 13561-01-H).

Provisions are required to accommodate an increase in fluid pressure due to the increase of ambient temperature from that existing during filling and sealing of the hydraulic system to that existing during emergency conditions. This requirement is satisfied by using a small accumulator (part no. 8 sheet 4 dwg. 13561-01-H) on the hydraulic cylinder external manifold. The accumulator is precharged with nitrogen at 100 psig, and has a design pressure limit of 5000 psig.

The valve is to be capable of opening at the rate of one inch plus or minus one-half inch per second. The opening speed adjustment is accomplished by use of a 1/2" flow control valve (part no. 7 sheet 4 dwg. no. 13561-01-H).

The valve operator is provided with an exercising control feature for stroking the valve from the 100% open position to the 94% open position. This requirement is accomplished by installing a normally open 1 1/4" three-way valve (part no. 2 sheet 4 dwg. no. 13561-01-H) in the line between the connection to the underside of the air cylinder operator and the main four-way air control valve. When the exercising control is energized, the under side of the pneumatic cylinder is vented and the springs (part no. 15 & 16) will force the valve toward the closed position.

NOTE: The isolation valve is equipped with a position switch to indicate when the 94% open position has been reached. If the three-way exercising control is left in the energized position, the main steam isolation valve will go to the fully closed position.

The exercising speed is such that the valve shall be capable of stroking from 100% open to the fully closed position in 45 to 60 seconds. The exercising speed adjustment is accomplished by use of a 1/2" air metering valve (part no. 9 sheet 4 of dwg. no. 13561-01-H) installed in the exhaust port of the three-way exercising valve. The above time for full closing is not intended to imply that the valve is to be exercised to the fully closed position when the plant is in operation.

### Operational Description of the Pneumatic System Components (Dwg. 13561-01-H Sheet 4)

The air supply to the pneumatic operating cylinder is controlled by a 1 1/4" four-way pilot operated valve (part no. 1) which depending on its position, applies air pressure to either the top or bottom end of the air cylinder operator while alternately exhausting the opposite end of the cylinder. This 1 1/4" four-way pilot operated valve (part no. 1) in turn is controlled by a three-way normally energized 1/4" dual solenoid operated valve (part no. 4).

## Operational Description of the Pneumatic System Components (Continued)

To open the main steam isolation valve, either or both of the solenoids on the three-way main pilot control valve (part no. 4) are energized which feeds air pressure to the piston of the 1 1/4" four-way pilot operated valve (part no. 1) causing it to shift its position. The four-way pilot operated valve (part no. 1) then feeds air pressure to the underside of the air operating cylinder and at the same time exhausts air from the top end of the cylinder and the main steam isolation valve opens. Should either of the solenoids of the three-way main pilot control valve (part no. 4) be de-energized while the other is energized, the air pressure would be maintained in the piston of the 1 1/4" four-way pilot operated valve (part no. 1) and it would maintain its position, thus the main steam isolation valve would remain in the open position.

In the event of loss of system air supply, the air pressure in the piston of the 1 1/4" four-way pilot operated valve (part no. 1) would exhaust out through the three-way solenoid operated valve (part no. 4) to the air supply line. The 1 1/4" four-way pilot operated valve (part no. 1) would shift its position and exhaust the air pressure from the underside of the operating cylinder. The force generated by the closing spring will close the main steam isolation valve, (any air pressure contained in the air storage tank will assist the spring in closing the valve).

To close the main steam isolation valve, both solenoids on the three-way main pilot control valve (part no. 4) are de-energized which exhausts the air pressure from the piston to the 1 1/4" four-way pilot operated valve (part no. 1) causing it to shift its position. The 1 1/4" four-way pilot operated valve (part no. 1) then feeds air pressure to the top side of the air operating cylinder and at the same time exhausts the air from the bottom side of the operating cylinder and the main steam isolation valve closes. It should be noted that in the event no air pressure is available for closing, the closing springs will supply the force to close the main steam isolation valve.

A 1 1/4" normally open three-way pilot operated valve (part no. 2) is installed in the air line between the underside of the air operating cylinder and the main 1 1/4" four-way pilot operated valve (part no. 1). Its purpose is to accomplish the exercising feature.

This 1 1/4" three-way pilot operated exercising valve (part no. 2) in turn is controlled by a three-way normally de-energized solenoid operated valve (part no. 5).

To exercise the main steam isolation valve, the three-way solenoid operated valve (part no. 5) is energized which feeds air pressure to the piston of the 1 1/4" three-way pilot operated valve (part no. 2) causing it to shift its position. The air supply being fed from the main 1 1/4" four-way pilot operated valve (part no. 1) to the underside of the air cylinder is blocked and the air in the cylinder is exhausted to atmosphere through the 1 1/4" three-way pilot operated exercising valve (part no. 2). When the air pressure in the under-side of the air operating cylinder decays to a point where its force can no longer overcome the force generated by the closing springs, the

## Operational Description of the Pneumatic Systems Components (Continued)

isolation valve will start to close. A 1/2" metering valve (part no. 9) installed in the exhaust port of the 1 1/4" three-way pilot operating exercising valve (part no. 2) is used to adjust the rate of exercising speed. The exercising speed from 100 percent open to fully closed position, (14 inches of valve stroke), is 45 to 60 seconds. When the three-way solenoid operated valve (part no. 5) is de-energized, it exhausts the air pressure from the piston of the three-way pilot operated exercising valve (part no. 2) causing it to shift its position. The exhaust port is now blocked and the air from the main 1 1/4" four-way pilot operated valve (part no. 1) is fed to the underside of the air cylinder operator and the main steam isolation valve returns to its full open position.

A 1 1/4" two-way pilot operated valve (part no. 3) is installed in a tee in the air line between the underside of the air operating cylinder and the 1 1/4" normally open three-way pilot operated exercising valve (part no. 2). This 1 1/4" two-way pilot operated valve (part no. 3) serves as an additional closing valve in the air control system. The 1 1/4" two-way pilot operated valve (part no. 3) is controlled by the same dual solenoid operated three-way valve (part no. 4) that controls the main 1 1/4" four-way pilot operated valve (part no. 1). When the three-way dual solenoid operated valve (part no. 4) is energized to open the main steam isolation valve, air pressure is also fed to the piston of the 1 1/4" two-way pilot operated valve (part no. 3) which shifts its position. The valve closes, blocking the exhaust port and prevents the air pressure in the line to the underside of the air operating cylinder from exhausting to atmosphere.

When the dual solenoids of the main three-way pilot operated valve (part no. 4) are de-energized to close the main steam isolation valve, the air pressure is exhausted from the piston of the 1 1/4" two-way pilot operated valve (part no. 3) causing it to shift its position. The air in the underside of the air cylinder operator is then exhausted to atmosphere through the open 1 1/4" two-way pilot operated valve (part no. 3) as well as through the main 1 1/4" four-way pilot operated valve (part no. 1).

### Hydraulic Speed Control System

The purpose of the hydraulic speed control system is to control the opening and closing speed of the pneumatic cylinder operator on the main steam isolation valve. The sub-plate mounted hydraulic speed control system is connected to the speed control cylinder at the top and bottom ports. By the use of adjustable flow control valves in the sub-plate assembly, the amount of flow from one side of the hydraulic cylinder piston to the other can be regulated. This regulated flow controls the operator cylinder opening and closing speed.

## Operational Description of the Hydraulic System Components

### Part Nos. From Dwg. 13561-01-H Sheet 4

A 1" closing flow control valve (part no. 6) (adjustable and pressure compensated), is sized so that the time to fully stroke the pneumatic operator is less than 3 seconds when only spring force is applied in the closing direction.

## Additional Description of the Hydraulic System Components (Continued)

It is also capable of adjusting the closing time to 10 or more seconds when both air pressure and spring loads are applied in closing direction. The range of closing speed adjustment, (3 to 10 seconds) is accomplished with not less than two full revolutions of the adjustment spindle. The closing flow control valve (part no. 6) is equipped with a minimum flow position to prevent its full closure. The minimum flow position is sized so that the time of full pneumatic operator stroke is greater than 10 seconds in order to achieve the adjustable closure range of 3 to 10 seconds. The adjustable spindle of the closing flow control valve (part no. 6) is provided with a positive locking device.

A 1/2" opening flow control valve (part no. 7), (adjustable and pressure compensated), is sized so that the time to fully stroke the pneumatic actuator (retract piston rod from fully extended position), is at a rate of 1 inch, plus or minus 1/2 inch per second. The opening flow control valve (part no. 7) is equipped with a minimum flow position to prevent its full closure. The minimum flow position is sized so that the time of full operator stroke is less than 1/2" per second in order to achieve the adjustable opening range of 1/2" to 1 1/2" per second. The adjustable spindle of the opening flow control valve (part no. 7) is provided with a positive locking device.

The accumulator is included in the hydraulic system in order to accommodate an increase in fluid pressure due to the increase of ambient temperature from that existing during filling and sealing of the hydraulic system to that existing during emergency ambient conditions.



## DYNAMIC INFORMATION

The required response spectra (RRS) used in this evaluation for the Grand Gulf MSIV Upper Structure are based on the following observations:

- a) The main steam isolation valve (MSIV) is mounted on the piping which is supported by the main steam guide and the head fitting. The main steam guide, in turn, is mounted on the platform near the drywell wall, and the head fitting is mounted in the shield building wall.
- b) The support system and valve body are stiff so that the loads (response spectra) input to the MSIV upper structure can be considered the same as obtained from the building model.

Based on the above observations, it can be shown that in the vicinity of the main steam isolation valves (MSIV), the controlling dynamic loads as determined by the piping dynamic analysis are the combination of safe shutdown earthquake (SSE) plus the safety relief valve blowdown structural load (SRV). Grand Gulf unique enveloped (SSE + SRV) response spectra, hereafter called the required response spectra (RRS), have been developed to compare with the test response spectra (TRS) used on the tests of similar valve upper structures. Based on the comparison of RRS and TRS, the following conclusions can be made:

1. Grand Gulf Project Unique Response Spectra show 2g ZPA loading on the MSIV, whereas the test response spectra used for testing the 24 inch and 26 inch MSIV upper structures used ZPA of 5.5g.
2. Test response spectra used for testing the MSIV upper structures were broad band in comparison with narrow band real input motion to Grand Gulf MSIV. So, it can be seen that TRS provide conservatively higher load than the required load (RRS).
3. The natural frequency of the Grand Gulf Upper Structure is about 13 Hz. The natural frequencies of the tested MSIV Upper Structures were between 10 Hz and 14 Hz. Since the tests were performed from 2 Hz to 40 Hz, excitation of the upper structure at the natural frequency is assured.
4. Comparison of different components of Grand Gulf MSIV Upper Structure and the tested MSIV Upper Structure have been made (Appendix I). The comparison shows that the Grand Gulf MSIV Upper Structure is physically similar to the tested upper structure and generally made out of better material.

Based on the above information, it can be concluded that the TRS used for testing the 24 inch and 26 inch MSIV upper structures envelop the Grand Gulf Unique Required Response Spectra (RRS) (See Fig. 1) and that comparison of these spectra is justified based on similarity of the valve upper structures.

TESTS AND ANALYSES SUPPORTING OPERABILITY  
OF GRAND GULF MAIN STEAM ISOLATION VALVES

Operability of the Grand Gulf Main Steam Isolation Valve is based on the following information:

1. A Static Bend Test was performed on the Grand Gulf Valve which demonstrated that the valve would close within the required time period of  $4.0 \pm 1$  seconds. The valve was exercised using air and springs, while the valve was being subjected to a static equivalent seismic load. In this test, the stem moved freely without any scratches or binding when a load of 18,550 lbs (approximately 5.6 g) was applied at the spring top plate. On the Grand Gulf valve, the maximum expected dynamic load is approximately 6.6 g's applied at the center of gravity of the upper structure. Calculating moments, the static bend test imposed a moment of approximately 280 in-lbs at the valve body/bonnet centerline. The comparable maximum expected dynamic moment is approximately 263 in-lbs. The static bend test therefore bounds the expected dynamic moment.
2. A special "Closure Analysis" was performed on the Grand Gulf 28" Main Steam Isolation Valves. This analysis was done to assure that the air pressure in the pneumatic cylinder and the springs are more than adequate to open/close the valve under the Grand Gulf specified flow conditions.
3. Upper Structures of two main steam isolation valves similar to the Grand Gulf Main Steam Isolation Valve have been previously tested. The Test Response Spectra of the tested Upper Structures envelope the Required Response Spectra of the Grand Gulf Upper Structure (See Figure 1). Operability of the Upper Structure was demonstrated during and after the seismic test.



## CONCLUSIONS AND JUSTIFICATIONS

Grand Gulf Main Steam Isolation Valves were supplied by Atwood and Morrill Valve Co. using Sheffer/Hiller SA-A039 pneumatic and hydraulic components. These valves remain in open position all the time during normal plant operation and are checked periodically for their closure capability. The Upper Structure of a similar 26" valve was tested and operated successfully during and after the test under simulated seismic loadings. The Test Response Spectra for the similar 26" valve Upper Structure envelopes the Grand Gulf Required Response Spectra. Grand Gulf Main Steam Isolation Valve Upper Structure is very similar to the tested Upper Structure (Refer to Appendix-I for detailed comparison). The Required Response Spectra for Grand Gulf is enveloped by the Test Response Spectra with substantial Margin. (See Figure 1 ). Based on the similarity of the tested Upper Structure and the Grand Gulf Upper Structure it is anticipated that the Grand Gulf Upper Structure would respond in a similar manner when dynamically tested. It is expected that the relative stress level in the Yoke Rods would be lower due to the use of superior yoke rod material and size which provides additional assurance of Upper Structure's seismic capability. Furthermore, successful "Static Bend Test" and "Closure Analyses" have been performed.

It is, therefore, concluded that the Grand Gulf Upper Structure is dynamically adequate to meet the expected loadings. Thus startup and operation of Grand Gulf Station is justified until such time as requalification is completed.

RESPONSE SPECTRUM LONGT. IN PHASE 11/15/77

POST TEST

# OF PULSES AT 0 DB = 3

G

DAMPING = 2.0% 1/3 OCTAVE




Figure 1 Response Spectrum

Appendix I

PHYSICAL COMPARISON OF GRAND GULF AND THE TESTED UPPER STRUCTURE

APPENDIX I - PHYSICAL COMPARISON OF GRAND GULF  
AND THE TESTED UPPER STRUCTURE  
(Actuator Only)

Item Description	Grand Gulf Upper Structure	24" - Tested Upper Structure Report No. NEDE-24122-2
Pneumatic/Hydraulic Component Vendor	Sheffer/Hiller	Sheffer/Hiller
Component Model No.	SA-A039	SA-A012
Dual Solenoid Supplier/Model No.	ASCO/HTX832320	ASCO/HTX832320
Single Solenoid Supplier/Model No.	ASCO/HTX8320A20	ASCO/HTX8320A20
2-Way Valve Supplier/Model No.	Norgren B0004A	Norgren/B-1026B-00-A1 Similar to B0004A
3-Way Valve Supplier/Model No.	Norgren/C0007A	Norgren/C-1037B-00A1 Similar to C0007A
4-Way Valve Supplier/Model No.	Norgren/F013A	Norgren F2227B-00-A1 Similar to F013A
O-Rings	Viton	Viton
Pneumatic Cylinder Height	24 1/8"	27 1/2"
Pneumatic Cylinder Bore Dia.	20"	20"
Piston Diameter	3"	3"
Stroke Length	15"	18"
Operating Pressure	90 - 125 PSI	90 - 125 PSI
Hydraulic Cylinder Bore Dia.	5"	5"
Piston Diameter	3"	3"
Hydraulic Fluid	GE Silicone-SF-1147	Shell IruS - 902

APPENDIX I - PHYSICAL COMPARISON OF GRAND GULF  
AND THE TESTED UPPER STRUCTURE  
(Yoke Components Only)

[illegible]


Appendix II

VALVE ASSEMBLY DRAWINGS





1. *medicinal plants and shrubs* (in German) 1987, 1988, 1989, 1990, 1991, 1992, 1993, 1994, 1995, 1996, 1997, 1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665,



THIS INFORMATION IS BEING USED TO CONTACT YOU  
 YOUR ORDER IS: 205AF 715  
 AND IS BEING USED TO CONTACT YOU  
 IF YOU ARE NOT INTERESTED  
 135-01-01 8-02

For more information, contact the author at 617-353-2600 ext. 200, fax at 617-353-2601, or e-mail at [john@johnmccormack.com](mailto:john@johnmccormack.com).  
 John McCormack is a senior advisor to the U.S. Environmental Protection Agency, where he has worked for 25 years. He is also a senior advisor to the U.S. Environmental Protection Agency, where he has worked for 25 years. He is also a senior advisor to the U.S. Environmental Protection Agency, where he has worked for 25 years.

$$\frac{d}{dt} \left( \frac{\partial L}{\partial \dot{x}} \right) = \frac{\partial L}{\partial x}$$

Section 8-2

H. CULUM

[illegible]

1561-00-4 2-11

44-10-1958





ATTACHMENT NO. 2

RHR Heat Exchangers  
E12-B001/R002

## JUSTIFICATION FOR INTERIM OPERATION

NAME: RHR Heat Exchanger

MPL: E12-B001/B002

### SAFETY FUNCTION:

To remove decay heat from the reactor.

### FAILURE MODES:

Fail Open	_____
Fail Closed	_____
Loss of Power	_____
Loss of Air	_____
Loss of Pressure Integrity	_____
Loss of Structural Integrity	_____
Distortion of Mounting	<u>  X  </u>

### FAILURE EFFECT:

#### A. Effect on Primary Use

Support structure could yield, under excessive seismic loads, causing heat exchanger nozzles to pick up additional load. If nozzles pick up additional load, they too might yield. However, pressure integrity and heat removal capability would be unimpaired.

#### B. Secondary Effect

None

### DISCUSSION AND CONCLUSION:

An analysis of the RHR heat exchanger shows that the fundamental frequency is greater than 6 hertz. A static analysis of the heat exchanger, using a static coefficient greater than 1.5 times the peak of the faulted response spectra for all frequencies greater than 6 hertz, shows that stresses imposed on the heat exchanger are all less than allowable. Therefore, interim operation with the Grand Gulf RHR heat exchanger does not pose a safety hazard.



GENERAL ELECTRIC CO.  
Nuclear Energy Business Group  
ENGINEERING CALCULATION SHEET

NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT \_\_\_\_\_ BY Jim Mohr SHEET 1 OF 11  
4/16/82

GRAND GULF RHR HEAT EXCHANGER

INTERIM OPERATION


JUSTIFICATION

- I. GRAND GULF RHR HEAT EXCHANGER DESIGN
- II. ESTIMATED HEAT EXCHANGER AND SUPPORT  
SYSTEM NATURAL FREQUENCY.
  - 1.) HAND CALCULATED VALUE
  - 2.) COMPARISON WITH OTHER PLANTS
- III. STATIC COEFFICIENT ANALYSIS
  - 1.) ACCELERATION VALUE FROM RESPONSE  
SPECTRA CURVES.
  - 2.) DISCUSSION OF STATIC COEFFICIENT
  - 3.) DESCRIPTION OF ANALYSIS METHOD
  - 4.) STRESS SUMMARY TABLE.
- IV. CONCLUSION.

## ENGINEERING CALCULATION SHEET

NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT \_\_\_\_\_ BY \_\_\_\_\_ SHEET 2 OF 11

### I Grand Gulf Rtr Heat Exchanger Design:



GENERAL ELECTRIC CO.  
Nuclear Energy Business Group  
ENGINEERING CALCULATION SHEET


NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT GRAND GULF RHR HX BY \_\_\_\_\_ SHEET 3 OF 11

## II. ESTIMATION OF HEAT EXCHANGER AND SUPPORT SYSTEM NATURAL FREQUENCY.

### 1.) HAND CALCULATED VALUE:

THE GRAND GULF RHR HEAT EXCHANGER HORIZONTAL NATURAL FREQUENCY WAS DETERMINED USING A SIMPLIFIED BEAM AND SUPPORT STIFFNESS MODEL FOR USE IN THE ORIGINAL SEISMIC CALCULATION. SEVERAL SIMPLIFYING ASSUMPTIONS WERE USED:

- A) MASS DISTRIBUTION WAS ASSUMED UNIFORM OVER THE HEAT EXCHANGER LENGTH
- B) SUPPORT STRUCTURE WAS REPRESENTED BY SINGLE SPRINGS AT THE UPPER AND LOWER SUPPORT LOCATIONS.
- C) BEAM MODEL IS SHOWN BELOW:



- D) MASS AND SECTION PROPERTIES WERE CALCULATED FROM THE HEAT EXCHANGER SITE DIMENSIONS.
- E) MINIMUM REQUIRED SUPPORT STIFFNESS VALUES ( $K_{top}$ ,  $K_{bottom}$ ) WERE SPECIFIED ON THE EQUIPMENT INTERFACE CONTROL DRAWING (ICD) TO THE PLANT AE.

RESULTS OF THE FREQUENCY ANALYSIS:

$$f_{n_H} = 18 \text{ Hz (HORIZONTAL)}$$

$$f_{n_V} > 30 \text{ Hz (VERTICAL)}$$

**GENERAL ELECTRIC CO.**  
Nuclear Energy Business Group  
**ENGINEERING CALCULATION SHEET**

NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT \_\_\_\_\_ BY \_\_\_\_\_ SHEET 4 OF 11

2.) COMPARISON WITH OTHER PLANTS

SINCE THE PREVIOUS CALCULATIONAL METHOD FOR SYSTEM FREQUENCY INCLUDED SEVERAL SIMPLIFYING ASSUMPTIONS, IT IS PRUDENT TO COMPARE THE RESULTS OF FINITE ELEMENT MODE AND FREQUENCY ANALYSES FOR OTHER PLANTS, USING SIMILAR HEAT EXCHANGERS TO THE GRAND GULF RESULTS.

GRAND GULF RHR HEAT EXCHANGER:

HAND CALCULATED FREQUENCY = 18 HZ  
SHELL ID = 60"  
SHELL THICKNESS = 1"  
ELEVATION = 370" (TOP SUPPORT) 156" (BOTTOM SUPPORT)  
SUPPORT STIFFNESS REQUIREMENT ON ICD =  $9.3 \times 10^6$  LB/IN

SUSQUEHANNA RHR HEAT EXCHANGER

HAND CALCULATED FREQUENCY = 15 HZ  
SHELL ID = 63"  
SHELL THICKNESS = 1"  
ELEVATION = 347" (TOP SUPPORT) 184" (BOTTOM SUPPORT)  
SUPPORT STIFFNESS REQUIREMENT ON ICD =  $10 \times 10^6$  LB/IN  
SAP4 FINITE ELEMENT ANALYSIS RESULT = 7.5 HZ

KUO SHENG RHR HEAT EXCHANGER

HAND CALCULATED FREQUENCY = 18 HZ  
SHELL ID = 52"  
SHELL THICKNESS = .9"  
ELEVATION = 306" (TOP SUPPORT) 131" (BOTTOM SUPPORT)  
SUPPORT STIFFNESS REQUIREMENT ON ICD =  $4.5 \times 10^6$  LB/IN  
SAP4 FINITE ELEMENT ANALYSIS RESULTS = 12 HZ

BASED ON THE ABOVE COMPARISON BETWEEN HAND CALCULATED FREQUENCY, AND SAP4 FINITE ELEMENT FREQUENCY, FOR SIMILAR HEAT EXCHANGERS,

**GENERAL ELECTRIC CO.**  
Nuclear Energy Business Group  
**ENGINEERING CALCULATION SHEET**

NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT \_\_\_\_\_ BY \_\_\_\_\_ SHEET 5 OF 11

IT IS EXPECTED THAT THE GRAND GULF RHR ITS HORIZONTAL FREQUENCY WOULD BE GREATER THAN 7.5 HZ.

ALSO, FREQUENCIES DETERMINED FROM FINITE ELEMENT ANALYSES, ON RHR HEAT EXCHANGERS FROM EIGHT REPRESENTATIVE BWR PLANTS HAVE ALL BEEN GREATER THAN THE 7.5 HZ VALUE FOR SUSQUEHANNA. THEREFORE, SINCE THE GRAND GULF HEAT EXCHANGER IS EXPECTED TO BE GREATER THAN 7.5 HZ, USE OF 7.5 HZ IS CONSERVATIVE.

**III. STATIC COEFFICIENT ANALYSES -**

- 1.) THE PLANT SPECIFIC ~~SEE~~ RESPONSE SPECTRA CURVES FOR THE RHR HEAT EXCHANGER (ATTACHED) HAVE A MAXIMUM ACCELERATION VALUE IN THE HORIZONTAL DIRECTIONS OF 0.65g AND IN THE VERTICAL DIRECTION OF 0.194g, USING 3% DAMPING. (FREQUENCIES AS LOW AS 6 HZ WILL STILL RESULT IN  $S_H \leq 0.65g$ )
- 2.) THE USE OF A STATIC COEFFICIENT MULTIPLIER FOR INCREASING SPECTRA ACCELERATIONS IS ACCEPTABLE AS AN ALTERNATE TO DYNAMIC ANALYSIS. AN ACCEPTED VALUE FOR SIMPLE BEAM AND FRAME STRUCTURES IS 1.5. DEPENDING ON THE COMPLEXITY OF THE EQUIPMENT THE FACTOR CAN BE SLIGHTLY HIGHER THAN 1.5 BUT IT NEVER EXCEEDS 2.0 FOR STRUCTURES SIMILAR TO THE GRAND GULF RHR HEAT EXCHANGER. THEREFORE, FOR CONSERVATISM A 2.0 FACTOR CAN BE USED.

THE STATIC COEFFICIENT ACCELERATION IS:

$$S_H = (2.0)(.65) = 1.3g$$

$$S_V = (2.0)(.194) = .39g$$

GENERAL ELECTRIC CO.  
Nuclear Energy Business Group  
ENGINEERING CALCULATION SHEET

NUMBER \_\_\_\_\_ DATE \_\_\_\_\_  
SUBJECT \_\_\_\_\_ BY \_\_\_\_\_ SHEET 6 OF 11

3.) DESCRIPTION OF ANALYSIS METHOD

A STATIC COEFFICIENT ANALYSIS OF THE RHR HEAT EXCHANGER USING  $S_H = 1.5g$  AND  $S_V = 1.75g$  (INCLUDING STATIC WEIGHT) WAS PERFORMED USING STANDARD ENGINEERING METHODS. THE ACCELERATION VALUE WAS APPLIED TO THE DISTRIBUTED WEIGHT, FORCES AND MOMENTS CALCULATED, NORMAL PRESSURE AND WEIGHT WAS INCLUDED, STRESSES CALCULATED, AND STRESSES WERE COMPARED TO ASME CODE ALLOWABLES. STATIC ACCELERATION WAS APPLIED SIMULTANEOUSLY IN THREE DIRECTIONS. NOZZLE LOADS WERE ASSUMED EQUAL TO MAXIMUM VALUES ON ICD.

4.) STRESS SUMMARY TABLE.

ATTACHED IS A COMPARISON OF CALCULATED TO ALLOWABLE STRESSES.

IV CONCLUSION

BASED ON THE CONSERVATIVE APPROXIMATION OF FREQUENCY, THE CONSERVATIVE 2.0 STATIC FACTOR, THE MARGIN BETWEEN THE 1.3g AND 1.5g ACCELERATIONS, AND THE MARGIN BETWEEN CALCULATED AND ALLOWABLE STRESSES, THE EQUIPMENT IS CAPABLE OF WITHSTANDING GRAND GULF SEISMIC LOADS. IN CONJUNCTION WITH ALL PLANT-NORMAL LOADS.



# Bechtel Power Corporation

Engineers—Constructors

15740 Shady Grove Road  
Gaithersburg, Maryland 20760  
301-948-2700



July 30, 1980

Mr. A. R. Smith, Project Manager  
General Electric Company (M/C-392)  
175 Curtner Avenue  
San Jose, California 95114

Grand Gulf 182 \_\_\_\_\_  
Date Received E-11-80  
Assigned To N/A  
Answered N/A

Dear Mr. Smith:

Nuclear QA Is Not Applicable  
Middle South Energy, Inc.  
Grand Gulf Nuclear Station  
Bechtel Job No. 9645  
File: 0265/6410/M-001.0  
Seismic Response Spectra  
GEB-80/0216

In response to the request of your Mr. C. Morris for the seismic response spectra applicable to the RHR heat exchangers location, enclosed are the following spectra for floor elevation 119'-0" of the auxiliary building:

N213  
N214  
E213  
E214  
V213  
V214

Very truly yours,

*for R. S. Trice*  
A. Zaccaria  
Project Engineer

RCG:jgt

Enclosures: Seismic Response Spectra (6 sheets)

cc: J. P. McGaughey, Jr., w/1  
L. F. Dale, 2/2  
C. K. McCoy, w/1  
T. H. Cloninger, w/1  
T. E. Reaves, w/1  
Dr. D. C. Gibbs, w/1  
W. A. Shanks, w/1 (GE Res. Site Mngr.)  
D. M. Lake, w/1  
H. H. Weber, w/1  
R. L. Scott, w/1

RECEIVED


AUG 7 1980

A. R. SMITH

reproduced, copied, loaned, exhibited, or used except in the limit and private use permitted by any written consent given by the lender

Calc. No. C-1400472 Rev. 0



MID SOUTH RESPONSE SPECTRUM, SSE, LATERAL ANAL., AUX. BLDG., M-5  
ACCELERATION SPECTRUM POINT = 2 DAMPING = 0.030  
0.1 0.2 0.4 0.6 1.0 2.0 4.0 6.0 10. 20. 40. 60. 100.




CG-10			AUX. BLDG. FLUOR SPECTRUM SSE, N-S, EL. 119'-0", 3L GRAND GULF NUCLEAR STATION UNITS 1&2	REVISIONS			BY <i>TH</i> CHK <i>1/3/73</i>	SHEET 5 OF 22
				ISSUED FOR USE				
				No.	DATE			
				6/11/73				

This document and the design it covers are the property of BECHTEL. They are merely loaned and on the borrower's express agreement that the reproduced, copied, loaned, exhibited, or used except in the borrower's private use permitted by any written consent given by the borrower.



CG-39


 	No. <span style="border: 1px solid black; padding: 2px;">6/11/73</span>		DATE		ISSUED FOR USE		REVISIONS		BY <span style="border: 1px solid black; padding: 2px;">H</span>	CHK <span style="border: 1px solid black; padding: 2px;">T/H</span>	APPR <span style="border: 1px solid black; padding: 2px;">P/K</span>
	AUX. BLDG. FLOOR SPECTRUM SSE, E-W, EL. 119'-0", 3%				JOB No. <span style="border: 1px solid black; padding: 2px;">9645</span>		E 214 RI		SHEET <span style="border: 1px solid black; padding: 2px;">3</span> OF <span style="border: 1px solid black; padding: 2px;">22</span>		
	GRAND GULF NUCLEAR STATION UNITS 1&2										



This document and the design it covers are the property of BECHTEL. They are merely loaned and on the borrower's express agreement that the borrower will not reproduce, copied, loaned, exhibited, or used except in the manner and private use permitted by any written consent given by the lender.

CG-

 	No. <u>6/11/73</u>		DATE <u>ISSUED FOR USE</u>		REVISIONS		BY <u>JK</u>	CHK <u>TJH</u>	APP <u>EA</u>	
	AUX. BLDG. FLOOR SPECTRUM SSE, VERT., EL. 119'-0", 3%						JOB No. <u>9645</u>		<u>V212</u>	
	GRAND GULF NUCLEAR STATION UNITS 1&2						SHEET <u>B</u>		OF <u>32</u>	



GENERAL ELECTRIC CO.  
Nuclear Energy Business Operations  
ENGINEERING CALCULATION SHEET

11 OF 11

NUMBER GRAND GULF 182 - RHR HEAT EXCHANGERS DATE 4/7/82  
SUBJECT STRESSES IN SHELL AND SUPPORT BY A.R. SCHICK SHEET 1 OF 1

REFERENCE :

(a) GE DWG. 762E 987, Rev. 6 - "GRAND GULF 182 RHR HEAT EXCHANGER INTERFACE CONTROL DWG".

THE CRITICAL STRESSES IN THE SHELLS AND SUPPORTS OF THE GRAND GULF 182 RHR HEAT EXCHANGERS FOR THE SUPPORT LOADS \* TABULATED IN NOTE 4 OF REF. (a) ARE LISTED BELOW:

STRESS LOCATION	UPSET		FAULTED	
	STRESS, psi	ALLOWABLE STRESS, psi	STRESS, psi	ALLOWABLE STRESS, psi
LONGITUDINAL STRESS IN THE SHELL JUST BELOW THE LOWER SUPPORTS	13,019	17,500	14,173	35,000
<u>UPPER SUPPORTS</u>				
MAX. STRESS IN SHELL-BITLAPD ANALYSIS	17,666	26,250	18,028	42,000
PAD-TO-SHELL ATTACHMENT WELD:				
SHEAR STRESS	1,070	8,575	1,451	17,150
BENDING STRESS	850	16,078	1,152	32,156
<u>LOWER SUPPORTS</u>				
MAX. STRESS IN SHELL-BITLAPD ANALYSIS	21,675	26,250	22,810	42,000
PAD-TO-SHELL ATTACHMENT WELD:				
SHEAR STRESS	4,099	8,575	5,367	17,150
BENDING STRESS	4,110	16,078	5,268	32,156
<u>SHELL FLANGE: BOLT STRESS</u>	27,899	37,500	28,906	50,000
HUB STRESS	38,279	39,375	39,769	52,500
FLANGE STRESS	24,637	26,250	25,594	35,000
<u>LOWER SUPPORT ANCHOR BOLTS:</u>				
SHEAR STRESS	—	—	4,985	10,000
TENSION STRESS	—	—	4,537	10,000

\* THE LOADS OF NOTE 4 WERE CALCULATED ON THE BASIS OF THE FOLLOWING SEISMIC

COEFFICIENTS :	DIRECTION	UPSET	FAULTED
	HORIZONTAL	1.0g	1.5g
	VERTICAL	0.5g	0.75g

ATTACHMENT NO. 3

CRD Solenoid Valve  
C11-F009

The valve name plate data identified the Grand Gulf Unit 1 CRD Solenoid Valve as an Automatic Switch Company (ASCO) Model 8323A22 dual solenoid valve (See attached Communication Record dated 3/31/82 between D. Bost and C. Nakayama). The ASCO Model 8323A22 was tested as part of the Zimmer/LaSalle seismic requalification program conducted by NUTECH. The tests included resonance searches from 1 to 100 Hz, biaxial random vibration seismic simulation, and fragility. The specimen functioned satisfactorily throughout testing. Peak loads were 8.6g horizontal and 8.1g vertical during seismic simulation and 12g during fragility testing with a 50 Hz sine wave input.

The following information is included in Attachment No. 1:

- A) Telecon between NUTECH/MP&L
- B) ASCO Bulletin 8323
- C) Test Report of ASCO Solenoid Valve 8323 for W. H. Zimmer & LaSalle County Nuclear Power Plant



# NUTECH COMMUNICATION RECORD

Persons Involved: <u>D. Post</u>	Date/Time: <u>3/31/82 9:43AM</u>
Company: <u>MP&amp;L</u>	Recorded By: <u>CEN</u>
<input checked="" type="checkbox"/> Telecon/Ph. No. <u>(601) 437-5260 x2873</u>	Copy To: <u>GC, PD.</u>
<input type="checkbox"/> Meeting/Location	Route To:
File:	Page <u>1</u> of <u>1</u>

SUBJECT: JIO Information

Denny relayed the following information on the ASCO model solenoid valve:

Catalog No.: HT8323A22

Ser # : 626402

Orifice: 3/32

pipe : 1/4

electrical: 9 watts

50hz

110V.

Air : Air  
110.

I requested ~~pre-arrange~~ a teleconference between his preprops engineers on the B-21 sys and P Donnelly today. Denny will be tracking them down, and will call us back in 1-2 hrs to arrange the conference.

He will be sending us the acceptance letter for Dynamic Testing & Analyses + JIO work end of this week; we will need to follow up with a work order.

Denny will be expecting us to Federal Express our write ups today.

## General Description

Bulletin 8323 covers a compact 3 way valve that incorporates two independent solenoids providing individual control for two internal orifices. This valve offers the flexibility of two 2 way valves in a common body, as well as 3 way valving operation.

These 3 way direct acting solenoid valves have forged brass bodies and two solenoids suitable for any combination of A-C and D-C voltages.

## Applications

This unique valve design is adaptable to many flow control requirements. For example, they may be used for inching or positioning of cylinders and diaphragms, diverting flow into one or two outlets, selection of one or two pressures into a common outlet, controlling air motors having an open exhaust, vending applications, gas samplings, etc.

The normally closed and normally open constructions are equipped with two operating solenoids for redundant control. These valve designs are intended for those applications where unauthorized valve shift would be critical. Valve shifting

without proper signal can be the result of normal power supply failures or possible coil failure. The valves are constructed so that uninterrupted control is maintained as long as either solenoid is energized. Separate electrical control circuits can be utilized to insure control in the event of normal electrical supply failure.

## Specifications

Operation (Refer to Flow Diagrams on following page):

Note: These typical flow diagrams cover valves with normally closed solenoids (open when energized, closed when de-energized). Normally open construction is available for either, or both solenoids in 1/4" size — consult factory when required.


Pipe Sizes: 1/8" and 1/4" N.P.T.

Valve Body: Forged Brass (stainless steel available).

Valve Seat: Buna "N."

Solenoid Construction: Internal parts in contact with fluid are made of 300 and 400 Series Stainless Steel.

Solenoid Enclosures: Two types available: (a) General Purpose (NEMA 1).



(b) Explosion-Proof and Watertight (NEMA 4, 7 and 9).

Electrical: Standard Voltages:

24, 120, 240, 480 volts, A-C, 60 Hz (or 50 Hz in 110 volt multiples).

6, 12, 24, 120, 240 volts, D-C.


Other voltages available when required.

Coil: Continuous Duty Molded Class A or F, as listed.

Temperature: To 200°F., as listed.

Installation: Mountable in any position without affecting operation.

Approvals: For UL listings, CSA and FM approvals refer to page 2.



## SPECIFICATIONS

### FORGED BRASS BODY, SOFT SEATING FOR GENERAL PURPOSE SERVICE

Pipe Size (Inch.)	Orifice Size (Inch.)	Maximum Operating Pressure Differential (P.S.I.)						Safe Body Working Pressure (P.S.I.)	Max. ① A-C Fluid Temp. °F.	Cv Flow Factor	General Purpose Solenoid Enclosure			Explosion-Proof — Watertight Solenoid Enclosure		Watt Rating		Class of Coil Insulation	Approx. ② Shipping Weight (Lbs.)	
		Air-Gas		Water		Light Oil					Catalog Number	Optional Feature Ref.	Constr. Ref.	Catalog Number	Optional Feature Ref.	A-C	D-C		A	B
		A-C	D-C	A-C	D-C	A-C	D-C													
UNIVERSAL OPERATION (Refer to Flow Diagrams) Pressure at Any Orifice. Both Solenoids Normally Closed.																				
1/8"	1/16"	100	65	100	65	100	65	500	180	.09	83231	II	1	83232	VI	9	9.7	F①	2	2 1/2
	1/32"	50	30	50	30	50	30	500	180	.15	83233	I	1	83234	V	6	9.7	A	2	2 1/2
	3/64"	30	20	30	20	30	20	500	180	.21	83235	II	1	83236	VI	9	9.7	F③	2	2 1/2
1/4"	1/8"	100	65	100	65	100	65	500	180	.09	83237	II	1	83238	VI	9	9.7	F①	2	2 1/2
	1/16"	125	125	125	125	125	125	500	200	.09	832313	III	2	832314	VII	15.4	16.8	A	4	4 1/2
	1/32"	40	40	40	40	40	40	500	180	.15	83239	I	1	832310	V	6	9.7	A	2	2 1/2
	3/64"	110	65	110	65	110	65	500	200	.15	832315	IV	2	832316	VIII	20	16.8	F①	4	4 1/2
	1/16"	30	20	30	20	30	20	500	180	.31	832311	II	1	832312	VI	9	9.7	F②	2	2 1/2
	3/64"	40	20	40	20	40	20	500	200	.38	832317	IV	2	832318	VIII	20	16.8	F②	4	4 1/2

### FORGED BRASS BODY, SOFT SEATING FOR AIR, GASES, WATER AND LIGHT OIL

Pipe Size (Inch.)	Orifice Size (Inch.)	Maximum Operating Pressure Differential (P.S.I.)		Safe Body Work. Press. (P.S.I.)	Max. ① A-C Fluid Temp. °F.	Cv Flow Factor	General Purpose Solenoid Enclosure				Explosion-Proof — Watertight Solenoid Enclosure				Watt Rating			Approx. ② Shipping Weight (Lbs.)		
							A-C - A-C Solenoids		A-C - D-C Solenoids		A-C - A-C Solenoids		A-C - D-C Solenoids		Solenoid #1	Solenoid #2				
		A-C	D-C				Catalog Number	Opt. Feature Ref.	Catalog Number	Opt. Feature Ref.	Constr. Ref.	Catalog Number	Opt. Feature Ref.	Catalog Number	Opt. Feature Ref.	A-C	A-C	D-C	A	B
		NORMALLY CLOSED OPERATION																		
1/4	1/8	125	125	500	180	.09	832319	IX	832335	IX	3	832320	XI	832336	XI	6	15.4	16.8	3	3 1/2
	1/16	110	100	500	180	.15	832321	IX	832337	IX	3	832322	XI	832338	XI	9	15.4	16.8	3	3 1/2
	1/32	40	40	500	180	.31	832323	IX	832339	IX	3	832324	XI	832340	XI	6	15.4	16.8	3	3 1/2
	3/64	125	①	300	180	.5	832325	X	832341	X	4	832326	XII	832342	XII	15.4	15.4	①	7	7 1/2
NORMALLY OPEN OPERATION																				
1/4	1/8	125	125	500	180	.09	832327	IX	832343	IX	3	832328	XI	832344	XI	6	15.4	16.8	3	3 1/2
	1/16	110	100	500	180	.15	832329	IX	832345	IX	3	832330	XI	832346	XI	9	15.4	16.8	3	3 1/2
	1/32	40	40	500	180	.31	832331	IX	832347	IX	3	832332	XI	832348	XI	6	15.4	16.8	3	3 1/2
	3/64	125	①	300	180	.5	832333	X	832349	X	4	832334	XII	832350	XII	15.4	15.4	①	7	7 1/2

Notes: ① Maximum Fluid Temperature on D-C is 120°F. for 9.7 watt and 180°F. for 16.8 watt rated valves.  
② D-C Coils supplied with Class A insulation.

③ Column A — Shipping weight for valves with General Purpose Solenoid Enclosure.  
④ Column B — Shipping weight for valves with Explosion-Proof — Watertight Solenoid Enclosure.  
⑤ For D-C construction — consult factory.

UNCONTROLLED COPY  
FOR INFORMATION ONLY

VIBRATION TEST OF  
ASCO SOLENOID VALVE 8323

for

WM. H. ZIMMER AND LASALLE COUNTY  
NUCLEAR POWER STATIONS

for

NUTECH

6835 Via Del Oro  
San Jose, California 95119

by

Southwest Research Institute  
6220 Culebra Road  
San Antonio, Texas 78284

NUTECH Contract MK2-0205.01  
SwRI Project No. 02-6056-007

October 16, 1981

Ernest R. Garcia  
Ernest R. Garcia  
Staff Technician

Daniel D. Kaga  
for H. Norman Abramson  
Vice President, Engineering Sciences

Daniel D. Kaga  
Daniel D. Kaga  
Manager, Structural Dynamics and Acoustics



## TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION . . . . .	1
1.1 Purpose of Test . . . . .	1
1.2 Reference . . . . .	1
2.0 SPECIFICATIONS AND STANDARDS . . . . .	1
3.0 DESCRIPTION OF TEST SPECIMEN . . . . .	1
4.0 TEST FACILITY . . . . .	2
4.1 Location . . . . .	2
4.2 General Purposes . . . . .	2
4.3 Seismic Table Description . . . . .	2
4.4 Associated Instrumentation . . . . .	2
4.5 Electrodynamic Table Description . . . . .	3
5.0 TEST EQUIPMENT IDENTIFICATION . . . . .	3
6.0 CALIBRATION . . . . .	3
7.0 TEST METHODS . . . . .	5
7.1 Specimen Mounting . . . . .	5
7.2 Instrumentation . . . . .	5
7.3 Exploratory Testing . . . . .	8
7.4 Proof Testing . . . . .	8
7.5 Fragility Testing . . . . .	10
7.6 Functional Tests and Monitoring . . . . .	11
8.0 RESULTS AND CONCLUSIONS . . . . .	11
9.0 PHOTOGRAPHS . . . . .	15
10.0 EXPLORATORY TEST DATA . . . . .	23
11.0 PROOF TEST DATA . . . . .	27
12.0 TEST SPECIMEN DATA . . . . .	81
13.0 ANALOG TAPE LOG . . . . .	85
14.0 SwRI LABORATORY DATA LOG . . . . .	89

## TEST REPORT

### 1.0 INTRODUCTION

#### 1.1 Purpose of Test

This test has been conducted to determine the dynamic qualification of a solenoid valve which is used to supply instrument air to activate or deactivate the Control Rod Drive Scram Discharge Volume drain and vent valves in the Wm. H. Zimmer and/or the LaSalle County Nuclear Power Plants. The valve was mounted to simulate in-service conditions and operated in typical sequences while subject to changes of state.

#### 1.2 Reference

The tests described herein are based on previous information resulting from the following reference:

- SwRI Proposal 02-1470, "Seismic and LOCA Dynamic Tests for Zimmer SQRT Re-evaluation/Requalification," December 7, 1979.

### 2.0 SPECIFICATIONS AND STANDARDS

- 1) Nutech Test Specification, "Vibration Test of Asco Solenoid Valve 8323 for Wm. H. Zimmer and LaSalle County Nuclear Power Stations," MK2-02-112, Rev. 0, File No. 135.2401.0227.
- 2) IEEE Standard 344-1975, "Guide for Seismic Qualification of Class 1 Electric Equipment for Nuclear Power Generating Stations,"
- 3) SwRI Nuclear Quality Assurance Program Manual, (NQAPM), Rev. 2, November 4, 1980.
- 4) SwRI Division 02 Nuclear Projects Operating Procedure XII-EE-101-2, Calibration of Mechanical Sciences Dynamics Test Equipment, January 15, 1980.
- 5) SwRI Division 02 Nuclear Projects Operating Procedure XI-EE-101-1, Seismic Test of Electrical and Mechanical Components, June 7, 1978.

### 3.0 DESCRIPTION OF TEST SPECIMEN

The device is an ASCO 8323A22 (60 Hz, 120 Vac) 3-way solenoid air pilot valve. The test specimen is a representative nuclear power plant Class 1E device which is identical to those installed in various locations



that open-loop operation is necessary in this range. Table responses are monitored by accelerometers whose outputs can be analyzed according to several standard parameters. Acceleration or velocity response spectrum can be computed and plotted within seconds by a Spectral Dynamics SD321 Shock Spectrum Analyzer, or by a DEC PDP 11/70 computer system. Power spectral density can be computed by a Nicolet Scientific 444A FFT Analyzer or with a Zomic multichannel FFT processor. All time histories can be recorded on analog or digital tape, on oscillographs, or monitored on oscilloscopes. Large volumes of data are usually recorded first on analog tape and then digitized for processing through a digital system which includes a DEC PDP 11/70 computer as its central processor.

#### 4.5 Electrodynamic Table Description

Part of the fragility tests were conducted with an electrodynamic shaker facility in order to achieve high acceleration levels. This facility contains an Unholtz-Dickie 1600 lb sine vector electrodynamic shaker which is powered by a 5 KVA amplifier. Vertical excitation is achieved by attachment of the specimen fixture directly to the shaker armature. Horizontal excitation is achieved by support of the specimen and fixture on a slip table whose plate is attached to the shaker armature.

#### 5.0 TEST EQUIPMENT IDENTIFICATION

The equipment used for simulation of the dynamic environment, acquisition, and processing of dynamic data is given in Table 5.0-1.

#### 6.0 CALIBRATION

- Instrumentation calibration was performed in accordance with Engineering Sciences Division Nuclear Projects Operating Procedure XII-EE-101-2, Calibration of Mechanical Sciences Dynamics Test Equipment.
- All accelerometers were calibrated using a reference standard Kistler 808K/561T which is traceable to the National Bureau of Standards.
- The Digital X-Y Plotter (Item 30) is calibrated with extreme set points which respond to signals from the Nicolet 444A FFT Analyzer.
- The Nicolet 444A (Item 31) was calibrated according to manufacturer's specifications.
- The Hewlett-Packard Tape Recorder (Item 32) was used solely as a signal source and was not calibrated on an absolute basis.



at Wm. H. Zimmer and LaSalle County Nuclear Power Stations. It is used to supply instrument air to activate or deactivate the Control Rod Drive Scram Discharge Volume drain and vent valves.

#### 4.0 TEST FACILITY

##### 4.1 Location

Southwest Research Institute  
Department of Engineering Mechanics  
6220 Culebra Road  
San Antonio, Texas 78284

##### 4.2 General Purposes

This facility has the capability of realistic simulation of an earthquake dynamic environment as well as all accepted standard approximations of such an environment. It has been designed principally for qualification testing of typical components to be used in nuclear and conventional power generation stations. It is also particularly suited to the study of structural scale model responses to seismic excitation. It can further be used as a general purpose shaker facility within its range of operation, and therefore can simulate nuclear plant operating transients.

##### 4.3 Seismic Table Description

A 6 by 6 foot mounting surface can be excited with simultaneous vertical and horizontal motion that is arbitrary and independent along each axis. Extenders are utilized for mounting somewhat larger specimens, when necessary. Maximum table payload capacity is 6,000 pounds dead weight. Drive mechanisms are servo-controlled electrohydraulic and have the following capabilities:

	<u>Horizontal</u>	<u>Vertical</u>
Frequency Range	0 - 1000 Hz	0 - 1000 Hz
Force Capacity	10,000 lb	20,000 lb
Maximum Stroke	8.0 in.	7.0 in.
Maximum Velocity	90 in/sec	22 in/sec
Maximum Acceleration*	10 g	10 g

##### 4.4 Associated Instrumentation

Excitation signals are provided typically by function generators or actual seismic signals recorded on analog instrumentation tape. Table displacement is accurately controlled at low to medium frequencies by automatic feedback to respond to an arbitrary voltage signal. Deterioration in control is experienced at higher frequencies such

---

\* At zero payload

TABLE 5.0-1 TEST EQUIPMENT

NO	ITEM	MAKE	MODEL	SERIAL	REMARKS
1	TONE GENERATOR	MICRODOT	F220A	3058	FUNCTION GENERATOR
2	SWEEP OSCILLATOR	SPECTRAL DYNAM	SD104A-5	1119	3 DECADE SWEEP
3	SWEEP OSCILLATOR	SPECTRAL DYNAM	SD104A-5	1856	3 DECADE SWEEP
4	SERVO MONITOR	SPECTRAL DYNAM	SD105A	557	5-10K HZ
5	SERVO MONITOR	SPECTRAL DYNAM	SD105C-1	935	1-5K HZ
6	FILTER	SKL	308A	368	VARIABLE FREQ.
7	POWER AMPLIFIER	TEAM	1528	102	PILOT VALVE DRIVER
8	ACCELEROMETER	ENDEVCO	2221D	JC 18	1-5000 HZ
9	ACCELEROMETER	ENDEVCO	2221D	XB-75	1-5000 HZ
10	ACCELEROMETER	ENTRAN	EGC-500DS-20	30H8IR1212	20G
11	AMPLIFIER	SWR.		2	BRIDGE 10 CHANNEL
12	DYNAMIC ANALYZER	SPECTRAL DYNAM	SD120/122L	86/259	2 CHANNEL
13	X-Y RECORDER	HEWLETT-PACKAR	7005B	1429	ANALOG
14	OP. AMP. MANIFOL	ANALOG DEVICES	194	136	ANALOG OPNS.
15	OP. AMP. MANIFOL	ANALOG DIVICES	194	12171	ANALOG OPNS.
16	ACCELEROMETER	BELL & HOWELL	4-202-0001	19742	HORIZ. TABLE
17	ACCELEROMETER	BELL & HOWELL	4-202-0001	22529	VERT. TABLE
18	CONTROLLER	TEAM	1522		HORIZ. TABLE
19	CONTROLLER	SWRI		2	VERT. TABLE
20	OSCILLOSCOPE	TEKTRONIX	5111	3118209	STORAGE
21	SCOPE PLUG-IN	TEKTRONIX	5A14N	8053025	4-CHANNEL
22	SCOPE PLUG-IN	TEKTRONIX	5A14N	8053045	4-CHANNEL
23	SCOPE PLUG-IN	TEKTRONIX	5B12N	8065791	DUAL TIME BASE
24	COUNTER	HEWLETT-PACKAR	5512A	450-01511	PERIOD/FREQ.
25	TAPE RECORDER	AMPEX	PR 2230	9170879	14-CHANNEL
26	DIGITAL MULTIMET	WESTON	4442	1294	BATTERY POWER
27	DIGITAL MULTIMET	HEWLETT-PACKAR	3466A	1716A01910	4 1/2 DIGIT
28	DIGITAL SERVO DI	TEAM	1564	102	USE W/ TEAM 1522
29	ACCELEROMETER/CA	KISTLER	808K/561T	769/416	NBS TRACEABLE

In addition, the following equipment was also used.

30	X-Y PLOTTER	TEKTRONIX	4662	3043979	DIGITAL PLOTTER
31	SPECTRUM ANALZ	NICOLET	444A	8948425	FFT COMPUTER
32	TAPE RECORDER	H/P	3964A	1925A01062	4-CHANNEL
33	DIGITAL COMPUTER	DEC PDP 11/70			SIGNAL SYNTHESIS
34	A-D SYSTEM	CAMAC			DATA PROCESSING
35	COMPUTER	TEKTRONIX	4006-1	3036557	DIGITAL DISPLAY
36	EM SHAKER	UNHOLTZ-DICKIE	56	203	VIBRATION TABLE
37	AMPLIFIER	ENDEVCO	2721A	BJ94	CHARGE
38	AMPLIFIER	ENDEVCO	2721A	BJ98	CHARGE
39	PRESS XDUCER	VIATRAN	218-15	133170	RANGE 0-500 psi
40	PRESS XDUCER	VALIDYNE	DP7	20398	RANGE 0-500 psi

- Both pressure transducers were calibrated to 1.0V/100 psi by means of internal calibration resistors.
- The digital synthesis system (Items 33-35) were used solely for shaping of table input signals, and no calibration was required for this process.

## 7.0 TEST METHODS

### 7.1 Specimen Mounting

The specimen was mounted in accordance with Figure 7-1. The valve was clamped to unistruts which were then mounted on a bookend. The clamps were designed to hold the 1/2" copper tubing 6" on either side of the valve. There was also a clamp holding the upper conduit 6" from the valve. This configuration was used on the hydraulic vibration table as shown in Figures 9-1 and 9-2. The fragility tests were re-run on the EM shaker. A smaller bookend was used during this test and the clamps were located 3" on either side of the valve. Details of this arrangement are shown in Figures 9-5 and 9-6.

Identification of excitation axes is as follows:

<u>Axes</u>	<u>Orientation</u>
XZ	Front to back/Vertical
YZ	Side to side/Vertical

### 7.2 Instrumentation

One accelerometer was used to monitor motions on the specimen only during the resonance searches. Location of this accelerometer is shown on Figure 9-3. Orientation of the accelerometer axes was parallel to the excitation.

Accelerometers for measuring table excitation were located on the bookend. For the X-Z excitation, the horizontal accelerometer was on the back side of the bookend face while the vertical was mounted on the side face of the bookend. For the Y-Z excitation, both accelerometers were on the side face of the bookend. (See Figures 9-2 and 9-4.).

The functional test setup was as shown in Figure 7-2. A pressure of 100 psi was applied to the common point of the valve during all tests that required pressure. Pressure transducers were mounted at the common (C) and the normally closed (N/C) points and were monitored on an oscillograph along with the two table accelerometers and ac input power to the solenoid. A water pan and a 1000 ml graduated cylinder were used (as shown in Figure 7-2) for valve seat leakage detection.




FIGURE 7-1. TEST SPECIMEN MOUNTING AND  
ACCELEROMETER LOCATION




FIGURE 7-2. FUNCTIONAL TEST SETUP USED DURING ALL SOLENOID VALVE TESTING

### 7.3 Exploratory Testing

Exploratory testing began with a sine sweep in the Z-axis. The frequency range was 1-100 Hz with a 0.5 octave/minute sweep rate and 0.1 g peak drive. The response accelerometer was mounted on the side of solenoid "A" coincident with the table axis. Table control accelerometers were mounted on the bookend during all tests.

The table vertical axis was locked down prior to running the horizontal exploratory tests to preclude any possible rocking mode coupling with the table mechanism. The parameters for the two horizontal axes tests are the same as for the vertical axis.

### 7.4 Proof Testing

Biaxial random vibration tests with flat excitation in 1-50 Hz, and of 30-second duration were conducted for each of the two required orientations. A given peak g level was required to be met or exceeded for each test run. The series of tests consisted of four (4) Upset runs in the X-Z orientation, four (4) Upset runs in the Y-Z orientation, three (3) Emergency runs in the Y-Z orientation, and one (1) Emergency run in the X-Z orientation. Excess runs were necessary for those runs where the input RMS value was not properly adjusted so that the test peak value was greater than the required peak g-level. Upset condition runs in each orientation included one (1) run with the specimen de-energized, one (1) run with the specimen energized, and one (1) run where the specimen changed state. Emergency condition runs in each orientation included a specimen change of state in every case. (See Section 11.0 for PSD and Peak information.)

Drive signals for each run were formed by a digital computer synthesis process which is described by the diagram in Figure 7-3. Initially, the seismic table transfer function data with the free table were acquired for each of the horizontal and vertical axes during the preliminary tests. These data are used along with the prescribed level to synthesize an initial drive signal for each axis. This synthesis process is accomplished within the computer by operating on 34 bands of narrow band random data, each of 1/6 octave bandwidth. The amplitude of each band is modified according to the required level and the table transfer function in that band. The final result is summed together and a proportional analog time history is formed for each axis independently on respective channels of an analog tape recorder. These signals are then used to drive the seismic simulator. The corresponding table accelerations are monitored and fed back to the computer to produce a second iteration as necessary. The response level of the table signals are computed and compared with the required level to determine whether further adjustments in any of the individual 34 frequency bands are required.






FIGURE 7-3. UPSET AND EMERGENCY SHAKER TABLE DRIVE

Table motions were monitored by independent horizontal and vertical accelerometers. Their output was recorded directly on an analog tape recorder and also on an oscilloscope for immediate visual display. During the preliminary test runs described above, it was found that high acceleration and frequency levels tended to cause some nonlinear rattling in the table, so that peak to RMS ratios were higher than that for normal random acceleration signals. Therefore, to make the test more conservative it was decided to filter the data by low pass below 65 Hz during its playback. Consequently, the peak value which occurred in the 1-50 Hz range was used as the basis for the test. Later, both unfiltered data as recorded on the tape recorder, and filtered data were compared. For example, peak levels for each of the filtered and unfiltered runs are shown in Tables 7-0.2 and 7-0.3, respectively. Note that the value for run number UPSYZ1A was 1.7 percent below minimum level inadvertently due to the procedure for monitoring the tests. For a given test run the value was monitored visually on the oscilloscope. Later, the test values were developed from time histories recorded on the oscillograph. The slight undertest for the one run was not noticed until the data were processed later. Since this represented a filtered peak value, no consequence was attributed to this result.

#### 7.5 Fragility Testing

Since there were no resonances below 50 Hz, the only requirement for the fragility testing was to slowly increase the table input level with a sine wave at 50 Hz and observe whether or not a valve leak would develop.

Fragility testing was begun with the specimen mounted in the X-axis. The starting level was at 2.0 g and increased to a level of 7.4 g at which point bubbles were observed due to some air leak in the valve. Pressure on the valve at this time and for all tests was at 100 psi.

The fixture was rotated to the Y orientation and fragility test at 50 Hz run, again starting from 2.0 g peak. This time the level of input to the table was raised to a maximum of 10 g peak and no leakage was detected.

Anchors at the four corners of the shaker table were removed to run the Z-axis fragility test. The table amplitude could not be raised above \* 5.0 g peak in this orientation due to a table malfunction at this time.

The solenoid valve was then removed from the hydraulically driven table, mounted on a smaller bookend and set on the EM shaker table. This approach was taken in order to preclude a delay while repair of the seismic table was effected. In this setup the clamps were set 3 inches

from the valve. This was necessary to allow mounting on the smaller book-end. The different mounting distance was considered acceptable since no resonance was detected below 50 Hz with the previously used, wider separation. Fragility testing at 50 Hz sine wave in the Z-axis was raised to a maximum of 12 g peak with no leaks detected.

The solenoid valve was then rotated 90° to the X-axis and the g level increased to 10 g's and then to 12 g's at which point minor bubbling was noted. This test was again repeated with no bubbles noted.

The EM shaker was rotated 90° to tie the slip table for horizontal motion. The solenoid valve with fixture was mounted in the X-axis. The fragility test was then run in this manner up to 10 g's and dwelled for 30 seconds with no bubbles noted. Oscillograph records are given in Section 12.0.

#### 7.6 Functional Tests and Monitoring

Prior to conduct of any dynamic tests, all functional tests were performed. Readout from table accelerometers, inlet and outlet pressure transducers and solenoid ac power were monitored and recorded on an oscillograph during proof testing only. Identification of the respective channels for each monitoring point is given in Table 7.0-1. Functional tests were also performed after each series of tests and at the end of all dynamic tests.

#### 8.0 RESULTS AND CONCLUSIONS

Results from the resonance searches are given in the form of transfer functions in Section 10.0. It can be seen that only one resonance occurred near 85 Hz for excitation along the X-axis (front to rear).

For proof tests, the results appear as tape recorded unfiltered time histories, which were further processed into oscillograph time histories and power spectral densities (PSD's). These data are given in Section 11.0. Power spectral densities were computed for the first run in each orientation series. PSD for filtered data is given in Figures 11-1 thru 11-8, while corresponding PSD's for unfiltered data are given in Figures 11-9 thru 11-16. Peak values associated with these data are given in Tables 7.0-2 and 7.0-3, respectively. Time histories for these data are given in Figures 11-20 thru 11-52. Data for each test run consists of 1) filtered acceleration time histories, 2) unfiltered acceleration time histories, and 3) a set of uncalibrated unfiltered time histories with output for monitoring the instrument functions. The latter time history signals were included on the monitoring output in order to show time coherence. Calibrations for all oscillograph channels are given in Figures 11-17 thru 11-19.

TABLE 7.0-1 IDENTIFICATION OF MONITOR CIRCUITS ON  
OSCILLOGRAPH RECORDS

<u>OSCILLOGRAPH CHANNEL</u>	<u>FUNCTION MONITORED</u>
1	Horizontal Table Accelerometer
2	Vertical Table Accelerometer
3	Inlet Valve Pressure
4	Outlet Valve Pressure
5	Solenoid AC Power

TABLE 7.0-2 PEAK LEVELS FILTERED AT 65 HZ, LOW PASS 65 HZ

<u>TEST NO.</u>	<u>HORIZONTAL PEAK</u>	<u>VERTICAL PEAK</u>
UPSXZ1A	6.2 g	6.0 g
UPSXZ2	6.0 g	6.1 g
UPSXZ3	6.1 g	6.2 g
UPSYZ1	5.0 g	6.2 g
UPSYZ1A	5.9 g	7.2 g
UPSYZ2	6.0 g	7.3 g
UPSYZ3	6.0 g	6.9 g
EMSYZ1	6.3 g	7.2 g
EMSYZ2	6.5 g	7.5 g
EMSYZ3	7.4 g	8.1 g
EMSXZ1	8.6 g	8.1 g

TABLE 7.0-3 PEAK LEVELS OF UNFILTERED TIME HISTORIES

<u>TEST NO.</u>	<u>HORIZONTAL PEAK</u>	<u>VERTICAL PEAK</u>
UPSXZ1A	8.9 g	8.1 g
UPSXZ2	8.3 g	7.8 g
UPSXZ3	8.5 g	8.1 g
UPSYZ1	5.0 g	6.8 g
UPSYZ1A	5.9 g	7.9 g
UPSYZ2	6.0 g	8.1 g
UPSYZ3	6.0 g	7.9 g
EMSYZ1	6.9 g	9.8 g
EMSYZ2	6.9 g	9.3 g
EMSYZ3	8.8 g	11.9 g
EMSXZ1	11.4 g	10.8 g

For the functional outputs, the solenoid valve trace was included starting with Run UPSXZ3. There was an intermittent connection on the power switch for this run. This was corrected by the following run. Finally, Run UPSYZ1 was not completely covered on the oscillograph. Inadvertently the oscillograph recorder was not started on time for this run. However, the data on magnetic tape is complete.

A review of the fragility data shows that for repeat of the front to rear (X-axis) excitation on the EM shaker a higher fragility level was achieved than on the seismic simulator. A further study of the data revealed the following explanation. For the initial fragility run on the seismic simulator, the table accelerometers (see Figure 9-4) were used to measure the input fragility level. For the repeated test runs on the electromagnetic shaker, the fragility level was measured on a response accelerometer mounted directly on the valve. It appeared that the valve mounting on the EM shaker was stiffer than the previous mounting on the seismic simulator. However, since the resonance search was conducted on the seismic simulator mounting and revealed no resonance below 90 Hz, it was concluded that the valve mounting must have become loose during the initial fragility runs, and produced erroneous data. Fragility values taken from the tests on the EM shaker are considered valid.

A thorough visual inspection was performed on the solenoid valve after completion of dynamic tests. No apparent physical damage was detected. The complete system was found to function normally before, during, and after these tests. It is our conclusion that the ASCO valve identified in Section 3.0 did pass the requirements of this test.

THIS PAGE INTENTIONALLY LEFT BLANK.



SECTION 9.0

PHOTOGRAPHS

THIS PAGE INTENTIONALLY LEFT BLANK.




FIGURE 9-1. SOLENOID VALVE MOUNTED ON SWRI BIAXIAL TABLE  
FOR X-Z RANDOM TESTS




FIGURE 9-2. SOLENOID VALVE MOUNTED ON SWRI BIAXIAL TABLE  
FOR Y-Z RANDOM TESTS

THIS PAGE INTENTIONALLY LEFT BLANK.




FIGURE 9-3. ACCELEROMETER LOCATION FOR X, Y & Z-AXES, RESONANCE SEARCH ON SOLENOID VALVE. ACCELEROMETER CIRCLED.




FIGURE 9-4. LOCATION OF INPUT MOTION ACCELEROMETERS MOUNTED ON THE BOOKEND. ACCELEROMETERS CIRCLED.

THIS PAGE INTENTIONALLY LEFT BLANK.






FIGURE 9-5. MOUNTING METHOD USED TO RUN SOLENOID VALVE FRAGILITY TESTS ON EM SHAKER FOR Z-AXIS




FIGURE 9-6. MOUNTING METHOD USED TO RUN SOLENOID VALVE FRAGILITY TESTS ON EM SHAKER FOR X-AXIS

THIS PAGE INTENTIONALLY LEFT BLANK.

## SECTION 10.0

## EXPLORATORY TEST DATA




FIGURE 10-1. RESONANCE SEARCH, X-AXIS, ACCELEROMETER ON SOLENOID "A",  
INPUT 0.1 G PEAK, SWEEP 0.5 OCTAVE/MINUTE




FIGURE 10-2. RESONANCE SEARCH, Y-AXIS, ACCELEROMETER ON SOLENOID "A",  
INPUT 0.1 G PEAK, SWEEP 0.5 OCTAVE/MINUTE






FIGURE 10-3. RESONANCE SEARCH, Z-AXIS, ACCELEROMETER ON SOLENOID "A",  
INPUT 0.1 G PEAK, SWEEP 0.5 OCTAVE/MINUTE




SECTION 11.0

PROOF TEST DATA

Figure 11-1

 $Q \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.311 g

 $S = 34 \text{ sec.}$ 

HORIZONTAL POWER SPECTRUM


AH - RUN UPXZ1A

Figure 11-2

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.436 g

S = 34 sec.




VERTICAL POWER SPECTRUM

AV - RUN UPXZ1A

Figure 11-3

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.226 g

 $S = 34 \text{ sec.}$ 

HORIZONTAL POWER SPECTRUM


AH - RUN UPYZIA

Figure 11-4

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.601 g

S = 34 sec.



VERTICAL POWER SPECTRUM


AV - RUN UPYZ1A

Figure 11-5

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.656 g

S = 34 sec.



HORIZONTAL POWER SPECTRUM


AH - RUN EMSYZ3



Figure 11-6

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.825 g

 $S = 34 \text{ sec.}$ 

VERTICAL POWER SPECTRUM


AV - RUN EMSYZ3

Figure 11-7

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.906 g

S = 34 sec.




HORIZONTAL POWER SPECTRUM

AH - RUN EMSXZ1

Figure 11-8

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.671 g

 $S = 34 \text{ sec.}$ 


VERTICAL POWER SPECTRUM

AV - RUN EMSXZ1

Figure 11-9

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.344 g

 $S = 34 \text{ sec.}$ 

HORIZONTAL POWER SPECTRUM


AH - RUN UPXZ1A

Figure 11-10

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.403 g

S = 34 sec.




VERTICAL POWER SPECTRUM

AV - RUN UPXZ1A

Figure 11-11

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.193 g

 $S = 34 \text{ sec.}$ 

HORIZONTAL POWER SPECTRUM

AH - RUN UPYZ1A




Figure 11-12

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.553 g

S = 34 sec.



VERTICAL POWER SPECTRUM

AV - RUN UPYZ1A


Figure 11-13

$$0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$$

$$\text{RMS} = 1.605 \text{ g}$$

$$B_e = 0.25 \text{ Hz}$$

$$S = 34 \text{ sec.}$$




HORIZONTAL POWER SPECTRUM

AH - RUN EMSYZ3

Figure 11-14

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.825 g

 $S = 34 \text{ sec.}$ 

VERTICAL POWER SPECTRUM

AV - RUN EMSYZ3


Figure 11-15

$$0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$$

$$\text{RMS} = 1.935 \text{ g}$$

$$B_e = 0.25 \text{ Hz}$$

$$S = 34 \text{ sec.}$$




HORIZONTAL POWER SPECTRUM

AH - RUN EMSXZT

Figure 11-16

 $0 \text{ dB} = 37.95 \text{ g}^2/\text{Hz}$  $B_e = 0.25 \text{ Hz}$ 

RMS = 1.660 g

 $S = 34 \text{ sec.}$ 

VERTICAL POWER SPECTRUM

AV - RUN EMSXZ1

Figure 11-17

9-24-81

Filtered

Low-Pass 65 Hz






Figure 11-18

9-24-81  
unfiltered




Figure 11-19




Figure 11-20

9-25-81

1115

VPSXZ1A

Filtered

Low-Pass 65Hz

6.2G

Horiz. Table

Accelerometer



6.0G

Vert. Table

Accelerometer



Figure 11-21

9-25-81

1115

UPXZ1A

unfiltered





Figure 11-22

9-25-81  
UPR 221A  
1115  
UNFILTERED  
VALVE SENSITIVE



Inlet Pressure

Outlet Pressure

Figure 11-23

9-25-81  
1323  
UP5X22  
Filtered  
Low-Pass 65Hz







Figure 11-24




Figure 11-25

9-25-81  
 1373  
 VP3 x 2  
 unfiltered  
 valves de l'eprouve

AH

AV

Inlet Pressure

Outlet Pressure

Figure 11-26




Figure 11-27

9-25-81  
1447  
UPS X 23  
Unfiltered

Horiz. Table  
Accelerometer



Vert. Table  
Accelerometer




Figure 11-28

9-25-81  
1447

9-25-81  
1447  
UPSX23  
unfiltered

Alt

AV

Inlet Pressure

Outlet Pressure

Solenoid Power





Figure 11-29

9-25-81  
1525  
UPSYZ1  
Filtered  
Low-Pass 65 Hz



5.0G



6.2G



Figure 11-30




Figure 11-31




Figure 11-32




Figure 11-33

9-25-61  
1543  
UPSVZ1A  
unfiltered




Figure 11-34

7-25-81

1543

UPSYE1A  
Unfiltered

AH

AY

Inlet Pressure

Outlet Pressure

Solenoid Power

Figure 11-35

9-25-81  
1603  
UPSYZ2  
Filtered  
Low-Pass 65 Hz

6.06

Horiz. Table  
Accelerometer

7.36

Vert. Table  
Accelerometer



Figure 11-36

9-25-81  
1603  
UPSYZ2  
unfiltered




Figure 11-37

7-25-81  
1103  
VPSV22  
unfiltered

RH

AV

Inlet Pressure

Outlet Pressure

Solenoid Power




Figure 11-38




Figure 11-39

9-25-81  
1611  
UPSYZ3  
Unfiltered




Figure 11-40

9-25-81

1611

UPSVZ3

unfiltered

AN

AV

Inlet Pressure

Outlet Pressure

Solenoid Power

Figure 11-41

9-25-81

1620

EMSY21

Filtered

Low-Pass 65Hz

6.3G

Horiz. Table  
Accelerometer

7.2G

Vert. Table  
Accelerometer



Figure 11-42




Figure 11-43

7-25-81  
1620  
EM8821  
UNFILTERED


AH

AV

Inlet Pressure

Outlet Pressure

Solenoid Power



1




Figure 11-44

9-25-81  
1635  
EMSY22  
Filtered  
Low-Pass 65 Hz

← 6.5 G

Horiz.  
Table  
Accelerometer



← 7.5 G

Vert.  
Table  
Accelerometer



Figure 11-45

9-25-81  
1635  
EM3YZ2  
Unfiltered




Figure 11-46

9-26-81

1635

EMSYZ7  
unfiltered

AH

AV

Inlet Pressure

Outlet Pressure

Solenoid Power

Figure 11-47

9-25-81  
1643  
EMSV23  
Filtered  
Low-Pass 65Hz

74G

Horiz. Table  
Accelerometer

Vert. Table  
Accelerometer

81G



Figure 11-48




Figure 11-49




Figure 11-50




Figure 11-51

9-26-81  
0842  
5MSX21  
Unfiltered





Figure 11-52

18-26-81

0842

6msx21  
unfiltered

Solenoid 4503



THIS PAGE INTENTIONALLY LEFT BLANK.



## SECTION 12.0

## TEST SPECIMEN DATA

THIS PAGE INTENTIONALLY LEFT BLANK.

# nutech

San Jose, California

Project Zimmer/La Salle SQRT Requalification Program File No. \_\_\_\_\_  
 Owner Cincinnati Gas and Electric Company/Commonwealth Edison Company  
 Client Cincinnati Gas and Electric Company/Commonwealth Edison Company

## TABLE I TEST SPECIMEN DATA

INSTRUMENT NAME: SOLENOID AIR PILOT VALVE  
 MODEL NO.: ASCO 8323A22  
 SERIAL OR ID. NO.: \* 84609J  
 MANUFACTURER: AUTOMATIC SWITCH CO.  
 SPECIAL FEATURES IF ANY: NONE  
 FUNCTION: SUPPLY INSTRUMENT AIR FOR  
 ACTUATION OF AIR OPERATED VALVE  
 DIMENSIONS: 7 1/16"H X 3 7/16"W X 2 3/4"D  
 WEIGHT: 3.1 LB  
 REQUIRED RANGE: 14.7 ~ 100 PSIG  
 MAXIMUM PERMISSIBLE LEAKAGE RATE: 0.1 SCFH/INCH OF NOMINAL VALVE  
 SIZE  
 MONITORING REQUIREMENTS: CHANGE OF STATE AND VALVE  
 SEAT LEAKAGE  
 MOUNTING DETAILS: SEE FIGURE 1  
 CHATTER TIME: N/A  
 NOMINAL VALVE SIZE: 1/2"

\* TO BE COMPLETED BY SWRI

Revision	0					Page	11
Prepared By/Date	DBT for SG 9/18/81					of	11
Checked By/Date	46 9/10/81						

THIS PAGE INTENTIONALLY LEFT BLANK.

SECTION 13.0  
ANALOG TAPE LOG

THIS PAGE INTENTIONALLY LEFT BLANK.



## ANALOG TAPE LOG

Tape Speed 3-3/4 ips

Tape channel designation and accelerometer location.

Channel 1	AH, Horizontal Accelerometer on Bookend
Channel 2	AV, Vertical Accelerometer on Bookend

## TAPE FOOTAGE

## DATA

840	X-Y Plotter Cal, 5.0 g pulse, Chan. 1
915	SW Cal., 1.0 g peak @ 50 Hz
924	SW Cal., 1.0 g peak @ 10 Hz
930	SW Cal., 2.0 g peak @ 10 Hz
935	SW Cal., 2.0 g peak @ 50 Hz
940	SW Cal., 8.0 g peak @ 50 Hz
948	SW Cal., 6.0 g peak @ 50 Hz
954	SW Cal., 4.0 g peak @ 50 Hz
965	UPS No. 1, X-Z Axis
1000	UPS No. 1A, X-Z Axis
1031	UPS No. 2, X-Z Axis
1064	UPS No. 3, X-Z Axis
1086	UPS No. 1, Y-Z Axis
1112	UPS No. 1A, Y-Z Axis
1135	UPS No. 2, Y-Z Axis
1162	UPS No. 3, Y-Z Axis
1185	EMS No. 1, Y-Z Axis
1209	EMS No. 2, Y-Z Axis
1235	EMS No. 3, Y-Z Axis
1256	EMS No. 1, X-Z Axis

THIS PAGE INTENTIONALLY LEFT BLANK.

## SECTION 14.0

## SWRI LABORATORY DATA LOG

DATE	TIME	OBSERVATIONS	PROTEC
9-10-81	14:30	① Check calibration and pentameter model 2B-K, set 132/70 pressure. Range 0-500 PSI with output. The calibration was checked at 500 PSI and was found to be accurate.	
	14:50	② Calibrate Validyne model DP25A Amprobe pressure meter and Air 100 Validyne transducer for Volt/Volts. It at several different pressure set points in board were as follows: Span = 1.76. The calibration gives a deflection (slope on Volt/division) with set as above.	
9-11-81	0800-1130	Made recommended set-up of Solenoid valve in test procedure reference for functional c.	
	1230-1400	An inspection of specimen was performed prior to any tests. There was no visual evidence of abnormalities. Valve was also cycled with no pressure. Operated properly. Several pressure levels were applied as follows: Input Transducer      Output transducer 0.645V      0.685V 0.809V      0.859V 1.007V      1.073V Both transducer cals are 3.99V with internal resistance	
Tests Conducted By:		5. K. Wilson Earnie Garcia	Witness SWRI Gov't

SOUTHWEST RESEARCH INSTITUTE  
LABORATORY DATA LOG

VALVE 2323

TEST ITEM IDENT. NUTECH ASCO SOLENOID PAGE 2 OF 7  
 TEST PROCEDURE REF. MK2-02-112 Rev. D  
 TEST NAME Seismic PROJECT NO. 02-6056-007

DATE	TIME	OBSERVATIONS
9-12-81	0900	Accelerometer Kistler Model EGC-500DS-20 S/N 3048I-R12-12 was calibrated according to XII-EE-101-2 for use with NUTCH ASCO Solenoid Valve 2323. All other equipment involved is within cal specs.
	0910	All items designated for cyclic calibration were verified to be within calibration. All items designated for calibration-before-use were calibrated according to QA procedure.
	1111	Exploratory testing began with sine sweep in Z-AXIS. Frequency is 1-100 Hz with 0.5 octave/minute sweep and 0.1 G Peak. Response accelerometer is mounted on side of Solenoid A coincident with table axis. Table control accelerometers are mounted on the bookend.
	1120	Anchored all four corners of table relative to the floor to run horizontal resonance searches.
	1157	Resonance Search in X-AXIS. Levels are all the same as for Z-AXIS.
	1215	Rotated bookend <del>in</del> with Solenoid valve to the Y-AXIS.
	1228	Resonance Search in Y-AXIS. Levels are the same as for Z-AXIS.

Tests Conducted By: Ernie Garcia Witness SWRT Gov't

SOUTHWEST RESEARCH INSTITUTE  
LABORATORY DATA LOG

TEST ITEM IDENT. NUTECH ASCO SOLENOID VALVE PAGE 3 OF 7

TEST PROCEDURE REF. MKA-02-112 Rev. 0

TEST NAME Seismic

PROJECT NO. 02-6056-007

DATE	TIME	OBSERVATIONS
9-25-81	0810	Run re-check of Functionals on ASCO Valve 8323 prior to start of seismic tests. Applied a 100 psi input at the command point. Check for leakage at the N/O after valve was activated. No measurable leak was detected.
Tape	1055	UPSET condition in X-Z Axis. UPSXZ1. Noticed after the test that tape inputs were improperly connected. Test will be repeated.
Tape 1000	1115	UPSXZ1A was run with the valve energized. This is slight deviation from test plan, but the second run will be with valve de-energized.
Tape 1031	1323	UPSXZ2 in X-Z Axis with valve de-energized.
Tape 1064	1447	UPSXZ3. Valve started energized, was de-energized and re-energized during the test.
	1503	Functional check was performed on valve after the three UPSET condition tests in the X-Z Axis. No leak with 100 psi was detected.
	1510	Rotated book end with valve to the Y-Z Axis to run tests in this direction.

Tests Conducted By: Ernie Garcia

Witness SWRI Gov't



SOUTHWEST RESEARCH INSTITUTE  
LABORATORY DATA LOG

TEST ITEM IDENT. NUTECH ASCO SOLENOID VALVE PAGE 4 OF 7

TEST PROCEDURE REF. NKA-02-112 Rev. 0

TEST NAME Seismic

PROJECT NO. 02-6056-007

DATE	TIME	OBSERVATIONS
9-25-81 Tape 1086	1525	UPSYZ1. Valve de-energized. The peak acceleration on the horizontal axis was below 6 g's. This test will be repeated.
Tape 1112	1543	UPSYZ1A Valve de-energized.
Tape 1135	1603	UPSYZ2. Valve energized. NO leaks detected.
Tape 1162	1611	UPSYZ3. Valve cycled. Valve was checked for leaks after this UPS test. None detected.
Tape 1185	1620	EMSYZ1. Valve cycled. Valve checked for leaks. None detected.
Tape 1209	1635	EMSYZ2 Repeat of 1620 due to horizontal acceleration being slightly low.
Tape 1235	1643	EMSYZ3. Repeat to increase horizontal acceleration.
9-26-81	0815	Rotated brookend with Solenoid Valve to the X-Z Axis
Tape 1256	0842	EMSXZ1. Valve cycled with 120 psi applied.
	0850	Functional check performed. No leaks detected. Also performed visual check. No apparent physical damage noticed.

Tests Conducted By: Fernando Garcia

Witness SWRI Gov't



SOUTHWEST RESEARCH INSTITUTE  
LABORATORY DATA LOG

TEST ITEM IDENT. NUTECH ASCO SOLENOID VALVE PAGE 5 OF 7

TEST PROCEDURE REF. MK2-02-112 Rev. 0

TEST NAME Seismic

PROJECT NO. 02-6056-007

DATE	TIME	OBSERVATIONS
9-26-81	0950	Ran fragility test in the X-Axis. Used 50 Hz and started at 2.0 G PK. Level was swept up while watching for leaks. Bubble began to come thru at 2.4 G PK. Table was anchored at all four corners relative to the floor for horizontal axis fragility tests. Pressure on the valve was 100 psi.
	1005	Fragility test in Y-Axis. Input level was slowly increased to a level of 10 G peak and no leaks were detected. The upper solenoid has a vibration sound continuously after this test.
	1035	Fragility test in Z-Axis. Could not increase table input more than 5 g peak. No leaks detected at this point.

Tests Conducted by: Ernie Garcia

Witness SWRT Gov't

## SOUTHWEST RESEARCH INSTITUTE

## LABORATORY DATA LOG

VANE 83-23

TEST ITEM IDENT. Nucleon ASCO SOLENOID PAGE 6 OF 7

TEST PROCEDURE REF. MK 2-02-112 REV. 0

TEST NAME Seismic PROJECT NO. 02-6056-007

DATE	TIME	OBSERVATIONS
9-30-81	14:00	<p>set-up equipment and pressure transducers and oscillograph for sine dwell at 50 Hz.</p> <p>Oscillograph used to record both pressures and the on-off functions of the solenoid.</p> <p>Two digital voltmeters used to monitor input and output pressure calibrated 1 volt / 100 psi.</p> <p>P.t. pressure on input and output and made functional check of item before test.</p> <p>Test will consist of raising the g level at 50 Hz from 2g's to a maximum of 10g's and note if there is any leakage during test while operating the solenoid.</p> <p>input pressure at: 102 psi</p> <p>output pressure at: 96.8 psi</p>
10-1-81	8:00	<p>Recheck all set-up and add accelerometer outputs to Oscillograph. Apply pressure and make functional check. input pressure = 106 psi</p> <p>output pressure = 112 psi</p>
	9:10	<p>start bringing up g's level till reaching 10g's, then going to a maximum of about 12g's with no sign of leakage. (Fn = 50 Hz) Z-AXIS</p>
	9:18	<p>end test, will now rotate test item 90° and retest.</p>
	9:30	<p>start test with item moved 90°, brought g's level up to 10g's then to 12g's and dwelled for several</p>

Tests Conducted By: S. X. Wilson

Witness SWRI Gov't



ATTACHMENT NO. 4

Conductivity Cell  
E12-N025A, B

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
Owner Mississippi Power and Light Co.  
Client Mississippi Power and Light Co.

INTERIM SEISMIC QUALIFICATION ANALYSIS

FOR THE CONDUCTIVITY CELL

(1" VALVE CONNECT TO

THE RHR LINE)

Revision	0					Page <u>1</u>
Prepared By/Date	BF / 4-16-82					of <u>12</u>
Checked By/Date	WPC / AS 4/16/82					

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

## Contents

	Page
I. Purpose	3
II. Conductivity Cell Environment	3
III. Method of Analysis	3
VI. Dimensions and Properties	4
V. Calculation of the Section Modulus and the Cross-Sectional Area of the Nipple	5
VI. Stress Calculation Due to Dead Weight	7
VII. Stress Calculation Due to Thermal Expansion	7
VIII. Stress Calculation Due to Internal Pressure	8
IX. Stress Calculation Due to Seismic Loads	8
X. Stress Summary and Code Evaluation	11
XI. Conclusion	11
References	12

Revision	0					Page <u>2</u>
Prepared By/Date	<i>JS</i> / 4-16-80					of <u>12</u>
Checked By/Date	<i>JS</i> / 4/16/82					



Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
Owner Mississippi Power and Light Co.  
Client Mississippi Power and Light Co.

### I. Purpose

Evaluate (based on seismic category 1, and ASME Class 2 equipment) the pressure integrity of the conductivity cell when subjected to combined operating and seismic loading.

### II. Conductivity Cell Environment

#### Design Condition (Reference 1)

Temperature = 350° F

Pressure = 500 psi

#### Operating Condition (Reference 1)

Temperature = 250° F

Pressure = 310 psi

#### Seismic Loads (Reference 2)

Peak excitation acceleration = 6g

### III. Method of Analysis

The most critical component affecting the pressure integrity of the conductivity cell is the 1" nipple. (Which connects the 1" valve to the RHR line.) The stress in the 1" nipple is estimated according to dead weight, thermal expansion, and seismic loads.


Revision	0					Page 3
Prepared By/Date	CE / 4-12-82					of 12
Checked By/Date	CE / 4-14-82					



Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

The seismic response is calculated with the conservative assumption that the excitation is the harmonic force with a frequency to which the conductivity cell responds most critically.

#### IV. Dimensions and Properties



#### Properties:

##### Nipple:

Size = 1" N.P.T. schedule 80 (3)  
 O.D. = 1.315 (4)  
 I.D. = .957 (4)  
 Wall Thickness = .179 (4)  
 Height of Thread = .06957 (5)  
 Engagement Length = .66" (5)  
 Material = 316 SS (6)  
 $S_m = 19650$  psi (@ design temperature of  $350^{\circ}$  F) (7)  
 Damping =  $\xi = 1\%$  (small pipe) (8)

Revision	0					Page 4
Prepared By/Date	6/14-16-82					of 12
Checked By/Date	6/18/82					

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

Valve:

Material = Stainless Steel ASTM A351

CF - 8M

CF - 3M (3)

Weight = 10 pounds (6)

Assumption

- o The 6.75" pipe is made of the same material that the 1" nipple is made of (316 SS)

$$\text{Weight of the 6.75" pipe} = \frac{6.75}{12} * 2.172 = 1.22 \text{ lb}$$

- o The weight of the nut and the assembly at the end of the 1" pipe is the same or less than the weight of the valve (10 lbs).

Note that this assumption is very conservative.

V. Calculation of the section modulus and the cross-sectional area of the nipple.

Assume the weakest point is the bottom of the thread.

$$S_N = \frac{I}{C}$$

Revision	0					Page	5
Prepared By/Date	GP 11-16-82					of	12
Checked By/Date	WCC for AS 7/14/82						

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

Where

$$\begin{aligned}
 I &= \frac{\pi}{64} \left[ (OD_{\min})^4 - ID^4 \right] \\
 &= \frac{\pi}{64} \left[ (1.315 - 2 * .06957)^4 - .957^4 \right] \\
 &= .05267 \text{ in}^4
 \end{aligned}$$

and

$$\begin{aligned}
 C &= OD/2 - \text{Thread Height} \\
 &= 1.315/2 - .06957 \\
 &= .5879 \text{ in}
 \end{aligned}$$

Substituting the values for I and C into equation (1),  
 the section modulus of the nipple can be calculated

$$\begin{aligned}
 S_N &= .05267 / .5879 \\
 &= .0896 \text{ in}^3 \\
 A_N &= \frac{\pi}{4} \left[ (OD_{\min})^2 - ID^2 \right] \\
 &= \frac{\pi}{4} \left[ (1.315 - 2 * .06957)^2 - .957^2 \right] \\
 &= .367 \text{ in}^2
 \end{aligned}$$

Revision	0					Page	6
Prepared By/Date	L.R./4-16-81					of	12
Checked By/Date	J/C/j. 4/16/82						

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

## VI. Stress Calculation Due to Dead Weight

Depending on the orientation of the RHR line (vertical or horizontal), there will be either membrane or bending stress due to dead weight.

### o Membrane Stress

$$\begin{aligned}\sigma_{DW} &= \frac{\text{weight}}{A_N} \\ &= \frac{10 + 1.22 + 10}{.367} \\ &= 58. \text{ psi}\end{aligned}$$

### o Bending Stress

$$\begin{aligned}\sigma_{DW} &= \frac{M}{S_N} \\ &= \frac{10*(3.25-.66)+1.22\left(\frac{6.75}{2}+3.25-.66\right)+10(6.75+3.25-.66)}{.0896} \\ &= 1413 \text{ psi}\end{aligned}$$

use  $\sigma_{DW} = 1413 \text{ psi}$

## VII. Stress Calculation Due to Thermal Expansion

Since one side of the 1" pipe is connected to a flexible wire, then the entire assembly can grow without any

Revision	0					Page <u>7</u>
Prepared By/Date	<u>W.F. / 4-10-82</u>					of <u>12</u>
Checked By/Date	<u>W.F. / 4-14-82</u>					

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

restriction. Consequently, the stress due to thermal expansion is zero.

$$\sigma_{TH} = 0$$

## VIII. Stress Calculation Due to Internal Pressure

$$\begin{aligned}\sigma_P &= \frac{Pr}{t} \\ &= \frac{500 (.957/2)}{.179 - .06957} \\ &= 2187 \text{ psi}\end{aligned}$$

## IX. Stress Calculation Due to Seismic Loads

A simple finite element model of the entire assembly is set up (for details see Appendix A). Natural frequencies for the entire assembly are then obtained.

First natural frequency =  $W_N = 98.9 \text{ Hz}$

The dynamic magnification factor can now be calculated from the following equation (9)

$$DLF = \frac{1}{\sqrt{\left[1 - \left(\frac{W}{W_N}\right)^2\right]^2 + \left[2 \xi \left(\frac{W}{W_N}\right)\right]^2}} \quad \text{(harmonic excitation, Conservative)}$$

Revision	C					Page 8
Prepared By/Date	Dr/4-16-82					of 12
Checked By/Date	Dr/4-16-82					

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

using

$$W_N = 98.9 \text{ Hz}$$

$W = 33 \text{ Hz}$  (highest frequency content of an  
 earthquake)

Revision	0					Page	9
Prepared By/Date	2/1/82					of	12
Checked By/Date	5/2/82						



# nutech

San Jose, California

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
Owner Mississippi Power and Light Co. \_\_\_\_\_  
Client Mississippi Power and Light Co. \_\_\_\_\_

One can calculate the DLF to be

$$\text{DLF} = \frac{1}{\sqrt{\left[1 - \left(\frac{33}{98.9}\right)^2\right]^2 + \left[2 \cdot .01 \left(\frac{33}{98.9}\right)\right]^2}}$$

= 1.13 (The assembly responds almost statically to earthquakes)

$$\text{Responds acceleration} = 6 \cdot 1.13 = 6.78 \text{ g}$$

Now the bending moment at the base of the 1" nipple can be calculated by multiplying the inertia forces ( $F = ma$ ) by the appropriate moment arms.

$$\begin{aligned} M &= 10 \cdot 6.78 \cdot (3.25 - .66) + 1.22 \cdot 6.78 \cdot (6.75/2 + 3.25 - .66) \\ &+ 10 \cdot 6.78 \cdot (6.75 + 3.25 - .66) \\ &= 858 \text{ in-lb} \end{aligned}$$

$$\begin{aligned} \sigma_S &= \frac{M}{S_N} \\ &= \frac{858}{.0896} \\ &= 9578 \text{ PSI} \end{aligned}$$

Revision	0					Page <u>10</u>
Prepared By/Date	LH/A-16-82					of <u>12</u>
Checked By/Date	HAC/AS 4/10/82					

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

## X. Stress Summary and Code Evaluation

The following is a summary of the stress calculated for the conductivity cell.

Event	Stress (psi)
Dead Weight	1413
Thermal Expansion	0
Internal Pressure	2187
Seismic	9578
TOTAL	13,178 (Allowable $S_M = 19,650$ psi)

## XI. Conclusion

Since the total stress calculated for the 1" nipple due to all loads (dead weight, thermal expansion, internal pressure, and seismic loads) is only 13,178 psi, and one  $S_m$  for the nipple is 19,650 psi, it is then concluded that the 1" nipple (which is the weakest point) and consequently the entire assembly for the conductivity cell, will meet the requirements of the ASME Boiler and Pressure Vessel Code, 1980 Edition.

This qualifies the conductivity cell to be Safe to operate in the environments explained in Section II of this report.

Revision	0					Page <u>11</u>
Prepared By/Date	<i>CE/H-10-80</i>					of <u>12</u>
Checked By/Date	<i>CE/H-10-80</i>					

# nutech

San Jose, California

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
Owner Mississippi Power and Light Co.  
Client Mississippi Power and Light Co.

## References

1. General Electric DWG 163C1544 SH No.2, "Purchased Part Conductivity Cell."
- 2.
3. General Electric DWG 163C1544 SH No. 1, "Purchased Part Conductivity Cell."
4. Properties of Pipe Table, Bergen-Paterson catalog.
5. Machinery's Handbook, 18th Edition, Industrial Press, Southeast.
6. NUTECH Communication Record, Telephone Conversation between Steven Hicks (from Foxboro Corp.) and R. Morton, File 32.1206.0001.
7. ASME Boiler and Pressure Vessel Code, 1980, Section III, Division 1, Appendix I, Table I-1.2.
8. U.S. Atomic Energy Commission, Regulatory Guide 1.61, "Damping Values for Seismic Design of Nuclear Power Plants."
9. William T. Thomson, "Theory of Vibration With Applications", 2nd Edition, Prentice Hall, 1981.


Revision	0					Page	12
Prepared By/Date	SA / 11-16-82					of	12
Checked By/Date	SIC for AJ 11/16/82						

Project Grand Gulf Nuclear Station File No. \_\_\_\_\_  
 Owner Mississippi Power and Light Co.  
 Client Mississippi Power and Light Co.

## APPENDIX A

### Simple Finite Element Model of the Entire Assemble of the Conductivity Cell:

PISTAR computer program is used to build a finite element model for the following:



Natural frequencies are calculated from a PISTAR model extraction run (Run ID = BOF325L). The next two pages are copies of inputs and outputs of the PISTAR model extration computer run.

Revision	0					Page <u>A-1</u>
Prepared By/Date	<u>LS/11-16-82</u>					of <u>4</u>
Checked By/Date	<u>LS-LS 4/16/82</u>					

## INPUT DATA ECHO PRINT

	1	11	21	31	41	51	61	71	81
	:	:	:	:	:	:	:	:	:
1 TITLE	CONDUCTIVITY CELL								
2 ID	CLIENT=GRAND GULF NUCLEAR STATION								
3 ID	PROJECT NAME=EQUIPMENT QUALIFICATION								
4 ID	PROJECT NUMBER=KMPLE-0607								
5 ID	PREPARED BY=B. FATEMI								
6 ID	CHECKED BY=								
7 GEOMETRY	CONDUCTIVITY CELL								
8 START	100								
9 CLASS 2									
10 PIPE	100	200	0.0	2.0	0.0		1	1	
11 PIPE	200	300	0.0	3.375	0.0		1	1	
12 PIPE	300	400	0.0	3.375	0.0		1	1	
13 ADD WEIGHT	200		10.0	10.0	10.0				
14 ADD WEIGHT	400		10.0	10.0	10.0				
15 PROPERTY	1								1.00SCH80 WATER
16 MATERIAL	1								STAINLESS
17 ANCHOR	100								
18 END GEOM									
19 LOADING	DW,MOD. EXT.								
20 CASE	DW								
21 DEAD LOAD									
22 PRINT		YES							
23 CASE	MAX								
24 FREQUENCY		1.0							
25 END LOADS									
	:	:	:	:	:	:	:	:	:
	1	11	21	31	41	51	61	71	81

Prepared by/Date: JF/4-15-82  
 Checked by/Date: JF/4-15-82

04/15/82

A-U-T-E-C-H / P-I-S-T-A-K

PAGE 18

F R E Q U E N C I E S      A N D      P E R I O D S

-- VERSION 1.5.2 --

EIGENVALUE PROBLEM

LOADING CONDITION MX

MODE NUMBER	CIRCULAR FREQUENCY (RAD/SEC)	FREQUENCY (CYCLES/SEC)	PERIOD (SEC)
1	.6217E+03	.9894E+02	.1011E-01
2	.6217E+03	.9894E+02	.1011E-01
3	.4720E+04	.7519E+03	.1330E-02
4	.4720E+04	.7519E+03	.1330E-02
5	.7759E+04	.1272E+04	.7865E-03

Frequency/Date 4/14-15-82  
Checked by 4/16/82

Page A-1

ATTACHMENT NO. 5

Air Operated Butterfly Valves  
M-257.0/M-258.0

A. ORIENTATION

The first item was to provide an explanation as to how the Bechtel design and qualification account for the orientation of valves in the piping systems. Of particular interest was any possible detrimental affects of the pipe hangers or piping elbows on the overall valve qualification. Our response to this item is that pipe analysis is performed by Bechtel using the pipe isometric drawings which show the physical configuration of elbows, flanges, pipe routing, valves and actuator orientation, etc. Support locations and types are modeled to obtain the proper flexibility and maintain code and SAR stress limits for the various loading combinations. The result of this analysis is not just that the NRC concerns are addressed, but they are the basis for our design.

B. LOADING

The second item was to compare the required plant loads for the valves to the loading used in qualifying the valves. When the analysis previously discussed was performed, the plant loads, including margin, were determined. These loads are as follows:

<u>System</u>	<u>Valve Number</u>	<u>Pratt Order Number</u>	<u>Design Loading</u>	<u>Static Test Loading</u>
P44	F116, 117, 118, 119	D-0073-1	3 g's	5 g's
P44	F122, 123	D-0073-2	3 g's	5 g's
P44	F120, 121	D-0073-3	3 g's	5 g's
G41	F019, 045	D-0089-1	3 g's	5 g's

The vendor, Henry Pratt, qualified the valves by testing one valve of each family of valves, and then showing that the test of the "parent" valve qualifies all other members of that valve family.

C. PRATT-BETTIS: PRD-81/44

The materials specified by Bettis for its springs are either AISI5160 or AISI1065. If AISI5160 material was not properly heat treated, the material would be "soft" (Rockwell Hardness Approx. 32), have low tensile strength, demonstrate no workability and permanently distort after the first deflection (approx. 50% of the deflection). Similar results could be expected from AISI1065 but to a lesser extent. The Bettis actuators have been bench tested in place and tested by CTO and Startup. The testing has not shown any permanent distortion of the springs, therefore, it must be assumed that appropriate heat treatment was done.



ATTACHMENT NO. 5 (Cont'd)

During the jobsite modifications of the Bettis actuators, Bechtel Field Engineering and Quality Control inspected the actuator components to determine size and configuration of the components. The results were documented and submitted to Bechtel Project Engineering for review and evaluation.

Bechtel Project Engineering has determined that in most cases, the measured dimensions agreed with the dimensions on the vendor drawings or in the stress report. Minor discrepancies existed in the air and spring cylinder dimensions.

The minor discrepancies in the dimensions are acceptable since they have little or no effect on the center of gravity of the cylinder, the analysis, or the actuator operation. Bettis actuator components have stress design safety-factors from 2.5 to over 50.

The most critical dimensions and sizes for design stress considerations were consistent between design documents and jobsite measurement. These dimensions are the rod sizes, bolt sizes, and bolt patterns, yoke keys and thread engagement between cylinders and adapters.

Based on the nonconformance of the critical dimensions and the design safety factors, Bechtel Project Engineering has determined that there is sufficient evidence that the actuator dimensions and components comply with the design documents.

Materials were not reviewed for specific ASTM designation, however, all materials that were degradable were replaced as part of the modification effort, i.e., seals and lubricants, or pins/rollers with the coating used in qualification testing.

The above information has been extracted from two (2) Bechtel letters to MP&L's Quality Assurance Organization. The above information will be utilized to close out PRD-81/44 on April 20, 1982.

D The following information is included in Attachment No. 5:

1. Henry Pratt letter dated December 15, 1981
2. Henry Pratt letter dated April 2, 1982
3. Henry Pratt test report



## HENRY PRATT COMPANY

creative engineering for fluid systems

401 SOUTH HIGHLAND AVENUE · AURORA, ILLINOIS 60607

December 15, 1981

Bechtel Power Corporation  
15740 Shady Grove Road  
Gaithersburg, MD 20760

ATTN: Mr. R. S. Trickovic  
Project Engineer

SUBJ: Grand Gulf Nuclear Station  
P.O. 9645-M-257/258,  
Revisions 30 and 36 Respectively  
HPCo S.O. D-28579

BECHTEL POWER CORP.

**RECEIVED**  
DEC 18 1981

JOB NO. 9645

Gentlemen:

In accordance with the above referenced order, enclosed please find one (1) copy of Henry Pratt certification of nonactive valve assemblies.

Should you have any questions or need additional information, please let us know.

Very truly yours,

HENRY PRATT COMPANY

Roger D. Nelson  
Nuclear Project Manager

RDN/clt

Enclosure



## HENRY PRATT COMPANY

creative engineering for fluid systems

401 SOUTH HIGHLAND AVENUE · AURORA, ILLINOIS 60607

December 14, 1981

SUBJECT: Bechtel Grand Gulf Project  
Seismic Analysis Report for Active & Non-Active  
Valve Assemblies

Reference: Pratt Job Numbers D-0073-1, D-0073-2  
D-0073-3, D-0089-1

Henry Pratt Company does not differentiate between active and non-active in the structural design of nuclear butterfly valves. In view of the fact that the active valve assemblies are already found to be adequate for the specified loading conditions on the basis of the functional qualification reports already approved by Bechtel Power Corporation, and that the Bechtel approved seismic analysis reports for both active and non-active valve assemblies demonstrate the structural integrity of those valve assemblies for conditions more severe than required in the specifications, we hereby certify that the structural integrity of both the active and non-active valve assemblies are considered adequate for their specified service conditions.



H. B. Washburn  
H. B. Washburn  
Senior Test Engineer

Certified By:

J. V. Ballun  
J. V. Ballun, P.E.

HBW:dg

**PRATT**

# HENRY PRATT COMPANY

creative engineering for fluid systems

401 SOUTH HIGHLAND AVENUE · AURORA, ILLINOIS 60507

April 2, 1982

Bechtel Power Corp.  
15740 Shady Grove Road  
Gaithersburg, MD 20877

ATTN: Mr. Frank M. Parks, Purchasing

SUBJ: Grand Gulf Nuclear Station  
P.O. 9645-M-257  
File 0763/M-257.0  
Passive to Active Valve Qualification  
HPCo Proposal No. X-51-8180

Gentlemen:

With reference to your request for quotation dated March 9, 1982, to include ten (10) valves in Pratt functional qualification test report for active valves, we are submitting herewith our proposal.

This proposal is based on the selection of prequalified parent valve assemblies.

The selected parent valve assemblies have been prequalified in accordance with the attached "Henry Pratt Functional Qualification Requirements for Power Operated Safety Related Active Butterfly Valve Assemblies for Nuclear Power Plants".

For valve assemblies of similar design the parent valve qualification will be extended to generically qualify the candidate valve assemblies utilizing generic qualification rules.

Below on the left are selected parent valve assemblies which were subjected to the test program. On the right are the generically qualified valve assemblies (candidate valves).

## Parent Valve Assemblies

36" (1100) T412-SR4  
D-0038-3  
\* Section 6A of existing report

will qualify

## Candidate Valve Assemblies

D-0073-1 24" (1100) T316-SR2  
D-0073-2 30" (1100) T416-SR3  
D-0073-3 36" (1100) T420-SR1

\* Results to be included in  
Section 6B of existing report

INITIAL	
DATE	4-6-82
FILE	0276/M 257.0
ACCT	7-9645-M 257.0
TITLE	Passive to Active Valve Qual
CORPORATION	Henry Pratt

**RECEIVED**

APR 5 1982

F. M. PARKS

**PRATT**

Bechtel Power Corp.  
April 2, 1982  
Page 2

12" (1100) 721C-SR80-12	will qualify	D-0089-1 10" (1100) 732C-SR80
D-0089-4		
* Old loads add on valve		* Will become part of Section 1B
Section 1A		of the add on report.

NOTE: It is assumed that the previously accepted qualification reports and procedures are still acceptable to Bechtel and as such the above valve qualification program will be integrated with those reports.

Should any additional tests be required, they would be quoted at additional cost.


The cost for revised functional qualification report as indicated above is \$18,000.

Completion of the analysis and submittal will be ten (10) weeks from receipt of a written purchase order.

This proposal is valid for 30 days; payment terms are net 30 days.

Truly yours,

HENRY PRATT COMPANY

  
John F. Triplett  
Manager, Spare Parts Department

JFT/clt

# HENRY PRATT FUNCTIONAL QUALIFICATION PROGRAM

FOR

POWER OPERATED-SAFETY RELATED

ACTIVE VALVE ASSEMBLIES

BECHTEL POWER CORP.

DEC 5 1979

JOB No. 9645

Project Site: Grand Gulf Nuclear Station  
Port Gibson, Mississippi

Customer: Mississippi Power & Light Company

Engineer: Bechtel Power Corporation

Specification: 9645-M-257.0  
9645-M-258.0

P.O. Number: 9645-M-257.0  
9645-M-258.0

VENDOR'S DOCUMENT REVIEW	
1	<input checked="" type="checkbox"/> Approved - Mtg. may be held
2	<input type="checkbox"/> Approved - Submit final d.s. - Mtg. may be held
3	<input type="checkbox"/> Approved - Submit final d.s. - Mtg. may be held
4	<input type="checkbox"/> Not Approved - Correct and resubmit
5	<input type="checkbox"/> Review not required - Mtg. may be held
Approval of this drawing by _____ Date: 12/2/79	
JOB NO. 9645	BECHTEL CORPORATION POWER & INDUSTRIAL DIVISION P.O. BOX 602 GAITHERSBURG, MD.

9645-M258.0-GS-26.0-10-D

Prepared By: Henry B. Washburn

11-8-79  
Date

Reviewed By: W. J. Adams

11-9-79  
Date

Certified By: Boni H. Zarola

11/9/79  
Date



705274

## TABLE OF CONTENTS

### Part I FUNCTIONAL QUALIFICATION REQUIREMENTS

### Part II FUNCTIONAL QUALIFICATION REPORT OF TEST VALVE, SELECTION AND TEST RESULTS

Introduction and Selection of QTVA  
and Qualified GFVA

Test Instrumentation and Calibration  
Data

#### Section 1 - Functional Qualification Test Reports

A. Report and Test Results for QTVA #D-0089-4  
(P.O. Item 1-3,10)

B. Generic Qualification Reports for GFVA #D-0089-5  
(P.O. Item 2-3,10)

Qualified by QTVA in Section 1A

#### Addendum



PART I

HENRY PRATT COMPANY

FUNCTIONAL QUALIFICATION REQUIREMENTS  
FOR  
POWER-OPERATED SAFETY-RELATED ACTIVE BUTTERFLY VALVE ASSEMBLIES  
FOR  
BECHTEL/GRAND GULF

FOREWARD

Power-operated safety-related active valve assemblies are required to perform their safety-related functions under specified operating conditions, including normal, upset, emergency and faulted plant conditions. It is the purpose of this standard to provide guidance for the preparation of functional specifications for the qualification of valves, actuators and the combination thereof (valve assemblies) by test and analysis for the intended service.

This standard provides a method by which a valve assembly can be qualified to the conditions specified by the manufacturer. If these conditions are at least as severe as the functional operating conditions specified by the owner, the valve assembly can thus be considered qualified.

## PART I

### TABLE OF CONTENTS

	<u>Page No.</u>
1.0 Scope	1
2.0 Definitions	3
3.0 Functional Qualification Requirements	4
4.0 Inspection, Verification and Record Control	4
5.0 Qualification Test Program	5
5.1 Test Plan	5
5.2 Orientation	5
6.0 Qualification Tests	5
6.1 Prerequisite Conditions	5
6.1.1 Installation for Tests	5
6.1.2 Record Control Points	5
7.0 Test Requirements	6
Appendix A - Valve Leakage Test	7
Appendix B - Cold Cyclic Test	8
Appendix C - Hot Cyclic Test	9
Appendix D - Temperature-Pressure Test	10
Appendix E - Seismic Loading Test	11
Appendix F - Vibration Test	12

## 1.0 SCOPE

- This standard establishes the rules for functional qualification of power-operated safety-related active butterfly valve assemblies.

## 1.2 Functional qualification consists of tests and/or analyses to demonstrate that a valve assembly will perform its required safety-related function. Generic qualification rules allow qualification of a candidate valve by analyses which demonstrate design similarity to a valve assembly qualified by testing.

## 1.3 Generic Qualification Rules

The following rules, as stated, relate specifically to butterfly valves. The Generic Family Valve Assembly is qualified provided the test valve assembly successfully passes all tests noted in this standard and the Generic Qualification Rules and/or ratios listed below are satisfied.

1.3.1 The GFVA is limited to size between 50% and 200% of the QTVA.

1.3.2 The GFVA and QTVA have similar seat taper angles.

1.3.3 Disc/seat interference of the GFVA  $\geq$  QTVA.

1.3.4 The GFVA and QTVA have the same basic seating surface materials.

1.3.5 The materials of construction of similar components of the GFVA have physical properties  $\geq$  than those of the QTVA.

1.3.6 
$$\frac{\text{Rated torque of actuator}}{\text{Calculated valve operating torque}} \geq 1$$

NOTE: The magnitude of the rated torque of the actuator above the calculated valve operating torque is not considered in the qualification rules since the maximum torque transmitted to the valve shaft is never greater than the value of the calculated valve operating torque.

1.3.7 Actuator and attached accessories have been qualified separately in accordance with I.E.E.E. 344 and I.E.E.E. 382.

1.3.8a. The ratio  $\frac{S_1}{S_2} > 1$  (Combined bonnet stress is less than the yield strength of bonnet material.)

Where  $S_1$  = Yield strength of bonnet material

$S_2$  = Combined bonnet stress due to seismic and operating loads.

1.3.8b. The ratio  $\frac{S_3}{S_4} > 1$  (Bonnet to valve bolting stress is less than the yield strength of bolt material.)

Where  $S_3$  = Yield strength (proof load) of bonnet to valve bolting  
 $S_4$  = Calculated stress of bonnet to valve bolting

1.3.8c. The ratio  $\frac{S_5}{S_6} > 1$  (Adapter plate to bonnet bolt stress is less than the yield strength of the bolt material.)

Where  $S_5$  = Yield strength (proof load) of adapter plate to bonnet bolting  
 $S_6$  = Calculated stress of bonnet to adapter plate

1.3.8d. The ratio  $\frac{S_7}{S_8} > 1$  (Actuator to adapter plate bolt stress is less than the yield strength of the bolt material.)

Note: In the case where an adapter plate is not used:

$S_5$  = Yield strength (proof load) of actuator to bonnet  
 $S_6$  = Calculated stress of bonnet to adapter plate bolting  
 $S_7$  and  $S_8$  are not present

1.3.9  $\Delta_L$  of QTVA or GFVA < .002".

Where  $\Delta_L$  = the calculated bonnet deflection at the base of the operator due to seismic or test loads.

Note: Since the deflections of the yoke assembly are extremely small .002" is an arbitrary limit. Considerably more deflection than .002" would be required to the cause binding in the operator to shaft connection or clearances. The actual deflections are significantly less than .002".

## 2.0 DEFINITIONS

- 2.1 Rated Torque of Actuator - Nominal torque capability of actuator under nominal motive power conditions as defined by the manufacturer.
- 2.2 Calculated Valve Operating Torque - Maximum torque required to operate valve for the intended service conditions.
- 2.3 Cold Working Pressure - The valve pressure rating at 100°F (38C).
- 2.4 Operating Time - The time required for the valve to complete each half of operating cycle.
- 2.5 Motive Power - The electrical, fluid or mechanical energy required to operate the valve assembly.
- 2.6 Operating Cycle - The movement of a valve closure element through its required operating travel under defined operating conditions, terminating with a return to the starting position.
- 2.7 Power Operated Active Valve Assembly - A butterfly valve assembly that must perform a mechanical motion to fulfill its system safety function through the application of external motive power.
- 2.8 Valve Actuator - A device which provides the torque necessary for valve operation.
- 2.9 Valve Assembly - A valve actuator combination including attached functional accessories:
  - 2.9.1 Test Valve Assembly (TVA) - A valve assembly selected for qualification testing.
  - 2.9.2 Qualified Test Valve Assembly (QTVA) - A test valve assembly which has been qualified by all appropriate testing required by this standard.
  - 2.9.3 Generic Family Valve Assembly (GFVA) - A valve assembly to be qualified by analysis which shows that the requirements for design similarity with the QTVA valve have been met.
  - 2.9.4 Qualified GFVA - A generic family valve assembly which has been qualified in accordance with 2.9.3.

### 3.0 FUNCTIONAL QUALIFICATION REQUIREMENTS

Functional qualification shall be demonstrated by suitable tests and/or analyses showing, on the basis of rules provided herein, that a valve assembly is qualified for defined limiting service conditions. The functional qualification shall demonstrate the following:

- 3.1 Valve shut-off capability and pressure boundary meeting applicable leakage tolerances.
- 3.2 Cyclic operability of the valve assembly.
- 3.3 Operability during and after loading representative of the maximum seismic incident.

### 4.0 INSPECTION, VERIFICATION AND RECORD CONTROL

Inspections of the test valve assembly on which testing is required shall be performed prior to and upon completion of the qualification test series.

- 4.1 Pre-test inspection shall be performed according to the test plan for such items as:
  - a. Control settings.
  - b. Securing of fasteners.
  - c. Motive power drive system.
  - d. Test equipment calibration.
- 4.2 A Functional Qualification Report shall be prepared for each valve assembly qualified. This report shall provide complete identification of the valve by type, size, pressure rating, actuator, and other data as appropriate. Any specific limitations restricting qualification shall be stated.
- 4.3 The Functional Qualification Report for a GFVA shall include the test plan, test results and inspections for the QTVA and the analyses used to show that the GFVA satisfies design similarity with the QTVA.
- 4.4 The Function Qualification Report shall be certified by one or more registered professional engineers competent in the field.

## 5.0 QUALIFICATION TEST PROGRAM

- 5.1 Test Plan - A Test Plan shall be prepared with appropriate inspection and test record forms to define test objectives, test fluids, conditions of the test, permissible maintenance or adjustments, and acceptance criteria. Where prequalified parts of the valve assembly (i.e. valve actuator, etc.) are utilized as part of the valve assembly qualification, the test plan shall reference the report upon which such prequalification is based.
- 5.2 Orientation - Functional Qualification tests for the valve orientation which results in the most severe loading of the valve assembly qualify the valve assembly for all orientations.

## 6.0 QUALIFICATION TESTS

### 6.1 Prerequisite Conditions

- 6.1.1 Installation for Tests - A test valve assembly shall be supported as required to permit testing in accordance with the applicable appendix and provided with appropriate means for pressurization and valve leakage measurement. All accessory equipment shall be adjusted to the manufacturer's recommended settings. Electric, pneumatic, or hydraulic connections for motive power shall be functionally equivalent to the actual valve assembly attachments.
- 6.1.2 Record Control Points - Prior to start of test sequence, all system conditions shall be recorded as applicable to the test valve assembly and test installation according to the test plan.



## TEST REQUIREMENTS

All of the tests listed below shall be conducted in accordance with the appropriate appendix:

Leakage. . . . .	Appendix A
Cold Cyclic . . . . .	Appendix B
Hot Cyclic . . . . .	Appendix C
Temperature-Pressure . . . . .	Appendix D
Seismic. . . . .	Appendix E
Vibration. . . . .	Appendix F

PART I  
APPENDIX A  
VALVE LEAKAGE TEST

Scope and Applicability

Valve leakage tests are intended to show that the test valve assembly is capable of meeting seat and stem packing sealing requirements.

Valve leakage tests are required for all test valve assemblies.

Test Requirements

- A.1 The test valve assembly shall be installed in accordance with Section 5.2, providing for pressurization of the test valve assembly and for collection and/or measurement of valve mainseat leakage in both directions for qualification of bidirectional valves or in the direction corresponding to the intended use for specific qualification.
- A.2 Leakage tests shall be made by applying cold working pressure or a lower pressure across the closure. The test fluid may be water (which may contain a corrosion inhibitor), steam, air, or inert gas. If a lower pressure is used, the functional qualification report for the valve shall include both the maximum rated pressure and the maximum rated valve seat sealing differential pressure. The test pressure shall be applied across the closure member in the direction producing the most adverse seating condition.
- A.3 The leakage rate test duration shall be adequate to determine the leakage rate, but no less than five minutes.
- A.4 Valve leakage shall be determined by placing the valve disc in the closed position. The test pressure shall then be applied across the closed disc.
- A.5 Packing leakage shall be observed at cold working pressure with the valve in the partially open position. For valves without leakoff connections, packing leakage shall be observed and the leak rate estimated. For valves with lantern rings and leakoff connections, leakage at the leakoff connections shall be measured and recorded. The initial packing leakage test shall be performed after fully cycling the test valve assembly 10 times. The leakage rate test duration shall be adequate to determine the leakage rate, but no less than 5 minutes.

PART I  
APPENDIX B  
COLD CYCLIC TEST

Scope and Applicability

Cold cyclic tests are intended to show that a test valve assembly is capable of closing and opening under the most adverse combination of motive power and system pressure.

Cold cyclic tests are required for all test valve assemblies.

Test Requirements

- B.1 The test fluid shall be as described in A.2.
- B.2 The test valve assembly shall be operated according to the following requirements and sequence:
  - B.2.1 One operating cycle, utilizing such voltage or actuating pressure, resulting in the nominal torque that is available, consisting of closing against internal pressure\* followed by opening with a differential pressure\* in the normal direction across the test valve assembly.
  - B.2.2 Three operating cycles, utilizing such voltage or actuating pressure, resulting in the maximum torque that is available with the test valve assembly depressurized.
  - B.2.3 Three operating cycles, utilizing such voltage or actuating pressure, resulting in the minimum torque that is available, closing against internal pressure\* and opening with a differential pressure\* in the normal direction across the test valve assembly.
- B.3 During each operating cycle the operating time in each direction of travel shall be recorded.

---

\*Internal pressure and differential pressure to be applied in cyclic testing shall be the maximum rated line pressure and differential operating pressure respectively for which the test valve assembly is to be qualified. Differential pressure need not be maintained after the test valve assembly is unseated.

PART I  
APPENDIX C  
HOT CYCLIC TEST

Scope and Applicability

Hot cyclic tests are intended to show the test valve assembly operability as for cold cyclic tests, but including imposed conditions of elevated system temperature, in excess of 200°F (93°C).

Test Requirements

- C.1 The test fluid shall be as described in A.2.
- C.2 The test fluid temperature shall be the highest temperature for which the test valve assembly is to be qualified. Test fluid and valve metal temperature shall be allowed to reach steady state before testing and shall be maintained during testing.
- C.3 The test valve assembly shall be operated according to the following requirements and sequence:
- C.3.1 One operating cycle, utilizing such voltage or actuating pressure, resulting in the nominal torque that is available, consisting of closing against internal pressure\* followed by opening with a differential pressure\* in normal direction across the test valve assembly.
- C.3.2 Three operating cycles utilizing such voltage or actuating pressure, resulting in the minimum torque that is available, closing against internal pressure\* followed by opening with a differential pressure in normal direction across the test valve assembly.
- C.4 While the test valve assembly is pressurized\*, it shall be closed utilizing such voltage or actuating pressure, resulting in the maximum torque that is available to seat the valve, and with the system at test pressure. The test valve assembly shall then be allowed to cool to 125°F (52°C) or lower. The test valve assembly shall then be opened, unseating against differential pressure\* utilizing such voltage or actuating pressure resulting in the minimum torque that is available.

---

\*Internal pressure and differential pressure to be applied in cyclic testing shall be the maximum rated line pressure (corresponding to the test temperature) and differential operating pressure respectively for which the test valve assembly is to be qualified. The test valve must successfully open under each of two conditions: (1) with balanced pressure in the test valve assembly and (2) with maximum rated operating differential pressure across the valve closure in the direction producing the greatest resistance to opening, unless the valve is unidirectional, in which case the differential shall be in the normal direction, or the valve is symmetrical, in which case the differential may be in either direction. Differential pressure need not be maintained after the test valve assembly is unseated.

PART I  
APPENDIX D  
TEMPERATURE-PRESSURE TEST

Scope and Applicability

Temperature-pressure tests are intended to show that the test valve assembly is capable of meeting seat sealing requirements following exposure to test fluids of specified temperature-pressure conditions.

This test is applicable for isolation valves where the safety related function of the valve is to close and remain in the closed position.

Test Requirements

- D.1 The test fluid shall be as described in A.2.
- D.2 The test fluid temperature shall be the highest temperature for which the test valve assembly is to be qualified.
- D.3 The test valve assembly shall be operated according to the following requirements and sequence.
  - D.3.1 Close test valve assembly utilizing such a voltage or actuating pressure resulting in the minimum torque that is available.
  - D.3.2 Expose closed test valve assembly to given temperature-pressure conditions.
  - D.3.3 Following exposure to temperature-pressure conditions, perform leakage test in accordance with Appendix "A".

PART I

APPENDIX E  
SEISMIC LOADING TEST

Scope and Applicability

The intent of this procedure is to show that a valve assembly will perform its function during and after specified loading. Seismic loading testing is required for each test valve assembly.

Test Requirements

- E.1 The test valve assembly may be mounted in any selected orientation.  
(See Paragraph 5.2)
- E.2 A static load shall be applied in line with the center of gravity of the valve operator. The static load shall equal twice the operator weight applied in the vertical direction (downward) and three times the operator weight in a direction parallel to the valve nozzle centerline applied simultaneously.
- E.3 A cold cyclic test shall be performed in accordance with Appendix B coincident with application of the loading specified in Paragraph E.2 above.



PART I  
APPENDIX F  
VIBRATION TEST

Scope and Applicability

The purpose of this test is to verify the test valve assembly operability when subjected to vibration.

Vibration testing is required of all test valve assemblies.

Test Requirements

- F.1 Except for the required cycling, tests F.2, F.3, and F.4 shall be performed with the test valve assembly in the normal operating positions for which the valve is to be qualified.
- F.2 Exploratory vibration test - Vibration shall be essentially sinusoidal with amplitudes to produce maximum acceleration of at least 0.2g (zero to peak). Exploratory vibration shall be performed by a sweep of the full frequency range at a rate not exceeding one octave per minute. Resonance shall be defined as a frequency at which acceleration of the actuator at the plane of the center of gravity perpendicular to the stem centerline exceeds the test acceleration value by a factor of 3 or more.
- F.3 The test frequencies at which resonances occur shall be noted and recorded.
- Variable frequency test - Tests shall be performed at a minimum force of 0.5 g (zero to peak) in the three mutually perpendicular axes at the following frequencies: 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz which are within the test frequency range determined in F.2. Tests shall also be performed at resonant frequencies. Operability of the test valve assembly shall be demonstrated by performing one operating cycle, as per B.2.1 except pressurization is not required, at each frequency.
- F.4 Endurance test - The test valve assembly shall be vibrated for a total of at least three minutes at each of the observed resonant frequencies with a minimum force at 0.5g (zero to peak) applied. At the conclusion of each endurance test, with the test valve assembly still vibrating, operability of the test valve assembly shall be demonstrated by performing one operating cycle. The test shall be performed at 33 Hz in any of the three mutually perpendicular axes where resonant frequencies are not found.



PART II

HENRY PRATT COMPANY

FUNCTIONAL QUALIFICATION REPORT OF RESULTS

FOR

POWER OPERATED-SAFETY RELATED

ACTIVE BUTTERFLY VALVE ASSEMBLIES

Prepared for: Bechtel/Grand Gulf

## SELECTION OF TEST VALVE ASSEMBLIES FOR QUALIFICATION

### BECHTEL/GRAND GULF

Selection of test valve assemblies (parent valves) shown below will be qualified by actual testing described in Part I "Henry Pratt Functional Qualification Requirements for Power Operated Safety Related Active Butterfly Valve Assemblies".

Upon successful completion of the test program, a "Functional Qualification Report" will be issued for each of the selected test valve assemblies (parent valves) certifying that these valves are qualified by all appropriate testing.

Valve assemblies of similar design (candidate valves) will be qualified by certifying that the generic qualification rules are satisfied.

Active nuclear valves of this order can be sorted into one group based on design similarity:

#### 1. Pneumatically operated type 1100 valve assemblies

In accordance with the above grouping, the list below on the left shows the selected test valve assembly (parent valve) which will be subjected to the test program and the list on the right shows the generically qualified valves (candidate valves).

#### Group 1 - Pneumatically Operated Type 1100 Valves

<u>Qualified Test Valve (Parent Valve)</u>	<u>Generically Qualified Valves (Candidate Valves)</u>
1. D-0089-4 12" 1100 (NXL) with 721C-SR-80-12	D-0089-5 12" 1100 (NXL) with 721C-SR-80-12

## SELECTION OF TEST VALVE ASSEMBLIES FOR QUALIFICATION

### BECHTEL/GRAND GULF

Selection of test valve assemblies (parent valves) shown below will be qualified by actual testing described in Part I "Henry Pratt Functional Qualification Requirements for Power Operated Safety Related Active Butterfly Valve Assemblies".

Upon successful completion of the test program, a "Functional Qualification Report" will be issued for each of the selected test valve assemblies (parent valves) certifying that these valves are qualified by all appropriate testing.

Valve assemblies of similar design (candidate valves) will be qualified by certifying that the generic qualification rules are satisfied.

Active nuclear valves of this order can be sorted into one group based on design similarity:

#### 1. Pneumatically operated type 1100 valve assemblies

In accordance with the above grouping, the list below on the left shows the selected test valve assembly (parent valve) which will be subjected to the test program and the list on the right shows the generically qualified valves (candidate valves).

#### Group 1 - Pneumatically Operated Type 1100 Valves

<u>Qualified Test Valve (Parent Valve)</u>	<u>Generically Qualified Valves (Candidate Valves)</u>
1. D-0089-4 12" 1100 (NXL) with 721C-SR-80-12	D-0089-5 12" 1100 (NXL) with 721C-SR-80-12

# TEST INSTRUMENTATION AND CALIBRATION DATA

<u>Item No.</u>	<u>Item Identification</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Mfg. Serial No.</u>	<u>HPCo Serial No.</u>	<u>HPCo Calibration Procedure No.</u>
1	Pressure Gauge	Robert Shaw	313D 0 - 600 psig	N/A	L-28	QAP 2 Para. 8.15.2
2	Pressure Gauge	Robert Shaw	313D 0 - 160 psig	N/A	L-29	QAP 2 Para. 8.15.2
3	Pressure Gauge	Robert Shaw	T21-313B 0 - 300 psig	N/A	L-30	QAP 2 Para. 8.15.2
4	Pressure Gauge	Robert Shaw	T21-313B 0 - 800 psig	N/A	L-31	QAP 2 Para. 8.15.2
5	Pressure Gauge	Robert Shaw	T21-313B 0 - 800 psig	N/A	L-32	QAP 2 Para. 8.15.2
6	Pressure Gauge	Robert Shaw	T21-313B 0 - 800 psig	N/A	L-33	QAP 2 Para. 8.15.2
7	Pressure Gauge	Robert Shaw	T21-313B 0 - 1,500 psig	N/A	L-34	QAP 2 Para. 8.15.2
8	Pressure Gauge	Robert Shaw	T21-313B 0 - 1,500 psig	N/A	L-35	QAP 2 Para. 8.15.2
9	Pressure Gauge	Robert Shaw	T21-313B 0 - 1,500 psig	N/A	L-36	QAP 2 Para. 8.15.2
10	Pressure Gauge	Robert Shaw	T21-313B 0 - 400 psig	N/A	L-37	QAP 2 Para. 8.15.2
11	Pressure Gauge	Robert Shaw	T21-313B 0 - 400 psig	N/A	L-38	QAP 2 Para. 8.15.2
12	Pressure Gauge	Robert Shaw	T21-313B 0 - 400 psig	N/A	L-39	QAP 2 Para. 8.15.2
13	Dead Weight Tester	Ashcroft	1305B 0 - 10,000 psig	1HA09029	DWT #1	QAP 2 Para. 8.10
14	Motor Controller	Arwal Control	N/A	N/A	L-EMC-1001	QAP 2 Para. 8.28
15	Circuit Tester	Weston	785	851	851	QAP 2 Para. 8.19
16	Potentiometer	Leeds and Northrup	-200 to 1000 <sup>0</sup> F	1316771	1316771	QAP 2 Para. 8.30

PART II

Section 1 A


FUNCTIONAL QUALIFICATION REPORT  
FOR  
QUALIFIED TEST VALVE ASSEMBLY (QTVA)

Job. No. D-0089-4

Prepared By: Henry B. Washburn 11-8-79  
Date

Reviewed By: Walter J. Selmer 11-9-79  
Date

Certified By: Sam H. Zarda 11/9/79  
Date



PART II

Section L A **ADD-ON**

FUNCTIONAL QUALIFICATION REPORT

FOR

QUALIFIED TEST VALVE ASSEMBLY (QTVA)

Job No. D-0089-A

Page No.

- |  |            |                     |    |
|--|------------|---------------------|----|
| 1. Description and Characteristics of QTVA   |            |                     | 1  |
| 2. Base Line Data of QTVA to be used for Generic Qualification of GFVA                             |            |                     | 2  |
| Results of Qualification Rules of Paragraph 1.3.8 and 1.3.9  |            |                     | 3  |
| 3. Copy of Functional Qualification Report of Actuator to Show Compliance to IEEE 344 and IEEE 382 |            |                     | 4  |
| 4. Test Plan Results:  |            | <u>Date of Test</u> |    |
| 4.1 Valve Leakage Test   | Appendix A | <u>10-2-79</u>      | 5  |
| 4.2 Cold Cyclic Test   | Appendix B | <u>10-3-79</u>      | 8  |
| 4.3 Seismic Loading Test   | Appendix E | <u>10-4-79</u>      | 11 |
| 4.3.7 Valve Leakage  | Appendix A | <u>10-5-79</u>      | 14 |
| 4.4 Vibration Test   | Appendix F | <u>8-20-79</u>      | 17 |
| 5. Dimensional Data Summary for Qualification Rules of Paragraph 1.3.8 and 1.3.9                   |            |                     |    |

THIS TEST VALVE ASSEMBLY WAS SUBJECTED TO ALL APPROPRIATE TEST REQUIREMENTS (PART I, PARAGRAPH 7.0) AND IT IS CONSIDERED A QUALIFIED TEST VALVE ASSEMBLY

Job No. D-0089-4

I. • DESCRIPTION AND CHARACTERISTICS

Valve Size and Type

12" NXL (1100)

Standard Pressure Class

150

Cold Working Pressure

275 psi

Rated Differential Pressure

200 psi

Maximum Service Temperature

200 °F

Actuator Type

— Electric  
Motor

✓

Air

Actuator Size

721C-80-12

Normal Motive Power

— Vac

110

psi

Minimum Motive Power

— Vac

80

psi

Maximum Motive Power

— Vac

110

psi



2. BASE LINE DATA OF QTVA TO BE USED FOR GENERIC QUALIFICATION OF GFVA

Reference  
Paragraph

1.3.1 Valve Size

12" NXL (1100)

1.3.2 Seat Taper Angle

15°

1.3.3 Disc/Seat Interference

.030

1.3.4 Seating Surface Materials

STAINLESS STEEL/EPT

1.3.5 Materials of Construction

Body

ASME SA-516 GR.70

Disc

ASME SA-516 GR.70

Shaft

ASME SA-564 TY. 630-H1150

Bearing

ASTM A-438 GR. 1 TYPE 2.

Seat

EPT

Retainer Segments

—

Packing

EPT

Thrust Collar

SAE 660 BRONZE

Bottom Cover

ASME SA-516 GR.70

Bonnet

ASTM A-36

Bolts: Valve to bonnet

SAE GR.8

Bonnet to Actuator

SAE GR.8

Adaptor plate to actuator

—

1.3.6 Actuator Rated Torque @ 80 PSI

3420

Calculated Operator Torque

2750

Ratio = 1.24

Operating Time

Open to Close

4

Sec.

Close to Open

4

Sec.

RESULTS OF QUALIFICATION RULES 1.3.8 and 1.3.9 FOR QTVA

Rule 1.3.8

- a.  $S_1 = \underline{36000}$  Yield strength of bonnet material  
 $S_2 = \underline{5187}$  Calculated bonnet stress  
 $S_1/S_2 = \underline{6.9} > 1$
- b.  $S_3 = \underline{120000}$  Yield strength (proof load) of bonnet to valve bolting  
 $S_4 = \underline{46848}$  Calculated stress of bonnet to valve bolting  
 $S_3/S_4 = \underline{2.56} > 1$
- c.  $S_5 = \underline{120000}$  Yield strength (proof load) of to bonnet bolting  
 $S_6 = \underline{36077}$  Calculated stress of to bonnet bolting  
 $S_5/S_6 = \underline{3.33} > 1$
- d.  $S_7 = \underline{\quad}$  Yield strength (proof load) of actuator to adapter plate bolting  
 $S_8 = \underline{\quad}$  Calculated stress of actuator to adapter plate bolting  
 $S_7/S_8 = \underline{\quad} > 1$

Rule 1.3.9

- $\Delta_L$  of QTVA = .00105" Deflection of test valve  
 $\Delta_L$  of QTVA .002"

Reference Addendum 1 & 2 for equations used to determine stresses and deflection for Rules 1.3.8 and 1.3.9.

Job No. D-0089-4

3. COPY OF FUNCTIONAL QUALIFICATION REPORT OF ACTUATOR TO  
SHOW COMPLIANCE TO IEEE 344 and IEEE 382

Reference

Paragraph

1.3.7

Job No. D-0089-4

## STATEMENT OF CERTIFICATION

### QUALIFICATION TESTING

GH-BETTIS Actuator Model N-721C-SR80 is hereby certified to be of the same construction as Bettis Actuator Model N-732C-SR80 which was qualified to the requirements of ANSI 278.2.1, Draft 3, Rev. 0, Feb. 1977 (IEEE 382) with the exception of LOCA by testing at Southwest Research Institute, San Antonio, Texas. Applicable test margins as described in paragraph 6.3.1.5 of IEEE 323-1974 were utilized with the exception of (8). Refer to SWRI Test Report No. 02-4854-RPT-1.

The LOCA testing required to complete the qualification program is scheduled to begin at Wyle Laboratories, Huntsville, Alabama on September 11. Upon successful completion of that testing a revised statement of certification will be issued referencing the applicable test report number.

### SEISMIC ANALYSIS

In addition to the seismic test results obtained in the above referenced tests, Bettis Seismic Analysis Report No. R-1062-25 Rev.A is offered as further supportive evidence to the rigidity of this actuator.

*Joel D. Page*

---


JOEL D. PAGE  
Senior Engineer  
Nuclear Products

JP/ksy  
8-31-78

Job No. D-0089-4

## VALVE LEAKAGE TEST

- 4.1.0 To demonstrate valve shut-off capability and pressure boundary meeting applicable leakage tolerances (para. 3.1). Test valve assembly to be mounted on test stand with the valve shaft oriented horizontally as shown in Figure 1.



- FIGURE 1

### 4.1.1 Pre-Test Inspection

- 4.1.2 Adjust limit switches for proper open and closed positions of valve disc.

- 4.1.3 Measure normal motive power to actuator.

— Vac. 100 psi

- 4.1.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>95</u>	Measured <u>95</u>
Bonnet to <del>adaptor plate</del>	Required <u>—</u>	Measured <u>—</u>
<del>Adaptor plate to actuator</del>	Required <u>95</u>	Measured <u>95</u>
Adaptor plate to trunnion	Required <u>—</u>	Measured <u>—</u>
Bottom cover to trunnion	Required <u>95</u>	Measured <u>95</u>

- 4.1.5 Verify calibration of required test equipment.

4.1.6 Test Procedure (Appendix A)

- a. With the test valve assembly in the most adverse position (as shown in Figure 1) operate the valve with normal motive power starting from full closed position three operating cycles.

Measure and Record:

Motive Power	<u>—</u> Vac.	<u>100</u> psi	
Operating Time	Cycle #1	Cycle #2	Cycle #3
Closed to Open	<u>2.3</u> sec.	<u>2.3</u> sec.	<u>2.3</u> sec.
Open to Closed	<u>2.4</u> sec.	<u>2.4</u> sec.	<u>2.4</u> sec.

- b. Repeat Step a with minimum motive power.

Motive Power	<u>—</u> Vac.	<u>80</u> psi	
Operating Time	Cycle #1	Cycle #2	Cycle #3
Closed to Open	<u>3.1</u> sec.	<u>3.0</u> sec.	<u>3.1</u> sec.
Open to Closed	<u>2.3</u> sec.	<u>2.4</u> sec.	<u>2.4</u> sec.

- c. With the valve disc in the closed position, cover the disc with a pool of water deep enough to submerge disc/seat interference line.
- d. Using air as test fluid, pressurize valve assembly to 200 psi differential pressure across disc. Hold pressure for a minimum time of five minutes (A-3). Observe and record leakage (A-4). Bubble tight condition of valve seat is considered a successful qualification of the TVA.

Leakage NONE Bubble Tight To AT LEAST 200 PSI

- e. Repeat steps c and d with pressure on opposite side of valve disc for bi-directional qualification

Leakage NONE Bubble Tight To AT LEAST 200 PSI

Job No. D-0089-A

- f. For the packing leak test the TVA is to be sandwiched in between two test heads as shown in Figure 2.




FIGURE 2

- g. With normal motive power applied to the actuator, cycle the TVA 10 times. Record cycle time for the first and tenth cycles.

Record:

Motive power	<u>—</u> Vac.	<u>100</u> psi
1st Cycle	Open to Close	<u>2.4</u> sec.
	Close to Open	<u>2.3</u> sec.
10th Cycle	Open to Close	<u>2.3</u> sec.
	Close to Open	<u>2.3</u> sec.

- h. With the valve disc in the open position, pressurize test valve assembly to cold working pressure of 275 psi using air as test fluid. Hold cold working pressure for a time period of 5 minutes. Observe leakage by applying soap solution around packing. Soap bubble tight condition of packing is considered successful qualification of TVA.

Leakage Observed NONE


Soap Bubble Tight TO ATLEAST  
275 PSI



Job No. D-0089-4

#### 4.2.0 Cold Cyclic Test

To demonstrate cyclic operability of the TVA (3.2) under the most adverse combination of motive power and system pressure. The test valve assembly is to be sandwiched between two test heads with the valve shaft oriented horizontally as shown in Figure 3.



#### 4.2.1 Pre-Test Inspection

4.2.2 Adjust limit switches for proper closed and open position of valve disc.

4.2.3 Measure motive power to actuator.

— Vac. 100 psi

4.2.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>95</u>	Measured <u>95</u>
Bonnet to <del>adapter plate</del>	Required <u>—</u>	Measured <u>—</u>
<del>Adapter plate to actuator</del>	Required <u>95</u>	Measured <u>95</u>
Adapter plate to trunnion	Required <u>—</u>	Measured <u>—</u>
Bottom cover to trunnion	Required <u>95</u>	Measured <u>95</u>

4.2.5 Verify calibration of required test equipment.

Job No. D-0089-4

4.2.6 Test Procedure (Appendix B)

- a. With the valve disc in the full open position pressurize pressure chamber A & B (Figure 3) to cold working pressure of 275 psi using air as test fluid. With minimum motive power of — Vac or 80 psi applied to actuator operate valve disc to full closed position.
- b. Reduce air pressure to 75 psi in pressure chamber B, and to 275 psi in pressure chamber A, to obtain a differential pressure of 200 psi across the closed valve disc.
- c. With minimum motive power of — Vac or 80 psi applied to actuator, open valve disc.
- d. Repeat steps a, b, and c twice.
- e. Data to be Recorded.

In step "a"	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Motive Power	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	( <u>80</u> psi	<u>80</u> psi	<u>80</u> psi
Operating Time			
Open to Close	<u>2.1</u> sec	<u>2.3</u> sec	<u>2.2</u> sec
In step "b"			
Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>75</u> psi	<u>75</u> psi	<u>75</u> psi
Motive Power	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	( <u>80</u> psi	<u>80</u> psi	<u>80</u> psi
Operating Time			
Close to Open	<u>3.1</u> sec	<u>3.1</u> sec	<u>3.0</u> sec

Job No. D-0089-A

f. Repeat steps a to d using nominal motive power of — Vac or 100 psi.

g. Data to be Recorded

Step f, a	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Motive	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	( <u>100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Open to Close	<u>2.5</u> sec	<u>2.5</u> sec	<u>2.6</u> sec
---------------	----------------	----------------	----------------

Step f, b

Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>75</u> psi	<u>75</u> psi	<u>75</u> psi
Motive	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	( <u>100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Close to Open	<u>2.3</u> sec	<u>2.3</u> sec	<u>2.3</u> sec
---------------	----------------	----------------	----------------

h. With the test valve assembly depressurized and maximum power of — Vac or 110 psi applied to actuator, perform three operating cycles.

Data to be recorded:

Operating Time	1st Cycle	2nd Cycle	3rd Cycle
Open to Close	<u>2.6</u> sec	<u>2.6</u> sec	<u>2.7</u> sec
Close to open	<u>2.0</u> sec	<u>2.1</u> sec	<u>2.1</u> sec

i. Measured operating times within operating times specified in paragraph 1.3.6 are considered successful qualification of the test valve assembly.

- 4.3.0 To demonstrate cyclic operability of TVA under the most adverse combination of motive power, system pressure and loading representative of the maximum seismic incident, the test valve assembly is sandwiched between two test heads as shown in Figure 4.




FIGURE 4

4.3.1 Pre-Test Inspection

4.3.2 Adjust limit switches for proper closed and open position of valve disc.

4.3.3 Measure motive power to actuator

— Vac 100 psi

4.3.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>95</u>	Measured <u>95</u>
Bonnet to <del>adapter plate</del>	Required <u>—</u>	Measured <u>—</u>
<del>Adapter plate</del> to actuator	Required <u>95</u>	Measured <u>95</u>
Adaptor plate to trunnion	Required <u>—</u>	Measured <u>—</u>
Bottom cover to trunnion	Required <u>95</u>	Measured <u>95</u>

Job No. D-0089-4

4.3.5 Test Procedure (Appendix E)

- a. The test valve assembly is subjected to a static load equivalent to 5 times the weight of the actuator applied simultaneously in each of the three mutually perpendicular axes through the center of gravity of the actuator and in the least rigid direction of the yoke. The least rigid direction of the yoke is determined as the direction of the yoke having the smaller moment of inertia.
- b. With the static load applied as described in Paragraph (a) and with the valve disc in the full open position, pressurize pressure Chamber A and B to a cold working pressure 275 psi. Use air as test fluid. With minimum motive power of — Vac or 80 psi applied to actuator, operate valve disc to full closed position.
- c. Reduce air pressure to 75 psi in pressure Chamber B and 275 psi in pressure Chamber A to obtain a differential pressure of 200 psi across valve disc.
- d. With minimum motive power of — Vac or 80 psi applied to actuator, open valve disc.
- e. Repeat Steps a, b, and c twice.
- f. Data to be recorded:

In Step A

Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Motive Power	<u>—</u> Vac	<u>—</u> Vac	<u>—</u> psi
	<u>80</u> psi	<u>80</u> psi	<u>80</u> psi

Operating Time

Open to Close	<u>2.3</u> sec	<u>2.3</u> sec	<u>2.4</u> sec
---------------	----------------	----------------	----------------

Job No. D-0089-4

In step b	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>75</u> psi	<u>75</u> psi	<u>75</u> psi
Motive Power	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	<u>(80</u> psi	<u>80</u> psi	<u>80</u> psi

Operating Time

Close to Open 3.0 sec 3.0 sec 3.0 sec

- g. Repeat steps a to d using normal motive power of — Vac or 100 psi.

- h. Data to be Recorded

Step g, b

Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Motive Power	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	<u>(100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Open to Close 2.7 sec 2.5 sec 2.6 sec

Step g, c

Pressure in Chamber A	<u>275</u> psi	<u>275</u> psi	<u>275</u> psi
Pressure in Chamber B	<u>75</u> psi	<u>75</u> psi	<u>75</u> psi
Motive Power	( <u>—</u> Vac	<u>—</u> Vac	<u>—</u> Vac
	<u>(100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Close to Open 2.3 sec 2.2 sec 2.1 sec

1. With the test valve assembly depressurized and maximum motive power of — Vac or 110 psi applied to actuator, perform three operating cycles.



Job No. D-0089-4

Data to be recorded:

Operating time	1st Cycle	2nd Cycle	3rd Cycle
Open to Close	<u>2.4</u> sec	<u>2.7</u> sec	<u>2.7</u> sec
Close to Open	<u>1.9</u> sec	<u>1.9</u> sec	<u>1.9</u> sec

- j. Measured operating times within operating times specified in paragraph 1.3.6 are considered successful qualification of the test valve assembly.

#### 4.3.6 Valve Leakage Test

To demonstrate that the test valve is capable of meeting seat and shaft packing sealing requirements after exposure to the most adverse combination of motive power, system pressure and seismic loading tests, the test valve assembly is mounted on test stand with the valve shaft oriented horizontally as shown in Figure 5.




FIGURE 5

#### 4.3.7 Pre-Test Inspection

4.3.8 Adjust limit switches for proper open and closed positions of valve disc.

4.3.9 Measure normal motive power to actuator.

— Vac 100 psi.



Job No. D-0089-4

4.3.10 Measure required torque setting of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>95</u>	Measured <u>95</u>
Bonnet to <del>adapter</del> plate	Required <u>—</u>	Measured <u>—</u>
<del>Adaptor</del> plate to actuator	Required <u>95</u>	Measured <u>95</u>
Adaptor plate to trunnion	Required <u>—</u>	Measured <u>—</u>
Bottom cover to trunnion	Required <u>95</u>	Measured <u>95</u>

4.3.11 Verify calibration of required test equipment.

4.3.12 Test Procedure (Appendix A)

- a. With the test valve assembly in the most adverse position (as shown in Figure 1) operate the valve with normal motive power starting from full closed position three operating cycles.

Data to be Recorded

Motive Power	<u>—</u> Vac	<u>100</u> psi	
Operating Time	1st Cycle	2nd Cycle	3rd Cycle
Closed to Open	<u>2.3</u> sec	<u>2.3</u> sec	<u>2.3</u> sec
Open to Closed	<u>2.4</u> sec	<u>2.4</u> sec	<u>2.4</u> sec

- b. Repeat step a with minimum motive power.

Motive Power	<u>—</u> Vac	<u>80</u> psi	
Operating Time	1st Cycle	2nd Cycle	3rd Cycle
Closed to Open	<u>3.1</u> sec	<u>3.0</u> sec	<u>3.1</u> sec
Open to Closed	<u>2.3</u> sec	<u>2.4</u> sec	<u>2.4</u> sec

- c. With the valve disc in the closed position, cover the disc with a pool of water deep enough to submerge disc/seal interference line.
- d. Using air as test fluid, pressurize valve assembly to 200 psi differential pressure across disc. Hold pressure for a time period of five minutes (A-3). Observe and record leakage (A-4). Bubble tight condition of valve seat is considered a successful qualification of TVA.

Leakage Observed NONE

Bubble Tight TO ATLEAST 200 PSI

Job No. D-0089-4

- e. Repeat steps c and d with pressure on opposite side of valve disc for bi-directional qualification.

Leakage Observed NONE

Bubble Tight To ATLEAST 200 psi

- f. For the packing leak test the TVA is to be sandwiched between two test heads as shown in Figure 6.




FIGURE 6

- g. With normal motive power applied to the actuator, cycle the TVA 10 times. Record cycle time for the first and tenth cycles.

Data to be Recorded

Motive Power — Vac 100 psi

1st Cycle Open to Close 2.4 sec

Close to Open 2.3 sec

10th Cycle Open to Close 2.4 sec

Close to Open 2.4 sec

- h. With the valve disc in the open position, pressurize test valve assembly to cold working pressure of 275 psi using air as test fluid. Hold cold working pressure for a time period of 5 minutes. Observe leakage by applying soap solution around packing. Soap bubble tight condition of packing is considered successful qualification of TVA.

Leakage Observed NONE

Soap Bubble Tight To ATLEAST  
275 PSI

#### 4.5.0 Vibration Test

To demonstrate operability of the test valve assembly during and after vibratory disturbances, and to establish the validity of natural frequency calculations the test valve assembly is to be mounted on a seismic test machine with the valve shaft oriented horizontally. (Para. 5.2 of Qualification Requirements)

#### 4.5.1 Pre-Test Inspection

- a. Receiving inspection - Identification and visual inspection of TVA for evidence of damage due to shipping. To be performed in the presence of HPCo. representative.
- b. Description of test valve assembly mounting to seismic test machine - photograph of test apparatus to be included.
- c. Adjust limit switches for proper open and closed position of valve disc.
- d. Measure motive power to actuator.

— Vac      100 psi

- e. Describe test equipment and calibration methods including location and number of control and response accelerometers.

#### 4.5.2 Test Procedure

- a. With the test valve assembly mounted to the seismic test machine in the most adverse position (para. 5.2 of Qualification Requirements) operate valve with nominal motive power starting from full closed position.

Measure and record:

Motive power      — Vac      100 psi

Operating time

Closed to open      2.5 sec

Open to closed      2-6 sec

- b. Resonance search - A steady state sinusoidal resonant search to be performed in each of the three mutually perpendicular axis. Input test level amplitude to be at least 0.2g (zero to peak). The frequency range of 3.5 to 95 Hz to be covered with a sweep rate not exceeding one octave per minute. For the purpose of this test resonance is defined as a frequency at which acceleration of the actuator at the plane of the center of gravity perpendicular to the shaft centerline exceeds the input acceleration level by a factor of 3 or more.
- c. Variable frequency test - A variable frequency test to be performed with a minimum input test level of 0.5 g (zero to peak) in the mutually perpendicular axis of the following frequencies. 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz. At each of the above frequencies repeat step a and record motive power and each half of operating time.
- d. Endurance test - The test valve assembly to be vibrated with a minimum input of 0.5g (zero to peak) in the three mutually perpendicular axis at resonant frequencies found in step b and at 33 Hz, for a time period of three minutes. At the conclusion of each of the three minute vibration test with the test assembly still vibrating, operability of the test valve assembly to be demonstrated by performing step a.
- e. Measured operating times within operating time specified in paragraph 1.3.6 and rechecked in para. a are considered successful qualification of test valve assembly.

SEE ATTACHED WYLE LABORATORIES TEST  
REPORT DATED 8-20-79

#### 4.5.3 Explanation of Vibration Test Report:

- 4.5.3.1 The following Wyle Laboratories Test Report (No. 44679-1) shows transmissibility plots for various pairs of accelerometers.

In conjunction with the Bechtel approved procedure developed to show compliance with the requirements of specifications 9645-M-257.0, 9645-M-258.0 and paragraph 4.5.2B on page 18 of this report, a transmissibility factor of three or more defines a natural frequency for the valve/operator assembly.

The transmissibility plots on pages 21, 31 and 41 of the Wyle Seismic Simulation Test Report (No. 44679-1) show that in the three major axes of excitation, the lowest natural frequencies occur at 41 and 78 Hz for the X and Y axes, respectively. There were no natural frequencies found below 95 Hz in the Z axis.

The other plots of transmissibility are included for informational purposes only and are not intended to demonstrate valve/operator rigidity. First, those plots that include accelerometers HCA and VCA show the shaker table and mounting structure responses and cannot be applied to the valve assembly. Secondly, the plots that are of cross coupling (i.e. input acceleration in one direction and output acceleration measured in another direction) are not relevant to the structural rigidity.

Since the transmissibility plots on pages 21, 31 and 41 of Wyle Laboratories Seismic Simulation Report (No. 44679-1) show the absence of natural frequencies below 33 Hz, we certify that the valve and operator structure is a rigid body at frequencies below 33 Hz and that this report meets the requirements of Bechtel Specification No.'s 9645-M-257.0 and 9645-M-258.0.


SEISMIC SIMULATION TEST PROGRAM

ON

A 12" VALVE ASSEMBLY

FOR

HENRY PRATT COMPANY  
401 SOUTH HIGHLAND AVENUE  
AURORA, ILLINOIS 60507



# SEISMIC SIMULATION Test Report

REPORT NO. 44679-1  
WYLE JOB NO. 44679  
CUSTOMER  
P. O. NO. B8429  
PAGE 1 OF 60 PAGE REPORT  
DATE August 20, 1979  
SPECIFICATION (S) See References  
in Section 7.0

- 1.0 CUSTOMER Henry Pratt Company  
ADDRESS 401 South Highland Avenue, Aurora, Illinois 60507  
2.0 TEST SPECIMEN 12" Valve Assembly  
3.0 MANUFACTURER Henry Pratt Company  
4.0 SUMMARY

A 12" Valve Assembly, hereinafter called the specimen, was subjected to a Seismic Simulation Test Program as required by the Henry Pratt Purchase Order Number B8429, and Wyle Laboratories' Seismic Test Procedure 541/2014/DK, dated June 26, 1979, Revision A.

The test program consisted of single-axis sine sweep testing, single-axis variable frequency testing, and single-axis endurance testing. The specimen was instrumented with accelerometers and electrically and pneumatically powered and monitored for functional operation during the test program.

It was demonstrated that the specimen possessed sufficient integrity to withstand, without compromise of structure or function, the prescribed seismic environment.

STATE OF ALABAMA } Ala. Professional Eng.  
COUNTY OF MADISON } Reg. No. 6363  
James W. Foreman, being duly sworn,  
deposes and says: The information contained in this report is the result of  
complete and carefully conducted tests and is to the best of his knowledge true  
and correct in all respects.  
SEAL James W. Foreman  
SUBSCRIBED and sworn to before me this 24th day of August 1979  
Virginia R. Dent  
Notary Public in and for the County of Madison, State of Alabama.  
My Commission expires June 13, 1983

Wyle shall have no liability for damages of any kind to person or property, including special or consequential damages, resulting from Wyle's providing the services covered by this report.  
PREPARED BY B. F. Fowler  
APPROVED BY Heischel D. Jordan  
WYLE Q. A. M. Kimbrell

**WYLE LABORATORIES**  
SCIENTIFIC SERVICES AND SYSTEMS GROUP  
HUNTSVILLE, ALABAMA



4.0 SUMMARY (Continued)

Table I contains the test run descriptions, including test numbers, axes, frequencies, and input acceleration.

Photograph 1 shows the specimen mounted on the Wyle Multiaxis Seismic Simulator Table.

Photographs 2 and 3 show the specimen-mounted accelerometers.

Appendix I contains transmissibility plots of the specimen response accelerometers.

Appendix II contains the Instrumentation Log Sheets and the Instrumentation Equipment Sheets.

Appendix III contains the Wyle Seismic Test Procedure 541/2014/DK, dated June 26, 1979, Revision A.

5.0 TEST REQUIREMENTS

5.1 Specimen Mounting and Orientation

A 12" Valve Assembly, hereinafter called the specimen, shall be installed on Wyle's Multiaxis Seismic Simulator Table. The specimen shall be tested in the first horizontal (X) axis and then rotated 90 degrees about its vertical centerline for the second test orientation. The specimen valve stem shall remain horizontal during the test. The specimen shall be tested in the following sequence:

- 1) Pretest Functional
- 2) Sine Sweep [1st horizontal (X) axis]
- 3) Sine Sweep [vertical (Y) axis]
- 4) Variable Frequency Test [1st horizontal (X) axis]
- 5) Variable Frequency Test [vertical (Y) axis]
- 6) Endurance Test [1st horizontal (X) axis]
- 7) Endurance Test [vertical (Y) axis]
- 8) Post-Test Functional
- 9) Sine Sweep [2nd horizontal (Z) axis]
- 10) Variable Frequency Test [2nd horizontal (Z) axis]
- 11) Endurance Test [2nd horizontal (Z) axis]
- 12) Post-Test Functional

5.2 Sine Sweep Test

A sine sweep test (approximately 0.2 g) from 3.5 to 95 Hz shall be performed in each of the three orthogonal axes. The sweep rate shall be one octave per minute.

5.3 Variable Frequency Test

A variable frequency (sine dwell) test shall be performed in each of the three orthogonal axes. The input test level shall be approximately 0.5 g (within the limitations of the test machine) at the following frequencies: 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz. Duration of the test shall be sufficient to allow the specimen to cycle close to open to close.

5.0 TEST REQUIREMENTS (Continued)

5.4 Endurance Test

An endurance test (sine dwell) shall be performed in each of the three orthogonal axes. The input test level shall be approximately 0.5 g (within the limitations of the test machine) at the resonant frequencies\* found in Paragraph 5.2 and at 33 Hz. Duration of the test shall be at least three (3) minutes.

\*Resonant frequencies are defined as a frequency at which the acceleration of the actuator center of gravity exceeds the input acceleration level by a factor of 3 or more.

5.5 Specimen Response

Six (6) specimen-mounted uniaxial piezo-electric accelerometers shall be provided for the specimen during the test. Placement of the accelerometers shall be as directed by the Henry Pratt Technical Representative or the Wyle Test Engineer. The accelerometers shall be recorded on FM tape and oscillograph recorders during the sine sweep test. Transmissibility plots of these accelerometers shall be provided in the test report.

5.6 Electrical Powering

Standard electrical power of 120 VAC shall be provided for the specimen.

5.7 Pneumatics

Air at a pressure of 80-110 psig shall be provided for the specimen.

5.8 Electrical Monitoring

Two (2) electrical monitoring channels shall be provided for the specimen. One (1) of the electrical monitoring channels shall monitor the solenoid voltage for the actuator. One (1) channel shall consist of a potentiometer used to monitor the shaft position of the specimen. The electrical monitoring channel and the output of the potentiometer shall be recorded on an oscillograph recorder.

5.9 Functional Tests

The specimen shall be operated prior to and after the test program and the cycling time recorded. During the variable frequency test and at the conclusion of the endurance test (after each 3-minute test), the specimen shall be operated and the cycling time recorded.

6.0 TEST PROCEDURES AND RESULTS

6.1 Specimen Mounting and Orientation Procedures

The specimen, described in Paragraph 5.1, was installed on Wyle's Multi-axis Seismic Simulator Table. The specimen was tested in the X and Y axes and then rotated 90 degrees about its vertical centerline for testing in the Z axis (see Photograph 1 for orientation of axes). The specimen was attached to a Wyle-fabricated fixture such that its valve stem remained horizontal throughout the test. Specimen mounting simulated in-service mounting conditions as closely as practical. The specimen was tested as shown below:

- 1) Pretest Functional
- 2) Sine Sweep (X axis)
- 3) Sine Sweep (Y axis)
- 4) Variable Frequency Test (X axis)
- 5) Variable Frequency Test (Y axis)
- 6) Endurance Test (X axis)
- 7) Endurance Test (Y axis)
- 8) Post-Test Functional
- 9) Sine Sweep (Z axis)
- 10) Variable Frequency Test (Z axis)
- 11) Endurance Test (Z axis)
- 12) Post-Test Functional

6.2 Sine Sweep Test Procedures

A low-level (approximately 0.2 g) single-axis sine sweep test, from 3.5 Hz to 95 Hz, was performed in each test axis to establish major resonances. The sweep rate was one octave per minute.

6.2.1 Sine Sweep Test Results

A description of the sine sweep tests, including test numbers, axes and input accelerations, are contained in Table I.

6.0 TEST PROCEDURES AND RESULTS (Continued)

6.2 Sine Sweep Test Procedures (Continued)

6.2.1 Sine Sweep Test Results (Continued)

Transmissibility plots of the specimen response accelerometers divided by the control accelerometers from the sine sweep tests are presented in Appendix I. In addition, transmissibility plots of the actuator center of gravity response accelerometer divided by the valve body response accelerometer are included in Appendix I.

It was demonstrated that the specimen possessed sufficient integrity to withstand the sine sweep tests without compromise of structure function.

6.3 Variable Frequency Test Procedures

A variable frequency (sine dwell) test was performed in each of the three orthogonal axes. The input test level was 0.5 g at the following frequencies: 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz. Duration of the test was sufficient to allow the specimen to cycle close to open to close.

6.3.1 Variable Frequency Test Results

It was demonstrated that the specimen possessed sufficient integrity to withstand, without compromise of structure or function, the prescribed simulated environment.

A description of the variable frequency tests, including test numbers, axes, frequencies, and input accelerations are contained in Table I.

6.4 Endurance Test Procedures

An endurance test (sine dwell with 0.5 g input) was performed in each of the three orthogonal axes at resonant frequencies\* found in Paragraph 6.2 and at 33 Hz. Duration of the test was three (3) minutes. The specimen was cycled close to open to close after three minutes while the specimen was still vibrating.

\*Resonant frequencies were defined as a frequency at which the acceleration of the actuator center of gravity exceeded the valve body acceleration level by a factor of 3 or more.

6.4.1 Endurance Test Results

The specimen demonstrated sufficient integrity to withstand the endurance test without compromise of structure or function.

A description of the endurance tests, including test numbers, axes, frequencies, and input accelerations, are contained in Table I.

6.0 TEST PROCEDURES AND RESULTS (Continued)

6.5 Specimen Response Procedures

Six (6) specimen-mounted uniaxial piezo-electric accelerometers were provided for the specimen during the test. Placement of the accelerometers was directed by the Henry Pratt Technical Representative. The accelerometers were recorded on FM tape and oscillograph recorders during the sine sweep test.

Photographs 2 and 3 show the accelerometer locations.

6.5.1 Specimen Response Results

Transmissibility plots of the specimen response accelerometers divided by the control accelerometers from the sine sweep tests are presented in Appendix II.

6.6 Electrical Powering Procedures

Standard electrical power of 120 VAC was provided for the specimen to actuate the solenoid valve.

6.7 Pneumatics Procedures

Air at a pressure of 80-110 psig was provided for the specimen.

6.7.1 Pneumatics Results

Air pressure readings taken prior to the open and close cycles are contained in Appendix I.

6.8 Electrical Monitoring Procedures

Two (2) electrical monitoring channels were provided for the specimen during the seismic testing. One (1) of the electrical monitoring channels monitored the solenoid voltage for the actuator and one (1) channel consisted of a potentiometer used to monitor the shaft position of the specimen. The electrical monitoring channel and the output of the potentiometer were recorded on an oscillograph recorder.

6.8.1 Electrical Monitoring Results

It was demonstrated that the specimen possessed sufficient integrity to withstand, without compromise of electrical function, the simulated seismic environment.

6.0 TEST PROCEDURES AND RESULTS (Continued)

6.9 Function Tests

The specimen was operated prior to and after the test program and the cycling time recorded. During the variable frequency test and at the conclusion of the endurance test, the specimen was operated and the cycling time recorded.

Functional Test Results

The cycling time in going from close to open ranged between 1.0 and 1.7 seconds. The cycling time in going from open to close ranged between 0.42 and 0.50 seconds.

Cycling times are contained in Table I.




7.0 REFERENCES

- 7.1 The Henry Pratt Purchase Order Number B8429.
- 7.2 Wyle Laboratories' Seismic Test Procedure 541/2014/DK, dated June 26, 1979,  
Revision A.


TABLE I  
TEST RUN DESCRIPTIONS

TEST NO.	TYPE OF TEST	AXIS	INPUT ACCELERATION (G)	PRESSURE (PSIG)		FREQUENCY (HZ)	STROKE TIME (SEC)	
				OPEN	CLOSE		OPEN	CLOSE
1	Sine Sweep	X	0.2	-	-	3.5-95	-	-
2	Sine Sweep	Y	0.2	-	-	3.5-95	-	-
3	Variable Frequency	X	0.5	84	80	3.5	1.5	0.45
4	Variable Frequency	X	0.5	86	86	4.5	1.2	0.48
5	Variable Frequency	X	0.5	100	96	6.0	1.1	0.45
6	Variable Frequency	X	0.5	102	100	8.0	1.05	0.45
7	Variable Frequency	X	0.5	90	80	11.0	1.2	0.48
8	Variable Frequency	X	0.5	82	80	15.0	1.5	0.45
9	Variable Frequency	X	0.5	90	86	21.0	1.4	0.45
10	Variable Frequency	X	0.5	98	94	29.0	1.2	0.45
11	Variable Frequency	X	0.5	102	100	39.0	1.05	0.48
12	Variable Frequency	X	0.5	88	80	53.0	1.4	0.50
13	Variable Frequency	X	0.5	86	80	71.0	1.4	0.42
14	Variable Frequency	X	0.5	88	82	95.0	1.4	0.42
15	Variable Frequency	Y	0.5	102	97	3.5	1.1	0.45
16	Variable Frequency	Y	0.5	100	88	4.5	1.2	0.48
17	Variable Frequency	Y	0.5	80	80	6.0	1.7	0.48
18	Variable Frequency	Y	0.5	88	82	8.0	1.3	0.45
19	Variable Frequency	Y	0.5	90	86	11.0	1.2	0.45
20	Variable Frequency	Y	0.5	94	90	15.0	1.1	0.48
21	Variable Frequency	Y	0.5	100	96	21.0	1.1	0.48
22	Variable Frequency	Y	0.5	103	97	29.0	1.1	0.45
23	Variable Frequency	Y	0.5	104	100	39.0	1.0	0.48
24	Variable Frequency	Y	0.5	92	82	53.0	1.3	0.45
25	Variable Frequency	Y	0.5	82	80	71.0	1.5	0.48
26	Variable Frequency	Y	0.5	90	86	95.0	1.2	0.48
27	Endurance Test	X	0.5	88	80	33.0	1.3	0.45
28	Endurance Test	X	0.5	103	99	41.0	1.1	0.45
29	Endurance Test	X	0.5	88	82	52.0	1.3	0.45
30	Endurance Test	Y	0.5	80	80	33.0	1.6	0.45
31	Endurance Test	Y	0.5	100	96	33.0	1.1	0.48
32	Endurance Test	Y	0.5	84	80	88.0	1.45	0.48
33	Sine Sweep	Z	0.2	-	-	3.5-95	-	-
34	Variable Frequency	Z	0.5	100	86	3.5	1.2	0.48
35	Variable Frequency	Z	0.5	94	86	4.5	1.2	0.45
36	Variable Frequency	Z	0.5	102	94	6.0	1.1	0.45
37	Variable Frequency	Z	0.5	104	99	8.0	1.0	0.48
38	Variable Frequency	Z	0.5	103	91	11.0	1.1	0.45
39	Variable Frequency	Z	0.5	88	80	15.0	1.3	0.42
40	Variable Frequency	Z	0.5	96	88	21.0	1.2	0.45
41	Variable Frequency	Z	0.5	102	84	29.0	1.1	0.48
42	Variable Frequency	Z	0.5	105	99	39.0	1.1	0.48
43	Variable Frequency	Z	0.5	92	83	53.0	1.3	0.46
44	Variable Frequency	Z	0.5	106	96	71.0	1.1	0.48
45	Variable Frequency	Z	0.5	104	100	95.0	1.1	0.48
46	Endurance Test	Z	0.5	90	84	33.0	1.3	0.48
47	Endurance Test	Z	0.5	86	79	38.0	1.4	0.42




PHOTOGRAPH 1

TEST SETUP



PHOTOGRAPH 2

ACCELEROMETER LOCATIONS, 1X, 2Y, 3Z



PHOTOGRAPH 3

ACCELEROMETER LOCATIONS 3X, 4Y, 5Z

APPENDIX I


TRANSMISSIBILITY PLOTS

Test Run 1	X Axis (Longitudinal)
Test Run 2	Y Axis (Vertical)
Test Run 33	Z Axis (Lateral)

HCA = Horizontal Control Accelerometer  
VCA = Vertical Control Accelerometer

# FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LONG

ACCEL NO. 1 LONG NO. HCA  
TEST RUN NO. 1



FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐



SPECIMEN 12"


AXIS LONG

ACCEL NO. 2407 NO. HCA

TEST RUN NO. 1

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 2"

AXIS LONG

ACCEL NO. 3LAT NO. NCA

TEST RUN NO. 1


## FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐SPECIMEN 12"AXIS LONGACCEL NO. 4 Long NO. HCATEST RUN NO. 1



# FULL SCALE TRANSMISSIBILITY

0.1 □ 1.0 □ 10 □ 100 □ 1000 □




SPECIMEN 12"  
AXIS LONG

ACCEL NO. 5VERT NO. HCM  
TEST RUN NO. 1

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐



SPECIMEN 12"


AXIS LONG

ACCEL NO. 6LMT NO. HCA

TEST RUN NO. 1

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐



SPECIMEN 12"

AXIS LONG


ACCEL NO. 4Long NO. 1Long

TEST RUN NO 1



FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LONG

ACCEL NO. 5VERT NO. 2VERT  
TEST RUN NO. 1



FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LONG

ACCEL NO. 6LAT NO. 3LAT  
TEST RUN NO. 1

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 12"  
AXIS VERT

ACCEL NO. 1/100 NO. VCA  
TEST RUN NO 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS VERT

ACCEL NO. 2VERT NO. VCA  
TEST RUN NO. 2



FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐



SPECIMEN 12'


AXIS VERT

ACCEL NO. 3LAT NO. VCA

TEST RUN NO. 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 12"  
AXIS VERT

ACCEL NO. 44045 NO. VCA  
TEST R N NO. 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐



SPECIMEN 12"

AXIS VERT


ACCEL NO SVERT NO. VCA

TEST RUN NO. 2



# FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 12"  
AXIS VERT

ACCEL NO. 6LAT NO. VCA  
TEST RUN NO. 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐



SPECIMEN 12"


AXIS VERT

ACCEL NO. 4 Long NO. 1 Long

TEST RUN NO. 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS VERT

ACCEL NO. 5VERT NO. 2VERT  
TEST RUN NO. 2




## FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐SPECIMEN 12"AXIS VERTACCEL NO. 6LAT NO. 3LATTEST RUN NO. 2

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐



SPECIMEN

AXIS


2"  
LAT

ACCEL NO. 1 LONG NO. HCA

TEST RUN NO. 33

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 12"  
AXIS LAT

ACCEL NO. 2 VERT NO. HCA  
TEST RUN NO. 33



FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LAT

ACCEL NO. 3LAT NO. HCA  
TEST RUN NO. 33

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐



SPECIMEN 12"


AXIS LAT

ACCEL NO. 4 Long NO. HCA

TEST RUN NO. 33

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☒ 100 ☐ 1000 ☐




SPECIMEN 12"  
AXIS LAT

ACCEL NO. 5Y00 NO. HCA  
TEST RUN NO. 33



## FULL SCALE TRANSMISSIBILITY


0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐

SPECIMEN 12"  
AXIS LAT

ACCEL NO. 6LAT NO. HCA  
TEST RUN NO. 33

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LAT

ACCEL NO. 4 LONG NO. 1 LONG  
TEST RUN NO. 33

FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐




SPECIMEN 12"  
AXIS LAT

ACCEL NO. 5VERT NO. 2VERT  
TEST RUN NO. 33



# FULL SCALE TRANSMISSIBILITY

0.1 ☐ 1.0 ☐ 10 ☐ 100 ☒ 1000 ☐



SPECIMEN 12"  
AXIS LAT

ACCEL NO 6LAT NO. 3LAT  
TEST RUN NO. 33

APPENDIX II

INSTRUMENTATION LOG SHEETS  
AND  
INSTRUMENTATION EQUIPMENT SHEETS

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44679LOG PAGE NO. 1 OF 9CUSTOMER HENRY PRATTTEST ENGINEER Blair J. Fulk(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
30 JULY 79		SET UP TO RECORD 2 CONTROL & 6 RESONANCE ACCELS ON TAPE AND O'GRAPH
		SET UP TO RECORD 2 ELECTRICAL MONITORS ON O'GRAPH
		RECORDED CAL SIGNAL OF 100MS 100HZ ON REEL # 2
		START 1320' STOP 1540'
		MOUNTED SPECIMEN IN LONG/VERT AXIS 12" VALVE
	1010	RUN #1 SINE SWEEP 3.5 - 75 Hz 0.2g HORIZ LONG AXIS START 1320' STOP 1540'
	1032	RUN #2 SINE SWEEP 3.5 - 75 Hz 0.2g VERT VERT AXIS START 1540' STOP 1745'
	1110	RUN #3 SINE SWEEP 3.5 Hz 0.5g LONG AXIS START 1745' STOP 1820'

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 4/L-79LOG PAGE NO. 2 OF 9CUSTOMER HENRY FRATTTEST ENGINEER B. M. Foulk(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
31 July 79	1112	Run #4 Side Drill @ 4.5 Hz 0.5g START 1820' STOP 1835' LONG AXIS
	1114	Run #5 Side Drill @ 6.0 Hz 0.5g START 1835' STOP 1845' LONG AXIS
	1118	Run #6 Side Drill @ 8.0 Hz 0.5g START 1845' STOP 1855' LONG AXIS
	1120	Run #7 Side Drill @ 11.0 Hz 0.5g START 1855' STOP 1865' LONG AXIS
	1121	Run #8 Side Drill @ 15.0 Hz 0.5g START 1865' STOP 1880' LONG AXIS
	1123	Run #9 Side Drill @ 21.0 Hz 0.5g START 1880' STOP 1890' LONG AXIS

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44679 LOG PAGE NO. 3 OF 9CUSTOMER KENNY PRATTTEST ENGINEER Bruce D. Dwyer(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
30 JUL 79	1126	RUN #10 SINE DURE @ 29.0 Hz 0.5g START 1890' STOP 1900' LINK AXIS
	1127	RUN #11 SINE DURE @ 29.0 Hz 0.5g START 1900' STOP 1910' LINK / AXIS
	1129	RUN #12 SINE DURE @ 53.0 Hz 0.5g START 1910' STOP 1920' LINK AXIS
	1133	RUN #13 SINE DURE @ 71.0 Hz 0.5g START 1920' STOP 1930' LINK AXIS CORRECTION OFFERED AND ACCEPTED
	1143	RUN #14 SINE DURE @ 95.0 Hz 0.5g START 1930' STOP 1940' LINK AXIS
	1148	RUN #15 SINE DURE @ 23.5 Hz 0.5g START 1940' STOP 1950' VIB. AXIS



W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44677LOG PAGE NO. 4 OF 9CUSTOMER HENRY PRATTTEST ENGINEER Bruce H. Fowler(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
30 JULY 79	1150	RUN 16 SINE SWELL @ 4.5 Hz 0.5g VERT AXIS START 1950' STOP 1960'
	1152	RUN 17 SINE SWELL @ 6.0 Hz 0.5g VERT AXIS START 1960' STOP 1970'
	1153	RUN 18 SINE SWELL @ 8.0 Hz 0.5g VERT AXIS START 1980' STOP 1990'
	1155	RUN 19 SINE SWELL @ 11.0 Hz 0.5g VERT AXIS START 1990' STOP 2000'
	1156	RUN 20 SINE SWELL @ 15.0 Hz 0.5g VERT AXIS START 2000' STOP 2010'
	1157	RUN 21 SINE SWELL @ 21.0 Hz 0.5g VERT AXIS START 2010' STOP 2020'



W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 11679 LOG PAGE NO. 5 OF 9CUSTOMER HEARST PAPERTEST ENGINEER B. M. H. F. F.(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS	
27. JUL 79	1158	Run 222 Start Date @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	
	1157	Run 223 Start Date @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	
	1201	Run 224 Start Date @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	
	1203	Run 225 Start Date @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	
	1205	Run 226 Start Date @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	
	1210	Run 227 UNDERLINE @ 29.0 hr 0.5g	VERT AXIS
		START 2020' STEP 2020'	

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44677LOG PAGE NO. 6 OF 9CUSTOMER KERRY FRATTTEST ENGINEER Edward J. Fisher(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
12/15/77	1215	Run 28 endurance @ 11.0 lb 0.5g START 2100' STOP 2120' LEAK AVG
	1220	Run 29 endurance @ 52.0 lb 0.5g START 2120' STOP 2145' LEAK AVG
	1227	Run 30 endurance @ 33.0 lb 0.5g START 2145' STOP 2150' LEAK AVG
	1233	Run 31 endurance @ 23.0 lb 0.5g START 2150' STOP 2205' LEAK AVG
	1237	Run 32 endurance @ 88.0 lb 0.5g START 2205' STOP 2237' LEAK AVG
		ROTATION STOPPED @ 70 THE INSTRUMENT WAS
		CHANGED FROM 70 CAL 11.8 IN 105 HR REF 3 0.100'

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44679LOG PAGE NO. 7 OF 9CUSTOMER HENRY PRITTITEST ENGINEER Bruce H. Fowler(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
30 June 79	1410	RUN # 33 SINE SWEEP 3.5 - 9.5 Hz 0.329 H LAT ONLY START 0100' STOP 0335'
	1435	RUN # 34 SINE Dwell @ 3.5 Hz 0.59 H LAT ONLY START 0335' STOP 0345'
	1437	RUN # 35 SINE Dwell @ 4.5 Hz 0.53 H LAT ONLY START 0345' STOP 0355'
	1442	RUN # 36 SINE Dwell @ 6.0 Hz 0.59 H LAT ONLY START 0355' STOP 0365'
	1444	RUN # 37 SINE Dwell @ 8.0 Hz 0.59 H LAT ONLY START 0365' STOP 0375'
	1445	RUN # 38 SINE Dwell @ 11.0 Hz 0.53 H LAT ONLY START 0375' STOP 0385'

W 322

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEETJOB NO. 44679LOG PAGE NO. 8 OF 9CUSTOMER HENRY PRATTTEST ENGINEER Blair Fowles(Include Run Number, Part Changes, Shift Changes  
and all other pertinent data)

DATE	TIME	REMARKS
30 July 79	1447	RUN 39, SINE DWELL @ 15 HZ 0.5g H LAT ONLY START 0335' STOP 0345'
	1449	RUN 40, SINE DWELL @ 21 HZ 0.5g H LAT ONLY START 0345' STOP 0405'
	1452	RUN 41, SINE DWELL @ 29 HZ 0.5g H LAT ONLY START 0405' STOP 0415'
	1454	RUN 42, SINE DWELL @ 39 HZ 0.5g H LAT ONLY START 0415' STOP 0425'
	1455	RUN 43, SINE DWELL @ 53.0 HZ 0.5g H LAT ONLY START 0425' STOP 0435'
	1459	RUN 44, SINE DWELL @ 71 HZ 0.5g H START 0435' STOP 0450'

WYLE LABORATORIES  
INSTRUMENTATION LOG SHEET

LOG PAGE NO. 7 OF 9

## TEST ENGINEER

26

(Include Run Number, Part Changes, Shift Changes and all other pertinent data)

DATE	TIME	DESCRIPTION	START	STOP	END
30 May 24	1502	RUN 45, SINK NOISEL (C) 35 Hz	0.50 Hz	0.50 Hz	1.17 ONLY
		START 0450'	STOP 0460'		
	1505	RUN 46, ENDURANCE (C) 33 Hz	0.50 Hz	0.50 Hz	1.17 ONLY
		START 0460'	STOP 0480'		
	1510	RUN 47, ENDURANCE (C) 38 Hz	0.50 Hz	0.50 Hz	1.17 ONLY
		START 0450'	STOP 0505'		
		END OF TEST			

Page No. 51  
Report No. 44679-1



# INSTRUMENTATION EQUIPMENT SHEET

Date 28 JULY 79 Job No. 44679 Test Area Pit #1  
 Technician W. MORROW Customer HENRY PRATT Type Test SEISMIC

No.	Instrument	Manufacturer	Model No.	Serial No.	Wyle or Gov't No.	Range	Accuracy	Calibration	
								On	Due
1	ACCELEROMETER	ENDEVCO	2213E	CP59	95283	1000g	±5%	6-12-79	9-12-79
2	ACCELEROMETER	ENDEVCO	2213	DA 44	95340	1000g	±5%	6-12-79	9-12-79
3	ACCELEROMETER	ENDEVCO	2272	NE 89	96192	1000g	±5%	6-27-79	9-27-79
4	ACCELEROMETER	ENDEVCO	2272	NA62	F1437	1000g	±5%	5-17-79	8-17-79
5	ACCELEROMETER	ENDEVCO	2272	EP53	96147	1000g	±5%	6-28-79	9-28-79
6	ACCELEROMETER	ENDEVCO	2272	NA68	F1406	1000g	±5%	6-1-79	9-1-79
7	ACCELEROMETER	ENDEVCO	7701-100	AG80	11350	1000g	±5%	6-12-79	9-12-79
8	ACCELEROMETER	ENDEVCO	7701-100	AG53	11759	1000g	±5%	6-12-79	9-12-79
9	CHARGE AMP	DYNAMICS	7302	—	1656	500g	±2%	6-1-79	12-1-79
10	CHARGE AMP	DYNAMICS	7302	—	1551	500g	±2%	6-1-79	12-1-79
11	CHARGE AMP	DYNAMICS	7302	—	1566	500g	±2%	6-1-79	12-1-79
12	CHARGE AMP	DYNAMICS	7302	—	1556	500g	±2%	6-4-79	12-4-79
13	CHARGE AMP	DYNAMICS	7302	—	1631	500g	±2%	6-4-79	12-4-79
14	CHARGE AMP	DYNAMICS	7302	—	1593	500g	±2%	6-1-79	12-1-79
15	CHARGE AMP	DYNAMICS	2740-B	—	11212	50 KHZ	±1.5%	6-22-79	12-22-79
16	CHARGE AMP	DYNAMICS	2740-B	—	11213	50 KHZ	±1.5%	6-22-79	12-22-79
17	GALVO AMP	HONEYWELL	T66A-5a	—	96258	1:1	±2%	2-6-79	8-6-79
18	GALVO AMP	HONEYWELL	T66A-5a	—	96275	1:1	±2%	2-22-79	8-22-79

Instrument Test Engineer Wayne Kilgore

Checked & Received By Bobby L. Quinn



# INSTRUMENTATION EQUIPMENT SHEET

Date 30 JULY '79

Job No. 44679

Test Area PIT #1

Technician W. MORROW

Customer HENRY PRATT

Type Test SEISMIC

No.	Instrument	Manufacturer	Model No.	Serial No.	Wyle or Gov't No.	Range	Accuracy	Calibration	
								On	Due
19	GALVO AMP	HONEYWELL	TEGA-500	-	96259	1:1	±2%	4-4-79	10-4-79
20	VISICORDER	HONEYWELL	1508	-	11167	D.C. - 2.5 KHZ	±2%	5-7-79	11-7-79
21	VISICORDER	HONEYWELL	1508	-	96056	D.C. - 2.5 KHZ	±2%	3-8-79	9-8-79
22	Timer/Counter	MONSANTO	101A	-	95371	D.C. - 99999 HZ	±1 count	5-11-79	8-11-79
23	GALVO AMP	HONEYWELL	TEGA-500	-	96261	1:1	±2%	2-28-79	8-28-79
24	TAPE RECORDER	BELL & HOWELL	QPR4010	-	72149	D.C. - 2.5 KHZ	±2%	7-5-79	10-5-79
25	SWEEP OSCILLATOR	SPEC. DYNAMICS	SD104	-	95360	.005 HZ - 50 KHZ	±0.5%	7-30-79	10-30-79
26	SERVO MONITOR	SPEC. DYNAMICS	SD105	-	95358	1000g	±4%	7-30-79	10-30-79
27	SERVO MONITOR	SPEC. DYNAMICS	SD105	-	95296	1000g	±4%	7-30-79	10-30-79
28	X-Y RECORDER	H.P.	7004B	-	95202	10V/IN	±0.2%	3-14-79	9-14-79
29	OSCILLOSCOPE	H.P.	122AR	-	80896	10V/IN	±3%	7-2-79	10-2-79
30	VOLTMETER	B&K	2426	-	95492	300V	±2%	7-18-79	10-18-79
31	LOG. FREQ. CONV.	SPEC. DYNAMICS	SD11C	-	95123	5 HZ - 50 KHZ	±2%	7-6-79	10-6-79
32	TRACKING FILTER	SPEC. DYNAMICS	SD131	-	11242	40dB	±0.5dB	5-31-79	11-31-79
33	TRACKING FILTER	SPEC. DYNAMICS	SD131	-	11243	40dB	±0.5dB	5-31-79	11-31-79
34	POWER SUPPLY	KEPCO	KS36-10	H50490	98723	0-50VDC		7-9-79	1-9-80
35	PRESSURE GAGE	ASHCROFT	AMP7322	-	97811	0-200 PSI	±1%	7-3-79	10-3-79
36	SWEEP OSCILLATOR	SPEC. DYNAMICS	SD104	-	95295	.005 HZ - 50 KHZ	±2%	7-11-79	10-11-79

Instrument Test Engineer H. H. H. H.

Checked & Received By James W. Foreman

Date 30 JULY 79 Job No. 44677 Test Area PT #1  
Technician C.R. FLOST Customer HENRY DRAIT Type Test SEISMIC

Checked & Received By Bobby L. Quinner

Instrument Test Engineer *H. Fordham*

WII-1029

APPENDIX III

SEISMIC TEST PROCEDURE



**WYLE LABORATORIES**  
SCIENTIFIC SERVICES AND SYSTEMS GROUP

1.0 PURPOSE

The purpose of this test plan is to describe the procedure to be used to seismically-qualify four (4) Valve Assemblies, hereinafter called the specimens, for Henry Pratt Company, Aurora, Illinois.

1.1 Specimen Description

<u>Specimen</u>	<u>Size</u>	<u>Description</u>	<u>Part No.</u>
1	12"	1200 with Bettis Actuator	D-0089-04
2	18"	1400 with Motor Operator	D-0115-10
3	24"	1200 with Motor Operator	D-0151-02
4	36"	1200 with Motor Operator	D-0114-14

2.0 SEISMIC QUALIFICATION TESTS

2.1 Mounting

2.1.1 Specimen Orientation

The specimens shall be installed separately on Wyle's Biaxial Seismic Simulator Table. The specimens shall be tested in the first horizontal axis and then rotated 90 degrees about their vertical centerlines for the second test orientation. Items 1 and 3 will be tested sequentially and Items 2 and 4 will be tested sequentially.

2.1.2 Specimen Tie-Down

The specimens will be premounted to a Wyle-furnished test fixture using commercially-available bolts, nuts and washers. The test fixtures will be welded to the test table. Figure 1 shows a typical test setup.

2.2 Excitation

2.2.1 Excitation Control

A control accelerometer shall be mounted on the test fixture.

2.2.2 Single-Axis Excitation

The specimens shall be subjected to single-axis sinusoidal excitation during the tests. Each of the three test axes shall be tested (two horizontal and one vertical).

**WYLE LABORATORIES**  
SCIENTIFIC SERVICES AND SYSTEMS GROUP

2.2.3 Resonance Search

A sine sweep test (approximately 0.2 g) from 3.5 to 95 Hz shall be performed in each of the three orthogonal axes. The sweep rate shall be one octave per minute.

2.2.4 Variable Frequency Test

A variable frequency test shall be performed in each of the three orthogonal axes. The input test level shall be approximately 0.5 g (within the limitations of the test machine) at the following frequencies: 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz. Duration of the test shall be sufficient to allow the specimens to cycle open to close to open. Motive power will be recorded at each half of operating time.

2.2.5 Endurance Test

An endurance test shall be performed in each of the three orthogonal axes. The input test level shall be approximately 0.5 g (within the limitations of the test machine) at the resonant frequencies\* found in Paragraph 2.2.3, and at 33 Hz. Duration of the test shall be at least three (3) minutes.

\*Resonant frequencies are defined as a frequency at which the acceleration of the actuator center of gravity exceeds the valve body acceleration level by a factor of 3 or more.

At the conclusion of each three (3) minutes with the specimen still vibrating, a functional test will be performed as specified in Paragraph 3.0.

2.3 Instrumentation

2.3.1 Specimen Response Accelerometers

Six (6) specimen-mounted uniaxial piezo-electric accelerometers shall be provided for the specimens during the test. Placement of the accelerometers will be as directed by the Henry Pratt Technical Representative or the Wyle Test Engineer. The accelerometers will be recorded on FM tape and oscillograph recorders during the sine sweep test. Transmissibility plots of these accelerometers will be provided in the test report. Additional accelerometers are quoted as an option.

2.3.2 Electrical Monitoring

A potentiometer will be used to monitor the shaft position of the specimens. The output of the potentiometer will be recorded on an oscillograph recorder.



**WYLE LABORATORIES**  
SCIENTIFIC SERVICES AND SYSTEMS GROUP

2.3.4 Electrical Powering

Standard electrical power of 460 VAC, 3-phase, will be provided for operation of the valve actuator.

3.0 FUNCTIONAL TESTS

Functional tests will be performed prior to and after the test program with the following parameters recorded:

Motive Power	VAC/PSI	Measured with volt meter/pressure gage
Operating Time	Closed to Open Open to Closed.	

4.0 IN-PROCESS INSPECTION

The records will be checked for quality of performance after each test.

The specimens will be examined for possible damage following all violent tests such as at a severe structural resonance.

All important vibration effects will be logged.

Photographs will be taken of any noticeable physical damage that may occur.

5.0 REPORT

Five (5) copies of a certification-type report for each Valve will be issued within four (4) weeks after completion of testing. This report will be signed by a Registered Professional Engineer, and will summarize the test response, results and conclusions, details and recommendations concerning deficiencies and repairs, photographs of test setups, failures, test procedures, etc. The report will also contain a list of test equipment used, calibrations, and Instrumentation Log Sheets. A description of the test facility and instrumentation will also be included in the test report.

**WYLE LABORATORIES**  
SCIENTIFIC SERVICES AND SYSTEMS GROUP

TABLE I

ORDER OF TESTS

- 1) Pre-Test Functional
- 2) Sine Sweep (1st horizontal axis)
- 3) Sine Sweep (vertical axis)
- 4) Variable Frequency Test (1st horizontal axis)
- 5) Variable Frequency Test (vertical axis)
- 6) Endurance Test (1st horizontal axis)
- 7) Endurance Test (vertical axis)
- 8) Post-Test Functional
- 9) Sine Sweep (2nd horizontal axis)
- 10) Variable Frequency Test (2nd horizontal axis)
- 11) Endurance Test (2nd horizontal axis)
- 12) Post-Test Functional





FIGURE 1. TYPICAL TEST SETUP

Job No. D-0089-4



FUNCTIONAL QUALIFICATION TEST FACILITY

HENRY PRATT COMPANY

AURORA, ILLINOIS

Job No. D-0089-4

DIMENSIONAL DATA QTVA

Valve Size 12" NXL (1100)

Operator Mounting TEE BONNET

Operator 721C-80-12

Minimum Cylinder Force Required to Equal Seismic Moments

$F_1 = \underline{846}$  lb. in x direction

$F_2 = \underline{1058}$  lb. in y direction

$F_3 = \underline{1009}$  lb. in z direction

Actual Test Cylinder Force 1421.7 lb. in x, 1421.7 lb. in y, 1421.7 lb. in z

$A_1$  .142

$A_2$  .126

$A_3$  .142

$A_4$  .126

$A_5$  -

$A_6$  -

$A_7$  9.69

$B_1$  4.5

$B_2$  3.0

$F_x$  1623.5

$F_y$  1421.7

$F_z$  1421.7

$g_x$  7.72

$g_y$  6.72

$g_z$  7.05

$H_1$  4.25

$H_2$  3.188

$H_3$  3.188

$H_4$  7

$I_1$  157.63

$I_2$  22.57

$J_1$  1625

$J_2$  .8125

$J_3$  3.156

$J_4$  1.656

$K_1$  3.5

$M_x$  7030

$M_y$  21383

$M_z$  20254

$\overline{M}_x$  -

$\overline{M}_y$  -

$\overline{\overline{M}}_x$  16982

$\overline{\overline{M}}_y$  32843

$T_1$  -

$T_2$  5000

$V_1$  -

$V_2$  -

$V_3$  -

$V_4$  -

$W_1$  201.75

$W_2$  27.5

$W_3$  -

$x_0$  11.82

$y_0$  2.125

$z_0$  2.82

PART II

SECTION 1 B

FUNCTIONAL QUALIFICATION REPORT

FOR

GENERIC FAMILY VALVE ASSEMBLY (GFVA)

Job No. D-0089-5

As qualified by QTVA form D-0089-4.

Page No.

- |    |   |   |
|----|---|---|
| 1. | Description and Characteristics of GFVA   | 1 |
| 2. | Base Line Data of GFVA to be used for Generic Qualification                                     | 2 |
|    | Results of Qualification Rules 1.3.8 and 1.3.9  | 3 |
|    | Dimensional Data Summary  | 4 |
| 3. | Copy of Functional Qualification Report of Actuator to show Compliance to IEEE 344 and IEEE 382 | 5 |

THIS GENERIC FAMILY VALVE ASSEMBLY SATISFIES ALL GENERIC QUALIFICATION RULES (PART I, PARAGRAPH 1.3) AND IT IS CONSIDERED A QUALIFIED GENERIC FAMILY VALVE ASSEMBLY.



1. DESCRIPTION AND CHARACTERISTICS

Valve Size and Type

12" NXL (1100)

Standard Pressure Class

150

Cold Working Pressure

275

psi

Rated Differential Pressure

200

psi

Maximum Service Temperature

200

°F

Actuator Type

—

Electric  
Motor

✓

Air

Actuator Size

721C-80-12

Normal Motive Power

—

Vac

100

psi

Minimum Motive Power

—

Vac

80

psi

Maximum Motive Power

—

Vac

110

psi

Job No. D-0089-5

2. BASE LINE DATA OF GFVA TO BE USED FOR GENERIC QUALIFICATION

Reference  
Paragraph

1.3.1 Valve Size

12" NXL (1100)

1.3.2 Seat Taper Angle

15°

1.3.3 Disc/Seat Interference

.030

1.3.4 Seating Surface Materials

STAINLESS STEEL/EPT

1.3.5 Materials of Construction

Body

ASME SA-516 GR.70

Disc

ASME SA-516 GR.70

Shaft

ASME SA-564 T.630-H1150

Bearing

ASTM B438 GR.1 TYPE Z

Seat

EPT

Retainer Segments

—

Packing

EPT

Thrust Collar

SAE 660 BRONZE

Bottom Cover

ASME SA-516 GR.70

Bonnet

ASTM A-36

Bolts: Valve to Bonnet

SAE GR. 8

Bonnet to Actuator

SAE GR. 8

1.3.6 Actuator Rated Torque @ 80 PSI

3420

Calculated Operator Torque

2750

Ratio = 1.24

Operating Time

Open to Close

4 Sec.

Close to Open

4 Sec.

RESULTS OF QUALIFICATION RULES 1.3.8 AND 1.3.9 FOR GFVARule 1.3.8

- a.  $S_1 = \underline{36000}$  Yield strength of bonnet material  
 $S_2 = \underline{3594}$  Calculated bonnet stress  
 $S_1/S_2 = \underline{10.02} > 1$
- b.  $S_3 = \underline{120000}$  Yield strength (proof load) of bonnet to valve bolting  
 $S_4 = \underline{33167}$  Calculated stress of bonnet to valve bolting  
 $S_3/S_4 = \underline{3.55} > 1$
- c.  $S_5 = \underline{120000}$  Yield strength (proof load) of actuator to bonnet bolting  
 $S_6 = \underline{26250}$  Calculated stress of actuator to bonnet bolting  
 $S_5/S_6 = \underline{4.57} > 1$

Rule 1.3.9 Bonnet Body Deflections ( $\Delta L$ )

- $\Delta L$  of GFVA = .00071 Deflection family valve  
 $\Delta L$  of GFVA < .002"

Job No. D-0089-5

3. COPY OF FUNCTIONAL QUALIFICATION REPORT OF ACTUATOR TO SHOW COMPLETE  
TO IEEE 344 AND IEEE 382

Reference

Paragraph

1.3.7

STATEMENT OF CERTIFICATION

QUALIFICATION TESTING

GH-BETTIS Actuator Model N-721C-SR80 is hereby certified to be of the same construction as Bettis Actuator Model N-732C-SR80 which was qualified to the requirements of ANSI 278.2.1, Draft 3, Rev. 0, Feb. 1977 (IEEE 382) with the exception of LOCA by testing at Southwest Research Institute, San Antonio, Texas. Applicable test margins as described in paragraph 6.3.1.5 of IEEE 323-1974 were utilized with the exception of (8). Refer to SWRI Test Report No. 02-4854-RPT-1.

The LOCA testing required to complete the qualification program is scheduled to begin at Wyle Laboratories, Huntsville, Alabama on September 11. Upon successful completion of that testing a revised statement of certification will be issued referencing the applicable test report number.

SEISMIC ANALYSIS

In addition to the seismic test results obtained in the above referenced tests, Bettis Seismic Analysis Report No. R-1062-25 Rev.A is offered as further supportive evidence to the rigidity of this actuator.

*Joel D. Page*

---

JOEL D. PAGE  
Senior Engineer  
Nuclear Products

JP/ksy  
8-31-78

Job No. D-0089-5

DIMENSIONAL DATA GFVA

Valve Size 12" NXL (1100)

Operator Mounting TRE BONNET

Operator 721C-80-12

A <sub>1</sub>	.142
A <sub>2</sub>	.126
A <sub>3</sub>	.142
A <sub>4</sub>	.126
A <sub>5</sub>	—
A <sub>6</sub>	—
A <sub>7</sub>	9.69
B <sub>1</sub>	4.5
B <sub>2</sub>	3.0
F <sub>x</sub>	1009
F <sub>y</sub>	1009
F <sub>z</sub>	1009
g <sub>x</sub>	5.0
g <sub>y</sub>	5.0
g <sub>z</sub>	5.0
H <sub>1</sub>	4.25
H <sub>2</sub>	3.188
H <sub>3</sub>	3.188
H <sub>4</sub>	7
I <sub>1</sub>	157.63
I <sub>2</sub>	22.57
J <sub>1</sub>	.625

J <sub>2</sub>	.8125
J <sub>3</sub>	3.156
J <sub>4</sub>	1.656
K <sub>1</sub>	3.5
M <sub>x</sub>	4988
M <sub>y</sub>	14768
M <sub>z</sub>	14067
H <sub>x</sub>	—
H <sub>y</sub>	—
H <sub>x</sub>	12531
H <sub>y</sub>	22311
T <sub>1</sub>	—
T <sub>2</sub>	5000
V <sub>1</sub>	—
V <sub>2</sub>	—
V <sub>3</sub>	—
V <sub>4</sub>	—
W <sub>1</sub>	201.75
W <sub>2</sub>	27.5
W <sub>3</sub>	—
X <sub>0</sub>	11.82
Y <sub>0</sub>	2.125
Z <sub>0</sub>	2.82



## Addendum 1

This Addendum presents the equations and the calculations required to obtain the required test cylinder forces and the results of the Generic Qualification Rules 1.3.8 and 1.3.9 for the Operability Assurance Program for Active Nuclear Valves.

<u>Table of Contents</u>	<u>Page No.</u>
Nomenclature	1
Derivation of the Required Cylinder Force to Apply to the Actuator Center of Gravity of the QTVA	4
Derivation of the Values of Generic Rules 1.3.8 and 1.3.9	6
Figures	10
Sample: Dimensional Data Sheet and Results of Rules 1.3.8 and 1.3.9 Sheet	13

### Forward to Addendum I

The following Addendum has been prepared utilizing a general case involving motor actuators.

This Addendum will also apply for the case involving pneumatic actuators if the adapter plate weight and thickness ( $W_3$  &  $T_1$ ) are taken to be zero. The "adapter plate" is assumed to be an integral part of the actuator and  $H_2$  is the actuator square.

Then the equation for  $S_6$  represents the actuator to bonnet bolt stress.

## ANALYSIS NOMENCLATURE

---

- $A_1$  Tensile area of trunnion bolt,  $\text{in}^2$   
 $A_2$  Shear area of trunnion bolt,  $\text{in}^2$   
 $A_3$  Tensile area of actuator bolt,  $\text{in}^2$   
 $A_4$  Shear area of actuator bolt,  $\text{in}^2$   
 $A_5$  Bonnet bolt tensile area,  $\text{in}^2$   
 $A_6$  Bonnet bolt shear area,  $\text{in}^2$   
 $A_7$  Bonnet body cross-sectional area,  $\text{in}^2$   
 $B_1$  Distance to outer fiber of bonnet from shaft on y axis, in.  
 $B_2$  Distance to outer fiber of bonnet from shaft on x axis, in.  
 $E$  Modulus of elasticity, psi. For steel =  $30 \times 10^6$   
 $F_1$  Required cylinder force in the x direction to equal seismic moments at body mounting surface, pounds  
 $F_2$  Required cylinder force in the y direction to equal seismic moments at body mounting surface, pounds  
 $F_3$  Required cylinder force in the z direction to equal seismic moments at body mounting surface, pounds  
 $F_x$   $W_1 g_x$  - Seismic force along x axis due to seismic acceleration acting on actuator extended mass, pounds  
 $F_y$   $W_1 g_y$  - Seismic force along y axis due to seismic acceleration acting on actuator extended mass, pounds  
 $F_z$   $W_1 g_z$  - Seismic force along z axis due to seismic acceleration acting on actuator extended mass, pounds  
 $g_x$  Seismic acceleration constant along x axis  
 $g_y$  Seismic acceleration constant along y axis  
 $g_z$  Seismic acceleration constant along z axis  
 $H_1$  Top trunnion bolt square, in.  
 $H_2$  Bonnet bolt square, in.  
 $H_3$  Actuator bolt circle, in.  
 $H_4$  Bonnet height, in.  
 $I_1$  Bonnet body moment of inertia means about x axis,  $\text{in}^4$

# ANALYSIS NOMENCLATURE

- $I_2$  Bonnet body moment of inertia means about y axis, in<sup>4</sup>
- $J_1$  Distance to neutral bending axis for top trunnion bolt pattern along x axis, in.
- $J_2$  Distance to neutral bending axis for top trunnion bolt pattern along y axis, in.
- $J_3$  Distance to neutral bending axis for bonnet bolt pattern along x axis, in.
- $J_4$  Distance to neutral bending axis for bonnet bolt pattern along y axis, in.
- $K_1$  Length along z axis to c.g. of bonnet plus adapter plate assembly, in.
- $M_x$   $W_1(g_y Z_0)$ , actuator extended mass seismic bending moment about the y axis, acting at the base of the actuator, in-lbs.
- $M_y$   $W_1(g_x Z_0)$ , actuator extended mass seismic bending moment about the y axis, acting at the base of the actuator, in-lbs.
- $M_z$   $W_1(g_x Y_0 + g_z X_0)$ , actuator extended mass seismic bending moment about the z axis, in-lbs.
- $\overline{M}_x$   $M_x + F_y T_1$ , actuator extended mass seismic bending moment about the x axis, acting at the bottom of the adapter plate, in-lbs.
- $\overline{M}_y$   $M_y + F_x T_1$ , actuator extended mass seismic bending moment about the y axis, acting at the bottom of the adapter plate, in-lbs.
- $\overline{\overline{M}}_x$   $M_x + F_y (T_1 + H_4) + g_y W_2 K_1$ , actuator extended mass seismic bending moment about the x axis, acting at the base of the bonnet, in-lbs.
- $\overline{\overline{M}}_y$   $M_y + F_x (T_1 + H_4) + g_x W_2 K_1$ , actuator extended mass seismic bending moment about the y axis, acting at the base of the bonnet, in-lbs.
- $T_1$  Adapter plate thickness, in.
- $T_2$  Maximum required operating torque for valve, in-lbs.
- $V_1$  Distances to bolts in bolt pattern on adapter plate, in.
- $V_2$  Distances to bolts in bolt pattern on adapter plate, in.
- $V_3$  Distances to bolts in bolt pattern on adapter plate, in.
- $V_4$  Distances to bolts in bolt pattern on adapter plate, in.

## ANALYSIS NOMENCLATURE

---

$W_1$	Actuator weight, pounds
$W_2$	Bonnet and adapter plate assembly weight, pounds
$W_3$	Adapter plate weight, pounds
$X_0$	Eccentricity of center of gravity of actuator extended mass along x axis, inches
$Y_0$	Eccentricity of center of gravity of actuator extended mass along y axis, inches
$Z_0$	Eccentricity of center of gravity of actuator extended mass along z axis, inches
$\Delta L_0$	Combined deflection of bonnet body due to seismic loads, inches
$\Delta L_x$	Deflection of bonnet body in x direction due to seismic load, inches
$\Delta L_y$	Deflection of bonnet body in y direction due to seismic load, inches

Derivation of the Required Cylinder Force to Apply  
to the Actuator Center of Gravity for the QTVA

The actuator mounting and orientation is shown in Figure 1 for a standard valve assembly. The test loading configuration is shown in Figure 2. A cylinder force is applied through the center of gravity of the actuator along both the x,y, and z directions. The cylinder load applied has greater or equal moments about the valve body mounting surface than the actuator assembly at the specified g levels.

In the x direction, the bonnet and actuator are oriented so that the least rigid direction of bonnet and the largest actuator eccentricity combine to form the worst loading case. Since the test valve orientation has the actuator weight acting in the same direction as the cylinder force due to gravity, the test valve actuator weight reduces the required cylinder force. The determination of the cylinder force is shown below. The terms used are listed in the Nomenclature and shown on Figure 2.

Moments of Actuator Assembly at Specified Accelerations

$$\text{About y axis} = W_1 g_x (H_4 + T_1 + Z_0) + W_2 g_x K_1$$

$$\text{About z axis} = W_1 g_x Y_0$$

Moments of Actuator Assembly and Cylinder Load ( $F_1$ )

$$\text{About y axis} = (W_1 + F_1) (H_4 + T_2 + Z_0) + W_2 K_1$$

$$\text{About z axis} = (W_1 + F_1) Y_0$$



Setting the moments about each axis equal and solving for the cylinder load results in two values. The test valve loading shall be equal to or larger than the larger of the two values.

The cylinder load is determined from the following:

$$\text{About y axis: } F_1 = \frac{W_1(g_x - 1)(H_4 + T_2 + Z_0) + W_2 K_1 (g_x - 1)}{H_4 + T_1 + Z_0}$$

$$\text{About z axis: } F_1 = W_1(g_x - 1)$$

In the y direction, the gravity effects are not involved and the cylinder load ( $F_2$ ) is determined from the following equations:

Moments of Actuator Assembly at Specified Accelerations

$$\text{About x axis} = W_1 g_y (H_4 + T_1 + Z_0) + W_2 g_y K_1$$

$$\text{About z axis} = W_1 g_y X_0$$

Moments of Cylinder Force with No Gravity Effect

$$\text{About x axis} = F_2 (H_4 + T_2 + Z_0)$$

$$\text{About z axis} = F_2 X_0$$

Setting the moments about each axis equal and solving for the cylinder load results in two values. The test valve loading shall be equal to or larger than the larger of the two values.

The cylinder load in the y direction is determined from the following:

$$\text{About y axis: } F_2 = \frac{W_1 g_y (H_4 + T_1 + Z_0) + W_2 g_y K_1}{H_4 + T_1 + Z_0}$$

$$\text{About z axis: } F_2 = W_1 g_y$$

Moments Due to Acceleration in z Direction

About x axis =  $W_1 g_z Y_0$

About y axis =  $W_1 g_z X_0$

These moments will be directly represented during the test by a force  $F_3$  applied at the c.g. of the operator.

$F_3 = W_1 g_z$

The values for Generic Rules 1.3.8 and 1.3.9 for the actual test valve QTVA are determined using the actual test force. The forces and moments are redefined by the following equations:

$$F_x = W_1 + F_1 \quad g_x = 1$$

$$F_y = F_2 \quad g_y = 1$$

$$F_z = F_3 \quad g_z = 1$$

$$M_x = F_2 Z_0 + F_3 Y_0$$

$$M_y = (W_1 + F_1) Z_0 + F_3 X_0$$

$$M_z = F_2 X_0 + (W_1 + F_1) Y_0$$

$$\overline{M}_x = F_2 (Z_0 + T_1) + F_3 Y_0$$

$$\overline{M}_y = (W_3 + F_2) (Z_0 + T_1) + W_3 T_1 / 2 + F_3 X_0$$

$$\overline{M}_x = F_2 (H_4 + T_1 + Z_0) + F_3 Y_0$$

$$M_y = (W_1 + F_1) (H_4 + T_1 + Z_0) + W_2 K_1 + F_3 X_0$$

The equations of 1.3.8 A through D can be used to determine values for  $S_2$ ,  $S_4$ ,  $S_6$ , and  $S_8$ .

The bonnet body deflections of Rule 1.3.9 for the QTVA are determined using the actual test force and are determined from the following equations:

$$\Delta L_x = \frac{(W_1 + W_2 + F_1) H_4^3}{3EI_2} + \frac{[(W_1 + F_1)(Z_0 + T_1) - W_2(H_4 - K_1)] H_4^2}{2EI_2} + \frac{F_3 X_0 H_4^2}{2EI_2}$$

$$\Delta L_y = \frac{F_2 H_4^3}{3EI_1} + \frac{F_2 (Z_0 + T_1) H_4^2}{2EI_1} + \frac{F_3 Y_0 H_4^2}{2EI_1}$$

$$\Delta L_0 = (\Delta L_x^2 + \Delta L_y^2)^{1/2}$$

Derivation of the Values for the  
Generic Rules 1.3.8 and 1.3.9

The actuator mounting consists of the top trunnion, the bonnet, the actuator housing, and the bolt connections. The elements of the assembly are shown in Figure 2. The following assumptions are used in the development of the equations:

- A. Torsional, direct shear, and direct tensile loads are shared equally by all bolts in the pattern.
- B. Moments across the bolt pattern are opposed in such a way that the load in each bolt is proportional to its distance from the neutral bending axis.
- C. All loads are transferred through the bolt connections.

1.3.8 a. The maximum combined stress in the bonnet was calculated using the following formulas:

$$S_2 = \frac{S_{10}}{2} + \frac{(S_{10}^2 + 4(S_{11} + S_{12})^2)^{1/2}}{2} = \text{Combined stress in bonnet legs, psi}$$

$$S_{10} = \frac{\overline{M}_x B_1}{I_1} + \frac{\overline{M}_y B_2}{I_2} = \text{Tensile stress due to bending moment, psi}$$

$$S_{11} = \frac{(F_x^2 + F_y^2)^{1/2} + W_2(g_x^2 + g_y^2)^{1/2}}{A_7} = \text{Direct shear stress, psi}$$

$$S_{12} = \frac{(M_z + T_2)(B_1^2 + B_2^2)^{1/2}}{I_2 + I_1} = \text{Torsional shear stress, psi}$$

1.3.8 b. Combined stress in bonnet to valve bolting. (See Figure 3)

$$S_4 = \frac{S_{13}}{2} + \frac{(S_{13}^2 + 4(S_{14} + S_{15})^2)^{1/2}}{2}$$

Where:

$$S_{13} = \frac{\overline{M}_x (J_2 + H_1)}{2J_2^2 + 2(J_2 + H_1)^2} + \frac{\overline{M}_y (J_1 + H_1)}{2J_1^2 + 2(J_1 + H_1)^2} = \text{Tensile stress due to extended mass bending moment, psi}$$

$A_1$

$$S_{14} = \frac{(F_x^2 + F_y^2)^{1/2} + W_2(g_x^2 + g_y^2)^{1/2}}{4A_2} = \text{Direct shear stress, psi}$$

$$S_{15} = \frac{(M_z + T_2)}{(.707 H_1) 4 A_2} = \text{Shear stress due to torsional load, psi}$$

1.3.8 c. Combined stress in adapter plate to bonnet bolting.

(Figure 4)

$$S_6 = \frac{S_{16}}{2} + \frac{(S_{16}^2 + 4(S_{17} + S_{18})^2)^{1/2}}{2}$$

Where:

$$S_{16} = \frac{\overline{M}_x(J_4 + H_2)}{2J_4^2 + 2(J_4 + H_2)^2} + \frac{\overline{M}_y(J_3 + H_2)}{2J_3^2 + 2(J_3 + H_2)^2} = \text{Tensile stress due to bending, psi}$$

$A_5$

$$S_{17} = \frac{(F_x^2 + F_y^2)^{1/2}}{4A_6} = \text{Direct shear stress}$$

$$S_{18} = \frac{M_z + T_2}{(.707 H_2) 4 A_6} = \text{Shear stress due to torsion, psi}$$

1.3.8 d. Combined stress in actuator to adapter plate bolting. (Figure 5)

$$S_8 = \frac{S_{19}}{2} + \frac{(S_{19}^2 + 4(S_{20} + S_{21})^2)^{1/2}}{2}$$

Where:

$$S_{19} = \frac{(M_x + M_y)V_4}{2(V_1^2 + V_2^2 + V_3^2 + V_4^2)A_3} = \text{Tensile stress due to bending moment, psi}$$

$$S_{20} = \frac{(F_x^2 + F_y^2)^{1/2}}{8A_4} = \text{Direct shear stress, psi}$$

$$S_{21} = \frac{(M_z + T_2)}{.5 H_3 8 A_4} = \text{Shear stress due to torsion, psi}$$

### 1.3.9 Bonnet Body Deflections

The deflections of the bonnet body are determined in each direction and are summed vectorially for a combined deflection.

The deflection in each direction was calculated using the following equations:

$$\Delta L_x = \frac{(W_1+W_2)g_x H_4^3}{3EI_2} + \frac{[W_1(Z_0+T_1)-W_2(H_4-K_1)]g_x H_4^2}{2EI_2} + \frac{W_1g_z X_0 H_4^2}{2EI_2}$$

= deflection in the x direction, in.



$$\Delta L_y = \frac{(W_1+W_2)g_y H_4^3}{3EI_1} + \frac{[W_1(Z_0+T_1)-W_2(H_4-K_1)]g_y H_4^2}{2EI_1} + \frac{W_1g_z Y_0 H_4^2}{2EI_1}$$

= deflection in the y direction, in.


The combined deflection is found from the following equation:

$$\Delta L_0 = (\Delta L_x^2 + \Delta L_y^2)^{\frac{1}{2}} = \text{Total deflection, in.}$$







Actuator Mounting Assembly  
Figure 1




**FIGURE 2**  
 Actuator Mounting Configuration  
 for Testing



TOP TRUNNION BOLTING  
Figure 3



BONNET BOLT PATTERN  
Figure 4



ADAPTER PLATE BOLT PATTERN  
Figure 5

Job No. \_\_\_\_\_

DIMENSIONAL DATA QTVA

Valve Size \_\_\_\_\_

Operator Mounting \_\_\_\_\_

Operator \_\_\_\_\_

Minimum Cylinder Force Required to Equal Seismic Moments

$F_1 =$  \_\_\_\_\_ lb. in x direction       $F_2 =$  \_\_\_\_\_ lb. in y direction

$F_3 =$  \_\_\_\_\_ lb. in z direction

Actual Test Cylinder Force \_\_\_\_\_ lb. in x, \_\_\_\_\_ lb. in y, \_\_\_\_\_ lb. in z

$A_1$  \_\_\_\_\_

$J_2$  \_\_\_\_\_

$A_2$  \_\_\_\_\_

$J_3$  \_\_\_\_\_

$A_3$  \_\_\_\_\_

$J_4$  \_\_\_\_\_

$A_4$  \_\_\_\_\_

$K_1$  \_\_\_\_\_

$A_5$  \_\_\_\_\_

$M_x$  \_\_\_\_\_

$A_6$  \_\_\_\_\_

$M_y$  \_\_\_\_\_

$A_7$  \_\_\_\_\_

$M_z$  \_\_\_\_\_

$B_1$  \_\_\_\_\_

$\overline{M}_x$  \_\_\_\_\_

$B_2$  \_\_\_\_\_

$\overline{M}_y$  \_\_\_\_\_

$F_x$  \_\_\_\_\_

$\overline{\overline{M}}_x$  \_\_\_\_\_

$F_y$  \_\_\_\_\_

$\overline{\overline{M}}_y$  \_\_\_\_\_

$F_z$  \_\_\_\_\_

$T_1$  \_\_\_\_\_

$g_x$  \_\_\_\_\_

$T_2$  \_\_\_\_\_

$g_y$  \_\_\_\_\_

$V_1$  \_\_\_\_\_

$g_z$  \_\_\_\_\_

$V_2$  \_\_\_\_\_

$H_1$  \_\_\_\_\_

$V_3$  \_\_\_\_\_

$H_2$  \_\_\_\_\_

$V_4$  \_\_\_\_\_

$H_3$  \_\_\_\_\_

$W_1$  \_\_\_\_\_

$H_4$  \_\_\_\_\_

$W_2$  \_\_\_\_\_

$I_1$  \_\_\_\_\_

$W_3$  \_\_\_\_\_

$I_2$  \_\_\_\_\_

$X_0$  \_\_\_\_\_

$J_1$  \_\_\_\_\_

$Y_0$  \_\_\_\_\_

$Z_0$  \_\_\_\_\_

RESULTS OF QUALIFICATION RULES 1.3.8 and 1.3.9 FOR QTVA

Rule 1.3.8

- a.  $S_1$  = \_\_\_\_\_ Yield strength of bonnet material  
 $S_2$  = \_\_\_\_\_ Calculated bonnet stress  
 $S_1/S_2$  = \_\_\_\_\_ > 1
- b.  $S_3$  = \_\_\_\_\_ Yield strength (proof load) of bonnet to valve bolting  
 $S_4$  = \_\_\_\_\_ Calculated stress of bonnet to valve bolting  
 $S_3/S_4$  = \_\_\_\_\_ > 1
- c.  $S_5$  = \_\_\_\_\_ Yield strength (proof load) of adapter plate to bonnet bolting  
 $S_6$  = \_\_\_\_\_ Calculated stress of adapter plate to bonnet bolting  
 $S_5/S_6$  = \_\_\_\_\_ > 1
- d.  $S_7$  = \_\_\_\_\_ Yield strength (proof load) of actuator to adapter plate bolting  
 $S_8$  = \_\_\_\_\_ Calculated stress of actuator to adapter plate bolting  
 $S_7/S_8$  = \_\_\_\_\_ > 1

Rule 1.3.9

$\Delta_L$  of QTVA = \_\_\_\_\_ Deflection of test valve  
 $\Delta_L$  of QTVA .002"

Reference Addendum 1 & 2 for equations used to determine stresses and deflection for Rules 1.3.8 and 1.3.9.

Job No. \_\_\_\_\_

DIMENSIONAL DATA GFVA

Valve Size \_\_\_\_\_

Operator Mounting \_\_\_\_\_

Operator \_\_\_\_\_

$A_1$  \_\_\_\_\_

$A_2$  \_\_\_\_\_

$A_3$  \_\_\_\_\_

$A_4$  \_\_\_\_\_

$A_5$  \_\_\_\_\_

$A_6$  \_\_\_\_\_

$A_7$  \_\_\_\_\_

$B_1$  \_\_\_\_\_

$B_2$  \_\_\_\_\_

$F_x$  \_\_\_\_\_

$F_y$  \_\_\_\_\_

$F_z$  \_\_\_\_\_

$g_x$  \_\_\_\_\_

$g_y$  \_\_\_\_\_

$g_z$  \_\_\_\_\_

$H_1$  \_\_\_\_\_

$H_2$  \_\_\_\_\_

$H_3$  \_\_\_\_\_

$H_4$  \_\_\_\_\_

$I_1$  \_\_\_\_\_

$I_2$  \_\_\_\_\_

$J_1$  \_\_\_\_\_

$J_2$  \_\_\_\_\_

$J_3$  \_\_\_\_\_

$J_4$  \_\_\_\_\_

$K_1$  \_\_\_\_\_

$M_x$  \_\_\_\_\_

$M_y$  \_\_\_\_\_

$M_z$  \_\_\_\_\_

$\overline{M_x}$  \_\_\_\_\_

$\overline{M_y}$  \_\_\_\_\_

$\overline{\overline{M_x}}$  \_\_\_\_\_

$\overline{\overline{M_y}}$  \_\_\_\_\_

$T_1$  \_\_\_\_\_

$T_2$  \_\_\_\_\_

$V_1$  \_\_\_\_\_

$V_2$  \_\_\_\_\_

$V_3$  \_\_\_\_\_

$V_4$  \_\_\_\_\_

$W_1$  \_\_\_\_\_

$W_2$  \_\_\_\_\_

$W_3$  \_\_\_\_\_

$X_0$  \_\_\_\_\_

$Y_0$  \_\_\_\_\_

$Z_0$  \_\_\_\_\_



RESULTS OF QUALIFICATION RULES 1.3.8 AND 1.3.9 FOR GFVARule 1.3.8

- a.  $S_1 =$  \_\_\_\_\_ Yield strength of bonnet material  
 $S_2 =$  \_\_\_\_\_ Calculated bonnet stress  
 $S_1/S_2 =$  \_\_\_\_\_  $\geq 1$
- b.  $S_3 =$  \_\_\_\_\_ Yield strength (proof load) of bonnet to valve bolting  
 $S_4 =$  \_\_\_\_\_ Calculated stress of bonnet to valve bolting  
 $S_3/S_4 =$  \_\_\_\_\_  $> 1$
- c.  $S_5 =$  \_\_\_\_\_ Yield strength (proof load) of adaptor plate to bonnet bolting  
 $S_6 =$  \_\_\_\_\_ Calculated stress of adaptor plate to bonnet bolting  
 $S_5/S_6 =$  \_\_\_\_\_  $> 1$
- d.  $S_7 =$  \_\_\_\_\_ Yield strength (proof load) of actuator to adaptor plate bolting  
 $S_8 =$  \_\_\_\_\_ Calculated stress of actuator to adaptor plate bolting  
 $S_7/S_8 =$  \_\_\_\_\_  $> 1$

Rule 1.3.9 Bonnet Body Deflections ( $\Delta L$ )

$\Delta L$  of GFVA = \_\_\_\_\_ Deflection family valve

$\Delta L$  of GFVA  $< .002"$

## PART II

Section 6 A


## FUNCTIONAL QUALIFICATION REPORT

FOR


QUALIFIED TEST VALVE ASSEMBLY (QTVA)

Pratt Job No. D-0038-3

BPC P.O. Item 2.03



JOB NO. 9645



VENDOR'S DOCUMENT REVIEW	
1	<input checked="" type="checkbox"/> Approved - Mfg. may proceed.
2	<input type="checkbox"/> Approved - Submit final dwg - Mfg. may proceed.
3	<input type="checkbox"/> Approved - except as noted - Make changes and submit final dwg - Mfg. may proceed as approved.
4	<input type="checkbox"/> Not Approved - Correct and resubmit.
5	<input type="checkbox"/> Review not required - Mfg. may proceed.
Approval of _____ Date <u>9-11-78</u>	
JOB NO. 9645	BECHTEL CORPORATION POWER & INDUSTRIAL DIVISION P.O. BOX 607 GAITHERSBURG, MD

Project Site: Grand Gulf Nuclear Station  
Port Gibson, Mississippi

Customer: Mississippi Power & Light Company

Engineer: Bechtel Power Corporation

Specification: 9645-M-257.0

BPC P.O. Item: 9645-M-257.0

Prepared By:

Robert C. Sanson9-11-78

Date

Babu m. Paul9-11-78

Date

Reviewed By:

Keith J. Selin9-7-78

Date

Certified By:

Istvan Huk9-11-78

Date

9645 - M257.0 - QS-26.0-8-09645 - M258.0 - QS-26.0-8-0

023210316

Section 6A

Section 6 A

FUNCTIONAL QUALIFICATION REPORT  
FOR  
QUALIFIED TEST VALVE ASSEMBLY (QTVA)

Job No. D0038-3

Page No.

1.	Description and Characteristics of QTVA		1
2.	Base Line Data of QTVA to be used for Generic Qualification of GFVA		2
	Results of Qualification Rules of Paragraph 1.3.8 and 1.3.9		3
3.	Copy of Functional Qualification Report of Actuator to Show Compliance to IEEE 344 and IEEE 382		4
4.	Test Plan Results		<u>Date of Test</u>
4.1	Valve Leakage Test	Appendix A	5 <u>6-9-78</u>
4.2	Cold Cyclic Test	Appendix B	8 <u>6-14-78</u>
4.3	Seismic Loading Test	Appendix E	11 <u>6-14-78</u>
4.3.7	Valve Leakage Test	Appendix A	14 <u>6-15-78</u>
4.4	Hot Cyclic Test*	Appendix C	17 <u>NA</u>
4.5	Vibration Test	Appendix F	20 <u>3-21-78</u>
4.6	Temperature-Pressure Test	Appendix D	23 <u>NA</u>
5.	Dimensional Data Summary for Qualification Rules of Paragraph 1.3.8 and 1.3.9.		

THIS TEST VALVE ASSEMBLY WAS SUBJECTED TO ALL APPROPRIATE TEST REQUIREMENTS (PART I, PARAGRAPH 7.0) AND IT IS CONSIDERED A QUALIFIED TEST VALVE ASSEMBLY.

\*Applicable for service temperature in excess of 200°F.

1. DESCRIPTION AND CHARACTERISTICS

Valve Size and Type

36" 1100

Standard Pressure Class

150

Cold Working Pressure

275 psi

Rated Differential Pressure

75 psi

Maximum Service Temperature

200 °F

Actuator Type

-

Electric  
Motor

✓

Air

Actuator Size

T412-SR4

Normal Motive Power

-

Vac

100 psi

Minimum Motive Power

-

Vac

80 psi

Maximum Motive Power

-

Vac

110 psi

Job No. D0038-3

2. BASE LINE DATA OF QTVA TO BE USED FOR GENERIC QUALIFICATION OF GFVA

Reference  
Paragraph

1.3.1 Valve Size

36"

1.3.2 Seat Taper Angle

11°

1.3.3 Disc/Seat Interference

.030

1.3.4 Seating Surface Materials

ASME SA-240 TYPE 304

1.3.5 Materials of Construction

Body

ASME SA-516 GR. 55

Disc

ASME SA-516 GR. 70

Shaft

ASME SA-564, TYPE 630 COND. H 1150

Bearing

ASTM B-438 GR 2 TYPE 2

Seat

E.P.T.

Retainer Segments

-

Packing

E.P.T

Thrust Collar

SAE 660 BRONZE

Bottom Cover

ASME SA-516 GR. 55

Bonnet

ASME SA-36

Bolts: Valve to bonnet

SA 193 GR. B7

Bonnet to adaptor plate

SA 193 GR 7

Adaptor plate to actuator

SA 193 GR. 7

1.3.6 Actuator Rated Torque

20200

Calculated Operator Torque

19440

Ratio = 1.04

Operating Time

Open to Close

4 Sec.

Close to Open

60 Sec.



RESULTS OF QUALIFICATION RULES 1.3.8 and 1.3.9 FOR QTVARule 1.3.8

a.  $S_1 = \underline{36.000}$  Yield strength of bonnet material

$S_2 = \underline{1419}$  Calculated bonnet stress

$S_1/S_2 = \underline{25.37} > 1$

b.  $S_3 = \underline{95.000}$  Yield strength (proof load) of bonnet to valve bolting

$S_4 = \underline{9750}$  Calculated stress of bonnet to valve bolting

$S_3/S_4 = \underline{9.74} > 1$

c.  $S_5 = \underline{95.000}$  Yield strength (proof load) of adapter plate to bonnet bolting

$S_6 = \underline{6185}$  Calculated stress of adapter plate to bonnet bolting

$S_5/S_6 = \underline{15.36} > 1$

Rule 1.3.9

$\Delta_L$  of QTVA = .00024 Deflection of test valve

$\Delta_L$  of QTVA .002"

Reference Addendum 1 & 2 for equations used to determine stresses and deflection for Rules 1.3.8 and 1.3.9.

STATEMENT OF QUALIFICATION

QUALIFICATION TESTING

GH-BETTIS Actuator Model NT-412B-SR4 is hereby certified to be of the same construction as Bettis Actuator Model NT-420B-SR1 which was qualified to the requirements of ANSI 278.2.1, Draft 3, Rev.0, Feb. 1977 (IEEE 382) with the exception of LOCA by testing at Southwest Research Institute, San Antonio, Texas. Applicable test margins as described in paragraph 6.3.1.5 of IEEE 323-1974 were utilized with the exception of (8). Refer to SWRI Test Report No. 02-4854-RPT-1.

The LOCA testing required to complete the qualification program is scheduled to begin at Wyle Laboratories, Huntsville, Alabama on September 11. Upon successful completion of that testing a revised statement of certification will be issued referencing the applicable test report number.

Supplementary seismic testing was performed on Bettis Actuator Model NT-520B-SR1 to the requirements of the above referenced ANSI document. Results of that testing are contained in the same report.

SEISMIC ANALYSIS


In addition to the seismic test results obtained in the above referenced tests, Bettis Seismic Analysis Report No. R-1062-40 is offered as further supportive evidence to the rigidity of this actuator.

*Joel D. Page*

JOEL D. PAGE  
Senior Engineer  
Nuclear Products

JDP/ksy  
8-31-78

- 4.1.0 To demonstrate valve shut-off capability and pressure boundary meeting applicable leakage tolerances (para. 3.1). Test valve assembly to be mounted on test stand with the valve shaft oriented horizontally as shown in Figure 1.



- FIGURE 1

0  
2  
3  
2  
1  
0  
3  
2  
2  
0

4.1.1 Pre-Test Inspection

- 4.1.2 Adjust limit switches for proper open and closed positions of valve disc.

- 4.1.3 Measure normal motive power to actuator.

— Vac. 100 psi

- 4.1.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>430</u>	Measured <u>430</u>
Bonnet to <del>adaptor plate</del>	Required <u>NA</u>	Measured <u>NA</u>
<del>Adaptor plate</del> to actuator	Required <u>430</u>	Measured <u>430</u>
Adaptor plate to trunnion	Required <u>NA</u>	Measured <u>NA</u>
Bottom cover to trunnion	Required <u>30</u>	Measured <u>30</u>

- 4.1.5 Verify calibration of required test equipment.

4.1.6 Test Procedure (Appendix A)

- a. With the test valve assembly in the most adverse position (as shown in Figure 1) operate the valve with normal motive power starting from full closed position three operating cycles.

Measure and Record:

Motive Power	<u>—</u> Vac.	<u>100</u> psi	
Operating Time	Cycle #1	Cycle #2	Cycle #3
Closed to Open	<u>11.8</u> sec.	<u>11.6</u> sec.	<u>11.8</u> sec.
Open to Closed	<u>3.1</u> sec.	<u>2.9</u> sec.	<u>2.8</u> sec.

- b. Repeat Step a with minimum motive power.

Motive Power	<u>—</u> Vac.	<u>80</u> psi	
Operating Time	Cycle #1	Cycle #2	Cycle #3
Closed to Open	<u>16.3</u> sec.	<u>16.3</u> sec.	<u>16.3</u> sec.
Open to Closed	<u>2.5</u> sec.	<u>2.5</u> sec.	<u>2.7</u> sec.

- c. With the valve disc in the closed position, cover the disc with a pool of water deep enough to submerge disc/seat interference line.
- d. Using air as test fluid, pressurize valve assembly to 3 psi differential pressure across disc. Hold pressure for a minimum time of five minutes (A-3). Observe and record leakage (A-4). Bubble tight condition of valve seat is considered a successful qualification of the TVA.

Leakage NONE Bubble Tight TO AT LEAST  
3 PSIG

- e. Repeat steps c and d with pressure on opposite side of valve disc for bi-directional qualification

Leakage NONE Bubble Tight TO AT LEAST  
3 PSIG

- f. For the packing leak test the TVA is to be sandwiched in between two test heads as shown in Figure 2.




FIGURE 2

- g. With normal motive power applied to the actuator, cycle the TVA 10 times. Record cycle time for the first and tenth cycles.

Record:


Motive power	<u>—</u>	Vac.	<u>100</u>	psi
1st Cycle	Open to Close		<u>2.9</u>	sec.
	Close to Open		<u>11.8</u>	sec.
10th Cycle	Open to Close		<u>2.8</u>	sec.
	Close to Open		<u>11.8</u>	sec.

- h. With the valve disc in the open position, pressurize test valve assembly to cold working pressure of 3 psi using air as test fluid. Hold cold working pressure for a time period of 5 minutes. Observe leakage by applying soap solution around packing. Soap bubble tight condition of packing is considered successful qualification of TVA.

Leakage Observed NONE Soap Bubble Tight TO AT LEAST  
3 PSIG

## 4.2.0 Cold Cyclic Test

To demonstrate cyclic operability of the TVA (3.2) under the most adverse combination of motive power and system pressure. The test valve assembly is to be sandwiched between two test heads with the valve shaft oriented horizontally as shown in Figure 3.

4.2.1 Pre-Test Inspection

4.2.2 Adjust limit switches for proper closed and open position of valve disc.

4.2.3 Measure motive power to actuator.

— Vac. 100 psi

## 4.2.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>430</u>	Measured <u>430</u>
Bonnet to <del>adaptor plate</del>	Required <u>NA</u>	Measured <u>NA</u>
<del>Adaptor plate</del> to actuator	Required <u>430</u>	Measured <u>430</u>
Adaptor plate to trunnion	Required <u>NA</u>	Measured <u>NA</u>
Bottom cover to trunnion	Required <u>30</u>	Measured <u>30</u>

## 4.2.5 Verify calibration of required test equipment.



Job No. D 0038-3

4.2.6 Test Procedure (Appendix B)

- a. With the valve disc in the full open position pressurize pressure chamber A & B (Figure 3) to cold working pressure of 3 psi using air as test fluid. With minimum motive power of - Vac or 80 psi applied to actuator operate valve disc to full closed position.
- b. Reduce air pressure to 0 psi in pressure chamber B, and to 3 psi in pressure chamber A, to obtain a differential pressure of 3 psi across the closed valve disc.
- c. With minimum motive power of - Vac or 80 psi applied to actuator, open valve disc.
- d. Repeat steps a, b, and c twice.
- e. Data to be Recorded.

In step "a"

	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Motive Power	( <u>-</u> Vac	( <u>-</u> Vac	( <u>-</u> Vac
	( <u>80</u> psi	( <u>80</u> psi	( <u>80</u> psi

Operating Time

	1st Cycle	2nd Cycle	3rd Cycle
Open to Close	<u>2.8</u> sec	<u>2.6</u> sec	<u>2.7</u> sec

In step "b"

	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>0</u> psi	<u>0</u> psi	<u>0</u> psi
Motive Power	( <u>-</u> Vac	( <u>-</u> Vac	( <u>-</u> Vac
	( <u>80</u> psi	( <u>80</u> psi	( <u>80</u> psi

Operating Time

	1st Cycle	2nd Cycle	3rd Cycle
Close to Open	<u>15.9</u> sec	<u>16.1</u> sec	<u>16.3</u> sec

f. Repeat steps a to d using nominal motive power of — Vac or 100 psi.

g. Data to be Recorded

Step f, a	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Motive	( <u>—</u> Vac <u>100</u> psi)	( <u>—</u> Vac <u>100</u> psi)	( <u>—</u> Vac <u>100</u> psi)

Operating Time

	1st Cycle	2nd Cycle	3rd Cycle
Open to Close	<u>3.2</u> sec	<u>3.0</u> sec	<u>3.5</u> sec

Step f, b

	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>0</u> psi	<u>0</u> psi	<u>0</u> psi
Motive	( <u>—</u> Vac <u>100</u> psi)	( <u>—</u> Vac <u>100</u> psi)	( <u>—</u> Vac <u>100</u> psi)

Operating Time

	1st Cycle	2nd Cycle	3rd Cycle
Close to Open	<u>11.4</u> sec	<u>11.4</u> sec	<u>11.5</u> sec

h. With the test valve assembly depressurized and maximum power of — Vac or 110 psi applied to actuator, perform three operating cycles.

Data to be recorded:

	1st Cycle	2nd Cycle	3rd Cycle
Operating Time			
Open to Close	<u>3.4</u> sec	<u>3.1</u> sec	<u>3.0</u> sec
Close to open	<u>10.3</u> sec	<u>10.2</u> sec	<u>10.2</u> sec

i. Measured operating times within operating times specified in paragraph 1.3.6 are considered successful qualification of the test valve assembly.

- 4.3.0 To demonstrate cyclic operability of TVA under the most adverse combination of motive power, system pressure and loading representative of the maximum seismic incident, the test valve assembly is sandwiched between two test heads as shown in Figure 4.




FIGURE 4

- 4.3.1 Pre-Test Inspection
- 4.3.2 Adjust limit switches for proper closed and open position of valve disc.
- 4.3.3 Measure motive power to actuator

— Vac 100 psi

- 4.3.4 Measure required torque settings of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>430</u>	Measured <u>430</u>
Bonnet to adaptor plate	Required <u>NA</u>	Measured <u>NA</u>
<del>Adaptor plate to actuator</del>	Required <u>430</u>	Measured <u>430</u>
Adaptor plate to trunnion	Required <u>NA</u>	Measured <u>NA</u>
Bottom cover to trunnion	Required <u>30</u>	Measured <u>30</u>

Job No. D0038-3

4.3.5 Test Procedure (Appendix E)

- a. A static load shall be applied in line with the center of gravity of the valve operator. The static load shall equal twice the operator weight applied in the vertical direction (downward) and three times the operator weight in a direction parallel to the valve nozzle centerline applied simultaneously. Ref. Addendum 1 & 2 for the determination of test loads to be applied.
- b. With the static load applied as described in paragraph a and with the valve disc in the full open position, pressurize pressure chamber A and B to a cold working pressure of 3 psi. Use air as test fluid. With minimum motive power of - Vac or 80 psi applied to actuator, operate valve disc to full closed position.
- c. Reduce air pressure to 0 psi in pressure chamber B and 3 psi in pressure chamber A to obtain a differential pressure of 3 psi across valve disc.
- d. With minimum motive power of - Vac or 80 psi applied to actuator, open valve disc.
- e. Repeat steps a, b, and c twice.
- f. Data to be Recorded:

In step A	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Motive Power	( <u>-</u> Vac	<u>-</u> Vac	<u>-</u> Vac
	( <u>80</u> psi	<u>80</u> psi	<u>80</u> psi
Operating Time			
Open to Close	<u>2.7</u> sec	<u>3.0</u> sec	<u>2.8</u> sec

0 2 3 2 1 0 3 2 9

In step b	1st Cycle	2nd Cycle	3rd Cycle
Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>0</u> psi	<u>0</u> psi	<u>0</u> psi
Motive Power	( <u>-</u> Vac	<u>-</u> Vac	<u>-</u> Vac
	( <u>80</u> psi	<u>80</u> psi	<u>80</u> psi

Operating Time

Close to Open 15.9 sec 15.9 sec 16.1 secg. Repeat steps a to d using normal motive power of - Vac or100 psi.

h. Data to be Recorded

Step g, b

Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Motive Power	( <u>-</u> Vac	<u>-</u> Vac	<u>-</u> Vac
	( <u>100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Open to Close 3.0 sec 3.0 sec 3.0 sec

Step g, c

Pressure in Chamber A	<u>3</u> psi	<u>3</u> psi	<u>3</u> psi
Pressure in Chamber B	<u>0</u> psi	<u>0</u> psi	<u>0</u> psi
Motive Power	( <u>-</u> Vac	<u>-</u> Vac	<u>-</u> Vac
	( <u>100</u> psi	<u>100</u> psi	<u>100</u> psi

Operating Time

Close to Open 11.5 sec 11.5 sec 11.6 sec

i. With the test valve assembly depressurized and maximum motive power of - Vac or 110 psi applied to actuator, perform three operating cycles.

Data to be recorded:

Operating time	1st Cycle	2nd Cycle	3rd Cycle
Open to Close	<u>2.9</u> sec	<u>3.0</u> sec	<u>3.1</u> sec
Close to Open	<u>10.3</u> sec	<u>10.3</u> sec	<u>10.3</u> sec

- j. Measured operating times within operating times specified in paragraph 1.3.6 are considered successful qualification of the test valve assembly.

#### 4.3.6 Valve Leakage Test

To demonstrate that the test valve is capable of meeting seat and shaft packing sealing requirements after exposure to the most adverse combination of motive power, system pressure and seismic loading tests, the test valve assembly is mounted on test stand with the valve shaft oriented horizontally as shown in Figure 5.




FIGURE 5

#### 4.3.7 Pre-Test Inspection

4.3.8 Adjust limit switches for proper open and closed positions of valve disc.

4.3.9 Measure normal motive power to actuator.

— Vac 100 psi



## 4.3.10 Measure required torque setting of fasteners. (Ft. Lb.)

Bonnet to trunnion	Required <u>430</u>	Measured <u>430</u>
Bonnet to <del>adaptor plate</del>	Required <u>NA</u>	Measured <u>NA</u>
<del>Adaptor plate to</del> actuator	Required <u>430</u>	Measured <u>430</u>
Adaptor plate to trunnion	Required <u>NA</u>	Measured <u>NA</u>
* Bottom cover to trunnion	Required <u>30</u>	Measured <u>30</u>

## 4.3.11 Verify calibration of required test equipment.

## 4.3.12 Test Procedure (Appendix A)

- a. With the test valve assembly in the most adverse position (as shown in Figure 1) operate the valve with normal motive power starting from full closed position three operating cycles.

Data to be Recorded

Motive Power	<u>—</u> Vac	<u>100</u> psi	
Operating Time	1st Cycle	2nd Cycle	3rd Cycle
Closed to Open	<u>12.0</u> sec	<u>11.6</u> sec	<u>11.5</u> sec
Open to Closed	<u>3.0</u> sec	<u>3.0</u> sec	<u>3.1</u> sec

- b. Repeat step a with minimum motive power.

Motive Power	<u>—</u> Vac	<u>80</u> psi	
Operating Time	1st Cycle	2nd Cycle	3rd Cycle
Closed to Open	<u>15.9</u> sec	<u>15.8</u> sec	<u>15.7</u> sec
Open to Closed	<u>2.7</u> sec	<u>2.7</u> sec	<u>2.8</u> sec

- c. With the valve disc in the closed position, cover the disc with a pool of water deep enough to submerge disc/seat interference line.
- d. Using air as test fluid, pressurize valve assembly to 3 psi differential pressure across disc. Hold pressure for a time period of five minutes (A-3). Observe and record leakage (A-4). Bubble tight condition of valve seat is considered a successful qualification of TVA.

Leakage Observed NONEBubble Tight TO AT LEAST3 PSIG

- e. Repeat steps c and d with pressure on opposite side of valve disc for bi-directional qualification.

Leakage Observed NONE Bubble Tight TO AT LEAST

- f. For the packing leak test the TVA is to be sandwiched between two test heads as shown in Figure 6.




FIGURE 6

- g. With normal motive power applied to the actuator, cycle the TVA 10 times. Record cycle time for the first and tenth cycles.

Data to be Recorded

Motive Power	<u>-</u> Vac	<u>100</u> psi
1st Cycle	Open to Close	<u>3.0</u> sec
	Close to Open	<u>11.6</u> sec
10th Cycle	Open to Close	<u>3.0</u> sec
	Close to Open	<u>11.6</u> sec

- h. With the valve disc in the open position, pressurize test valve assembly to cold working pressure of 3 psi using air as test fluid. Hold cold working pressure for a time period of 5 minutes. Observe leakage by applying soap solution around packing. Soap bubble tight condition of packing is considered successful qualification of TVA.

Leakage Observed NONE Soap Bubble Tight TO AT LEAST  
3 PSIG



Bechtel Power Corporation

# ORIGINAL PAGE MISSING

9645 Supplier Document

M-258.0 QS 26.0-8-0

(356718)

Page 17

Section 6A Part II

(IDENTIFY MISSING PAGES, IF POSSIBLE)



Bechtel Power Corporation

# ORIGINAL PAGE MISSING

9645 Supplier Document

M-258.0 QS 26.0-8-0

(356718)

Page 18

Section 6A Part 2

(IDENTIFY MISSING PAGES, IF POSSIBLE)



Bechtel Power Corporation

# ORIGINAL PAGE MISSING

9645 Supplier Document

M-258.0 QS 26.0-8-0

(356718)

Page 19

Section 6A Part 2

(IDENTIFY MISSING PAGES, IF POSSIBLE)



Bechtel Power Corporation

# ORIGINAL PAGE MISSING

QW45 Supplier Document

M-258.0 QS 26.0.8-0

(356718)

Page 20

Section 6A Part 2

(IDENTIFY MISSING PAGES, IF POSSIBLE)



#### 4.5.0 Vibration Test

To demonstrate operability of the test valve assembly during and after vibratory disturbances, and to establish the validity of natural frequency calculations the test valve assembly is to be mounted on a seismic test machine with the valve shaft oriented horizontally. (Para. 5.2 of

\* Qualification Requirements)

#### 4.5.1 Pre-Test Inspection

- a. Receiving inspection - Identification and visual inspection of TVA for evidence of damage due to shipping. To be performed in the presence of HPCo. representative.
- b. Description of test valve assembly mounting to seismic test machine - photograph of test apparatus to be included.
- c. Adjust limit switches for proper open and closed position of valve disc.
- d. Measure motive power to actuator.

— Vac 90 psi

- e. Describe test equipment and calibration methods including location and number of control and response accelerometers.

#### 4.5.2 Test Procedure

- a. With the test valve assembly mounted to the seismic test machine in the most adverse position (para. 5.2 of Qualification Requirements) operate valve with nominal motive power starting from full closed position.

Measure and record:

Motive power — Vac 90 psi

Operating time

Closed to open 12 sec

Open to closed 3 sec

0 2 3 2 1 0 3 3 8


- 023210339
- b. Resonance search - A steady state sinusoidal resonant search to be performed in each of the three mutually perpendicular axis. Input test level amplitude to be at least 0.2g (zero to peak). The frequency range of 3.5 to 95 Hz to be covered with a sweep rate not exceeding one octave per minute. For the purpose of this test resonance is defined as a frequency at which acceleration of the actuator at the plane of the center of gravity perpendicular to the shaft centerline exceeds the input acceleration level by a factor of 3 or more.
  - c. Variable frequency test - A variable frequency test to be performed with a minimum input test level of 0.5 g (zero to peak) in the mutually perpendicular axis of the following frequencies. 3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71, and 95 Hz. At each of the above frequencies repeat step a and record motive power and each half of operating time.
  - d. Endurance test - The test valve assembly to be vibrated with a minimum input of 0.5g (zero to peak) in the three mutually perpendicular axis at resonant frequencies found in step b and at 33 Hz, for a time period of three minutes. At the conclusion of each of the three minute vibration test with the test assembly still vibrating, operability of the test valve assembly to be demonstrated by performing step a.
  - e. Measured operating times within operating time specified in paragraph 1.3.6 and rechecked in para. a are considered successful qualification of test valve assembly.

FOR TEST RESULTS SEE ATTACHED

AERO-NAV LAB. REPORT DATED MAY-9-1978

# AERO NAV

LABORATORIES, INC.



14-29 112TH STREET • COLLEGE POINT, N.Y. 11356 • (212) 939-4422

( UNCLASSIFIED )


REPORT OF SEISMIC TEST  
ON  
36-INCH VALVE WITH  
ROBOTARM OPERATOR  
FOR  
HENRY PRATT COMPANY  
AURORA, ILLINOIS

TESTED BY	<i>Joseph Z. Ed</i>	ETL REPORT	7-6534-7
CHECKED BY	<i>for Henry Pratt</i>	AERO NAV SALES ORDER	7-6534
APPROVED BY	<i>Floyd Se</i>	CUSTOMER P.O.	B-58030
DATE	9 MAY 1978	P.O. ITEM NO. - 4 TEST VALVE NO. - 6 PRATT JOB NO. - D-0038-3	
GOVERNMENT QAR	NONE		

0 2 3 2 1 0 3 4 0

( UNCLASSIFIED )  
ADMINISTRATIVE DATA

DATE  
9 May 1978



PURPOSE OF TEST: To determine the effects of Seismic Vibration on the physical and operational characteristics of the submitted specimen.

MANUFACTURER: HENRY PRATT COMPANY  
401 S. Highland Avenue  
Aurora, Illinois 60507

MANUFACTURER TYPE AND SERIAL NUMBER: As specified on Purchase Order, the following nomenclature applies:  
36-inch Valve with Robotarm Operator  
See Paragraph 2.0 for nameplate data.

DRAWINGS SPECIFICATIONS OR EXHIBIT: Tested in accordance with Henry Pratt Company Test Procedure

QUANTITY OF ITEMS TESTED: One (1) only

EQUIPMENT: Unclassified  
REPORT: Unclassified


DATE TEST COMPLETED: 21 March 1978

TEST CONDUCTED BY: AERO NAV LABORATORIES, INC.  
14-29 112th STREET  
COLLEGE POINT, NEW YORK 11356

DISPOSITION OF SPECIMEN: Returned to client

ABSTRACT: It is the function of the Aero Nav Laboratories, Inc., as an impartial testing agency in performing this test to subject the specimen to seismic vibration of magnitude and direction as specified in the detailed specifications.


## FACTUAL DATA

1.0 DESCRIPTION OF TEST APPARATUS:

- 1.1 Accelerometers, Model No. 2213E, Serial Nos. CP36, CP37, CP43, CP47 & CP48, manufactured by Endevco Corporation.  
Calibration Due: 13 July 1978.
- 1.2 Amplifier, Model No. 2616, Serial No. CA-13, manufactured by Endevco Corporation.  
Calibration Due: 13 July 1978.
- 1.3 Amplifier, Model No. 2616B, Serial No. KA-07, manufactured by Endevco Corporation.  
Calibration Due: 13 July 1978.
- 1.4 Power Supply, Model No. 2621, Serial No. 9026, manufactured by Endevco Corporation.  
Calibration Due: 13 July 1978.
- 1.5 Power Supply, Model No. 2622, Serial No. CA-24, manufactured by Krohn-Hite Corporation.  
Calibration Due: 13 July 1978.
- 1.6 Band Pass Filter, Model No. 330M, Serial No. 2116, manufactured by Ballantine Labs.  
Calibration Due: 12 September 1978.
- 1.7 True R.M.S. VTVM, Model No. 320A, Serial No. 8400, manufactured by Ballantine Labs.  
Calibration Due: 4 May 1978.
- 1.8 Vibration Test Stand, Model 72-5000, Serial No. 51402, manufactured by L.A.B. Corporation.  
Calibration Due: 13 July 1978.

0 2 3 2 1 0 3 4 2

FACTUAL DATA



2.0 NAMEPLATE DATA:


Nameplate Data (valve)  
Nuclear Class 3  
3 PSI at 150°F  
Valve S/N D-0038-3-4  
Tag No. SQ-36-HBC-AO-F020-OWY  
Body Mat. SA516 GR55  
Year 1976  
P.O. 9645-M-257.0  
Job 9645 Item 2-2.03B

Nameplate Data (actuator)  
Robotarm  
Model No. 7412-SR-4  
Serial No. 50929-4  
Nominal Working Press. 91 PSI  
Maximum Working Press. 220 PSI  
Maximum Test Press. 220 PSI

0 2 3 2 1 0 3 4 3



## FACTUAL DATA

3.0 METHOD OF TEST:

The submitted valve, mounted so as to simulate installed conditions, was affixed to the table of the seismic simulator and was subjected to the following:

3.1 Resonance Frequency Search:

The specimen was subjected to a resonant frequency search from 3.5 to 95 Hz. The input acceleration was in accordance with Table I.

TABLE I

<u>Frequency</u>	<u>Acceleration</u>
3.5 to 95 Hz	0.2 g's

The frequency was increased in steps of 1 Hz and vibration was maintained at each frequency for a period of approximately twenty (20) seconds.

The above test was performed in each of the three (3) mutually perpendicular axes independently.

For the purpose of this test, resonance is defined as a frequency at which acceleration of the actuator at the plane of the center of gravity perpendicular to the shaft centerline exceeds the input acceleration level by a factor of three (3) or more.

3.2 Variable Frequency Test:


Upon completion of resonant frequency search in each of the three (3) mutually perpendicular axes, the specimen was subjected to a dwell test at the following frequencies:

3.5, 4.5, 6, 8, 11, 15, 21, 29, 39, 53, 71 and 95 Hz. The acceleration level was 0.5 g's. Vibration was maintained at each frequency for a sufficient length of time in order to determine the following valve/actuator parameters:

- (1) Input Air - 90 psig shop air nominal
- (2) Operating Time
  - (a) Closed to open
  - (b) Open to closed

The above test was accomplished in each of the three (3) mutually perpendicular axes.

0 2 3 2 1 0 3 1 4

METHOD OF TEST (continued)3.3 Endurance Test:

The specimen was subjected to vibration at an amplitude of 0.5g at each of the resonant frequencies encountered during the resonant search and at 33 Hz for a time period of three (3) minutes at each frequency.


At the conclusion of each of the three (3) minute vibration test the following valve/actuator parameters were determined.

- (1) Input Air - 90 psig shop air nominal
- (2) Operating Time
  - (a) Closed to open
  - (b) Open to closed

The above test was accomplished in each of the three (3) mutually perpendicular axes.

0 2 3 2 1 0 3 4 5

FACTUAL DATA



4.0 RESULTS OF TESTS:

4.1 Horizontal (along the valve stem) Axis (H2)

4.1.1 Resonance Frequency Search:

Accelerometer Locations:

Input accelerometers are located on the valve side of the bonnet on the valve.

Output accelerometers are located on the actuator side of the bonnet on the actuator.


Inputs A - Horizontal across stem (H1)  
B - Horizontal with stem (H2)  
C - Vertical (V)

Outputs D - Horizontal across stem (H1)  
E - Horizontal with stem (H2)  
F - Vertical (V)

0 2 3 2 1 0 3 4 6

( UNCLASSIFIED )

FACTUAL DATA



RESULTS OF TESTS:


Horizontal (along the valve stem) Axis (H2)

Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
5	.010	.090	.012	.010	.080	.056
6	.012	.15	.026	.010	.14	.060
7	.014	.22	.048	.012	.22	.070
8	.019	.30	.065	.014	.30	.084
9	.011	.11	.028	.010	.10	.030
10	.014	.15	.037	.010	.15	.040
11	.018	.20	.050	.010	.20	.050
12	.020	.23	.055	.010	.23	.054
13	.028	.30	.072	.010	.30	.070
14	.011	.10	.028	.010	.10	.025
15	.013	.12	.032	.010	.12	.029
16	.014	.14	.037	.010	.14	.032
17	.016	.16	.042	.010	.16	.034
18	.018	.18	.049	.010	.18	.039
19	.019	.20	.055	.010	.20	.044
20	.021	.23	.060	.010	.23	.045
21	.024	.25	.066	.010	.25	.050
22	.029	.29	.076	.010	.29	.050
23	.033	.30	.08	.010	.30	.054
24	.016	.096	.040	.028	.096	.032
25	.017	.099	.042	.031	.099	.024
26	.017	.11	.047	.020	.11	.040
27	.016	.115	.050	.022	.115	.040
28	.015	.12	.054	.047	.115	.070
29	.028	.14	.062	.033	.14	.080
30	.026	.145	.062	.020	.145	.042
31	.024	.155	.066	.024	.155	.040
32	.020	.17	.070	.022	.17	.045
33	.021	.18	.073	.024	.18	.046
34	.019	.185	.076	.020	.185	.049
35	.023	.19	.078	.0225	.19	.054
36	.025	.20	.086	.025	.20	.060
37	.024	.22	.096	.030	.22	.040
38	.025	.23	.11	.040	.23	.036
39	.028	.24	.115	.035	.25	.080
40	.036	.25	.14	.046	.27	.068

0 2 3 2 1 0 3 4 7

## FACTUAL DATA


RESULTS OF TESTS:Horizontal (along the valve stem) Axis (H2)Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
41	.2	.081	.2	.10	.44	.16
42	.2	.080	.19	.088	.42	.15
43	.2	.080	.19	.10	.35	.15
44	.2	.092	.17	.11	.42	.17
45	.2	.10	.18	.12	.47	.16
46	.2	.12	.18	.14	.70	.22
47	.2	.115	.18	.14	.71	.22
48	.2	.13	.46	.19	1.0	.30
49	.2	.10	.20	.14	1.2	.39
50	.2	.09	.38	.13	1.15	.38
51	.2	.061	.084	.085	1.0	.34
52	.2	.051	.078	.078	1.0	.34
53	.2	.033	.084	.061	.92	.33
54	.2	.031	.099	.051	.89	.31
55	.2	.040	.11	.070	.81	.26
56	.2	.060	.15	.095	.70	.23
57	.2	.085	.30	.13	.90	.28
58	.2	.079	.40	.15	.78	.26
59	.2	.074	.32	.11	.72	.25
60	.2	.13	.26	.16	.78	.26
61	.2	.14	.30	.15	.84	.27
62	.2	.15	.25	.16	1.1	.35
63	.2	.14	.28	.15	1.4	.42
64	.2	.13	.40	.16	1.4	.39
65	.2	.12	.47	.17	.88	.25
66	.2	.13	.45	.19	.62	.15
67	.2	.084	.22	.12	.9	.28
68	.2	.11	.4	.17	.9	.28
69	.2	.075	.3	.11	.33	.075
70	.2	.076	.36	.12	.52	.12
71	.2	.085	.42	.18	.8	.2
72	.2	.17	.5	.28	.9	.25
73	.2	.12	.4	.15	.32	.3
74	.2	.09	.34	.12	.4	.25
75	.2	.10	.38	.14	.48	.26
76	.2	.15	.44	.26	.69	.32
77	.2	.2	.5	.3	.86	.35
78	.2	.087	.34	.13	.45	.21
79	.2	.16	.4	.28	.58	.25
80	.2	.22	.45	.29	.88	.28

0 2 3 2 1 0 3 4 8

( UNCLASSIFIED )

FACTUAL DATA



RESULTS OF TESTS:

Horizontal (along the valve stem) Axis (H2)

Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
81	.2	.14	.4	.23	.5	.21
82	.2	.25	.44	.29	.67	.3
83	.2	.21	.4	.26	.56	.25
84	.2	.29	.46	.27	.3	.2
85	.2	.28	.47	.28	.41	.24
86	.2	.28	.5	.27	.46	.25
87	.2	.26	.47	.26	.42	.24
88	.2	.25	.43	.23	.44	.24
89	.2	.2	.42	.22	.41	.23
90	.2	.18	.37	.2	.3	.22
91	.2	.16	.34	.17	.28	.22
92	.2	.10	.26	.12	.23	.2
93	.2	.039	.17	.05	.23	.2
94	.2	.018	.12	.035	.24	.19
95	.2	.017	.10	.020	.25	.20

0 3 4 9

0 2 3 2 1



# RESULTS OF TESTS:

## Horizontal (along the valve stem) Axis (H2) (continued)

### 4.1.2 Variable Frequency Test:

Frequency (Hz)	Inputs (G's)			Outputs (G's)			Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
4.5	.11	.11	.11	.05	.08	.05	12	3
6	.18	.11	.11	.08	.14	.08	12	3
8	.35	.14	.16	.11	.35	.10	12	3
11	.5	.14	.22	.05	.5	.08	12	3
15	.5	.11	.2	.07	.5	.1	12	3
21	.5	.12	.27	.14	1.5	.54	12	2.8
29	.5	.16	.55	.24	1.7	.45	12	3
39	.5	.17	.32	.18	1.2	.44	12	3
53	.5	.10	.11	.16	2.1	.72	12	2.7
71	.5	.065	.27	.078	.75	.18	12	2.7
95	.5	.090	.24	.086	.19	.24	12.1	2.7

There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

( UNCLASSIFIED )  
FACTUAL DATA

## RESULTS OF TESTS:

### Horizontal (along the valve stem) Axis (H2) (continued)


#### 4.1.2 Endurance Vibration Test:

The endurance vibration test was performed at the following frequency for a time period of three (3) minutes.

Frequency (Hz)	Inputs (G's)			Outputs (G's)			Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
33	.50	.24	.51	.31	2.2	.58	12.0	2.8
49	.50	.22	.35	.30	2.2	.69	12.0	2.8
57	.50	.11	.41	.18	1.55	.49	12.0	2.8
64	.50	.32	1.1	.48	3.3	.68	12.0	2.8
67	.50	.52	2.0	.86	7.6	1.3	12.0	2.8
72	.50	.50	2.0	.72	6.4	1.2	12.0	2.7
77	.50	.40	1.6	.75	2.9	.75	12.0	2.7
80	.50	.55	.9	.57	2.4	.84	12.0	2.8
82	.50	.54	.75	.51	1.6	.65	12.0	2.7

There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

FACTUAL DATA



RESULTS OF TESTS (continued)

4.2 Vertical Axis:

4.2.1 Resonance Frequency Search:

Accelerometer Locations:

Input accelerometers are located on the valve side of the bonnet on the valve.

Output accelerometers are located on the actuator side of the bonnet on the actuator.


Inputs A - Horizontal across stem (H1)  
B - Horizontal with stem (H2)  
C - Vertical (V)

Outputs D - Horizontal across stem (H1)  
E - Horizontal with stem (H2)  
F - Vertical (V)

0 2 3 2 1 0 3 5 2

( UNCLASSIFIED )

FACTUAL DATA



RESULTS OF TESTS:


Vertical Axis:

Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
5	.040	.010	.11	.010	.010	.11
6	.056	.013	.17	.010	.010	.17
7	.080	.018	.24	.010	.010	.25
8	.036	.010	.10	.010	.010	.11
9	.044	.011	.13	.010	.010	.13
10	.055	.013	.15	.010	.010	.16
11	.068	.017	.20	.010	.010	.22
12	.080	.021	.25	.010	.010	.26
13	.094	.024	.30	.012	.010	.30
14	.036	.014	.12	.015	.010	.12
15	.040	.014	.13	.012	.010	.14
16	.046	.017	.15	.012	.010	.16
17	.052	.019	.17	.014	.010	.18
18	.057	.023	.19	.013	.011	.20
19	.065	.024	.21	.013	.011	.22
20	.071	.26	.23	.014	.010	.26
21	.080	.028	.27	.017	.010	.29
22	.090	.031	.30	.021	.010	.32
23	.025	.020	.096	.013	.012	.10
24	.028	.021	.10	.018	.013	.11
25	.027	.024	.11	.019	.012	.11
26	.028	.026	.12	.019	.011	.12
27	.030	.026	.135	.028	.012	.135
28	.038	.030	.14	.050	.014	.165
29	.036	.034	.15	.028	.020	.18
30	.038	.035	.16	.020	.019	.20
31	.040	.031	.18	.020	.020	.21
32	.045	.040	.19	.015	.022	.225
33	.048	.043	.20	.019	.023	.24
34	.050	.046	.205	.020	.030	.26
35	.056	.045	.22	.018	.030	.23
36	.060	.047	.25	.018	.025	.30
37	.064	.050	.27	.020	.027	.31
38	.070	.057	.28	.026	.023	.315
39	.078	.059	.29	.022	.025	.33
40	.10	.061	.30	.045	.025	.33

0 2 3 2 1 0 3 5 3


## FACTUAL DATA

RESULTS OF TESTS:Vertical Axis:Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
41	.034	.025	.2	.52	.028	.2
42	.032	.023	.2	.55	.031	.16
43	.038	.042	.2	.63	.057	.19
44	.033	.033	.2	.56	.043	.2
45	.032	.027	.2	.63	.034	.2
46	.031	.024	.2	.56	.028	.185
47	.033	.025	.2	.56	.024	.19
48	.03	.044	.2	.6	.035	.21
49	.071	.093	.2	.63	.096	.18
50	.072	.1	.2	.66	.11	.18
51	.033	.04	.2	.56	.05	.13
52	.029	.025	.2	.58	.055	.15
53	.023	.022	.2	.61	.023	.17
54	.021	.021	.2	.64	.027	.17
55	.02	.029	.2	.57	.03	.16
56	.041	.068	.2	.65	.041	.17
57	.050	.078	.2	.88	.070	.24
58	.057	.084	.2	.92	.060	.25
59	.058	.11	.2	.9	.065	.24
60	.060	.065	.2	.8	.055	.25
61	.069	.070	.2	.8	.1	.23
62	.046	.064	.2	.68	.070	.2
63	.033	.063	.2	.7	.068	.121
64	.037	.047	.2	.72	.042	.21
65	.042	.032	.2	.68	.050	.22
66	.043	.040	.2	.61	.035	.19
67	.038	.050	.2	.6	.047	.2
68	.045	.033	.2	.46	.035	.16
69	.045	.028	.2	.47	.40	.15
70	.037	.037	.2	.47	.026	.15
71	.040	.039	.2	.45	.034	.14
72	.058	.027	.2	.4	.039	.14
73	.055	.020	.2	.4	.032	.15
74	.053	.023	.2	.41	.031	.145
75	.050	.015	.2	.36	.026	.14
76	.054	.035	.2	.34	.025	.13
77	.063	.028	.2	.23	.034	.12
78	.066	.028	.2	.22	.028	.12
79	.07	.03	.2	.23	.021	.12
80	.066	.027	.2	.27	.04	.12

0 2 3 2 i 0 3 5 4

## FACTUAL DATA

RESULTS OF TESTS:Vertical Axis:Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
81	.12	.032	.2	.54	.041	.1
82	.11	.041	.2	.6	.057	.11
83	.080	.042	.2	.58	.065	.13
84	.055	.045	.2	.55	.057	.12
85	.048	.047	.2	.36	.051	.1
86	.051	.056	.2	.33	.066	.1
87	.071	.060	.2	.45	.085	.11
88	.085	.047	.2	.8	.056	.17
89	.043	.045	.2	.5	.044	.12
90	.046	.066	.2	.38	.070	.085
91	.033	.074	.2	.33	.076	.070
92	.024	.082	.2	.26	.086	.057
93	.019	.094	.2	.23	.1	.05
94	.013	.115	.2	.18	.12	.057
95	.064	.16	.2	.34	.16	.13

0 3 5 5

0 2 3 2 1



# RESULTS OF TESTS:

## Vertical Axis (continued)

### 4.2.2 Variable Frequency Test:

Frequency (Hz)	Inputs (G's)				Outputs (G's)		Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
3.5	.06	-	.1	.04	.02	.09	12	2
4.5	.02	.02	.13	.02	.02	.13	12	3
6	.02	.04	.19	.02	.02	.18	12	3
8	.02	.07	.31	.02	.02	.31	12	3
11	.07	.11	.5	.02	.04	.5	12	3
15	.03	.05	.5	.02	.05	.5	12	3
21	.06	.02	.5	.04	.02	.5	12	3
29	.09	.04	.5	.04	.04	.53	12	3
39	.078	.042	.5	1.5	.074	.48	12	3
53	.048	.063	.5	1.3	.064	.37	12	3
71	.12	.056	.5	2.6	.4	.7	12	3
95	.14	.38	.5	2.6	.4	.7	12	3

There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

### 4.2.3 Endurance Vibration Test:


The endurance vibration test was performed at the following frequency for a time period of three (3) minutes.

Frequency (Hz)	Inputs (G's)				Outputs (G's)		Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
33	.13	.18	.5	.54	.19	.54	12	3

There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

UNCLASSIFIED

FACTUAL DATA



RESULTS OF TESTS (continued)

4.3 Horizontal (perpendicular to the valve stem) Axis (H1)

4.3.1 Resonance Frequency Search:

Accelerometer Locations:

Input accelerometers are located on the valve side of the bonnet on the valve.


Output accelerometers are located on the actuator side of the bonnet on the actuator.

Inputs A - Horizontal across stem (H1)  
B - Horizontal with stem (H2)  
C - Vertical (V)

Outputs D - Horizontal across stem (H1)  
E - Horizontal with stem (H2)  
F - Vertical (V)

0 2 3 2 1 0 3 5 7


## FACTUAL DATA

RESULTS OF TESTS:Horizontal (perpendicular to the valve stem) Axis (H1)Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
5	.090	.01	.03	.090	.01	.01
6	.15	.01	.03	.15	.01	.01
7	.22	.01	.03	.22	.01	.02
8	.096	.01	.03	.098	.01	.02
9	.11	.02	.04	.11	.01	.02
10	.15	.02	.05	.15	.01	.03
11	.18	.03	.07	.19	.01	.03
12	.21	.03	.08	.21	.01	.04
13	.26	.05	.11	.26	.02	.06
14	.30	.06	.12	.31	.03	.06
15	.096	.07	.12	.097	.03	.08
16	.10	.01	.04	.10	.03	.10
17	.12	.02	.05	.12	.01	.03
18	.13	.02	.05	.13	.01	.04
19	.15	.02	.05	.15	.01	.05
20	.096	.03	.04	.10	.01	.04
21	.10	.03	.04	.11	.01	.04
22	.12	.03	.03	.12	.01	.04
23	.13	.03	.04	.14	.01	.05
24	.14	.04	.04	.15	.016	.07
25	.16	.04	.05	.17	.025	.11
26	.17	.04	.06	.19	.01	.07
27	.19	.05	.06	.2	.016	.07
28	.2	.05	.06	.21	.01	.05
29	.22	.05	.07	.24	.01	.08
30	.24	.06	.08	.26	.01	.10
31	.25	.06	.08	.27	.01	.10
32	.26	.06	.08	.29	.01	.10
33	.28	.06	.10	.31	.01	.11
34	.3	.07	.09	.34	.01	.13
35	.13	.01	.02	.12	.03	.09
36	.14	.01	.02	.13	.04	.10
37	.14	.01	.07	.14	.04	.12
38	.16	.01	.03	.14	.03	.12
39	.17	.01	.03	.14	.02	.10
40	.18	.02	.03	.16	.02	.06

0 2 3 2 1 0 3 5 3


## FACTUAL DATA

RESULTS OF TESTS:Horizontal (perpendicular to the valve stem) Axis (H1)Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)				Outputs (G's)	
	A	B	C	D	E	F
41	.13	.2	.37	.21	.78	.25
42	.11	.2	.37	.20	.77	.25
43	.12	.2	.43	.26	.76	.26
44	.105	.2	.39	.24	.73	.24
45	.10	.2	.36	.21	.76	.25
46	.087	.2	.42	.21	.80	.26
47	.12	.2	.54	.22	.96	.31
48	.11	.2	.54	.20	.84	.28
49	.10	.2	.50	.21	.80	.27
50	.11	.2	.52	.21	.81	.26
51	.086	.2	.54	.19	.74	.25
52	.086	.2	.55	.21	.74	.25
53	.081	.2	.53	.20	.60	.21
54	.076	.2	.47	.20	.52	.17
55	.074	.2	.44	.18	.49	.18
56	.072	.2	.41	.18	.47	.17
57	.057	.2	.38	.16	.45	.15
58	.055	.2	.37	.16	.52	.13
59	.068	.2	.30	.17	.66	.18
60	.088	.2	.30	.20	.99	.28
61	.086	.2	.33	.20	1.2	.38
62	.080	.2	.33	.19	.86	.27
63	.084	.2	.32	.18	.88	.29
64	.12	.2	.40	.20	1.2	.38
65	.12	.2	.46	.21	1.4	.43
66	.15	.2	.67	.28	1.6	.55
67	.17	.2	.72	.27	1.6	.55
68	.17	.2	.20	.28	1.4	.48
69	.13	.2	.63	.25	1.2	.41
70	.16	.2	.66	.27	1.2	.41
71	.15	.2	.65	.27	1.1	.40
72	.16	.2	.68	.28	1.2	.40
73	.15	.2	.59	.28	.97	.33
74	.21	.2	.72	.28	1.7	.52
75	.23	.2	.70	.27	1.4	.48
76	.19	.2	.50	.26	.77	.58
77	.17	.2	.44	.27	.62	.24
78	.17	.2	.41	.22	.60	.22
79	.15	.2	.36	.20	.43	.16
80	.16	.2	.35	.19	.46	.15

0 2 3 2 1 0 3 5 9

## FACTUAL DATA

RESULTS OF TESTS:Horizontal (perpendicular to the valve stem) Axis (H1)Resonance Frequency Search (continued)

Frequency (Hz)	Inputs (G's)			Outputs (G's)		
	A	B	C	D	E	F
81	.19	.2	.31	.24	.84	.24
82	.18	.2	.50	.20	.76	.17
83	.19	.2	.46	.24	.47	.39
84	.16	.2	.70	.25	2.4	.64
85	.094	.2	.18	.13	1.1	.34
86	.090	.2	.16	.15	.75	.26
87	.094	.2	.21	.18	.49	.18
88	.088	.2	.27	.17	.47	.13
89	.13	.2	.28	.22	.55	.14
90	.13	.2	.45	.23	.99	.22
91	.12	.2	.45	.20	.95	.21
92	.11	.2	.50	.21	1.2	.28
93	.11	.2	.52	.25	1.3	.25
94	.10	.2	.48	.25	1.2	.30
95	.074	.2	.45	.19	1.0	.27

0 3 6 0

0 2 3 2 1

## RESULTS OF TESTS:

### Horizontal (perpendicular to the valve stem) Axis (H1) (continued) \*

#### 4.3.2 Variable Frequency Test:

Frequency (Hz)	Inputs (G's)			Outputs (G's)			Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
4.5	.23	.05	.16	.23	.03	.06	12	3
6	.34	.07	.23	.32	.06	.06	12	3
8	.3	.10	.46	.22	.07	.14	12	3
11	.5	.14	.8	.44	.12	.22	12	3
15	.45	.2	.8	.46	.13	.4	12	3
21	.5	.30	.8	.50	1.4	.4	12.1	2.8
29	.5	.28	.8	.48	1.6	.45	12.1	2.8
39	.5	.35	1.0	.53	1.7	.55	12.1	2.8
53	.5	.16	.86	.56	.9	.35	12.1	2.7
71	.5	.40	1.5	.65	2.9	.92	12.0	2.8
95	.5	.27	1.2	.55	3.0	.76	12.0	2.8

There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

#### 4.3.3 Endurance Vibration Test:

The endurance vibration test was performed at the following frequency for a time period of three (3) minutes.

Frequency (Hz)	Inputs (G's)			Outputs (G's)			Operating Time	
	A	B	C	D	E	F	Open Seconds	Close
33	.5	.40	.76	.53	1.4	.46	12.0	2.8


There was no evidence of external physical damage, pneumatic or electrical malfunctions as a result of this test.

FACTUAL DATA

( UNCLASSIFIED )



FACTUAL DATA



5.0 VISUAL POST TEST EXAMINATION:

Visual post test examination revealed no evidence of external physical damage as a result of the stress of this test.


6.0 RECOMMENDATIONS:

None, data merely submitted.

7.0 CONCLUSIONS:

Final evaluation of the submitted specimen for conformance to the requirements of the detailed specifications will be accomplished by the Henry Pratt Company upon review of results reported herein and further examination as required.

0 2 3 2 1 0 3 6 2




HENRY PRATT COMPANY

AURORA, ILLINOIS

36-INCH VALVE

WITH ROBOTARM OPERATOR



Seismic Test Setup

0 2 3 2 1 0 3 6 4

DIMENSIONAL DATA QTVAValve Size 36"Operator Mounting ANGLE BONNET Operator T412-SR4

Minimum Cylinder Force Required to Equal Seismic Moments


Along x axis: From Y:  $F_1 = 835 \#$  Along y axis: From X:  $F_2 = 1252 \#$

From Z:  $F_1 = 774 \#$  From Z:  $F_2 = 1161 \#$

Actual Test Cylinder Force = 1003<sup>#</sup> in. x and 1504 in. y

5	$A_1$	<u>.462</u>	$J_1$	<u>1.25</u>
6	$A_2$	<u>.419</u>	$J_2$	<u>3.25</u>
3	$A_3$	<u>.462</u>	$J_3$	<u>NA</u>
0	$A_4$	<u>.419</u>	$J_4$	<u>NA</u>
3	$A_5$	<u>15</u>	$K_1$	<u>4.8</u>
2	$B_1$	<u>6.25</u>	$M_x$	<u>6436</u>
1	$B_2$	<u>3</u>	$M_y$	<u>10879</u>
0	$F_x$	<u>1161</u>	$M_z$	<u>5584</u>
2	$F_y$	<u>1161</u>	$\overline{M}_x$	<u>17471</u>
3	$g_x$	<u>3</u>	$\overline{M}_y$	<u>21913</u>
0	$g_y$	<u>3</u>	$T_2$	<u>20,000</u>
2	$H_1$	<u>5</u>	$W_1$	<u>387</u>
3	$H_2$	<u>7</u>	$W_2$	<u>81</u>
0	$H_4$	<u>8.5</u>	$X_0$	<u>3.84</u>
2	$I_1$	<u>497.2</u>	$Y_0$	<u>.97</u>
3	$I_2$	<u>70.3</u>	$Z_0$	<u>4.25</u>

0 2 3 2 1 0 3 6 6



FUNCTIONAL QUALIFICATION TEST FACILITY

HENRY PRATT COMPANY

AURORA, ILLINOIS

Section 6B

PART II

SECTION 6 B

FUNCTIONAL QUALIFICATION REPORT  
FOR  
GENERIC FAMILY VALVE ASSEMBLY (GFVA)

Job No. D-0038-4

As qualified by QTVA form D-0038-3

Page No.

- |    |   |   |
|----|---|---|
| 1. | Description and Characteristics of GFVA   | 1 |
| 2. | Base Line Data of GFVA to be used for Generic Qualification                                     | 2 |
|    | Results of Qualification Rules 1.3.8 and 1.3.9  | 3 |
|    | Dimensional Data Summary  | 4 |
| 3. | Copy of Functional Qualification Report of Actuator to show Compliance to IEEE 344 and IEEE 382 | 5 |

THIS GENERIC FAMILY VALVE ASSEMBLY SATISFIES ALL GENERIC QUALIFICATION RULES (PART I, PARAGRAPH 1.3) AND IT IS CONSIDERED A QUALIFIED GENERIC FAMILY VALVE ASSEMBLY.



1. DESCRIPTION AND CHARACTERISTICS

Valve Size and Type

44" 1100

Standard Pressure Class

150

Cold Working Pressure

275 psi

Rated Differential Pressure

200 psi

Maximum Service Temperature

200 °F

Actuator Type

Electric  
Motor

✓ Air

Actuator Size

T420-SR1

Normal Motive Power

- Vac

100 psi

Minimum Motive Power

- Vac

80 psi

Maximum Motive Power

- Vac

110 psi

Job No. D0038-4

2. BASE LINE DATA OF GFVA TO BE USED FOR GENERIC QUALIFICATION

Reference  
Paragraph

1.3.1 Valve Size

4 1/2"

1.3.2 Seat Taper Angle

11°

1.3.3 Disc/Seat Interference

.030"

1.3.4 Seating Surface Materials

ASME SA-240 TYPE 304

1.3.5 Materials of Construction

Body

ASME SA-516 GR.55

Disc

ASME SA-516 GR.70

Shaft

ASME SA-564 TYPE G30 COND. H115

Bearing

ASTM B-438 GR.1 TYPE 2

Seat

E.P.T

Retainer Segments

-

Packing

E.P.T

Thrust Collar

SAE 660 BRONZE

Bottom Cover

ASME SA-516 GR.55

Bonnet

ASME SA-36

Bolts: Valve to Bonnet

SA-193 GR.B7

Bonnet to Actuator

SA-193 GR.B7

1.3.6 Actuator Rated Torque

48500

Calculated Operator Torque

29040

Ratio =

1.67

Operating Time

Open to Close

4

Sec.

Close to Open

60

Sec.

RESULTS OF QUALIFICATION RULES 1.3.8 AND 1.3.9 FOR GFVARule 1.3.8

a.  $S_1 = \underline{36,000}$  Yield strength of bonnet material

$S_2 = \underline{2819}$  Calculated bonnet stress

$S_1/S_2 = \underline{12.8} > 1$

b.  $S_3 = \underline{95,000}$  Yield strength (proof load) of bonnet to valve bolting

$S_4 = \underline{19671}$  Calculated stress of bonnet to valve bolting

$S_3/S_4 = \underline{4.8} > 1$

c.  $S_5 = \underline{95,000}$  Yield strength (proof load) of actuator to bonnet bolting

$S_6 = \underline{13565}$  Calculated stress of actuator to bonnet bolting

$S_5/S_6 = \underline{7.0} > 1$

Rule 1.3.9 Bonnet Body Deflections ( $\Delta L$ )

$\Delta L \text{ of GFVA} = \underline{.00039}$  Deflection family valve

$\Delta L \text{ of GFVA} < .002"$

Job No. D0038-4

DIMENSIONAL DATA GFVA

Valve Size 44"

Actuator Mounting ANGLE BONNET Actuator T420-SR1

0	A <sub>1</sub>	.462	J <sub>1</sub>	1.25
2	A <sub>2</sub>	.419	J <sub>2</sub>	3.25
3	A <sub>3</sub>	.462	J <sub>3</sub>	NA
7	A <sub>4</sub>	.419	J <sub>4</sub>	NA
2	A <sub>5</sub>	15	K <sub>1</sub>	4.8
1	B <sub>1</sub>	6.25	M <sub>x</sub>	25409
	B <sub>2</sub>	3	M <sub>y</sub>	21101
	F <sub>x</sub>	2244	M <sub>z</sub>	20914
	F <sub>y</sub>	2244	$\overline{M}_x$	45650
	g <sub>x</sub>	3	$\overline{M}_y$	41341
	g <sub>y</sub>	3	T <sub>2</sub>	30,000
	H <sub>1</sub>	5	W <sub>1</sub>	748
	H <sub>2</sub>	7	W <sub>2</sub>	81
	H <sub>4</sub>	8.5	X <sub>0</sub>	3.94
	I <sub>1</sub>	497.2	Y <sub>0</sub>	5.38
	I <sub>2</sub>	70.3	Z <sub>0</sub>	4.15

STATEMENT OF QUALIFICATION

QUALIFICATION TESTING

GH-BETTIS Actuator Model NT-420B-SR1 is hereby certified to be of the same construction as Bettis Actuator Model NT-420B-SR1 which was qualified to the requirements of ANSI 278.2.1, Draft 3, Rev.0, Feb. 1977 (IEEE 382) with the exception of LOCA by testing at Southwest Research Institute, San Antonio, Texas. Applicable test margins as described in paragraph 6.3.1.5 of IEEE 323-1974 were utilized with the exception of (8). Refer to SWRI Test Report No. 02-4854-RPT-1.

The LOCA testing required to complete the qualification program is scheduled to begin at Wyle Laboratories, Huntsville, Alabama on September 11. Upon successful completion of that testing a revised statement of certification will be issued referencing the applicable test report number.

Supplementary seismic testing was performed on Bettis Actuator Model MT-520B-SR1 to the requirements of the above referenced ANSI document. Results of that testing are contained in the same report.

SEISMIC ANALYSIS

In addition to the seismic test results obtained in the above referenced tests, Bettis Seismic Analysis Report No. R-1062-29 Rev. A, is offered as further supportive evidence to the rigidity of this actuator.

*Joel D. Page*

JOEL D. PAGE  
Senior Engineer  
Nuclear Products

JDP/ksy  
8-31-78

ATTACHMENT NO. 6

Safety Relief Valve  
M-141.1



# SEISMIC CALCULATIONS

SAFETY AND RELIEF VALVES

FOR

MISSISSIPPI POWER & LIGHT

GRAND GULF POWER STATION

PORT GIBSON, MISSISSIPPI

UNIT NO. 1 & 2

BECHTEL P.O. NO. 9645-M-141.1

LONERGAN NO. 500320-1

500320-2

APPROVED BY  
J. E. LONERGAN COMPANY

A. J. SCHMIDT, CHIEF ENGINEER

REV.	DATE	APPROVED
1	5/19/75	<i>[Signature]</i>
2	7/11/75	<i>[Signature]</i>
3	1/12/76	<i>[Signature]</i>
4	9/23/76	<i>[Signature]</i>
5	12/19/80	<i>[Signature]</i>

BECHTEL TOWER CORP.  
**RECEIVED**  
APR 29 1981  
JOB NO. 9645

VENDOR'S DOCUMENT REVIEW	
<input checked="" type="checkbox"/>	Approved - All items checked
<input type="checkbox"/>	Approved - All items checked - All items approved
<input type="checkbox"/>	Approved - All items checked - All items approved and submitted for review
<input type="checkbox"/>	Not Approved - Correct and resubmit
<input type="checkbox"/>	Not Approved - Correct and resubmit
<input type="checkbox"/>	Not Approved - Correct and resubmit
Approved of this document does not constitute an approval of the contract or purchase order.	
<i>B. White</i> 5/15/81	
BECHTEL	
JOB NO. 9645	BECHTEL POWER CORPORATION 1540 SHADY GROVE ROAD GAITHERSBURG, MD.

8	4/1/81	BTK	ALA	SEE SDAN- QS-7.0-1-8	<i>[Signature]</i>	<i>[Signature]</i>
REV	DATE	RECH	CHK	DESCRIPTION	GRP	SUP
BECHTEL REVISION						
DOC. 9645-M-141.1-QS-7.0-1-8						

9645-M-141.1-QS-7.0-1-8

J. E. LONERGAN COMPANY  
POST OFFICE BOX 6167  
PHILADELPHIA, PA. 19115


**SEISMIC CALCULATIONS**

PAGE 11

## REVISION RECORD

REV. NO.	PAGE NO.	DESCRIPTION OF CHANGE	APPROVED BY
5	ii	Added New	1. Engineering Department Prepared by: <u>J. T. 12/19/80</u> Checked by: <u>AD 12/19/80</u> Approved by: <u>[Signature]</u> 12/19/80
	ic	Added New Item NO., Tag NO., and Page NO.	
4		Revised Seismic Acceleration 6.0g Horizontal and 6.0g Vertical.	
21		Added Item NO. 37.	
29-31		Added Item NO. 38, 39, Seismic Calculations.	
35		Revised "Y" Dimension. "Y" = 14.9 Was "Y" = 29.8".	

U S 2 0 1 0 / 3 1




MANUFACTURERS OF SAFETY-RELIEF VALVES

## SEISMIC CALCULATIONS

Page iii

### REVISION RECORD

REV. NO.	PAGE NO.	DESCRIPTION OF CHANGE	APPROVED BY
6	iii	Added New	1. Engineering Department
	1b.	Revised Item NO. 31 Tag NO. HBC-PSV-F300A HBC-PSV-F300B	Prepared by: <i>Jen Tain</i> 3/5/78
		Item NO. 33, 34 Tag No. HCC-PSV-F125J HCC-PSV-SPARE	Checked by: <i>Q. R. [unclear]</i> 3/5/81
			Approved by: <i>[Signature]</i>
	11.	Revised 3. Combined Stresses Acting at Base. C. Bending Stress Due to 1a, 2d, 2e. "S <sub>b</sub> = 583.44 psi" was "S <sub>b</sub> = 501.25 psi"  d. Combined Stress Due to 3a, 3b, 3c, 1c. "S = 1329.86 psi" was "S = 1248 psi"	



MANUFACTURERS OF SAFETY-RELIEF VALVES

## SEISMIC CALCULATIONS

PAGE IV

## REVISION RECORD

REV. NO.	PAGE NO.	DESCRIPTION OF CHANGE	APPROVED BY:
7	IV.	ADDED NEW	Engineering Department
	5.	Added Symbol: "W <sub>c</sub> = Valve Capacity - S.C.F.M."	1. PREPARED BY: <i>Joe Long 4/27/81</i>
	6.	Added Formula: "(Gases) F <sub>r</sub> = 0.0405 W <sub>c</sub> "	CHECKED BY: <i>D. R. Smith 4/27/81</i>
	8.	Revised Item No. 4 Tag. No. "PSV-F031A" was "PSV-F031"	APPROVED BY: <i>J. S. [Signature]</i>
		Revised Item No. 6 Tag. No. PSV-F041 Set Pressure. "150 PSIG" was "185 PSIG"	
		Revised Item No. 7 Tag No. "PSV-F084 A,B" was "PSV-F094 A,B."	
		Revised Item No. 25 Tag No. PSV-F017- A,B,C. Set Pressure "166 PSIG" was "200 PSIG".	
		Revised Item No. 31, Tag No. "PSV-F300 A,B." was "PSV-F197A,B." Set Pressure "100 PSIG" was "155 PSIG".	
	13.	Revised Item No. 18, Tag No. PSV-F029- A,B. Valve Capacity "Q = 66.7 GPM" was "Q = 67 GPM"	
	19.	Revise Item No. 33 Tag No. "PSV-F125J" was "PSV-F122" Set Pressure "190 PSIG" was "175 PSIG"	
	21.	Revised Item No. 23, Tag No. PSV-F035 Set Pressure and Valve Capacity. "1560 PSIG" was "1575 PSIG" and "Q" = 38.5 GPM" was "Q = 38.8 GPM"	
	24	Revised Item No. 23, Tag No. PSV-F014 Set Pressure "100 PSIG" was "95 PSIG"	
	27	Revised Item No. 29, Tag No. PSV-F018. Set Pressure and Valve Capacity, "510 PSIG" was "600 PSIG" and "Q = 163 GPM" was "Q = 176 GPM"	

# INDEX

SEISMIC REQUIREMENTS  
BASIS OF CALCULATIONS  
ALLOWABLE STRESSES  
CONCLUSIONS  
SYMBOLS  
FORMULAS  
SAMPLE DIAGRAMS  
CALCULATIONS

## PAGE

2  
2  
3  
3  
4, 5  
6  
7, 7a, 7b, 7c, 7d

### ITEM NO.

### TAG NO.

1

HBC-PSV-F100 A  
HBC-PSV-F100 B

8, 9, 10, 11

3

HBC-PSV-F024 A  
HBC-PSV-F024 B

8, 9, 10, 11

4

HBC-PSV-F031 A

8, 9, 10, 11

5

HBC-PSV-F036

8, 9, 10, 11

6

HBC-PSV-F041

8, 9, 10, 11

7

HBC-PSV-F084 A  
HBC-PSV-F084 B

8, 9, 10, 11

8

HBC-PSV-F097 A  
HBC-PSV-F097 B

8, 9, 10, 11

9

HBC-PSV-F104

8, 9, 10, 11

10

HBC-PSV-F127 A  
HBC-PSV-F127 B

8, 9, 10, 11

11

HBC-PSV-F138 A  
HBC-PSV-F138 B

8, 9, 10, 11

12

HBC-PSV-F157 A  
HBC-PSV-F157 B

8, 9, 10, 11

13

HBC-PSV-F151 A  
HBC-PSV-F151 B

8, 9, 10, 11

14

HBC-PSV-F049

8, 9, 10, 11



ITEM NO.TAG NO.PAGE

15	HBC-PSV-F055	8, 9, 10, 11
16	HBC-PSV-F061	8, 9, 10, 11
17	HBC-PSV-F046	8, 9, 10, 11
18	DCB-PSV-F029 A DCB-PSV-F029 B	12, 13, 14
19	GBB-PSV-F055 A GBB-PSV-F055 B	15, 16, 17, 18
20	HBB-PSV-F017	23, 24, 25
21	HBB-PSV-F018	29, 30, 31
22	HBB-PSV-F014	23, 24, 25
23	DBB-PSV-F035	9, 21, 22
24	GBB-PSV-F005	8, 9, 10, 11
25	GBB-PSV-F017 A GBB-PSV-F017 B GBB-PSV-F017 C	8, 9, 10, 11
26	GBB-PSV-F025 A GBB-PSV-F025 B GBB-PSV-F025 C	8, 9, 10, 11
27	HBB-PSV-F036	32, 33, 34
28	HBB-PSV-F031	23, 24, 25
29	GBB-PSV-F018	26, 27, 28
30	HBC-PSV-F194 A HBC-PSV-F194 B	8, 9, 10, 11
31	HBC-PSV-F300 A HBC-PSV-F300 B	8, 9, 10, 11
32	HBC-PSV-F031 B	8, 9, 10, 11
33	HCC-PSV-F125 J	9, 19, 20
34	HBC-PSV-F293 A, B	9, 19, 20
35	HCC-PSV-F124 A HCC-PSV-F124 B HCC-PSV-F124 C HCC-PSV-F124 D HCC-PSV-F124 E HCC-PSV-F124 F HCC-PSV-F124 G HCC-PSV-F124 H	9, 19, 20
36	HCC-PSV-F125 A HCC-PSV-F125 B HCC-PSV-F125 C HCC-PSV-F125 D HCC-PSV-F125 E HCC-PSV-F125 F HCC-PSV-F125 G HCC-PSV-F125 H	9, 19, 20



# J. E. LONERGAN COMPANY

<u>ITEM NO.</u>	<u>TAG NO.</u>	<u>PAGE</u>
37	DBB-PSV-F090	9, 21, 22
38	HBC-PSV-F026A	29, 30, 31
39	HBC-PSV-F026B	29, 30, 31

U S 2 0 1 0 / 9 2

SEISMIC REQUIREMENTS

Bechtel Spec. No. 9645-M-141.1 para. 5.2.4 requires that valves be capable of withstanding a seismic load of 6.0 g horizontal and 6.0 g vertical. Forces will be considered to act simultaneously.

The stresses due to horizontal and vertical seismic forces shall be considered to act simultaneously in the most disadvantageous manner and shall be added directly. The stresses in the valve components due to seismic loads shall be combined with the stresses due to other live, dead, and operating loads. The combined stress levels must not exceed those allowable in ASME Code, Section III, 1971 Edition.

BASIS OF CALCULATIONS

Critical stress areas will be areas where bending moments due to seismic acceleration and reaction forces are the greatest. These areas will be at the valve inlet and, in the case of bolted bonnet valves, the bonnet bolts. The section of highest stress at the valve inlet is taken in the inlet nipple at the point where it enters the socket on weld end valves, and at the inlet neck at the back of the flange for flanged end valves.

For determination of stress at the section of highest stress at the valve inlet, the center of gravity is taken; vertically, one-half the distance from the face of the inlet to the top of the valve and horizontally, one-third the distance from the center line to the face of the outlet.

In determining stress in bonnet bolting due to seismic acceleration, the weight of the bonnet section of the valve is taken as one-half the weight of the valve. The center of gravity of the bonnet section is taken on the vertical center line at one half the distance from the face of the bonnet flange to the top of the valve. These assumptions will yield conservative results.

Shear stress in the bonnet bolting is not considered since the bonnet is held in firm alignment with the body by the guide which is recessed into both the bonnet and the body.

The moment due to the reaction force of the discharge jet at the valve outlet is included in the stress calculations. The reaction force is taken at the highest pressure setting for each type of valve. Valves set at lower pressures will have lower reaction forces.

Stress due to inlet pressure based on the highest pressure setting plus 10% overpressure is included where inlet pressure acts on the inlet neck. In full nozzle valves, the inlet pressure is retained in the nozzle, not the body neck; therefore, stress due to pressure is not included in the calculations. However, in the case of full nozzle valves, the spring force is acting in tension on both the bonnet bolting and the section of highest stress at the valve inlet. The maximum spring force at the rated lift of the valve is used in the stress calculations.

# J. E. LONERGAN COMPANY

## ALLOWABLE STRESSES

Allowable stresses based upon ASME CODE, Section III, are listed below:

<u>MATERIAL</u>	<u>SPEC.</u>	<u>ALLOWABLE STRESS AT TEMP.</u>	
Stainless Steel	ASME A-351 GR CF 8	(.8 x 13,900) 11,121 psi	@ 400° F.
Alloy Bolting	ASME SA-320 GR B 8	12,600 psi	@ 400° F.
Stainless Steel Bar	ASME SA-479 TP 304	16,000 psi	@ 400° F.
Seamless Pipe	ASME SA-106 GRB	16,500 psi	@ 400° F.

## CONCLUSION

The summation of stresses due to maximum acceleration forces and maximum operating forces combined with maximum pressures are well within those permitted by ASME CODE, Section III, 1971 Edition, with all addenda including Summer 1973.

U 5 2 U I U / 4 4

# J. E. LONERGAN COMPANY

## SYMBOLS:

$A$	-	Area of inlet section (at O), sq. in.
$A_b$	-	Effective area of bolt at root of thread, sq. in.
$A_i$	-	Area of inlet, sq. in.
$A_n$	-	Area of Nozzle, sq. in.
$A_o$	-	Area of outlet, sq. in.
$A_s$	-	Area of valve seat, sq. in.
$D$	-	Outside diameter of section, inches.
$d$	-	Inside diameter of section, inches.
$F_o$	-	Maximum force in bonnet bolting due to horizontal acceleration, LBS.
$F_p$	-	Force due to inlet pressure, lbs.
$F_r$	-	Reaction force, lbs.
$F_s$	-	Horizontal shear due to horizontal acceleration, lbs.
$F_{sp}$	-	Spring force, lbs.
$F_v$	-	Vertical force due to vertical acceleration, lbs.
$a_h$	-	Horizontal acceleration = 6.0 g
$a_v$	-	Vertical acceleration = 6.0 g
$I/o$	-	Section Modulus, Inches <sup>3</sup>
$J/o$	-	Polar Section Modulus, inches <sup>3</sup>
$L$	-	Valve lift, inches.
$M_{bh}$	-	Moment in bonnet bolting due to horizontal acceleration, in. lbs.
$M_h$	-	Bending moment due to horizontal acceleration, in. lbs.
$M_v$	-	Bending moment due to vertical acceleration, in. lbs.
$n$	-	Number of bolts.
$O$	-	Section of highest stress (at inlet).
$P$	-	Pressure, PSIG.

# J. E. LONERGAN COMPANY

## SYMBOLS: (Continued)

- Q = Valve capacity, GPM
- R = Spring Deflection rate, lbs./in.
- r = Distance from centerline to bonnet bolts, inches.
- S = Numerically combined stress ( $S_t + S_s + S_b + S_p$ ), PSI
- $S_b$  = Stress due to bending, PSI
- $S_{bc}$  = Combined stress in bonnet bolt due to  $S_{bm} + S_{bt}$ , PSI
- $S_{bsa}$  = Stress in bonnet bolt due to horizontal acceleration, PSI
- $S_{bt}$  = Bonnet bolt tensile stress, PSI
- S = Stress due to internal pressure, PSI
- $S_s$  = Stress in shear, PSI
- $S_t$  = Stress in tension, PSI
- T = Torsion due to horizontal acceleration, in. lbs.
- t = Wall thickness, inches
- u = Distance from face of bonnet flange to center of gravity of bonnet section, inches.
- $v_o$  = Specific Volume (from steam tables)
- $V_o$  = Velocity - Ft/sec.
- W = Total weight of valve, lbs.
- w = Steam capacity - #/sec.
- $W_b$  = Weight of bonnet section of valve. lbs.
- $W_c$  = Valve capacity - s.c.f.m.
- $W_p$  = Valve capacity - lbs/hr. steam.
- x = Horizontal distance from centerline of valve to center of gravity, inches.
- y = Vertical distance from section of highest stress at inlet to center of gravity, inches.
- z = Vertical distance from section of highest stress at inlet to centerline of outlet, inches.

U 5 2 0 1 U / 4 0



# J. E. LONERGAN COMPANY

## REACTION FORCES

$$1 \text{ (Liquid)} \quad F_r = 0.00139 \frac{Q^2}{A_o}$$

$$2 \text{ (Air)} \quad F_r = .0405 W_c$$

$$3 \text{ (Steam)} \quad F_r = \frac{W V_o}{g} + (P_o - 15) A_o$$

$$3a \quad P_o = .58 \left( \frac{A_n}{A_o} \right) (1.10 P + 15)$$

$$3b \quad V_o = \frac{v_o W}{A_o}$$

## FORCE FORMULAS

$$F_p = A_i \times P \times 1.10$$

$$F_o = \frac{M_{bh} r_2}{2(r_1^2 + r_2^2)}$$

$$F_s = g_h \times W$$

$$F_{sp} = P A_s + L R$$

$$F_v = L_v \times W - W$$

## MOMENT FORMULAS

$$M_{bh} = g_h \times W_b \times u$$

$$M_h = y (g_h \times W)$$

$$M_v = x (g_v \times W + W)$$

$$T = g_h \times W \times (x)$$

$$I/c = \frac{\pi}{32} \frac{(D^4 - d^4)}{D}$$

$$J/c = \frac{\pi}{16} \frac{(D^4 - d^4)}{D}$$

## STRESS FORMULAS

$$15 \quad S_p = \frac{1.1 P d}{2 t}$$

$$16 \quad S_t = \frac{F_p + F_v}{A}$$

$$17 \quad S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c}$$

$$18 \quad S_b = \frac{(F_r \times z) + M_v + M_h}{I/c}$$

$$19 \quad S = S_t + S_s + S_b + S_p$$

## STRESS FORMULAS (BONNET)


$$20 \quad S_{bt} = \frac{F_{sp} + F_v}{n A_b}$$

$$21 \quad S_{bm} = \frac{F_o}{A_b} \text{ or } \frac{M_{bli}}{r \times 2 A_t}$$




$$22 \quad S_{bc} = S_{bt} + S_{bm}$$




SKETCHES OF TYPICAL VALVE ARRANGEMENTS  
 SHOWING LOCATION OF CENTER OF GRAVITY  
 WITH RESPECT TO SECTION OF  
 HIGHEST STRESS.






SKETCHES OF TYPICAL VALVE ARRANGEMENTS  
SHOWING LOCATION OF CENTER OF GRAVITY  
WITH RESPECT TO SECTION OF  
HIGHEST STRESS.







SKETCHES OF TYPICAL VALVE ARRANGEMENTS  
SHOWING LOCATION OF CENTER OF GRAVITY  
WITH RESPECT TO SECTION OF  
HIGHEST STRESS.






SKETCHES OF TYPICAL VALVE ARRANGEMENTS  
SHOWING LOCATION OF CENTER OF GRAVITY  
WITH RESPECT TO SECTION OF  
HIGHEST STRESS.



7c

U 5 2 J I U 7 5 I

SKETCHES OF TYPICAL VALVE ARRANGEMENTS  
SHOWING LOCATION OF CENTER OF GRAVITY  
WITH RESPECT TO SECTION OF  
HIGHEST STRESS.



J. E. LONERGAN COMPANY

1/2" x 1"  
3/4" x 1"  
1" x 1"

LCT-11

MALE x FEMALE

DWQ. NO. A-2587

ITEM NO.

TAG NO.

SET PRESSURE

1	PSV-F 100 A, B	185 PSIG
3	PSV-F 024 A, B	170 PSIG
4	PSV-F 031 A	150 PSIG
5	PSV-F 036	180 PSIG
6	PSV-F 041	150 PSIG
7	PSV-F 084 A, B	185 PSIG
8	PSV-F 097 A, B	175 PSIG
9	PSV-F 104	185 PSIG
10	PSV-F 127 A, B	175 PSIG
11	PSV-F 138 A, B	175 PSIG
12	PSV-F 157 A, B	175 PSIG
13	PSV-F 151 A, B	175 PSIG
14	PSV-F 049	185 PSIG
15	PSV-F 055	150 PSIG
16	PSV-F 061	150 PSIG
17	PSV-F 046	180 PSIG
24	PSV-F005	200 PSIG
25	PSV-F017 A, B, C	166 PSIG
26	PSV-F025 A, B, C	500 PSIG
30	PSV-F194 A, B	175 PSIG
31	PSV-F300 A, B	100 PSIG
32	PSV-F031 B	150 PSIG

\* This item used for calculations.



# J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT (BECHTEL)

P. O. NO. 9645-M-141.1


LONERGAN No. 500320-1 & 2

1" x 1" - LCT-11

MALE x FEMALE

Natural Frequency Calculations

ITEM PSV-F025 A, B, C



$$W = 4.25 \text{ LBS.}$$

$$y = 4.06 \text{ in.}$$

$$D = 1.050 \text{ in.}$$

$$d = .625 \text{ in.}$$

$$E = 30 \times 10^6$$

$$k = 386 \text{ in/sec}^2$$

$$ncps = \frac{1.73}{2\pi} \sqrt{\frac{E E I}{W y^3}}$$

$$I = \frac{\pi (D^4 - d^4)}{64}$$

$$I = \frac{\pi}{64} (1.05^4 - .625^4) = .052$$

$$ncps = \frac{1.73}{2\pi} \sqrt{\frac{386 \times 30 \times 10^6 \times .052}{4.25 \times 4.06^3}}$$

$$= .275 \sqrt{2,117,109} = 400 \text{ c.p.s.}$$

# **J. E. LONERGAN COMPANY**

A	=	1.05 in. <sup>2</sup>	P	=	500 PSIG	x	=	.58 in.
A <sub>1</sub>	=	.307 in. <sup>2</sup>	Q	=	21.9 GPM	y	=	4.06 in.
A <sub>0</sub>	=	.864 in. <sup>2</sup>	W	=	4.25 LBS.	z	=	2.25 in.
D	=	1.315 in.	t	=	.34 in.	J/c	=	.42 in. <sup>3</sup>
d	=	.625 in.				I/c	=	.21 in. <sup>3</sup>

## 1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_0} = \frac{.00139 \times 21.9^2}{.864} = .77 \text{ LBS.}$$

- b. Vertical force acting on valve centerline due to inlet pressure.

$$F_p = A_1 \times P \times 1.10 = .307 \times 1.1 \times 500 = 169 \text{ LBS.}$$

- c. Stress in base due to internal pressure.

$$S_p = \frac{1.10 P d}{2 t} = \frac{1.1 \times 500 \times .625}{2 \times .34} = 505 \text{ PSI}$$

## 2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W = W = 6.0 \times 4.25 = 25.5 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_s = g_h \times W = 6.0 \times 4.25 = 25.5 \text{ LBS.}$$

- c. Torison about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 4.25 \times .58 = 14.79 \text{ IN. LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = .58 (6.0 \times 4.25 + 4.25) = 17.26 \text{ IN. LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 4.06 \times 6.0 \times 4.25 = 103.53 \text{ IN. LBS.}$$

731

J. E. LOMERGAN COMPANY

3. COMBINED STRESSES ACTING AT BASE

a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_P + F_Y}{A} = \frac{169 + 21.25}{1.05} = 181.19 \text{ PSI}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{.77 + 25.5}{1.05} + \frac{14.79}{\frac{\pi}{16} \left( \frac{1.315^4}{1.315} - \frac{.625^4}{1.315} \right)}$$

$$= \frac{26.27}{1.05} + \frac{14.79}{.42} = 60.23 \text{ PSI}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(.77 \times 2.25) + 17.26 + 103.53}{.21} = 583.44 \text{ PSI}$$

d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 181.19 + 60.23 + 583.44 + 505 = 1329.86 \text{ PSI}$$

# J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT (BECHTEL)


P.O. NO. 9645-M-141.1

LONERGAN NO. 500320 1 & 2

1-1/2" x 2" D-70 D / L3

Natural Frequency Calculations

ITEM PSV-F 029 A & B



$$W = 58 \text{ LBS.}$$

$$y = 8.625 \text{ in.}$$

$$D = 2.50 \text{ in.}$$

$$d = 1.755 \text{ in.}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$\text{ncps} = \frac{1.73}{2 \pi} \sqrt{\frac{g E I}{W y^3}}$$

$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$= \frac{\pi}{64} (2.5^4 - 1.755^4) = 1.45 \text{ in.}^4$$

$$\text{ncps} = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 1.45}{58 \times 8.625^3}}$$

$$= .275 \sqrt{451,186} = 185 \text{ cps}$$

# J. E. LONERGAN COMPANY

1-1/2" x 2" D-70 D / L3 900# L.G. x 150# R.P.

DWG. NO. A-2687

ITEM NO.

TAG NO.

SET PRESSURE

18

PSV-F 029 A, B.

1386 PSIG

A = 2.49 in. <sup>2</sup>	L = .132 in.	r <sub>1</sub> = 1.68 in.	x = 1.833 in.
A <sub>b</sub> = .126 in. <sup>2</sup>	n = 8	r <sub>2</sub> = 2.375 in.	y = 8.625 in.
A <sub>o</sub> = 3.14 in. <sup>2</sup>	P = 1386 PSIG	u = 5.94 in.	z = 2.125 in.
A <sub>s</sub> = .307 in. <sup>2</sup>	Q = 66.7 GPM	W = 58 LBS.	J/c = 2.32 in. <sup>3</sup>
D = 2.50 in.	R = 2085#/in.	W <sub>b</sub> = 29 LBS.	I/c = 1.16 in. <sup>3</sup>
d = 1.755 in.			

## 1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_o} = \frac{.00139 \times (66.7^2)}{3.14} = 1.97 \text{ LBS.}$$

- b. Vertical force acting on centerline due to spring compression.

$$F_{sp} = P \times A_s + L \times R = 1386 \times .307 + .132 \times 2085 = 5 + 275 = 280 \text{ LBS.}$$

## 2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W = W = 6.0 \times 58 = 58 = 290 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 58 = 348.0 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 58 \times 1.833 = 637.9 \text{ IN. LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = 1.833 (6.0 \times 58 + 58) = 744.2 \text{ IN. LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 8.625 \times 6.0 \times 58 = 3001.5 \text{ IN. LBS.}$$

# J. E. LONERGAN COMPANY

## 3. COMBINED STRESSES ACTING AT POINT "O"

- a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_{sp} + F_v}{A} = \frac{700 + 290}{2.49} = 397.6$$

- b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{1.97 + 348}{2.49} + \frac{637.9}{\frac{\pi}{16} (2.50^4 - 1.755^4)} \\ = \frac{349.97}{2.49} + \frac{637.9}{2.32} = 415.51 \text{ PSI}$$

- c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(1.97 \times 2.125) + 744.2 + 3001.5}{1.16} = 3232.66 \text{ PSI}$$

- d. Combined stress due to 3a, 3b, 3c.

$$S = S_t + S_s + S_b = 397.6 + 415.51 + 3232.66 = 4045.77 \text{ PSI}$$

## 4. COMBINED STRESSES ACTING AT BOLTING

- a. Tensile stress due to 1b, 2a.

$$S_{bt} = \frac{F_{sp} + F_v}{n \times A_b} = \frac{700 + 290}{8 \times .126} = 982 \text{ PSI}$$

- b. Bending stress due to horizontal acceleration (Bonnet only).

$$M_{bh} = g_h \times W_b \times u = 6.0 \times 29 \times 5.94 = 1034 \text{ IN. LBS.}$$

$$F_o = \frac{M_{bh} r_2}{2 (r_2^2 + r_1^2)} = \frac{1034 \times 2.375}{2 (2.375^2 + 1.6^2)} = 145.05$$

$$S_{bm} = \frac{F_o}{A_b} = \frac{145.05}{.126} = 1151 \text{ PSI}$$

(NOTE: Use number of bolts in plane of maximum stress)

- c. Combined stress due to 4a, 4b.

$$S_{bc} = S_{bt} + S_{bm} = 982 + 1151 = 2133 \text{ PSI}$$



J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT - (BECHTEL)

P.O. NO. 9645-M-141.1


LONERGAN NO. 500320-1 & 2

6" x Q x 8"

D-52 Q

Natural Frequency Calculations

ITEM PSV-F 055 A, B.



$$W = 630 \text{ LBS.}$$

$$y = 22.75 \text{ in.}$$

$$D = 7.562 \text{ in.}$$

$$d = 6.445 \text{ in.}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$\text{ncps} = \frac{1.73}{2 \pi} \sqrt{\frac{g E I}{W y^3}}$$

$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$\frac{\pi}{64} (7.562^4 - 6.445^4) = 75.84 \text{ in.}^4$$

$$\text{ncps} = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 75.84}{630 \times 22.75^3}}$$

$$= .275 \sqrt{116351} = 95 \text{ cps.}$$

## J. E. LONERGAN COMPANY

6" x 8"

D-52 Q

600# RF x 150# RF FLANGED

DWG. NO. A-2369

ITEM NO.TAQ NO.SET PRESSURE

19

PSV-F 055 A  
PSV-F 055 B

500 PSIG

$A = 12.28 \text{ in.}^2$	$L = .985 \text{ in.}$	$r_1 = 3.17 \text{ in.}$	$x = 3.17 \text{ in.}$
$A_b = .302 \text{ in.}^2$	$n = 12$	$r_2 = 5.49 \text{ in.}$	$y = 22.75 \text{ in.}$
$A_n = 12.18 \text{ in.}^2$	$P = 500 \text{ PSIG}$	$r_3 = 6.34 \text{ in.}$	$z = 6.75 \text{ in.}$
$A_o = 50 \text{ in.}^2$	$P_o = 80 \text{ PSIA}$	$u = 15.19 \text{ in.}$	$J/c = 40.11 \text{ in.}^3$
$A_s = 13.7 \text{ in.}^2$	$R = 5200 \text{ #/in.}$	$W = 630 \text{ LBS.}$	$I/c = 20.06 \text{ in.}^3$
$D = 7.562 \text{ in.}$		$W_b = 315 \text{ LBS.}$	
$d = 6.445 \text{ in.}$		$W_p = 311,997 \text{ #/hr.}$	

1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along the centerline of the outlet.

$$P_o = .58 \left( \frac{A_n}{A_o} \right) (1.10 P + 14.7) = .58 \left( \frac{12.18}{50} \right) (1.10 \times 500 + 14.7) = 80 \text{ PSIA}$$

$$v_o = 5.472 \text{ ft./#}^3 \text{ (from steam tables)}$$

$$w/\text{sec.} = \frac{311997}{3600} = 86.67 \text{ #/sec.}$$

$$y_o = \frac{v_o w}{A_o} = \frac{5.472 \times 86.67 \times 144}{50} = 1366 \text{ ft/sec.}$$

$$F_r = \frac{w v_o}{g} + (P_o - 14.7) A_o = \frac{86.67 \times 1366}{32.2} + (80 - 14.7) 50$$

$$= 3677 + 3265 = 6942 \text{ LBS.}$$

- b. Vertical force acting on centerline due to spring compression.

$$F_{sp} = P \times A_s + L \times R = 500 \times 13.7 + .985 \times 5200$$

$$= 6850 + 5122 = 11972 \text{ LBS.}$$

# J. E. LONERGAN COMPANY

## 2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W = W = 6.0 \times 630 = 630 = 3150 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_s = g_h \times W = 6.0 \times 630 = 3780 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 630 \times 3.17 = 11983 \text{ IN. LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = 3.17 (6.0 \times 630 + 630) = 13980$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 22.75 \times 6.0 \times 630 = 85995 \text{ IN. LBS.}$$

## 3. COMBINED STRESSES ACTING AT POINT "O".

- a. Tensile stress due to 1b., 2a.

$$S_t = \frac{F_{sp} + F_v}{A} = \frac{11972 + 3150}{.785 (7.562^2 - 6.445^2)} = \frac{15122}{12.26} = 1231 \text{ PSI}$$

- b. Shear stress due to 1a, 2a, 2b., 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{6942 + 3780}{12.26} + \frac{11983}{\frac{\pi}{16} (7.562^4 - 6.445^4)} = \frac{10722}{12.26} + \frac{11983}{40.11} = 1172 \text{ PSI}$$

- c. Bending stress due to 1a, 2d., 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(6942 \times 6.75) + 13960 + 85995}{20.06} = 7320 \text{ PSI}$$

- d. Combined stress due to 3a, 3b, 3c.

$$S = S_t + S_s + S_b = 1231 + 1172 + 7320 = 9723 \text{ PSI}$$

## J. E. LONERGAN COMPANY

4. COMBINED STRESSES ACTING ON BOLTING

a. Tensile stress due to lb, 2a.

$$S_{bt} = \frac{F_{sp} + F_v}{n \times A_b} = \frac{11972 + 3150}{12 \times .302} = 4173 \text{ PSI}$$

b. Bending stress due to horizontal acceleration (bonnet only).

$$M_{bh} = E_h \times W_b \times u = 6.5 \times 315 \times 15.19 = 31102 \text{ IN. LBS.}$$

$$F_o = \frac{M_{bh} \times r_3}{2(r_3^2 + r_2^2 + r_1^2)} = \frac{31102 \times 6.34}{2(6.34^2 + 5.49^2 + 3.17^2)}$$

$$= \frac{21532 \times 6.34}{161} = 1225 \text{ LBS.}$$

$$S_{bm} = \frac{F_o}{A_b} = \frac{1225}{.302} = 4056 \text{ PSI}$$

(NOTE: Use number of bolts in plane of maximum stress).

c. Combined stress due to lb, lb.

$$S_{bc} = S_{bt} + S_{bm} = 4173 + 4056 = 8229 \text{ PSI}$$


J. E. LONERGAN COMPANY

DWG. No. A-2587

1" x 1" LCT-11

MALE x FEMALE

ITEM NO.  
33  
34  
35  
36

TAG NO.  
PSV-F1251  
PSV-F293A, B   
PSV-F124 A-H  
PSV-F125 A-H

SET PRESSURE  
190 PSIG  
175 PSIG  
190 PSIG  
190 PSIG

A = 1.05 in<sup>2</sup>  
A<sub>1</sub> = .307 in<sup>2</sup>  
D = 1.315 in  
d = .625 in

P = 190 PSIG  
W = 4.25 LBS.  
W<sub>c</sub> = 221 SCFM  
t = .34 in

x = .58 in.  
y = 4.06 in  
z = 2.25 in.  
J/c = .42 in<sup>3</sup>  
I/c = .21 in<sup>3</sup>

\* NOTE: THIS ITEM USED FOR CALCULATION.

1. OPERATING FORCES

- a. Reaction force due to discharge jet acting horizontally along centerline of outlet.  
$$F_r = .0405 W_c = .0405 \times 221 = 8.95 \text{ LBS.}$$
- b. Vertical force acting on valve centerline due to inlet pressure.  
$$F_p = A_1 \times P \times 1.10 = .307 \times 190 \times 1.1 = 64.16 \text{ LBS.}$$
- c. Stress in base due to internal pressure.  
$$S_p = \frac{1.1 \times P \times d}{2 t} = \frac{1.1 \times 190 \times .625}{2 \times .34} = 192.1 \text{ PSI}$$

2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.  
$$F_v = g_v \times W - W = 6.0 \times 4.25 - 4.25 = 21.3 \text{ LBS.}$$
- b. Horizontal shear due to horizontal acceleration.  
$$F_h = g_h \times W = 6.0 \times 4.25 = 25.50 \text{ LBS.}$$
- c. Torsion about vertical centerline due to horizontal acceleration.  
$$T = g_h \times W \times (x) = 6.0 \times 4.25 \times .58 = 14.8 \text{ IN. LBS.}$$
- d. Bending moment due to vertical acceleration.  
$$M_v = x(g_v \times W + W) = .58(6.0 \times 4.25 + 4.25) = 17.3 \text{ IN. LBS.}$$
- e. Bending moment due to horizontal acceleration.  
$$M_h = y(g_h \times W) = 4.06 \times 6.0 \times 4.25 = 103.5 \text{ IN. LBS.}$$

3. COMBINED STRESSES ACTING AT BASE

a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_p + F_v}{A} = \frac{64.16 + 21.3}{1.05} = 81.39 \text{ PSI.}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{8.95 + 25.5}{1.05} + \frac{14.8}{\frac{\pi}{16} \left( \frac{1.315^4 - .625^4}{1.315} \right)}$$

$$= \frac{34.45}{1.05} + \frac{14.8}{.42} = 68 \text{ PSI}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(8.95 \times 2.25) + 17.3 + 103.5}{.21} = 671 \text{ PSI}$$

d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 81.39 + 68 + 671 + 192.1 = 1012.49 \text{ PSI.}$$



# J. E. LOWERY COMPANY

1" x 1"

LCT-11

1500/L.G. x 150/R.F. FLANGED

DWG. NO.

## ITEM NO.

## TAG NO.

## SET PRESSURE

* 23	PSV-F035	1560 PSIG
37	PSV-F090	1500 PSIG
* NOTE:--This Item used for calculation.		
A = 1.05 in <sup>2</sup>	P = 1560 PSIG	x = 1.00 in
A <sub>1</sub> = .307 in <sup>2</sup>	Q = 38.6 GPM	y = 8.00 in
A <sub>0</sub> = .78 in <sup>2</sup>	W = 10 LBS.	z = 2.56 in
D = 1.315 in	t = .34 in	J/c = .42 in <sup>3</sup>
d = .625 in		I/c = .21 in <sup>3</sup>

## 1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_0} = \frac{.00139 \times 38.6^2}{.78} = 2.65 \text{ LBS.}$$

- b. Vertical force acting on valve centerline due to inlet pressure.

$$F_p = A_1 \times P \times 1.10 = .307 \times 1560 \times 1.1 = 527 \text{ LBS.}$$

- c. Stress in base due to internal pressure.

$$S_p = \frac{1.10 P d}{2 t} = \frac{1.1 \times 1560 \times .625}{2 \times .34} = 1577 \text{ PSI}$$

## 2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 10 - 10 = 50 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 10 = 60 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 10 \times 1.0 = 60 \text{ IN.LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = 1.0 (6.0 \times 10 + 10) = 70 \text{ IN.LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 8.0 \times 6.0 \times 10 = 480 \text{ IN.LBS.}$$

COMBINED STRESSES ACTING AT BASE

- a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_p + F_v}{A} = \frac{527 + 60}{1.05} = 550 \text{ PSI}$$

- b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{2.65 + 60}{1.05} + \frac{60}{\frac{\pi}{16} \left( \frac{1.315^4}{1.315} - \frac{.625^4}{1.315} \right)}$$

$$\triangle = \frac{62.65}{1.05} + \frac{60}{.42} = 202.53 \text{ PSI}$$

- c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(2.65 \times 2.56) + 70 + 480}{.21} = 2651.35 \text{ PSI}$$

- d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 550 + 202.53 + 2651.35 + 1577 = 4980.86 \text{ PSI}$$

J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT (Bechtel)


P.O. No. 9645-M-141.1

LONERGAN NO. 500320

3/4" x 1" LCT-20 Female x Female

Natural Frequency Calculations

ITEM PSV-F031



W = 22 LBS

y = 7.56 in.

D = 2.656 in.

d = .92 in

E =  $30 \times 10^6$

g = 386 in/sec<sup>2</sup>

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{E \cdot \pi}{W \cdot y^3}}$$

$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$= \frac{\pi}{64} (2.656^4 - .92^4) = 2.41 \text{ in}^4$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 2.41}{22 \times 7.56^3}}$$

$$= .275 \sqrt{2,935,774} = 471 \text{ cps}$$

U  
S  
2  
U  
I  
0  
/

3/4" x 1"

LCT-20

FEMALE x FEMALE

DWG. No. A-2624

ITEM NO.TAG NO.SET PRESSURE

20

PSV-F017

75 PSIG

22

PSV-F014

100 PSIG

\* 28

PSV-F031

100 PSIG

\*This item used for calculations.

$$A = 4.87 \text{ in}^2$$

$$P = 100 \text{ PSIG}$$

$$x = .96 \text{ in}$$

$$A_1 = .66 \text{ in}^2$$

$$Q = 17.9 \text{ GPM}$$

$$y = 7.56 \text{ in}$$

$$A_o = .72 \text{ in}^2$$

$$W = 22 \text{ LBS}$$

$$z = 2.62 \text{ in.}$$

$$D = 2.656 \text{ in}$$

$$t = .87 \text{ in}$$

$$J/c = 3.62 \text{ in}^3$$

$$d = .92 \text{ in}$$

$$I/c = 1.81 \text{ in}^3$$

1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_o} = \frac{.00139 \times 17.9^2}{.72} = .62 \text{ LBS.}$$

- b. Vertical force acting on valve centerline due to inlet pressure.

$$F_p = A_1 \times P \times 1.10 = .66 \times 100 \times 1.1 = 7.26 \text{ LBS}$$

- c. Stress in base due to internal pressure.

$$S_p = \frac{1.10 P d}{2 t} = \frac{1.1 \times 100 \times .92}{2 \times .87} = 58 \text{ PSI}$$

2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 22 - 22 = 110 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 22 = 132 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 22 \times .96 = 127 \text{ IN. LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = .96 (6.0 \times 22 + 22) = 148 \text{ IN. LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 7.56 \times 6.0 \times 22 = 998 \text{ IN. LBS.}$$

3. COMBINED STRESSES ACTING AT BASE

a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_p + F_v}{A} = \frac{72.6 + 110}{4.87} = 38 \text{ PSI}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{.62 + 132}{4.87} + \frac{127}{\frac{\pi}{16} \left( \frac{2.656^4}{2.656} - .92^4 \right)}$$

$$= \frac{132.62}{4.87} + \frac{127}{3.62} = 62 \text{ PSI}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(.62 \times 2.62) + 148 + 998}{1.81} = 634 \text{ PSI}$$

d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 38 + 62 + 634 + 58 = 792 \text{ PSI}$$

# J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT (Bechtel)

P.O. No. 9645-M-141.1


LONERGAN NO. 500320

1 1/2" x 2" LCT-20

Female x Female

Natural Frequency Calculations

ITEM PSV-F018



$$W = \text{LBS.}$$

$$y = 8.06 \text{ IN.}$$

$$D = 3.275 \text{ in.}$$

$$d = 1.73 \text{ in}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{E E I}{W y^3}}$$

$$I = \frac{\pi}{64} (D^4 - d^4)$$

$$= \frac{\pi}{64} (3.275^4 - 1.73^4) = 5.21 \text{ in}^4$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 5.21}{33 \times 8.06^3}}$$

$$= .275 \sqrt{3491565} = 514 \text{ cps}$$



**J. E. LOWERY COMPANY**

1-1/2" x 2"

LCT-20

FEMALE x FEMALE

DWG. No. A2624

<u>ITEM NO.</u>	<u>TAG NO.</u>	<u>SET PRESSURE</u>
29	PSV-F018	510 PSIG
A = 6.86 in <sup>2</sup>	h = 510 PSIG	x = .96 in
A <sub>1</sub> = 2.35 in <sup>2</sup>	Q = 163 GPM	y = 8.06 in
A <sub>0</sub> = 2.95 in <sup>2</sup>	W = 33 LBS	z = 3.00 in
D = 3.275 in	t = .77 in	J/c = 6.36 in <sup>3</sup>
d = 1.73 in		I/c = 3.18 in <sup>3</sup>

1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_0} = \frac{.00139 \times 163^2}{2.95} = 12.52 \text{ LBS.}$$

- b. Vertical force acting on valve centerline due to inlet pressure.

$$F_p = A_1 \times P \times 1.10 = 2.35 \times 510 \times 1.1 = 1318.35 \text{ LBS}$$

- c. Stress in base due to internal pressure.

$$S_p = \frac{1.10 P d}{2 t} = \frac{1.1 \times 510 \times 1.73}{2 \times .77} = 630.21 \text{ PSI}$$

2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 33 - 33 = 165 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 33 = 198 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 33 \times .96 = 190 \text{ IN.LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = .96(6.0 \times 33 + 33) = 222 \text{ IN.LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 8.06 \times 6.0 \times 33 = 1596 \text{ IN.LBS.}$$

# J. E. LONGERMAN COMPANY

## 3. COMBINED STRESSES ACTING AT BASE

a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_p + F_y}{A} = \frac{1318.35 + 165}{6.86} = 216.23 \text{ PSI}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{12.52 + 198}{6.86} + \frac{190}{\frac{\pi}{16} \left( \frac{3.275^4 - 1.73^4}{3.275} \right)}$$

$$= \frac{210.52}{6.86} + \frac{190}{6.36} = 60.56 \text{ PSI}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(12.52 \times 3) + 222 + 1596}{3.18} = 583.51 \text{ PSI}$$

d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 216.23 + 60.56 + 583.51 + 630.21 = 1490.51 \text{ PSI.}$$

MISSISSIPPI POWER AND LIGHT (Bechtel)

P. O. No. 9645-M-141.1


LONERGAN NO. 500320-1 & 2

1 1/2" x 2" - LCT-20 150 # R.F. x 150 # R.F.

# Natural Frequency Calculations

Item No. 1-1.06A  
1-1.06B

Tag No. SQ-1 1/2 HBC-PSV-F026A  
SQ-1 1/2 HBC-PSV-F026B



$$W = 41 \text{ LBS.}$$

$$y = 9.16 \text{ INS.}$$

$$D = 1.90 \text{ INS.}$$

$$d = 1.50 \text{ INS.}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{E I}{W y^3}}$$


$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$I = \frac{\pi}{64} (1.90^4 - 1.50^4) = 0.39$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6}{41 \times 9.16^3}}$$

$$= .275 \sqrt{367484}$$

$$= 167 \text{ CPS.}$$



MANUFACTURERS OF SAFETY-RELIEF VALVES

## SEISMIC CALCULATIONS

1½" x 2" LCT-20

150 # R.F. x 150 # R.F.

DWG. No. A-2371

ITEM NO.	TAG NO.	SET PRESSURE
38	SQ-1½HBC-PSV-F026A	40 PSIG
39	SQ-1½HBC-PSV-F026B	40 PSIG
A	= 1.07 IN. <sup>2</sup>	P = 40 PSIG
A <sub>1</sub>	= 1.767 IN. <sup>2</sup>	Q = 43.2 GPM.
A <sub>0</sub>	= 2.95 IN. <sup>2</sup>	W = 41 LBS.
D	= 1.90 IN. <sup>2</sup>	t = 0.20 INS.
d	= 1.50 IN. <sup>2</sup>	
		x = 1.88 INS.
		y = 9.16 INS.
		z = 5.19 INS.
		J/c = .82 IN. <sup>3</sup>
		I/c = .41 IN. <sup>3</sup>

### 1. OPERATING FORCES

- a. Reaction force of discharge jet horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_o} = \frac{0.00139 (43.2)^2}{2.95} = 0.88 \text{ LBS.}$$

- b. Vertical force acting on valve centerline due to inlet pressure.

$$F_p = A_1 \times P \times 1.10 = (1.767) \times 40 \times 1.10 = 77.8 \text{ LBS.}$$

- c. Stress in base due to internal pressure.

$$S_p = \frac{1.10 P d}{2 t} = \frac{(1.10) (40) (1.50)}{2 (0.20)} = 165 \text{ psi.}$$

### 2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 41 - 41 = 205 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 246 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 41 \times (1.88) = 463 \text{ IN.-LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v W + W) = (1.88) \times (6.0 \times 41 + 41) = 540 \text{ IN.-LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 9.16 \times (6.0 \times 41) = 2253 \text{ IN.-LBS.}$$



MANUFACTURERS OF SAFETY-RELIEF VALVES

## SEISMIC CALCULATIONS

### COMBINED STRESSES ACTING AT BASE

a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_p + F_v}{A} = \frac{77.8 + 205}{1.07} = 264 \text{ psi.}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{0.88 + 246}{1.07} + \frac{463}{0.82} = 795 \text{ psi.}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(0.88 \times 5.19) + 540 + 2253}{0.41} = 6823 \text{ psi}$$

d. Combined stress due to 3a, 3b, 3c, 1c.

$$S = S_t + S_s + S_b + S_p = 264 + 795 + 6823 + 165 = 8047 \text{ psi.}$$

# J. E. LONERGAN COMPANY

MISSISSIPPI POWER & LIGHT (Bechtel)


P.O. No. 9645-M-141.1

LONERGAN NO. 500320

1 1/2" x 3" D-10H 150/RF x 150/RF FLANGED

Natural Frequency Calculations

ITEM PSV-F018



$$W = 50 \text{ LBS.}$$

$$y = 9.47 \text{ in.}$$

$$D = 2.62 \text{ in.}$$

$$d = 2.00 \text{ in.}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{g E I}{W y^3}}$$

$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$= \frac{\pi}{64} (2.62^4 - 2.0^4) = 1.53 \text{ in}^4$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 1.53}{50 \times 9.47^3}}$$

$$.275 \sqrt{417209} = 178 \text{ cps}$$



**J. E. LONERGAN COMPANY**

1-1/2" x 3"

D-10H

150#RF x 150#RF FLANGED

DWG. No. A-2370

ITEM NO.  
21

TAG NO.  
PSV-F018

SET PRESSURE  
75 PSIG

$A = 2.25 \text{ in}^2$	$L = .263 \text{ in}$	$r_1 = 1.68 \text{ in.}$	$x = 1.62 \text{ in}$
$A_b = .126 \text{ in}^2$	$n = 4$		$y = 9.47 \text{ in}$
$A_o = 7.0 \text{ in}^2$	$P = 75 \text{ PSIG}$	$u = 5.81 \text{ in}$	$z = 3.87 \text{ in}$
$A_s = .992 \text{ in}^2$	$Q = 111 \text{ GPM}$	$W = 50 \text{ LBS}$	$J/c = 2.33 \text{ in}^3$
$D = 2.62 \text{ in}$	$R = 196 \text{ #/inch}$	$W_b = 25 \text{ LBS.}$	$I/c = 1.16 \text{ in}^3$
$d = 2.00 \text{ in}$			

1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_o} = \frac{.00139 \times 111^2}{7.0} = 2.45 \text{ LBS.}$$

- b. Vertical force acting on centerline due to spring compression.

$$F_{sp} = P \times A_s + L \times R = 75 \times .992 + .263 \times 196$$

$$= 74.4 + 51.5 = 126 \text{ LBS.}$$

2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 50 - 50 = 250 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 50 = 300 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 50 \times 1.62 = 486 \text{ IN.LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = 1.62 (6.0 \times 50 + 50) = 567 \text{ IN.LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 9.47 \times 6.0 \times 50 = 2841 \text{ IN.LBS.}$$

U 5 2 U 1 U / 7 B

3. COMBINED STRESSES ACTING AT POINT "O"

- a. Tensile stress due to 1b, 2a.

$$S_t = \frac{F_{sp} + F_v}{A} = \frac{126 + 250}{2.25} = 167 \text{ PSI}$$

- b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{2.45 + 300}{2.25} + \frac{486}{\frac{\pi}{16} \left( \frac{2.62^4}{2.62} - \frac{2.0^4}{2.62} \right)}$$

$$= \frac{302.45}{2.25} + \frac{486}{2.33} = 343 \text{ PSI}$$

- c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(2.45 \times 3.87) + 567 + 2841}{1.16} = 2946 \text{ PSI}$$

- d. Combined stress due to 3a, 3b, 3c.

$$S = S_t + S_s + S_b = 167 + 343 + 2946 = 3456 \text{ PSI}$$

4. COMBINED STRESSES ACTING ON BOLTING

- a. Tensile stress due to 1b, 2a.

$$S_{bt} = \frac{F_{sp} + F_v}{n \times A_b} = \frac{126 + 250}{4 \times .126} = 746 \text{ PSI}$$

- b. Bending stress due to horizontal acceleration (bonnet only).

$$M_{bh} = g_h \times W_b \times u = 6.0 \times 25 \times 5.81 = 872 \text{ IN.LBS.}$$

$$S_{bm} = \frac{M_{bh}}{r \times 2 \times A_b} = \frac{872}{1.68 \times 2 \times .126} = 2059 \text{ PSI}$$

- c. Combined stress due to 4a, 4b.

$$S_{bc} = S_{bt} + S_{bm} = 746 + 2059 = 2805 \text{ PSI}$$

U / 7 7  
U 5 2 U I

# J. E. LONERGAN COMPANY

MISSISSIPPI POWER AND LIGHT (Bechtel)


P.O. No. 9645-M-141.1

LONERGAN No. 500320

4" x 6" D-10K 150#RF x 150#RF FLANGED

Natural Frequency Calculations

ITEM PSV-F036



$$W = 200 \text{ LBS.}$$

$$y = 14.9 \text{ in}$$

$$D = 5.75 \text{ in.}$$

$$d = 4.63 \text{ in}$$

$$E = 30 \times 10^6$$

$$g = 386 \text{ in/sec}^2$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{g E I}{W y^3}}$$

$$I = \pi \left( \frac{D^4 - d^4}{64} \right)$$

$$= \frac{\pi}{64} (5.75^4 - 4.63^4) = 31.1 \text{ in}^4$$

$$ncps = \frac{1.73}{2 \pi} \sqrt{\frac{386 \times 30 \times 10^6 \times 31.1}{200 \times 149^3}}$$

$$= .275 \sqrt{67886} = 203 \text{ cps}$$

4" x 6"

D-10W

150#RF x 150#RF FLANGED

DWG. NO. A-2370

ITEM NO.TAG NO.SET PRESSURE

27

PSV-F036

75 PSIG

$A = 9.12 \text{ in}^2$        $L = .62$        $r_1 = 2.78 \text{ in}$        $x = 2.75 \text{ in}$   
 $A_b = .202 \text{ in}^2$        $n = 8$        $r_2 = 3.94 \text{ in}$        $y = 14.9 \text{ in}$   
 $A_o = 28 \text{ in}^2$        $P = 75 \text{ PSIG}$        $u = 9.1 \text{ in}$        $z = 6.125 \text{ in}$   
 $A_s = 5.40 \text{ in}^2$        $Q = 613 \text{ GPM}$        $W = 200 \text{ LBS.}$        $J/c = 21.6 \text{ in}^3$   
 $D = 5.75 \text{ in}$        $R = 400\#/inch$        $W_b = 100 \text{ LBS}$        $I/c = 10.8 \text{ in}^3$   
 $d_1 = 4.630 \text{ in}$

1. OPERATING FORCES

- a. Reaction force of discharge jet acting horizontally along centerline of outlet.

$$F_r = \frac{.00139 Q^2}{A_o} = \frac{.00139 \times 613^2}{28} = 18.6 \text{ LBS.}$$

- b. Vertical force acting on centerline due to spring compression

$$F_{sp} = P \times A_s + L + R = 75 \times 5.4 + .62 \times 400$$

$$= 405 + 248 = 653 \text{ LBS.}$$

2. SEISMIC FORCES

- a. Vertical tension due to vertical acceleration.

$$F_v = g_v \times W - W = 6.0 \times 200 - 200 = 1000 \text{ LBS.}$$

- b. Horizontal shear due to horizontal acceleration.

$$F_h = g_h \times W = 6.0 \times 200 = 1200 \text{ LBS.}$$

- c. Torsion about vertical centerline due to horizontal acceleration.

$$T = g_h \times W \times (x) = 6.0 \times 200 \times 2.75 = 3300 \text{ IN.LBS.}$$

- d. Bending moment due to vertical acceleration.

$$M_v = x (g_v \times W + W) = 2.75 (6.0 \times 200 + 200) = 3850 \text{ IN.LBS.}$$

- e. Bending moment due to horizontal acceleration.

$$M_h = y (g_h \times W) = 14.9 \times 6.0 \times 200 = 17880 \text{ IN.LBS.}$$

3. COMBINED STRESSES ACTING AT POINT "O"

a. Tensile stress due to lb, 2a.

$$S_t = \frac{F_{sp} + F_v}{A} = \frac{653 + 1000}{9.12} = 181 \text{ PSI}$$

b. Shear stress due to 1a, 2b, 2c.

$$S_s = \frac{F_r + F_s}{A} + \frac{T}{J/c} = \frac{18.6 + 1200}{9.12} + \frac{3300}{\frac{\pi}{16} \left( \frac{5.75^4}{5.75} - \frac{4.63^4}{5.75} \right)}$$

$$= \frac{1218.6}{9.12} + \frac{3300}{21.6} = 286 \text{ PSI}$$

c. Bending stress due to 1a, 2d, 2e.

$$S_b = \frac{(F_r \times z) + M_v + M_h}{I/c} = \frac{(18.6 \times 6.125) + 3850 + 17880}{10.8} = 2023 \text{ PSI}$$

d. Combined stress due to 3a, 3b, 3c.

$$S = S_t + S_s + S_b = 181 + 286 + 2023 = 2490 \text{ PSI}$$

4. COMBINED STRESSES ACTING AT BOLTING

a. Tensile stress due to lb, 2a.

$$S_{bt} = \frac{F_{sp} + F_v}{n \times A_b} = \frac{653 + 1000}{8 \times .202} = 1023 \text{ PSI}$$

b. Bending stress due to horizontal acceleration (Bonnet only).

$$M_{bh} = S_h \times W_b \times u = 6.0 \times 100 \times 9.1 = 5460 \text{ IN.LBS.}$$

$$F_o = \frac{M_{bh} r_2}{2(r_2^2 + r_1^2)} = \frac{5460 \times 3.94}{2(3.94^2 + 2.78^2)} = 463 \text{ LBS.}$$

$$S_{bm} = \frac{F_o}{A_b} = \frac{463}{.202} = 2292 \text{ PSI}$$

(NOTE: Use number of bolts in plane of maximum stress.)

c. Combined stress due to 4a, 4b.

$$S_{tc} = S_{bt} + S_{bm} = 1023 + 229 = 1252 \text{ PSI}$$



SUPPLIER DRAWING  
REVISION NOTICE

JOB NO	DRAWING NO	REV NO
2846	9645-M-141.1 QS-7.0-1	8
RN NO.	8	PAGE 1 OF 1
BY	B. KHVC	DATE 8/7/81

REASON FOR CHANGE CHANGE TAG NO. OF ITEM NO. 34.  
CORRECT CALCULATION.

DESCRIPTION OF CHANGE

ZONE LOCATION

- 1) CHANGED TAG NO. OF ITEM NO. 34. PAGES 1b, 19  
WAS: HCC-PSV-SPARE  
NOW: HBC-PSV-F293A,B
- 2) CORRECTED NUMBER 59.67 TO 62.65 PAGE 22

8/7/81  
*G. Kerbin*  
GROUP SUPV / DATE

*M. Knight* 8/11/81  
PE / APE / DATE



ATTACHMENT NO. 7

Refurbishment Schedule  
E22-F004

TARGET SCHEDULE FOR MODIFICATION  
OF THE GRAND GULF  
E22-F004 LIMITORQUE ACTUATOR

1. Removal of Unit 2 F004  
Limitorque Actuator and  
Ship to Limitorque for Refurbishment Mid-May 1982
2. Completion of Refurbishing Valve Mid-Dec 1982  
New stem and stem nut  
New self-locking worm gear  
New motor  
Remove brake
3. Ship to Grand Gulf site ready for Mid-Jan 1983  
installation