



ARKANSAS POWER & LIGHT COMPANY

Arkansas Nuclear One

TITLE: RECORD OF CHANGES AND REVISIONS

FORM NO. 1000.06A

EMERGENCY PLAN PROCEDURE

REV. # 12 PC #

Safety Related YES ☒ NO ☐

COMMUNICATIONS EQUIPMENT TESTS

1903.61 REV. 2

UN-CONTROLLED COPY

103

PAGE	REV	PC#	PAGE	REV	PC#	PAGE	REV	PC#	PAGE	REV	PC#	PAGE	REV	PC#
------	-----	-----	------	-----	-----	------	-----	-----	------	-----	-----	------	-----	-----

1	2													
2	2													
3	2													
4	1													
5	2													
6	2													
7	2													
8	1													

APPROVED BY:

APPROVAL DATE

James M. Levine
(General Manager)

3/16/83
REQUIRED EFFECTIVE DATE:

8303300633 830325
PDR ADOCK 05000313
F PDR



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:
COMMUNICATIONS EQUIPMENT TESTS

NO:
1903.61

ARKANSAS NUCLEAR ONE

PAGE	1 of 8		
REVISION	2	DATE	11/29/82
CHANGE		DATE	

1.0 PURPOSE

The purpose of this procedure is to provide the requirements for testing the emergency communications equipment and to identify the necessary roster/call lists that must be verified periodically.

2.0 SCOPE

This procedure applies to communications systems and roster/call lists that would be used during an emergency situation at ANO.

3.0 REFERENCES

3.1 References Used in Procedure Preparation

3.1.1 Arkansas Nuclear One Emergency Plan

3.2 References Used in Conjunction with this Procedure

3.2.1 None

3.3 Related ANO Procedures

3.3.1 None

4.0 DEFINITIONS

None

5.0 RESPONSIBILITIES

5.1 The Emergency Planning Coordinator is responsible for coordinating ANO emergency communications equipment tests as required by this procedure.

6.0 DESCRIPTION

6.1 The following communications equipment/systems are available for use during an emergency:

6.1.1 Continental Telephone system

6.1.2 ANO plant phone system

6.1.3 Gai-tronics paging system

6.1.4 ANO radio system

6.1.5 NRC ENS (Hotline) phone

6.1.6 NRC HPN phone

6.1.7 AP&L Microwave



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:

COMMUNICATIONS EQUIPMENT TESTS

NO:

1903.61

ARKANSAS NUCLEAR ONE

PAGE	2 of 8		
REVISION	2	DATE	11/29/82
CHANGE		DATE	

6.2 The following roster/call lists are maintained in each Control Room for use during an emergency:

- 6.2.1 Duty Emergency Coordinator Roster
- 6.2.2 Staff Augmentation Group Roster/Call List
- 6.2.3 Beeper Assignment List

7.0 INSTRUCTIONS

7.1 The following items shall be accomplished on a monthly basis by the Emergency Planning Coordinator or a designee:

- 7.1.1 Verify the operability of the direct Continental Telephone lines to each Control Room.
- 7.1.2 Verify the operability of the radios located in at least one of the following areas:
 - A. Unit One Control Room
 - B. Unit Two Control Room
 - C. Technical Support Center
 - D. Emergency Control Center
 - E. Site Vehicles (except Security vehicles)
 - F. Communications Equipment Locker
 - G. AP&L Local Office
- 7.1.3 Verify the operability of the NRC-HPN phones in each one of the following locations:
 - A. Unit One Control Room
 - B. Technical Support Center
 - C. Emergency Control Center



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:

COMMUNICATIONS EQUIPMENT TESTS

NO:

1903.61

ARKANSAS NUCLEAR ONE

PAGE 3 of 8

REVISION 2 DATE 11/29/82

CHANGE DATE

7.1.4 Verify the telephone numbers for the following groups:

- A. Nuclear Regulatory Commission
- B. Arkansas Department of Health
- C. Little Rock Control Center
- D. Four - County Sheriffs
- E. National Weather Service

7.1.5 Verify the placement and correctness of the roster/call lists maintained in the following locations:

- A. Unit One Control Room
- B. Unit Two Control Room

7.1.6 The following communications equipment/systems do not require additional testing due to the indicated reasons:

- A. NRC-ENS (Hotline) phone located in each Control Room (used daily by the Shift Supervisors).
- B. ANO plant phone system, AP&L microwave system and the Gai-tronics paging system (used as a part of normal plant operation).
- C. Early Warning System (tested by the State of Arkansas).

7.2 Form 1903.61A, "Monthly Communications Testing Record", should be completed to document the performance of the monthly test.

7.3 Communications links between the plant, federal, state and local emergency operation centers and field assessment teams shall be tested annually (this may be done as a part of the plant's annual exercise). Form 1903.61B should be completed to document this test.

8.0 ACCEPTANCE CRITERIA

8.1 Tests shall be carried to a conclusion such that the test is adequate to verify equipment operability.

8.2 Upon discovery of inoperable emergency communications equipment, action shall be taken to initiate repair of the equipment.

NOTE: If loss of radio communication with offsite agencies occurs then an Unusual Event Emergency Action Level must be declared per procedure 1903.10, "Emergency Action Level Response".



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:

COMMUNICATIONS EQUIPMENT TESTS

NO:

1903.61

ARKANSAS NUCLEAR ONE

PAGE 5 of 8

REVISION 2 DATE 11/29/82

CHANGE DATE

ATTACHMENT 1

Communication Links Available
Between the Emergency Response
Centers

	CONTROL ROOM	OPERATIONAL SUPPORT CENTER	TECHNICAL SUPPORT CENTER	EMERGENCY CONTROL CENTER	RUSSELLVILLE FIRE DEPARTMENT	POPE COUNTY SHERIFF OFFICE	NRC REGION IV OFFICE & BETHESDA	AP&L CORPORATE OFFICES/LITTLE ROCK	STATE OF ARKANSAS EMERGENCY SERVICES	DEPT. OF HEALTH	ST. MARY'S HOSPITAL	POPE COUNTY EMERG. OPERATIONS CENTER	LOGAN/YELL/JOHNSON EMERGENCY OPERATIONS CENTERS	U.S.D.O.E. OAK RIDGE RAD. COORD. OFFICE
CONTROL ROOM	1	1,5	1,6	1	1	1	1	1	1	1,5*	1	1	1	1
	4	4,8	5	6	6	7	2	8	8		8	8	8	
ONSITE OPERATIONAL SUPPORT CENTER	1	3	3	1	1	1	1	1	1	1	1	1	1	1
	4	-	4				2							
ONSITE TECHNICAL SUPPORT CENTER	1,3	3,6	3	1,6	3,8	1	1	2	1	1,8	1	1	1	1
	4,8	4	-	5	6	6	7	8	5*		5	8	6,8	
EMERGENCY CONTROL CENTER	1,6	1,6	1,6	1	1	1	1	1	1	1	1	1	1	1
	3,8	3	3,8	1	1	7	2	1	1,8		6,8	6,8		
	5	5	-	6	6		8	5*						
RUSSELLVILLE FIRE DEPARTMENT	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	6			-	6			6	6			6	6	
POPE COUNTY SHERIFF OFFICE	1	1	1	1	6	1	1	1	6	1	6	6	1	
	6				-									
NRC REGION IV OFFICE AND BETHESDA	1	1	1,7	7	1	1	-	1	1	1	1	1	1	1
	1													
AP&L CORPORATE OFFICES LITTLE ROCK	1	1	1	1	1	1	1	-	1	1	1	1	1	1
	2	2	2	2										
STATE OF ARKANSAS OFFICE OF EMERGENCY SERVICES	1	1	1,8	1,8	1	1	1	1	-	1	1	1	1	1
	8			6	6				8		8	8		
DEPARTMENT OF HEALTH	1,*5	*5,8	*5,8	1	1	1	1	1	1	-	1	1	1	1
	8	1	1	1				8			8	8		
ST. MARY'S HOSPITAL	1	1	1	1	1	1	1	1	1	1	-	1	1	1
	1													
POPE COUNTY EMERGENCY OPERATIONS CENTERS	1	1	1,6	1	1	1	1	1	1	1	1	1	1	1
	8		8	6,8	6	6		8	8			8		
LOGAN, YELL*, AND JOHNSON COUNTY EMERGENCY OPERATIONS CENTERS	1	1	1,6	1	1	1	1	1	1	1	1	1	1	1
	8		8	6,8	6	6		8	8			8		
U.S. DEPARTMENT OF ENERGY OAK RIDGE RADIOLOGICAL COORDINATING OFFICE	1	1	1	1	1	1	1	1	1	1	1	1	1	-

COMMUNICATION LINKS:

- 1 - Continental Telephone
- 2 - AP&L Microwave Telephone
- 3 - Plant Phone System
- 4 - Gai-Tronics Paging System
- 5 - ANO Radio Frequency
- 6 - Pope County Sheriff's Radio/Frequency
- 7 - Hot Line
- 8 - OES Radio/Frequency

* Number 8 not applicable.

* In order for the Dept. of Health to communicate via the ANO radio frequency, the ANO radio must be in the "scrambler off" position.



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:

COMMUNICATIONS EQUIPMENT TESTS

NO:

1903.61

ARKANSAS NUCLEAR ONE

PAGE 6 of 8

REVISION 2 DATE 11/29/82

CHANGE DATE



ARKANSAS POWER & LIGHT COMPANY Arkansas Nuclear One

TITLE:

MONTHLY COMMUNICATIONS TESTING RECORD

FORM NO.

1903.61A

REV. # 2 PC #

Page 1 of 2

1.0 COMMUNICATIONS EQUIPMENT OPERABILITY TEST

Date _____

1.1 Direct Continental Telephone Line

Location	Results
ANO-1	
ANO-2	

1.2 ANO Radios

	Location	Channels Tested	Results
1.2.1	ANO-1/ANO-2/	1,2,3,4,5,6,7,8	
	TSC/ECC	1,2,3,4,5,6	
1.2.2	ANO Van	1,2,3	
1.2.3	ANO Pickup	1,2,3	
1.2.4	GM Car	1,2,3	
1.2.5	4WD Vehicle	1,2,3	
1.2.6	Portable Radios:		
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
	Unit _____	1,2,3	
1.2.7	SCBA Bone Phones (4 Total)	NA	

1.3 NRC-HPN Phones

Location	Results
ANO-1/ANO-2/TSC/ECC	



PLANT MANUAL SECTION:
EMERGENCY PLAN
PROCEDURE

PROCEDURE/WORK PLAN TITLE:

COMMUNICATIONS EQUIPMENT TESTS

NO:

1903.61

ARKANSAS NUCLEAR ONE

PAGE 7 of 8

REVISION 2

DATE

11/29/82

CHANGE

DATE



ARKANSAS POWER & LIGHT COMPANY Arkansas Nuclear One

TITLE:

MONTHLY COMMUNICATIONS TESTING RECORD

FORM NO.

1903.61A

REV. # 1

PC # 1

Page 2 of 2

1.4 Key Button Phones

	Location	Lines Tested	Results
1.4.1	ANO-1 (Sta. _____)		
1.4.2	ANO-2 (Sta. _____)		
1.4.3	TSC (Sta. _____)		
1.4.4	ECC (Sta. _____)		

2.0 TELEPHONE NUMBER VERIFICATION

	Agency	Phone No.
2.1	NRC	
2.2	Department of Health	
2.3	Little Rock Control Center	
2.4	National Weather Service	
2.5	Pope County Sheriff	
2.6	Yell County Sheriff	
2.7	Johnson County Sheriff	
2.8	Logan County Sheriff	
2.9	Pope Co. Ambulance Service	
2.10	Russellville Fire Department	
2.11	St. Mary's Hospital	
2.12	Millard Henry Clinic	
2.13	Babcock & Wilcox	
2.14	Combustion Engineering	

3.0 ROSTER/CALL LIST VERIFICATION

	List	ANO-1	ANC-2
3.1	Duty Emergency Coordinator		
3.2	Staff Augmentation Group: Engineering (T.S.)		
	Health Physics		
3.3	Beeper Assignment List		

4.0 CORRECTIVE ACTION REQUIRED (IF ANY):

Performed By _____