

Docket No. 50-423
B14943

Attachment 1

Millstone Nuclear Power Station, Unit No. 3
Proposed Revision to Technical Specifications

Ultimate Heat Sink
Marked-up Page

August 1994

PLANT SYSTEMS

JAN 31 1986

3/4.7.5 ULTIMATE HEAT SINK

LIMITING CONDITION FOR OPERATION

3.7.5 The ultimate heat sink shall be OPERABLE with an average water temperature of less than or equal to 75°F at the Unit 3 intake structure.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTION:

With the requirement of the above specification not satisfied, be in at least HOT STANDBY within 6 hours* and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.5 The ultimate heat sink shall be determined OPERABLE:

- a. At least once per 24 hours by verifying the average water temperature at the Unit 3 intake structure to be within limits.
- b. At least once per 6 hours by verifying the average water temperature at the Unit 3 intake structure to be within limits when the average water temperature exceeds 70°F.

* For a period from August — 1994, to October 1, 1994, the allowed time to reach a HOT STANDBY condition will be 24 hours. During this period, if the temperature increases above 77°F, be in HOT STANDBY within the next 6 hours.

Docket No. 50-423
B14943

Attachment 2

Millstone Nuclear Power Station, Unit No. 3
Proposed Revision to Technical Specifications

Ultimate Heat Sink
Retyped Page

August 1994

PLANT SYSTEMS

3/4.7.5 ULTIMATE HEAT SINK

LIMITING CONDITION FOR OPERATION

3.7.5 The ultimate heat sink shall be OPERABLE with an average water temperature of less than or equal to 75°F at the Unit 3 intake structure.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTION:

With the requirement of the above specification not satisfied, be in at least HOT STANDBY within 6 hours* and in COLD SHUTDOWN within the following 30 hours.

SURVEILLANCE REQUIREMENTS

4.7.5 The ultimate heat sink shall be determined OPERABLE:

- a. At least once per 24 hours by verifying the average water temperature at the Unit 3 intake structure to be within limits.
- b. At least once per 6 hours by verifying the average water temperature at the Unit 3 intake structure to be within limits when the average water temperature exceeds 70°F.

*For a period from August __, 1994 to October 1, 1994, the allowed time to reach a HOT STANDBY condition will be 24 hours. During this period, if the temperature increases above 77°F, be in HOT STANDBY within the next 6 hours.