

Attachment 1

383HA617 Rev. 0

Evaluation of CRD Scram Characteristics  
Under Simulated Earthquake Conditions

**TRANSMITTAL**

**FOR INTERNAL USE ONLY**

PROJECT "D" Lattice Core - 0.750 nom. gap

DOCUMENT TITLE Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

TYPE OF DOCUMENT REPLACES  
OR DRAWING: DOCUMENT NO.

RESPONSIBLE ENGINEER P. G. Rentz ISSUED BY B. L. Smith DATE DEC - 8 1971

REFERENCE DOCUMENTS

MASTER PARTS LIST NUMBER

REVISION RECORD

REVISED PER (ECA, ECN, ETC.)

SHEETS AFFECTED  REVISION IDENTIFIED WITH

COMMENTS:

DISTRIBUTION

NAME	MAIL CODE	COPIES	NAME	MAIL CODE	COPIES
N. J. Biglieri	711	(1)	H. E. Williamson/		
B. Vandemark	406	(1)	D. A. Vencer	155	(1)
M. G. Dunn	711	(2)	I. R. Kobsa	743	(1)
Wilmington Engrg.	009	(3)	V. W. Pence	711	(1)
P. G. Rentz	711	(1)	R. Buchanan, Jr.	406	(1)
B. L. Smith	624	(5)			
F. F. Smith, Jr.	711	(5)	Moe	742	1
GRU	742	(1)	DCC	742	3
L. K. Liu	375	(5)			
S. W. Smith	711	(1)			
D. L. Peterson	711	(1)			
F. E. Cooke	747	(1)			
J. R. Fritz	135	(1)			
J. Jacobson	713	(1)			

ADD NO ADDITIONAL DISTRIBUTION

CLASS II

FOR G.E. EMPLOYEES & SELECTED  
EXTERNAL ADDRESSEES

DISCLAIMER OF RESPONSIBILITY

This document was prepared as an account of research and development work performed by General Electric Company. It is being made available by General Electric Company without consideration in the interest of promoting the spread of technical knowledge. Neither General Electric Company nor the individual author:

- A. Makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information disclosed in this report may not infringe privately owned rights; or
- B. Assumes any responsibility for liability or damage which may result from the use of any information disclosed in this report.

# GENERAL ELECTRIC

NUCLEAR ENERGY DIVISION

ATOMIC POWER EQUIPMENT DEPARTMENT

San Jose, California

MCSR 262

DOCUMENT NO. 383HA617 REV. 0

APPLICATION \_\_\_\_\_

☐ SPECIFICATION ☐ DRAWING

TYPE INTERNAL

DOCUMENT TITLE Evaluation of CRD Scram Characteristics Under  
Simulated Earthquake Conditions

REVISIONS			
0	0		
<small>MADE BY</small> BL Smith <i>BL Smith</i>		<small>APPROVALS</small> PG Rentz <i>PG Rentz</i> 12/3/71	
<small>ISSUED</small> DEC - 8 1971		<small>CONT ON SHEET</small> 2 <small>SH NO</small> 1	

REVISION STATUS SHEET



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

REFERENCE:

- 1) 1970 PEP Q0002, RC10 CRD Scram Capability with Earthquake Induced Misalignment of Core Components.
- 2) 1971 PEP Q0062, CE-12, RC-3.
- 3) Letter to S. W. Smith from F. E. Cooke July 28, 1970 (attached).
- 4) Letter to J. Fritz from R. J. Murkowski May 12, 1970.
- 5) 731E849 Control Rod Clearance Study.
- 6) TRA-378 Earthquake Core Misalignment Test (attached).

1.0 INTRODUCTION:

In order to evaluate the scram characteristics of the control rod drive during an earthquake, a three phase test program was drafted and executed. Each phase was designed to simulate one of the core conditions resulting from an earthquake as defined in ref. 3. The program was authorized and funded as a PEP (see ref. 1&2).

The testing consisted of determining CRD scram performance under the following conditions:

Phase 1 - 500 pound constant friction load simulated by adding 500 pounds to the present drive line weight,

Phase 2 - maximum core misalignment due to allowable drawing tolerances, and

Phase 3 - additional misalignment due to earthquake, and finally with an aligned core, fuel channels bowed to a maximum of 1.5 inches.

2.0 RESULTS AND CONCLUSIONS:

2.1 Phase 1

A. At 1030 psig, vessel pressure with 500 pounds added to an aligned driveline, the 90% scram increases from an expected value of 2.5 seconds to 5.3 seconds.

B. At zero vessel pressure, the 90% scram times were only increased by approximately 10%.

C. At vessel pressures between 800 and 925 psig, the CRD will not full insert.

2.2 Phase 2

At maximum misalignment conditions due to drawing and installation tolerances, there was no significant effect on CRD performance.

BY		APPROVALS	REV 0
ISSUED DEC - 8 1971			383HA617
			CONT ON SHEET 3 SH NO. 2

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

### 2.3 Phase 3

A. -Additional static misalignment to simulate a possible earthquake condition when superimposed upon the maximum misalignment condition of Phase 2 had no significant effect on CRD performance.

B. With an aligned core, the first significant degradation of scram times occurs at channel bows of 0.6". At channel bows of 0.9" through 1.5" the CRD does not fully insert. At .9" bow and 1030 psi vessel pressure, the CRD stopped at 07 or 85%. At 1.5" bow and 1030 psi the CRD stopped at 42 or 17%. All scram tests were conducted with a static bow.

C. Channel bows at 0.9" at temperatures up to 546°F and 1.5" at ambient conditions do not produce channel yielding.

D. The misalignments to simulate earthquake displacements of the core supports and the channel bowing tests produced wear on the control rod and channels. This wear generated metal chips which get into the CRD and will effect its maintenance life.

### 3.0 TEST PROCEDURE:

#### 3.1 Phase 1

Phase 1 testing was intended to simulate friction in the driveline caused by lateral loading during an earthquake. The amount of friction was set at 500 pounds per ref. 3. This friction was simulated by adding 500 pounds to a control rod blade. Square bars were added to two sides of the control rod as shown in Figure 1. A fuel support was modified to allow these weights to pass, and a spacer was used at the top grid to hold the two remaining fuel bundles in proper position.

Testing consisted of running drive traces and scrams. A drive trace consists of recording drive pressures, position and time, while continuously inserting and withdrawing the CRD. The drive system was adjusted to provide a slower than normal drive insert and withdraw speed of approximately one inch per second. The scrams were performed from the fully withdrawn position with an accumulator gas precharge of 575 psi and a final water charge of 1510 psi. The order and number of drive traces and scrams were as follows:

<u>Vessel Pressure (psi)</u>	<u>Testing</u>
23	2 drive traces, 2 scrams & 2 drive traces
1030 (cold hydro)	1 drive trace, 5 accumulator scrams, 1 drive trace,
	2 vessel scrams, 1 drive trace
800       "       "	1 drive trace, 2 accum. scram, 1 drive trace
	1 vessel scram, 1 drive trace
900       "       "	1 accum. scram, & 1 vessel scram
950       "       "	1 accum. scram, & 1 vessel scram
925       "       "	1 accum. scram, 1 vessel scram & 1 drive trace
23	1 drive trace, 2 scrams, & 1 drive trace

BY		REV 0
APPROVALS		NO.
ISSUED DEC - 8 1977		303HA617
		CONT ON SHEET 4 SH NO. 3

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

### 3.2 Phase 2

The second phase was intended to test the scram performance of the CRD under maximum expected core misalignment due to fabrication and installation tolerances.

The lower core plate was misaligned with respect to the CRD housing centerline.

0.136 in. as defined in 731E849 (ref.5) plus  
0.030 in. hole position for a total of  
0.166 in. The top grid was misaligned  
0.124 in. as defined in ref. 4.

These dimensions were target misalignments. An optical alignment fixture was used to establish the target points and measure the actual misalignments obtained. The accuracy of the alignment system is estimated at  $\pm .020$ .

The direction in which the misalignment was made is shown in Fig. 2. The actual dimensions obtained are listed in Table 1.

Testing was similar to phase 1 with the addition of jog traces and settle friction test. Jog traces consist of measuring driving pressures, position and time as the drive was jogged in and out one notch at a time over the full stroke. Settle friction testing consists of measuring the pressure under the drive piston as the drive settles back into each notch.

Testing consisted of two drive traces, one jog trace, one settle friction, two scrams and one settle friction performed with no core misalignment. Then, after the core plate and top grid had been moved to the misaligned position, this test was repeated. No testing was performed at higher vessel pressures since no effects of misalignment were observed on CRD performance at ambient conditions.

### 3.3 Phase 3

The final phase was divided into two tests. The first was with earthquake induced lateral core misalignments and the second was with earthquake induced channel or core bow. The amount of misalignment and bow were defined in ref. 3. The misalignment for part 1 was in addition to and in a plane  $90^\circ$  to the phase 2 misalignment. Fig. 2 defines this condition where the target displacements were "A"=.166, "B"=.042 (.166-.124=.042), "C"=.20 and "D"=.60.

With this misalignment established in the core plate and top grid respectively the following tests were performed:

#### Vessel Pressure (psi)

23 (ambient)

800 cold Hydro

500 & 800 Hot

#### Tests

2 drive traces, 1 jog trace, 1 settle friction,  
2 scrams & 1 settle friction  
3 accum. scrams & 2 vessel scrams  
1 drive trace, 1 settle friction, 2 accum.scrams,  
2 vessel scrams, 1 settle friction, 1 drive trace

BY		APPROVALS	REV 0
ISSUED DEC - 8 1971			383HA617
			CONT ON SHEET 5 SH NO. 4

TITLE

Scram Characteristics Under Simulated Earthquake Conditions

Vessel Pressure (psi)

1030 Hot

23 (ambient)

Tests

1 drive trace, 1 settle friction, 5 accum. scrams,  
2 vessel scrams, 1 settle friction and 1 drive  
trace  
1 settle friction, 2 scrams, 2 drive traces, &  
1 jog trace

The 800 psi cold hydro was run in order to determine if the effects seen during ambient testing warranted hot testing. The answer was yes and hot testing commenced.

Part 2 testing was performed with varying amounts of bow in the channels. The core was aligned prior to bowing. The bowing was accomplished by first articulating the center bars of the Building G fuel bundles with a ball joint. A spacer block was installed and the channels drilled to line up with tapped holes in the block (see Fig. 4, 5 and 6). The four bundles were then held together in their proper orientation while a plate was bolted, through the channels, to the spacer blocks. A scissors jack arrangement was installed to the plate as shown in Fig. 7. This assembly was lifted (see Fig. 8) and lowered into the 30" vessel. The scissors jack slipped onto two pins on one of the "T" bars which are welded to the inside of the vessel. The top grid was then installed using 1/2" pins to take the side loads (see Fig. 9).

Before the fuel assembly was lowered into place, an optical target scale was clamped to the plate. The alignment scope was used to view the scale. The scope in its mount is shown in Fig. 10, and the view of the scale through the scope is shown in Fig. 11. The cross hairs of the scope were lined up on a number, then after jacking the plate over the amount of bow could be determined by subtracting the original number from the final. The maximum bow reached was 1.5 inches. The effects on the channels of this 1.5 inch bow can be seen in Fig. 12, while Fig. 13 shows an overall sketch of this set-up.

In terms of testing, one new type of test was introduced in this part. The CRD was driven in using cooling water at elevated pressures rather than using the normal drive insert system. The results of this test were traces of pressure which indicate driveline friction in the insert direction.

To facilitate the writing of the test request and the running of the test, a basic test was defined as follows:

- A. Two cooling water driving traces.
- B. One settle friction trace.
- C. Two drive traces.
- D. Two accum. scrams (1510/575).

The test sequence is shown in Table 2. Referring then to this table, the following comments are in order. First, increased vessel pressure testing started as soon as the effects of bowing were deemed significant, i.e. 0.9 inch bow. Second, after 1.3 and 1.5 inch bow the jack was backed off to 0 bow to verify that the channels were still in the elastic range. Then, the bow was increased to 0.6 to determine if any damage had occurred due to testing.

BY	APPROVALS	REV NO. 0 383HA617
ISSUED DEC - 8 1971		CONT ON SHEET 6 SH NO. 5



ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

The next point is that the 0.9 inch bow hot tests were run to verify that the cold hydro tests yield results which are very close to the hot condition. It should be noted that the optical scale was removed prior to going hot.

After hot testing, an attempt to return to zero bow failed. A galled thread on the jacking screw caused the mechanism to bind up at about 0.7 bow. The bundles were removed, disassembled and inspected at this point. The control rod and fuel support were also removed and inspected.

The fuel bundles were reassembled with some new cables (see cable in Fig. 4 & 5) and reinstalled in the vessel. Testing continued as shown in Table 2. The remaining tests were performed in order to demonstrate high energy scram effects (N<sub>2</sub> precharge increased from 575 to 710 to 875 psig) and to determine if CRD housing deflections had any effect on scrambling.

One other dimensional check was made in conjunction with returning the channels to zero bow after the final 1.5 inch bow tests. The dimensions between the top grid and the T-bars on the vessel wall were determined under both loaded and unloaded conditions. This was to ascertain if any movement of the top grid occurred due to loading which would invalidate the amount of bow which was measured on the scale.

#### 4.0 TEST RESULTS:

##### 4.1 Phase 1 (Control Rod Drive)

The primary piece of data from phase 1 is scram times. At zero vessel pressure, the times to 90% stroke were between 1.725 and 1.741 sec. which is slightly slower than the 1.6 second normal; however, at 800 psi vessel pressure the drive stopped after 2.2 seconds at position 22. At 900 psi, the drive stopped after 0.6 seconds at position 26. In addition, at both vessel pressures the CRD did not move during a fifteen second vessel scram (accumulator valved out).

Fig. 14 plots the results of 925, 950 and 1030 psi testing. At the normal operating pressures of 1030 psig and normal accumulator charge, the 90% scram time was approximately five seconds which is about twice the time for a normal scram. The conclusion is that if the CRD sees an additional friction load of 500 pounds, there will be reduced speeds at normal operating pressures, and within some pressure spread less than 925 psi, full stroke will not be achieved. The additional possibility exists that no CRD motion will occur at these lower vessel pressures.

##### 4.2 Phase 2

The results of phase 2 testing were that there was no detected change in CRD performance due to expected fabrication and installation misalignment. Scram times were 1.548 sec. aligned and 1.558 misaligned. Both times were within the normal 90% scram time spread for CRD #880 (Engineering test CRD).

Settle friction ranged from 40 to 45 psi aligned and 39 to 46 psi misaligned. Both ranges are normal.

BY		APPROVALS	REV NO. 0
ISSUED			383HA617
200 - 8 1971			7 SH NO. 6
			CONT ON SHEET

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

The drive trace data was likewise similar between aligned and misaligned. This data is presented in the attached phase 2 test data section.

4.3 Phase 3

During initial testing of part 1 of this phase, the data (see attached phase 3 part 1 test data section) indicated a decrease in settle pressures of approximately 5 psi. This can be and was interpreted as increased friction. Scram times and drive performance were normal.

In order to determine if the increased friction would effect scram times at elevated vessel pressure, scram testing at a cold hydro of 800 psi was performed. The accumulator scram times were normal but the vessel scram times were about 15% slow. To verify this slowing, and to determine temperature effects, a hot test was performed. At 500 and 800 psi vessel pressure, accumulator and vessel scram times were normal. At 1030 psi, some slowing was observed, approximately 15% both in accumulator and vessel scram times. Fig. 15 presents the normal scram speed profile for drive 880 with the new data plotted.

Settle friction and drive data at all vessel pressures tested showed normal performance. The post pressurized settle friction indicated a decrease in friction of approximately 10 psi. Since the alignment did not change during the test, a wearing-in action is the most likely explanation for the reduced friction.

During the first part of testing, the channels were coated with blueing so the rub marks would be very evident. Fig. 16 shows a typical result of this technique. Actual metal removal could be detected but no heavy wear marks were visible.

Since little or no effects on drive performance were found, it is concluded that under static conditions the lateral displacement used in this test will have no effect on scram capability.

Part 2 of this testing phase was channel bowing. As the amount of bow was increased incrementally to 1.5 inches, and primarily between 0.6 and 1.5 inch, the distance of the control rod would travel decreased. Fig. 17 shows that accum. (1510/575) scram travel is a function of vessel pressure and bow. That is as the amount of bow increased the amount of travel decreased. Also, at elevated vessel pressures the amount of travel decreased. In Figure 17, the travel is shown to be more at 1030 psi than at 800 psi vessel pressure. This effect of vessel pressure can be predicted and explained from the scram profile (see Fig. 15). The other variable, bow, was predicted as the results of the friction observed during the cooling water drive test (see Fig. 18). As can be seen, the cooling water pressure and therefore the friction, increased greatly as bow increased. Once 0.9 in. bow tests were run and the stopping point, position 07 at 1030 psi was observed and the corresponding cooling pressure, about 250 psi, was determined, then it could be anticipated that at 1.2 inch bow and 1030 psi the drive would stop near position 12. Likewise, at 1.5 inch bow and 1030 psi

		REV 0
BY	APPROVALS	383HA617
ISSUED	0 1979	CONT ON SHEET 8 SH NO. 7

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

position 40 could be predicted. The horizontal line on Fig. <sup>15</sup> at 255 psi is the evidence of the repeatability of the stopping point.

In addition to Fig. 17, Fig. 19 is presented to indicate the times associated with the various amounts of travel at zero and 1030 vessel pressure. Only accumulator scram data is presented on this figure.

The significant fact of this data and figures is that at some point between 0.6 and 0.9" bow, drive line friction was not high enough to keep the CRD from completing its full stroke. It must be kept in mind that these scram tests at the specified channel bows were all performed at static conditions. If a seismic oscillation occurred which produced channel bows up to 1.5" and no yielding of the channels occurred at this deflection, then it is possible that if the driveline has stopped because of deflections > 0.9 inch, it will continue on in as the deflections swing back through approximately 0.6" back to zero and then to 0.6". The channels were shown to be elastic when the jack was backed off from 1.2 inch and 1.5 inch bow. Note, however, that no hot tests were run at 1.2 or 1.5 inch bow. In each case, cold, the bundles moved back to within .03 inches of the original zero. The .03 inch can be explained since each time a test was run after a given bow was set the bundles moved back about .03. At 1.2 and 1.5, the scope had to be reinstalled after cold pressure tests. The .03 was not taken into account when reinstalling the scope. Therefore, when backed off the final position is 0.03 above 0.

If yielding were to occur at 1.5 inch bow and 1030 psi, 546°F vessel conditions, due to a lower yield strength at elevated temperatures, then the scram would not be accomplished as stated above. Under yielded fuel channel conditions of 1.5 inch deflection, a full insertion of the control rod blade would only occur if, as the blade experiences increased friction, due to bow, the fuel channels are deflected back towards zero bow by the control rod. If this deflection reduces bow to that point between 0.6 inch and 0.9 inch bow, discussed above, the blade will continue movement to full insertion. During this test, the jack mechanism did not allow any verification of this theory.

During testing, it was found that settle friction results (Fig. 20) showed similar characteristics as cooling water results (Fig. 18). This can best be seen in the plot for 0.9 inch bow. Cooling pressure increased, decreased then increased to its high of 300 psi. Settle friction pressures, which decrease with increased friction, decreased until the drive would not settle, then increased and decreased to zero again as the cooling pressure changed. This correlation supports the shape of the cooling curve.

The explanation of this shape can be seen in Fig. 21. During the first half of the stroke, the loading is as shown in 21A. High friction occurs at the bottom of the fuel channels. In 21B, the roller has gone past halfway and is unloaded to some degree, thus, decreasing load and friction at the bottom. Friction increases again as the roller picks up the other side in 21C and contact occurs at the middle and bottom.

BY	APPROVALS	REV NO. 0 383HA617
ISSUED DEC - 8 1971		CONT ON SHEET 9 SH NO. 8

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

The results of the inspection of internals are pictured in Figures 22 through 31 with Figure 22 provided to aid in interpretation.

Referring to Figure 21C and 22, it would be expected that wear marks would be found on the upper and lower areas of the north and west channels as well as in the middle of the south and east channels. Figure 23 shows the north and west channels with wear marks at the bottom and the upper one-third. Note the wear on the north channel being close to the inside corner. Figure 24 shows the south and east channel wear as covering the middle one-third of the length. Again, the inner edge is worn. Note that at the center, where the spacer blocks were, a wider spot of wear occurred. Such a mark indicates some distortion of the channel shape at that location.

Figure 25 and 26 show the corresponding wear on the control rod. Also, rub marks were found on both sides of the handle on the top of the control rod. The side which faced the north and west channels is pictured in Figure 27.

The unpredicted rubbing which was discovered upon inspection and was the cause of much friction, was between the northwest edge of the control rod and the fuel support. The entire length of the fuel support was galled (see Figure 28). The resulting groove was the width of the control rod and about .06 inch deep at the top of the fuel support. The control rod was galled and torn over 90% of its length from the velocity limiter (Fig. 29) to near the top. Fig. 30 shows the resulting edge of the control rod. The material which was removed by galling and tearing was found in the CRD inner filter (see Fig. 31). Such materials in the CRD would significantly reduce seal life.

An explanation of how this rubbing occurs is presently in Fig. 32. During the lower half of the stroke, the rollers are loaded as in A with the loading at the bottom of the channels shown in B. Note the bending of the wings which allows contact with the fuel support as in C. Above the halfway point, the loading of the rollers is as in D. The loading in the middle is as in E, and the bottom is again as in B. The result is the same with rubbing occurring as in C. The wear marks near the inner edge on the channels verify this explanation.

The results of the high energy scrams at 1.5 inch bow were that the drive went in an additional 15% for a total of 30% with 1320/710 charge, and 40% more for a total of 55% with 1510/875 charge. These were at 800 psi with similar results at 900 and 1030 psi vessel pressure.

The deflecting of the CRD housing 0.5 inches and .625 inch, in addition to the 1.5 inch bow, had no effect on the scrams. Quick releasing the housing and hand exciting the housing had also no effect on scrambling.

The results of the loaded-unloaded top grid measurements are shown in Fig. 33. The maximum difference was .016 inch which was not considered significant.


		REV NO. 0
BY	APPROVALS	383HA617
ISSUED	DEC - 8 1971	CONT ON SHEET 10 SH NO. 9



ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

TABLE 1



Alignment  $\pm .02$

Test	Core Plate				Top Grid			
	NW	("A")	SW	("C")	NW	("B")	SW	("D")
	Actual	Target	Actual	Target	Actual	Target	Actual	Target
Phase 1	*	0	*	0	*	0	*	0
Phase 2								
Pre-test Alignment	*	0	*	0	*	0	*	0
Initial Misalignment	.184	.166	-.053	0	.029	.042	-.029	0
Pre-Test Check	.184	.166	-.034	0	.029	.042	-.019	0
Phase 3								
Part 1	.155	.166	.195	.2	.024	.042	.611	.6
Post Test Check	.150	.166	.180	.2	.028	.042	.611	.6
Part 2	.010	0	-.003	0	.008	0	-.004	0
Post Test Check	.078	0	.003	0	.008	0	-.004	0

\* Tight wire system used; actuals unknown

\*\* .166-.124 = .042

BY	APPROVAL	REV 0
ISSUED	DEC - 8 1971	383HA617
		CONT ON SHEET 11 SH NO. 10

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

TABLE 2  
TEST SEQUENCE

Amount of Bow	Vessel Pressure (PSI)	Basic Test	Other Tests
0	23 (ambient)	X	None
.3	23 (ambient)	X	None
.6	23 (ambient)	X	None
.9	23 (ambient)	X	None
	1030 cold Hydro		2 accum scrams 2 vessel scrams
	800 & 900		1 accum scram
1.2	23 (ambient)	Parts A, B & D	None
	800, 900 and 1030 cold Hydro		1 accum scram
.6	23 (ambient)	X	None
1.5	800		1 accum scram 2 vessel scrams
	900 and 1030		1 accum scram 1 vessel scram
	23 (ambient)	Part B	1 cooling trace 1 accum scram
.6	23 (ambient)	X	None
.9	23 (ambient)	X	
	800 & 900)	Part D	2 vessel scrams
	1030 ) Hot	Parts A, B and D	1 drive trace
	23	X	
0	23 (ambient)	X	None
1.5	800, 900 and 1030 cold Hydro		2 accum scrams (1320/710) 2 scrams (1510/875)
	1030		2 scrams (1510/575)

BY	APPROVALS	REV NO. 0
ISSUED	DEC - 8 1971	383HA617
		CONT ON SHEET 12 SH NO. 11

ENGINEERING FORM

TITLE  
 Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

TABLE 2 (cont.)

1.5 with .5 CRD housing displacement	1030 cold Hydro	1 accum scram (1510/575)
1.5 with isolating CRD housing	1030 cold Hydro	3 scrams (1510/575)
1.5 with .625 CRD housing displacement		2 accum scrams 1 dynamic 1 static

1.5

Part D

BY		APPROVALS	REV 0 NO.
ISSUED 100 - 0 1071			383HA617
			CONT ON SHEET 13 SH NO 12

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 1

BY		APPROVALS	REV 0
ISSUED			383HA617
DEC - 8 1971			CONT ON SHEET 14 SH NO. 13

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

"B" Top Grid  
Displacement  
("A" Minus Top  
Grid Misalignment)  
(See Table 1)



"A" Lower Core  
Plate Misalignment  
(See Table 1)

Two points which  
establish CRD housing  
centerline

FIGURE 2

BY	APPROVALS	REV. 0
ISSUED	CCC - 8 1971	383HA617
		CONT ON SHEET 15 SH NO. 14

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 3

BY	APPROVALS	REV NO. 0
ISSUED		383HA617
		CONT ON SHEET 16 SH NO. 15

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions



FIGURE 4



FIGURE 5



FIGURE 6




FIGURE 7




FIGURE 8


BY		APPROVALS	REV 0
ISSUED 500-3 1076			383HA617
			CONT ON SHEET 17 SH NO. 16



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions



"T" BAR

FIGURE 9





FIGURE 10



HAIR LINE

FIGURE 11

BY	APPROVALS	REV 0
ISSUED	DEC - 3 1971	383HA617
		CONT ON SHEET 18 SH NO. 17



ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions



FIGURE 12

BY		APPROVALS	REV NO. 0
ISSUED LEC - 8 1971			383HA617
			CONT ON SHEET 19 SH NO. 18

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 13

BY	APPROVALS	REV 0
ISSUED		383HA617
DEC - 8 1971		CONT ON SHEET 20 SH NO. 19

ENGINEERING FORM

TITLE Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 14

14.1 (SCRAM TIME) (SEC)

BY	APPROVALS	REV 0
ISSUED		383HA617
100-8-1971		21 SH NO. 20
		CONT ON SHEET

ENGINEERING FORM

TITLE Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 15

VESSEL PRESSURE (PSIG)

REV 0

BY

APPROVALS

383HA617

ISSUED LSC - 0 1971

CONT ON SHEET 22 SH NO. 21

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 16



BY	APPROVALS	REV NO. 0
ISSUED 000-8 1971		383HA617
		CONT ON SHEET 23 SH NO. 22

ENGINEERING FORM

TITLE Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 18

No. n

BY	APPROVALS	REV NO. 0
ISSUED 020-8 1971		383HA617
		CONT ON SHEET 24 SH NO. 23

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 19

BY	APPROVALS	REV 0
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 25 SH NO. 24



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 21

SY	APPROVALS	REV NO. 0
ISSUED DEC - 8 1971		383HA617
		26
		CONT ON SHEET 25



ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 22





FIGURE 23

BY	APPROVALS	REV NO. 0
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 27 SH NO. 26

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 24

BY		APPROVALS	REV NO. 0
ISSUED 1-2-0 1074			383HA617
			CONT ON SHEET 28 SH NO. 27

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 25

BY		APPROVALS	REV 0
ISSUED			383HA617
			CONT ON SHEET 29 SH NO. 28

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions






FIGURE 26

BY		APPROVALS	REV NO. 0
ISSUED DEC - 8 1971			383HA617
			CONT ON SHEET 30 SH NO. 29

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions



N-W SIDE

FIGURE 27




FIGURE 28

BY	APPROVALS	REV NO. 0
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 31 SH NO. 30

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 29

BY	APPROVALS	REV NO. 0
ISSUED DFC - 0 1279		383HA617
		CONT ON SHEET 32 SH NO. 31



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions






FIGURE 30

BY		APPROVALS		REV 0
ISSUED				383HA617
LTD - 0				33 32
				CONT ON SHEET SH NO.

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions




FIGURE 31

BY	APPROVALS	REV 0
ISSUED DEC - 8 1971		383HA617
		CONTY ON SHEET 34 SH NO. 33



ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions





FIGURE 32

BY	APPROVALS	REV 0
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 35 SH NO. 34

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions



"X"	LOADED	UNLOADED
SE	6.725	6.734
SW	7.208	7.192
NE	6.494	6.488
NW	7.004	6.999

FIGURE 33

BY	APPROVALS	REV NO. 0
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 36 SH NO. 35

ENGINEERING FORM

TITLE  
Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

PHASE 1

TEST DATA

		REV 0
		383HA617
BY	APPROVALS	
ISSUED DEC - 8 1971		CONT ON SHEET 37 SH NO. 36

TITLE EARTHQUAKE CORE MISALIGNMENT TEST REQUEST 378 PHASE 1

DRIVE MODEL ENG. S/N 880 ROD WT. (lb) 756

COOLING PRESS (PSIG) 15 TEST SYSTEM 30" 15 GPM AT 1500 PSIG

SCRAM DATA

SCRAM (M)	VESSEL PRESSURE (PSIG)	ACCUMULATOR CHARGE (PSIG)	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG. LOSS TO DO-46 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME DO-05 TO DO-05 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	P/PR Position 24	P/PR Position 24	P/PR Position 24	P/PR Position 24	REMARKS
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	USED START of Motion from Scram #2
1	23	1510/581	72	72	72	.207	.348	1.020	1.726	.290	.396	250	550	220		
2	23	1510/581	72	72	72	.207	.352	1.015	1.725	.288	.417	250	575	210		
3	1030	1510/581	544	544	90	.242	.620	3.195	5.428		.820	945	7	10	1000	
4	1030	1510/581	544	544	96	.220	.590	2.530	4.420	1.321	.770	900	15	28	940	
5	1030	1510/581	544	544	100	.224	.590	2.997	5.195	1.776	.796	950	5	28	1000	
6	1030	1510/581	544	544	129	.230	.619	3.082	5.265	1.291	.830	960	0	23	1007	
7	1030	1510/581	544	544	121	.239	.624	3.275	5.630	1.310	.832	960	10	25	1000	
8	1030	1510/581	543	543	106	.403	.985	3.717	6.142	1.117	1.250	380	950			
9	1030	1510/581	544	544	116	.399	.917	3.577	6.184	1.183	1.180	955	920			
10	800	1510/585	513	513	102	.250	.440	2.172			.565	760	40	9	830	Stopped @ 22 pos.
11	800	1510/585	513	512	102	.250	.410	2.112			.562	750	60	0	820	Stopped @ 22 pos
12	800	1510/588	513	513	107											DID NOT MOVE ALO 519 15 sec
13	900	1510/588	525	523	200	.260	.450	.612								Stopped @ 26 pos.
14	900	1510/588	523	524	182											DID NOT MOVE ALO 519 15 sec
15	950	1510/588	530	531	198	.235	.506	3.822	8.109	2.046	.642	900	5	18	960	
16	950	1510/582	532	532	112	.450	1.131	4.996	9.610	2.630	1.490	895	900			
17	925	1510/582	529	529	116	.220	.475	3.518	16.200	5.738	.605	880	8	15	940	
18	925	1510/582	528	528	116	.529	1.295	5.898	16.624	3.684	1.722	880	875			
19	23	1510/592	178	74	74	.225	.368	1.030	1.741	.262	.421	250	560	215	850	
20	23	1510/592	178	74	74	.215	.353	1.038	1.732	.260	.428	240	560	220	850	

CONT SHEET 38 PH NO 37

770 - 0 107

DATE 9-29-70 9-30-70 10-1-70

### DRIVE DATA

TITLE ENGINE  
DRIVE MODEL ENG.  
COOLING PRESS (PSIG) \_\_\_\_\_

S/N 880

ROG M. (10)

730 (over)

PSIG

TEST REQUEST A-378 PHASE 1

DATE 8-29-70

PAGE

TECHNICIAN

Alkalic

430921094

REMARKS

DEC - 3 1971

3834617

CONT ON SHEET 34 BH NO. 38



# LEAKAGE & FRICTION DATA PRE-TEST

SEAL LEAKAGE TEST PAR. 7.0												
INDEX TUBE	APPLIED PRESSURE		LEAK POINT								TOTAL LEAKAGE	
			P.O. PORT		COLLET		SPUD		VESSEL PORTS			
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN		ML/MIN	
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL
EXTENDED	200 AT P.O.	200	N.A.	0	2650	825	1138	805	758*	200	4160	1830
RETRACTED	200 AT P.U.	200	758	0	1705	410	189	0	567	60	2460	470
* VESSEL PORTS + P.U. PORT												
NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST												

# LEAKAGE & FRICTION DATA POST TEST (10-1-70)

SEAL LEAKAGE TEST PAR. 7.0												
INDEX TUBE	APPLIED PRESSURE		LEAK POINT								TOTAL LEAKAGE	
			P.O. PORT		COLLET		SPUD		VESSEL PORTS			
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN		ML/MIN	
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL
EXTENDED	200 AT P.O.	200	N.A.	0	2650	1670	1138	1495	758*	660	4160	3825
RETRACTED	200 AT P.U.	200	758	55	1705	1345	189	0	567	85	2460	1485
* VESSEL PORTS + P.U. PORT												
NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST												

TABLE LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE CORE MISALIGNMENT TEST REQUEST A-378

DRIVE MODEL ENG S.N. 880 DATE 9-28-70

REF ID: 3834617

COUNT ON SHEET 40 SH NO. 39

DEC-8 1971



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

PHASE 2

TEST DATA

BY	APPROVAL	REV 0 NO.
ISSUED DEC - 8 1971		383HA617
		CONT ON SHEET 41 SH NO. 40

## TABLE

## SCRAM DATA

PHASE 2

TITLE EARTHQUAKE CORE MISALIGNMENT (PRE-TEST) TEST REQUEST A-376-1

DRIVE MODEL

SN 880

ROD WT. (lb)

COOLING PRESS (PSIG)

TEST SYSTEM

30'15

GPM AT

PSIG

SCRAM COUNTER

CUMULATIVE  
SCRAM (#)VESSEL  
PRESSURE (PSIG)

TIME

STEAM SPACE  
TEMPERATURE (°F)VESSEL BOTTOM  
TEMPERATURE (°F)PROBE  
TEMPERATURE (°F)START OF MOTION SCRAM  
SIG. LOSS TO DO-48 (sec)5% STROKE-SCRAM SIG.  
LOSS TO DO-45 (sec)10% STROKE-SCRAM SIG.  
LOSS TO DO-43 (sec)20% STROKE-SCRAM SIG.  
LOSS TO PU-38 (sec)50% STROKE-SCRAM SIG.  
LOSS TO DO-24 (sec)90% STROKE-SCRAM SIG.  
LOSS TO DO-05 (sec)BUFFER TIME (sec)  
DO-03 TO DO-06PU/PR MIDSTROKE  
 $\Delta P$  (PSI)PO/PR MIDSTROKE  
 $\Delta P$  (PSI)VESSEL WATER  
CONDUCTIVITY-(MEGOHM)

REMARKS

BUBNIK/PARDO  
TECHNICIANDATE 2-9-71

PAGE

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16

1 22 1540 63 63 63 63 132 240 293 430 884 1550 224 450 230

PRE-TEST  
(ALIGNED)

2 22 1550 63 63 63 63 117 235 293 425 887 1545 217 465 255

TEST 2-9-71  
(MISALIGNED)

1 21 1330 63 63 63 63 125 245 298 420 890 1566 332 460 240

2 21 1335 63 63 63 63 110 220 290 420 870 1550 223 445 240

DEC - 0 1971

CONT ON SHEET 42 SH NO 41

383H4617

### LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE CORE MISALIGNMENT (PAC-TEST) TEST REQUEST A 378-1  
DRIVE MODEL ENG S/N 880 DATE 2-2-71

SEAL LEAKAGE TEST PAR. 7.0														
INDEX TUBE	APPLIED PRESSURE		LEAK POINT						TOTAL LEAKAGE					
			P.O. PORT		COLLET		SPUD		VESSEL PORTS		ML/MIN			
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN					
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL		SPEC.	ACTUAL			
	EXTENDED	200 AT P.O.	200	N.A.	0	2650	2260	1138	1120	758*	200	4160	3580	
RETRACTED	200 AT P.U.	200	758	0	1705	420	189	0	567	40	2460	660		
*VESSEL PORTS		P. U. PORT		NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST								COOLING ORIFICE LEAKAGE		ML/MIN
30 PSIG APPLIED @ P. U. RETRACTED. 1050/1703 ML/MIN SPEC.														

COLLET FRICTION PAR. 8.1.						
VESSEL PRESSURE psig	SPEC. MIN. psig	TRIAL				
		1 P. O. MIN. psig	2 P. O. MIN. psig	3 P. O. MIN. psig	4 P. O. MIN. psig	5 P. O. MIN. psig
	70					

SETTLE FRICTION					
PAR. B.2.1					
<div style="border: 1px solid black; padding: 5px; text-align: center;">           40 PSID MIN. W/10            psig MAX. VARIANCE         </div>					
PHASE 2 - PRE-TEST (ALIGNED)					
NOTCH	VESSEL PSIG				
	20	22			
48	42	44			
46	43	45			
44	43	44			
42	43	44			
40	43	43			
38	43	44			
36	43	43			
34	43	42			
32	43	43			
30	43	43			
28	43	42			
26	42	42			
24	42	41			
22	42	42			
20	42	42			
18	42	42			
16	41	41			
14	42	42			
12	42	42			
10	41	41			
08	42	42			
06	42	42			
04	41	41			
02	40	42			
00	44	43			
		REV NO. 0			

3834A617

DEC - 8 1971

CONT ON SHEET 43 BH NO. 42

# LEAKAGE & FRICTION DATA

## TABLE

## LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE Core MISALIGNMENT

TEST REQUEST A-378-1

DRIVE MODEL ENG 880

S/N 880

DATE 2-9-71

SEAL LEAKAGE TEST PAR. 7.0										
INDEX TUBE	APPLIED PRESSURE psig		P.O. PORT ML/MIN		COLLET ML/MIN		SPUD ML/MIN		VESSEL PORTS ML/MIN	
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL
EXTENDED	200 AT P.O.	200	N.A.	0	2650	1340	1138	1200	758*	310
RETRACTED	200 AT P.U.	200	758	90	1705	680	189	0	567	70
*VESSEL PORTS P. U. PORT NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST										
30 psig APPLIED @ P. U. RETRACTED, 1060/1703 ML/MIN SPEC.										
TOTAL LEAKAGE ML/MIN										
SPEC. 4160										
ACTUAL 2850										
COOLING ORIFICE LEAKAGE ML/MIN										
SPEC. 2460										
ACTUAL 810										

COLLET FRICTION PAR. 8.1.						
VESSEL PRESSURE psig	SPEC. MIN. psig	TRIAL				
		1 P. O. MIN. psig	2 P. O. MIN. psig	3 P. O. MIN. psig	4 P. O. MIN. psig	5 P. O. MIN. psig
	70					
		</				

## DRIVE DATA

TEST REQUEST A-378-1

- psig

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
DATE															
VESSEL PRESSURE (psi g)															
STEAM SPACE TEMPERATURE (°F)															
VESSEL BOTTOM TEMPERATURE (°F)															
PROBE TEMPERATURE (°F)															
HCU SUPPLY PRESSURE UP P1L/PR ΔP (psi)															
PRESSURE UNDER PISTON DRIVING UP-P13/PR ΔP (psi)															
PRESSURE OVER PISTON DRIVING UP-P12/PR ΔP (psi)															
SPEED DRIVING UP (in./sec)															
HCU SUPPLY PRESSURE DOWN -P1L/PR ΔP (psi)															
PRESSURE OVER PISTON DRIVING DOWN-P12/PR ΔP (psi)															
PRESSURE UNDER PISTON DRIVING DOWN-P13/PR ΔP (psi)															
SPEED DRIVING DOWN (in./sec)															
DRIVE UP FLOW (GPM)															
DRIVE DOWN FLOW (GPM)															
STALL UP FLOW (GPM)															
STALL DOWN FLOW (GPM)															
TIME															

DATE 2-2-1971

PAGE 45

TECHNICIAN Vic Mike

REMARKS

PRE-TEST (ALIGNED)

TEST - 2-7-71 (MISALIGNED)

CONT ON SHEET 45 BH NO. 44

38344617

DEC - 8 1971

ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

PHASE 3 PART 1

TEST DATA

BY	APPROVALS	REV 0 NO.
ISSUED		383HA617
DEC - 8 1971		CONT ON SHEET 46 SH NO. 45



# TABLE SCRAM DATA

TITLE **EARTHQUAKE CORE MISALIGNMENT**

TEST REQUEST **A-378-2**

DRIVE MODEL **ENG** S/N **880** ROD WT. (lb) **15**

COOLING PRESS (PSIG) **30** TEST SYSTEM **30** GP/AT **1.5** PSI **350**

SCRAM COUNTER

	CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBC TEMPERATURE (°F)	START OF MOTION SCRAM SIG. LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG. LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-GG	PU/PR ΔP MIDSTROKE (PSI)	PO/PR ΔP MIDSTROKE (PSI)	ACC. CHARGE (PSIG)
1	22	1535	70	70	70	147	247	300	425	870	1538	247	500	190	1570	11
2	22	1545	70	70	70	127	238	297	416	867	1518	226	510	188	1571	11
3	800	1570	61	65	61	130	295	390	620	1460	2658	440	20	720	1510	11
4	800	1555	61	65	61	132	298	380	615	1462	2672	442	20	700	1510	11
5	800	1605	61	65	61	135	290	400	620	1472	2700	450	20	700	1510	11
6	800	1610	61	65	61	152	387	528	852	1880	3324	512	230	650	1510	11
7	800	1625	61	65	61	158	384	532	866	1900	3340	520	225	650	1510	11
8	500	1230	466	466	83	130	266	326	497	1120	2136	360	160	320	1510	11
9	500	1245	466	466	95	130	266	336	503	1132	2170	365	140	340	1510	11
10	500	1250	465	465	128	180	550	790	1325	3085	5580	850	100	460	1510	11
11	500	1300	465	465	129	185	557	790	1310	3075	5550	830	100	460	1510	11
12	800	1250	510	510	100	135	295	388	615	1485	2665	447	0	695	1510	11
13	800	1300	510	510	115	140	300	397	613	1450	2644	443	0	680	1510	11
14	800	1305	510	510	145	156	400	530	845	1870	3175	445	490	700	1510	11
15	800	1315	510	510	165	153	390	530	815	1786	3073	440	400	690	1510	11
16	1030	1505	540	540	159	135	307	410	620	1322	2447	370	0	360	1510	11
17	1030	1510	540	540	147	138	308	410	610	1380	2448	372	0	350	1510	11

PAGE \_\_\_\_\_  
DATE **2-12-1971**  
BUENIAK/PARDO  
TECHNICIAN  
REMARKS

\*COLD HYDRO  
COLD VYRAM

REV 0  
3834617  
CONT ON SHEET 47 SH NO 46

# TABLE SCRAM DATA

TITLE EARTHQUAKE CORE MISALIGNMENT

DRIVE MODEL ENG SYN 880 ROD WT. (lb) 30"

COOLING PRESS (PSIG) 15 GPM AT 15 PSIG

TEST REQUEST A-378-2

SCRAM COUNTER

CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-06	PU/PR MIDSTROKE (PSI)	PO/PR MIDSTROKE (PSI)	ACCUM. CHARGE (PSIG)
----------------------	------------------------	------	------------------------------	--------------------------------	------------------------	---	---	--	--	--	--	----------------------------------	-----------------------	-----------------------	----------------------

1	1030	1515	540	540	174	.148	.337	.460	.700	.1510	.2570	.368	200	900	1650
18	1030	1525	540	540	200	.144	.325	.438	.685	.1475	.2538	.360	400	850	1650
19	1030	1530	540	540	200	.130	.303	.400	.610	.1350	.2390	.372	0	875	1510
20	1030	1540	540	540	195	.134	.310	.412	.616	.1352	.2390	.368	0	875	1510
21	1030	1545	540	540	207	.142	.314	.406	.615	.1353	.2386	.356	0	875	1510
22	24	1016	192	120	70	.150	.260	.310	.460	.230	.1632	.228	550	250	1570
23	24	1015	192	120	70	.130	.240	.300	.445	.920	.1610	.232	550	255	1570
24															

HOT

2-17-1971  
with sample 6 0930 = .25  
" " 1030 = .20  
" " 1130 = .20

2-18-1971  
with sample 6 0830 = .16  
" " 0930 = .18  
" " 1230 = .28  
" " 1330 = .26  
" " 1430 = .23  
" " 1530 = .28

2-10-1971  
with sample 6 0930 = .25  
" " 1030 = .23  
" " 1130 = .25

## TABLE

### LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE CORE MISALIGNMENT

TEST REQUEST A-378-2

DRIVE MODEL ENGS/N ~~100~~ 880

DATE 2-12-71

PRE-TEST

VIC & MIKE

SEAL LEAKAGE TEST PAR. 7.0													
INDEX TUBE	APPLIED PRESSURE		LEAK POINT								TOTAL LEAKAGE		
			P.O. PORT		COLLET		SPUD		VESSEL PORTS				
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN		ML/MIN		
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	
	EXTENDED	200 AT P.O.	200	N.A.	0	2650	740		1138	1040	758*	100	1880
RETRACTED	200 AT P.U.	200	758	60	1705	850		189	0	567	150	1050	
NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST													
VESSEL PORTS		P. U. PORT		COOLING ORIFICE LEAKAGE								ML/MIN	
				30 PSIG APPLIED @ P. U. RETRACTED, 1060/1703 ML/MIN SPEC.									

COLLET FRICTION PAR. B.1.							
	VESSEL PRESSURE psig	SPEC. MIN. psig	TRIAL				
			1 P. O. MIN. psig	2 P. O. MIN. psig	3 P. O. MIN. psig	4 P. O. MIN. psig	5 P. O. MIN. psig
0		70					

SETTLE FRICTION					
PAR. 8.2.1					
40 PSID MIN. W/10 psig MAX. VARIANCE					
NOTCH	VESSEL PSIG				
	22	22	500	500	500
48	47	44	45	49	50
46	47	46	46	50	50
44	45	43	45	48	49
42	45	42	44	48	48
40	44	44	44	48	49
38	44	42	44	48	49
36	44	42	44	48	48
34	42	41	44	48	48
32	43	42	43	48	48
30	43	43	42	48	48
28	42	42	42	48	48
26	42	42	42	49	48
24	42	42	42	48	48
22	42	42	42	48	48
20	40	42	42	47	47
18	40	41	43	47	47
16	40	41	43	48	48
14	40	42	42	48	48
12	40	42	42	47	48
10	40	42	42	47	48
08	41	42	43	48	48
06	42	42	44	47	48
04	42	42	44	47	48
02	41	43	42	46	49
00	44	45	46	50	50

100 - 3 1971

3834AL17

\* Col. 0.00 @ 8.0

CONT ON SHEET 49 SH NO. 48

# LEAKAGE & FRICTION DATA

## TABLE

## LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE CASE MISALIGNMENT

TEST REQUEST

A-378-2

DRIVE MODEL

ENG

S/N

880

DATE

2-18-1971

SEAL LEAKAGE TEST PAR. 7.0												
INDEX TUBE	APPLIED PRESSURE		LEAK POINT						TOTAL LEAKAGE			
			P.O. PORT		COLLET		SPUD				VESSEL PORTS	
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN			
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL		
	EXTENDED	200 AT P.O.			N.A.		2650		1138		758*	
RETRACTED	200 AT P.U.			758		1705		189		567		2460
*VESSEL PORTS		P. U. PORT		NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST						COOLING ORIFICE LEAKAGE		ML/MIN
30 PSIG APPLIED @ P. U. RETRACTED, 1060/1703 ML/MIN SPEC.												

COLLET FRICTION PAR. 8.1.									
TRIAL									
VESSEL PRESSURE PSIG	SPEC. MIN. PSIG	1		2		3		4	
		P. O. MIN. PSIG		P. O. MIN. PSIG		P. O. MIN. PSIG		P. O. MIN. PSIG	
0	70								

SETTLE FRICTION					
PAR. 8.2.1					
40 PSID MIN. W/10 PSIG MAX. VARIANCE					
NOTCH	VESSEL PSIG				POST TEST
	800	800	1030	1030	
48	45	42	42	41	52
46	44	42	44	43	53
44	44	42	43	42	53
42	43	42	43	42	52
40	43	42	43	42	52
38	44	42	42	41	52
36	44	41	42	42	52
34	44	41	42	41	52
32	44	41	42	41	52
30	44	41	42	41	51
28	43	41	42	41	52
26	43	41	42	42	52
24	43	41	42	42	52
22	43	41	42	41	51
20	43	41	42	41	51
18	43	41	42	41	50
16	43	41	42	41	50
14	43	41	42	41	50
12	43	41	42	41	50
10	43	42	42	42	50
08	43	42	42	43	50
06	43	42	43	43	50
04	43	42	43	43	50
02	43	42	42	43	50
00	46	44	43	45	52

2-18-1971

3834617  
CONT ON SHEET 50 SH NO. 49



## TABLE

## DRIVE DATA

TITLE EARTHQUAKE CORE MISALIGNMENTDRIVE MODEL EN-6S N 880

ROD WT. (lb)

TEST REQUEST A-378-2

COOLING PRESS (psig)

TEST SYSTEM 30"

GPM AT

PSIG

DATE 2-12-1971

PAGE

TECHNICIAN

BURMAN / BDO

REMARKS

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16																				
DATE		VESSEL PRESSURE (psig)		STEAM SPACE TEMPERATURE (°F)		VESSEL BOTTOM TEMPERATURE (°F)		PROBE TEMPERATURE (°F)		HCU SUPPLY PRESSURE UP P11/PR ΔP (psi)		PRESSURE UNDER PISTON DRIVING UP-P13/PR ΔP (psi)		PRESSURE OVER PISTON DRIVING UP-P12/PR ΔP (psi)		SPEED DRIVING UP (in/sec)		HCU SUPPLY PRESSURE DOWN -P11/PR ΔP (psi)		PRESSURE OVER PISTON DRIVING DOWN-P12/PR ΔP (psi)		PRESSURE UNDER PISTON DRIVING DOWN-P13/PR ΔP (psi)		SPEED DRIVING DOWN (in. sec)		DRIVE UP FLOW (GPM)		DRIVE DOWN FLOW (GPM)		STALL UP FLOW (GPM)		STALL DOWN FLOW (GPM)		TIME	
2-11-71	22	70	70	70	250	82	10	5000	253	230	98	4320	3.7	2.1	1.7	1.1	1430																		
2-11-71	22	70	70	70	250	80	9.5	4990	258	230	98	4300	3.8	2.1	1.7	1.2	1435																		
2-11-71	500	466	463	10.5	250	80	8	4880	240	230	102	41.54	3.8	2.5	2.6	1.6	1420																		
2-11-71	580	466	465	13.3	250	80	7.5	5078	256	240	103	41.20	3.9	2.2	2.2	1.3	1345																		
2-11-71	800	509	509	140	250	65	6	4860	253	248	97	39.40	4.1	2.8	2.4	1.4	1120																		
2-11-71	800	510	510	178	253	93	7	5040	270	240	112	4020	4.8	3.6	3.6	1.6	1340																		
2-11-71	1030	539	539	126	263	65	7.5	5060	275	245	95	39.26	4.7	3.4	3.4	1.4	1425																		
2-11-71	1030	539	539	126	260	65	7.5	51.73	263	240	95	39.85	3.9	2.6	2.6	1.6	1430																		
2-11-71	1030	540	540	150	260	60	7	5190	268	240	93	39.76	4	2.6	2.7	1.7	1600																		
2-11-71	23	121	177	68	250	83	7	5220	250	230	107	42.50	3.7	2	1.6	1.2	1020																		
2-11-71	23	121	177	68	250	83	7	5185	250	225	115	42.60	3.7	2.1	1.7	1.2	1030																		

1000 - 0 1075

CONT ON SHEET 51 BH NO. 50

38344617

AFTER HOT TEST

TABLE

LEAKAGE & FRICTION DATA

TITLE EARTHQUAKE CORE MISALIGNMENT TEST REQUEST A 378-2  
DRIVE MODEL ENG S/N 880 DATE 2-19-1971

LEAKAGE & FRICTION DATA

SEAL LEAKAGE TEST PAR. 7.0												
INDEX TUBE	APPLIED PRESSURE		LEAK POINT						TOTAL LEAKAGE			
			P.O. PORT		COLLET		SPUD		VESSEL PORTS		ML/MIN	
	PSIG		ML/MIN		ML/MIN		ML/MIN		ML/MIN			
	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL	SPEC.	ACTUAL		SPEC.	ACTUAL	
	EXTENDED	200 AT P.O.	200	N.A.	0	2650	1850	1138	1400	758*	150	4160
RETRACTED	200 AT P.U.	200	758	20	1705	1100	189	0	567	130	2460	1250
*VESSEL PORTS P. U. PORT			NOTE: PLUG COOLING WATER ORIFICE DURING LEAK TEST						COOLING ORIFICE LEAKAGE ML/MIN			
30 psig APPLIED @ P. U. RETRACTED, 1060/1703 ML/MIN SPEC.												

COLLET FRICTION PAR. 8.1.									
TRIAL									
VESSEL PRESSURE PSIG	SPEC. MIN. PSIG	1		2		3		4	
		P. O. MIN. PSIG		P. O. MIN. PSIG		P. O. MIN. PSIG		P. O. MIN. PSIG	
0	70								

SETTLE FRICTION									
PAR. 8.2.1									
40 PSID MIN. W/10 psig MAX. VARIANCE									
NOTCH	VESSEL PSIG								
48									
46									
44									
42									
40									
38									
36									
34									
32									
30									
28									
26									
24									
22									
20									
18									
16									
14									
12									
10									
08									
06									
04									
02									
00									

DEC - 8 1971

3835A617  
CONT ON SHEET 52 BH NO. 51



ENGINEERING FORM

TITLE

Evaluation of CRD Scram Characteristics Under Simulated Earthquake Conditions

PHASE 3 PART 2

TEST DATA

BY	APPROVALS	REV 0 NO.
ISSUED DEC - 8 1971		383HA617 CONT ON SHEET 53 SH NO 52

# TABLE

# SCRAM DATA

TITLE ERTINGURNE CORE MISALIGNMENT

TEST REQUEST R-378-3 01

DRIVE MODEL ENG S/N B80 ROD WT. (lb) \_\_\_\_\_

COOLING PRESS (PSIG) 25-15-30 TEST SYSTEM 30 GPM AT WORKING PSIG SCRAM COUNTER \_\_\_\_\_

CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG. LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-GG	PU/PR MIDSTROKE (PSI)	PO/PR MIDSTROKE (PSI)	VESSEL WATER CONDUCTIVITY-MEGOHM	REMARKS
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	015P
1	23	1420	69	69	69	.128	.232	.299	.432	.508	1.578	.250	480	270	.420	0.0
2	23	1426	69	69	69	.128	.238	.295	.430	.899	1.562	.260	480	270	.420	0.0
3	23	1618	69	69	69	.128	.230	.290	.424	.878	1.540	.260	500	270	.420	0.3
4	23	1625	69	69	69	.130	.230	.290	.430	.880	1.560	.260	500	270	.420	0.3
5	23	1030	69	69	69	.128	.238	.298	.425	.885	1.558	.275	480	260	.420	0.6
6	23	1036	69	69	69	.130	.240	.300	.480	.892	1.580	.280	480	265	.420	0.6
7	23	15.15	69	69	69	.122	.225	.281	.427	.910	1.604	.327	490	260	.420	0.9
8	23	15.22	69	69	69	.127	.230	.291	.492	.908	1.605	.312	490	260	.420	0.9
9	1030	1050	69	69	69	.130	.310	.413	.650	1.548	2.742	—	30	900	.420	0.9
10	1030	1105	69	69	69	.138	.308	.415	.648	1.535	2.692	—	30	900	.420	0.9
11	1030	1112	69	69	69	.130	.330	.442	.712	1.680	2.960	—	30	900	.420	0.9
12	1030	1115	69	69	69	.130	.330	.445	.708	1.680	2.808	—	30	900	.420	0.9
13	1030	1125	69	69	69	.145	.320	.423	.670	1.586	2.712	—	20	810	.420	0.9
14	1030	1130	69	69	69	.148	.300	.395	.642	1.621	2.689	—	20	730	.420	0.9
15	23	16.10	69	69	69	.132	.230	.289	.480	.934	1.768	.437	540	215	.420	1.2
16	23	16.15	69	69	69	.133	.236	.294	.440	.936	1.768	.430	550	210	.420	1.2
17	23	09.25	68	68	68	.140	.299	.404	.688	—	1.816	—	—	—	.420	1.2

ROLOWELL / BURMAN  
TECHNICIAN

PAGE 1  
DATE 5-16-71

REMARKS

015P  
0.0  
0.0  
0.3  
0.3  
0.6  
0.6  
0.9  
0.9  
0.9  
0.9  
0.9  
0.9  
0.9  
0.9  
0.9  
0.9

CONT. ON SHEET \_\_\_\_\_  
REV. NO. \_\_\_\_\_  
REV. NO. \_\_\_\_\_

1791-C-1971

SCRAM DATA

TEST REQUEST A-378-3

ROD WT. (lb)

GPMAT

ALMA COHEN

PAGE 2

DATE 5-18-71 +

TECHNICIAN

REMARKS

<div style="display: flex; justify-content: space-between;"> <div> <p>PAGE <u>2</u></p> <p>DATE <u>5-18-71</u> +</p> </div> <div> <p>TECHNICIAN _____</p> <p>REMARKS _____</p> </div> </div>															
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG. LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG. LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-66	PU/PR MIDSTROKE (PSI)	PO/PR MIDSTROKE (PSI)	VESSEL WATER CONDUCTIVITY—(MEGOHM)
18	480	0935	69	69	69	141	311	430	749	2469	2648		5	880	420
19	480	0938	69	69	69	140	305	419	688	1996	3269		5	945	420
20	23	1412	69	69	69	150	242	300	438	905	1580	272	480	260	420
21	23	1415	69	69	69	140	240	305	432	892	1570	240	480	270	420
22	480	1605	69	69	69	150	308	413	783		1957				420
23	480	1610	69	69	69	148	326	452			1732				430
24	480	1615	69	69	69	139	316	435			1736				430
25	800	1617	69	69	69	143	303	404	770		1970				430
26	800	1620	69	69	69	153	400	628							430
27	900	1622	69	69	69	151	362	531							430
28	1030	1625	69	69	69	139	339	488							430
29	23	0935	69	69	69	143	252	308	467	1048	1907	280	460	265	440
30	23	1315	69	69	69	128	236	296	433	897	1573	280	460	265	440
31	23	1320	69	69	69	132	241	299	433	893	1578	284	460	260	440
32	23	1545	69	69	69	132	237	296	423	885	1591	326	485	260	430
33	23	1555	69	69	69	132	236	293	433	902	1644	340	470	265	420
34	800	12.30	509	511	89	142	306	396	624	1641	2740		6	700	410

28333555

CONT. ON SHEET 5

5-18-71

1761 8 - 321

234547

0

# TABLE SCRAM DATA

TITLE EARTHQUAKE CORE MISALIGNMENT

TEST REQUEST A-378-4

DRIVE MODEL EAG SN 880 ROD WT. (lb) 15

COOLING PRESS (PSIG) 30" TEST SYSTEM 15 GPMAT

SCRAM COUNTER

PAGE 3

DATE 5-18-71

TECHNICIAN

REMARKS

SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG. LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG. LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-GG	PU/PR MIDSTROKE (PSI)	PO/PR MIDSTROKE (PSI)	VESSEL WATER CONDUCTIVITY (MEG OHM)
1															
35	800	12:35	509	511	120	.138	.291	.389	.615	1.618	2.786		10	690	.410
36	800	12:40	509	511	117	.146	.393	.539	.869	2.056	3.321		VESSEL	710	.410
37	800	12:45	509	511	160	.152	.379	.529	.846	2.045	3.411		VESSEL	710	.410
38	900	13:05	523	526	85	.132	.307	.405	.653	1.536	2.765		10	750	.410
39	900	13:10	523	526	103	.135	.308	.406	.661	1.561	2.834		50	790	.410
40	900	13:15	523	525	126	.141	.356	.483	.782	1.809	3.097		VESSEL	800	.410
41	900	13:20	523	525	142	.139	.346	.471	.761	1.798	3.036		VESSEL	800	.410
42	1030	13:35	545	545	109	.123	.307	.402	.630	1.451	2.732		30	875	.410
43	1030	13:40	545	545	148	.132	.308	.403	.634	1.463	2.695		30	875	.410
44	1030	13:45	545	546	162	.142	.331	.448	.704	1.570	2.911		VESSEL	900	.410
45	1030	13:50	545	546	172	.126	.323	.433	.685	1.562	2.769		VESSEL	875	.410
46	23	13:40	157	98	73	.148	.252	.308	.443	.923	1.643	320	510	300	.410
47	23	13:50	157	98	73	.129	.243	.300	.452	.948	1.682	318	510	340	.410
48															

\* DO-09

\* DO-09

\* PU-08

\* PU-07

\* PU-07

\* PU-07

\* PU-07

DO-06

DO-06

DO-05

DO-06

5-8-1971

REV NO 0  
383 HAG 17  
CONT ON SHEET 56 SH NO 55



# TABLE SCRAM DATA

TITLE EARTHQUAKE CORE MISALIGNMENT

TEST REQUEST A-378-5

DRIVE MODEL ENG S/N 880 ROD WT. (lb) 30"

COOLING PRESS (PSIG) 30" TEST SYSTEM 30" GPM AT PSIG SCRAM COUNTER

CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG. LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG. LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG. LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG. LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG. LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG. LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-00	PU/PR MIDSTROKE ΔP (PSI)	PO/PR MIDSTROKE ΔP (PSI)	NA Paschman	H <sub>2</sub> O changed
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	
48	23	1357	67	67	67	.149	.251	.312	.439	.914	1.600	.295	500	240	563	
49	23	1404	67	67	67	.132	.238	.293	.433	.914	1.596	.298	500	280	563	
50	800	0855	69	69	69	.143	.277	.357	.588	1.994	2.112		110	850	710	
51	800	0905	69	69	69	.148	.271	.353	.582	2.099			110	860	710	
52	900	0915	69	69	69	.151	.281	.373	.624		1.993				710	
53	900	0920	69	69	69	.141	.278	.371	.618		1.912				710	
54	1030	0925	69	69	69	.134	.295	.397	.712		1.320				710	
55	1030	0930	69	69	69	.142	.292	.384	.668		1.510				710	
56	800	0948	69	69	69	.148	.261	.326	.510	1.340	1.995		180	790	873	
57	800	0954	69	69	69	.144	.259	.323	.513	1.352	2.081		200	820	875	
58	900	1000	69	69	69	.138	.258	.335	.523	1.508	1.956		125	950	875	
59	900	1005	69	69	69	.141	.261	.336	.525	1.535	2.038		120	950	875	
60	1030	1300	68	68	68	.142	.265	.349	.564		1.738				875	
61	1030	1305	68	68	68	.140	.267	.348	.561		1.738				875	
62	1030	1320	68	68	68	.138	.314	.438	.941						564	
63	1030	1325	68	68	68	.144	.317	.456	1.006						564	
64	1030	0845	68	68	68										564	

PAGE 4

DATE 6-3-71

TECHNICIAN

REMARKS

DEC - 8 1971

CONT ON SHEET 57

3807A617

5 Deflection

## SCRAM DATA

4-378-5

# TITLE EARTHQUAKE CORE MISALIGNMENT

ENGINE SN 880 ROD WT. (lb)

SHIRAZ MODEL 30" 35" 51

CPM AT PSIG

SCRAM COUNTER

PAGE 5

DATE 6-3-71 +

TECHNICIAN

REMARKS

1.5 Bow	1.5 Deflection
1.5 Bow	1.5 Deflection
1.5 Bow @ D.O. of 38	5.0 Deflection
1.5 Bow @ D.O. of 38	5 Deflection
1.5 Bow @ D.O. of 38	5 Deflection
1.5 Bow D.O. of 38	6.25 Deflection
1.5 Bow D.O. of 38	6.25 Deflection
1.5 Bow D.O. of 38	5 Deflection
1.5 Bow D.O. of 38	5 Deflection
1.5 Bow D.O. of 38	(0) Deflection
1.5 Bow D.O. of 38	(0) Deflection

CUMULATIVE SCRAM (#)	VESSEL PRESSURE (PSIG)	TIME	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	START OF MOTION SCRAM SIG LOSS TO DO-48 (sec)	5% STROKE-SCRAM SIG LOSS TO DO-45 (sec)	10% STROKE-SCRAM SIG LOSS TO DO-43 (sec)	20% STROKE-SCRAM SIG LOSS TO PU-38 (sec)	50% STROKE-SCRAM SIG LOSS TO DO-24 (sec)	90% STROKE-SCRAM SIG LOSS TO DO-05 (sec)	BUFFER TIME (sec) DO-03 TO DO-GG	PU/PR MIDSTROKE VP (PSI)	PO/PR MIDSTROKE VP (PSI)	H <sub>2</sub> O CHARGE
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
65	1030	0852	68	68	68										1510
66	1030	0858	68	68	68										1510
67	1030	0905	68	68	68	140	323	396	971		1113				1510
68	1030	0910	68	68	68	138	312	448	970		1173				1510
69	1030	0920	68	68	68	140	321	443	1010		1116				1510
70	1030	0925	68	68	68	139	313	442	973						1510
71	1030	0930	68	68	68	140	320	449	964		1108				1510
72	1030	0935	68	68	68	139	312	446	939		1068				1510
73	1030	0945	68	68	68	139	314	437	905		1017				1510
74	1030	0950	68	68	68	134	308	439	973		1100				1510
75	1030	0955	68	68	68	140	316	445	968		1089				1510

CEC - B 1971

3834 A617

CONT ON SHEET 58 SH NO. 57



## TEST REMARKS SHEET

PAGE 1 OF     

EARTHQUAKE CORE

PROJECT MISALIGNMENTSPECIFICATION NO.                     SPEC. SECTION NO.                     TR NO. A-378-3SUPPLEMENT NO. 3TEST LOCATION 30"EQUIPMENT                                     S/N #880MODIFICATIONS:                                     COOLING WATER DRIVING TESTSPURPOSE: TO DETERMINE PSIG REQUIRED TO MOVE CRD

REMARKS: <u>                                    </u>								DISP
RUN#	POS	48R	48	36	24	12	02	<del>00</del>
1	PRESS	78	78	80	80	84	82	0.0
2		78	78	80	80	82	80	0.0
1		84	85	92	94	93	92	0.3
2		97	97	90	90	89	90	0.3
1		75	77	85	85	88	145	0.6
2		73	75	85	83	87	142	0.6
1		75	78	112	117	150	290	0.9
2		75	79	120	130	140	310	0.9
1		75	74	75	76	79	125	0.6 REPEAT
2		74	76	79	77	78	125	0.6 REPEAT
1		74	74	80	77	80	130	0.6 <sup>2nd</sup> REPEAT
2		70	70	78	77	80	129	0.6 <sup>1st</sup> REPEAT

DEC - 8 1971

REV  
NO. 0

388 HALL

LOCATION ON SHEET 59

BY NO. 58

TEST OPERATOR HOLLOWELLDATE 5/6-71APPROVED                     DATE

## TABLE

## LEAKAGE &amp; FRICTION DATA

P. 2

TITLE EARTH QUAKE CORE MISALIGNMENT TEST REQUEST 378-5  
 DRIVE MODEL ENG. S/N 880 DATE 6-3-71

PAR. 8.2.1

40 PSID MIN. W/10  
psig MAX. VARIANCE

## COOLING TEST

NOTCH	1.2 DISPLACEMENT VESSEL PSIG				
	1	2	1.5 Bow PSI	.9	.9
	PSI	PSI	PSI	PSI	PSI
48	76	88	75	74	78
46	78	78	95	76	78
44	95	87	105	78	80
42	115	145	160	78	83
40	150	160	260	85	86
38	195	185	295	95	95
36	195	220	325	100	100
34	195	225	310	110	105
32	192	225	310	110	105
30	195	210	310	110	110
28	190	210	300	110	110
26	190	210	300	105	110
24	210	200	230	105	107
22	225	205	330	103	100
20	205	205	340	92	90
18	190	200	360	90	88
16	210	180	415	85	84
14	245	280	505	100	98
12	265	265	585	135	130
10	340	320		175	168
08	380	385		215	200
06	415	440		260	230
04	440	430		275	260
02	470	480		345	285
00	—	—		255	250

PAR. 8.2.1

PAR. 8.2.1

COOLING WATER DRIVING  
TESTS

40 PSID MIN. W/10  
psig MAX. VARIANCE

40 PSID MIN. W/10  
psig MAX. VARIANCE

## Cooling Test

NOTCH	.9 .9 VESSEL PSIG .9				DATE		DISPLACEMENT VESSEL PSIG			
	1	2	3	4	6-3	6-3	1.2	1.2	EXPANDED FROM SH-1	EXPANDED FROM SH-1
	PSI	PSI	PSI	PSI	PSI	PSI	PSI	PSI		
48	82	78	80	78	82	83			78	79
46	80	78	82	81	83	83			80	85
44	83	82	83	83	85	84			80	85
42	83	82	82	83	86	87			85	95
40	85	85	87	92	86	87			95	100
38	92	91	99	110	85	86			105	110
36	98	96	105	116	85	86			112	120
34	110	105	107	115	85	85			120	125
32	120	118	116	115	85	85			120	130
30	118	112	111	110	84	86			130	125
28	128	120	119	112	85	86			125	130
26	118	115	108	114	85	86			120	130
24	110	105	105	112	86	86			117	130
22	103	98	101	102	85	86			115	115
20	95	91	85	99	85	86			100	105
18	88	91	83	90	86	87			95	100
16	85	86	83	82	86	87			95	100
14	97	90	93	88	86	87			120	180
12	130	115	104	125	87	87			150	140
10	145	135	140	160	87	87			200	190
08	215	200	202	212	87	87			230	230
06	245	235	230	250	87	88			255	260
04	290	250	265	265	89	89			285	290
02	280	270	260	265	87	87			290	310
00					86	89				

DEC - 8 1971

3834617

CONT ON SHEET 60 SH NO. 59

## TABLE

## LEAKAGE &amp; FRICTION DATA

TITLE EARTHQUAKE MISALIGNMENTTEST REQUEST A 3783445DRIVE MODEL ENGS/N 880DATE 5-25-71 THRU 6-2-71

SETTLE FRICTION						SETTLE FRICTION						SE	SETTLE FRICTION					
PAR. 8.2.1						PAR. 8.2.1							PAR. 8.2.1					
40 PSID MIN. W/10 psig MAX. VARIANCE						40 PSID MIN. W/10 psig MAX. VARIANCE						40 PS	40 PSID MIN. W/10 psig MAX. VARIANCE					
													DATE					
N O T C H	VESSEL PSIG					REPEAT	VESSEL PSIG					0.9	VESSEL PSIG					
	0.0	0.3	0.6	0.9	1.2	0.6	1.5	2.6	2.9	0.9	23 PSI	6-3	DISPLACEMENT					
	23	23	23	23	23	23	23	23	23	1030		0.0						
48	47	47	49	47	49	48	49	47	48	52	50	46						
46	47	48	49	48	48	48	28	47	48	53	51	46						
44	46	47	48	47	28	46	DID NOT SETTLE	47	47	53	51	45						
42	46	46	48	38	DID NOT SETTLE	46		47	47	52	46	46						
40	46	46	48	28		46		47	43	46	38	45						
38	46	47	48	20		46		47	33	38	30	46						
36	46	47	46	18		44		46	27	28	21	46						
34	46	46	46	DID NOT SETTLE		44		46	24	23	16	46						
32	46	46	47	12		44		46	23	19	18	45						
30	46	46	47	DID NOT SETTLE		44		46	20	18	12	46						
28	45	46	47	9		45		46	21	14	19	46						
26	45	46	47	DID NOT SETTLE		44		46	21	20	16	45						
24	45	46	47	DID NOT SETTLE		45		46	23	27	23	45						
22	44	45	46	16		44		46	28	33	30	45						
20	44	45	47	32		45		45	35	40	48	46						
18	44	45	46	36		44		45	38	44	49	44						
16	44	45	46	38		44		45	42	50	50	43						
14	44	45	46	21		44		45	30	40	37	43						
12	44	44	44	DID NOT SETTLE		43		44	8	10	9	42						
10	44	45	38			42		36	-	-	-	43						
08	44	45	24			34		24				44						
06	44	44	13			26		14				44						
04	44	44	5			18		4				44						
02	43	43	28			08						44						
00	46	47	-			DID NOT SETTLE						47						

383HA617

DEC - 8 1971

CONT ON SHEET 61 SH NO. 60

### DRIVE DATA

TITLE EARTHQUAKE CORE MISALIGNMENT

TEST REQUEST A-378-3

DRIVE MODEL FA/B S/N BB0  
COOLING PRESS (PSIG) 45 ± 30 TEST SYSTEM 30"

ROD WT. (lb) \_\_\_\_\_

- ps16

DATE 5-16-71

PAGE

TECHNICIAN

WORKSHEET / BUBBLES

REMARKS

DATE 5-16-71																TECHNICIAN		REMARKS																	
PAGE 1																HOLLOWELL/GRUBMAN																			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	DISE																			
DATE		VESSEL PRESSURE (psig)		STEAM SPACE TEMPERATURE (°F)		VESSEL BOTTOM TEMPERATURE (°F)		PROBE TEMPERATURE (°F)		HCU SUPPLY PRESSURE UP P11/PR ΔP (psi)		PRESSURE UNDER PISTON DRIVING UP-P13/PR ΔP (psi)		PRESSURE OVER PISTON DRIVING UP-P12/PR ΔP (psi)		SPEED DRIVING UP (in./sec)		HCU SUPPLY PRESSURE DOWN -P11/PR ΔP (psi)		PRESSURE OVER PISTON DRIVING DOWN-P12/PR ΔP (psi)		PRESSURE UNDER PISTON DRIVING DOWN-P13/PR ΔP (psi)		SPEED DRIVING DOWN (in./sec)		DRIVE UP FLOW (GPM)		DRIVE DOWN FLOW (GPM)		STALL UP FLOW (GPM)		STALL DOWN FLOW (GPM)		TIME	
5-16	23	61	61	61	247	77	11.0	47.0	250	235	105	41.2	38	15	1405	0.0																			
5-16	23	61	61	61	248	76	11.0	47.0	250	235	105	41.2	38	15	1410	0.0																			
5-16	23	69	69	69	250	80	11.0	46.6	250	240	105	41.2	39	14	1610	0.3																			
5-16	23	69	69	69	250	80	11.0	46.8	250	240	105	41.2	38	14	1615	0.3																			
5-17	23	69	69	69	248	80	12.0	48.7	250	240	105	45.0	39	15	1015	0.6																			
CHANGE IN DRIVE PRESS. AND FLOW 250-270 80-105 12-8																																			
* OCCURRED PISTON DRIVE PRESS. CHANGES TOOK PLACE PRO 1 POS 13 TO 00 RND 02-12																																			
5-17	23	69	69	69	248	77	11.0	49.0	242	230	103	44.2	38	14	1020	0.6																			
Range from 90 to 00 RND 02-12																																			
5-18	23	69	69	69	263	125	10.8	83.1	268	260	65	11.5	14	0.3																					
Range from 90 to 00 RND 02-12																																			
5-18	23	69	69	69	270	122	10	71.0	272	265	70	11.5	14	0.3																					
Range from 90 to 00 RND 02-12																																			
No	PRIVE	4.2 0.15																																	
5-20	23	69	69	69	260	75	11.0	45.4	240	230	102	46.9	38	14	1340	0.6	REPEAT																		
Range from 90 to 00 RND 02-12																																			
5-20	23	69	69	69	258	75	11.0	45.8	240	230	101	45.0	38	13	0.9																				
Range from 90 to 00 RND 02-12																																			

Pressure started Dropping for (C) 8000 PSI

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

0.6

<

1761 8 - 377

Pressure Statist Drinking  
K<sub>2</sub>(O) 800 PSI

5



## TABLE

## DRIVE DATA

TITLE EARTHQUAKE CORE MISALIGNMENTTEST REQUEST A-378-3 +4DRIVE MODEL ENGS/N BDOROD WT. (lb) 1.2GPM AT 1.2

PSIG

COOLING PRESS (PSIG)

TEST SYSTEM 30"GPM AT 1.2

PSIG

DATE 5-21-71PAGE 1

TECHNICIAN


MCKINLEY/BOBEN/ARK

REMARKS

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16		
DATE	VESSEL PRESSURE (psig)	STEAM SPACE TEMPERATURE (°F)	VESSEL BOTTOM TEMPERATURE (°F)	PROBE TEMPERATURE (°F)	HCU SUPPLY PRESSURE UP PIL/PR ΔP (psi)	PRESSURE UNDER PISTON DRIVING UP-P13/PR ΔP (psi)	PRESSURE OVER PISTON DRIVING UP-P12/PR ΔP (psi)	SPEED DRIVING UP (in./sec)	HCU SUPPLY PRESSURE DOWN -PIL/PR ΔP (psi)	PRESSURE OVER PISTON DRIVING DOWN-P12/PR ΔP (psi)	PRESSURE UNDER PISTON DRIVING DOWN-P13/PR ΔP (psi)	SPEED DRIVING DOWN (in./sec)	DRIVE UP FLOW (GPM)	DRIVE DOWN FLOW (GPM)	STALL UP FLOW (GPM)	STALL DOWN FLOW (GPM)	TIME
5-21 21	23	69	69	69	260	75	11.0	47.1	250	230	100	44.8	3.7	1.3	1.3	0.9	13:05
					260	75	11.0		260	230	100		3.7	1.3	1.3	0.9	
5-21	23	69	69	69	260	75	11.0	47.8	250	230	100	45.0	3.7	1.3	1.3	0.9	13:10
					260	75	11.0		260	230	100		3.7	1.3	1.3	0.9	
5-21	23	69	69	69	270	110	9.0	71.6	250	250	75	48.4	3.4	1.2	1.3	0.9	15:30
					270	110	9.0		250	250	75		3.4	1.2	1.3	0.9	
5-21	23	69	69	69	270	107	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	107	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270	105	9.0		250	230	70		3.4	1.2	1.4	0.9	
5-21	23	69	69	69	270	105	9.0	69.06	250	230	70	48.4	3.4	1.2	1.4	0.9	15:40
					270												







cc: N. J. Biglieri  
J. F. Cage, Jr.  
J. J. Gallagher  
K. J. Jamrus  
L. K. Liu  
P. E. Moore  
F. F. Smith, Jr.  
L. E. Suggs  
S. W. Tagart  
D. A. Venier  
R. E. Williams  
H. E. Williamson

July 28, 1970

Subject: Test Procedure for Core Misalignment Test PEP RC-10, 1970

To: S. W. Smith  
M/C 711

Ref. Above subject test procedure, S. W. Smith, July 14, 1970.

This letter provides the basic core misalignment information required for the above reference testing.

REF LETTER TO J.S. WILEY  
FROM F.E. COOKE MAR - 17, 1970

During the first scram testing phase, the blade should have 500 lb. excess weight above normal. This is to demonstrate that the blade can be inserted without stalling during quake lateral loading. For this first phase, scram speed should be determined with the core plate, upper guide and fuel channels displaced relative to the upper end of the control drive housing by the maximum amounts shown on Drawing 731E849. This drawing shows the possible misalignment effects due to component and installation tolerances combined with reactor assembly differential thermal expansion and pressure effects.

The next testing phase should simulate the effects of shroud rotation about its supports during quake loading conditions together with the effects of control drive housing dynamic behavior during quake loading conditions. For this phase, scram speeds should be determined with normal blade weight and with the core plate and upper guides displaced horizontally an additional 0.2 and 0.6 inch respectively to that shown on Drawing 731E849. The core plate and upper guide move together in the same direction.

The effect on scram speed should be checked by initially deflecting the flange end of the control drive housing and releasing it to simulate quake dynamic effects (this is similar to the tests reported in APED-4853).

The final testing phase should include scram speed determinations with normal misalignment and blade weight but with the midpoint of the fuel channel bowed in progressive increments to a limit of 1 1/2 inches (with the ends simply supported). The four channels surrounding the blade should be uniformly deflected together by jacking or tensioning them. This test is to simulate fuel channel loadings up to the channel yield collapse strength limit at operating temperature.

*F. E. Cooke*  
F. E. Cooke  
Reactor Assembly  
M/C 743

REF LETTER TO I.R. KOBZA FROM F.E. COOKE  
MARCH 6, 1970

dw

DEC - 8 1971

REF NO.	0
3834A617	
CONT ON SHEET	66 SH NO. 65

May 12, 1970

cc: I.R. Fobba  
R.E. Williams  
P.F. Cooke

J. Fritz  
M/C 135

Replying to your question about misalignment of top guide and core support plates for use in your test program, I have the following comments:

Recent vendors deviations have caused us to establish what is the maximum amount of variance from true position that we will accept. This study has shown that the total amount of offset between top guide and core support plate will be limited to .093 inch. Further offsets can be expected as shown below.

.008 Top Guide master hole selection tolerance

.008 Core Plate master hole selection tolerance

.015 Field alignment tolerance of top guide to core plate.

Total .031

Therefore, the total offset between the top guide and the core support plate due to manufacturing deviations and field installation tolerances could be 0.124 inch.

Misalignment due to C.P.D. penetrations deviating from true position could cause an additional .060" misalignment.

I further suggest that for a more detailed criteria on misalignments, refer to APED 4835, titled "Locking Piston Control Rod Drive Design Evaluation Tests", in particular, Page A-9 which shows the resulting drive friction on pounds resulting from various misalignments. For this test, the offset was as high as 133% of design criteria, which resulted in a misalignment of the guide tube from true vertical position of 7/8" over a 17 foot length, or an angle of offset of the guide tube equal to 0° 15'. This should be applicable to your test, and would serve as a comparison of the old design and the new design.

R. J. Murkowski  
Reactor Assembly  
M/C 743

/bh

DEC - 8 1971

REV NO.	0
383HA617	
CONT ON SHEET	67
SH. NO.	66

CHECK ONE:

PAGE 1 OF 3☒ Test RequestTEST REQUEST☐ SupplementTest Request Number A-378 Supplement Number \_\_\_\_\_Equipment EARTHQUAKE CORE MISALIGNMENT P/N \_\_\_\_\_ S/N \_\_\_\_\_Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. Q5475

## PURPOSE:

To determine screen characteristics under different conditions of core misalignment and earthquake induced deflections.

~~RECOMMENDATION~~ TEST EQUIPMENT:

- 1) Drive - - - - S/N 880
- 2) Index Tube - - S/N 540
- 3) Piston Tube - - S/N 442
- 4) Collet - - - -

## TEST PROCEDURE:

- NOTES: 1) The cognizant engineer must be present during all testing.  
2) Record all data during testing.

PHASE I1) Additional Equipment Required:

- A) Modified control blade (750 lb total weight)
- B) Modified fuel support casting
- C) Retaining plate for fuel bundles

2) Test Facility Modifications:

- A) Remove fuel bundles, fuel support casting and the control blade.
- B) Install the modified control blade. (Use extreme caution when handling this blade; it weighs 750 lbs.)
- C) Install the modified fuel support casting oriented such that the open rods are in line with the square weights on the modified control blade.
- D) Install two fuel assemblies and attach the retaining plate.

3) Inspect Drive:

- A) Carefully inspect the collet, noting the condition prior to testing. Pay particular attention to the collet fingers.
- B) Inspect the notches on the index tube and note any chipped notches. Measure the bow of the index tube.
- C) Inspect all inner surfaces that can come into contact with the index tube and verify that the surfaces are clean and free of defects. Pay particular attention to the type of defect which could be caused by rubbing against the index tube.

Requestor S. SmithDate 2/24/76Approved [Signature]Date 2/24/76

DEC 2 1976

3834A617
CONT ON SHEET 68 SH NO. 67

CHECK ONE:

☒ Test Request

☐ Supplement

## TEST REQUEST

PAGE 2 OF 3

Test Request Number A-378

Supplement Number \_\_\_\_\_

### EARTHQUAKE CORE MISALIGNMENT

Equipment \_\_\_\_\_ P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. 05475

PURPOSE:

MODIFICATIONS:

TEST PROCEDURE:

- D) Inspect the spud being sure the fingers are straight and not damaged.
- 4) Assemble and leak check the drive.
- 5) Install the Drive in the Vessel:
  - A) When coupling the drive, be very careful so the spud doesn't hit the heavy blade too hard.
  - B) Be sure no interferences exist in the drive line -- the weights on the blade must clear during the entire stroke.
  - C) The settle circuit should be set so the drive will settle very slowly.
- 6) Do 2 (two) full stroke drive traces (drive in only).

NOTE: For all screen testing the system will be set up as follows:

- A) Accumulator charge = 575/1510
  - B) Inlet line loss = 330 psi @ 108 GPM (cold)
  - C) Discharge line loss = 248 psi @ 29.6 GPM (cold)
  - D) Screen valve down pressure = 100 psi
  - E) All vessel temperatures are the saturation temperatures at the specified pressure.
- 7) Do 2 (two) full stroke screens at ambient pressure.
  - 8) Do 1 (one) drive in trace at ambient pressure.
  - 9) Do 1 (one) drive in trace at 1030 psi
  - 10) Do 5 (five) full stroke screens at 1030 psi.
  - 11) Do 1 (one) drive in trace at 1030 psi.

Requestor \_\_\_\_\_ Date \_\_\_\_\_ Approved \_\_\_\_\_

DEC - 8 1971

REV NO	0	Date	
383HA617			
CONT ON SHEET 69 SH NO. 68			



CHECK ONE:

☒ Test Request

☐ Supplement

## TEST REQUEST

PAGE 3 OF 3

Test Request Number A-576 Supplement Number \_\_\_\_\_

Equipment EARTHQUAKE CORE MISALIGNMENT P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. 03475

PURPOSE:

MODIFICATIONS:

### TEST PROCEDURE:

- 12) Do 2 (two) vessel screws at 1030 psi (full stroke).
- 13) Do 1 (one) drive in trace at 1030 psi.
- 14) Do 1 (one) drive in trace at 800 psi.
- 15) Do 2 (two) full stroke screws at 800 psi.
- 16) Do 1 (one) drive in trace at 800 psi.
- 17) Do 1 (one) drive in trace at ambient pressure.
- 18) Do 2 (two) full stroke screws at ambient pressure.
- 19) Do 1 (one) drive in trace at ambient pressure.
- 20) Remove drive and leak check.
- 21) Disassemble and inspect drive.

DEC - 8 1979

REV NO.	0
383HA617	
CONT ON SHEET	70
SH NO.	69

Requestor \_\_\_\_\_ Date \_\_\_\_\_ Approved \_\_\_\_\_ Date \_\_\_\_\_

CHECK ONE:

☐ Test Request

☒ Supplement

## TEST REQUEST

PAGE 1 OF 3

Test Request Number A-378 Supplement Number 1

Earthquake Core

Equipment Misalignment P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. 05475

### PURPOSE:

To determine any effects on screws of maximum expected core misalignment due to fabrication and installation tolerances.

### MODIFICATIONS:

Misalign 30" vessel per attached sketch.

### TEST PROCEDURE:

#### TEST EQUIPMENT

- 1) Drive
- 2) Index Tube
- 3) Piston Tube
- 4) Blade
- 5) Guide Tube
- 6) Dummy Bundles

#### NOTES:

- 1) The cognizant Engineer must be present during all testing.
- 2) The data to be recorded are the normal parameters related to ship, drive and screw functions. There are no special parameters to be recorded. Record all data during testing.

#### PHASE II

- 1) Inspect components paying particular attention to any defects that may have been caused by rubbing of the moving components.
  - A) Inspect guide tube.
  - B) Inspect Fuel bundles.
  - C) Inspect blade.

DEC - 8 1971

REV NO.	0
383HA617	
CONT ON SHEET	71
SH NO.	70

Requestor \_\_\_\_\_ Date \_\_\_\_\_ Approved \_\_\_\_\_ Date \_\_\_\_\_

2.

2) Inspect drive.

- A) Inspect the index tube paying particular attention to any condition that could be caused by rubbing during operation.
- B) Inspect all inner surfaces of the drive that can come into contact with the index tube and verify that the surfaces are clean and free of defects, paying particular attention to the type of defect which could be caused by rubbing against the index tube.

3) Assemble and leak check the drive.

4) Install the drive in the vessel and set up the 30" system for normal drive operation.

NOTE:

For all scram testing, the system will be set up as follows unless otherwise indicated:

- A) Accumulator Charge = 1510/575
- B) Inlet line loss = 350 psi @ 108 GPM (cold)
- C) Discharge line loss = 248 psi @ 29.6 GPM (cold)
- D) Scram valve dome pressure = 100 psi
- E) All vessel temperatures are the saturation temperatures at the specified pressure.

PERFORM TESTING AS LISTED BELOW

Ambient Pressure

- 1) Two full stroke drive traces (in and out)
- 2) One jog trace (in and out)
- 3) One settle friction trace
- 4) Two full stroke scrams
- 5) One settle friction trace

500 psi

- 6) One drive trace (in and out)
- 7) One settle friction trace
- 8) Two full stroke scrams
- 9) Two full stroke vessel scrams
- 10) One settle friction trace
- 11) One drive trace (in and out)

DEC - 8 1971

REV	0
NO.	3834A617
CONT. IN SHEET	72
REV.	71

3.

800 psi

- 12) One drive trace (in and out)
- 13) One settle friction trace
- 14) Two full stroke scrams
- 15) Two full stroke vessel scrams
- 16) One settle friction trace
- 17) One drive trace (in and out)

1030 psi

- 18) One drive trace (in and out)
- 19) One settle friction trace
- 20) Five full stroke scrams
- 21) Two full stroke vessel scrams
- 22) One settle friction trace
- 23) One drive trace (in and out)

Ambient Pressure

- 24) One settle friction trace
- 25) Two full stroke scrams
- 26) Two full stroke drive trace (in and out)
- 27) One full stroke jog trace (in and out)
- 28) Remove and leak check drive
- 29) Disassemble and inspect drive noting any conditions different from that at the beginning of the test. Refer. Steps 1 and 2.
- 30) Remove and inspect fuel bundles
- 31) Remove and inspect blade

NOTE: 500, 800 and 1030 psi testing may be deleted if no significant effects are seen at ambient pressure.


DEC - 8 1971

REV NO	0
383HA617	
CONT ON SHEET	73
SN NO.	22

Nuclear Energy Division  
ENGINEERING CALCULATION SHEET

DATE \_\_\_\_\_  
SHOP ORDER NO. CORE MISALIGNMENT - TRA-378  
SUBJECT \_\_\_\_\_ BY S. SMITH SHEET 1 OF 1

MAXIMUM CORE MISALIGNMENT DUE  
TO INSTALLATION AND FABRICATION  
TOLERANCES



- 1) LETTER TO J. FRITZ  
FROM R.J. MURKOWSKI  
DATED 5/12/1970.
- 2) DRAWING 731E B49  
ZONE C-13

DEC - 8 1971

REV NO	0
3834A617	
CONT ON SHEET	74
SH NO.	73



CHECK ONE:

☐ Test Request

☒ Supplement

## TEST REQUEST

PAGE 1 OF 3

Test Request Number A-378 Supplement Number 2

Equipment Earthquake Core Misalignment P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. 05475

### PURPOSE:

To determine any effects on screen of maximum expected core misalignment due to fabrication and installation tolerances plus earthquake induced deflections of the core plate and top guide.

### MODIFICATIONS:

Misalign the 30" vessel per attached sketch.

### TEST PROCEDURE:

#### TEST EQUIPMENT

- 1) Drive
- 2) Index Tube
- 3) Piston Tube
- 4) Blade
- 5) Guide Tube
- 6) Dummy Bundles

#### NOTES:

- 1) The cognizant Engineer must be present during all testing.
- 2) The data to be recorded are the normal parameters related to shim, drive and screen functions. There are no special parameters to be recorded. Record all data during testing.

#### PHASE III

- 1) Inspect components paying particular attention to any defects that may have been caused by rubbing of the moving components.

- A) Inspect guide tube.
- B) Inspect fuel bundles.
- C) Inspect blade.

REF NO.	0
383HA617	
CONT ON SHEET	75 SH NO. 74

LEC - 8 1971

Requestor \_\_\_\_\_ Date \_\_\_\_\_ Approved \_\_\_\_\_ Date \_\_\_\_\_

- 2) Inspect drive.
  - A) Inspect the index tube paying particular attention to any condition that could be caused by rubbing during operation.
  - B) Inspect all inner surfaces of the drive that can come into contact with the index tube and verify that the surfaces are clean and free of defects, paying particular attention to the type of defect which could be caused by rubbing against the index tube.
- 3) Assemble and leak check the drive.
- 4) Install the drive in the vessel and set up the 30" system for normal drive operation.

NOTE:

For all scram testing, the system will be set up as follows unless otherwise indicated:

- A) Accumulator Charge = 1510/575
- B) Inlet line loss = 350 psi @ 108 GPM (cold)
- C) Discharge line loss = 248 psi @ 29.6 GPM (cold)
- D) Scram valve dome pressure = 100 psi
- E) All vessel temperatures are the saturation temperatures at the specified pressure.

PERFORM TESTING AS LISTED BELOW

Ambient Pressure

- 1) Two full stroke drive traces (in and out)
- 2) One jog trace (in and out)
- 3) One settle friction trace
- 4) Two full stroke scrams
- 5) One settle friction trace

500 psi

- 6) One drive trace (in and out)
- 7) One settle friction trace
- 8) Two full stroke scrams
- 9) Two full stroke vessel scrams
- 10) One settle friction trace
- 11) One drive trace (in and out)

REV NO.	0
383HA617	
CONT ON SHEET	76 SH NO. 75

DEC - 8 1971

3.

800 psi

- 12) One drive trace (in and out)
- 13) One settle friction trace
- 14) Two full stroke scrams
- 15) Two full stroke vessel scrams
- 16) One settle friction trace
- 17) One drive trace (in and out)

1030 psi

- 18) One drive trace (in and out)
- 19) One settle friction trace
- 20) Five full stroke scrams
- 21) Two full stroke vessel scrams
- 22) One settle friction trace
- 23) One drive trace (in and out)

Ambient Pressure

- 24) One settle friction trace
- 25) Two full stroke scrams
- 26) Two full stroke drive trace (in and out)
- 27) One full stroke jog trace (in and out)
- 28) Remove and leak check drive
- 29) Disassemble and inspect drive noting any conditions different from that at the beginning of the test. Refer. Steps 1 and 2.
- 30) Remove and inspect fuel bundles
- 31) Remove and inspect blade

NOTE: 500, 800 and 1030 psi testing may be deleted if no significant effects are seen at ambient pressure.

LEO - 8 1971


REV NO.	0
3834A617	
CONT ON SHEET	77
BN NO.	76

## ENGINEERING CALCULATION SHEET

DATE

SHOP ORDER NO. CORE MISALIGNMENT - TRA-378SUBJECT BY S. SMITH SHEET 1 OF 1

MAXIMUM CORE MISALIGNMENT DUE TO INSTALLATION  
AND FABRICATION TOLERANCES PLUS MAXIMUM  
EARTHQUAKE DISPLACEMENT

PLAN VIEW

DEC - 8 1971

REV	0
NO.	3834A617
CONT ON SHEET	78 SH NO. 77

CHECK ONE:

☐ Test Request

☒ Supplement

## TEST REQUEST

PAGE 1 OF 1

Test Request Number A-378 Supplement Number 3

Equipment EARTHQUAKE CORE MISALIGNMENT P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. U3727


### PURPOSE:

To determine effect of bowing the channels on drive performance.

### MODIFICATIONS:

install channel bow equipment.

### TEST PROCEDURE:

- 1) Basic Test
  - A) Drive the CRD in using cooling water (twice).
  - B) Perform settle friction test.
  - C) Obtain two-drive traces
  - D) Perform two screws (1910/575).
- 2) Displacements of bowing plate at which basic test is to be repeated;  
0, .3, .6, .9, 1.2, 1.5.
- 3) All testing is to have engineering coverage, and  approval prior to each step of each test.

DEC - 8 1971

REV NO.	0
383HA 617	
CONT ON SHEET	79
SH NO.	78

Requestor P. D. Renty Date 5/12/71 Approved \_\_\_\_\_ Date \_\_\_\_\_



CHECK ONE:

PAGE 1 OF 1

☐ Test Request

## TEST REQUEST

☒ Supplement

Test Request Number A-378 Supplement Number 4

Equipment Earthquake Core  
Misalignment P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. U3727

PURPOSE:

Continue channel bow tests of Supplement 3.

MODIFICATIONS:

TEST PROCEDURE:

- A) After 1.2 and 1.5, back off to 0 then set displacement at .6. Repeat Para. 1 of Supplement 3.
- B) Cold Hydro
  - 1) At .9 displacement, run 2 accumulator (1510/575) w screens, and two vessel screens at 1030 psi. Also one accumulator screen at 900 and 800 psi vessel pressure.
  - 2) At 1.2 and 1.5, run one accumulator screen at 800, 900 and 1030 psi.
- C) Raset to .9 after .6 after 1.5 and repeat Para. 1 of Supplement 3.
- D) Hot Test at .9.
  - 1) Run 2 accumulator and 2 vessel screens at 800, 900 and 1030 psi.
  - 2) Repeat Para. 1, A., B., and C. of Supplement 3 at 1030 psi.
- E) Repeat Para. 1 of Supplement 3 at 0 vessel pressure after the hot test at .9 displacement.

REQ NO.	<u>0</u>
<u>383HA617</u>	
CONT ON SHEET	<u>80</u> SH NO. <u>79</u>

Requestor P.D. Renty Date 5/25/71 Approved \_\_\_\_\_ Date \_\_\_\_\_

DEC - 8 1971

CHECK ONE:

☐ Test Request

☒ Supplement

## TEST REQUEST

PAGE 1 OF 1

Test Request Number A-378 Supplement Number 5

Equipment Earthquake  
Core Misalignment P/N \_\_\_\_\_ S/N \_\_\_\_\_

Specification No. \_\_\_\_\_ Spec. Sect. No. \_\_\_\_\_ W.O. No. U-3727

PURPOSE:

MODIFICATIONS:

TEST PROCEDURE:

1. Repeat 0 displacement tests per Supp. 3
2. At 1.5 displacement and 800,900 and 1030 psi cold hydro, perform two accumulator screens (1320/710).
3. Repeat 2. with 1510/875 accumulator.
4. Repeat 2. at 1030 psi with 1510/575 accumulator.
5. Deflect CRD housing .3 inches and repeat 4.
6. With a quick release, release CRD housing and at the same time, repeat 4.

REF NO	0
383 HABIT	
CONT ON SHEET	7
SH NO.	80

Requestor P.B. Renty Date 6/2/71 Approved \_\_\_\_\_ Date DEC - 8 1971