

SNUPPS

Standardized Nuclear Unit
Power Plant System

5 Choke Cherry Road
Rockville, Maryland 20850
(301) 869-8010

April 26, 1983

SLNRC 83- 0022 FILE: 0278/0650.2

SUBJ: Containment Recirculation
Sump Testing

Mr. Harold R. Denton, Director
Office of Nuclear Reactor Regulation
U.S. Nuclear Regulatory Commission
Washington, D.C. 20555

Dockets Nos: STN 50-482 and STN 50-483


- References: 1) Para. C1b(2), Regulatory Guide 1.79, Revision 1, 9/75:
Preoperational Testing of Emergency Core Cooling Systems
for Pressurized Water Reactors
2) SLNRC 82-03, 1/18/82: ECCS Sump Test
3) SLNRC 82-044, 11/2/82: Containment Recirculation Sump
Testing

Dear Mr. Denton:

As described in References 2 and 3 the SNUPPS Utilities contracted with the Alden Research Laboratory for hydraulic model testing of the containment recirculation sumps, in lieu of site testing as discussed in Reference 1. This testing has now been completed and a copy of the final test report is attached for your information.

A design change has been made as a result of the testing. Vortex suppression was determined to be necessary and a suitable device, a horizontal grating, was designed and tested. As the results indicate, the sumps as now designed have satisfactory hydraulic performance under the design conditions of restricted flow and partial screen blockages.

Very truly yours,


Nicholas A. Petrick

RFS/bds/4b26
Attachment

cc: G. L. Koester KGE
D. T. McPhee KCPL
D. F. Schn. 11 UE
N. S. Schum USNRC/WC
J. H. Neisler USNRC/CAL

Boo1

8304280003 830406
PDR ADDCK 05000482
PDR
A