

Docket No. 50-336
813830

Attachment 1

Millstone Nuclear Power Station, Unit No. 2
Proposed Changes to Technical Specifications

June 1991

9106170047 910610
PDR ADOCK 05000336
PDR

3.4.10 SPECIAL TEST EXCEPTIONS

SHUTDOWN MARGIN

LIMITING CONDITION FOR OPERATION

3.10.1 The SHUTDOWN MARGIN requirement of Specification 3.1.1.1 may be suspended for measurement of CEA worth and shutdown margin provided reactivity equivalent to at least the highest estimated CEA worth is available for trip insertion from OPERABLE CEA(s).

APPLICABILITY: MODES 2 and 3.

ACTION:

- a. With any full length CEA not fully inserted and with less than the above reactivity equivalent available for trip insertion, within 15 minutes initiate and continue boration at > 40 gpm of boric acid solution at or greater than the required refueling water storage tank (RWST) concentration (ppm) until the SHUTDOWN MARGIN required by Specification 3.1.1.1 is restored.
- b. With all full length CEAs inserted and the reactor subcritical by less than the above reactivity equivalent, immediately initiate and continue boration at > 40 gpm of boric acid solution at or greater than the required refueling water storage tank (RWST) concentration (ppm) until the SHUTDOWN MARGIN required by Specification 3.1.1.1 is restored.

SURVEILLANCE REQUIREMENTS

4.10.1.1 The position of each full length CEA required either partially or fully withdrawn shall be determined at least once per 2 hours.

4.10.1.2 Each CEA not fully inserted shall be demonstrated capable of full insertion when tripped from at least the 50% withdrawn position within 7 days prior to reducing the SHUTDOWN MARGIN to less than the limits of Specification 3.1.1.1.