

1  
2  
3  
4 UNITED STATES OF AMERICA  
5 NUCLEAR REGULATORY COMMISSION  
6

7 BEFORE THE ATOMIC SAFETY AND LICENSING APPEAL BOARD  
8

9  
10 In the Matter of:

11 PACIFIC GAS AND ELECTRIC  
12 COMPANY

13 (Diablo Canyon Nuclear  
14 Power Plant, Units 1 and 2)

Docket Nos. 50-275 O.L.  
50-323 O.L.

15  
16 TESTIMONY ON BEHALF OF THE INDEPENDENT  
17 DESIGN VERIFICATION PROGRAM

18 OF

19 Dr. William E. Cooper  
20 Dr. Robert L. Cloud  
21 Mr. John E. Krechting  
22 Mr. Roger F. Reedy

23 REGARDING

24 CONTENTIONS 1, 2 and 5-8  
25  
26  
27  
28

1  
2 In the Matter of:

3 PACIFIC GAS AND ELECTRIC  
4 COMPANY

5 (Diablo Canyon Nuclear  
6 Power Plant, Units 1 and 2)

Docket Nos. 50-275 O.L.  
50-323 O.L.

7 TESTIMONY REGARDING CONTENTIONS 1,2 and 5-8

8 INTRODUCTORY TESTIMONY

9 Q.1: Please state your name, current position, business  
10 address and qualifications.

11 A.1: (WEC) I am Dr. William E. Cooper, Consulting Engineer  
12 for Teledyne Engineering Services (TES), located at 130 Second  
13 Avenue, Waltham, Massachusetts, 02254. My educational background  
14 and professional experience are summarized in Attachment 1 to  
15 this testimony.

16 (RLC) I am Dr. Robert L. Cloud, Principal in the firm of  
17 Robert L. Cloud Associates (RLCA), located at 125 University  
18 Avenue, Berkeley, California, 94710. My educational background  
19 and professional experience are summarized in Attachment 2 to  
20 this testimony.

21 (JEK) I am John E. Krechting, Project Engineer, with Stone  
22 & Webster Engineering Company (SWEC), 245 Summer Street, Boston,  
23 Massachusetts 02107. My educational background and professional  
24 experience are summarized in Attachment 3 to this testimony.

25 (RFR) I am Roger F. Reedy, Principal in the firm of R.F.  
26 Reedy, Inc. (RFR), 105 Albright Way, Los Gatos, California,  
27 95030.  
28

1 My educational background and professional experience are  
2 summarized in Attachment 4 to this testimony.

3 Q.2: Please describe your participation in the Independent  
4 Design Verification Program (IDVP).

5 A.2: (WEC) As Project Manager for TES Project 5511, I  
6 managed the efforts of TES as Program Manager for the IDVP as  
7 described in A.2 of the Testimony Regarding Contentions 1 and 2.

8 (RLC) As the principal of RLCA, I managed the firm's  
9 efforts in connection with the IDVP as described in A.2 of the  
10 Testimony Regarding Contentions 1 and 2.

11 (JEK) As Project Engineer, I managed the technical effort  
12 of SWEC in connection with the IDVP as described in A.2 of the  
13 Testimony Regarding Contentions 1 and 2.

14 (RFR) As the principal of RFR, I managed the firm's efforts  
15 in connection with the IDVP as described in A.2 of the Testimony  
16 Regarding Contentions 1 and 2.

17 Q.3: What is the purpose of your testimony?

18 A.3: (ALL) This testimony describes the role of the IDVP in  
19 the verification of design work of the DCNPP-1, and how the IDVP  
20 performed its work. In addition, this testimony addresses  
21 Contentions 1,2 and 5-8 as they relate to the IDVP's work.

## CONTENTIONS 1 AND 2

"1. The scope of the IDVP review of both the seismic and non-seismic aspects of the designs of safety-related systems, structures and components (SS&C's) was too narrow in the following respects:

(a) The IDVP did not verify samples from each design activity (seismic and non-seismic).

(b) In the design activities the IDVP did review, it did not verify samples from each of the design groups in the design chain performing the design activity.

(c) The IDVP did not have statistically valid samples from which to draw conclusions.

(d) The IDVP failed to verify independently the analyses but merely checked data of inputs to models used by PG&E.

(e) The IDVP failed to verify the design of Unit 2.

"2. The scope of the ITP review of both the seismic and non-seismic aspects of the designs of the safety-related systems, structures and components (SS&C's) was too narrow in the following respects:

(a) The ITP did not verify samples from each design activity (seismic and non-seismic).

(b) In the design activities the ITP did review, it did not verify samples from each of the design groups in the design chain performing the design activity.

(c) The ITP did not have statistically valid samples from which to draw conclusions.

(d) The ITP has failed systematically to verify the adequacy of the design of Unit 2."

Q.1: Why was the Independent Design Verification Program (IDVP) for the Diablo Canyon Nuclear Power Plant, Unit 1 (DCNPP-1) established?

A.1: (WEC) On November 19, 1981, the Commission issued Order CLI-81-30 (Commission Order) suspending portions of Operating License No. DPR-76. At the same time, the NRC Staff issued a letter (Staff Letter) which required additional steps prior to power ascension. The Commission Order and Staff Letter required an independent verification of design efforts performed internally by Pacific Gas and Electric Company (PGandE) or on behalf of PGandE by service-related contractors on safety-related structures, systems, and components (SSCs). The IDVP was



1 established in response to the Commission Order and the Staff  
2 Letter.

3 Q.2: Which organizations participated in the IDVP?

4 A.2: (A) The participants in the IDVP were as follows:

5 o Teledyne Engineering Services (TES) served as Program  
6 Manager. In that capacity, TES assured that the IDVP  
7 was conducted in accordance with approved program  
8 plans, including review and approval of all IDVP  
9 reports and conclusions.

10 o R.F. Reedy, Inc. (RFR) performed the Design QA Audits  
11 and Reviews and the design office verification of the  
12 Diablo Canyon Project (DCP) Corrective Action Program  
13 (CAP).

14 o Robert L. Cloud Associates, Inc. (RLCA) verified the  
15 seismic, structural, and mechanical aspects of the  
16 design process.

17 o Stone & Webster Engineering Corporation (SWEC) verified  
18 the safety system and safety analysis aspects of the  
19 design process.

20 In addition to these major participants, TES retained a  
21 number of organizations and individuals to assist the IDVP in  
22 specialty areas. Of most importance in this regard was the  
23 participation of Professors Myle J. Holley, Jr., and John M.  
24 Biggs, who were sufficiently involved in the review of the civil-  
25 structural area that they were able to co-approve, with TES, the  
26 resulting Interim Technical Reports (ITRs).

27 Q.3: To whom did the IDVP Program Manager report?  
28

1           A.3: (WEC) As IDVP Program Manager, TES reported independ-  
2           ently to NRC (Denton) and PGandE (Maneatis).

3           Q.4: Please summarize the requirements of the Commission  
4           Order and the process which lead to Commission approval of the  
5           IDVP Phase I Program Plan.

6           A.4: (WEC, RLC) The Commission Order required performance  
7           "of an independent design verification of all safety-related  
8           activities performed prior to June 1, 1978, under all seismic-  
9           related service contracts utilized in the design process for  
10          safety-related structures, systems, and components." In summary,  
11          the IDVP was to include the following program elements: QA pro-  
12          cedures and controls relative to the related criteria of Appendix  
13          B to 10 CFR 50; identification of interfaces between PGandE in-  
14          ternal design groups and each contractor; implementation of the  
15          QA procedures and controls; and selection and performance of  
16          sample calculations, with criteria for expanding the sample when  
17          problems in verification are encountered.

18          The program developed in response to the Commission Order  
19          was identified as Phase I and was initially submitted by PGandE's  
20          letter of December 4, 1981. During the period December 1981  
21          through March 1982 there were a series of meetings involving the  
22          various parties to review the proposed program and revisions  
23          thereto. These culminated in NRC SECY-82-89 which summarized the  
24          Staff evaluation of the scope and technical adequacy of the Phase  
25          I program and concluded that the proposed program satisfied the  
26          Commission Order requirements and, if properly implemented, would  
27          allow determination of whether there was reasonable assurance  
28          that the overall seismic design was in conformance with the

1 license application. After TES was named as Program Manager, it  
2 submitted the Phase I Program Management Plan, which integrated  
3 previous submittals and included requirements for TES review and  
4 acceptance of IDVP work done prior to March 25, 1982. An NRC  
5 letter to PGandE dated April 27, 1982 approved the activities  
6 covered by the Plan as being responsive to the Commission Order,  
7 to SECY-82-89 as revised and voted upon by the Commission on  
8 March 4, 1982, and to previous Staff concerns.

9 Q.5: Please summarize the requirements of the Staff Letter  
10 and the process which lead to Commission approval of the IDVP  
11 Phase II Program Plan.

12 A.5: (WEC, JEK) The Staff Letter is similar to the Commis-  
13 sion Order, except that it addresses three aspects: all non-  
14 seismic service-related contracts prior to June 1978; PGandE  
15 internal design activities, without stated restriction as to  
16 date; and all service-related contracts post-January 1, 1978.

17 Based upon the total IDVP efforts to date, on June 18, 1982,  
18 TES developed and transmitted the IDVP Phase II Program Plan to  
19 NRC and PGandE. There followed a series of meetings similar to  
20 those held during the earlier period with respect to Phase I,  
21 which resulted in the Staff position documented by SECY-82-414.  
22 On December 9, 1982, the Commission approved "the Phase II  
23 Program Plan of June 18, 1982, including the proposed IDVP  
24 Contractors, as modified by the Staff in Enclosure 11 to SECY-82-  
25 414." This approval was contained in an NRC letter to PGandE  
26 dated December 25, 1982.

27 Q.6: Is the distinction between Phase I and Phase II mean-  
28 ingful at this time?

1 A.6: (ALL) No, in that there is a more useful distinction  
2 available, that between "seismic" and "non-seismic" considera-  
3 tions. In using the term "seismic", however, it must be under-  
4 stood that the review included effects resulting from non-seismic  
5 loadings which, in accordance with license application criteria,  
6 must be combined with the effects of seismic loadings.

7 Q.7: Please identify the IDVP program elements and which  
8 organization was responsible for each element.

9 A.7: (ALL) The program elements are described in Section  
10 3.5 of the IDVP Final Report. A convenient breakdown of the  
11 program elements, including subsequent portions of this testimony  
12 where each is addressed, is as follows:

<u>Element</u>	<u>Q/A No.</u>	<u>IDVP Program Element</u>
1	9-14	Design Chain
2	15	QA Audits and Reviews
3	16, 20	Initial and additional sample verification
4	17-19	Verification of CAP
5	21-24	Identification and resolution of concerns

21 RFR, RLCA and SWEC performed element (1). RFR performed ele-  
22 ment (2) and the QA audit and the "design office verification"  
23 which was part of element (4).

24 RLCA and SWEC performed elements (3), (5), and (6) in their  
25 area of responsibility and RLCA performed the design process ver-  
26 ification identified as part of element (4). The RLCA area of  
27 responsibility included all seismic, structural and mechanical  
28

1 aspects as defined by the IDVP Program Plan and ITR-1, and the  
2 verification of the CAP as defined in ITRs-8 and -35.

3 The SWEC area of responsibility included the system design  
4 aspects of safety-related systems and the performance of safety-  
5 related analyses for the sample systems and analyses defined by  
6 the IDVP Program Plan, and verification of the corrective action  
7 taken by the DCP with respect to the generic concerns identified  
8 by the IDVP (ITR-34).

9 All of the major IDVP participants were involved in the  
10 identification of "basic cause", in the evaluations contained in  
11 Section 6 of the IDVP Final Report, and in developing the IDVP  
12 conclusions contained in Section 2 of that report.

13 Q.8: Please describe the types of reports issued by the  
14 IDVP.

15 A.8: (WEC) A description of Program Reporting is included  
16 in Section 3.6 of the IDVP Final Report, and can be summarized as  
17 follows:

- 18 o The IDVP issued Semimonthly Reports to all parties.
- 19 o The Error or Open Item (EOI) File System was used for  
20 tracking of IDVP concerns. When either the verifica-  
21 tion of the initial sample or the QA Audits and Reviews  
22 determined that an item did not meet verification  
23 criteria or unresolved issues existed, an Open Item  
24 Report (OIR) was issued. An OIR indicated a concern  
25 that had not been verified, fully understood, or  
26 assessed as to its significance.
- 27 o Interim Technical Reports (ITRs) were used by the IDVP  
28 to document programmatic aspects or to report detailed



1 technical results. An ITR was prepared when a program  
2 participant completed an aspect of its assigned effort.  
3 Most ITRs were technical and provided the results of a  
4 completed verification or were in support of an Error,  
5 Open Item, or Program Resolution Report. Other ITRs  
6 (e.g., ITRs-1, -8, -34, and -35) were programmatic and  
7 used to define the IDVP decision as to the need for  
8 additional verification, additional samples, or verifi-  
9 cation of DCP activities.

- 10 o The IDVP Final Report summarizes the IDVP efforts and  
11 includes the IDVP conclusions and evaluation in  
12 response to the Commission Order and the Staff Letter.

13 Q.9: What is a "design chain", and were design chains  
14 identified by the IDVP?

15 A.9: (ALL) As discussed in the IDVP Final Report, Section  
16 4.1, the IDVP developed design chains that identified the organi-  
17 zations involved in the separate but linked process of providing  
18 the design for a specific safety-related SSC selected for evalua-  
19 tion. Each design chain was developed from a listing of service-  
20 related PGandE contractors. The specific contractors who had an  
21 influence on the final (as of November 30, 1981) safety-related  
22 design were identified. Additionally, interfaces were identified  
23 between service-related contractors and PGandE.

24 Q.10: What assurance does the IDVP have that all service-  
25 related contractors contributing to the final (as of November 30,  
26 1981) design were identified?

27 A.10: (ALL) The SSCs subject to Hosgri qualification and  
28 the participating organizations were identified by RLCA prior to



1 the development of the Phase I Program Plan, so were considered  
2 in developing the initial samples. Similarly, the systems for  
3 which PGandE was responsible were known at the time the Phase II  
4 Program Plan was developed and three SWEC sample systems were  
5 chosen accordingly.

6 RFR performed a review of the contractors list early in  
7 Phase II, which provided additional assurance as to the role of  
8 the various organizations. The RFR effort confirmed the earlier  
9 RLCA work with respect to Hosgri organizations. With respect to  
10 the three SWEC sample systems considered in Phase II, the SWEC  
11 design process verification confirmed the RFR developed con-  
12 tractor list. The remaining organizations to be identified were  
13 those involved with PGandE subsequent to January 1, 1978 which  
14 were not involved with Hosgri qualification or the SWEC sample.  
15 The RFR identification of these organizations was confirmed by  
16 the subsequent QA Audit and Review of PGandE interfaces with con-  
17 tractors and by the review of the PGandE "lookback" QA review.  
18 These combined activities provided assurance that the IDVP con-  
19 sidered the proper service-related organizations in performance  
20 of the QA Audits and Reviews and the design process verification.

21 Q.11: Which service-related contractors were included in  
22 the design chains identified by the IDVP?

23 A.11: (ALL) The nine firms were ANCO Engineers, URS/J.  
24 Blume, Cygna Energy Services (formerly Earthquake Engineering  
25 Services), EDS Nuclear, Inc., Garretson-Elmendorf-Zinov, Harding-  
26 Lawson Associates, Quadrex (formerly Nuclear Services Corp.),  
27 Radiation Research Associates, and Wyle Laboratories.

1 Q.12: Please explain why other service-related contractors  
2 were eliminated from the list of those considered by the IDVP?

3 A.12: (ALL) As stated in Section 4.1.4 of the IDVP Final  
4 Report, PGandE had identified 61 safety-related service con-  
5 tractors which were active at any time for seismic and non-  
6 seismic activities. All of these and their scope of work are  
7 identified in ITR-9. Of the 52 contractors not included in the  
8 IDVP design chains, 43 were eliminated because they did not con-  
9 tribute significantly to the final design, that is, they were  
10 involved only in licensing or in design studies, they provided  
11 only minor design input, they performed only non-destructive  
12 examination (NDE) services, or they provided only design inputs  
13 which were not used in final design.

14 The remaining nine firms were eliminated for the following  
15 reasons. Two firms, RLCA and TES, were eliminated because they  
16 were participating in the IDVP. Westinghouse was eliminated  
17 because it is the NSSS supplier. Three firms, James Engineering  
18 Company, Kaiser Engineers and Mark G. Jones, were eliminated  
19 because all of their work had been performed in the PGandE office  
20 under the PGandE QA program. Two firms, Nutech, Inc. and Western  
21 Canada Hydraulic Laboratories, were eliminated because their work  
22 was subject to separate audit by the NRC. Finally, General  
23 Electric Co. was eliminated because it provided only consulting  
24 services in the testing of switchgear. It is included in this  
25 specific listing only because its name had been raised in pre-  
26 vious discussions. However, since its participation was limited  
27 to consulting services, it could have been eliminated on the same  
28

1 basis as other firms which did not contribute significantly to  
2 the final design.

3 Q.13: Please explain why the elimination of these con-  
4 tractors from the IDVP's verification did not detract from the  
5 IDVP's ability to reach its conclusions as to the design of  
6 DCNPP-1.

7 A.13: (ALL) Obviously the elimination of the contractors  
8 which did not contribute significantly to the final design had no  
9 impact on the IDVP's efforts.

10 Elimination of the contractors named in A.12 did not detract  
11 from the IDVP's ability to reach its conclusions for differing  
12 reasons dependent upon the specific firms involved. The exclu-  
13 sion of the IDVP participants (TES and RLCA) was a recognized  
14 fact since the beginning of the program, and the Program Plans  
15 were approved by the Commission with that exclusion. The exclu-  
16 sion of Westinghouse is discussed in the testimony regarding  
17 Contention 6. The work of the three firms working under the  
18 PGandE program was subject to verification as part of the PGandE  
19 effort, and thus was included or excluded solely on the basis of  
20 whether it was part of an IDVP sample. Two firms, Nutech and  
21 Western Canada Hydraulic Laboratories, were excluded because the  
22 specific work performed with regard to DCNPP-1 had previously  
23 been reviewed by the NRC, and it was unnecessary to duplicate  
24 such effort.

25 Q.14: What was the effect of this design chain effort on  
26 the verification performed by the IDVP?

27 A.14: (ALL) The nine service-related contractors included  
28 in the design chains were all subjected to the IDVP QA Audits and

1     Reviews, in accordance with the requirements of the Commission  
2     Order and the Staff Letter. Knowledge of the participating  
3     organizations was also useful in verification of the design  
4     process. Of the nine identified organizations, the work of all  
5     but two was included in the initial samples for one or both of  
6     the design process verification phases. The two organizations,  
7     whose work was not included in the initial samples, were Harding-  
8     Lawson Associates and Garretson-Elmendorf-Zinov (GEZ). Because  
9     of negative results from the subsequent evaluation of the QA  
10    Audit and Review, additional verification was performed of the  
11    soils work originally conducted by Harding-Lawson Associates.  
12    Because GEZ was known not to be included in the initial sample  
13    for Phase II, particular attention was given to its efforts by  
14    RFR, and EOI 7001 was opened to assure that additional investiga-  
15    tion was conducted of an aspect of potential concern. Additional  
16    verification resolved the potential concern satisfactorily, and  
17    the EOI file was closed.

18       Q.15: What was the purpose of performing the QA Audits and  
19    Reviews?

20       A.15: (WEC, RFR) The QA Audits and Reviews were performed  
21    to evaluate both the formal QA program imposed for the work and  
22    the implementation of that program. Although QA Audits and  
23    Reviews provided certain information in direct response to the  
24    Commission Order and Staff Letter, another IDVP purpose was to  
25    obtain background information which might have impacted the  
26    extent of design process verification. Based on Phase I experi-  
27    ence, an additional step was added for Phase II. If the reviewed  
28    organization did not have a formal QA program, or if its formal

1 QA program was not properly implemented, its actual design con-  
2 trol practices were evaluated and reported as a part of the QA  
3 Audit and Review Report. Additional sampling was considered if  
4 negative results were obtained from the QA Audit and Review of an  
5 organization whose work was not included in the initial sample.  
6 Similarly, additional verification was considered when the organ-  
7 ization's work was included in the initial sample, but that  
8 sample did not include the negative aspect.

9 Q.16: How were the initial samples chosen for verification  
10 of the design process?

11 A.16: (WEC, RLC, JEK) The selection of the initial samples  
12 to be used for verification of the design process are indicated  
13 in the Engineering Program Plan for each phase. All initial  
14 sample activities were performed on work completed on or before  
15 November 30, 1981. For both the seismic and non-seismic verifi-  
16 cations, the initial samples were chosen on the basis of  
17 engineering judgement, considering the experience of the partici-  
18 pants in the design of Pressurized Water Reactors (PWRs) and the  
19 implications of seismic and other operating conditions on such  
20 systems.

21 Q.17: Was the IDVP's work on the initial samples and addi-  
22 tional verifications/samples in the seismic review superseded by  
23 subsequent events?

24 A.17: (WEC, RLC) Yes. In response to the seismic design  
25 concerns identified by June, 1982, PGandE instituted the CAP,  
26 which was consistent with and responsive to both the IDVP and the  
27 Commission Order. As described in the PGandE Phase I Final  
28 Report, Section 1.5.2, the CAP included the performance of a



1 broad-based review of safety-related SSCs enveloping and correct-  
2 ing the previous ITP and IDVP results. The expanded ITP effort  
3 provided more complete and consistent documentation of the design  
4 work, with all new work performed to the latest approved QA  
5 requirements and procedures. Finally, the expanded program was  
6 intended to make it unnecessary to review older analyses or cal-  
7 culations which were being redone. The CAP results became the  
8 seismic analyses of record.

9 In response to this action, the IDVP issued ITR-8, "Verifi-  
10 cation of the Corrective Action Program". This plan included an  
11 examination of the corrective action scope, criteria, and  
12 methodology for consistency with the criteria of the license  
13 application. It also required that the CAP be audited for proper  
14 implementation of the NRC-approved QA requirements, with emphasis  
15 on technical interface control and project indoctrination. The  
16 purpose of these audits was to gain assurance that the very ex-  
17 tensive CAP was being conducted in a planned and controlled  
18 manner.

19 Q.18: What was the scope of the IDVP verification of the  
20 CAP seismic review and how was it accomplished?

21 A.18 (WEC, RLC) The scope of the IDVP verification of the  
22 CAP seismic review required a verification of all the CAP  
23 activities for each safety-related SSC within PGandE's original  
24 scope for design.

25 The IDVP verification program for CAP activities was defined  
26 by ITR-8. Prior to preparation of that ITR, the DCP had provided  
27 its detailed plans in open meetings during the summer of 1982 and  
28 had described its methodology in sufficient detail for the IDVP



1 to judge that the CAP was a reasonable substitute for the program  
2 of additional verification described by Revision 0 to ITR-1.  
3 Specifically, it permitted the IDVP to combine several EOI Files  
4 that had either indicated errors in the previous PGandE work, or  
5 that had raised issues about that work which had not been  
6 resolved, into a limited number of generic EOIs which were used  
7 to track the IDVP verification of the CAP work. Hence, those  
8 generic EOIs identified all of the IDVP concerns previously  
9 identified and all of the DCP efforts related to the safety-  
10 related SSCs to which these concerns applied.

11 The general approach of the IDVP toward verification of CAP  
12 activities was intended to develop a sound understanding of all  
13 of the engineering used in the design activities subject to the  
14 IDVP. The IDVP wanted to understand the rationale, methods and  
15 computer codes used by considering: all the options available;  
16 the level and degree of sophistication of models employed; and  
17 the completeness of the work. In short, the IDVP sought to  
18 develop a complete understanding of the design process and confi-  
19 dence that the process was being properly applied.

20 With respect to SSCs, ITR-8 defined the following to be sub-  
21 ject to verification:

- 22 o Buildings (containment, auxiliary, fuel handling,  
23 turbine, intake)
- 24 o Piping (large and small bore, with the supports)
- 25 o Mechanical and electrical equipment (at least one of  
26 each type)
- 27 o HVAC equipment and ducts, electrical raceways, and in-  
28 strument tubing, all with supports.

1 The detailed application of this definition is described by the  
2 appropriate sections of the IDVP Final Report and in the ITRs  
3 numbered -51 and higher.

4 Three different approaches were followed by the CAP in the  
5 performance of its review: a complete reanalysis, a complete  
6 review followed by reanalysis of deficient segments and a  
7 sampling approach. The IDVP verification methodology varied with  
8 the approach followed by the CAP, which is also defined in ITR-8.

9 Given the SSCs subject to verification and the CAP identifi-  
10 cation of the approach it intended to use for each, it was  
11 possible for the IDVP to establish categories of like items,  
12 where the term "like" relates to the engineering process required  
13 for qualification. For example, the qualification of piping and  
14 supports involves similar features and uniform methodologies,  
15 whereas each of the buildings involves unique features and a  
16 differing methodology.

17 For each category, the IDVP reviewed the methodology to be  
18 applied, requested and received a complete index of the CAP work  
19 with respect to the subject SSCs, reviewed that index to assure  
20 that the CAP work was totally responsive to its scope, and then  
21 selected Design Review Packages (DRPs) for detailed review. The  
22 selection of appropriate DRPs was crucial to achieving the  
23 objectives of the verification efforts. It was necessary to  
24 select DRPs that addressed concerns developed by the IDVP either  
25 during earlier verifications or during review of the CAP  
26 methodology. It was also important for the IDVP to select a  
27 total set of DRPs sufficient to provide for an evaluation of the  
28 entire CAP process and to develop confidence in the implementa-

1 tion of that process. In addition, the DRPs were chosen to re-  
2 view the CAP work both while in-progress and after completion of  
3 a significant portion of the work. In total, approximately 200  
4 DRPs were reviewed in detail by the IDVP. Both the available and  
5 the selected packages are identified in an appendix in each of  
6 the CAP-related ITRs.

7 Upon receipt, each DRP was subjected to detailed review by  
8 the IDVP, applying, singularly or in combination, two of the  
9 recognized methods for design verification--design review or  
10 independent analysis. As questions arose, they were transmitted  
11 in writing to the CAP and all responses which the IDVP relied  
12 upon were also in writing.

13 After completion of the review of various DRPs, the IDVP  
14 applied its improved knowledge of the CAP design process to  
15 develop a comprehensive understanding of that process and of the  
16 results obtained through the process. Where, in the opinion of  
17 the IDVP, additional reviews were required or where planned  
18 reviews could be deleted, the IDVP verification process was  
19 revised. Finally, the IDVP reached its present state of  
20 understanding and acceptance of the CAP work.

21 Q.19: Please describe in more detail how the verification  
22 of the CAP was performed by considering a specific area of  
23 seismic verification.

24 A.19: (RLC) The specific area chosen as an example is the  
25 verification of stresses in the containment shell.

26 Verification of the containment building was reported in  
27 ITR-54. That verification included both the interior and  
28 exterior concrete structures as well as the polar crane. The

1 containment shell and the base slab constitute the exterior  
2 structure, which is a Design Class 1 structure. The seismic con-  
3 ditions considered are Hosgri (both Newmark and Blume), Design  
4 Earthquake (DE) and the Double Design Earthquake (DDE), each in  
5 appropriate combination with thermal effects, pipe reactions,  
6 missile impact and internal pressures.

7 The scope of the DCP work is defined in the PGandE Phase I  
8 Final Report, and included a complete review of the dynamic  
9 analysis and member qualifications, with physical modifications  
10 to be implemented if required. The first step in the IDVP veri-  
11 fication was to compare the DCP scope to the applicable criteria  
12 of the license application to assure that all requirements were  
13 being addressed.

14 The second step in the IDVP verification was to review the  
15 methodology described in the PGandE Phase I Final Report with  
16 respect to assumptions, modeling techniques and structure-unique  
17 requirements. For example, the basic safety function of the con-  
18 tainment shell is to retain pressure during a Faulted Condition  
19 with recognition of all the defined load combinations.

20 Therefore, the methodology review included an evaluation of  
21 the three-dimensional models used for analysis of the containment  
22 shell with respect to assumptions, computation of mass and stiff-  
23 ness properties, boundary conditions and the finite element  
24 modeling of the physical structure. The DCP analysis of the  
25 overall dynamic response of the containment building was not  
26 reviewed in detail, because such review was performed with  
27 respect to other structures.

1        Having developed an understanding of the general approach to  
2 be applied by the DCP in its review of the containment shell, and  
3 considering the IDVP knowledge of the similarities and  
4 differences between the containment shell and the other  
5 structures, the IDVP was in a position to select the DRPs for  
6 detailed review. The first step in this process was the receipt  
7 from the DCP of a calculation index identifying all calculations  
8 pertinent to the containment building, which is an appendix to  
9 ITR-54. The IDVP examined this index to assure that all  
10 calculations required to perform the work were included, and  
11 found that it was complete. The IDVP reviewed this list for  
12 the purpose of identifying those DRPs which were to be subjected  
13 to detailed review. This selection was made with the objective  
14 of reviewing those DRPs which dealt with any previously  
15 identified IDVP concerns and those which, when considered  
16 together with the DRPs requested on other subjects, would provide  
17 a comprehensive understanding of the DCP process.

18        With respect to verification of the containment shell, the  
19 IDVP requested DRPs applicable to:

- 20        o Evaluation of the general containment shell using
- 21        seismic loads from the URS/Blume axisymmetric models
- 22        (Hosgri) and the associated pressure and thermal loads.
- 23        o Modeling and evaluation of the equipment hatch region.
- 24        o Modeling and evaluation of the base slab/shell junc-
- 25        tion.

26        The first of these calculations permitted review of the general  
27 characteristics of the containment shell. The second and third  
28



1 permitted review of those portions of the containment shell which  
2 are usually limiting in the structural capability.

3 Each DRP was then reviewed by RLCA in accordance with a  
4 checklist which was designed to ensure that all significant  
5 topics are addressed. The main checklist items and guidelines  
6 are as follows:

- 7 o Proper transfer of data from construction (pour lift  
8 and shop drawings) to design drawings. Verification of  
9 field conditions versus drawings was done on a sample  
10 basis.
- 11 o Limitations of formulas, mathematical models, etc. and  
12 impact on results. Degree of conservatism or non-  
13 conservatism present, if any.
- 14 o Formulation of mathematical models with respect to  
15 licensing commitments and required data. Use of proper  
16 seismic ground motion.
- 17 o Inclusion of proper degree of freedom, mass, stiffness,  
18 and boundary conditions.
- 19 o Accuracy of results obtained and assessment of any  
20 method limitations.
- 21 o Applicability of the time history and response spectrum  
22 analysis methods.
- 23 o Verification that proper formulas are used.
- 24 o Verification of the mathematical accuracy of selected  
25 calculations.
- 26 o Verification that all required loads, displacements and  
27 accelerations are obtained for member evaluation.
- 28 o Review of all required load combinations and resulting



1 stresses against allowables in accordance with the  
2 specified criteria.

- 3 o Sample verification of data transfer for both hand cal-  
4 culations and computer runs.
- 5 o Verification that all calculation files reviewed are  
6 properly signed, dated, referenced and approved.

7 Review of each of the DRPs against the applicable portions  
8 of this check list was intended to assure that the IDVP consider-  
9 ed the important aspects of each DRP. ITR-54 includes a summary  
10 of the DCP and IDVP results for each DRP.

11 The effort expended by the IDVP for the review, briefly  
12 described above, was extensive. RLCA first reviewed each DRP to  
13 identify issues where more information was required from the CAP.  
14 Following receipt of the additional information, a final review  
15 was made. RLCA documented both reviews, and the DCP and RLCA  
16 packages were reviewed by TES in conjunction with Professors  
17 Holley and/or Biggs. Formal Requests for Information (RFI) were  
18 used by both RLCA and TES to obtain additional information from  
19 the DCP whenever questions arose in the course of the review, and  
20 public meetings were held to permit the DCP to explain its  
21 approach, to answer questions and to identify additional  
22 information which was available through the RFI process. In the  
23 course of this total verification effort RLCA issued almost 1200  
24 RFIs and approximately 40 open meetings were held.

25 It was this extensive effort which enabled the IDVP to reach  
26 the affirmative conclusions concerning the design of the contain-  
27 ment shell that are stated in ITR-54 and Section 4.4.4 of the  
28 IDVP Final Report.

1 Q.20: Please explain the scope of the IDVP's non-seismic  
2 review and why the IDVP believes that this scope was sufficient.

3 A.20: (WEC, JEK) The selection of the non-seismic sample  
4 of safety-related systems and analyses to be verified by the IDVP  
5 was based on engineering judgement. The objective was to select  
6 samples of various types of engineering design work to ensure  
7 that generic errors did not exist in the unreviewed design.

8 The first step in the sample selection procedure was to  
9 identify the safety-related systems designed by PGandE and any  
10 service-related contractors who performed work that significantly  
11 affected the system's final design as of November 30, 1981. The  
12 IDVP also identified the various PGandE internal design groups  
13 that were responsible for the PGandE designed safety-related  
14 systems.

15 Based on this information, the IDVP selected samples of  
16 systems such that all of the PGandE design groups responsible for  
17 non-seismic system design were sampled. In addition, the  
18 service-related contractor who performed the most significant  
19 design work in the non-seismic system design area was reviewed.  
20 The only other seismic-related contractor which performed system-  
21 related design work was reviewed in detail as to its QA and  
22 design control practices by the IDVP. See discussion of GEZ in  
23 A.14. The IDVP selected safety-related analysis work such that  
24 all other identified service-related contractors which performed  
25 significant non-seismic analyses were sampled.

26 The selected systems were the auxiliary feedwater (AFW)  
27 system, the control room ventilation and pressurization (CRVP)  
28

1 system and the safety-related portion of the 4160 V electric  
2 distribution system.

3 The AFW system was selected because its design represents an  
4 interrelationship of several design criteria and interfaces.  
5 Specifically, it involves interface with NSSS vendor criteria,  
6 with containment design criteria, interface of PGandE internal  
7 design organizations, and the methodology of determining a water  
8 system's mechanical, electrical, and control component design  
9 criteria. In addition, AFW systems often appear in the dominant  
10 accident sequences in various probabilistic risk assessment pro-  
11 grams.

12 The CRVP system was selected because it too represents an  
13 interrelationship of several design criteria and interfaces.  
14 Specifically, it involves interface with a service-related con-  
15 tractor, interface of PGandE internal design organizations, and  
16 interface with the control room habitability criteria. It also  
17 represents a contrast of design methods since it is an air system  
18 rather than a water system.

19 The safety-related portion of the 4160 V electrical distri-  
20 bution system was selected because it is the basic power supply  
21 for safety-related electrical equipment. It also represents an  
22 interrelationship of several design criteria and involves the  
23 interfaces among several PGandE internal design organizations.

24 The three sample systems were designed by different engi-  
25 neering groups within PGandE, thus providing for evaluation of a  
26 broad spectrum of the PGandE engineering organization.

27 In addition, the IDVP selected two areas of safety-related  
28 analyses for review: the integrated dose analyses; and the tem-

1 perature, pressure and humidity analyses as they affect environ-  
2 mental qualification of equipment. These analyses were selected  
3 since this work was done almost exclusively by three service-  
4 related contractors and utilized by PGandE. The service-related  
5 contractors were different and their work involved a flow of  
6 design information through PGandE engineering groups.

7 For the three selected sample systems, a complete vertical  
8 verification of the system design was performed. The applicable  
9 licensing criteria were identified, and a system design chain was  
10 developed. The system's design was then reviewed to determine if  
11 the licensing criteria were satisfied. The review included the  
12 aspects of mechanical, electrical and instrumentation and control  
13 design.

14 In addition, the IDVP performed the following verifications  
15 of the sample systems. The IDVP verified the fire protection  
16 provided for the sample systems, including the separation, fire  
17 barriers, suppression and detection systems provided in areas  
18 containing sample system components. The IDVP verified that the  
19 AFW and CRVP systems were adequately protected from the effects  
20 of a high energy line break (HELB), high energy line crack  
21 (HELC), and moderate energy line break (MELB). This was an  
22 extensive effort which required identification of all high energy  
23 and moderate energy lines in relationship to the AFW and CRVP  
24 system components to ensure that these components were adequately  
25 protected. The IDVP verified that the AFW and CRVP system com-  
26 ponents were adequately protected from the effects of internally  
27 generated missiles. This again required identification of  
28

1 potential missile sources and AFW and CRVP system targets to  
2 ensure that adequate protection was provided.

3 Although the verification described by the preceding para-  
4 graph and the safety-related analyses verification (radiation and  
5 pressure, temperature and humidity) previously described were  
6 specific to the three sample systems, the design work and  
7 methodology reviewed are generic to all safety-related systems in  
8 DCNPP-1, and in this sense are horizontal reviews. Thus, these  
9 reviews permitted the IDVP to examine a very broad aspect of  
10 safety-related design that is applicable to all safety-related  
11 systems.

12 In addition, when the IDVP identified concerns that were  
13 potentially generic, another review was performed by the DCP for  
14 that specific concern for all PGandE designed safety related  
15 systems and was verified by the IDVP. These reviews and verifi-  
16 cations were performed in all areas of analyses of pressure,  
17 temperature and humidity due to HELB; selection of system design  
18 pressure and temperature; selection of differential pressure  
19 across power operated valves; redundancy of power supplies for  
20 shared systems; separation and single failure criteria for  
21 mutually redundant circuits; and jet impingement effects of HELB  
22 inside containment.

23 In summary, the IDVP not only performed very detailed and  
24 comprehensive reviews of three sample systems which included all  
25 the PGandE internal design groups responsible for non-seismic  
26 safety-related system design, but the IDVP verification also  
27 included work by the service-related contractor who provided the  
28 most significant input into the safety-related system design. In



1 addition, the IDVP performed many verifications of analysis and  
2 design functions that are generic to the design or design method-  
3 ology of all safety-related systems. Moreover, the latter  
4 reviews included work from the various PGandE design groups as  
5 well as from all service-related contractors performing signifi-  
6 cant non-seismic design analysis.

7 Based on these extensive and detailed reviews, the IDVP has  
8 achieved a very broad-based and comprehensive understanding of  
9 the non-seismic design of the DCNPP-1. It is this broad-based  
10 and comprehensive understanding that provides the IDVP confidence  
11 in its conclusions as to the adequacy of the non-seismic design  
12 of DCNPP-1, as discussed in Sections 2 and 6 of the IDVP Final  
13 Report.

14 Q.21: How did the IDVP resolve any specific concern that it  
15 identified?

16 A.21: (ALL) Additional verifications were performed to  
17 resolve specific concerns if deficiencies were found by the eval-  
18 uation of the QA Audits and Reviews with respect to the safety-  
19 related SSCs of the initial sample systems or if the verification  
20 criteria were found to be violated.

21 Additional sampling was performed either when significant  
22 deficiencies in the QA Program or its implementation were  
23 identified for an organization that was not a part of the initial  
24 sample system design chain, or when the reasons for the discrep-  
25 ancies found during design process verification were not clear  
26 and additional information was required.

27 Based on the results of each additional verification or  
28 additional sample, the responsible IDVP participant submitted a



1 recommendation to the Program Manager. When the item was deter-  
2 mined not to have met licensing criteria, this recommendation may  
3 have included recommendations for additional verification of a  
4 generic concern. When the IDVP determined that the item met  
5 licensing criteria, the item was closed and the results reported.

6 Q.22: How were generic concerns identified and resolved?

7 A.22: (ALL) The identification of generic concerns was an  
8 important part of the IDVP. A generic concern was a concern  
9 which could impact design acceptability beyond the immediate SSCs  
10 for which the concern was initially identified. The IDVP conclu-  
11 sion that a generic concern existed was identified in an ITR  
12 (e.g., ITRs-1, -34). When generic concerns were identified, the  
13 steps that were taken included, as appropriate, the evaluation  
14 of the effect of the generic concern on other safety-related  
15 structures and components within the initial sample system,  
16 and/or an evaluation of the effect of the generic concern on  
17 safety-related structures and components in other systems.

18 Q.23: What did the IDVP do when it determined that cor-  
19 rective action was required?

20 A.23: (WEC, RLC, JEK) An item that was determined not to  
21 have met licensing criteria was reported to DCP for corrective  
22 action, and the IDVP performed verifications of DCP corrective  
23 actions. As stated in the Program Management Plan, "After PGandE  
24 takes corrective action on an error, or performs physical modifi-  
25 cations to alleviate an error or deviation originating in the  
26 independent program, the PGandE engineering results are subject  
27 to design verification by the independent program to assure that  
28 proper resolution has been achieved." When IDVP verification of

1 a corrective action indicated that the corrected item met  
2 licensing criteria, the item was considered closed. If verifica-  
3 tion indicated that the corrective action did not meet licensing  
4 criteria, the item was again reported to DCP for continuation of  
5 corrective action.

6 Q.24: The answer to Q.19 describes how the IDVP resolved  
7 its concerns in a specific area of seismic verification. Please  
8 describe similarly how the IDVP identified and resolved concerns  
9 in a specific area of non-seismic verification.

10 A.24: (JEK) A similar example in the non-seismic area is  
11 the IDVP verification process related to the pressure and  
12 temperature analysis to determine the environmental conditions  
13 for equipment qualification for DCNPP-1, which has been reported  
14 in ITRs -14, -34, and -47.

15 The verification was performed in accordance with the IDVP  
16 scope of work defined in the Phase II Engineering Program Plan,  
17 SWEC Project Procedure 5-2-2, "System Design Verification Pro-  
18 gram", and the NRC-approved Topical Report, SWQAP 1-74A, "Stone &  
19 Webster Standard Nuclear Quality Assurance Program".

20 The sample verified was defined in the Engineering Program  
21 Plan to include the temperature and pressure analyses for two  
22 representative locations outside containment, one associated with  
23 the AFW and the other associated with the CRVP. The scope of  
24 work was further defined to include a calculation by IDVP using  
25 identical input to the codes used by PGandE or service-related  
26 contractors from one specific calculation. The independent  
27 results calculated by IDVP using its codes were to be compared  
28 with the PGandE design analysis.

1 Document requests were sent to PGandE to obtain plant  
2 specific licensing documents such as Safety Analysis and Evalu-  
3 ation Reports and plant design drawings. Applicable generic  
4 licensing documents were also reviewed. The "Design Chain-  
5 Initial Sample" (ITR-29) indicated that Nuclear Service Corp.  
6 (NSC) was the only service-related contractor responsible for the  
7 subject analysis.

8 After preliminary review of the DCNPP-1 design documents,  
9 two specific locations in the auxiliary and turbine buildings  
10 were chosen for the initial sample work. The following  
11 activities were then undertaken by the IDVP to verify the  
12 analysis of those areas:

- 13 o Two independent blowdown calculations were performed  
14 for main steam line double-ended rupture in the select-  
15 ed areas.
- 16 o Independent calculations were performed of pressure and  
17 temperature transients in two areas.
- 18 o A sensitivity study was performed to compare CONTEMPT,  
19 the computer program used by NSC, to THREED, the SWEC  
20 program used in the independent analysis.

21 The computer sensitivity study revealed that CONTEMPT  
22 calculated lower temperatures and could not model adjacent com-  
23 partments properly. As a result EOI 8001 was issued to report  
24 the inappropriate application of CONTEMPT.

25 However, IDVP continued the verification procedure to deter-  
26 mine if further concerns existed. The IDVP's independent  
27 pressure and temperature calculations were performed using models  
28 and input data developed from the basic plant design documents

1 and IDVP's blowdown calculations without reference to the exist-  
2 ing NSC calculations. These independent calculations resulted in  
3 higher pressure and temperatures. The NSC analyses were then  
4 reviewed and it was determined that the calculation of computer  
5 program input data was not appropriate. Several further EOIs  
6 were issued as a result of this review, as reported in ITR-14.

7 In order to perform the above work, the IDVP performed six  
8 calculations based on input from approximately 64 drawings,  
9 reviewed five NSC calculations and two reports, and performed a  
10 field verification of as-built geometries used for input calcula-  
11 tions.

12 In parallel with this analytical design effort, the IDVP  
13 performed a QA audit and review of NSC as described in the  
14 Engineering Program Plan. Two EOIs were issued concerning the QA  
15 aspects of information used as inputs to the NSC calculations.

16 The IDVP received information concerning all the EOIs issued  
17 for this area of verification from DCP during several meetings  
18 and resolution/completion packages for each EOI. The IDVP  
19 reviewed this information and determined that the analytical  
20 errors and the QA concerns addressed in seven EOIs were not  
21 resolved. Therefore, the DCP committed to reanalyze all the  
22 pressure and temperature transients to resolve the EOIs. These  
23 were combined in EOI 8001, which was classified as a Class A/B  
24 Error.

25 Since the CONTEMPT computer program was used for areas out-  
26 side containment other than those included in the initial sample,  
27 the problem was considered to be generic and, as such, required  
28 additional verification. The additional verification was per-

1 formed on the DCP reanalysis on a sample basis as identified in  
2 ITR-34. The approach taken for this additional sample was  
3 similar to the initial sample with the exception that more areas  
4 were reviewed. Document requests were issued to obtain the cal-  
5 culations and results of the DCP reanalysis. Approximately 12  
6 calculations were reviewed and the results reported in ITR-47.

7 The DCP utilized the Bechtel Computer program FLUD to per-  
8 form the reanalysis. The IDVP performed a sensitivity study to  
9 compare FLUD and THREED with satisfactory results. The DCP  
10 results for the selected areas were compared with the IDVP  
11 independent calculations and were satisfactory. Further, the DCP  
12 calculations were reviewed to determine if the specific concerns  
13 identified in the EOI files and related to the initial sample had  
14 been addressed by PGandE. The results of this review were also  
15 satisfactory.

16 Based on these satisfactory reviews of the reanalysis, no  
17 further additional verification was required. The IDVP Final  
18 Report describes the initial sample verification in Sec-  
19 tion 4.7.6, the additional verification in Section 4.8.4, the  
20 IDVP findings in Section 5.2 and the causes of EOI 8001 in Sec-  
21 tion 6.3.4.

22 Q.25: There have been approximately 300 EOIs. Does this  
23 mean that there were 300 errors in the DCNPP-1 design?

24 A.25: (ALL) No. The opening of an EOI File meant that a  
25 condition had been identified which required additional evalua-  
26 tion to determine its significance, so a file number had been  
27 assigned to track this additional effort. If the additional  
28 effort subsequently established that an applicable license appli-



1 cation criterion had been violated, the item would be classified  
2 and reported as an IDVP Finding. Many of the EOIs were, of  
3 course, resolved without being established as errors. Further,  
4 since the significance of an EOI cannot be determined simply by  
5 looking at its eventual classification, it is very easy to over-  
6 estimate or to underestimate the significance of EOIs by a simple  
7 "counting" of the files.

8 There is also no general relationship between the eventual  
9 classification of a file and the potential for that file to  
10 indicate a generic concern. The IDVP carefully considered the  
11 generic implication of every EOI, as well as the generic implica-  
12 tions of possibly related concerns reflected in several EOIs, as  
13 described in the IDVP Final Report, Sections 5.5 and 5.6.

14 Q.26: In the judgement of the IDVP, was the scope of the  
15 IDVP sufficient to provide reasonable assurance that those  
16 aspects of DCNPP-1 design which did not meet the criteria of the  
17 license application have been identified?

18 A.26: (ALL) Yes. The initial sample and additional sample  
19 effort resulted in detailed verification of aspects of the work,  
20 a so-called vertical slice. When the IDVP identified concerns  
21 with respect to specific aspects of these samples, the IDVP work  
22 was expanded in accordance with the program plans to review those  
23 concerns as they may have affected other safety-related SSCs, a  
24 so-called horizontal slice. Thus, the IDVP program utilized a  
25 systematic approach for determining the extent of its review  
26 necessary to identify technical concerns. With respect to  
27 seismic design, the fact that the DCP undertook an essentially  
28 total review of the DCNPP seismic design, subject to verification

1 by the IDVP, provides further assurance that technical concerns  
2 were identified. Similar, but less extensive, DCP responses were  
3 made with respect to non-seismic generic concerns. For the  
4 reasons described in the IDVP Final Report and the previous  
5 testimony, in the judgement of the IDVP the scope of the IDVP was  
6 sufficient to provide the assurance sought by the Commission  
7 Order and Staff Letter, and such scope was, of course, approved  
8 by the Commission.

9 Q.27: Does this mean that the IDVP identified each and  
10 every deficiency in compliance with the criteria of the license  
11 application?

12 A.27: (ALL) No. The IDVP was not intended to do this, nor  
13 could any reasonable independent verification program. The IDVP  
14 was sufficient, and the procedures utilized to identify concerns  
15 effective, to provide reasonable assurance that those aspects of  
16 the design work on DCNPP-1 performed by PGandE or service-related  
17 contractors which did not meet the license application criteria  
18 have now been identified. This conclusion should not be inter-  
19 preted, however, to mean that the IDVP identified each and every  
20 error or questionable aspect of the design product of PGandE and  
21 its contractors or of the design process they utilized. It does  
22 mean that, in the judgment of the IDVP, there is very little  
23 likelihood that any significant undetected errors exist in such  
24 design work.

25 Q.28: Did the IDVP retain a statistician in the conduct of  
26 its program?

27 A.28: (WEC) No. Neither the Commission Order nor the Staff  
28 Letter required the use of a statistician in the IDVP efforts.

1 Appendix C of the Program Management Plans indicated that the  
2 IDVP would arrange for an evaluation of the completed program by  
3 an expert in the application of statistics to an engineered  
4 system. However, the IDVP later determined that such an evalu-  
5 ation was not required, particularly since in its review of the  
6 Phase II Program Plan the NRC Staff stated that "Rigorous  
7 statistical techniques are largely inappropriate for a design  
8 verification program" (see Enclosure 11 to SECY-82-414), and on  
9 December 9, 1982, the Commission approved "the Phase II Program  
10 Plan of June 18, 1982, including the proposed IDVP contractors as  
11 modified by the Staff in Enclosure 11 to SECY-82-414." Neverthe-  
12 less, because issues relating to the use of statistics continued  
13 to be raised by some of the interested parties, the IDVP believed  
14 that a review of its efforts by a statistician should be con-  
15 ducted. As described in Section 3.5 of the IDVP Final Report,  
16 the IDVP recommended that any proper statistical evaluation  
17 should address the efforts of both the IDVP and the DCP and con-  
18 curred in the selection of a statistician retained by PGandE.

19 Q.29: In the judgement of the IDVP, was the scope of its  
20 program sufficient without the participation of a statistician?

21 A.29: (ALL) Yes. The IDVP never intended to use  
22 statistical sampling in its verification program. The IDVP  
23 believes that the scope of its review was sufficient without the  
24 participation of a statistician because its program complied with  
25 the Program Plans for Phases I and II approved by the Commission  
26 and the Staff and because it enabled the IDVP to obtain reason-  
27 able assurance that the design of DCNPP-1 complies with license  
28 application criteria, as stated in Sections 2 and 6 of the IDVP

1 Final Report. The IDVP did not perform analyses to determine  
2 whether its sampling was "statistically valid" to any particular  
3 statistical confidence level.

4 The IDVP technical program concept employed an audit and  
5 review of design QA in parallel with an engineering program for  
6 verification of the design process in a manner which did not  
7 depend upon the effectiveness of the QA program applied in the  
8 original DCNPP-1 process. The IDVP verification samples were  
9 carefully chosen in both the seismic and non-seismic areas, and  
10 the verification was expanded whenever necessary to resolve con-  
11 cerns that were identified in our original review. All potential  
12 concerns were recorded, tracked, and resolved in a systematic  
13 manner using the EOI system, and reported in detail in ITRs. In  
14 addition, the IDVP was organized to require levels of engineering  
15 peer review by different organizations within the program to  
16 ensure the validity of all IDVP technical conclusions. The  
17 reasons for the IDVP's belief that these samples were properly  
18 chosen and suitable for the IDVP's purposes are set forth in the  
19 IDVP final Report and the ITRs, and are amply illustrated in A.19  
20 and A.24.

21 Q.30: In the conduct of its program, has the IDVP "merely  
22 checked data of inputs to models used by PGandE"?

23 A.30: (WEC, RLC, JEK) No. In its verification of seismic  
24 design, the IDVP performed a complete independent analysis of the  
25 initial sample and additional sample/verification in accordance  
26 with the Phase I Program Plan. In its verification of the CAP as  
27 defined by ITR-8, and in its verification of the DCP activities  
28 as defined in ITR-35, the IDVP used independent calculations on a

1 selected basis as part of the design verification process. In  
2 every aspect of the IDVP's seismic work, the verification process  
3 consisted of much more than merely checking data of inputs to  
4 models used by PGandE.

5 In its verification of the non-seismic design, the IDVP per-  
6 formed independent calculations or analyses, and/or independent  
7 review of PGandE calculations and analyses in accordance with the  
8 Phase II Program Plan. The majority of the Phase II non-seismic  
9 verification consisted of the performance by the IDVP of in-  
10 dependent calculations or analyses. The independent calculations  
11 and analyses performed by the IDVP used independent models devel-  
12 oped by IDVP and/or different computer programs. In its addi-  
13 tional verification of DCP-performed activities as defined by  
14 ITR-34, the IDVP used independent calculations, analyses, and/or  
15 field verification for essentially all of the verification  
16 effort. In every aspect of the IDVP's non-seismic work, the ver-  
17 ification process consisted of much more than merely checking  
18 data of inputs to models used by PGandE.

19 The full extent of the IDVP's verification efforts is  
20 spelled out in the IDVP Final Report and the ITRs, and is amply  
21 illustrated in A.19 and A.24.

22 Q.31: Did the IDVP verify the design of the Diablo Canyon  
23 Nuclear Power Plant, Unit 2?

24 A.31: (WEC) No. The IDVP's review was performed in  
25 accordance with the Commission Order and the Staff Letter, which  
26 contemplated only an independent verification of Unit 1. In  
27 addition, the IDVP completed its work in accordance with the  
28



1 Program Plans, approved by the Commission, which included only  
2 Unit 1.

3 Q.32: Was the scope of the ITP's analyses and modifications  
4 of the seismic and non-seismic aspects of the design of safety-  
5 related SSCs at DCNPP-1 sufficient for the purposes of the IDVP?

6 A.32: (ALL) Yes. The scope of the ITP's analyses and  
7 modifications was sufficient to respond to all of the IDVP's con-  
8 cerns, to permit the IDVP to complete its verification in  
9 accordance with the Program Plans, and to enable the IDVP to  
10 reach the conclusions and evaluations stated in Section 2 and 6  
11 of the IDVP Final Report. The design work performed by the ITP  
12 for verification by the IDVP is set forth in ITRs-8, -34, and -35  
13 and is discussed further in Section 3.5 of the IDVP Final Report.  
14 The results of the IDVP's verification of design activities per-  
15 formed by the ITP is set out in ITRs-45 to -49 (SWEC), ITR-51  
16 (TES) and ITRs-54 to -61, -63, -65, -67 and -68 (RLCA).

17 Q.33: In summary, in the judgment of the IDVP, was the  
18 scope of its efforts sufficient that it could properly reach the  
19 conclusions and evaluations stated in Sections 2 and 6 of the  
20 IDVP Final Report?

21 A.33: (ALL) Yes.  
22  
23  
24  
25  
26  
27  
28

1        CONTENTION 5

2        "The verification program has not verified that Diablo  
3        Canyon Units 1 and 2 'as built' conform to the design drawings  
4        and analyses."

5        Q.1: As part of its verification of non-seismic design, did  
6        the IDVP perform field verifications of implementation of the  
7        design of the DCNPP-1?

8        A.1: (WEC, JEK) Yes.

9        Q.2: Please explain how such field verifications were per-  
10       formed.

11       A.2: (JEK) As described in the Phase II Program Plan, the  
12       IDVP performed independent field verifications to ensure that the  
13       safety-related SSCs in its sample are configured in the same  
14       manner as described in the PGandE design documents used in the  
15       IDVP analysis or calculations. The IDVP also independently field  
16       verified all modifications performed by the DCP to resolve EOIs.  
17       However, the field verifications did not necessarily include all  
18       of the aspects normally associated with a complete "as-built"  
19       review, such as material selection and application, fabrication,  
20       examination and inspection (including the pre-service inspection  
21       requirements), system installation requirements, system cleaning,  
22       pre-operational testing or wiring checkout, unless these were  
23       specifically required to support the IDVP's conclusions.

24       The specific IDVP field verifications of as-built conditions  
25       are described in detail in various ITRs. For example, ITR-18  
26       describes the field verification of the as-built location of AFW  
27       and CRVP system electrical cables/wires to ensure that FSAR  
28       separation requirements were satisfied. This ITR also describes  
29       the field verification of the fire zone separation/barriers,

1 detection system, suppression system, and special hazards control  
2 for areas containing AFW and CRVP system components to ensure  
3 that they were installed in accordance with licensing commit-  
4 ments. Additional descriptions of the IDVP non-seismic field  
5 verifications are contained in ITRs -14, -19 through -28, -48,  
6 and -49.

7 Q.3: As part of its verification of seismic design, did the  
8 IDVP perform field verifications of the implementation of the  
9 design of the DCNPP-1?

10 A.3: (WEC,RLC) Yes.

11 Q.4: Please explain how such verifications were performed.

12 A.4: (RLC) Field verifications were performed as part of  
13 the seismic design verifications of the initial samples, the ad-  
14 ditional verifications, and the verification of the CAP.

15 A field verification was performed for the purpose of deter-  
16 mining if an SSC was configured in the manner for which it was  
17 qualified. The word "configured" was used in the IDVP program  
18 plans to emphasize that the field verification was a part of the  
19 design verification process and that there was no intention to  
20 include the aspects of material selection and application, fabri-  
21 cation, examination, or inspection. The purpose was to gain  
22 reasonable assurance that the as-built dimensions were properly  
23 established and used in the design process or in the verification  
24 program. As with all IDVP activities, the IDVP applied the  
25 criteria on configurations which were intended to be used during  
26 the licensing process. For example, in evaluating the as-built  
27 configuration of piping systems, the acceptance criteria were  
28 those used with I&E Bulletin 79-14.

1       The specific field verifications performed are described in  
2 detail in the various seismic-related ITRs. Of particular sig-  
3 nificance in this regard, because the CAP effort superseded the  
4 earlier activities as described in A.17 of the Testimony on Con-  
5 tentions 1 and 2, are the ITRs numbered above -50, with the  
6 exception of ITR-68. In each case the field verification was  
7 performed by a joint RLCA-TES team working with specific check-  
8 lists. Field verifications were performed as required with  
9 respect to the specific DRPs being verified, were sometimes per-  
10 formed before selection of the DRPs either to assist in the  
11 IDVP's understanding of the methodology or to help to select the  
12 DRPs, and were performed as a part of the "completion sample" to  
13 assure that intended modifications had been implemented.

14       Q.5: Did the IDVP include within its scope any other veri-  
15 fication relating to the conformance of the DCNPP-1 "as-built" to  
16 design drawings?

17       A.5: (WEC, RFR) Yes. As part of the audit of the implemen-  
18 tation of the CAP, RFR audited the procedures for engineering  
19 review of design changes recommended in the field and the related  
20 procedures for incorporating field changes into the final design  
21 drawings. The audit of implementation of the CAP process for  
22 controlling the as-built update of engineering documents included  
23 both the method for controlling design changes and the update of  
24 documents to as-built conditions. The interfaces involved both  
25 DCP internal activities (among engineering design groups and  
26 between engineering and construction) and DCP external activities  
27 (between PGandE and outside contractors). ITR-41 concluded that  
28

1 this portion of the QA program was being implemented in a full  
2 and effective manner.

3 Q.6: Based upon the work performed by the IDVP, what con-  
4 clusions has the IDVP reached with respect to whether the "as-  
5 built" condition of the DCNPP-1 conforms to final design docu-  
6 ments?

7 A.6: (ALL) The IDVP has not performed an as-built walkdown  
8 of DCNPP-1. However, the IDVP has determined that the as-built  
9 condition of those aspects of the DCNPP-1 that it field-verified  
10 properly implement the essential design elements reviewed by the  
11 IDVP.

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28



1     CONTENTION 6

2             "The verification program failed to verify that the design  
3 of safety related equipment supplied to PGandE by Westinghouse  
met licensing criteria."

4             Q.1: Did the IDVP verify that the design of safety-related  
5 equipment provided to PGandE by Westinghouse met licensing cri-  
6 teria?

7             A.1: (ALL) No. However, the IDVP did verify the  
8 Westinghouse/PGandE interfaces. This verification was initially  
9 performed in response to EOIs 976, 978 and 1004 which were opened  
10 because of concerns identified by RLCA in its November 1981 Pre-  
11 liminary Report. The specific issues included questions concern-  
12 ing transmittals of information and the Westinghouse use of a  
13 tau-corrected spectrum in computing a vertical design response  
14 spectrum, rather than the uncorrected spectrum as required by the  
15 Hosgri Report. The need for verification of this interface was  
16 also recommended by the NRC Staff in SECY-82-414, and this recom-  
17 mendation was approved by the Commission. Since the non-seismic  
18 Phase II efforts described below were also in progress at the  
19 time the Staff recommendation was made, the IDVP did not consider  
20 this Commission-approved Staff recommendation to be an expansion  
21 of its planned program. Rather, it was considered as further  
22 assurance that the IDVP plans were consistent with the NRC  
23 requirements.

24             ITR-11 reports the Phase I verification of this interface  
25 with respect to seismic considerations. This ITR was prepared by  
26 TES based upon an in-house audit of Westinghouse and subsequent  
27 review of the information obtained from Westinghouse. The veri-  
28 fication included the interface for transmittal of the Hosgri

1 spectra and the review, on a sampling basis, of the Westinghouse  
2 use of the Hosgri spectra in its qualification and evaluation  
3 process. ITR-11 concluded that the Hosgri spectra were being  
4 properly transmitted by PGandE and properly received, controlled,  
5 and applied by Westinghouse. This verification provides reason-  
6 able assurance that this aspect of the design of Westinghouse-  
7 supplied equipment was properly performed.

8 In the Phase II Program, the IDVP verified that Westinghouse  
9 obtained from PGandE and used the correct design parameters for  
10 the AFW in its analysis of accidents identified in Chapter 15 of  
11 the FSAR. (See ITR-22 and IDVP Final Report, Section 4.1.3.) The  
12 IDVP also performed independent calculations to verify that con-  
13 densate storage tank capacity and required AFW flow rates speci-  
14 fied by Westinghouse were met by PGandE's design. In addition,  
15 RFR's Phase II QA audit and review also included an examination  
16 of the interface between PGandE and Westinghouse. (See ITR-42  
17 and IDVP Final Report, Section 4.1.3.) Based upon the work de-  
18 scribed above, the IDVP verified that the PGandE/Westinghouse in-  
19 terface for the NSSS system included appropriate controls for the  
20 transfer of design information and that the NSSS vendor used the  
21 applicable information.

22 Q.2: Why was the design of Westinghouse equipment excluded  
23 from the scope of the IDVP?

24 A.2: (WEC) The Commission Order and the Staff Letter re-  
25 quired an independent verification of the design work of PGandE  
26 and service-related contractors. This was interpreted as not in-  
27 cluding design work of vendors of systems and equipment, such as  
28 Westinghouse. Accordingly, the Program Plans submitted to, and

1 approved by, the Commission specifically excluded design work  
2 performed by Westinghouse.

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

1     CONTENTION 7

2             "The verification program failed to identify the root causes  
3     for the failures in the PGandE design quality assurance program  
   and failed to determine if such failures raise generic concerns."

4             Q.1: Did the IDVP ascertain the "root" or "basic" causes of  
5     the design errors it identified during the Program?

6             A.1: (ALL) Yes. The Commission Order and the Staff Letter  
7     directed that the IDVP assess and report the basic causes of all  
8     design errors identified during the program. This was done close  
9     to the conclusion of the IDVP program and was based upon a back-  
10    ward look at all of the deficiencies identified by the IDVP. The  
11    IDVP's determinations of basic cause are reported in the IDVP  
12    Final Report, Section 6.3.

13            Q.2: In the judgment of the IDVP, what were the basic  
14    causes of the design errors it identified?

15            A.2: (ALL) The two basic causes of design errors identified  
16    by the IDVP, in addition to random causes, were control of design  
17    interfaces and documentation and interpretation of design.  
18    However, the basic causes can only be properly addressed in light  
19    of several underlying factors that, in combination, contributed  
20    significantly to most of the design problems. These factors are  
21    identified in the IDVP Final Report as follows:

22            (1) Safety-related systems were seismically designed twice  
23               to meet two sets of criteria, with a substantial time  
24               interval between the two design efforts.

25            (2) The plant had substantial design work performed as a  
26               result of I&E bulletins and TMI requirements.

27            (3) The design work was performed over a period of 15  
28               years.

1           (4) Seismic design methodology and criteria changed signif-  
2           icantly during the 15 years from a rudimentary to a  
3           reasonably mature, systematic, and sophisticated  
4           process.

5           (5) Nuclear plant design naturally requires the transfer of  
6           large amounts of information from one design group to  
7           another; such design interfaces existed in especially  
8           large numbers both within PGandE and between PGandE and  
9           its service-related contractors.

10          (6) Design control practices acceptable during the period  
11          of the initial design process were not consistent with  
12          the eventual duration and complexity of the reiterative  
13          design process required at DCNPP.

14          Q.3: Is the IDVP satisfied that the consequences of these  
15          basic causes were identified and corrected?

16          A.3: (ALL) Yes. Although the basic causes were not ex-  
17          plicitly identified until late in the program, they involved  
18          aspects of the design process which had been carefully reviewed  
19          throughout the program.

20          Because of the known concerns about control of design inter-  
21          faces, the IDVP had paid particular attention to review of the  
22          flow of information among PGandE and its contractors and within  
23          PGandE. This concern was addressed by both QA and design process  
24          verification efforts and, in the case of the CAP, by the "design  
25          office verification" procedure developed specifically by the IDVP  
26          to assure that the QA procedures and their implementation were  
27          adequate to the specific design aspects.



1 With respect to the documentation and interpretation of de-  
2 sign, the IDVP was sensitive to the possibility that any identi-  
3 fied deficiencies in these areas could have generic impacts.  
4 Thus, throughout the verification efforts, criteria and method-  
5 ology were carefully defined and documented so as to assure that  
6 generic concerns associated with problems in documentation and  
7 interpretation of design were identified and resolved.

8 Q.4: Did the IDVP identify generic concerns associated with  
9 design errors identified during its program?

10 A.4: (ALL) Yes. The IDVP reviewed every EOI resulting from  
11 the verification effort for generic concerns and resolved all  
12 such generic concerns as part of the verification effort. As  
13 discussed in A.22 of the Testimony on Contentions 1-2, the  
14 identification of generic concerns was an important part of the  
15 IDVP.

16 Q.5: Did the identification of basic causes later in the  
17 program result in any new generic concerns?

18 A.5: (ALL) No. The verification effort for the initial  
19 samples and additional sample/verification were performed under  
20 the assumption that design QA was deficient, and the basic causes  
21 identified turned out to be design QA related. Since the IDVP  
22 assumed inadequate design QA in developing the IDVP programs, the  
23 identification of root causes which were actually associated with  
24 QA deficiencies was no surprise to the IDVP and did not result in  
25 a requirement for additional expansion.

26 Q.6: In his answers to interrogatories (e.g., Answer No. 66  
27 to Applicant's Second Set of Interrogatories), Governor  
28 Deukmejian appears to criticize the IDVP for allegedly failing to

1 identify the underlying cause for any EOI. Did the IDVP ignore  
2 causation in resolving EOIs?

3 A.6: (ALL) No. In resolving every EOI, the IDVP not only  
4 disposed of the specific concern raised by the EOI, but determin-  
5 ed whether there existed a generic concern, as described in A.22  
6 of the Testimony on Contentions 1 and 2. Obviously, in some  
7 cases it was necessary to examine the cause of the EOI as part of  
8 the specific concern which had to be remedied; while in other  
9 instances the cause of the EOI led to its being designated as a  
10 generic concern. Although the IDVP documentation did not neces-  
11 sarily include a specific label for "cause", in the case of each  
12 EOI the IDVP determined whether the factors relating to the cause  
13 of the EOI required that any additional action be taken.

14 To the extent that Governor Deukmejian is suggesting that  
15 the IDVP, in addition to dealing with causation as described  
16 above, should also have separately identified the "basic cause"  
17 of each and every EOI, the IDVP believes that such an exercise  
18 was wholly unnecessary. In the IDVP's view, assessment of basic  
19 cause (as such term was used by the IDVP) is more meaningful when  
20 it can encompass a review of all the deficiencies identified in  
21 an entire program, rather than by focusing on isolated items.  
22 This is what the IDVP did as reported in Section 6.3 of the Final  
23 Report.

24 Q.7: Has the IDVP neglected "to identify the root causes  
25 for the failures in the PGandE design quality assurance program,"  
26 as alleged in Contention 7?

27 A.7: (ALL) As explained in A.1 above, the IDVP identified  
28 two basic causes for the design errors identified by it. Each of

1 these causes related to some extent to a QA function: control of  
2 design interfaces and inadequate documentation of design. If  
3 this ambiguous contention is alleging that the IDVP should have  
4 ascertained the basic causes associated with QA deficiencies, the  
5 IDVP has in part done so in its discussion of basic causes and  
6 the underlying factors which contributed to them. (See A.2 above  
7 and discussion of "Fundamental Factors" in IDVP Final Report,  
8 Section 6.3.1.)

9 However, if the contention alleges that the IDVP should  
10 automatically have ascertained the basic cause (as such term was  
11 used by the IDVP) of each identified deficiency in the PGandE  
12 design QA program, this was neither done nor necessary, as dis-  
13 cussed in A.6. Moreover, as discussed in A.5, the IDVP program  
14 for verification of design was structured to verify conformance  
15 of the design of DCNPP-1 to license criteria without reliance on  
16 the effectiveness of a design QA program. Thus, no purpose would  
17 have been served by inquiry by the IDVP into the basic causes of  
18 design QA deficiencies.

19 Q.8: Does this mean that the IDVP may have failed to ident-  
20 ify generic concerns with the design of the DCNPP-1 that could  
21 have resulted from failures in the PGandE design QA program?

22 A.8: (ALL) No. IDVP's confidence that this has not  
23 occurred is based upon the IDVP's exhaustive review which, as  
24 stated above, included a detailed search for the type of generic  
25 concerns which could result from design QA deficiencies (e.g.,  
26 concerns relating to interface control, checking of calculations,  
27 etc.).  
28

1        CONTENTION 8

2        "The ITP failed to develop and implement in a timely manner  
3        a design quality assurance program in accordance with 10 CFR Part  
4        50, Appendix B to assure the quality of the recent design modifi-  
5        cations to the Diablo Canyon facility and the IDVP failed to  
6        ensure that the corrective and preventative action programs  
7        implemented by the ITP are sufficient to assure that the Diablo  
8        Canyon facilities will meet licensing criteria."

9        Q.1: Did the IDVP perform an audit of the implementation of  
10       the DCP design QA program for the ITP?

11       A.1: (WEC, RFR) RFR audited that portion of the ITP work  
12       which was performed as part of the CAP. Other work performed by  
13       the ITP was outside of the RFR audit scope, as specified in ITR-  
14       8.

15       Q.2: Why was this audit performed?

16       A.2: (WEC, RLC, RFR) Both the Phase I and Phase II IDVP  
17       Program Plans required the IDVP to verify any PGandE corrective  
18       action resulting from the design verification performed by the  
19       IDVP. The CAP was considered such a corrective action, and the  
20       IDVP issued ITR-8 to describe the IDVP's verification of CAP  
21       activities. ITR-8 committed the IDVP to perform an audit of the  
22       DCP QA program implementation commencing August 20, 1982.

23       Q.3: When was the audit performed?

24       A.3: (RFR) An initial audit of the CAP was performed during  
25       the period of November 11, 1982 through December 7, 1982. A  
26       follow-up audit was performed on March 17, 1983.

27       Q.4: Why was the initial audit not performed until November  
28       11, 1982?

29       A.4: (WEC, RFR) The DCP QA program, initially submitted for  
30       NRC review and approval on June 18, 1982, was found acceptable by  
31       the NRC on August 2, 1982, and was approved contingent upon DCP

1       submittal of revisions which addressed NRC comments. The DCP  
2       response to the NRC comments was submitted on August 13, 1982.

3       ITR-8 was issued on October 5, 1982. On October 27, 1982, a  
4       pre-audit scoping meeting was held between the IDVP and DCP for  
5       the purpose of reviewing the status of DCP work which was per-  
6       formed as part of the CAP and which was, therefore, within the  
7       audit scope. As a result of this meeting, RFR scheduled the  
8       initial audit on November 11, 1982 in order to provide an early  
9       evaluation of the effectiveness of the CAP's implementation of  
10      the DCP design QA program.

11      Q.5: Please explain how RFR prepared for the initial audit.

12      A.5: (RFR) Preparations for the audit occurred in several  
13      steps. Initially, RFR obtained and reviewed the DCP QA manual  
14      and implementing procedures. An audit team was selected, con-  
15      sisting of experienced design control auditors, all of whom were  
16      qualified to ANSI 45.2.23. After the October 27 meeting with  
17      representatives of the DCP, audit checklists were prepared using  
18      the DCP QA manual and implementing procedures as the basis to  
19      cover every significant commitment of the DCP QA program.

20      Two checklists were developed: one was designed to audit  
21      CAP internal design activities and the other to audit internal  
22      and external interface controls. During the preparation of these  
23      checklists, RFR also reviewed the QA procedures for conformance  
24      to the commitments of the DCP QA manual. Finally, members of the  
25      audit teams were instructed as to the checklists and assigned  
26      audit areas by the team leaders.

27      Q.6: Please explain how RFR conducted the initial audit.



1           A.6: (RFR) A pre-audit conference was held with representa-  
2           tives of the DCP on November 11, 1982 to discuss the audit scope.  
3           For the actual audit, the audit team was then split into four  
4           sub-teams consisting of civil/structural, electrical and instru-  
5           mentation and controls (I&C), mechanical/piping, and adminis-  
6           trative controls. The audit team for each engineering discipline  
7           then selected representative design activities within that team's  
8           area. Using the design activities associated with each dis-  
9           cipline, each audit team determined whether the CAP had complied  
10          with the checklist items by reviewing design documents, memos,  
11          letters, audit reports, EOIs and other DCP documentation. At the  
12          conclusion of each day of auditing, an administrative meeting to  
13          discuss audit status and schedule was held between the audit team  
14          members and representatives of the DCP.

15          Q.7: Please describe the results of the initial audit.

16          A.7: (RFR) The initial audit showed that a number of design  
17          and QA activities were incomplete at the time of the audit or not  
18          yet fully documented. As a result, insufficient completed docu-  
19          mentation was available to determine accurately the adequacy of  
20          the DCP QA program implementation. Twenty-four (24) conditions  
21          or areas that were found to be incomplete were identified in the  
22          first audit for subsequent follow-up by the IDVP.

23          Q.8: Did the IDVP consider that the DCP did not implement  
24          its design QA program in a timely fashion because of the aspects  
25          of the design QA program that were not fully implemented at the  
26          time of the IDVP's first audit?

27          A.8: (WEC, RFR) No. The QA program was determined to be  
28          implemented in a timely manner.

1 Q.9: When did the IDVP conduct its follow-up audit?

2 A.9: (RFR) The follow-up audit was conducted on March 17,  
3 1983.

4 Q.10: Why did RFR wait until that time?

5 A.10: (RFR) RFR waited to conduct a follow-up audit to  
6 allow for design activities performed by the CAP to progress to a  
7 point where a sufficient volume of documentation had been com-  
8 pleted that could then be reviewed to assess adequately the  
9 overall implementation of the QA program. During the period be-  
10 tween the two audits, RFR was in communication with the other  
11 IDVP organizations and, through this communication, was able to  
12 select the earliest date for a follow-up audit which was con-  
13 sistent with the required status of completion of CAP design  
14 activities.

15 Q.11: Did RFR prepare for and conduct the follow-up audit  
16 in the same manner as the initial audit?

17 A.11: (RFR) Yes, except for a few differences. Initially,  
18 the follow-up included a specific review of the 24 conditions  
19 noted during the first audit. For each of these conditions the  
20 documentation looked at earlier was again requested and reexamined  
21 to determine the adequacy of correction or completion, and  
22 documents not available initially were requested and examined to  
23 determine compliance with QA program commitments. Finally,  
24 responsible DCP personnel were questioned to determine whether  
25 they understood the requirements of the QA program.

26 Q.12: Please describe the results of the follow-up audit.

27 A.12: (RFR) RFR's conclusion, based upon the information  
28 obtained during the follow-up audit, was that the open or unre-

1 solved items from the previous audit were satisfactorily re-  
2 solved, and no new items of non-compliance were identified.

3 Q.13: Based upon the results of the audits of the CAP, did  
4 the IDVP identify any generic concerns as to the overall DCP QA  
5 program?

6 A.13: (WEC, RFR) No.

7 Q.14: Did the IDVP conduct any further audit of the imple-  
8 mentation of the DCP QA program?

9 A.14: (WEC, RFR) No. The audits of the CAP showed that the  
10 DCP QA program, under which all ITP work was being done, was  
11 being effectively implemented, and it was therefore determined  
12 that no further audits were necessary. This is standard practice  
13 for the conduct of QA audits.

14 Q.15: In addition to auditing the performance of the CAP QA  
15 program, did the IDVP also verify the DCP's control of informa-  
16 tion across design interfaces?

17 A.15: (RFR) Yes. Design interface controls were verified  
18 during the CAP audit conducted on December 6 and 7, 1982, and as  
19 part of each of the Design Office Verification (DOV) audits.

20 Q.16: Please describe the DOV audits performed by the IDVP.

21 A.16: (WEC, RLC, RFR) ITR-8 required that interface control  
22 and project indoctrination be verified by the IDVP for each  
23 subject where design process verification was required. RFR per-  
24 formed these aspects of the DOV between December 20, 1982 and  
25 March 11, 1983. Audit teams verified technical interface con-  
26 trols and project indoctrination in order to assure that the  
27 Hosgri and non-Hosgri seismic design inputs were correctly trans-  
28 lated into applicable design documents and across design inter-

1 faces using the most recent inputs. The audit was performed by  
2 tracking seismic inputs from the ground acceleration values to  
3 each seismic Category I structure and to the building floor  
4 spectra applicable to the piping design documents sampled. The  
5 DOV also verified that computer programs used in the seismic  
6 design analyses had been verified by the DCP. As described in  
7 ITR-41, the DOV was performed in the areas of mechanical equip-  
8 ment, the auxiliary building, the intake structure, large bore  
9 piping and supports, instrument tubing and supports, the fuel  
10 handling building, the turbine building, the HVAC system,  
11 electrical equipment and instrumentation, small bore piping and  
12 supports, electrical raceway supports and the containment struc-  
13 ture. The DOV was conducted by selected professionals experi-  
14 enced in design control and qualified to ANSI N45.2.23 . The  
15 audit team used a checklist based upon ITR-8 and the DCP QA  
16 program procedures applicable to the control of the design inter-  
17 faces, training and the verification of computer programs.

18 Q.17: What were the results of the DOV?

19 A.17: (WEC, RFR) The DOV showed that control of internal  
20 and external interfaces was adequate to assure the use of correct  
21 seismic inputs and the correct translation of seismic inputs into  
22 corresponding design documents. The auditors also determined  
23 that design personnel using seismic information were aware of the  
24 applicable QA program controls and that computer programs that  
25 were used by the DCP were appropriately verified.

26 Q.18: What are the overall conclusions reached by the IDVP  
27 on the basis of its audit of the DCP QA program and the DOV?  
28

1           A.18: (WEC, RFR) As a result of the CAP audits and the DOV,  
2 the IDVP concluded that the DCP QA program was effectively imple-  
3 mented. The IDVP's conclusions are reported in ITR-41 and in the  
4 IDVP Final Report, Section 4.2.

5           Q.19: Did the IDVP also verify the engineering work of the  
6 ITP as applied to corrective actions apart from its verification  
7 of the DCP QA program?

8           A.19: (WEC, RLC, JEK) Yes. The IDVP conducted a detailed  
9 engineering peer review on a sampling basis, similar to that per-  
10 formed in the verification of the initial samples, and in  
11 accordance with the Program Plans. The peer review, conducted by  
12 RLCA, TES, and SWEC, was conducted in accordance with the method  
13 prescribed in the Program Plans. The areas where this verifica-  
14 tion was to be performed, along with the approach to be used,  
15 were specified in ITRs -8, -34, and -35. The results of the IDVP  
16 review of DCP corrective actions is presented in the series of  
17 corrective action ITRs (ITRs -45 to -49, -51, -54 to -61, -63, -  
18 65, -67, and -68) issued to document the results of the IDVP peer  
19 review.

20           Q.20: What were the results of the IDVP's peer review of  
21 the ITP?

22           A.20: (WEC, RLC, JEK) The IDVP determined that the ITP has  
23 been effective in resolving earlier EOIs and in reviewing the  
24 seismic design of the DCNPP-1. The IDVP's verification of the  
25 activities of the ITP resulted in 26 new EOIs, each of which was  
26 subsequently resolved and closed.

1 Q.21: In the judgment of the IDVP, does the issuance of  
2 these EOIs indicate that the design work performed by the ITP was  
3 not being performed in a competent manner?

4 A.21: (WEC, RLC, JEK) No. The EOIs do not necessarily  
5 represent a confirmed violation of license criteria, but rather  
6 are a vehicle established by the IDVP to indicate an area which  
7 requires further investigation before the IDVP can reach a deci-  
8 sion on whether it will impact on the satisfaction of licensing  
9 criteria. Of the 26 EOIs identified in this portion of the  
10 program only 1 was later designated as a Finding. Thus, of the  
11 tremendous volume of design work reviewed, the IDVP found only a  
12 very limited area where the ITP did not initially demonstrate  
13 compliance with the licensing criteria.

14 Q.22: In the judgment of the IDVP, does the issuance of  
15 these EOIs indicate that the ITP was not implementing its design  
16 QA program properly?

17 A.22: (ALL) No. The fact that an EOI file was opened as to  
18 a technical issue does not necessarily mean that there is either  
19 a design error or a breakdown in the DCP QA program - only that a  
20 technical question exists. No EOIs were issued by RFR identify-  
21 ing any inadequacy in the DCP QA program implementation.

22 Q.23: In the judgment of the IDVP, has the ITP developed  
23 and implemented in a timely manner the design QA program approved  
24 by the NRC?

25 A.23: (ALL) Yes. The IDVP's conclusion is based upon the  
26 audits and verifications it has performed, as described in this  
27 testimony. The EOIs issued by the IDVP do not detract from the  
28 conclusion reached by the IDVP.