

Washington Public Power Supply System

Box 1223

Elma, Washington 98541-1223

(206)482-4428

Docket No. 50-508
November 22, 1983
G03-83-893

Director of Nuclear Reactor Regulation
ATTN: Mr. G. W. Knighton, Chief
Licensing Branch No. 3
U. S. Nuclear Regulatory Commission
Washington, D. C. 20555

Subject: NUCLEAR PROJECT 3
RESPONSES TO NRC QUESTIONS

In accordance with the guidance of Generic Letter 82-14, the Supply System hereby submits 40 copies of responses to the NRC's requests for Additional Information as shown.

In preparing this submittal it was necessary to revise several large Tables from the FSAR. Since as a practical matter it is quite difficult to include a copy of each for each copy of this letter, the NRC Licensing Project Manager will receive three copies of each for Distribution.

This situation has been discussed with the NRC Licensing Project Manager for WNP-3.

8312060322 831122
PDR ADOCK 05000508
A PDR

Boo1
1/40

Mr. G. W. Knighton
Page 2

NUCLEAR PROJECT 3 RESPONSES TO NRC QUESTIONS

If you require additional information or clarification, the Supply System Point of Contact for this matter is Mr. D. W. Coleman, Licensing Project Manager (206/482-4428 ext. 5436).

Sincerely,

D. W. Coleman for

G. C. Sorensen, Manager
Regulatory Programs

GCS/kh

Attachments: 1. NRC Question No. 430.21
 2. NRC Question No. 430.36
 3. NRC Question No. 430.37
 4. NRC Question No. 430.61
 5. NRC Question No. 430.64
 6. NRC Question No. 450.6
 7. NRC Question No. 450.12
 8. NRC Question No. 460.1
 9. NRC Question No. 471.6
 10. NRC Question No. 480.13
 11. NRC Question No. 480.17
 12. NRC Question No. 480.18
 13. NRC Question No. 480.21

cc: P Christofakis - Ebasco NYO
 N. S. Reynolds - D & L
 J. A. Adams - NESCO
 D. Smithpeter - BPA
 A. Vietti - NRC
 A. A. Tuzes - CE
 Ebasco - Elma
 WNP-3 Files

Question No.

- 430.21 (SRP 9.5.4) Discuss the precautionary measures that will be taken to assure the quality and reliability of the fuel oil supply for emergency diesel generator operation. Include the type of fuel oil, impurity and quality limitations as well as diesel index number or its equivalent, cloud point, entrained moisture, sulfur, particulates and other deleterious insoluble substances; procedure for testing newly delivered fuel, periodic sampling and testing of onsite fuel oil (including interval between tests), interval of time between periodic removal of condensate from fuel tanks and periodic system inspection. In your discussion include reference to industry (or other) standard which will be followed to assure a reliable fuel oil supply to the emergency generators.

Response

The specific standards that will be followed to assure a reliable supply of fuel oil to the emergency diesel generators are:

- (1) ASTM-D240-65, Standard Method of Sampling Petroleum and Petroleum Products.
- (2) ASTM-D975-74, Standard Classification of Diesel Fuel Oils.
- (3) Manufacturers Diesel Fuel Recommendations, Maintenance Instruction 1750 Rev. D, March 1973, EMD - General Motors Corporation.

The fuel is No. 2-D and meets the requirements of the following specifications:

<u>Requirement</u>	<u>Specification 2</u>	<u>Analysis Method</u>
1. Cetane Number	50 min, 57 max	ASTM-D-613
2. 90% Boiling Pt	600 max	ASTM-D-86
	----	ASTM-D-86
Final Boiling Pt	625°F max	ASTM-D-86
Distillation Recovery	99.0%	ASTM-D-86
3. Total Sulphur	.2% max not to exceed legal limit	ASTM-D-129 or ASTM-D-1552
4. Copper Strip Corrosion 3 hr @ 212°F	No. 1 Strip or better	ASTM-D-130 Modified
5. Carbon Residue 10% bottoms	.15% max	ASTM-D-189 or ASTM-D-524

Question No.

430.21

Response (Cont'd)

<u>Requirement</u>	<u>Specification 2</u>	<u>Analysis Method</u>
6. Ash, wt%	trace max	ASTM-D-482
7. Water and Sediment	trace max	ASTM-D-96
8. Cloud & Pour Point	ASTM-D-975	ASTM-D-2500
9. Flash Point	150°F min	ASTM-D-93
10. Organic Chlorides	20ppm max total chloride	UOP Method 395
11. Filtration Cleanliness	1.3 mg/l max on 0.80 Micron Filter	ASTM-D-2276
12. ASTM Color	1.0 max	ASTM-D-1500
13. Viscosity, 100°F Kinematic, est.	2.4 min ----	ASTM-D-445
14. Gravity, API	37 max	ASTM-D-287
15. Thermal stability 16 hr	15 mg max	ASTM-D-2274
16. Aniline Point, F	115 min	ASTM-D-611
17. Neutralization Number	0.2 max	ASTM-D-974

Representative samples shall be collected from new delivered fuel.

Representative samples of diesel fuel from the diesel fuel storage tanks will also be collected quarterly (every 92 days).

Viscosity, API gravity, water and sediment, and flash point will be determined for each sample. If the diesel fuel does not meet the manufacturer's specifications it will be replaced or, in the case of water and sediment, treated to remove impurities.

See the response to Q430.17 concerning the removal of water from the diesel fuel storage tanks.

Question No.

430.36 Provide the design dew point temperature ($^{\circ}\text{F}$) for the compressed (SRP 9.5.6) air as it leaves the refrigerant air dryers. Show that the design dew point will be at least 10°F lower than the lowest possible ambient temperature in the diesel generator room. Discuss the procedures that will be implemented to ensure that compressed air dew point design is maintained and that moisture does not collect in the air receivers.

Response

The compressed air design dew point temperature is 35°F (1.7°C). This temperature is maintained in the heat exchanger automatically by a thermostat that controls the operation of the refrigeration system. The moisture is collected in the condensate separator and is periodically drained (see response to Question 430.37). As described in Subsection 9.4.5.2.1, the lowest ambient temperature in the DG room is 60°F during all conditions of operation and varying outside air temperature. This is 25°F higher than the automatically maintained design dew point temperature of 35°F .

Table 9.5.6-1 will be amended to reflect the design dew point of the diesel generator compressed air system.

TABLE 9.5.6-1

DIESEL GENERATOR STARTING SYSTEM EQUIPMENT DESIGN DATA1. Air Compressors

Operator	motor, 15 HP, 3 ph, 60 Hz, 460V	1
Design Pressure, psig	700	
Design Temperature, F	139	
Quantity/Engine	2	
Seismic Category	I	

2. Air Receivers

Volume ft ³	54.7	1
Design Pressure, psig	700	
Design Temperature, F	139	
Quantity/Engine	2	
Seismic Category	I	
ASME Section	III	

3. Air Dryers

Type	Refrigerant	1
Design Pressure, psig	700	
Design Temperature, F	139	
Quantity/Engine	2	
Seismic Category	I	

4. Shutdown Air Accumulator

Volume, Cu. inches	230	1
Design Pressure, psig	700	
Operating Pressure, psig	670	
Design Temperature, F	140	
Quantity/Engine	1	
ASME Section	III	

DESIGN Dew
Point, F

35

Q 430.36
SCN 570

Question No.

430.37 Describe the provisions in the design of your compressed air
(SRP 9.5.6) system which prevent accumulation of dirt and oil in the receiver
and/or other parts of the system.

Response

The Ingersoll-Rand refrigeration type air dryers are installed between the air compressors and receivers. They are utilized to remove moisture, dirt, oil vapor and other contaminants from compressed air. The moisture, dirt and oil vapor are collected in the air dryers (condensate separator) and periodically drained and cleaned in accordance with the procedure provided in Vendor Instruction Manual.

Subsection 9.5.6.2 will be amended to reflect the response to this question.

INSERT 1

and foreign materials. Both air starting systems are used for normal starts. Therefore, the combined capacity of the dual train system is 10 cold start cycles without recharging the air receivers. The average expected cranking cycle duration is three to three and one half seconds. A limit switch is provided to limit the duration of cranking cycle to a maximum of seven seconds. If this duration exceeds seven seconds the air supply for cranking will be shutoff. The air receivers are provided with a pressure switch to start and stop the compressor as required. Each air train is provided with a low pressure alarm. The compressors are not required during the starting operation or during diesel engine operation. Two complete automatic refrigerant type air dryers on the discharge side of the air compressors provide moisture-free air by reducing the air dewpoint for starting and control. A check valve located upstream of the air receiver ensures that a broken line in the non-safety portion of the piping will not result in a sudden loss of air. The main air start control valve and air start solenoid valves are used for startup of the system.

A shutdown air accumulator with a solenoid operated shutdown valve is provided, which holds enough air trapped by a check valve on the upstream of the accumulator to close the fuel racks to shut the diesel engine down even if both starting air systems lose pressure. The design data for major components of this system is shown in Table 9.5.6-1.

9.5.6.3 Safety Evaluation

The portion of the diesel generator starting system between the diesel generator and the first check valves upstream of the air receivers is classified as Nuclear Safety Class 3 and designed to ASME Section III, Class 3, seismic Category I requirements to ensure system operation during an SSE. The non-safety portions of the starting air system are designed in accordance with the applicable codes and standards listed in Table 9.5.4-2. The system is shown on Figure 9.5.6-1.

The air starting systems for one diesel are physically and electrically separated from those for the other diesel to assure that no single failure can cause malfunction of both divisions of standby ac power.

The single failure criterion is satisfied and significantly enhanced by having a dual train air starting system for each diesel generator.

The dual train starting system ensures that a failure of any components of any train cannot cause loss of system ability to start the diesel, to supply emergency power, so as to safely mitigate the consequences of an accident and safely shutdown the reactor. A failure in the non-safety portion of the system piping will not have any impact in the safe operation of the system. A failure mode and effects analysis of the DGSS is presented in Table 9.5.6-2.

9.5.6.4 Inspection and Testing Requirements

The system will be operated and tested initially with regard to flow path, flow capacity and mechanical operability in accordance with Section 14.0. To

Q430.37

SCN571

Question 430.37

INSERT 1

Moisture, dirt, oil vapor are removed from the compressed air. They are collected in the condensate separators, which are periodically drained and cleaned in accordance with the Vendor Instruction Manual.

Question No.

430.61 Discuss your inservice testing and inspection program for the
(SRP 10.2) motor operated steam extraction valves such as provided for the
turbine governor, control, interceptor, and reheat stop valves.

Response

Inservice inspection is not covered by SRP 10.2 for turbine extraction motor operated valves. The acceptance criteria (10.2.II.3) is directed at extraction steam non-return valves limiting steam flow so turbine speed stabilizes. The motor operated valves do not perform this function.

Question No.

430.64
(SRP
10.4.1)

In Section 10.4.1.4 you have discussed tests and initial field inspection but not the frequency and extent of inservice inspection of the main condenser. Provide this information in the FSAR.

Response

Inservice inspection is performed in two ways:

- a) Continuous monitoring of condensate to detect leaks and;
- b) Periodic (refueling outage intervals) inspections to assess conditions of tubes in known, industry wide problem areas, and to assess condenser air in leakage.

The Supply System will continue to follow industry efforts to improve condenser leakage detection and will select additional inspection methods as the worth of these inspections is proven.

Question No.

450.6 (15.6.3) The operating procedures for responding to a steam generator tube rupture are currently an open issue on CESSAR. Resolution of the bases for analysis of this accident must either be accomplished for CESSAR, or on a plant specific basis for WNP-3. In order to resolve the issue for WNP-3, the following question must be answered. The current operating procedures call for the operators to steam the affected steam generator to prevent overfilling. the present steam generator tube rupture accident evaluation in the FSAR assumed tht no releases occur from the affected steam generator after 30 minutes. Describe why the CESSAR-FSAR evaluation is bounding for a steam generator tube rupture event in light of the operator action guidance.

Response This issue has been addressed on the CESSAR-F Docket via letter LD-83-066, from A. E. Scherer to D. G. Eisenhut, dated July 22, 1983, "Confirmatory Item 18 Steam Generator Tube Rupture Event". Additionally, guidance for operator actions during emergencies is contained in CEN-152, "Emergency Procedure Guidelines" which have been approved by the NRC via a Safety Evaluation Report forwarded by letter from D. G. Eisenhut to R. W. Wells, dated July 29, 1983. The WNP-3 emergency procedure will be developed from these guidelines, which include specifics concerning Steam Generator Tube Rupture.

Once confirmatory Item 18 is accepted by the staff the Supply System will reflect the most limiting SGTR event in the WNP-3 FASR, as appropriate.

Question No.

450.12 Because WNP-3 intends to reference CESSAR for certain accidents, demonstrate how the interface requirements for CESSAR are met.

Response

Chapter 15, as presently written, does not identify any interface conditions as specified in CESSAR System 80. It should, however, be noted that the FSAR sections which describe those systems that are used to mitigate the accidents described in Chapter 15 do reference and denote which interface requirements are met. Those sections also note those interface requirements which have been modified, as required. Furthermore, FSAR Section 1.9 lists all CESSAR interface requirements, cross-reference to interface requirements, FSAR compliance status with the CESSAR requirements, and the FSAR sections which address the NSSS requirements.

Question No.

460.1 Supply information relating to the effluent radiation monitors
(11.5.2.4.2) for steam generator blowdown flash tank vent and steam seal
 gland steam condenser ventilation which the FSAR indicates as
 later or provide a schedule for submittal of this information.

Response

As committed to in Letter #G03-82-1085, dated October 22, 1982.
FSAR Section 11.5 will be updated as shown to include the re-
quested information.

pre-established setpoints an annunciation is made through the system CRTs and event typer. If the activity exceeds the high radiation alarm setpoint, or if the monitor fails, as determined by the local microprocessor, a contact closure is made at the local microprocessor which is used to automatically terminate the waste gas discharge.

The receipt of these alarms will alert the operators to analyze additional gas samples to determine the reason for the alarm. The records of the total quantity of radioactive material released is used in writing the reports required by Regulatory Guide 1.21. The alarm setpoints are selected in consideration of the requirement to prevent activity concentrations at the plant boundary or beyond from exceeding 10CFR20 limits, and to support the release limits set in the plant technical specification. The setpoints may be adjusted continuously over the entire range of the monitor. The range of this monitor was selected to span the expected range of radioactive gas concentrations expected in the waste gas.

e) Steam Generator Blowdown Flash Tank Vent Radiation Monitor

The steam generator blowdown flash tank vent radiation monitor provides plant operations personnel with an indication and record of contamination of the Secondary Steam System and the potential for release via the steam generator blowdown flash tank vent. This contamination could occur due to leakage of primary reactor coolant into the secondary coolant through a steam generator.

This monitor is an ambient type monitor located next to the steam generator blowdown flash tank vent line 6BD12-200 ~~at EL. 423 ft. in the Turbine Building.~~ ^{outlet on the roof of} The monitor is collimated with a lead shield to reduce the effect of background. The unshielded portion of the detector has an unobstructed view of the vent line. The ambient monitor is described in Subsection 11.5.2.8.

The measured activity level is automatically transmitted to the system computer where it is recorded and available for display. If the activity exceeds setpoints an annunciation is made through the system CRTs and event typer. Receipt of these alarms will alert the operator to the possibility of contamination of the Secondary Steam System and indicate the need for additional sampling and further action.

The alarm setpoints are selected above plant background to give the greatest sensitivity for possible contamination without causing frequent false alarms. These setpoints may be adjusted continuously over the entire range of the monitor.

f) Auxiliary Condensate Flash Tank Radiation Monitor

The auxiliary condensate flash tank radiation monitor provides plant operations personnel with an indication and record of contamination of the Auxiliary Steam System and the potential for release via various vents in the Auxiliary Steam and Condensate System. This contamination could occur due to inleakage from the various radioactive systems that are serviced by the Auxiliary Steam System.

Q460.1
SCN 38821

WNP-3
FSARVent Line (6458-037)
Outlet on the roof of
the Reactor Auxiliary
Building

This monitor is an ambient type monitor located next to the Auxiliary Condensate Flash Tank in the Reactor Auxiliary Building next to line 6B012-200 on the 335 ft. level. The monitor is collimated with a lead shield to reduce the effect of background. The unshielded portion of the detector has an unobstructed view of the flash tank. The ambient monitor is described in Subsection 11.5.2.3.

The measured activity level is automatically transmitted to the system computer where it is recorded and available for display. If the activity exceeds setpoints an annunciation is made through the system CRTs and event typer. Receipt of these alarms will alert the operators to the possibility of contamination of the Auxiliary Steam and Condensate System and indicate the need for additional sampling and further action.

The alarm setpoints are selected above plant background to give the greatest sensitivity for possible contamination without causing frequent false alarms. These setpoints may be adjusted continuously over the entire range of the monitor.

g)

Steam Seal Gland Steam Condenser Exhaust Radiation Monitor

The steam seal gland steam condenser radiation monitor provides plant operations personnel with an indication and record of contamination of the Secondary Steam System and the potential for release via the steam seal gland steam condenser vent. This contamination could occur due to leakage of primary reactor coolant into the secondary coolant through a steam generator.

Outlet on the
roof

The monitor is an ambient type monitor located next to the vent line (6AE10-022) on SL 455 ft. of the Turbine Building.

The monitor is collimated with a lead shield to reduce the effect of background. The unshielded portion of the detector has an unobstructed view of the vent line. The ambient monitor is described in Subsection 11.5.2.3.

The measured activity level is automatically transmitted to the system computer where it is recorded and available for display. If the activity exceeds setpoints an annunciation is made through the system CRTs and event typer. Receipt of these alarms will alert the operators to the possibility of contamination of the Secondary Steam System and indicate the need for additional sampling and further action.

The alarm setpoints are selected above plant background to give the greatest sensitivity for possible contamination without causing frequent false alarms. These setpoints may be adjusted continuously over the entire range of the monitor.

Q460.1
SEN 38811

WNP-3
FSAR

TABLE 11.5-1 (Cont'd)

Name (Instrument Tag Number)	Q'ty	Design Background (mR/hr Co-60)	Sampler Type	Activity Measured	Sensitivity @ Background	Range $\mu\text{Ci/cc}$	Typical Alarm Set- points $\mu\text{Ci/cc}$	Automatic Actions Initiated	Location	Duty
Administration Building Discharge Radiation Monitor (RE-RM-0008 & RE-RM-0009)	1	2.5	Two Stage Airborne	Gross β Particu- late & Gas	1×10^{-9} $\mu\text{Ci/cc}$ Sr-90 @ 1 mR/hr Co-60 (2) 1×10^{-6} $\mu\text{Ci/cc}$ Kr-85 @ 1 mR/hr Co-60 (3)	1×10^{-10} to 1×10^{-5} 1×10^{-7} to 1×10^{-2}	3×10^{-10} 3×10^{-9} 5×10^{-7} 5×10^{-6}	Alarm Only	Inside HR-51	Continuous
Condenser Mechanical Vacuum Pump Discharge Radiation Monitor (RE-AE-1400)	1	2.5	One Stage Airborne	Gross β Gas	1×10^{-6} $\mu\text{Ci/cc}$ Xe-133 @ 1 mR/hr Co-60 (3)	1×10^{-7} to 1×10^{-2}	1×10^{-4} 1×10^{-3}	Alarm Only	Line 6AE16-021	Continuous
Waste Gas Discharge Radiation Monitor (RE-WG-0548)	1	2.5	One Stage Airborne	Gross β Gas	1×10^{-2} $\mu\text{Ci/cc}$ Kr-85 @ 1 mR/hr Co-60 (3)	1×10^{-3} to 1×10^{-3}	2×10^{-1} 2×10^0	Alarm, Termina- tion of Discharge	6CM1- 137R	Batch
Steam Generator Blowdown Flask Tank Vent Radiation Monitor	1		Ambient Pb Columnated	Gross γ Later	Later 70cpm/mR (4)	1×10^{-1} to 1×10^4 mR/hr	Above ambient background	Alarm Only	Line 6BD12-200	Continuous
Auxiliary Condensate Flash Tank Radiation Monitor	1	2.5	Ambient Pb Columnated	Gross γ Later	Later 70cpm/mR (4)	1×10^{-1} to 1×10^4 mR/hr	Above ambient background	Alarm Only	Line 6ASB-037 Boat Aux. Cond. Tank Flash	Continuous
Steam Gland Seal Steam Exhaust Radiation Monitor	1	2.5	Ambient Pb Columnated	Gross γ Later	Later 70cpm/mR (4)	1×10^{-1} to 1×10^4 mR/hr	Above ambient background	Alarm Only	Line 6AE10-022	Continuous
Hot Machine Shop Discharge Sampler (RE-RM-0010)	1	2.5	Sampler	None	N.A.	N.A.	N.A.	None	Inside GH-51	Continuous
Waste Management System Discharge Radiation Monitor (RE-WM-6213)	1	2.5	Liquid	Gross γ	1×10^{-6} $\mu\text{Ci/cc}$ Cs-137 @ 1 mR/hr Co-60 (1)	5×10^{-7} to 5×10^{-2}	5×10^{-5} 5×10^{-4}	Alarm Termina- tion of Discharge	Line 6LS3-080 WNP-3 6LS3-101 WNP-5	Batch
Common Plant Effluent Radiation Monitor (RE-CW-8810)	1	2.5	Liquid	Gross γ	1×10^{-6} $\mu\text{Ci/cc}$ Cs-137 @ 1 mR/hr Co-60 (1)	5×10^{-7} to 5×10^{-2}	5×10^{-6} 5×10^{-5}	Alarm Only	Line 6CW21- 05b via 6CW 1 1/2-123	Continuous

note (4): Efficiency of detector

Q460.1
SCN38811

Question No.

471.6
(12.5.2)

Regulatory Guide 1.70 and the SRP (NUREG-0800) state that the description of the health physics instrumentation should include the instruments sensitivity. You provided the type of radiation the instrument detects and not the instrument sensitivity in Table 12.5-1. Provide the requested information.

Response

As committed to in Letter #G03-82-1085, dated October 22, 1982. FSAR Section 12.5 will be updated as shown to provide the requested information.

TABLE 12.5-1

WNP-3/5 PLANT HEALTH PHYSICS INSTRUMENTATION

<u>Number/Plant</u>	<u>Type</u>	<u>Sensitivity</u>	<u>Range</u>	
1	Multichannel Gamma Spectrometer with Ge(Li) or HPGe Detector	Gamma note 1	N/A	1
1	Multichannel Gamma Spectrometer with NaI(Tl) Detector	Gamma note 1	N/A	1
2	Low Background Alpha-Beta Proportional Counters	Alpha, Beta note 1	N/A	
1	Liquid Scintillation Counter	Beta note 1	N/A	
4	End Window G-M Counting Systems	Beta note 1	N/A	
14	Ion Chamber Dose Rate Meters	Beta, Gamma 1 mR/hr	10 ⁻³ -5 R/hr	1
4	Extendable Probe High Range Dose Rate Meters	Gamma 1 mR/hr	10 ⁻³ -10 ⁴ R/hr	
2	Neutron Dose Equivalent Rate Meters	Neutron 1 mR/hr	10 ⁻³ -10 rem/hr	1
14	G-M Survey Meters with Thin Wall, End Window or Pancake Probe	Beta, Gamma 500 dpm/100 cm ²	0-50,000 cpm	
2	Portable Alpha Counters	Alpha 100 dpm/100 cm ²	0-500,000 cpm	
10	Frisker Type Personnel Contamination Monitors	Beta, Gamma 500 dpm/100 cm ²	0-50,000 cpm	
2	Portal Radiation Monitors	Beta and/or Gamma 0.5 μ Ci	N/A	1
6	Portable Constant Air Monitors	Beta in 2 mR/hr background 1 x 10 ⁻⁹ μ Ci/cc Sr-90	10 ⁻¹⁰ -10 ⁻⁴ μ Ci/cc Sr-90	1
500	Direct Reading Personnel Dosimeters	Gamma N/A	0-500 mR	
100	Direct Reading Personnel Dosimeters-High Range	Gamma N/A	Various ranges to 100 R	

notes:

1. The sensitivity will meet or exceed the LLD values given in NUREG-0972, "Draft Radiological Effluent Technical Specifications for PWR's."

Question No.

480.13 In Appendix 6.2A, it is stated that the WATEMPT code is an extension of the CONTEMPT code. Identify the modifications that have been made to the CONTEMPT code to assure a conservative calculation of the shield building annulus pressure response.

Response The modifications to the code which assure a conservative calculation of the Shield Building annulus pressure response are described in a proprietary description of the WATEMPT code. This proprietary code was also used to analyze the performance of the Shield Building Ventilation System for St Lucie Unit 2 (Florida Power & Light Co.) and its approval by the staff was benchmarked via St Lucie Unit 2's Safety Evaluation Report (NUREG-0843).

Question No.

480.17 Identify all valves in FSAR Table 6.2.4-1 that are greater than 10
(6.2.4) feet from the containment wall. Provide the rationale for their locations and justify that they have been placed as close to the containment as practical, as required by L.C. 55, 56, and 57.

Response

All the containment isolation valves in FSAR Table 6.2.4-1 that are greater than 10 feet from the containment are listed on Table 480.17-1. The valves listed are all located in the penetration area adjacent to the containment building. These containment isolation valves have been located as close to the containment as possible while allowing adequate space requirements for operability and maintenance.

FSAR Table 6.2.4-1 will be updated as shown.

1519W-1

WNP-3
FSAR

1519W-2

TABLE 6.2-4-1
CONTAINMENT ISOLATION SYSTEM

Penetration No.	Service	GDC Isolation Criteria	System Category	Valve No.	Electrical Division	Electrical Power	Valve Size (Inches)	Type of Valve Operator	Valve Type	Location with Respect to RB	Normal Valve Position	Shutdown Valve Position	Post-Accident Valve Position	Post-Accident Valve Failure Mode	Length from Penetration (Feet)	Valve Closure Signal	Valve Open Signal	Closure Time (Seconds)	Override	Fluid	Type C Test
1	SG1 Main Steam Line	57 A	ESFREL	ZMS-VDO01	SA/SB	-	20	AO	Gate	0	0	C	C	FAI	31	MSIS	-	5	No	S	No
				ZMS-VDO91	SA	-	2	AO	Globe	0	C	C	C	FC	11	MSIS	-	10	No	-	-
				ZMS-R009	SA	-	8	Spr	Relief	0	C	C	O/C	-	8	-	-	-	-	-	-
				ZMS-R010	SA	-	8	Spr	Relief	0	C	C	O/C	-	13	-	-	-	-	-	-
				ZMS-R011	SA	-	8	Spr	Relief	0	C	C	O/C	-	20	-	-	-	-	-	-
				ZMS-P016	SA	440V ac	8	ER	Globe	0	C	C	O/C	FC	38	MSIS	-	13	Yes	-	-
				ZMS-VDO55	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO56	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO57	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO58	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
2	SG1 Main Steam Line	57 A	ESFREL	ZMS-VDO02	SA/SB	-	20	AO	Gate	0	0	C	C	FAI	31	MSIS	-	5	No	S	No
				ZMS-R007	SA	-	8	Spr	Relief	0	C	C	O/C	-	8	-	-	-	-	-	-
				ZMS-R008	SA	-	8	Spr	Relief	0	C	C	O/C	-	13	-	-	-	-	-	-
				ZMS-R009	SA	-	8	Spr	Relief	0	C	C	O/C	-	20	-	-	-	-	-	-
				ZMS-P012	SB	440V ac	8	ER	Globe	0	C	C	O/C	FC	38	MSIS	-	13	Yes	-	-
				ZMS-V013B	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V013C	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V013D	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V0003	SA/SB	-	20	AO	Gate	0	0	C	C	FAI	31	MSIS	-	5	No	S	No
				ZMS-VDO92	SB	-	2	AO	Globe	0	C	C	C	FC	11	MSIS	-	10	No	-	-
3	SG2 Main Steam Line	57 A	ESFREL	ZMS-R018	SB	-	8	Spr	Relief	0	C	C	O/C	-	8	-	-	-	-	-	-
				ZMS-R019	SB	-	8	Spr	Relief	0	C	C	O/C	-	13	-	-	-	-	-	-
				ZMS-R020	SB	-	8	Spr	Relief	0	C	C	O/C	-	20	-	-	-	-	-	-
				ZMS-P023	SA	440V ac	8	ER	Globe	0	C	C	O/C	FC	38	MSIS	-	13	Yes	-	-
				ZMS-VDO81	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO82	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO83	SB	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-VDO84	SA/SB	-	20	AO	Gate	0	0	C	C	FAI	31	MSIS	-	5	No	S	No
				ZMS-R013	SB	-	8	Spr	Relief	0	C	C	O/C	-	8	-	-	-	-	-	-
				ZMS-R014	SB	-	8	Spr	Relief	0	C	C	O/C	-	13	-	-	-	-	-	-
4	SG2 Main Steam Line	57 A	ESFREL	ZMS-R015	SB	-	8	Spr	Relief	0	C	C	O/C	-	20	-	-	-	-	-	-
				ZMS-P021	SB	440V ac	8	ER	Globe	0	C	C	O/C	FC	38	MSIS	-	13	Yes	-	-
				ZMS-V014D	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014E	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014F	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014G	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014H	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014I	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014J	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-
				ZMS-V014K	SA	-	4	AO	Gate	0	C	C	O/C	FO	14	MSIS	AFAS	10	No	-	-

the *Force* is a hydraulic converter. Check valve feature is lost and removed.

QUESTION 480.17TABLE 480.17-1CONTAINMENT ISOLATION VALVES

<u>Valve No.</u>	<u>Length from Penetration (ft.)</u>	<u>Service</u>	<u>Penetration Number</u>
2MS-VD001	31	SG1 MS Line	1
2MS-VE091	31	SG1 MS Line	1
2MS-R010	13	SG1 MS Line	1
2MS-R011	20	SG1 MS Line	1
2MS-P016	38	SG1 MS Line	1
2MS-VE055	14	SG1 MS Line	1
2MD-VE001	39	SG1 MS Line	1
2MD-VE087	42	SG1 MS Line	1
2MS-VD002	31	SG1 MS Line	2
2MS-R007	13	SG1 MS Line	2
2MS-R008	20	SG1 MS Line	2
2MS-P012	38	SG1 MS Line	2
2MS-VE138	14	SG1 MS Line	2
2MD-VE002	39	SG1 MS Line	2
2MD-VE088	42	SG1 MS Line	2
2MS-VD003	31	SG2 MS Line	3
2MS-VE092	31	SG2 MS Line	3
2MS-R019	13	SG2 MS Line	3
2MS-R020	20	SG2 MS Line	3
2MS-P023	38	SG2 MS Line	3
2MS-VE082	14	SG2 MS Line	3
2MD-VE003	39	SG2 MS Line	3
2MD-VE089	42	SG2 MS Line	3
2MS-VD004	31	SG2 MS Line	4
2MS-R014	13	SG2 MS Line	4
2MS-R015	20	SG2 MS Line	4
2MS-P021	38	SG2 MS Line	4
2MS-VE140	14	SG2 MS Line	4
2MD-VE004	39	SG2 MS Line	4
2MD-VE090	42	SG2 MS Line	4
2FW-VD036	15	SG2 Main FW	7
2FW-VD021	15	SG1 Main FW	8
2FW-VD042	15	SG2 Main FW	9
2FW-VD027	15	SG1 Main FW	10

QUESTION 480.17

TABLE 480.17-1 (Cont'd)

CONTAINMENT ISOLATION VALVES

<u>Valve No.</u>	<u>Length from Penetration (ft.)</u>	<u>Service</u>	<u>Penetration Number</u>
2FW-VD038	16	SG2 DWNCMR FW & Aux FW	11
2FW-VD039	13	SG2 DWNCMR FW & Aux FW	11
2AF-VE135	23	SG2 DWNCMR FW & Aux FW	11
2AF-VD036	27	SG2 DWNCMR FW & Aux FW	11
2AF-VE132	23	SG2 DWNCMR FW & Aux FW	11
2AF-VD039	27	SG2 DWNCMR FW & Aux FW	11
2FW-VD023	16	SG1 DWNCMR FW & Aux FW	12
2FW-VD024	13	SG1 DWNCMR FW & Aux FW	12
2AF-VE133	23	SG1 DWNCMR FW & Aux FW	12
2AF-VD040	27	SG1 DWNCMR FW & Aux FW	12
2AF-VE134	23	SG1 DWNCMR FW & Aux FW	12
2AF-VD035	27	SG1 DWNCMR FW & Aux FW	12
2SI-VQ019	14	HPSI Loop 2A	13
2SI-VQ020	17	HPSI Loop 2A	13
2SI-VQ016	17	HPSI Loop 2B	14
2SI-VQ017	14	HPSI Loop 2B	14
2SI-VQ013	19	HPSI Loop 1A	15
2SI-VQ014	16	HPSI Loop 1A	15
2SI-VQ008	19	HPSI Loop 1B	16
2SI-VQ009	16	HPSI Loop 1B	16
2SI-VS060	15	SHTDN COOL Suction	27
2SI-VU061	12	SHTDN COOL Suction	27
2SI-VS054	15	SHTDN COOL Suction	28
2SI-VU055	12	SHTDN COOL Suction	28

Question No.

480.18 Provide a tabulation of those containment isolation valves for
(6.2.4) which provision has been made to allow them to be individually
leak tested, in the correct direction.

Response

Containment Isolation Valves which have provisions for leak testing are shown on Table 480.18-1.

FSAR Figures 6.2-36b - k, m, o and p and Table 6.2.4-1 will be revised as shown.

TABLE 480.18-1

<u>PENETRATION</u>	<u>VALVE</u>	<u>SERVICE</u>
21	2CS-VS091	Containment Spray
21	2CS-VS037	Containment Spray
22	2CS-VS092	Containment Spray
22	2CS-VS038	Containment Spray
23	2CS-B002	Containment Spray
24	2CS-B001	Containment Spray
27	2SI-VS060	Safety Injection
27	2SI-VU061	Safety Injection
27	1SI-VP097	Safety Injection
28	2SI-VS054	Safety Injection
28	2SI-VU055	Safety Injection
28	1SI-VP091	Safety Injection
29	2SI-VQ169	Safety Injection
29	2SI-VQ115	Safety Injection
30	2CC-B522	Component Cooling
30	2CC-VH012	Component Cooling
31	2CC-B521	Component Cooling
31	2CC-VH023	Component Cooling
32	2CC-B526	Component Cooling
32	2CC-B524	Component Cooling
33	2CC-B525	Component Cooling
33	2CC-B523	Component Cooling
34	2HA-VS002	Hydrogen Analyzer
34	2HA-VS008	Hydrogen Analyzer
34	2HA-VS009	Hydrogen Analyzer
34	2HA-VS010	Hydrogen Analyzer
34	2HA-VS012	Hydrogen Analyzer
35	2HA-VS021	Hydrogen Analyzer
35	2HA-VS027	Hydrogen Analyzer
35	2HA-VS028	Hydrogen Analyzer
35	2HA-VS029	Hydrogen Analyzer
35	2HA-VS031	Hydrogen Analyzer
36	2SL-VP102	Sampling
36	2SL-VP103	Sampling
38	2IA-VE020	Instrument Air
38	2IA-VE021	Instrument Air
39	2SA-VH007	Station Air
39	2SA-VH008	Station Air
40	2CH-VP011	CVCS
40	2CH-VP077	CVCS
41	2CH-VQ040	CVCS
41	2CH-VQ064	CVCS
42	2CH-VP029	CVCS
42	2CH-VP030	CVCS
42	2DI-VS043	Dionized Water
42	2DI-VS044	Dionized Water
44	2CH-VW037	CVCS
44	2CH-VW040	CVCS

TABLE 480.18-1 (Cont'd)

<u>PENETRATION</u>	<u>VALVE</u>	<u>SERVICE</u>
45	2CH-VS041	CVCS
45	2CH-VS501	CVCS
46	2SI-VQ173	Safety Injection
46	1SI-VP183	Safety Injection
47	2SI-VQ172	Safety Injection
47	1SI-VP181	Safety Injection
50	2PC-VW010	Fuel Pool Cleanup
50	2PC-VW011	Fuel Pool Cleanup
51	2PC-VW008	Fuel Pool Cleanup
51	2PC-VW009	Fuel Pool Cleanup
54	2NG-VE057	Nitrogen Supply
54	2NG-VE058	Nitrogen Supply
56	2SL-VP104	Sampling
56	2SL-VP105	Sampling
56	2SL-VP106	Sampling
56	2SL-VP107	Sampling
60	2PV-B009	Plant Ventilation
60	2PV-B010	Plant Ventilation
65	2PV-B014	Plant Ventilation
65	2PV-V015	Plant Ventilation
68	2PV-B016	Plant Ventilation
68	2PV-B017	Plant Ventilation
68	2PV-B018	Plant Ventilation
70	2PV-B109	Plant Ventilation
70	2PV-B110	Plant Ventilation
73	2PV-B111	Plant Ventilation
73	2PV-B112	Plant Ventilation
73	2PV-B113	Plant Ventilation
75	2PV-B114	Plant Ventilation
75	2PV-B115	Plant Ventilation
80	2PV-B019	Plant Ventilation
80	2PV-V021	Plant Ventilation
81	2PV-B164	Plant Ventilation
81	2PV-B064	Plant Ventilation
82	2EC-B009	Chilled Water
82	2EC-B010	Chilled Water
83	2EC-B011	Chilled Water
83	2EC-B012	Chilled Water
90	2CH-VS042	CVCS
90	2CH-VS044	CVCS
90	2CH-VS047	CVCS
90	2CH-VS049	CVCS
93	2CH-VQ005	CVCS
93	2CH-VQ006	CVCS
95	2FP-VH003	Fire Protection
95	2FP-VH006	Fire Protection
96	2SD-VS126	Sump Discharge
96	2SD-VS127	Sump Discharge

WFP-3
FLAR

15199-2

15199-8

TABLE 6.2.4-1 (Cont'd)

Procedure List No.	Service	Isolation Criteria	System Category	Valve No.	Electrical Division	Electrical Power	Valve Size (Inches)	Type of Valve	Operator	Valve Type	Location with Respect to RB	Normal Valve Position	Shutdown Valve Position	Post-Acti- on Valve Position	Failure Mode	Length from Penetration (feet)	Valve Close Signal	Valve Open Signal	Valve Close Time (Seconds)	Override	Fluid	Type of Test
23	Recirc Pump B Discharge	B	ESF	2CB-8002	SB	440V ac	30	MO	MO	Buttly	0	C	C	0	FAL	2	SIAS	SIAS	10	Yes	M	Yes
24	Recirc Pump A Discharge	B	ESF	2CB-8001	SA	440V ac	30	MO	MO	Buttly	0	C	C	0	FAL	2	SIAS	SIAS	10	Yes	M	Yes
25	Flow Penetration (Breakdown) B. g/c	C	NOF	27F-8007 27F-8006	SB SA	440V ac	4 4	MO	MO	Gate Druck	0 1	C C	C C	C C	FAL FAL	1 1	CIAS	CIAS	10	No	M	No
26	SG1 Sample	A	MOH	28D-80035 28D-80033	SB SA	-	1 1	AO	AO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	3 -	MSIS MSIS	-	10 10	No No	M	No
26	SG2 Sample	A	MOH	28D-80091 28D-80089	SB SA	-	1 1	AO	AO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	3 -	MSIS MSIS	-	10 10	No No	M	No
26	SG2 Sample	A	MOH	28D-80092 28D-80090	SB SA	-	1 1	AO	AO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	3 -	MSIS MSIS	-	10 10	No No	M	No
26	SG2 Sample	A	MOH	28D-80036 28D-80034	SB SA	-	1 1	AO	AO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	3 -	MSIS MSIS	-	10 10	No No	M	No
27	Shutdown Cool. Section	B	ESF	281-80040 281-80041 281-80097 281-80054 281-80033 281-80034	SB SA SB SA/SA SA/SA SA/SA	440V ac 440V ac 440V ac 440V ac 440V ac 440V ac	10 16 16 4 4 4	MO MO SB Sbr Sbr Sbr	MO MO Sbr Sbr Sbr Sbr	Globe Gate Gate Ball Ball Ball	0 0 1 1 1 1	C C C C C C	0 0 0 0 0 0	0 0 0 0 0 0	FAL FAL FAL FAL FAL FAL	15 12 -	RM RM RM RM RM RM	RM RM RM RM RM RM	10 10 -	- - - - - -	M	No
28	Shutdown Cool. Section	B	ESF	281-80034 281-80035 281-80036 281-80037	SA SA SA SA/SA	440V ac 440V ac 440V ac 440V ac	10 16 16 4	MO MO Sbr Sbr	MO MO Sbr Sbr	Globe Gate Gate Ball	0 0 1 1	C C C C	0 0 0 0	0 0 0 0	FAL FAL FAL FAL	15 12 -	RM RM RM RM	RM RM RM RM	10 10 -	- - - -	M	No

TABLE 6-2.4-1 (Cont'd)

Promoter Elem. No.	Service	ISOC Isolation Criteria	System Category	Valve No.	Electrical Division	Electrical Power	Valve Size (Inches)	Type of Valve	Valve Dys.	Location with Respect to AB	Normal Valve Position	Shutdown Valve Position	Post-Acti- vated Valve Position	Failure Mode	Length From Reference (Feet)	Valve Closure Signal	Valve Open Signal	Closure Time (Seconds)	Override	Fluid	Type C (Feet)
29	SLT Fill & Drain	56 B	ROM	281-00169 281-00170 281-00171	8A/8B 8A 8A/8B	- - -	2 2 3/4	MO MO BPR	Globe Globe Ball	0 1 1	LC C C	LC C C	LC C C	FC FC FC	1 - -	M SIAS -	R -	5 -	- Yes -	M	Yes
30	Cooling Water to RCP 2A and 2B	56 C	ESP/REL	20C-0522 20C-05012	8B 8A/8B	440V ac -	8 8	MO -	Ball Check	0 1	0 0	0 0	0 0	FC FC	2 -	CIAB -	- -	10 -	Yes -	M	Yes
31	Cooling Water to RCP 1A and 1B	56 C	ESP/REL	20C-0521 20C-05011	8B 8A/8B	440V ac -	8 8	MO -	Ball Check	0 1	0 0	0 0	0 0	FC FC	2 -	CIAB -	- -	10 -	Yes -	M	Yes
32	Cooling Water from RCP 2A and 2B	56 C	ESP/REL	20C-0524 20C-05014	8B 8A	440V ac -	10 10	MO -	Ball Check	0 1	0 0	0 0	0 0	FC FC	2 -	CIAB -	- -	10 -	Yes -	M	Yes
33	Cooling Water from RCP 1A and 1B	56 C	ESP/REL	20C-0525 20C-05015	8B 8A	440V ac -	10 10	MO -	Ball Check	0 1	0 0	0 0	0 0	FC FC	2 -	CIAB -	- -	10 -	Yes -	M	Yes
34	Hydrogen Analyzer Suction	56 B	ESP	28A-05009 28A-05008	8A 8A	125V dc 125V dc	3/8 3/8	BO BO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	- -	BN BN	BN BN	5 5	- -	A	Yes
35	Hydrogen Analyzer Return	56 B	ESP	28A-05010 28A-05011	8A 8A	125V dc 125V dc	3/8 3/8	BO BO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	- -	BN BN	BN BN	5 5	- -	A	Yes
36	Hydrogen Analyzer Suction	56 B	ESP	28A-05020 28A-05021	8B 8B	125V dc 125V dc	3/8 3/8	BO BO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	- -	BN BN	BN BN	5 5	- -	A	Yes
37	Hydrogen Analyzer Return	56 B	ESP	28A-05022 28A-05023	8B 8B	125V dc 125V dc	3/8 3/8	BO BO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	- -	BN BN	BN BN	5 5	- -	A	Yes
38	Over Feed to SCV	57 A	MOB	20P-05004 20P-05005	8A 8A	- -	1 1	MO MO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	3 -	BN BN	BN BN	10 10	No No	M	Yes
39	Pre-Drain Line Sample	57 C	MOB	28L-05003 28L-05004	8B 8A	- -	3/8 3/8	MO MO	Globe Globe	0 1	0 0	0 0	0 0	FC FC	2 -	CIAB CIAB	- -	5 5	No No	M	Yes

TABLE 6.2.A-1 (Cont'd)

Penetration No.	Service	QDC Isolation Criteria	System Category	Valve No.	Electrical Releaser	Electrical Power	Valve Size (Inches)	Type of Valve Operation	Valve Type	Location with Respect to RB	Normal Valve Position	Shutdown Valve Position	Post-Accident Valve Position	Failure Mode	Length from Penetration (Feet)	Valve Closure Signal	Valve Open Signal	Closure Time (Seconds)	Override	Fluid	Type C Test
55	Sparg Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
56	BC Hot Leg Sample	55 C	NOM	28L-98106-107 28L-98106-108	SB SB	125V dc 125V dc	3/8 3/8	SO	Globe	0	C	C	C	PC	2	CIAS	-	5	No	M	Yes
56	P2B Steam Space Sample	55 C	NOM	28L-98105 28L-98104	AD AD	- -	3/8 3/8	SO	Globe	0	C	C	C	PC	2	CIAS	-	5	No	S	Yes
57	Post-accident Sampling (Liquid) return	56 B	ESF	28L-98176 28L-98178	SB SB	125V dc -	1 1	SO	Globe	0	C	C	C	LATCH	-	-	-	5	No	M	No
57	Post-accident Sampling (gas) return	56 B	ESF	28L-98177 28L-98179	SB SB	125V dc -	1 1	SO	Globe	0	C	C	C	LATCH	-	-	-	5	No	A	No
58	Sparg Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
59	Sparg Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
60	Hydrogen Purge Return	56 C	ESF/REL	27P-8009 27P-8010	SB SB	440V ac 440V ac	8 8	MO	Buttly	0	C	C	C	FAI	5	CIAS	-	10	No	A	Yes
61	Shield Bldg Vent Supply	58	ESF	27P-8025	SA	440V ac	30	MO	Buttly	0	C	C	C	FAI	2	-	HP	10	No	A	No
62	Shield Bldg Vent Exhaust	58	ESF	27P-8031	SA	440V ac	30	MO	Buttly	0	C	C	C	FAI	2	-	HP	10	No	A	No
63	Sparg Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
65	Re Vacuum Piped	56 C	NOM	27P-8014 27P-8015	SA SA	440V ac -	4.2 4.2	MO	Buttly	0	C	C	C	FAI	3	-	HP	10	No	A	Yes
66	SB Vacuum Nodot	58	NOM	27P-8023 27P-8024	SB SA	- -	10 10	AD	Buttly	0	0	0	C	PC	1	CIAS	-	5	No	A	No

TABLE 6.2.4-1 (Cont'd)

Procedure Step No.	Service	QSC Isolation Criteria	System Category	Valve No.	Electrical Division	Electrical Power	Valve Size (Inches)	Type of Valve	Valve Type	Location with Respect to RB	Normal Valve Position	Shutdown Valve Position	Post- Accident Valve Position	Failure Mode	Length from Penetration (feet)	Valve Closure Signal	Valve Open Signal	Closure Time (Seconds)	Override	Fluid	Type C Test
90	Helium from RC Drain Tank	56 C	WH	2CH-V8042 2CH-V8044	SB SA	-	1-1/4 1-1/4	AO AO	Globe Globe	0 1	0 0	0 0	C C	FC FC	2 -	CIAS CIAS	-	5 5	No No	G	Yes
90	Helium from RC Drain Tank	56 C	WH	2CH-V8047 2CH-V8049	SB SA	-	1-1/4 1-1/4	AO AO	Globe Globe	0 1	0 0	0 0	C C	FC FC	2 -	CIAS CIAS	-	5 5	No No	G	Yes
91	GC Sample	57 A	WH	2SD-V8060 2SD-V8076	SB SA	-	1 1	AO AO	Globe Globe	0 1	0 0	0 0	C C	FC FC	1 -	MSLS MSLS	-	10 10	No No	M	No
92	Fire Protection (Header) Sump	58 C	WH	2FP-V8003 2FP-V8005	SB SA	440V ac	3 3	MO MO	Globe Globe	0 1	0 0	0 0	C C	FC FC	1 -	CIAS CIAS	-	10 10	No No	M	Yes
93	RCP Seal Inj	55 C	EHREL	2CH-V8003 2CH-V8006	SB SA	440V ac	1-1/2 1-1/2	MO MO	Globe Globe	0 1	0 0	0 0	C C	FC FC	1 -	CIAS CIAS	-	5 5	-	M	Yes
94	Space Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Yes
95	Fire Protection (Header)	56 C	WH	2FP-V8006 2FP-V8003	SB SA	440V ac	3 3	MO MO	Globe Globe	0 1	0 0	0 0	C C	FC FC	1 -	CIAS CIAS	-	10 10	No No	M	Yes
96	RCP Pump Discharge	56 C	WH	2SD-V8127 2SD-V8128	SB SA	-	2 2	AO AO	Globe Globe	0 1	0 0	0 0	C C	FC FC	2 -	CIAS CIAS	-	10 10	No No	M	Yes
97	Station Air to Shield Bldg	58 C	WH	2SA-V8017	SA/SB	-	1	MO	Globe	0	-	LC	LC	-	1	M	N	-	-	-	Yes
98	Space Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Yes
99	Space Penetration	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Yes
200, 201, 202, 203	Main Steam to Aux Feedwater System	58 C	ESP	None	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Yes
204, 205	Aux Feedwater Pump to Feedwater System	58 C	ESP	None	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Yes
206	H ₂ Analyzer Buct.	58 C	ESP	2HA-V8002	SA	125V dc	3/8	SO	Globe	0	C	C	O/C	FC	-	RM	RM	5	-	A	NA
209	H ₂ Analyzer Buct.	58 C	ESP	2HA-V8021	SA	125V dc	3/8	SO	Globe	0	C	C	O/C	FC	-	RM	RM	5	-	A	NA
210	Space Penetration	58 C	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
211	Space Penetration	58 C	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Figures 6.2-36 through 6.2-36r and Figures 3.8.2-1 through 5 show the various piping and electrical penetrations, respectively. Mechanical and electrical penetrations that will not be subject to Type B tests are those that rely on welds for sealing and are designed such that the penetrations are subject to the Integrated Leak Rate Test conditions. Leakage from those penetrations will be included in the overall leak rate measured during the Type A test. Test of the personnel access lock after each entry under some conditions is described below.

6.2.6.3 Containment Isolation Valve Leak Rate Test

Table 6.2.4-1 also provides a listing of all containment isolation valves and identifies those that require and those that are exempt from leak rate test Type C. Type C leak testing is performed as for Type B leak testing described in Subsection 6.2.6.2a or b.

Type C Leak test should be completed prior to Type A tests. In the event that a Type C test is not completed prior to the Type A test, any Type C penetration path test leakage not accounted for in the Type A test shall be added to the measured leakage determined by the Type A test.

~~Figures 6.2-36 through 6.2-36r show the arrangement to be provided for testing of containment isolation valves subject to Type C testing along with the direction of pressurization to be used for the test.~~ Type C tests are performed by local pressurization. Each valve to be tested shall be closed by normal operation without any preliminary exercising or adjustments and pressurized to not less than the peak accident pressure of 39.4 psig.

The combined leakage of penetrations and valves subject to Type B and C testing shall be less than 0.60 of La. { in the correct direction

6.2.6.4 Scheduling and Reporting of Periodic Tests

The Type A, B and C leakage tests will be completed prior to any reactor operating period. After the initial preoperational leak testing, periodic tests shall be performed in accordance with the following schedule:

- a) A set of three Type A tests shall be performed at approximately equal intervals during each 10 year service period. The third test of each set shall be conducted when the plant is shut down for the 10 year plant in-service inspection.
- b) Type B tests shall be performed during each reactor shutdown for refueling, or other convenient intervals, but in no case at intervals greater than two years. Air locks shall be tested at six month intervals. Air locks which are opened during such intervals shall be tested after each opening.
- c) Type C tests shall be performed during each reactor shutdown for refueling, but in no case at an interval greater than two years.

{ Containment isolation valve arrangements and indicate those valves for which test provisions have been provided for individual leak testing.


by tag number

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES


13, 14, 15, 16
HPSI TO
COLD LEGS




17, 18, 19, 20
LPSI



21, (22)
CONT SPRAY



23, (24)
RECIRC
SUMP



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SCN577


FIGURE
6.2-36b

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES


§ 92
25 (92 AND 95)
FIRE
PROTECTION




26
SG SAMPLE



27, (28)
SHUTDOWN
COOLING



29
SIT
FILL & DRAIN



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

FIGURE
6.2-36c


Q480.18
SCN 577

PENETRATION NO./
SERVICE


INSIDE
CONTAINMENT OUTSIDE
CONTAINMENT

NOTES


30,(31)
COOLING WATER
TO RCP




32,(33)
COOLING WATER
FROM RCP



34,(35)
HYDROGEN
ANALYZER
SUCTION &
RETURN



36
CHEM FEED
TO SG'S AND
PZR SURGE
LINE SAMPLE



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
36N577

FIGURE

6.2-36d


PENETRATION NO./ SERVICE	<div> <div>INSIDE CONTAINMENT</div> <div>OUTSIDE CONTAINMENT</div> </div> <div> <div>STEEL CONTAIN. VESSEL</div> <div>CONCRETE SHIELD BUILDING</div> </div>	NOTES
37 SPARE		
38 INSTRUMENT AND CONTROL AIR		
39 SERVICE AIR		
40 LETDOWN LINE		
WASHINGTON PUBLIC POWER SUPPLY SYSTEM Nuclear Projects 3 & 5 FINAL SAFETY ANALYSIS REPORT		AMENDMENT NO. 1 (10/82) CONTAINMENT ISOLATION VALVES ARRANGEMENT Q480.18 5CN577
FIGURE 6.2-36e		

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES


41
CHARGING
LINE &
AUX SPRAY




42
RCP
CONTROLLED
BLEEDOFF &
DEIONIZED
WATER



43
CONTAINMENT
LEAK RATE
TEST



44
REACTOR
COOLANT
DRAIN
TANK
OUTLET



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM


Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q 480.18 SCN577

FIGURE

6.2-36f




PENETRATION NO./
SERVICE

INSIDE CONTAINMENT OUTSIDE CONTAINMENT


NOTES

50
REFUELING
CAVITY PURIF.
SUPPLY




51
REFUELING
CAVITY PURIF.
RETURN


52
FAILED FUEL
DETECTOR



53
FUEL TRANSFER
CANAL



54
NITROGEN
SUPPLY



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SLN577

FIGURE


6.2-36h

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES


55
SPARE




56
RC HOT LEG
SAMPLE,
PRESSURIZER
STEAM
SPACE SAMPLE



57
POST-ACCIDENT
SAMPLING
RETURNS



58
SPARE



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SCN 572

FIGURE


6.2-36i

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT
←-----○-----→

NOTES

59
SPARE




60 (AND 70)
HYDROGEN
PURGE
EXHAUST



*PENETRATION 60
CONNECTS TO
PENETRATION 62.
PENETRATION 70
CONNECTS TO
PENETRATION 72.

61 (AND 71)
SHIELD BLDG
SUPPLY

62 (AND 72)
SHIELD BLDG
EXHAUST



63
SPARE



DOES NOT HAVE A
SHIELD BUILDING
PENETRATION.

AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM


Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SC4577

FIGURE

6.2-36i



AMENDMENT NO. 2 (12/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SCN 577

FIGURE


6.2-36k

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES

80
CONTAINMENT
VENT MAKE-UP




81
CONTAINMENT
VENT EXHAUST




82
CHILLED WATER
SUPPLY

(83)
CHILLED WATER
RETURN



84
INSTRUMENT
LINES



AMENDMENT NO. 2 (12/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SCN 577

FIGURE


6.2-36m

PENETRATION NO./
SERVICE

INSIDE CONTAINMENT OUTSIDE CONTAINMENT


NOTES

89
INSTRUMENT
LINES



TO SB ANNULUS VACUUM MAIN-
TAINANCE SYST. 'B' - ANNULUS
TO OUTSIDE RAB DIFF. PRES.
INSTRUMENTS

90
REACTOR DRAIN
TANK VENT,
AND REACTOR
DRAIN TANK
NITROGEN SUPPLY




91

SEE PENETRATION 48

92

SEE PENETRATION 25

93
SEAL INJECTION
HEADER



AMENDMENT NO. 2 (12/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT
Q450.18
SCN577

FIGURE


6.2-36o

PENETRATION NO./
SERVICE


INSIDE CONTAINMENT OUTSIDE CONTAINMENT

NOTES


94
SPARE




95
FIRE
Protection



96
RB SUMP
PUMP
DISCHARGE



97
STATION
AIR TO
SHIELD
BLDG.



AMENDMENT NO. 1 (10/82)

WASHINGTON PUBLIC
POWER SUPPLY SYSTEM

Nuclear Projects 3 & 5
FINAL SAFETY ANALYSIS REPORT

CONTAINMENT ISOLATION
VALVES ARRANGEMENT

Q480.18
SCN577

FIGURE

6.2-36p

Question No.

480.21 Section 6.2.5.2.1 states that manual operator action from the
(6.2.5) control room is required to actuate the containment hydrogen
 analyzers. Discuss and justify the emergency procedures that
 will alert an operator of the need to actuate the hydrogen
 analyzers.

Response

The WNP-3 Emergency Procedures have not yet been fully developed. These procedures will, however, be based on the guidance of CEN-152 "Combustion Engineering Emergency Procedure Guidelines", which include discussions on containment combustible gas control. The subject CE guidelines have received an SER, per NRC letter dated July 29, 1983; D. G. Eisenhower to R. G. Wells of CE Owners Group; Safety Evaluation of "Emergency Procedure Guidelines".