


REV. 0
MARCH 7, 1984

Control Room Design Review

Operating Experience Review Validation Report

The South Texas Project



HOUSTON LIGHTING & POWER COMPANY

8404180220 840412
PDR ADOCK 05000498
A PDR



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

OPERATING EXPERIENCE REVIEW

VALIDATION REPORT



OPERATING EXPERIENCE REVIEW VALIDATION REPORT

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
	TABLE OF CONTENTS	i
	LIST OF TABLES	ii
	SUMMARY	iii
	ACRONYMS AND ABBREVIATIONS	iv
	PREFACE	vii
1.0	<u>INTRODUCTION</u>	1-1
2.0	<u>METHODOLOGY</u>	2-1
2.1	VALIDATION QUESTIONNAIRE	2-1
2.2	DATA COLLECTION	2-3
2.3	DATA ANALYSIS	2-3
	<u>REFERENCES</u>	3-1

APPENDICES

APPENDIX

- A OPERATOR EXPERIENCE REVIEW VALIDATION QUESTIONNAIRE
- B SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

LIST OF TABLES

<u>Table No.</u>	<u>Title</u>	<u>Page</u>
2.1-1	NUMBER OF PROBLEMS REPORTED IN THE OER REPORT	2-2
2.3-1	PROBLEMS RECEIVING OPERATOR CONSENSUS	2-4
2.3-2	PROBLEMS NOT RECEIVING OPERATOR CONSENSUS	2-5
B-1	SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE	B-1



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

SUMMARY

During the May 1983 NRC Audit of the new layout of the STP control room panels, it was decided to have 33 percent or more of the operations personnel that provided the basic data for the Operator Experience Review (OER) report review and validate the new panel layouts. This report documents the review of the new panel layouts to determine if the problems identified in the OER had been corrected and if any new problems were created.

A validation questionnaire, addressing the 78 problems identified during the OER, was completed by 4 of the 11 operators that responded to the questionnaire in Reference 1. The operators responding to the validation questionnaire used the Bechtel full-scale mock-up and the current set of panel design drawings.

Results of the responses received from the validation questionnaire reveal that 74 problems generated during the OER were corrected to the operators' satisfaction. Four problems, two with controls, one with annunciator and one with Panel Layout/Integration were not corrected. The four problems are discussed herein and the disposition of each adequately resolved to satisfy the human factors specifications according to the Criteria Report, Reference 2.

Further, no new problems or human engineering observations were identified as a result of this OER validation effort.



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

ACRONYMS AND ABBREVIATIONS

ARO	Auxiliary Reactor Operator
ASSOC	Associated
ASST	Assistant
AUX	Auxiliary
CAT	Category
CLO	Checklist Observation
CONT	Control
CR	Control Room
CRDR	Control Room Design Review
CRT	Cathode Ray Tube
CVCS	Chemical Volume Control System
EES	Emergency Event Sequences
EOF	Emergency Operating Facility
EPRI	Electric Power Research Institute
ESF	Engineered Safety Feature(s)
EST	Estimate(d)
EXPER	Experience
FW	Feedwater
HE	Human Engineering
HED	Human Engineering Discrepancy
HHSI	High Head Safety Injection
HL&P	Houston Lighting and Power Company
HPSI	High Pressure Safety Injection
I&C	Instruments and Controls
IN PO	Institute of Nuclear Power Operators
INSTR	Instrument
LDR	Leader
LHSI	Low Head Safety Injection
LOCA	Loss of Coolant Accident
LOSP	Loss of Offsite (AC) Power
LPSI	Low Pressure Safety Injection



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

ACRONYMS AND ABBREVIATIONS (Cont.)

LR01	Licensed Reactor Operator #1
LR02	Licensed Reactor Operator #2
M/M	Man/Machine
MCP	Main Control Panel
MON	Monitor
MSR	Moisture Separator Reheater
MT	Management Team
MW(e)	Megawatts (electric)
NOS	Numbers
NRC	Nuclear Regulatory Commission
OERT	Operating Experience Review Task Group
OSC	Operational Support Center
PORV	Power Operated Relief Valve
PRT	Project Review Team
PSAR	Preliminary Safety Analysis Report
RAS	Recirculation Actuation Signal
PZR	Pressurizer
RCB	Reactor Containment Building
RCP	Reactor Coolant Pump
RCS	Reactor Coolant System
RECIRC	Recirculating
REQ'D	Required
RG	Regulatory Guide
RHR	Residual Heat Removal
RO	Reactor Operator
RWST	Refueling Water Storage Tank
RX	Reactor
SBCS	Standby Cooling System
SFTA	System Function and Task Analysis
SG	Steam Generator
SIS	Safety Injection System



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

ACRONYMS AND ABBREVIATIONS (Cont.)

SOE	Selected Operational Event(s)
SPDS	Safety Parameter Display System
SRO	Senior Reactor Operator
SS	Subsystem
STAT	Systems Task Analysis Team
SUPVR	Supervisor
SW	Switch
SYS	System
TMI	Three-Mile Island
TSC	Technical Support Center



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

PREFACE

The control room design review (CRDR) of the South Texas Project (STP) Nuclear Generating Station was started in September 1982. This review is being performed by Torrey Pines Technology for Houston Lighting & Power Company (HL&P) with Bechtel Energy Corporation (Bechtel) acting as agent.

Prior to completion of the CRDR, a decision was made by HL&P to redesign six of the ten main control panels. This redesign effort was required to accommodate design changes resulting from plant design evolution and Reg. Guide 1.97 requirements. Human engineering discrepancies determined in the CRDR have been or are in the process of correction.

The CRDR is described in the Program Plan document. It contains a detailed description of the plans for the majors task elements. Due to the control room redesign effort, a modified approach was required to complete and document the CRDR program. The following changes have been made in the CRDR Program Plan:

- A. The documentation program described in the Program Plan was changed to allow reporting of results on the individual CRDR tasks.
- B. An Implementation Plan Report, was written to describe the background and reasons for the redesign effort. It outlines the approach to be used for implementing panel layout changes.
- C. The tasks described in the Program Plan have been completed for the original design. The SFTA and the control room survey have been updated to validate any design revisions.



The following is a description of the documents covering this CRDR (see figure P-1):

- A. Program Plan - Defines the plan for performing the CRDR.
- B. Criteria Report - Provides the detailed guidelines and basis for the CRDR and describes the interface between the control room and plant systems.
- C. Operating Experience Review (OER) Report - Describes the review process results, conclusions and recommendations of the operating experience review (OER) task defined in the Program Plan.
- D. System Function and Task Analysis (SFTA) Report - Describes the methodology, results, conclusions and recommendations for the SFTA effort defined in the Program Plan.
- E. Control Room Survey (CRS) Report - Describes the review process, results, conclusions and recommendations of the control room survey task defined in the Program Plan. This report also includes the final results and dispositions for the human factor observations obtained from the OER and the SFTA.
- F. Annunciator Report - Describes the review process, results, conclusions and recommendation of the annunciator review task defined in the Program Plan.
- G. Special Studies Report - Describes details of miscellaneous studies performed as part of the CRDR. This includes the anthropometric study, the hierarchical labeling study and the demarcation study.




- H. Implementation Plan Report - Summarizes the CRDR, the control room design changes, and the proposed methods of implementing the design changes.
- I. SFTA Validation Report - Summarizes the second SFTA review based on relayed out panels and walk-through/talk-through validation.
- J. OER Validation Report - Summarizes the review made by operators to determine if the redesigned panels corrected concerns reported in the OER Report and if any new problems were created.
- K. CRS Validation Report - Summarizes the review made to determine if the category A and representative samples of the Category B HEDS are satisfactorily corrected and if any new problems were created.
- L. Executive Summary - Summarizes the CRDR, results, conclusions and recommendations. Technical details are in the Operating Experience Review Report, the System Function and Task Analysis Report, the Control Room Survey Report, the Special Studies Report, and the Annunciator Report.



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

PLANNING



PROGRAM PLAN

REVIEW & DESIGN SUPPORT



CRITERIA

OPERATING
EXPERIENCE
REVIEW

SYSTEM FUNCTION
& TASK ANALYSIS

CONTROL ROOM
SURVEY

ANNUNCIATOR

SPECIAL
STUDIES

ASSESSMENT IMPLEMENTATION EFFECTIVENESS



EXECUTIVE
SUMMARY

IMPLEMENTATION

OPERATING EXPERIENCE
REVIEW VALIDATION

SYSTEM FUNCTION
& TASK ANALYSIS
VALIDATION

CONTROL ROOM
SURVEY
VALIDATION

STP CRDR MAJOR REPORTS

Figure P-1



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

1.0 INTRODUCTION

The STP Control Room Design Review (CRDR) Program Plan defined, "Operator Experience Review" (OER) was completed in the first quarter of 1983, Reference 1. This report was submitted to the NRC in support of their audit of the CRDR facility during May 1983. During this audit the NRC was advised that 33 percent or more of the operations personnel who provided the basic data for the OER report would be asked to review the new panel layouts. The objective of this review was to determine whether the reported discrepancies were corrected and if any new problems were created.

This document contains the data, analysis and results of the validation process.



2.0 METHODOLOGY

2.1 VALIDATION QUESTIONNAIRE

The problem areas identified by the eleven (11) operators in response to the questionnaire, Reference 1, were organized into a validation questionnaire, Appendix A. The problems used in this questionnaire were the result of 13 questions that were answered "No" by nine (82%) or more of the 11 respondents to the OER questionnaire.

The operators were given one week to study the questionnaire prior to the exercise. A short orientation was given to the operators to make sure they understood the objectives of the review.

The one half scale panels 001 - 010 mosaic was used to show the panel layout at the time the OER concerns were surfaced. The relayed out mock up, and revised panel layout drawings were used for comparison.

There was a short debriefing period and additional operator communications to clarify some of the questionnaire responses.

Table 2.1-1 shows the number of problems reported in the OER report by area.



TABLE 2.1-1

NUMBER OF PROBLEMS REPORTED IN THE OER REPORT

AREA	NUMBER OF PROBLEMS REPORTED	QUESTIONNAIRE SECTIONS*
WORKSPACE	7	A
CONTROLS	25	B, C and D
ANNUNCIATORS	28	E, F, G, H and I
LABELS & LOCATION AIDS	8	J and K
PANEL LAYOUT/INTEGRATION	10	L and M
TOTAL	78	

* Each section is associated with a specific question used in Appendix A of Reference 1.

Each of the 78 problems was identified separately and grouped by section to conform with the specific question used in Appendix A of Reference 1.

Operators were requested to address each problem and mark one or more of the following categories as appropriate.

- ☐ Problem Corrected
- ☐ Problem Not Corrected
- ☐ No New Problems
- ☐ Created New Problem



The operators were asked to clarify their response in the "Remarks" column for the Categories marked with "Problem Not corrected" or "Created New Problem."

2.2 DATA COLLECTION

On August 16, 1983, four (4) of the original eleven (11) operators that completed the initial questionnaire used for the OER report, Reference 1, completed the validation questionnaire, Appendix A at the mockup facility. A complete set of the current panel design drawings were continuously available for this review.

The operators verified the problems on the one-half scale mosaic, then examined the relayed out panels and answered each problem query.

2.3 DATA ANALYSIS

The responses to the 78 problem areas were consolidated onto one data collection form and summarized in Table B-1 of Appendix B. Table 2.3-1 shows the number of problems, by area, where operator consensus reported that the problems were corrected. Table 2.3-2 shows that four problems did not receive operator consensus as being corrected.



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE 2.3-1
PROBLEMS RECEIVING OPERATOR CONSENSUS

AREA	PROBLEMS PER AREAS	PROBLEM CORRECTED
WORKSPACE	7	7
CONTROLS	25	23
ANNUNCIATORS	28	27
LABELS & LOCATION AIDS	8	8
PANEL LAYOUT/INTEGRATION	10	9
TOTAL	78	74



TABLE 2.3-2
PROBLEMS NOT RECEIVING OPERATOR CONSENSUS

<u>PROBLEM NUMBER</u>	<u>STATEMENT</u>
Controls - C1	"Boards are too tall"
Controls - D8	"Feedpump Master Controller should be nearer the middle of 006"
Annunciators - E4	"Permissives need auditory tone when actuated and when reset"
Panel Layout/Integration - L6	"Feedpump Master Controller should be located between individual controls"

The category "Creates New Problem", received only three single responses, indicating that the new design did not introduce any new problem.

The "No New Problem" was marked by only three of the four operators when their response to the "Problem Corrected" category was marked. This category did not provide any differential or meaningful data; therefore, it was not used in this survey evaluation.



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

The data from the completed questionnaire reveals that four problems previously identified in the OER Report have not been changed. The reported problems are:

C-1 "Boards Are Too Tall":

Although the boards are still the same height, most of the controls have been lowered. Approximately 20 switch controls on panel CP-010 exceed the upper height limits for control according to the Criteria Report, Reference 2. An examination was conducted to determine the trade-off between (1) lowering the switches on CP-010 and (2), providing an effective mimic. Results of the examination revealed that the 20 switches are not safety-related nor critical and are used infrequently. Further, lowering the switches would disrupt an operationally effective mimic. Based on this examination, the results of the current design arrangement were selected as being optimum. Other operator comments regarding the board height concern the changing of recorder paper. It should be noted that recorder paper is not changed during high activity periods and an "operator aid" (mobile ladder) will be procured for the control room. This is a commonly accepted practice in current control rooms.

Two problems, D-8 and L6, are essentially the same but reported in two separate areas, i.e.:

D-8 "Feedpump Master Controller should be nearer the middle of 006", and

L6 "Feedpump Master Controller should be located between individual controls".

The Feedwater Pump Master Controller is located to the far right of panel 006. However, comments of the four operators associated with these queries indicate that the location of this control does not create a problem.



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

Subsequent to the completion of the questionnaire, a debriefing was conducted with four operational personnel regarding the control location. The operators were unanimous in stating that, "the current feedwater control arrangement is satisfactory".

E-4 "Permissives need auditory tone when activated and when reset." Specifications for the Westinghouse startup permissives, interlocks, and blocks "Permissive Panel" will be modified to include an auditory tone when an annunciator is activated and when the panel is reset.

Although not identified as a problem, two comments suggested that the labeling on the sample "Permissive" annunciator panel is not consistent. The Annunciator Study Group has reviewed this labeling and the necessary changes have been made.

Based on the responses to the validation questionnaire, no human engineering observations resulted from this review.



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

REFERENCES

1. Houston Lighting & Power Company, Operating Experience Review Report, March 25, 1983.
2. Houston Lighting & Power Company, Criteria Report, February 4, 1983.
3. Human Engineering Guide for Enhancing Nuclear Control Rooms, EPRI NP-2411, May 1982.



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

APPENDIX A

OPERATOR EXPERIENCE REVIEW
VALIDATION QUESTIONNAIRE



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

OPERATOR EXPERIENCE REVIEW VALIDATION PHASE

1.0 INTRODUCTION

The STP Control Room Design Review (CRDR) Program Plan defined, "Operator Experience Review" (OER) and was completed in the first quarter of 1983. Rev. 0 of the OER report is dated March 15, 1983. This report was informally submitted to the NRC in support of their audit of the CRDR Facility on May 1983. During this audit the NRC was advised that 33 percent of the operations personnel who provided the basic data for the OER report would be asked, to review the new panel layouts and determine if the reported discrepancy had been corrected and if any new problems were created.

This document covers the "data input" portion of the validation process.

2.0 Methodology

2.1 The STP Operations Department is to designate four (4) of the original eleven (11) operations personnel to complete the attached questionnaire.

2.2 Completed questionnaires are to be submitted to TPT.



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

INSTRUCTION

1. Operator shall review stated problem by review of the mosaic.
2. Check the new panel layouts and determine if the revised layout corrects the problem. If it does not, state why in remarks column.
3. Check to see that the revision does not create a new problem. If it does, indicate why in the remarks column.

PROBLEM REPORTED IN OER REPORT

A. WORKSPACE

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. INDICATORS (PRESSURE, TEMPERATURE, FLOW) TOO HIGH ON PANELS

REMARKS: _____

2. ANNUNCIATORS HARD TO READ

REMARKS: _____

3. PERMISSIVE PANEL HARD TO READ FROM RO PANEL

REMARKS: _____

4. RECORDERS TOO HIGH ON PANEL

REMARKS: _____

5. SYNCH. SCOPE ON 010 TOO HIGH

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

A. WORKSPACE

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

6. BISTABLE STATUS LIGHTS HARD TO READ

REMARKS:

7. AUXILIARY FEED FLOW INDICATORS HARD TO READ

REMARKS:

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

B. CONTROLS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

**1. TURBINE CONTROLS AND GENERATOR VOLTAGE AND BREAKER
CONTROLS ARE TOO FAR APART**

REMARKS: _____

2. AUXILIARY FEEDWATER CONTROLS ARE SCATTERED

REMARKS: _____

3. CONTROLS ARE NOT MIMICED AND HARD TO IDENTIFY

REMARKS: _____

4. VCT CONTROLS ARE POORLY ARRANGED

REMARKS: _____

5. MAIN FEEDWATER SYSTEM CONTROLS NOT GROUPED PROPERLY

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

B. CONTROLS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

6. ESF CONTROLS INCONSISTENT ACROSS 001, 002, AND 003

REMARKS: _____

7. STEAM DUMP CONTROL SWITCHES ARE TOO FAR AWAY FROM STEAM DUMP CONTROLLERS

REMARKS: _____

8. ONE SET OF MANUAL SI SWITCHES SHOULD BE ON ESF PANELS

REMARKS: _____

9. HVAC SPREAD ALL OVER PANELS

REMARKS: _____

10. CONTROLS REQUIRE EXCESSIVE OPERATOR MOVEMENT

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

B. CONTROLS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

11. CONTROLS ARE NOT STANDARDIZED BY CONTROL FUNCTION

REMARKS:

REMARKS:

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

C. CONTROLS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. BOARDS ARE TOO TALL

REMARKS: _____

2. SMALL OPERATORS WILL HAVE PROBLEMS REACHING CERTAIN
CONTROLS ON VERTICAL PANELS

REMARKS: _____

3. SOME CONTROLS AND ALL RECORDERS ARE HARD TO REACH, EVEN
FOR TALL PERSONS

REMARKS: _____

4. DRPI CONTROLS ON 305 IMPOSSIBLE TO REACH

REMARKS: _____

5. BTRS CONTROLS ON 004 HARD TO REACH

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

D. CONTROLS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. 004 ILLOGICALLY ARRANGED

REMARKS: _____

2. TURBINE DRAIN SWITCHES ARE SCATTERED

REMARKS: _____

3. GENERATOR CONTROLS SHOULD BE NEARER TURBINE CONTROLS

REMARKS: _____

4. CONTROLS FOR SAME SYSTEM ARE ON DIFFERENT PANELS OR SPREAD
TOO MUCH ON ONE PANEL

REMARKS: _____

5. RESET SWITCHES ON ESF BOARDS POORLY ARRANGED

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

D. CONTROLS

**PROBLEM
CORRECTED**

**PROBLEM NOT
CORRECTED**

**NO NEW
PROBLEM**

**CREATES NEW
PROBLEM**

6. CVCS SYSTEM CONTROLS NOT INTEGRATED

REMARKS: _____

7. AUXILIARY FEEDWATER SYSTEM ILLOGICAL

REMARKS: _____

**8. FEEDPUMP MASTER CONTROLLER SHOULD BE NEARER THE MIDDLE
OF 006**

REMARKS: _____

9. CONTROLS ARE TOO SCATTERED ABOUT THE PANELS

REMARKS: _____

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

E. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. ANNUNCIATORS SHOULD BE ARRANGED BY DEGREE OF IMPORTANCE
(NEED PRIORITIZATION)

REMARKS: _____

2. LAYOUT IS INCONSISTENT WITH WESTINGHOUSE DESIGN FOR PERMISSIVES AND IS NOT LABELED FOR CLEAR UNDERSTANDING

REMARKS: _____

3. PERMISSIVES SHOULD BE ON SEPARATE PANEL WITH PERMISSIVE NUMBER

REMARKS: _____

4. PERMISSIVES NEED AUDITORY TONE WHEN ACTUATED AND WHEN RESET

REMARKS: _____

5. NEED FIRST-OUT INDICATIONS

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

E. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

6. ANNUNCIATORS ARE HARD TO READ

REMARKS: _____

7. COMMON SYSTEMS ARE NOT GROUPED TOGETHER

REMARKS: _____

**8. MANY ALARMS ON 007 (e.g. RCB AND LOOSE PARTS MONITORING)
SHOULD BE ON 005**

REMARKS: _____

9. ANNUNCIATOR LAYOUT IS ILLOGICAL WITH RESPECT TO SYSTEMS

REMARKS: _____

**10. SHOULD BE ABLE TO SILENCE AN ALARM FROM ANY PANEL AND
ACKNOWLEDGE FROM SYSTEM PANEL**

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

E. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

11. RECOMMEND COLOR CODED ANNUNCIATOR SYSTEM

REMARKS:

12. PANELS CONTAIN TOO MANY MISCELLANEOUS ALARMS

REMARKS:

13. CONTROLS FOR A GIVEN SYSTEM ARE ON DIFFERENT PANEL FROM
THEIR CORRESPONDING ANNUNCIATOR WINDOWS

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

F. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. TOO MANY HIGH/LOW INPUTS (NEED INDICATION OF STATUS NEARBY
IF MULTIPLE INPUT ALARMS ARE TO BE USED)

REMARKS: _____

2. COMMON ALARM ANNUNCIATORS SHOULD BE CAREFULLY REVIEWED

REMARKS: _____

3. THESE ARE SEVERAL GENERAL CATEGORY ALARMS

REMARKS: _____

REMARKS: _____

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

G. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. THERE ARE NO FIRST-OUTS (THEY ARE NEEDED BADLY)

REMARKS:

2. HIGHLY RECOMMEND THAT FIRST-OUT FEATURE BE INCORPORATED
INTO DESIGN

REMARKS:

3. IN THE EVENT OF COMPUTER OUTAGE, OPERATOR HAS NO WAY TO
DIAGNOSE WHAT CAUSED A PLANT TRIP

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

H. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. NO ANNUNCIATOR PRIORITIES HAVE BEEN ESTABLISHED

REMARKS:

2. ANNUNCIATORS NEED TO BE COLOR-CODED BY PRIORITY

REMARKS:

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

I. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. TILES ARE TOO SMALL AND TOO CLUTTERED

REMARKS: _____

2. TOO MANY LETTERS IN SMALL AREA

REMARKS: _____

3. DIFFICULT TO DISTINGUISH AMONG TILES

REMARKS: _____

4. POOR LABELING

REMARKS: _____

5. INCONSISTENT ABBREVIATIONS

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

I. ANNUNCIATORS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

6. HARD TO READ AND IDENTIFY

REMARKS:

7. LABELS ARE INCONSISTENT WITHIN PANELS AND ACROSS PANELS

REMARKS:

REMARKS:

REMARKS:

REMARKS:

PROBLEM REPORTED IN OER REPORT

J. LABELS AND LOCATION AIDS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. LABELING NEEDS TO BE REVIEWED FOR ACCURACY AND CONSISTENCY WITH FSARs AND WESTINGHOUSE TECH MANUALS

REMARKS: _____

2. RECORDERS (e.g. STEAM GENERATOR LEVEL, STEAM FLOW) ARE POORLY LABELED

REMARKS: _____

3. NEED MAJOR SYSTEM LABELS (ESPECIALLY ON ESFs)

REMARKS: _____

4. LABELS ON CONTROLLERS NEED TO INCLUDE THE SYSTEM OR FUNCTION BEING CONTROLLED

REMARKS: _____

5. RECORDER LABELS DO NOT INDICATE WHAT IS RECORDED (RCP AND SG)

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

K. LABELS AND LOCATION AIDS

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. VERY LITTLE DEMARCATION IS USED

REMARKS: _____

2. DEMARCATION IS USED ONLY ON ESF PANELS AND IT IS NOT LABELED

REMARKS: _____

3. DEMARCATION IS NEEDED ON PANELS 004, 005, 007, 008 AND 009

REMARKS: _____

REMARKS: _____

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

L. PANEL LAYOUT/INTEGRATION

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. NEED MORE LOGICAL AND FUNCTIONAL GROUPINGS

REMARKS: _____

2. NEED BETTER DEMARCATION AND BETTER LABELING

REMARKS: _____

3. 004, 005, 006 AND 007 ARE ESPECIALLY POORLY LAID OUT

REMARKS: _____

4. MANY OF PERIPHERAL PANELS THAT ARE OUTSIDE OF THE PRIMARY OPERATING AREA NEED TO BE INCLUDED IN MAIN PANEL LAYOUT

REMARKS: _____

5. ELECTRICAL CONTROLS ARE MUCH TOO FAR FROM TURBINE CONTROLS

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

L. PANEL LAYOUT/INTEGRATION

**PROBLEM
CORRECTED**

**PROBLEM NOT
CORRECTED**

**NO NEW
PROBLEM**

**CREATES NEW
PROBLEM**

**6. FEED PUMP MASTER CONTROLLER SHOULD BE LOCATED BETWEEN
INDIVIDUAL CONTROLS**

REMARKS: _____

7. PANELS NEED EXTENSIVE REARRANGEMENT

REMARKS: _____

REMARKS: _____

REMARKS: _____

REMARKS: _____

PROBLEM REPORTED IN OER REPORT

M. PANEL LAYOUT/INTEGRATION

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

1. THE FOLLOWING SYSTEMS ARE ILLOGICALLY GROUPED:
RHR AND CVCS

REMARKS:

TURBINE TO GENERATOR

REMARKS:

MAIN FEEDWATER

REMARKS:

AUXILIARY FEEDWATER

REMARKS:

ENC CONTROLS

REMARKS:

PROBLEM REPORTED IN OER REPORT

M. PANEL LAYOUT/INTEGRATION

PROBLEM
CORRECTED

PROBLEM NOT
CORRECTED

NO NEW
PROBLEM

CREATES NEW
PROBLEM

2. STEAM GENERATOR CONTROLS AND DISPLAYS ARE SPLIT

REMARKS: _____

**3. ROD POSITION INDICATION AND CONTROLS COULD BE BETTER
INTEGRATED**

REMARKS: _____

REMARKS: _____

REMARKS: _____

REMARKS: _____



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

APPENDIX B

SUMMARY OF
OPERATOR RESPONSES TO OER VALIDATION
QUESTIONNAIRE



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	PROBLEM NUMBER	RESPONSES				REMARKS/COMMENT
		PROBLEM CORRECTED	PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	
A W O R K S P A C E	1	4		3		
	2	4		3		
	3	3		3	1	Markings not consistent for "P" numbers. New permissive not on panel; cannot evaluate. Permissives should be readily available e.g., P4 Rx TRP.
	4	3		2		
	5	3	1	2		Synch OK on 007. No problem with Synch on 007.
	6	3	1	2		New lights not on panel.
	7	4		3		Interchange FI indicators. (Note: Indicators fell off mock-up).



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES		PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED				
B	1	4		3		
C O N T R O L S	2	3		3		Still scattered, but improved.
	3	3		3		In general, mimics incorporated where necessary. All controls and systems not mimiced.
	4	4		3		
	5	4		3		
	6	4		3		
	7	4		3		
	8	1	1	2		No SI switch on ESF panels. Gone on 005.
	9	4		3		
	10	4		3		
	11	4		3		



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES					REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	
C	1	1	2	3		Do not know what can be done. Cannot correct problem. Yes
C O N T R O L S	2	3	1	2		Possibly, with short operators changing recorder paper, CP-010 and 006 still have problems.
	3	3	1	2		Some controls and generator recorder PORV on 006; current and voltages on 010; valve leak on 001, surge tank 002 and some on 004.
	4	4		3		
	5	4		3		



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES					REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	
D	1	4		3		Mimics help a lot. Very good.
C O N T R O L S	2	4		3		
	3	4		3		
	4	4		3		Situation still exists but layed out best.
	5	4		3		
	6	4		3		
	7	4		3		
	8	1	2	2		The control is functional where it is.
	9	4		3		



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES			NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED			
E A N N U N C I A T O R S	1	4		3		
	2	4		2	1	See A-3 Permissives
	3	4		2	1	See A-3 Permissives
	4	1	2	1		Not ready yet
	5	4		3		
	6	4		3		Should be OK, if 2" x 3".
	7	4		3		
	8	4		3		
	9	4		3		
	10	4		3		True
	11	3	1	3		
	12	4		3		
	13	4		3		



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES			NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED			
F	1	3	1	3		Still have Hi/Lo but with indication, agree with parenthesis statement.
A N N U N C I A T O R S	2	3	1	3		Reviewed with respect to "1F" indication on function i.e., flow Hi/Lo is near annunciator.
	3	4		3		



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES		PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS / COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED				
G	1	4		3		
A	2	4		3		
N	3	4		3		
N						
U						
N						
C						
I						
A						
T						
O						
R						
S						

Should have enough
indication on
board.



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES					REMARKS / COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	
H	1	4		3		
A N N U N C I A T O R S	2	4		3		



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES		PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED				
I	1	4		3		
A	2	4		3		
N	3	4		3		
N	4	4		3		
U	5	4		3		
N	6	4		3		
C	7	4		3		
I						
A						
T						
O						
R						
S						



HOUSTON
LIGHTING
&
POWER CO.

**CONTROL ROOM
DESIGN REVIEW**

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES			NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED			
J	1	3	1	3		"Blank"
L	2	4		3		
A	3	4		3		
B	4	4		3		
E	5	3	1	3		"Blank"
L						
S						
A						
N						
D						
L						
O						
C						
A						
T						
I						
O						
N						
A						
I						
D						
S						



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES			NO NEW PROBLEM	CREATES NEW PROBLEM	REMARKS / COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED			
K	1	4		3		
L A B E L S	2	3	1	3		Too much on 003-subsystem labels. Should be the same color as their demarcation lines.
A N D	3	3		3		Single color demarcation inadequate.
L O C A T I O N						
A I D S						



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES			NO NEW PROBLEM		REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED	PROBLEM	CREATES NEW PROBLEM	
L P A N E L L A Y O U T / I N T E G R A T I O N	1	4		3		
	2	3	1	3		"Blank"
	3	4		3		
	4	4		3		Cannot determine if there are any new problems at this time.
	5	4		3		
	6	1	2	2		See D-8. Located on side but OK. "Blank". No.
	7	4		3		



HOUSTON
LIGHTING
&
POWER CO.

CONTROL ROOM DESIGN REVIEW

TABLE B-1

SUMMARY OF OPERATOR RESPONSES TO OER VALIDATION QUESTIONNAIRE

QUESTIONNAIRE SECTION	RESPONSES					REMARKS/COMMENT
	PROBLEM NUMBER	PROBLEM CORRECTED	PROBLEM NOT CORRECTED	NO NEW PROBLEM	CREATES NEW PROBLEM	
M	1	4		3		
P	2	4		3		With exception of feedwater.
A						
N	3	4		3		
E						
L						
L						
A						
Y						
O						
U						
T						
/						
I						
N						
T						
E						
G						
R						
A						
T						
I						
O						
N						

Control Room Design Review

Operating Experience Review Report

The South Texas Project



HOUSTON LIGHTING & POWER COMPANY